



CO1 ON THIS SIDE OF WALL NEATLY CUT AND MODIFY EXISTING TO REMAIN EXPOSED T GRID TO ACCOMMODATE WALL LOCATION. PROVIDE NEW WALL ANGLE AND PATCH AND REPAIR ACOUSTICAL CEILING TILES



(F01) REMOVE PORTION OF WALL AND REFRAME AS REQUIRED FOR NEW OPENING. PROVIDE NEW 3'-0" WIDE OPENING WITH WOOD JAMBS WITHOUT STOPS AND CASING TO FINISHED AND STAINED TO MATCH EXISTING.

(F02) DENTAL FURNITURE SUPPLIED BY OTHERS. CONTRACTOR IS TO COORDINATE AND PROVIDE AIR, WATER, ELECTRIC AND LOW-VOLTAGE HOOK-UP REQUIREMENTS AS RECOMMENDED BY DENTAL SUPPLIER. FIN

(F03) PLASTIC LAMINATE CASEWORK TO BE DESIGN BUILT BY CONTRACTOR TO MATCH CASEWORK IN EXISTING EXAM ROOMS. PROVIDE SHOP DRAWINGS AND OBTAIN FINAL APPROVAL OF CASEWORK DESIGN FROM DOCTOR PRIOR TO FABRICATION.

(F04) THROUGHOUT ROOM OR AREA PROVIDE NEW LVT FLOOR. PROVIDE NEW BASE AT NEW WALLS TO MATCH EXISTING. PRIME UNFINISHED GYPSUM BOARD. PAINT ALL NEW AND EXISTING WALL WITH TWO COATS OF LATEX PAINT.

(F05) THROUGHOUT ROOM OR AREA FLOORING IS EXISTING TO REMAIN. PROVIDE NEW BASE AT NEW WALLS TO MATCH EXISTING. PRIME UNFINISHED GYPSUM BOARD. PAINT ALL NEW AND EXISTING WALL WITH TWO COATS OF LATEX PAINT.

FIXTURE	WASTE	VENT	CX	HW
S-1	1-1/4"	1-1/4"	1/2"	1/2"