
DATE: 2-5-21

PROJ. #20-142

NOTE:
PLANS DESIGNED PER IRC AS
ADOPTED BY GOVERNING JURISDICTION



ROOF PLAN SCALE: 1/4" = 1'-0"

ROOF FRAMING NOTES

ROOF DESIGNED FOR LIGHT ROOF COVERING 30psf TOTAL LOAD [10psf DL, 20psf LL (SL)]

ROOF SYSTEM IS DESIGNED TO MEET REQUIREMENTS OF IRC 802

*RAFTERS (HEM-FIR, DOUG-FIR, OR EQUAL): SEE SPAN CHARTS BELOW

CODE MINIMUM				
RAFTERS	SPACING	MAX HORIZONTAL CLEARSPAN		
#2-2x6	AT 24" OC	11'-7"		
#2-2x6	AT 16" OC	14'-2"		
#2-2x8	AT 24" OC	14'-8"		
#2-2x8	AT 16" OC	17'-11"		
#2-2x10	AT 24" OC	17'-10"		
#2-2x10	AT 16" OC	21'-11"		

NOTE: CODE MINIMUM ALLOWS FOR A RAFTER DEFLECTION OF L/180 TOTAL LOAD

HIGHER PERFORMANCE

RAFTERS	SPACING	MAX HORIZONTAL CLEARSPAN		
#2-2x6	AT 24" OC	8'-6"		
#2-2x6	AT 16" OC	9'-9"		
#2-2x8	AT 24" OC	11'-3"		
#2-2x8	AT 16" OC	12'-9"		
#2-2x10	AT 24" OC	14'-3"		
#2-2x10	AT 16" OC	16'-3"		
AREY ENGINEEDS INC. RECOMMENDED				

APEX ENGINEERS, INC. RECOMMENDED DEFLECTION = L/360 LIVE LOAD, L/240 TOTAL LOAD

*RIDGE BOARDS ARE (UNLESS OTHERWISE NOTED) #2-2x10 UP TO 9:12 PITCH

#2-2x12 OVER 9:12 PITCH *ALL HIPS AND VALLEYS ARE (UNLESS OTHERWISE NOTED) #2-2x10 UP TO 9:12 PITCH

#2-2x12 OVER 9:12 PITCH *PURLINS ARE 2x6 MIN

- PURLIN STRUTS ARE AT 4'-0" OC

- PURLIN STRUTS SHALL BE INSTALLED AT NOT LESS THAN A 45 DEGREE ANGLE WITH THE HORIZONTAL

- ALL PURLIN STRUTS SHALL HAVE A MAX UNBRACED LENGTH OF 8'-0"

- PURLIN STRUTS SHALL BE CONSTRUCTED IN A "T" CONFIGURATION AND PER THE FOLLOWING CHART:

PURLIN STRUT	MAX PURLIN STRUT LENGTH
(2)2x4	8'-0"
(1)2x4 AND (1)2x6	12'-0"
(1)2x6 AND (1)2x8	20'-0"
(2)2x6 AND (1)2x8	30'-0"
CONSULT ARCH ENGR	>30'-0"

*EACH END OF STRUT SHALL BE FASTENED WITH MIN (3)8d OR (2)16d NAILS

*RIDGE BRACERS ARE SAME AS PURLIN BRACES-SPACING, SIZE, CONFIGURATION, AND INSTALLATION (SEE PURLIN

BRACE NOTES ABOVE) *HIP AND VALLEY BRACES ARE THE SAME AS PURLINS SIZE, CONFIGURATION, AND INSTALLATION (SEE PURLIN BRACE NOTES ABOVE)

= ROOF BRACE/STRUT (PER CHART) -SLASH IS TOP END OF BRACE -CIRCLE IS BOTTOM END OF BRACE

├── = PURLIN STRUTS AT 48" OC (PER CHART) U.N.O. -SLASH IS TOP END OF BRACE -ARROW IS BEARING LOCATION

DENOTES BEARING WALL ---- DENOTES PURLIN **____ __ ___** DENOTES BEARING STRUCTURE

B = BOLTED RAFTER CONNECTION, REF DETAIL 2/S3.2

1. THIS IS AN ENGINEERED ROOF STRUCTURE DESIGNED FOR COMPLIANCE WITH IRC 802.3, BUILD AS SHOWN WITH NO DEVIATIONS. 2. ALL HIPS ARE DESIGNED TO BE CONTROLLED BY

3. SHEAR AT BEARING WITH MIN 5½" DEPTH DOES NOT CONTROL DESIGN. FOR VALLEYS REF 4/S3.2