


**MARSHALL HOME DESIGN**

**"BUILDERS PLANS DEFINITION"**


THE TERM "BUILDERS PLAN" REFERS TO A CERTAIN LEVEL OF DEVELOPMENT OF THE DRAWINGS, AS THE NAME IMPLIES. THESE PLANS REQUIRE THAT THE CONTRACTOR POSSESSES COMPETENCE IN RESIDENTIAL CONSTRUCTION. THE CONTRACTOR WARRANTS TO MARSHALL HOME DESIGN, LLC AND ITS CONSULTANTS, THAT THEY POSSESS THE PARTICULAR COMPETENCE AND SKILL IN CONSTRUCTION NECESSARY TO BUILD THIS PROJECT WITHOUT FULL ENGINEERING AND ARCHITECTURAL DESIGN SERVICES. AND FOR THAT REASON, THE CONTRACTOR OR HOME OWNER HAS RESTRICTED THE SCOPE OF PROFESSIONAL SERVICES. THE CONSTRUCTION DOCUMENTS PROVIDED BY THE LIMITED SERVICES SHALL BE TERMED "BUILDERS PLANS" IN RECOGNITION OF THE CONTRACTOR'S SOPHISTICATION. ALTHOUGH MARSHALL HOME DESIGN, LLC AND ITS CONSULTANTS HAVE PERFORMED THEIR SERVICES WITH DUE CARE AND DILIGENCE, WE CANNOT GUARANTEE PERFECTION. ANY AMBIGUITY OR DISCREPANCY DISCOVERED BY THE USE OF THESE PLANS SHALL BE REPORTED IMMEDIATELY TO MARSHALL HOME DESIGN, LLC. CONSTRUCTION MAY REQUIRE THAT THE CONTRACTOR ADAPT THE "BUILDERS PLANS" TO THE FIELD CONDITIONS ENCOUNTERED AND MAKE LOGICAL ADJUSTMENTS IN FIT, FORM, FINISH AND QUALITY. CHANGES MADE FROM THE PLANS WITHOUT THE CONSENT OF MARSHALL HOME DESIGN, LLC AND ITS CONSULTANTS ARE UNAUTHORIZED. IT IS ALSO UNDERSTOOD THAT THE CONTRACTOR WILL BE RESPONSIBLE FOR MEETING ALL APPLICABLE BUILDING CODES. IN THE EVENT ADDITIONAL DETAIL OR GUIDANCE IS NEEDED BY THE CONTRACTOR OR HOMEOWNER FOR THE CONSTRUCTION OF ANY ASPECT OF THE PROJECT MARSHALL HOME DESIGN, LLC OR A QUALIFIED ARCHITECT OR ENGINEER SHALL IMMEDIATELY BE RETAINED. FAILURE TO NOTIFY MARSHALL HOME DESIGN, LLC OF THESE NEEDS OR OF CHANGES TO THE PLANS, SHALL RELIEVE MARSHALL HOME DESIGN, LLC, AND ITS CONSULTANTS OF ALL RESPONSIBILITIES OF THE CONSEQUENCES. STRUCTURAL DESIGN, SITE DESIGN, SOILS TESTING, MEP PLANS BY OTHERS.

HOME BUILDER:  
**ASPEN HOMES**  
 6618 ROYAL ST., PLEASANT VALLEY, MO. 64068  
 RESIDENTIAL DESIGN BY:  
**MARSHALL HOME DESIGN, LLC.**  
 1723 N.W. 57th COURT, KANSAS CITY, MO. 64151




**FRONT ELEVATION**

SCALE 1/4"=1'-0" FRONT DOOR AND GARAGE DOOR STYLE MAY BE DIFFERENT THAN WHAT IS SHOWN ON PLANS. VERIFY STYLE WITH BUILDER.




**LEFT ELEVATION**

SCALE 1/8"=1'-0"



**RIGHT ELEVATION**

SCALE 1/8"=1'-0"



**BACK ELEVATION**

SCALE 1/8"=1'-0"

THIS DOCUMENT CONTAINS COPYRIGHTED MATERIAL AND CONFIDENTIAL INFORMATION BELONGING TO HD ENGINEERING UNAUTHORIZED USE, DISCLOSURE, REPRODUCTION, OR DUPLICATION OF ANY OF THE INFORMATION CONTAINED HEREIN MAY RESULT IN LIABILITY UNDER APPLICABLE LAW.

**HD ENGINEERING & DESIGN, INC**  
 11666 W. 75TH STREET  
 SHAWNEE, KS 66214  
 WWW.HDENGINEERS.COM  
 913.631.2222  
 SERVICE@HDENGINEERS.COM



**ASPEN HOMES, INC.**  
 BIRCH II GL LOT 6 HOOK FARMS  
 2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

STRUCTURAL DETAILS & NOTES

HD#: 42613  
 DATE: 10/07/2021  
 CHECKED BY: CLS

NO.	ISSUE/REVISION	Revision Date


PLANS DRAWN BY OTHERS

**S-0.1**



HOMEOWNER:  
**ASPEN HOMES**  
 6618 ROYAL ST., PLEASANT VALLEY, MO. 64068  
 RESIDENTIAL DESIGN BY:  
**MARSHALL HOME DESIGN, LLC.**  
 1723 N.W. 57th COURT, KANSAS CITY, MO. 64151

**HD ENGINEERING & DESIGN, INC.**  
 1766 W. 75TH STREET  
 SHAWNEE, KS 66214  
 WWW.HDENGINEERS.COM  
 913.631.2222  
 SERVICE@HDENGINEERS.COM




**ASPEN HOMES, INC.**  
 BIRCH II GL LOT 6 HOOK FARMS  
 2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

STRUCTURAL DETAILS & NOTES

- LOAD BEARING WALL
- LOAD BEARING BEAM
- SMOKE DETECTOR
- CARBON MONOXIDE SENSOR

**GENERAL NOTES:**  
 -WINDOW SHALL HAVE FALL PROTECTION PER IRC 312.2.4  
 -HOUSE WILL BE PROVIDED WITH A "UFERS" GROUND PER IRC SECTION 3608.1.5  
 -OVERHEAD GARAGE DOORS MUST MEET DASHA REQUIREMENTS SEE DETAIL SHEET S-1.0  
 -ALL HEADERS NOT LABELED SHALL BE MIN (2) #2-2X10 DFL  
 -DBL ALL JST UNDER ISLAND  
 -SOILS IN THIS AREA COMMONLY HAVE A VERY HIGH SHRINK SWELL CAPACITY, OUR FIRM RECOMMENDS ALL SITES BE EVALUATED BY A GEOTECHNICAL FIRM PRIOR TO PLACEMENT OF FOUNDATIONS  
 -PROVIDE CARBON MONOXIDE AND SMOKE DETECTORS PER IRC REQUIREMENTS  
 -ANY PORTION OF THESE PRINTS ISSUED WITHOUT A MIN. OF S-1.0 - S-4.0 SHALL NOT BE CONSIDERED A COMPLETE SET OF CONSTRUCTION DOCUMENTS  
 -ICE AND WATER SHIELD AS REQUIRED PER IRC

**TYPICAL TIE DOWN AT NARROW WALL**







**BRACED WALLS:**

SEE CALCULATIONS ON SHEET S-2.0, PER ASCET-10 REQUIREMENTS AS ALLOWED BY IRC 2018 R301.2.1  
 ALL EXTERIOR WALLS SHALL BE SHEATHED PER ANY ONE OF THE FOLLOWING OPTIONS:  
 -7/16" APA-RATED PLYWOODS WITH 8d NAILS @ 6" O.C. AT EDGES AND @ 12" O.C. IN THE FIELD  
 -7/16" SHIPLAP PANEL SHEATHING (I.E. LP SMARTSIDE OR EQUIVALENT) WITH 8d NAILS @ 6" O.C. AT EDGES AND @ 12" O.C. IN THE FIELD  
 -3/8" SHIPLAP PANEL SHEATHING (I.E. LP SMARTSIDE OR EQUIVALENT) WITH 8d NAILS @ 4" O.C. AT EDGES AND @ 12" O.C. IN THE FIELD

**INTERIOR BRACED WALL LOCATIONS ONLY SHOWN**

WHEN REQUIRED BY ADDITIONAL BRACING SECTION OF CALCULATIONS ON SHEET S-2.0



48 S.F. STOOP  
 625 S.F. GARAGE  
 1027 S.F. FIRST FLOOR  
 1261 S.F. SECOND FLOOR  
 2288 S.F. TOTAL AREA  
 144 S.F. COVERED PATIO/DECK  
 921 SF UNFINISHED BASEMENT

**FIRST FLOOR PLAN**  
 SCALE 1/4"=1'-0"

HD#: 42613  
 DATE: 10/07/2021  
 CHECKED BY: CLS

NO.	ISSUE/REVISION	Revision Date




PLANS DRAWN BY OTHERS

**S-0.3**

HOMEOWNER:  
**ASPEN HOMES**  
 6618 ROYAL ST., PLEASANT VALLEY, MO. 64068  
 RESIDENTIAL DESIGN BY:  
**MARSHALL HOME DESIGN, LLC.**  
 1723 N.W. 57th COURT, KANSAS CITY, MO. 64151

THIS DOCUMENT CONTAINS  
 COPYRIGHTED MATERIAL AND  
 CONFIDENTIAL INFORMATION  
 BELONGING TO HD ENGINEERS.  
 UNAUTHORIZED USE, DISCLOSURE,  
 REPRODUCTION OR DUPLICATION OF  
 ANY OF THE INFORMATION  
 CONTAINED HEREIN MAY RESULT IN  
 LIABILITY UNDER APPLICABLE LAW.

**HD ENGINEERING & DESIGN, INC.**  
 11656 W. 75TH STREET  
 SHAWNEE, KS 66214  
 WWW.HDENGINEERS.COM  
 913.631.2222  
 SERVICE@HDENGINEERS.COM





- - LOAD BEARING WALL
- - - - - - LOAD BEARING BEAM
- SD - SMOKE DETECTOR
- CO - CARBON MONOXIDE SENSOR

**GENERAL NOTES:**  
 - WINDOW SHALL HAVE FALL PROTECTION PER IRC 312.2.4  
 - HOUSE WILL BE PROVIDED WITH A 'UFER' GROUND PER IRC SECTION 3608.1.5  
 - OVERHEAD GARAGE DOORS MUST MEET DASMA REQUIREMENTS SEE DETAIL SHEET S-1.0  
 - ALL HEADERS NOT LABELED SHALL BE MIN (2) #2-2X10 DFL  
 - DEL ALL 1ST UNDER ISLAND  
 - SOILS IN THIS AREA COMMONLY HAVE A VERY HIGH SHRINK SWELL CAPACITY. OUR FIRM RECOMMENDS ALL SITES BE EVALUATED BY A GEOTECHNICAL FIRM PRIOR TO PLACEMENT OF FOUNDATIONS  
 - PROVIDE CARBON MONOXIDE AND SMOKE DETECTORS PER IRC REQUIREMENTS  
 - ANY PORTION OF THESE PRINTS ISSUED WITHOUT A MIN. OF S-1.0 S-4.0 SHALL NOT BE CONSIDERED A COMPLETE SET OF CONSTRUCTION DOCUMENTS  
 - ICE AND WATER SHIELD AS REQUIRED PER IRC

**BRACED WALLS:**  
 SEE CALCULATIONS ON SHEET S-2.0, PER ASCE7-10 REQUIREMENTS AS ALLOWED BY IRC 2018 R301.2.1

ALL EXTERIOR WALLS SHALL BE SHEATHED PER ANY ONE OF THE FOLLOWING OPTIONS:  
 - 7/16" APA-RATED PLYWOOD/OSB WITH 8d NAILS @ 6" O.C. AT EDGES AND @ 12" O.C. IN THE FIELD  
 - 7/16" SHIPLAP PANEL SHEATHING (I.E. LP SMARTSIDE OR EQUIVALENT) WITH 8d NAILS @ 6" O.C. AT EDGES AND @ 12" O.C. IN THE FIELD  
 - 3/8" SHIPLAP PANEL SHEATHING (I.E. LP SMARTSIDE OR EQUIVALENT) WITH 6d NAILS @ 4" O.C. AT EDGES AND @ 12" O.C. IN THE FIELD

INTERIOR BRACED WALL LOCATIONS ONLY SHOWN WHEN REQUIRED BY ADDITIONAL BRACING SECTION OF CALCULATIONS ON SHEET S-2.0



**ASPEN HOMES, INC.**  
 BIRCH II GL LOT 6 HOOK FARMS  
 2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

STRUCTURAL DETAILS & NOTES

HD#: 42613  
 DATE: 10/07/2021  
 CHECKED BY: CLS

NO.	ISSUE/REVISION	Revision Date


PLANS DRAWN BY OTHERS

**S-0.4**

HOMEOWNER:  
**ASPEN HOMES**  
 6618 ROYAL ST., PLEASANT VALLEY, MO. 64068  
 RESIDENTIAL DESIGN BY:  
**MARSHALL HOME DESIGN, LLC.**  
 1723 N.W. 57th COURT, KANSAS CITY, MO. 64151

THIS DOCUMENT CONTAINS  
 COPYRIGHTED MATERIAL AND  
 CONFIDENTIAL INFORMATION  
 BELONGING TO HD ENGINEERS.  
 UNAUTHORIZED USE, DISCLOSURE,  
 REPRODUCTION OR DUPLICATION OF  
 ANY OF THE INFORMATION  
 CONTAINED HEREIN MAY RESULT IN  
 LIABILITY UNDER APPLICABLE LAW.

**HD ENGINEERING & DESIGN, INC.**  
 11656 W. 75TH STREET  
 SHAWNEE, KS 66214  
 WWW.HDENGINEERS.COM  
 913.631.2222  
 SERVICE@HDENGINEERS.COM



**NOTES**

ROOF DESIGNED FOR LIGHT ROOF COVERING 30PSF  
 TOTAL LOAD (10PSF DL, 20PSF LL (SL))

RAFTERS (DOUG-FIR, OR EQUAL):  
 SEE SPAN CHARTS BELOW

CODE MINIMUM

RAFTERS	SPACING	MAX HORIZONTAL CLEARSPAN
#2-2x6	@24" O.C.	11'-11"
#2-2x6	@16" O.C.	14'-1"
#2-2x8	@24" O.C.	15'-1"
#2-2x8	@16" O.C.	18'-5"
#2-2x10	@24" O.C.	18'-5"
#2-2x10	@16" O.C.	22'-6"

NOTE: CODE MINIMUM L/240 DEFLECTION

GREATER THAN CODE

RAFTERS	SPACING	MAX HORIZONTAL CLEARSPAN
#2-2x6	@24" O.C.	8'-6"
#2-2x6	@16" O.C.	9'-0"
#2-2x8	@24" O.C.	11'-3"
#2-2x8	@16" O.C.	12'-9"
#2-2x10	@24" O.C.	14'-3"
#2-2x10	@16" O.C.	16'-3"

DEFLECTION = L/360 LIVE LOAD, L/240 TOTAL LOAD  
 VAULTS TO BE 2x10 DEPTH

ALL RIDGES, HIPS, AND VALLEYS NOT MARKED SHALL BE (1)  
 NOMINAL SIZE LARGER THAN THE INTERSECTING RAFTERS

PUHLINS ARE 2x6 MIN.  
 PUHLIN STRUTS ARE AT 4'-0" O.C.  
 PUHLIN STRUTS SHALL BE INSTALLED AT NOT LESS  
 THAN A 45 DEGREE ANGLE WITH THE HORIZONTAL  
 ALL PUHLIN STRUTS SHALL HAVE A MAXIMUM UNBRACED  
 LENGTH OF 8'-0"  
 PUHLIN STRUTS SHALL BE CONSTRUCTED IN A "T"  
 CONFIGURATION AND PER THE FOLLOWING CHART

PUHLIN STRUT	MAX PUHLIN STRUT LENGTH
(2) 2x4	8'-0"
(1) 2x4 & (1) 2x6	12'-0"
(1) 2x6 & (1) 2x8	20'-0"
(2) 2x6 & (1) 2x8	30'-0"
CONSULT ARCH/ENGR.	>30'-0"

SEE DETAILS 1, 5, 6, 7, 11, 12, 13, & 14 ON S-1.2  
 FOR ROOF FRAMING AND INSULATION OPTIONS

- - - - - PURLIN
- LOAD BEARING WALL
- - - - - LOAD BEARING BEAM/  
GIRDER PER PLAN



**ASPEN HOMES, INC.**  
 BIRCH II GL LOT 6 HOOK FARMS  
 2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

STRUCTURAL DETAILS & NOTES

HD#: 42613  
 DATE: 10/07/2021  
 CHECKED BY: CLS


NO.	ISSUE/REVISION	Revision Date

PLANS DRAWN BY OTHERS


**S-0.5**








**11 HIP SUPPORT FRAME**  
3/8" = 1'-0"




**10 BEAM TO GIRDER CONNECTION**  
3" = 1'-0"

BEAM CONNECTION SCHEDULE	
BEAM SIZE	# OF BOLT IN CONNECTION
W8, W10	2
W12, W14	3
W16, W18	4

NOTES:  
1. NUMBER OF BOLTS DETERMINED BY SMALLER OF TWO BEAMS BEING CONNECTED  
2. ALL BOLTS, 3/4" DIAMETER A325-N, UNO  
3. FULL PERIMETER 1/4" FILLET WELD MAY BE SUBSTITUTED FOR EITHER OR BOTH BOLTED CONNECTIONS




**8 UPSET STEEL BEAM DETAIL**  
1 1/2" = 1'-0"




**9 STEEL BEAM SPLICE DETAIL**  
1 1/2" = 1'-0"

BEAM SIZE	# BOLTS PER SIDE
W8, W10	2
W12, W14	3
W16, W18	4


BOLTS SHALL BE EVENLY SPACED TOP TO BOTTOM




**7 OPTION 4 RAFTER BEARING**  
1" = 1'-0"



**6 OPTION 3 RAFTER BEARING**  
1" = 1'-0"



**5 OPTION 2 RAFTER BEARING**  
1" = 1'-0"  
THIS OPTION NOT AVAILABLE IN KC, MO




**14 VAULTED RAFTER INSULATION**  
3/4" = 1'-0"


TYPE	MAX. UNSUPPORTED SPAN				
	2x8	2x10	2x12	1 3/4"x9 1/2" LVL	1 3/4"x11 7/8" LVL
HIP RAFTER	11'-3"	13'-3"	15'-2"	15'-8"	18'-2"
VALLEY RAFTER	8'-11"	10'-6"	12'-0"	13'-2"	15'-3"

RAFTER SIZE	VAULT FURR DOWN SCHEDULE	
	R-30C INSULATION (X = 9 1/4")	R-38C INSULATION (X = 11 1/4")
2x6	2x6	2x8
2x8	2x4	2x6
2x10	NOT REQUIRED	2x4
2x12	NOT REQUIRED	2x2


NOTES:  
1. ALL VAULTS SHALL BE FURRED DOWN WITH 2X FRAMING TO THE REQUIRED DEPTH OF INSULATION, PLUS 1" AIR SPACE.  
2. R-38C REQUIRED = 11" WITH AIR SPACE.  
3. ALL VAULTED RAFTERS SHALL BE MIN. #2 2x6 DFL @ 16" O.C. OR PER ROOF PLAN.




**12 RAFTER TIE CONNECTION**  
1/2" = 1'-0"




**13 RIDGE SUPPORT**  
1/2" = 1'-0"




**4 STAIR/ RAIL DETAIL**  
1/2" = 1'-0"



**3 BUILT-UP STUD COLUMN**  
1 1/2" = 1'-0"



**2 EGRESS WINDOW SECTION**  
1/2" = 1'-0"




**1 TYPICAL WALL SECTION**  
3/4" = 1'-0"

DUE TO THE WIDE VARIETY OF SOIL CONDITIONS IN OUR AREA AND THE WIDE VARIETY OF PLASTICITY INDEX AND SOIL BEARING CAPACITIES OUR FIRM RECOMMENDS ALL SITES BE EVALUATED BY HD ENGINEERING OR AN HD ENGINEERING REFERRED GEOTECHNICAL FIRM PRIOR TO PLACEMENT OF ANY "STANDARD" FOUNDATIONS.

THIS DOCUMENT CONTAINS COPYRIGHTED MATERIAL AND CONFIDENTIAL INFORMATION BELONGING TO HD ENGINEERING. UNAUTHORIZED USE, DISCLOSURE, REPRODUCTION, OR DUPLICATION OF ANY OF THE INFORMATION CONTAINED HEREIN MAY RESULT IN LIABILITY UNDER APPLICABLE LAW.

HD ENGINEERING & DESIGN, INC.  
11656 W. 75TH STREET  
SHAWNEE, KS 66214  
WWW.HDENGINEERS.COM  
913.631.2222  
SERVICE@HDENGINEERS.COM



STATE OF MISSOURI  
CHRIS SATHOFF  
LICENSED PROFESSIONAL ENGINEER  
NUMBER 2008001865  
EXPIRES 10/07/2022

**ASPEN HOMES, INC.**  
BIRCH II GL LOT 6 HOOK FARMS  
2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

STRUCTURAL DETAILS & NOTES

HD#: 42613



DATE: 10/07/2021  
CHECKED BY: CLS

NO.	ISSUE/REVISION	Revision Date

FRAMING SECTIONS

**S-1.2**






**ASPEN HOMES, INC.**  
 BIRCH II GL LOT 6 HOOK FARMS  
 2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

STRUCTURAL DETAILS & NOTES


HD#: 42613

DATE: 10/07/2021  
 CHECKED BY: CLS


NO.	ISSUE/REVISION	Revision Date




**8** GUARD RAIL  
 1/2" = 1'-0"




**9** STAIR STRINGER DETAIL  
 1/2" = 1'-0"



**7** ROOF LEVEL INTERIOR BEAM TO COLUMN  
 1" = 1'-0"



**6** DECK LEVEL INTERIOR BEAM TO COLUMN  
 1" = 1'-0"



**5** DECK LEVEL EXTERIOR BEAM TO COLUMN  
 1" = 1'-0"

**TABLE IRC2018 R507.9.1.3(1)**  
**DECK LEDGER CONNECTION TO BAND JOIST**<sup>a,b</sup>  
 (DECK LIVE LOAD = 40 PSF, DECK HEAD LOAD = 10 PSF, SNOW LOAD ≤ 40 PSF)


JOIST SPAN	6' AND LESS	6'-1" TO 8'	8'-1" TO 10'	10'-1" TO 12'	12'-1" TO 14'	14'-1" TO 16'	16'-1" TO 18'
CONNECTION DETAILS	ON-CENTER SPACING OF FASTENERS <sup>c,d</sup>						
1/2" LAG SCREW WITH 15/32" MAX. SHEATHING <sup>c,d</sup>	30	23	18	15	13	11	10
1/2" DIAM. BOLT WITH 15/32" MAX. SHEATHING <sup>d</sup>	36	36	34	29	24	21	19
1/2" DIAM. BOLT WITH 15/32" MAX. SHEATHING & 1/2" STACKED WASHERS <sup>e</sup>	36	36	29	24	21	18	16

For SI: 1 inch = 25.4mm, 1 foot = 304.8mm, 1 pound per square foot = 0.0479 kPa  
 a. Ledges shall be flashed in accordance with Section R703.4 to prevent water from contacting the house band joist.  
 b. Snow load shall not be assumed to act concurrently with live load.  
 c. The tip of the lag screw shall fully extend beyond the inside face of the band joist.  
 d. Sheathing shall be wood structural panel or solid sawn lumber.  
 e. Sheathing shall be permitted to be wood structural panel, gypsum board, fiberboard lumber or foam sheathing. Up to 1/2" thickness of stacked washers shall be permitted to substitute for you to 1/2" of allowable sheathing thickness where combined with wood structural panel or lumbers sheathing.


**TABLE IRC2018 R507.9.1.3(2)**  
**PLACEMENT OF LAG SCREWS AND BOLT IN DECK LEDGERS AND BAND JOISTS**

MINIMUM END AND EDGE DISTANCES AND SPACING BETWEEN ROWS				
	TOP EDGE	BOTTOM EDGE	ENDS	ROW SPACING
LEDGER <sup>a</sup>	2 inches <sup>d</sup>	3/4 inches	2 inches <sup>b</sup>	1 5/8 inches <sup>b</sup>
BAND JOIST <sup>c</sup>	3/4 inches	2 inches	2 inches	1 5/8 inches <sup>b</sup>


For SI: 1 inch = 25.4mm.  
 a. Lag screws or bolts shall be staggered from the top to the bottom along the horizontal run of the deck ledger in accordance with Figure R507.9.1.3(1)  
 b. Maximum: 5 inches  
 c. For engineered rim joists, the manufacturer's recommendations shall govern.  
 d. The minimum distances from bottom row of lag screws or bolts to the top of the ledger shall be in accordance with Figure R507.9.1.3(1)





**4** DECK LEDGER TO CANTILEVER  
 3/4" = 1'-0"



**2** DECK LEDGER ATTACHMENT  
 3/4" = 1'-0"



**1** DECK CORNER COLUMN  
 1" = 1'-0"







**ASPEN HOMES, INC.**  
 BIRCH II GL LOT 6 HOOK FARMS  
 2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

HD#: 42613  
 DATE: 10/07/2021  
 CHECKED BY: CLS

NO.	ISSUE/REVISION	Revision Date

BRACED WALL NOTES & DETAILS


**S-2.0**



**3** BRACED WALL PANEL CONNECTIONS  
 1" = 1'-0"

STRUCTURAL DETAILS & NOTES

## TENSION STRAP CAPACITY REQUIRED FOR RESISTING WIND PRESSURES PERPENDICULAR TO METHOD PFH, PFG AND CS-PF BRACED WALL PANELS IRC2018 TABLE R602.10.6.4



**6 LIB BRACING**  
3/8" = 1'-0"

FOR IRC CODE PRESCRIPTIVE METHOD  
**TABLE R602.10.5 MINIMUM LENGTH OF BRACED WALL PANELS**

METHOD (SEE TABLE R602.10.4)	MINIMUM LENGTH (INCHES) <sup>a</sup>					CONTRIBUTING LENGTH (INCHES)	
	WALL HEIGHT						
	8 FEET	9 FEET	10 FEET	11 FEET	12 FEET		
DWB, WSP, SFB, PBS, PCP, HPS, BV-WSP	48	48	48	53	58	ACTUAL <sup>b</sup>	
GB	48	48	48	53	58	DOUBLE SIDED = ACTUAL SINGLE SIDED = .5x ACTUAL	
LIB	55	62	69	NP	NP	ACTUAL <sup>b</sup>	
ABW	SDC A, B, AND C ULTIMATE DESIGN WIND SPEED < 140	28	32	34	38	42	48
	SDC D, D, D ULTIMATE DESIGN WIND SPEED < 140	32	32	34	NP	NP	
PFH	SUPPORTING ROOF ONLY	16	16	16	NOTE C	NOTE C	48
	SPTNG. ONE STORY & ROOF	24	24	24	NOTE C	NOTE C	
PFG		24	27	30	NOTE D	NOTE D	1.5 x ACTUAL <sup>b</sup>
CS-G		24	27	30	33	36	ACTUAL <sup>b</sup>
CS-PF		16	18	20	NOTE E	NOTE E	ACTUAL <sup>b</sup>
CS-WSP, CS-SFB	ADJACENT CLEAR OPENING HEIGHT (INCHES)						ACTUAL <sup>b</sup>
	≤64	24	27	30	33	36	
	68	26	27	30	33	36	
	72	27	27	30	33	36	
	76	30	29	30	33	36	
	80	32	30	30	33	36	
	84	35	32	32	33	36	
	88	38	35	33	33	36	
	92	43	37	35	35	36	
	96	48	41	38	36	36	
	100	-	44	40	38	38	
	104	-	49	43	40	39	
	108	-	54	46	43	41	
	112	-	-	50	45	43	
	116	-	-	55	48	45	
	120	-	-	60	52	48	
124	-	-	-	56	51		
128	-	-	-	61	54		
132	-	-	-	66	58		
136	-	-	-	-	62		
140	-	-	-	-	66		
144	-	-	-	-	72		

<sup>a</sup> LINEAR INTERPOLATION SHALL BE PERMITTED  
<sup>b</sup> USE THE ACTUAL LENGTH WHEN IT IS GREATER THAN OR EQUAL TO THE MINIMUM LENGTH  
<sup>c</sup> MAX. HEADER HEIGHT FOR PFH IS 10' IN ACCORDANCE WITH R602.10.6.2. WALL HEIGHT MAY BE INCREASED TO 12' WITH PONY WALL.  
<sup>d</sup> MAX. OPENING HEIGHT FOR PFH IS 10' IN ACCORDANCE WITH R602.10.6.3. WALL HEIGHT MAY BE INCREASED TO 12' WITH PONY WALL.  
<sup>e</sup> MAX. OPENING HEIGHT FOR CS-PF IS 10' IN ACCORDANCE WITH R602.10.6.4. WALL HEIGHT MAY BE INCREASED TO 12' WITH PONY WALL.

**BRACED WALL PRESCRIPTIVE METHOD:**  
CONTINUOUS EXTERIOR SHEATHING (CS-WSP) PER WSP METHOD (BELOW) UNLESS OTHERWISE NOTED ON THE PLAN

**EXTERIOR BRACED WALL METHOD: (SEE ON THIS SHEET)**

WOOD STRUCTURAL PANEL SHEATHING WITH A THICKNESS NOT LESS THAN 3/8" WITH MINIMUM SPAN RATING OF 24/0 FOR 16" O.C. STUD SPACING WITH 8d COMMON NAILS @ 6" O.C. EDGES AND 12" O.C. FIELD OR SHEATHING THICKNESS NOT LESS THAN 7/16" WITH MINIMUM SPAN RATING OF 24/16 FOR 24" O.C. SPACING WITH 8d COMMON NAILS @ 6" O.C. EDGES AND 12" O.C. IN FIELD (NOTE: FRAMING MEMBERS 16" O.C. MAX. UNBLOCKED, AND W/ SHEATHING APPLIED DIRECTLY TO FRAMING MEMBERS).

**INTERIOR BRACED WALLS (SEE ON THIS SHEET)**

**GB METHOD:**  
1/2" MINIMUM GYPSUM BOARD OVER STUDS SPACED @ 24" MAXIMUM FASTENED W/ #6- 1 1/4" TYPE "W" OR "S" DRYWALL SCREWS @ 7" O.C. EDGES AND FIELD (MIN. 4'-0" SECTION FOR BOTH SIDES)  
OR



**LIB METHOD:**  
1x4 WOOD FASTENED W/ (3) 8d COMMON NAILS OR SIMPSON / USP 16 GA. TYPE WB (OR EQUIVALENT) STL. X-BRACE(S) @ 45° TO 60° ANGLES, MAXIMUM 16" O.C. STUDS FASTENED PER MANUF. SPECS.

MINIMUM WALL STUD FRAMING NOMINAL SIZE & GRADE	MAX. PONY WALL HEIGHT (FEET)	MAX. TOTAL WALL HEIGHT (FEET)	MAX. OPENING WIDTH (FEET)	TENSION STRAP CAPACITY REQUIRED (POUNDS) <sup>a</sup>	
				ULTIMATE DESIGN WIND SPEED V (MPH)	
				115	115
				EXPOSURE B	EXPOSURE C
2x4 NO. 2 GRADE	0	10	18	1,000	1,000
			9	1,000	1,000
			16	1,025	2,500
			18	1,275	2,850
			9	1,000	1,875
			16	2,175	4,125
	2	10	18	2,500	DR
			9	1,500	3,175
			16	3,375	DR
			18	3,975	DR
			9	2,750	DR
			12	3,775	DR
2x6 STUD GRADE	2	12	9	1,000	2,025
			16	2,150	3,675
			18	2,550	DR
			9	1,750	3,125
			16	2,400	DR
			18	3,800	DR
	4	12	9	1,500	3,175
			16	3,375	DR
			18	3,975	DR
			9	2,750	DR
			12	3,775	DR
			18	3,800	DR


<sup>a</sup> DR = DESIGN REQUIRED  
<sup>b</sup> STRAP SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

### END WALL CONDITIONS

FOR CONTINUOUSLY SHEATHED BRACED WALL LINES




**1 DIAPHRAGM CONNECTION TO INTERIOR WALL**  
3/8" = 1'-0"




**5 GB BRACING**  
1/2" = 1'-0"

### FRONT ELEVATION

EXTENT OF HEADER WITH DOUBLE PORTAL FRAMES (TWO BRACED WALL PANELS)




### OVER CONCRETE OR MASONRY BLOCK FOUNDATION



### OVER RAISED WOOD FLOOR - FRAMING ANCHOR OPTION

(WHEN PORTAL SHEATHING DOES NOT LAP OVER BAND OR RIM JOIST)





### OVER RAISED WOOD FLOOR - OVERLAP OPTION

(WHEN PORTAL SHEATHING LAPS OVER BAND OR RIM JOIST)

**4 CS-PF**  
1/2" = 1'-0"

THIS DOCUMENT CONTAINS COPYRIGHTED MATERIAL AND CONFIDENTIAL INFORMATION BELONGING TO HD ENGINEERING UNAUTHORIZED USE, DISCLOSURE, REPRODUCTION OR DUPLICATION OF ANY OF THE INFORMATION CONTAINED HEREIN MAY RESULT IN LIABILITY UNDER APPLICABLE LAW.  
**HD ENGINEERING & DESIGN, INC**  
 11656 W. 75TH STREET  
 SHAWNEE, KS 66214  
 WWW.HDENGINEERS.COM  
 913.631.2222  
 SERVICE@HDENGINEERS.COM



**ASPEN HOMES, INC.**  
 BIRCH II GL LOT 6 HOOK FARMS  
 2018 SW FARMFIELD LN. LEE'S SUMMIT, MO  
 STRUCTURAL DETAILS & NOTES


HD#: 42613

DATE: 10/07/2021  
 CHECKED BY: CLS


NO.	ISSUE/REVISION	Revision Date

BRACED WALLS NOTES & DETAILS


S-2.1




**1** SOLID FOOTING JUMP DETAIL  
3/8" = 1'-0"




**2** RETURN WALL DETAIL  
1/2" = 1'-0"



**3** REINFORCEMENT AT CORNERS AND STEPS  
1/2" = 1'-0"




**4** RETURN WALL PLACEMENT  
3/16" = 1'-0"



**IMPORTANT NOTE:**  
ANY SLAB WITH GREATER THAN 2' OF GRADED ROCK OR 8' OF FILL SOIL BELOW SHALL BE DESIGNED AS STRUCTURAL PER PLAN. OUR FIRM SHOULD BE CONTACTED IMMEDIATELY FOR DESIGN RECOMMENDATIONS. DESIGN MUST BE COMPLETED PRIOR TO PLACEMENT OF PIERS OR FOOTINGS.

**6** WALKOUT DETAIL  
3/4" = 1'-0"




**5** UNRESTRAINED FOUNDATION WALL  
1/2" = 1'-0"

CONCRETE STRENGTH	8" THICK WALL		10" THICK WALL		
	8'	9'	8'	9'	10'
3000 PSI/ 40 KSI	16	12	24	16	12
3500 PSI/ 40 KSI	16	12	24	24	12
3000 PSI/ 60 KSI	24	16	24	20	16
3500 PSI/ 60 KSI	24	16	24	24	16

HORIZONTAL REINFORCEMENT**	4'-#4		5'-#4		6'-#4	
	4'-#4	5'-#4	4'-#4	5'-#4	6'-#4	6'-#4
ONE BAR 12" FROM TOP OF WALL; MAX. SPACING 24" O.C.	4-#4	5-#4	4-#4	5-#4	6-#4	6-#4

\* CONCRETE SHALL HAVE AIR ENTRAINMENT OF 5-7%.  
 \* MINIMUM REQUIREMENT FOR VERTICAL REBAR IN PLAIN CONCRETE WALLS IS #4 @ 36" ON CENTER (ACI 332).  
 \* VERTICAL BARS SHALL BE CONTINUED UP TO WITHIN 8" OF THE TOP OF THE WALL.  
 \* REBAR SHALL BE POSITIONED AT THE TENSION FACE OF THE WALL (2" FROM THE INSIDE FACE).  
 \* REINFORCEMENT SHALL LAP A MINIMUM OF 24 INCHES AT ENDS, SPLICES, AND AROUND CORNERS.  
 \*\* #4 BARS @ 24" ON CENTER.  
 \*\* #4 BAR WITHIN 12 OF TOP AND BOTTOM OF WALL.  
 \*\* MINIMUM GRADE 40 (40ksi) STEEL (PER ACI 332).  
 \*\* HORIZONTAL REINFORCEMENT SHALL BE INSTALLED ON THE COMPRESSION SIDE (SOIL SIDE) OF THE VERTICAL REINFORCEMENT



**7** FOUNDATION FOOTINGS  
1/2" = 1'-0"



**ASPEN HOMES, INC.**  
 BIRCH II GL LOT 6 HOOK FARMS  
 2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

STRUCTURAL DETAILS & NOTES


HD#: 42613  
 DATE: 10/07/2021  
 CHECKED BY: CLS

NO.	ISSUE/REVISION	Revision Date


CONCRETE DETAILS

**S-3.0**


DETAILS PROVIDED ARE DERIVED FROM JOHNSON COUNTY RESIDENTIAL FOUNDATION GUIDELINE



**7 GARAGE SLAB COLUMN DETAIL**  
1" = 1'-0"




**8 STRUCTURAL SLAB/ WALL**  
1 1/2" = 1'-0"




**9 TYPICAL GARAGE SLAB**  
1/4" = 1'-0"

**HD ENGINEERING STRUCTURAL GARAGE SLAB DETAILS**




**6 SUSPENDED PORCH STOOP SLAB**  
1 1/2" = 1'-0"

FOR SUSPENDED SLABS A MAXIMUM OF 10' ABOVE FLOOR BELOW: TEMPORARY SHORING WALLS SHALL BE PLACED AT A MAXIMUM OF 4' O.C./#2-2X4 STUDS AT 16" O.C. W/ TOP AND BOTTOM PLATE. WALL TO HAVE CONTINUOUS DIAGONAL BRACING. LATERAL BRACING TO BE RUN FROM WALL TO WALL AT MID HEIGHT 4' ON CENTER. SHORING TO REMAIN IN PLACE FOR AT LEAST 21 DAYS.




**1 SUSPENDED SLAB BEAM/WALL CONNECTION**  
1 1/2" = 1'-0"




\*FASTEN STEEL ANGLE TO BEAM W/ TEK SCREWS OR 2"x1/4" FILLET WELD @ 12" O.C.


**2 SUSPENDED SLAB POUR STOP**  
1 1/2" = 1'-0"




**3 SUSPENDED SLAB/STEEL BEAM CROSS SECTION**  
1 1/2" = 1'-0"



**4 SUSPENDED SLAB/WALL CONNECTION**  
1 1/2" = 1'-0"





**10 ZERO ENTRY GARAGE DETAIL**  
1 1/2" = 1'-0"



**5 CONCRETE HEADER DETAIL**  
1 1/2" = 1'-0"

**IMPORTANT NOTE:**  
FOR SUSPENDED SLABS A MAXIMUM OF 10' ABOVE FLOOR BELOW: TEMPORARY SHORING WALLS SHALL BE PLACED AT A MAXIMUM OF 4' O.C./#2-2X4 STUDS AT 16" O.C. W/ TOP AND BOTTOM PLATE. WALL TO HAVE CONTINUOUS DIAGONAL BRACING. LATERAL BRACING TO BE RUN FROM WALL TO WALL AT MID HEIGHT 4' ON CENTER. SHORING TO REMAIN IN PLACE FOR AT LEAST 21 DAYS.  
ANY CAST IN PLACE SLABS FORMED MORE THAN 10' ABOVE THE FLOOR BELOW SHALL HAVE A SITE SPECIFIC SHORING DESIGN DONE. OUR FIRM SHOULD BE CONSULTED FOR THIS DESIGN ONCE FOUNDATION WALLS ARE IN PLACE TO EVALUATE ALL FIELD CONDITIONS. IT SHOULD BE NOTED THAT FAILURE TO HAVE AN ADEQUATE SHORING DESIGN CAN RESULT IN FORM COLAPSE AND/OR CATASTROPHIC FAILURE.




**ASPEN HOMES, INC.**  
BIRCH II GL LOT 6 HOOK FARMS  
2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

STRUCTURAL DETAILS & NOTES


HD#: 42613  
DATE: 10/07/2021  
CHECKED BY: CLS

NO.	ISSUE/REVISION	Revision Date


SUSPENDED SLAB DETAILS




10 ZERO ENTRY SHOWER DETAIL  
1/4" = 1'-0"




5 STEEL BEAM TO WOOD PLATE  
1 1/2" = 1'-0"




9 WOOD TO WOOD STACKED CONNECTION  
1" = 1'-0"




4 FLUSH WOOD BEAM CONNECTION  
1 1/2" = 1'-0"




8 UPSET WOOD/STEEL PARALLEL TO WALL  
1" = 1'-0"




3 EXTERIOR WALL STEEL BEAM BEARING  
1" = 1'-0"




7 UPSET WOOD PERPENDICULAR TO WALL  
1" = 1'-0"




2 DOWN WOOD BEAM PERPENDICULAR  
1" = 1'-0"



11 SHEATHING JOINT LOCATION  
1" = 1'-0"





6 STEEL COLUMN TO WOOD FLOOR  
1 1/2" = 1'-0"



1 DOWN WOOD BEAM PARALLEL  
1" = 1'-0"

THIS DOCUMENT CONTAINS COPYRIGHTED MATERIAL AND CONFIDENTIAL INFORMATION BELONGING TO HD ENGINEERING UNAUTHORIZED USE, DISCLOSURE, REPRODUCTION, OR DUPLICATION OF ANY OF THE INFORMATION CONTAINED HEREIN MAY RESULT IN LIABILITY UNDER APPLICABLE LAW.

HD ENGINEERING & DESIGN, INC  
11656 W. 75TH STREET  
SHAWNEE, KS 66214  
WWW.HDENGINEERS.COM  
913.631.2222  
SERVICE@HDENGINEERS.COM



ASPEN HOMES, INC.  
BIRCH II GL LOT 6 HOOK FARMS  
2018 SW FARMFIELD LN. LEE'S SUMMIT, MO

STRUCTURAL DETAILS & NOTES

HD#: 42613  
DATE: 10/07/2021  
CHECKED BY: CLS

NO.	ISSUE/REVISION	Revision Date

GENERAL DETAILS

S-4.0