

| ROOF AREA | |
|-------------|-------|
| PITCH | SA. |
| 8/12 | 24.58 |
| 7/12 | 3.39 |
| 3/12 (CLAD) | 3.25 |

ROOF
SCALE: 1/4" = 1'-0"

WALL RAFTERS SHALL BE 2" X 6" @ 16" O.C., UNLESS NOTED OTHERWISE.
SEE DETAIL 7/332 FOR ALTERNATE RAFTER BEARING DETAIL WHEN RAFTERS ARE REQUIRED TO BEAR HIGHER THAN THE WALL DOUBLE TOP PLATE.
FLASHING NOTE:
DROP EDGE, VALLEYS AND FLASHINGS TO BE METAL CLAD.
ROOF NOTES:
ROOF DESIGNED FOR LIGHT ROOF COVERING
30psf TOTAL LOAD (30psf DL, 20psf LL (SL))
* RAFTERS CHEM-FIR, DOUG-FIR, OR EQUAL.
SEE SPAN CHARTS BELOW

| RAFTERS | SPACING | MAX HORIZONTAL CLEARSPAN |
|---------|-----------|--------------------------|
| R2-2x6 | R24" O.C. | 11'-3" |
| R2-2x6 | R32" O.C. | 14'-2" |
| R2-2x6 | R24" O.C. | 14'-8" |
| R2-2x8 | R36" O.C. | 17'-11" |
| R2-2x10 | R24" O.C. | 17'-10" |
| R2-2x10 | R36" O.C. | 21'-11" |

| RAFTERS | SPACING | MAX HORIZONTAL CLEARSPAN |
|---------|-----------|--------------------------|
| R2-2x6 | R24" O.C. | 8'-6" |
| R2-2x6 | R36" O.C. | 9'-3" |
| R2-2x8 | R24" O.C. | 11'-3" |
| R2-2x8 | R32" O.C. | 12'-9" |
| R2-2x10 | R24" O.C. | 14'-3" |
| R2-2x10 | R36" O.C. | 16'-3" |

DEFLECTION = L/360 LIVE LOAD, L/240 TOTAL LOAD
* WALLS TO BE 2x10 DEPTH
* RIDGE BOARDS ARE UNLESS OTHERWISE NOTED:
- R2-2x8 UP TO 10/12 PITCH
- R2-2x10 OVER 10/12 PITCH
* ALL HIPS & VALLEYS ARE UNLESS OTHERWISE NOTED:
- R2-2x8 UP TO 10/12 PITCH
- R2-2x10 OVER 10/12 PITCH
* PURLINS ARE 2x6 MIN.
- PURLIN STRUTS ARE AT 4'-0" O.C.
- PURLIN STRUTS SHALL BE INSTALLED AT NOT LESS THAN A 45 DEGREE ANGLE WITH THE HORIZONTAL.
- ALL PURLIN STRUTS SHALL HAVE A MAXIMUM UNBRAZED LENGTH OF 8'-0"
- PURLIN STRUTS SHALL BE CONSTRUCTED IN A "Y" CONFIGURATION AND PER THE FOLLOWING CHART:

| PURLIN STRUT | MAX PURLIN STRUT LENGTH |
|----------------------|-------------------------|
| (2) 2x4 | 8'-0" |
| (1) 2x4 & (1) 2x6 | 12'-0" |
| (1) 2x6 & (1) 2x8 | 20'-0" |
| (1) 2x6 & (1) 2x10 | 30'-0" |
| (CONSULT ARCH/ENGR.) | 30'-0" |

* RIDGE BRACES ARE SAME AS PURLIN BRACES - SPACING, SIZE, CONFIGURATION & INSTALLATION (SEE PURLIN BRACE NOTES ABOVE)
* HIP & VALLEY BRACES ARE SAME AS PURLIN SIZE, CONFIGURATION & INSTALLATION (SEE PURLIN BRACE NOTES ABOVE)
* VERTICAL BRACE IF DOT IS UNDER HIP OR VALLEY
* SLASH IS TOP END OF BRACE (/)
* DOT IS BOTTOM OF BRACE (•)
* --- DENOTES BEARING WALL
* --- DENOTES ROOF BRACE
* --- DENOTES PURLIN
* --- DENOTES BEARING STRUCTURE

These plans and specifications are protected under federal copyright laws. Copyright © 2021 Viewpoint Residential Design, LLC. Care and effort have gone into the creation and design of this plan. However, the user of these plans is advised that the user must be undertaken without the assistance of a construction professional, architect or engineer. Because of the impossibility of any on site consultation and supervision, Viewpoint Residential Design, LLC and Designer assume no responsibility for any damage, injury or loss of life or property that may result from the use of these plans, drawings or blueprints. Also, site conditions may vary from those illustrated on this plan. Designer does not warrant the suitability of these plans for use on your specific site. Consult your architect to determine the suitability of these plans for your specific site and application.

"For God so loved the world, that he gave his only begotten Son, that whosoever believeth in him should not perish, but have everlasting life." (John 3:16)

VIEWPOINT
RESIDENTIAL DESIGN LLC
Office: (816) 354-0400
Email: admin@viewpointdesign.net

Site Description:
Lot 116, New Longview
Street Address:
**3234 SW Pergola Park Dr.,
Lee's Summit, Missouri**


Designed for:
Thomas & Sophie WILLIAMS
General Contractor:
Bellah Homes, LLC



Date: 10 - 9 - AD 2021
Rev. 1:
Rev. 2:
Rev. 3:

Sheet Title:
ROOF PLAN

Sheet No.:
A-2 of 5



8'-0" CEILING
 SECOND LEVEL
 SCALE: 1/4" = 1'-0"

***** = WALL BRACING PER FRAMING NOTE #1 AND PER CALCULATIONS ON SHEET S31.

FRAMING NOTES

- SECOND LEVEL EXTERIOR WALLS SHALL BE SHEATHED W/ 7/16" OSB. APA PANELS W/ 6d COMMON NAILS @ 6" O.C. AT EDGES & @ 12" O.C. IN THE FIELD. SMART PANEL, OR EQUAL, INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
- XXXXXXXXXXXX = 6d: 1/2" MIN. GYPSUM BOARD OVER STUDS SPACED 24" MAX. FASTENED W/ NO. 6 - 1 1/4" TYPE W OR S DRYWALL SCREWS @ 7" O.C. EDGES & FIELD. (MIN. 8'-0" SECTIONS ONE SIDE OF WALL (30" MIN. 4'-0" SECTION FOR BOTH SIDES))
- XXXXXXXXXXXX = LOAD BEARING INTERIOR WALL.
- (2) 2" X 10" #2 HEADER AT ALL EXTERIOR AND LOAD BEARING WALLS, UNLESS NOTED OTHERWISE.
- LOW TIES @ 4'-0" O.C. (TYPICAL)
- ROW STUDS THE FULL HEIGHT OF RAISED PLATE WALLS.
- BLECK: JOISTS ABOVE BEAMS, CANTILEVERS AND LOAD BEARING WALLS WITH JOIST MATERIAL (NOT REQUIRED WITH F-EXIST).
- PROVIDE MULTIPLE STUDS FOR SOLID BEARING BELOW ALL BEAMS.
- ALL DESIGNATED 2" X 6" WALLS SHALL HAVE DOUBLE KING STUDS AT DOOR AND WINDOW OPENINGS.
- ALL UNSURE WALLS SHALL BE 45", UNLESS NOTED OTHERWISE.
- ALL WALLS TO BE FRAMED W/ MIN. STUD GRADE 2" X 4S @ 16" O.C. UNLESS NOTED OTHERWISE.
- EXTERIOR WALL BOTTOM PLATES SHALL BE NAILED TO FRAMING BELOW WITH 16d COMMON NAILS @ 16" O.C. MAX. (WHERE APPLICABLE)
- LVL'S SHOWN ON PLANS MAY BE REPLACED WITH 18"/16" GRADE 24F-V4 GLULAM BEAMS OF THE SAME DEPTH, AND THE FOLLOWING WIDTHS:
 (2) 1 3/4" LVL PILES = 3 1/2" GLULAM
 (3) 1 3/4" LVL PILES = 5 1/2" GLULAM
- CONTRACTOR SHALL NOTIFY ENGINEER OF RECORD BEFORE CONSTRUCTION OF ANY DEFLECTION LIMITATIONS MORE STRINGENT THAN CODE MINIMUMS ABOVE ANY OPENINGS.


These plans and specifications are protected under federal copyright laws.
 Copyright © 2021 Viewpoint Residential Design, LLC.
 Care and effort have gone into the creation and design of this plan. However, the user of these plans is advised that the user must be responsible for obtaining all necessary permits and for the proper construction of the project. Viewpoint Residential Design, LLC and Designer assume no responsibility for any damages, errors, or omissions that may occur in the construction of the project. The user of these plans is advised that the user must be responsible for obtaining all necessary permits and for the proper construction of the project. Viewpoint Residential Design, LLC and Designer assume no responsibility for any damages, errors, or omissions that may occur in the construction of the project. The user of these plans is advised that the user must be responsible for obtaining all necessary permits and for the proper construction of the project. Viewpoint Residential Design, LLC and Designer assume no responsibility for any damages, errors, or omissions that may occur in the construction of the project.

"For God so loved the world, that he gave his only begotten Son, that whosoever believeth in him should not perish, but have everlasting life." (John 3:16)

VIEWPOINT
 RESIDENTIAL DESIGN LLC
 Office: (816) 354-0400 Email: admin@viewpointdesign.net

Site Description:
Lot 116, New Longview
 Street Address:
3234 SW Pergola Park Dr.,
Lee's Summit, Missouri


Designed for:
Thomas & Sophie WILLIAMS
 General Contractor:
Bellah Homes, LLC



Date: 10-9-AD 2021
 Rev. 1:
 Rev. 2:
 Rev. 3:

Sheet Title:
SECOND LEVEL PLAN

Sheet No.:
A-4 of 5



9'-0" FOUNDATION WALLS
(UNLESS NOTED OTHERWISE)
ON 16" X 8" STRIP FOOTINGS
(STEP WHERE GRADE REQUIRES)

2" X 10" FLOOR SYSTEM ABOVE
FOUNDATION
SCALE: 1/4" = 1'-0"

***** = WALL BRACING PER FRAMING NOTE #1 AND PER CALCULATIONS IN SHEET S11.

FRAMING NOTES

1. BASEMENT LEVEL EXTERIOR WOOD-FRAMED WALLS SHALL BE SHEATHED W/ 7/16" OSB APA PANELS W/ 84 COMMON WALLS @ 6" OC. AT EDGES & @ 12" OC. IN THE FIELD. SMART PANEL, OR EQUAL, INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
2. = 60-1/2" MIN. GYPSUM BOARD OVER STUDS SPACED 24" MAX FASTENED W/ #6 @ 1-1/4" TYPE W OR 3/8" WALL SCREWS @ 7" OC. EDGES & FIELD. MIN. 8'-0" SECTIONS ONE SIDE OF WALL. (SEE MIN. 4'-0" SECTION FOR BOTH SIDES).
3. = LOAD BEARING INTERIOR WALL.
4. (2) 2" X 10" #2 HEADER AT ALL EXTERIOR AND LOAD BEARING WALLS, UNLESS NOTED OTHERWISE.
5. LVL STUDS @ 4'-0" O.C. (TYPICAL).
6. RUN STUDS THE FULL HEIGHT OF RAISED PLATE WALLS.
7. BLOCK JOISTS ABOVE BEAMS, CANTILEVERS AND LOAD BEARING WALLS WITH JOIST MATERIAL NOT REQUIRED WITH I-JOISTS.
8. PROVIDE MULTIPLE STUDS FOR SOLID BEARING BELOW ALL BEAMS.
9. ALL RESISTED 2" X 6" WALLS SHALL HAVE DOUBLE KING STUDS AT DOOR AND WINDOW OPENINGS.
10. ALL UNSQUARE WALLS SHALL BE 45°, UNLESS NOTED OTHERWISE.
11. ALL WALLS TO BE FRAMED W/ MIN. STUD GRADE 2" X 4" @ 16" O.C. UNLESS NOTED OTHERWISE.
12. 1/2" # ANCHOR BOLTS W/ MIN. 7" EMBEDMENT @ 48" O.C. MAX. & WITHIN 6" - 12" OF END OF EACH PLATE LENGTH.
13. LVL'S SHOWN ON PLANS MAY BE REPLACED WITH 15/16" OEG 24F-V4 GLULAM BEAMS OF THE SAME DEPTH AND THE FOLLOWING WIDTHS:
(1) 3/4" LVL PLIES = 3 1/2" GLULAM
(2) 1 3/4" LVL PLIES = 5 1/2" GLULAM
14. NEW FOUNDATION SHALL BEAR ON ORIGINAL SOIL WITH MINIMUM BEARING CAPACITY OF 1500 PSF. A GEOTECHNICAL ENGINEER IS RECOMMENDED FOR VERIFICATION OF THESE CONDITIONS DURING THE EXCAVATION PHASE. ENGINEER OF RECORD ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION NOT VERIFIED TO BE FOUNDED ON ANYTHING SHORT OF THE AFOREMENTIONED REQUIREMENTS.
15. CONTRACTOR SHALL NOTIFY ENGINEER OF RECORD BEFORE CONSTRUCTION OF ANY DEFLECTION LIMITATIONS MORE STRINGENT THAN CODE MINIMUMS ABOVE ANY OPENINGS.

| STEEL COLUMN & PAD FOOTING SCHEDULE | |
|-------------------------------------|---|
| | 3" X 11 GA STEEL COLUMN ON 36" X 36" X 10" PAD FOOTING W/ (4) #4 BARS EACH WAY (C253) |
| | 3 1/2" X 11 GA STEEL COLUMN ON 36" X 36" X 10" PAD FOOTING W/ (4) #4 BARS EACH WAY (C810) |
| | 3" S24 40 STEEL COLUMN ON 42" X 42" X 12" PAD FOOTING W/ (3) #4 BARS EACH WAY (C453) |
| | 3 1/2" S24 40 STEEL COLUMN ON 48" X 48" X 12" PAD FOOTING W/ (3) #4 BARS EACH WAY (C203) |
| | 3 1/2" S24 40 STEEL COLUMN ON 54" X 54" X 14" PAD FOOTING W/ (3) #4 BARS EACH WAY (A153) |
| | 3 1/2" S24 40 STEEL COLUMN ON 60" X 60" X 14" PAD FOOTING W/ (3) #4 BARS EACH WAY (C83) |


These plans and specifications are protected under federal copyright laws. Copyright © 2021 Viewpoint Residential Design, LLC. Care and effort have gone into the creation and design of this plan. However, the user of this plan is advised that the design is not to be used for any other project without the assistance of a construction professional, architect or engineer. Because of the impossibility of any on-site consultation and supervision, Viewpoint Residential Design, LLC and Designer assume no responsibility for any damage, injury, or loss of property, or for any other consequences that may result from the use of these blueprints. Also, site conditions may vary from those illustrated on this plan. Designer does not warrant the suitability of these plans for use on your specific site. Consult your architect to determine the suitability of these plans for your specific site and applicable laws.

"For God so loved the world, that he gave his only begotten Son, that whosoever believeth in him should not perish, but have everlasting life." (John 3:16)

VIEWPOINT
RESIDENTIAL DESIGN LLC
Office: (816) 354-0400 Email: admin@viewpointdesign.net

Site Description:
Lot 116, New Longview
Street Address:
**3234 SW Pergola Park Dr.,
Lee's Summit, Missouri**

Designed for:
Thomas & Sophie WILLIAMS
General Contractor:
Bellah Homes, LLC



Date: 10-9-AD 2021
Rev. 1:
Rev. 2:
Rev. 3:

Sheet Title:
FOUNDATION PLAN

Sheet No.:
A-5 of 5

RESIDENTIAL SEISMIC & WIND ANALYSIS

DETERMINE WEIGHT OF HOUSE:

| LOCATION | DEAD LOAD (psf) | AREA (ft ²) | WEIGHT (lbs.) |
|-------------------------------------|-----------------|-------------------------|---------------|
| ROOF | 10 | 2360 | 23600 |
| CEILING | 10 | 2360 | 23600 |
| SECOND FLOOR | 10 | 1053 | 10530 |
| FIRST FLOOR | 10 | 2360 | 23600 |
| SECOND FLOOR EXT. WALL DL | 161.32 | 8 | 10324.48 |
| FIRST FLOOR EXT. WALL DL | 208.86 | 10 | 20886 |
| SECOND FLOOR INT. PARTITION WALL DL | 6 | 1053 | 6318 |
| FIRST FLOOR INT. PARTITION WALL DL | 6 | 2360 | 14160 |

| PROJECTED AREAS (WIND DESIGN PER 115 MPH 3-SECOND GUST, EXPOSURE C AND MEAN ROOF HEIGHT <= 30 FT ASSUMED) | | | |
|---|--------|--------------|-------------------------|
| FRONT-TO-BACK | | SIDE-TO-SIDE | |
| AREA | LOAD | AREA | LOAD |
| SLOPED ROOF | 221 | 1890 | 187 |
| VERT. ROOF | 194 | 2412 | 309 |
| 2ND | 308.97 | 3862 | 416.97 |
| 1ST | 399.63 | 4968 | 748 |
| PRESSURE (PSF) - PER ASCE CH. 6 | | 1ST | |
| SLOPED ROOF | 9.7 | 11.3 | 2a (FIG. 28.6-1, ASCE7) |
| WALL/VERT. ROOF | 14.2 | 7.7 | 7.266 |
| MEAN ROOF HT., ft | 27 | | |

a) If there is a walkout wall to be sheathed, determine tributary wind area and enter here. If no walkout, enter 0 for area.
 $C_{e10} = 0.00256 K_d K_{e1} V_f$ (ASCE7-10 Velocity Pressure) $C_{e10} = 0.6 Q_{z10}$ (Design Velocity Pressure for ASD analysis under ASCE7-10 and IRC/IBC 2012)

| | |
|---|----------|
| 2ND FLOOR TRIBUTARY WEIGHT | 52362.24 |
| 1ST FLOOR TRIBUTARY WEIGHT | 84805.48 |
| S _s (SITE GROUND MOTION - %g - FROM ASCE7 SEISMIC MAP) | 12.0% |
| F _a (from ASCE7 Table 11.4-1) | 1.6 |
| S _{ps} (= 2/3 * S _s * F _a) | 0.128 |
| R (from ASCE7 Table 12.2-1) | 6.5 |

SEISMIC SHEAR

| LOCATION | From ASCE7 (Eq. 12.8-1): | V (= 1.2 * S _{ps} * W / R) (lbs.) |
|-----------|--------------------------|--|
| 2ND FLOOR | | 1237 |
| 1ST FLOOR | | 2904 |

| Sheathing Location | Min. Sheathing Schedule | Fastening Schedule | Allowable Shear (#/LF) | Code Reference |
|----------------------|---|--|------------------------|--------------------------|
| Exterior (Option #1) | 7/16" APA Rated Plywood/OSB | 1/2" 18ga. Staples w/ 1" penetration @ 4" O.C. Edges, 8" O.C. Field for 24" stud spacing, 12" O.C. Field for 18" stud spacing | 155 | per IBC, Table 2306.3(1) |
| Exterior (Option #2) | 7/16" APA Rated Plywood/OSB | 1/2" 18ga. Staples w/ 1" penetration @ 4" O.C. Edges, 8" O.C. Field for 24" stud spacing, 12" O.C. Field for 18" stud spacing | 230 | per IBC, Table 2306.3(1) |
| Exterior (Option #3) | 7/16" APA Rated Plywood/OSB | 1/2" 18ga. Staples w/ 1" penetration @ 3" O.C. Edges, 8" O.C. Field for 24" stud spacing, 12" O.C. Field for 18" stud spacing | 310 | per IBC, Table 2306.3(1) |
| Exterior (Option #4) | 7/16" APA Rated Plywood/OSB or shiplap panel sheathing, or 3/8" shiplap panel sheathing with tighter nail spacing | 8d Common Nails w/ 1-3/8" penetration @ 6" O.C. Edges, 12" O.C. Field for 7/16" APA-rated plywood/OSB or shiplap panel sheathing OR @ 4" O.C. Edges, 12" O.C. Field for 3/8" shiplap panel sheathing | 220 | AF&PA SDPWS Table 4.3A |
| Exterior (Option #5) | 7/16" APA Rated Plywood/OSB or shiplap panel sheathing, or 3/8" shiplap panel sheathing with tighter nail spacing | 8d Common Nails w/ 1-3/8" penetration @ 4" O.C. Edges, 12" O.C. Field for 7/16" APA-rated plywood/OSB or shiplap panel sheathing OR @ 3" O.C. Edges, 12" O.C. Field for 3/8" shiplap panel sheathing | 320 | AF&PA SDPWS Table 4.3A |
| Exterior (Option #6) | 7/16" APA Rated Plywood/OSB or shiplap panel sheathing, or 3/8" shiplap panel sheathing with tighter nail spacing and double studs at each panel edge | 8d Common Nails w/ 1-3/8" penetration @ 3" O.C. Edges, 12" O.C. Field | 410 | AF&PA SDPWS Table 4.3A |
| Interior | 1/2" Gypsum Board | No. 6-1 1/4" Type W or S Screws @ 8" O.C. Edges, 12" O.C. Field | 60 | per IBC, Table 2306.4.4 |
| Interior | 16 Ga. Simpson/USP Type WB Steel X-Brace (or equal) | (3) 16d @ end studs & (1) 8d @ intermediate studs (per manufacturer specifications - see detail on sheet S3) | 325 | |

| | |
|--|---|
| EXTERIOR SHEATHING OPTION FOR SECOND FLOOR | 4 |
| EXTERIOR SHEATHING OPTION FOR FIRST FLOOR | 5 |

| WIDTH OF 1ST STORY (FT.) | 36.33 | WIDTH OF 2ND STORY (FT.) | 34.33 |
|---------------------------|-------|--------------------------|-------|
| DEPTH OF 1ST STORY (FT.) | 68 | DEPTH OF 2ND STORY (FT.) | 46.33 |
| BACK WALL OF GARAGE (FT.) | 0 | | |
| GAR. WALL: 1=F-B, 2=S-S | 2 | | |

EXTERIOR STRUCTURAL WALL LENGTHS (ft) & RESISTANCES

| | SEISMIC | | | WIND | | |
|-----------|---------------|-------------------|--------------|---------------|-------------------|--------------|
| | FRONT-TO-BACK | RESISTANCE (lbs.) | SIDE-TO-SIDE | FRONT-TO-BACK | RESISTANCE (lbs.) | SIDE-TO-SIDE |
| 2ND FLOOR | 35 | 9800 | 42 | 35 | 13720 | 42 |
| 1ST FLOOR | 63 | 23940 | 46 | 63 | 33516 | 46 |

| | ADDITIONAL RESISTANCE REQUIRED | | Anchor Bolt Spacing (in.) | | 16d Nail Spacing req'd at bottom plate (in.) | |
|-------------------------|--------------------------------|------|---------------------------|------------------|--|---------------|
| | SEISMIC | WIND | diameter (in.) | spacing (inches) | 2nd Floor F-B | 1st Floor S-S |
| 2ND FLOOR FRONT-TO-BACK | 0 | 0 | 0.5 | 944 | 20 | 20 |
| 2ND FLOOR SIDE-TO-SIDE | 0 | 0 | 187.8 | 187.8 | 28 | 28 |
| 1ST FLOOR FRONT-TO-BACK | 0 | 0 | 89.8 | 89.8 | 10 | 10 |
| 1ST FLOOR SIDE-TO-SIDE | 0 | 0 | | | | |

RESISTANCE REQUIRED IN ADDITION TO RESISTANCE PROVIDED BY EXTERIOR WALLS**

| | ADDITIONAL RESISTANCE REQUIRED (POUNDS) | PORTAL FRAMES OR PERF. SHEAR WALL RESISTANCE | INTERIOR X-BRACES (325#/BRACE) | INTERIOR WALL LENGTH W/ 1/2" GYPSUM BOARD PER TABLE (FT.) | INT. WALL LENGTH SHEATHED W/ OSB (TOTAL LENGTH, ONE SIDE, FT.) | RESISTANCE PROVIDED BY ADDITIONAL METHODS (POUNDS) | OK? |
|-------------------------|---|--|--------------------------------|---|--|--|-----|
| 2ND FLOOR FRONT-TO-BACK | 0 | | | | | 0 | YES |
| 2ND FLOOR SIDE-TO-SIDE | 0 | | | | | 0 | YES |
| 1ST FLOOR FRONT-TO-BACK | 0 | | | | | 0 | YES |
| 1ST FLOOR SIDE-TO-SIDE | 0 | | | | | 0 | YES |

**NOTES: 1) SEE ATTACHED CALCULATIONS FOR PORTAL FRAME OR PERFORATED SHEAR WALL RESISTANCE CAPACITIES (IF APPLICABLE).

2) SEE SHEET S1 FOR INTERIOR STEEL X-BRACE INSTALLATION. 3) INTERIOR WALLS SHEATHED WITH OSB SHALL BE ATTACHED WITH SAME STAPLE/NAILING PATTERN AS EXTERIOR OSB ON SAME FLOOR (SEE TABLE ABOVE) AND ARE ONLY APPLICABLE FOR FULL-HEIGHT SECTIONS OF 2'-8" OR LONGER

ALL LATERAL BRACING ACHIEVED AT EXTERIOR WALLS AND WALLS DIRECTLY ON FOUNDATIONS; THEREFORE, NO INTERIOR BRACING PER 2012 IRC SECTION R502.2.1 IS REQUIRED


WIND UPLIFT ANALYSIS

| ROOF PITCH (MAX) | X/12 | DEGREES | PITCH OF 6 OR LESS: EOH -13.3, E -7.2, G -5.2 |
|-------------------------|--|--------------------------------|---|
| | 9 | 33.7 | |
| ASCE 7 | | | |
| OVERHANG | LENGTH (FT.) | PRESSURE (PSF) | LINAL FT. OF OH |
| | | -1.08 | -1.08 |
| | TOTAL AREA (FT ²) | ZONE E AREA (FT ²) | ZONE G AREA (FT ²) |
| | 2470.44 | 960.972036 | 1509.467904 |
| MAIN ROOF** | | 960.972036 | -1.08 |
| | | | -0.36 |
| ALONG PERIMETER | TOTAL UPLIFT PER LINEAL FOOT ALONG EXTERIOR (POUNDS) | | -3.7 |
| **INSIDE EXTERIOR WALLS | RESISTANCE DUE TO DEAD WEIGHT & (3) 16d NAILS | | 251.6 |
| | | | UPLIFT OK |

NOTE FOR CONSTRUCTION: THE CONTINUOUS STRUCTURAL PANEL SHEATHING BRACING METHOD REQUIRES USE OF THE ABOVE TABLE FOR SHEATHING OF THE ENTIRE STRUCTURE. IN ADDITION, FRAMING MEMBERS SHALL BE @ 16" O.C. MAX, UNBLOCKED, AND W/ SHEATHING APPLIED DIRECTLY TO FRAMING MEMBERS

NOTE FOR DESIGN: ALL WALLS USED IN THE CALCULATION OF THE RESISTANCE FOR THIS STRUCTURE SHALL HAVE A MINIMUM UNINTERRUPTED HEIGHT OF 8'-0" AND LENGTH OF 2'-8". ALLOWABLE RESISTANCES HAVE BEEN #/FT AND INCREASED BY 40% FOR WIND LOADS, PER VALUES IN 2012 IBC SECTION 2306 AND AF&PA SDPWS TABLE 4.3A. FOR EXAMPLE, 7/16" APA-RATED SHEATHING WITH 8d @ 6" & 12" HAS A SEISMIC SHEAR VALUE OF 240 A WIND SHEAR VALUE OF 335#/FT - 40% GREATER THAN THAT OF SEISMIC)

NOTE: SOIL SITE CLASS ASSUMED TO BE CLASS D. IF SITE CONDITIONS ARE DETERMINED TO BE CLASS E OR F, CONSULT ENGINEER BEFORE PROCEEDING WITH CONSTRUCTION



1 BRACED RAFTER CONSTRUCTION
 S1.1 SCALE: 1" = 16" (18x20) OR 1/2" = 16" (20x20)

VISTA
 ENGINEERING, LLC
 14718 NW DELIA STREET * PORTLAND, OREGON 97229
 OFFICE: 971.255.6099 * MOBILE: 971.255.6099 *
 DENNIS@VISTAENGINEERING.COM * VISTAENGINEERING.COM

CLIENT: BELLAH HOMES, LLC
 JOB TITLE: NLV116 WILLIAMS
 LOT 116, NEW LONGVIEW
 LOCATION: 3234 SW PERGOLA PARK DR.
 LEE'S SUMMIT, MISSOURI


STATE OF MISSOURI
 DENNIS HEIER
 NUMBER: PE-2018001772
 PROFESSIONAL ENGINEER
 10-11-2021

| NO. | DATE | REVISION | BY |
|-----|------|----------|----|
| | | | |
| | | | |
| | | | |
| | | | |

DRAWING TITLE
STRUCTURAL CALCULATIONS


ENGINEER: DMH CHECKED BY: DMH
 JOB NO. 3885 DRAWN BY: DMH
 DATE: 10-11-21
 SHEET NUMBER
S1.1

RELEASE FOR CONSTRUCTION
 NOTED FOR REVIEW
 LEE'S SUMMIT, MISSOURI
 11/15/2021




1 DAYLIGHT WALL CONSTRUCTION
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)


| DAYLIGHT BASEMENT WALL SCHEDULE | | | | | | |
|---------------------------------|-------|-------|--------|--------|---------------------|---------------|
| A | B | C | D | E | F | G |
| 4'-0" | 1'-6" | 0'-8" | 0'-5" | (2) #4 | #4 VERT. @ 12" O.C. | (2) #4 HORIZ. |
| 5'-0" | 2'-0" | 0'-8" | 0'-7" | (2) #4 | #4 VERT. @ 12" O.C. | (3) #4 HORIZ. |
| 6'-0" | 2'-6" | 0'-8" | 0'-10" | (3) #4 | #4 VERT. @ 12" O.C. | (3) #4 HORIZ. |




3 CONCRETE WALL SECTION
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)



2 COLUMN AND BEARING PAD SCHEDULE
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)




5 SOLID JUMP
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)



6 REINFORCEMENT AT OPENING CORNERS AND STEP CORNERS @ INSIDE CORNERS
SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)

NOTE: WHERE FLOOR JOIST RUNS PARALLEL TO FDN WALL, SOLID BLOCK OUTSIDE 3 JOIST SPACES @ 36" OC ALIGNING BLOCKING WITH THE ANCHOR BOLT




7 RETURN WALL DETAIL
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)

| CONCRETE STRENGTH/GRADE REINFORCEMENT (#4 BARS) | 8" THICK WALL | | | 10" THICK WALL | | |
|---|---------------|----|-----|----------------|----|-----|
| | 8' | 9' | 10' | 8' | 9' | 10' |
| 3,000 PSI/ GRADE 40 | 24 | 24 | 16 | 24 | 24 | 18 |
| 3,500 PSI/ GRADE 40 | 24 | 24 | 16 | 24 | 24 | 18 |
| 3,000 PSI/ GRADE 60 | 24 | 24 | 16 | 24 | 24 | 18 |
| 3,500 PSI/ GRADE 60 | 24 | 24 | 16 | 24 | 24 | 18 |

| HORIZONTAL REINFORCEMENT - MINIMUM GRADE 40 STEEL | | | | | | |
|---|------|------|------|------|------|------|
| ONE BAR 12" FROM TOP OF WALL; MAX. SPACING 24" OC | 6-#4 | 7-#4 | 7-#4 | 6-#4 | 7-#4 | 7-#4 |

- FOOTNOTES:
- 1) WALL HEIGHT IS MEASURED FROM THE TOP OF THE WALL TO THE TOP OF THE FLOOR SLAB
 - 2) VERTICAL REINFORCEMENT FOR CONCRETE WALLS THAT ARE NOT FULL HEIGHT, AND FOR REINFORCEMENT SPACING 24" OC, REINFORCEMENT MAY BE PLACED IN THE MIDDLE OF THE WALL. OTHER WALLS SHALL HAVE VERTICAL REINFORCEMENT AS FOLLOWS:
 - A) 8" WALL - MINIMUM 5" FROM THE OUTSIDE FACE
 - B) 10" WALL - MINIMUM 6 3/4" FROM THE OUTSIDE FACE
 - C) EXTEND BARS TO WITHIN 8" OF THE TOP OF THE WALL
 - 3) REINFORCEMENT CLEARANCES:
 - A) CONCRETE EXPOSED TO EARTH - MINIMUM 1 1/2"
 - B) NOT EXPOSED TO WEATHER (INTERIOR SIDE OF WALLS) - 3/4"
 - C) CONCRETE EXPOSED TO WEATHER (TOP CLEARANCE IN GARAGE AND DRIVEWAY SLABS) - 1 1/2"
 - 4) HORIZONTAL REINFORCEMENT:
 - A) ONE BAR SHALL BE PLACED WITHIN 12" OF THE TOP OF THE WALL
 - B) OTHER BARS SHALL BE EQUALLY SPACED WITH SPACING NOT TO EXCEED 24" OC
 - C) HORIZONTAL BARS SHOULD BE AS CLOSE TO THE TENSION FACE AS POSSIBLE (INTERIOR) AND BEHIND THE VERTICAL REINFORCEMENT (I.E. 2" TOWARD THE INSIDE)
 - D) SUPPLEMENTAL REINFORCEMENT AT CORNERS - PLACE (1) #4 BAR 48" LONG AT 45 DEGREE ANGLE AT CORNERS OF OPENINGS. PLACE REINFORCEMENT WITHIN 6" OF THE EDGE OF INSIDE CORNERS.
 - 5) REINFORCEMENT SHALL BE LAPPED A MINIMUM 24" AT ENDS, SPLICES, AND AROUND CORNERS.
 - 6) AT MASONRY LEDGES THE MINIMUM WALL THICKNESS SHALL BE 3 1/2". LEDGES SHALL NOT EXCEED A DEPTH OF MORE THAN 24" BELOW THE TOP OF THE WALL. FOR WALL THICKNESSES LESS THAN 4" PROVIDE #4 BARS AT MAX. 24" OC TO WITHIN 8" OF THE TOP OF THE WALL.
 - 7) STRAIGHT WALLS MORE THAN 5' TALL AND MORE THAN 16 FEET LONG SHALL BE PROVIDED WITH EXTERIOR BRACED RETURN WALLS. WALL LENGTH SHALL BE MEASURED USING INSIDE THE SHORTEST DIMENSION BETWEEN INTERSECTING WALLS
 - 8) WALL SHALL NOT BE BACKFILLED UNTIL FLOOR SYSTEM AND DIAPHRAGM ARE IN PLACE

4 FOUNDATION WALL REINFORCEMENT TABLE
S2.0 NO SCALE



8 CONCRETE GRADE BEAM
S2.0 SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)

VISTA ENGINEERING, LLC
14718 NW DELIA STREET * PORTLAND, OREGON 97229
OFFICE: 971.255.6099 * MOBILE: 971.255.6099 *
DENNIS@VISTAENGINEERING.COM * VISTAENGINEERING.COM

CLIENT: BELLAH HOMES, LLC
JOB TITLE: NLY116 WILLIAMS LOT 116, NEW LONGVIEW
LOCATION: 3234 SW PERGOLA PARK DR. LEE'S SUMMIT, MISSOURI


STATE OF MISSOURI
DENNIS HEIER
NUMBER: PE-2018001772
PROFESSIONAL ENGINEER
10-11-2021

| NO. | DATE | REVISION | BY |
|-----|------|----------|----|
| | | | |
| | | | |
| | | | |

DRAWING TITLE
FOUNDATION DETAILS

ENGINEER: DMH CHECKED BY: DMH
JOB NO: 3885 DRAWN BY: DMH
DATE: 10-11-21
SHEET NUMBER
S2.0

REUSE FOR CONSTRUCTION NOTED FOR REVIEW ONLY
LEE'S SUMMIT, MISSOURI
11/15/2021




1 METHOD PFH (PORTAL FRAME WITH S3.0 HOLD-DOWNS) - PER FIGURE IRC R602.10.6.2

SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)

| | MINIMUM PANEL LENGTH FOR DETAIL 1/S3.0 (INCHES) | | | | |
|-------------------------------|---|--------|---------|---------|---------|
| | WALL HEIGHT | | | | |
| | 8 FEET | 9 FEET | 10 FEET | 11 FEET | 12 FEET |
| SUPPORTING ROOF ONLY | 16 | 16 | 16 | 18 | 20 |
| SUPPORTING ONE STORY AND ROOF | 24 | 24 | 24 | 27 | 29 |

| TENSION STRAP REQUIRED FOR HEADER TO JACK STUD FOR DETAILS 1/S3.0 AND 2/S3.0 (FROM TABLE R602.10.6.4) | | | | | |
|---|--------------------------|------------------------|-----------------------|---|--|
| MAX GARAGE OPENING (FT.) | PONY WALL WALL HT. (FT.) | REQUIRED SIMPSON STRAP | MIN. STRAP END LENGTH | NAILS REQUIRED IN EACH STRAP END LENGTH | |
| 18'-0" | 0'-0" | CS20 | 0'-9" | (7) 8d | |
| 9'-0" | 1'-0" | CS20 | 0'-9" | (7) 8d | |
| 18'-0" | 1'-0" | CS14 | 1'-4" | (15) 8d | |
| 9'-0" | 2'-0" | CS18 | 0'-11" | (9) 8d | |
| 18'-0" | 2'-0" | CMSTC16 | 1'-8" | (25) 16d SINKER | |
| 9'-0" | 4'-0" | CMSTC16 | 1'-8" | (25) 16d SINKER | |
| 16'-0" | 4'-0" | CMST14 | 2'-6" | (33) 10d | |




2 METHOD PFG (PORTAL FRAME AT GARAGE S3.0 DOOR) - PER FIGURE IRC R602.10.6.3

SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)


| MINIMUM PANEL LENGTH FOR DETAIL 2/S3.0 (INCHES) | | | | |
|---|--------|---------|-----------------|-----------------|
| WALL HEIGHT | | | | |
| 8 FEET | 9 FEET | 10 FEET | 11 FEET | 12 FEET |
| 24 | 27 | 30 | 33 ^a | 36 ^a |

a. Maximum opening height for PFG is 10 feet in accordance with Figure R602.10.6.3, but wall height may be increased to 12 feet with pony wall




3 EXTERIOR WALL SHEATHING S3.0 PANEL ATTACHMENT

SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)




4 SHEATHING EDGE AT TOP AND BOTTOM PLATES S3.0

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)




5 SHEATHING EDGE AT HORIZONTAL S3.0 FRAMING MEMBER

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)




6 SHEATHING EDGE AT PANEL S3.0 SPLICE ACROSS STUDS

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)



7 RAFTER BEARING OPTION DETAIL S3.0


SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)



8 FASTENING INSTRUCTIONS FOR S3.0 SHIPLAP PANEL SHEATHING

SCALE: 4" = 1'-0" (18x24) OR 6" = 1'-0" (24x36)

*NOTE: NAILING INTO TOP AND BOTTOM LAP IS IN ADDITION TO NAILING REQUIRED INTO BOTTOM LAP. FOR EXAMPLE, IF PLAN CALLS FOR NAILS @ 6" O.C. AT EDGES, BOTTOM LAP SHALL BE FASTENED AT 6" O.C. AND, IN ADDITION, NAILING SHALL ALSO BE INSTALLED THROUGH TOP AND BOTTOM LAP @ 6" O.C. STAGGERED 3" FROM BOTTOM LAP NAILING



9 GARAGE HOLD-DOWN S3.0 STRAP INSTALLATION

SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)

VISTA ENGINEERING, LLC
 1478 NW DELIA STREET * PORTLAND, OREGON 97229
 OFFICE: 971.255.6099 * MOBILE: 971.255.6099 *
 DENNIS@VISTAENGINEERING.COM * VISTAENGINEERING.COM

CLIENT: BELLAH HOMES, LLC
 JOB TITLE: NLY116 WILLIAMS
 LOT 116, NEW LONGVIEW
 LOCATION: 3234 SW PERGOLA PARK DR.
 LEE'S SUMMIT, MISSOURI


STATE OF MISSOURI
 DENNIS HEIER
 NUMBER: PE-201001772
 PROFESSIONAL ENGINEER
 10-11-2021

| NO. | DATE | REVISION | BY |
|-----|------|----------|----|
| | | | |
| | | | |
| | | | |

DRAWING TITLE
FRAMING DETAILS


ENGINEER: DMH CHECKED BY: DMH
 JOB NO.: 3885 DRAWN BY: DMH
 DATE: 10-11-21
 SHEET NUMBER
S3.0

RELEASE FOR CONSTRUCTION
 NOTED FOR REVIEW
 11/15/2021




1 EXTERIOR WALL SHEATHING PANEL ATTACHMENT
S3.1 PANEL SPLICE OVER HORIZONTAL FRAMING MEMBER

SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)




2 EXTERIOR WALL SHEATHING PANEL ATTACHMENT
S3.1 PANEL SPLICE OCCURRING ACROSS STUDS

SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)





4 FLOOR JOIST TO FLUSH STEEL BEAM DETAIL
S3.1 SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)



5 CEILING JOIST TO FLUSH STEEL BEAM DETAIL
S3.1 SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)

3 EXTERIOR WALL SECTION
S3.1 SCALE: 3/4" = 1'-0"



VISTA
STRUCTURAL
ENGINEERING, LLC

14718 NW DELIA STREET * PORTLAND, OREGON 97129
OFFICE: 971.255.6099 * MOBILE: 971.255.6099 *
* DENNIS@VISTASTRUCTURAL.COM * VISTASTRUCTURAL.COM

CLIENT: BELLAH HOMES, LLC
JOB TITLE: NLY16 WILLIAMS
LOT 116, NEW LONGVIEW
LOCATION: 3234 SW PERGOLA PARK DR.
LEE'S SUMMIT, MISSOURI

STATE OF MISSOURI
DENNIS HEIER
NUMBER: PE-201801772
PROFESSIONAL ENGINEER
10-11-2021


| NO. | DATE | REVISION | BY |
|-----|------|----------|----|
| | | | |
| | | | |
| | | | |
| | | | |

DRAWING TITLE
FRAMING DETAILS


ENGINEER: DMH CHECKED BY: DMH
JOB NO.: 3885 DRAWN BY: DMH
DATE: 10-11-21
SHEET NUMBER

S3.1


RELEASE FOR CONSTRUCTION
NOTED FOR REVIEW
11/15/2021




1 RIDGE FRAMING DETAIL
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)




2 TRUSS CONNECTION TO EXT. WALL BEARING
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)




3 VAULTED RAFTER INSULATION DETAILS
S3.2 SCALE: 3/4" = 1'-0"




4 STAIR AND HANDRAIL/GUARDRAIL DETAIL
S3.2 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)




5 RAFTER TIES AT CEILING JOISTS PERP. TO RAFTERS
S3.2 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)




7 RAFTER BEARING OPTION DETAIL
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)



9 COPED I-JOIST REINFORCEMENT
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)



6 FIELD-CONSTRUCTED A-FRAME DETAIL
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)



8 MAXIMUM ALLOWABLE LENGTH OF WOOD WALL STUDS (IRC TABLE 602.3.1)
S3.2

10 HEADER/BEAM CONNECTION OPTIONS AT OUTDOOR/OPEN SPACE
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)

| HEIGHT (FT.) | SPACING (INCHES O.C.) | | | |
|----------------------------------|-----------------------|-----|-----|-----|
| | 24 | 16 | 12 | 8 |
| SUPPORTING A ROOF ONLY | | | | |
| 10 OR LESS | 2x4 | 2x4 | 2x4 | 2x4 |
| 12 | 2x6 | 2x4 | 2x4 | 2x4 |
| 14 | 2x6 | 2x6 | 2x6 | 2x4 |
| 16 | 2x6 | 2x6 | 2x6 | 2x4 |
| 18 | DR | 2x6 | 2x6 | 2x6 |
| 20 | DR | DR | 2x6 | 2x6 |
| SUPPORTING ONE FLOOR AND A ROOF | | | | |
| 10 OR LESS | 2x6 | 2x4 | 2x4 | 2x4 |
| 12 | 2x6 | 2x6 | 2x6 | 2x4 |
| 14 | 2x6 | 2x6 | 2x6 | 2x6 |
| 16 | DR | 2x6 | 2x6 | 2x6 |
| 18 | DR | 2x6 | 2x6 | 2x6 |
| 20 | DR | DR | 2x6 | 2x6 |
| SUPPORTING TWO FLOORS AND A ROOF | | | | |
| 10 OR LESS | 2x6 | 2x6 | 2x4 | 2x4 |
| 12 | 2x6 | 2x6 | 2x6 | 2x6 |
| 14 | 2x6 | 2x6 | 2x6 | 2x6 |
| 16 | DR | 2x6 | 2x6 | 2x6 |
| 18 | DR | DR | 2x6 | 2x6 |
| 20 | DR | DR | DR | 2x6 |

NOTES:
1) DR = DESIGN REQUIRED
2) UTILITY, STANDARD, STUD AND #3 GRADE LUMBER OF ANY SPECIES ARE NOT PERMITTED
3) THIS TABLE DOES NOT APPLY FOR STUDS SUPPORTING MEMBERS WITH A TRIB. LENGTH GREATER THAN 6'-0"



CLIENT: BELLAH HOMES, LLC
JOB TITLE: NLY116 WILLIAMS LOT 116, NEW LONGVIEW
LOCATION: 3234 SW PERGOLA PARK DR. LEE'S SUMMIT, MISSOURI






| NO. | DATE | REVISION | BY |
|-----|------|----------|----|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

DRAWING TITLE
FRAMING DETAILS

ENGINEER: DMH CHECKED BY: DMH
JOB NO.: 3885 DRAWN BY: DMH
DATE: 10-11-21
SHEET NUMBER
S3.2

RELEASE FOR CONSTRUCTION
REVISED FOR PERMITS
11/15/2021






1 WELDED T-BEAM CONNECTION FOR W8x AND W10x BEAMS
S3.4 SCALE: 2" = 1'-0" (18x24) OR 3" = 1'-0" (24x36)

1 BOLTED T-BEAM CONNECTION FOR W8x AND W10x BEAMS
S3.4 SCALE: 2" = 1'-0" (18x24) OR 3" = 1'-0" (24x36)

3 BEAM SPLICE CONNECTION FOR W8x AND W10x BEAMS
S3.4 SCALE: 2" = 1'-0" (18x24) OR 3" = 1'-0" (24x36)

(OPTION #1)

(OPTION #2)




4 RAFTER FLITCH PLATE DETAIL
S3.4 SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)

2 WELDED T-BEAM CONNECTION FOR W12x, W14x, W16x & W18x BEAMS
S3.4 SCALE: 2" = 1'-0" (18x24) OR 3" = 1'-0" (24x36)


2 BOLTED T-BEAM CONNECTION FOR W12x, W14x, W16x & W18x BEAMS
S3.4 SCALE: 2" = 1'-0" (18x24) OR 3" = 1'-0" (24x36)

(OPTION #1)


(OPTION #2)



5 SPLICED WALL CONNECTION
S3.4 SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)



6 3RD CAR STALL BRACING
S3.4 SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)



7 EXTERIOR STEEL COLUMN CONNECTIONS
S3.4 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)

VISTA
 ENGINEERING, LLC
 14718 NW DELIA STREET * PORTLAND, OREGON 97129
 OFFICE: 971.255.6099 * MOBILE: 971.255.6099 *
 DENNIS@VISTASTRUCTURAL.COM * VISTASTRUCTURAL.COM

CLIENT: BELLAH HOMES, LLC
 JOB TITLE: NLY116 WILLIAMS
 LOT 116, NEW LONGVIEW
 LOCATION: 3234 SW PERGOLA PARK DR.
 LEE'S SUMMIT, MISSOURI

STATE OF MISSOURI
 DENNIS HEIER
 NUMBER: PE-201001772
 PROFESSIONAL ENGINEER
 10-11-2021

| NO. | DATE | REVISION | BY |
|-----|------|----------|----|
| | | | |
| | | | |
| | | | |
| | | | |

DRAWING TITLE
FRAMING DETAILS

ENGINEER: DMH CHECKED BY: DMH
 JOB NO. 3885 DRAWN BY: DMH
 DATE: 10-11-21
 SHEET NUMBER
S3.4

PLEASE FOR CONSTRUCTION
 NOTED FOR REVIEW
 11/15/2021