

Electrical Scope of Work

1. Demo existing electrical and low voltage in walls to be removed.
2. Supply and install three can lights to match existing.
3. Relocate two existing can lights to complete uniform layout.
4. Relocate two existing 8' pendants.
5. Relocate existing exit sign.
6. Two new 120 volt receptacles in south wall.
7. Two three-way switches to control pendant lights. (One by front entry and one by back entry)
8. Relocate existing dimmer for can lights to entry door by lobby.
9. Relocate existing light switches by lobby door entry to other side of new wall.