



RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW Development Services LEE'S SUMMIT, MISSOURI

RE: MN112 Lot 112 MN

MiTek USA, Inc. 16023 Swingley Ridge Rd Chesterfield, MO 63017 314-434-1200

Site Information:

Customer: Project Name: MN112 Lot/Block: Address: City:

Model: Subdivision: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2018/TPI2014 Design Program: MiTek 20/20 8.4 Wind Code: ASCE 7 - 16[Low Rise] Wind Speed: 115 mph Roof Load: 45.0 psf Floor Load: N/A psf

This package includes 40 individual, dated Truss Design Drawings and 0 Additional Drawings.

Table with 8 columns: No., Seal#, Truss Name, Date, No., Seal#, Truss Name, Date. Lists 40 truss designs from A1 to V15, all dated 11/15/2021.

The truss drawing(s) referenced above have been prepared by MiTek USA, Inc under my direct supervision based on the parameters provided by Wheeler - Waverly. Truss Design Engineer's Name: Garcia, Juan My license renewal date for the state of Kansas is April 30, 2022. Kansas COA: E-943

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



November 15, 2021



RE: MN112
Lot 112 MN

MiTek USA, Inc.
16023 Swingley Ridge Rd
Chesterfield, MO 63017
314-434-1200

Site Information:

Customer: Project Name: MN112
Lot/Block:
Address:
City:

Model:
Subdivision:
State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):


Design Code: IRC2018/TPI2014
Wind Code: ASCE 7 - 16[Low Rise]
Roof Load: 45.0 psf
Design Program: MiTek 20/20 8.4
Wind Speed: 115 mph
Floor Load: N/A psf

This package includes 40 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I48794651	A1	11/15/2021	21	I48794671	D1	11/15/2021
2	I48794652	A2	11/15/2021	22	I48794672	D2	11/15/2021
3	I48794653	A3	11/15/2021	23	I48794673	D3	11/15/2021
4	I48794654	A4	11/15/2021	24	I48794674	P1	11/15/2021
5	I48794655	A5	11/15/2021	25	I48794675	P2	11/15/2021
6	I48794656	B1	11/15/2021	26	I48794676	V1	11/15/2021
7	I48794657	B2	11/15/2021	27	I48794677	V2	11/15/2021
8	I48794658	B3	11/15/2021	28	I48794678	V3	11/15/2021
9	I48794659	B4	11/15/2021	29	I48794679	V4	11/15/2021
10	I48794660	B5	11/15/2021	30	I48794680	V5	11/15/2021
11	I48794661	B6	11/15/2021	31	I48794681	V6	11/15/2021
12	I48794662	C1	11/15/2021	32	I48794682	V7	11/15/2021
13	I48794663	C2	11/15/2021	33	I48794683	V8	11/15/2021
14	I48794664	C3	11/15/2021	34	I48794684	V9	11/15/2021
15	I48794665	C4	11/15/2021	35	I48794685	V10	11/15/2021
16	I48794666	C5	11/15/2021	36	I48794686	V11	11/15/2021
17	I48794667	C6	11/15/2021	37	I48794687	V12	11/15/2021
18	I48794668	C7	11/15/2021	38	I48794688	V13	11/15/2021
19	I48794669	C8	11/15/2021	39	I48794689	V14	11/15/2021
20	I48794670	C9	11/15/2021	40	I48794690	V15	11/15/2021

The truss drawing(s) referenced above have been prepared by MiTek USA, Inc under my direct supervision based on the parameters provided by Wheeler - Waverly. Truss Design Engineer's Name: Garcia, Juan My license renewal date for the state of Missouri is December 31, 2022. Missouri COA: 001193

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.





Job MN112	Truss A1	Truss Type Common Supported Gable	Qty 2	Ply 1	Lot 112 MN Job Reference (optional)	148794651
--------------	-------------	--------------------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:28
 ID: Hr0UoluygMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBgKwRcDoi7J4zJC7f

Page: 1



Scale = 1:69.3

Plate Offsets (X, Y): [9:0-3-8,0-3-0], [28:0-2-8,0-1-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.29	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.15	Horz(CT)	-0.01	20	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-R							Weight: 208 lb	FT = 10%

- LUMBER**
- TOP CHORD 2x4 SPF No.2
 - BOT CHORD 2x4 SPF No.2
 - WEBS 2x4 SPF No.2
 - OTHERS 2x4 SPF No.2

- BRACING**
- TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 - BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

- WEBS**
- 1 Row at midpt 19-20, 15-24, 14-25, 13-26, 12-27, 16-23, 17-22, 18-21

- REACTIONS (lb/size)**
- 20=41/33-2-8, 21=158/33-2-8, 22=185/33-2-8, 23=186/33-2-8, 24=168/33-2-8, 25=187/33-2-8, 26=179/33-2-8, 27=180/33-2-8, 29=180/33-2-8, 30=178/33-2-8, 31=180/33-2-8, 32=182/33-2-8, 33=179/33-2-8, 34=180/33-2-8, 35=178/33-2-8, 36=186/33-2-8, 37=151/33-2-8, 38=154/33-2-8
 - Max Horiz 38=353 (LC 5)
 - Max Uplift 20=31 (LC 4), 21=29 (LC 4), 22=57 (LC 9), 23=47 (LC 9), 24=9 (LC 20), 25=45 (LC 8), 26=50 (LC 8), 27=47 (LC 8), 29=48 (LC 8), 30=47 (LC 8), 31=47 (LC 8), 32=49 (LC 8), 33=48 (LC 8), 34=47 (LC 8), 35=53 (LC 8), 36=27 (LC 8), 37=148 (LC 8)

- Max Grav**
- 20=52 (LC 16), 21=158 (LC 1), 22=185 (LC 22), 23=188 (LC 22), 24=168 (LC 15), 25=189 (LC 21), 26=179 (LC 21), 27=180 (LC 1), 29=180 (LC 21), 30=178 (LC 1), 31=180 (LC 1), 32=182 (LC 21), 33=179 (LC 21), 34=180 (LC 1), 35=178 (LC 21), 36=186 (LC 1), 37=151 (LC 21), 38=223 (LC 16)

- FORCES (lb) - Maximum Compression/Maximum Tension**
- TOP CHORD** 2-38=-184/0, 1-2=0/27, 2-3=-318/41, 3-4=-262/37, 4-5=-238/35, 5-6=-212/32, 6-7=-191/29, 7-8=-177/28, 8-10=-163/42, 10-11=-135/68, 11-12=-122/94, 12-13=-108/121, 13-14=-94/148, 14-15=-85/173, 15-16=-84/174, 16-17=-96/152, 17-18=-112/125, 18-19=-152/125, 19-20=-122/103
 - BOT CHORD** 37-38=-116/88, 36-37=-116/88, 35-36=-116/88, 34-35=-116/88, 33-34=-116/88, 32-33=-116/88, 31-32=-116/88, 30-31=-116/87, 29-30=-116/87, 27-29=-116/87, 26-27=-116/87, 25-26=-116/87, 24-25=-116/87, 23-24=-116/87, 22-23=-116/87, 21-22=-116/87, 20-21=-116/87
 - WEBS** 15-24=-128/46, 14-25=-149/69, 13-26=-139/74, 12-27=-140/71, 11-29=-140/72, 10-30=-138/71, 9-31=-140/71, 8-32=-142/73, 7-33=-139/72, 6-34=-140/71, 5-35=-139/74, 4-36=-145/61, 3-37=-116/126, 16-23=-148/73, 17-22=-144/73, 18-21=-122/101

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 2x4 MT20 unless otherwise indicated.
- 5) Gable requires continuous bottom chord bearing.
- 6) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 7) Gable studs spaced at 2-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.



November 15, 2021

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss A1	Truss Type Common Supported Gable	Qty 2	Ply 1	Lot 112 MN Job Reference (optional)	I48794651
--------------	-------------	--------------------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:28
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 2

- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 20, 9 lb uplift at joint 24, 45 lb uplift at joint 25, 50 lb uplift at joint 26, 47 lb uplift at joint 27, 48 lb uplift at joint 29, 47 lb uplift at joint 30, 47 lb uplift at joint 31, 49 lb uplift at joint 32, 48 lb uplift at joint 33, 47 lb uplift at joint 34, 53 lb uplift at joint 35, 27 lb uplift at joint 36, 148 lb uplift at joint 37, 47 lb uplift at joint 23, 57 lb uplift at joint 22 and 29 lb uplift at joint 21.
- 11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss A2	Truss Type Roof Special	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794652
--------------	-------------	----------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:30
ID: Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1




Job MN112	Truss A3	Truss Type Roof Special	Qty 2	Ply 1	Lot 112 MN Job Reference (optional)	148794653
--------------	-------------	----------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:31
ID: Hr0UloiygMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRcDoi7J4zJC?f

Page: 1



Scale = 1:74.4
Plate Offsets (X, Y): [3:0-0-11,Edge], [5:0-4-0,Edge], [9:0-3-0,0-1-12], [10:Edge,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.86	Vert(LL)	-0.31	21-22	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.81	Vert(CT)	-0.56	21-22	>712	240		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.32	10	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.24	21-22	>999	240	Weight: 204 lb	FT = 10%

LUMBER
TOP CHORD 2x6 SPF No.2 *Except* 8-9:2x4 SPF No.2, 1-5:2x8 SP DSS
BOT CHORD 2x4 SPF No.2 *Except* 3-18:2x6 SPF 1650F 1.4E, 21-20:2x3 SPF No.2
WEBS 2x3 SPF No.2 *Except* 23-3,19-6,18-4,16-7,10-9:2x4 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 8-3-0 oc bracing.
WEBS 1 Row at midpt 4-18, 7-16, 9-10
JOINTS 1 Brace at Jt(s): 13


REACTIONS (lb/size) 2=1554/0-3-8, 10=1480/
Mechanical
Max Horiz 2=388 (LC 8)
Max Uplift 2=230 (LC 8), 10=218 (LC 8)
Max Grav 2=1628 (LC 2), 10=1735 (LC 2)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/12, 2-3=-777/0, 3-4=-4381/700, 4-6=-2638/374, 6-7=-2041/335, 7-8=-1101/190, 8-9=-1100/211, 10-12=-1607/243, 9-12=-1494/254
BOT CHORD 2-23=0/0, 3-22=-1008/4216, 21-22=-1006/4216, 18-21=-998/4192, 20-21=0/41, 19-20=-8/25, 17-18=-510/2324, 16-17=-385/1850, 15-16=-8/33, 13-15=-8/33, 12-13=-8/33, 11-14=0/0, 10-11=0/0
WEBS 3-23=0/67, 18-19=0/36, 6-18=-42/608, 14-15=0/111, 4-22=0/278, 4-18=-1932/511, 6-17=-863/228, 7-17=-136/995, 7-16=-1318/341, 8-16=-6/460, 11-13=0/61, 9-16=-204/1288

NOTES
1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
- All plates are 2x4 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 230 lb uplift at joint 2 and 218 lb uplift at joint 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard




November 15, 2021

Job MN112	Truss A4	Truss Type Roof Special	Qty 2	Ply 1	Lot 112 MN Job Reference (optional)	148794654
--------------	-------------	----------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:31
ID: Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:80

Plate Offsets (X, Y): [3:0-6-4,Edge], [3:0-1-14,0-1-11], [6:0-4-0,Edge], [9:0-2-5,Edge], [10:Edge,0-1-8], [12:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.86	Vert(LL)	-0.30	14-15	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.73	Vert(CT)	-0.53	14-15	>744	240		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.65	Horz(CT)	0.27	10	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.17	14-15	>999	240	Weight: 195 lb	FT = 10%

LUMBER
TOP CHORD 2x6 SPF No.2 *Except* 8-9:2x4 SPF No.2, 1-6:2x8 SP DSS
BOT CHORD 2x4 SPF No.2 *Except* 3-14:2x4 SPF 2100F 1.8E, 5-13:2x3 SPF No.2
WEBS 2x3 SPF No.2 *Except* 16-3:2x6 SPF No.2, 11-7,11-8,10-9,11-9:2x4 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-14, 7-11, 9-10

REACTIONS (lb/size) 2=1554/0-3-8, 10=1480/
Mechanical
Max Horiz 2=265 (LC 8)
Max Uplift 2=-38 (LC 8), 10=-42 (LC 8)
Max Grav 2=1606 (LC 2), 10=1608 (LC 2)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/12, 2-3=-758/0, 3-4=-4038/147, 4-5=-2796/94, 5-7=-2735/165, 7-8=-978/67, 8-9=-975/78, 9-10=-1463/77
BOT CHORD 2-16=0/0, 3-15=-355/3895, 14-15=-353/3891, 13-14=0/96, 5-14=-339/112, 12-13=-15/99, 11-12=-116/1597, 10-11=-3/19
WEBS 3-16=0/65, 4-15=-3/173, 4-14=-1479/156, 12-14=-103/1522, 7-14=-147/1458, 7-12=-82/162, 7-11=-1201/131, 8-11=0/375, 9-11=-47/1231

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60

- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 38 lb uplift at joint 2 and 42 lb uplift at joint 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss B1	Truss Type Roof Special	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794656
--------------	-------------	----------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:32
ID: Hr0UoloygMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCdoi7J4zJC7f

Page: 1



Scale = 1:76.2

Plate Offsets (X, Y): [4:0-1-8,0-2-12], [9:Edge,0-2-8], [12:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.94	Vert(LL)	-0.18	12-13	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.61	Vert(CT)	-0.36	12-13	>779	240		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.47	Horz(CT)	-0.02	9	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	-0.04	9-10	>999	240	Weight: 136 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except* 14-4:2x3 SPF No.2
WEBS 2x3 SPF No.2 *Except* 16-2:2x6 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 6-10, 7-10, 8-9

REACTIONS (lb/size)
9=1036/ Mechanical,
13=1267/9-11-8, 14=84/9-11-8,
15=355/9-11-8, 16=294/9-11-8
Max Horiz 16=336 (LC 5)
Max Uplift 9=-109 (LC 8), 13=-274 (LC 8),
14=-52 (LC 5), 16=-52 (LC 4)
Max Grav 9=1134 (LC 2), 13=1294 (LC 2),
14=120 (LC 2), 15=422 (LC 16),
16=294 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/30, 2-3=-209/23, 3-4=-250/77,
4-6=-1090/154, 6-7=-714/169, 7-8=-688/186,
2-16=-264/76, 8-9=-986/154
BOT CHORD 15-16=-227/99, 14-15=-227/99, 13-14=0/0,
4-13=-1182/325, 12-13=-63/115,
10-12=-120/912, 9-10=-98/75
WEBS 3-14=-105/198, 4-12=-61/871,
6-12=-119/163, 6-10=-517/183,
7-10=-59/194, 8-10=-69/787, 3-15=-240/56

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60

- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 52 lb uplift at joint 16, 274 lb uplift at joint 13, 52 lb uplift at joint 14 and 109 lb uplift at joint 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss B4	Truss Type Roof Special	Qty 2	Ply 1	Lot 112 MN Job Reference (optional)	I48794659
--------------	-------------	----------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66671,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:33
ID: Hr0UoloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:78.9

Plate Offsets (X, Y): [2:0-3-3,Edge], [8:0-3-0,0-1-12], [9:Edge,0-1-8], [18:0-2-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	-0.55	18-19	>725	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	1.00	Vert(CT)	-0.99	18-19	>402	240	MT18HS	197/144
BCLL	0.0*	Rep Stress Incr	YES	WB	0.94	Horz(CT)	0.41	9	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.39	18-19	>999	240	Weight: 159 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF 2100F 1.8E *Except* 5-7:2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except* 2-19:2x8 SP DSS, 19-16:2x4 SPF 2100F 1.8E
WEBS 2x3 SPF No.2 *Except* 19-3:2x8 SP DSS, 9-8,12-10,6-15,18-3:2x4 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-4-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
8-1-3 oc bracing: 2-19
1-4-12 oc bracing: 18-19.



WEBS 1 Row at midpt 8-9, 6-15, 3-18, 4-17
JOINTS 1 Brace at Jt(s): 12

REACTIONS (lb/size) 2=1567/0-3-8, 9=1493/0-3-8
Max Horiz 2=341 (LC 7)
Max Uplift 2=-253 (LC 8), 9=-196 (LC 8)
Max Grav 2=1627 (LC 2), 9=1743 (LC 2)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/9, 2-3=-7667/1393, 3-4=-3256/500, 4-6=-2094/353, 6-7=-1140/238, 7-8=-1143/257, 9-11=-1608/223, 8-11=-1489/244
BOT CHORD 2-19=-1489/7107, 18-19=-1295/5917, 17-18=-526/2958, 15-17=-254/1851, 14-15=-130/100, 12-14=-130/100, 11-12=-130/100, 10-13=0/0, 9-10=0/0
WEBS 13-14=0/116, 3-19=-367/2419, 7-15=-46/483, 8-15=-164/1283, 10-12=0/65, 6-15=-1279/330, 3-18=-2974/773, 4-18=0/595, 4-17=-1286/316, 6-17=-77/899

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) All plates are MT20 plates unless otherwise indicated.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 253 lb uplift at joint 2 and 196 lb uplift at joint 9.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSITPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss B6	Truss Type Roof Special	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794661
--------------	-------------	----------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:34
ID:Hr0UoloygMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCDoi7J4zJC7f

Page: 1



Scale = 1:84.5

Plate Offsets (X, Y): [2:0-3-15,0-1-6], [18:0-2-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	-0.46	18-19	>869	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.91	Vert(CT)	-0.91	18-19	>438	240	MT18HS	197/144
BCLL	0.0*	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.40	11	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.42	18-19	>938	240	Weight: 177 lb	FT = 10%

LUMBER

TOP CHORD 2x4 SPF No.2 *Except* 1-5:2x4 SPF 2100F 1.8E
 BOT CHORD 2x4 SPF No.2 *Except* 2-19:2x8 SP DSS, 19-17:2x4 SPF 2100F 1.8E, 15-7:2x3 SPF No.2
 WEBS 2x3 SPF No.2 *Except* 19-3:2x6 SPF No.2, 18-3,11-10:2x4 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 6-2-13 oc bracing. Except:
 1 Row at midpt 7-14
 WEBS 1 Row at midpt 3-18, 4-16, 6-14, 8-13, 10-11

REACTIONS (lb/size) 2=1567/0-3-8, 11=1493/0-3-8
 Max Horiz 2=380 (LC 8)
 Max Uplift 2=-234 (LC 8), 11=-214 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/9, 2-3=-7214/1520, 3-4=-3094/483, 4-6=-1969/320, 6-7=-1396/273, 7-8=-1326/337, 8-9=-1093/249, 9-10=-1115/214, 10-11=-1440/249
 BOT CHORD 2-19=-1770/6670, 18-19=-1568/5762, 16-18=-671/2794, 15-16=-1/35, 14-15=0/107, 7-14=-249/161, 13-14=-191/1077, 12-13=0/113, 9-13=-352/185, 11-12=0/16
 WEBS 3-19=-443/2120, 3-18=-2982/901, 4-18=0/526, 4-16=-1252/338, 6-16=0/320, 14-16=-399/1771, 6-14=-710/202, 8-14=-368/1317, 8-13=-560/123, 11-13=-11/5, 10-13=-218/1293

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BC DL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) All plates are MT20 plates unless otherwise indicated.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 6) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 234 lb uplift at joint 2 and 214 lb uplift at joint 11.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSITPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss C1	Truss Type GABLE	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794662
--------------	-------------	---------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:35
ID: Hr0UoluyigMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRcDoi7J4zJC?f

Page: 1



Scale = 1:47.7

Plate Offsets (X, Y): [10:0-2-0,Edge], [20:0-5-10,0-1-8], [35:0-5-10,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.07	Horz(CT)	0.00	20	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-R								
											Weight: 107 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size)
20=146/20-0-0, 21=84/20-0-0, 22=127/20-0-0, 23=119/20-0-0, 24=120/20-0-0, 25=120/20-0-0, 26=119/20-0-0, 27=123/20-0-0, 28=123/20-0-0, 29=119/20-0-0, 30=120/20-0-0, 31=120/20-0-0, 32=119/20-0-0, 33=127/20-0-0, 34=84/20-0-0, 35=146/20-0-0
Max Horiz 35=189 (LC 6)
Max Uplift 20=42 (LC 5), 21=-97 (LC 9), 22=-29 (LC 9), 23=-44 (LC 9), 24=-40 (LC 9), 25=-41 (LC 9), 26=-58 (LC 9), 29=-56 (LC 8), 30=-41 (LC 8), 31=-40 (LC 8), 32=-44 (LC 8), 33=-26 (LC 8), 34=-110 (LC 8), 35=-81 (LC 4)
Max Grav 20=152 (LC 15), 21=130 (LC 16), 22=127 (LC 22), 23=124 (LC 16), 24=123 (LC 16), 25=123 (LC 16), 26=126 (LC 16), 27=127 (LC 17), 28=136 (LC 18), 29=123 (LC 15), 30=123 (LC 15), 31=123 (LC 15), 32=125 (LC 15), 33=127 (LC 21), 34=150 (LC 15), 35=184 (LC 16)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD
2-35=-149/64, 1-2=0/36, 2-3=-134/122, 3-4=-95/94, 4-5=-89/89, 5-6=-78/94, 6-7=-67/114, 7-8=-57/135, 8-9=-47/164, 9-10=-36/131, 10-11=-32/128, 11-12=-30/148, 12-13=-24/116, 13-14=-32/95, 14-15=-40/74, 15-16=-48/53, 16-17=-56/60, 17-18=-98/76, 18-19=0/36, 18-20=-133/34
BOT CHORD
34-35=-81/97, 33-34=-81/97, 32-33=-81/97, 31-32=-81/97, 30-31=-81/97, 29-30=-81/97, 28-29=-81/97, 27-28=-81/97, 26-27=-81/97, 25-26=-81/97, 24-25=-81/97, 23-24=-81/97, 22-23=-81/97, 21-22=-81/97, 20-21=-81/97
WEBS
3-34=-100/89, 4-33=-99/51, 5-32=-96/58, 6-31=-96/57, 7-30=-96/57, 8-29=-96/72, 9-28=-110/5, 11-27=-101/0, 12-26=-99/74, 13-25=-96/57, 14-24=-96/57, 15-23=-96/58, 16-22=-99/52, 17-21=-89/82

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BC DL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) All plates are 2x4 MT20 unless otherwise indicated.
5) Gable requires continuous bottom chord bearing.
6) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
7) Gable studs spaced at 1'-4" oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-06" tall by 2'-00" wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 81 lb uplift at joint 35, 42 lb uplift at joint 20, 110 lb uplift at joint 34, 26 lb uplift at joint 33, 44 lb uplift at joint 32, 40 lb uplift at joint 31, 41 lb uplift at joint 30, 56 lb uplift at joint 29, 58 lb uplift at joint 26, 41 lb uplift at joint 25, 40 lb uplift at joint 24, 44 lb uplift at joint 23, 29 lb uplift at joint 22 and 97 lb uplift at joint 21.
11) This truss is designed in accordance with the 2018 International Residential Code sections R502.4.1 and R802.10.2 and referenced standard ANSI/TPI 1.
LOAD CASE(S) Standard




November 15, 2021

Job MN112	Truss C2	Truss Type Common	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	I48794663
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:35
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:48.4

Plate Offsets (X, Y): [8:0-3-11,0-8-1], [10:0-2-9,0-4-7]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.85	Vert(LL)	-0.17	8-9	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.74	Vert(CT)	-0.35	8-9	>667	240		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.24	Horz(CT)	0.03	8	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.06	9	>999	240	Weight: 70 lb	FT = 10%

LUMBER
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x3 SPF No.2 *Except* 10-2-8-6:2x8 SP DSS

6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING
 TOP CHORD Structural wood sheathing directly applied or 3-1-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 8=955/0-3-8, 10=955/0-3-8
 Max Horiz 10=192 (LC 6)
 Max Uplift 8=-130 (LC 9), 10=-130 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/42, 2-3=-1148/182, 3-4=-875/141, 4-5=-875/141, 5-6=-1148/183, 6-7=0/42, 2-10=-852/178, 6-8=-852/178
 BOT CHORD 9-10=-167/901, 8-9=-79/881
 WEBS 4-9=-6/460, 5-9=-255/206, 3-9=-254/206

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 130 lb uplift at joint 10 and 130 lb uplift at joint 8.



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss C3	Truss Type GABLE	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794664
--------------	-------------	---------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:35
ID:Hr0UoluygMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:42.3

Plate Offsets (X, Y): [8:0-1-0,0-4-0], [11:0-1-0,0-4-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.85	Vert(LL)	-0.21	9-10	>716	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.68	Vert(CT)	-0.48	9-10	>312	240		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.18	Horz(CT)	0.19	8	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.10	9-10	>999	240	Weight: 59 lb	FT = 10%

LUMBER

TOP CHORD	2x4 SPF No.2
BOT CHORD	2x4 SPF No.2 *Except* 10-9:2x4 SPF 2100F 1.8E
WEBS	2x3 SPF No.2 *Except* 11-2,8-6:2x6 SP DSS
OTHERS	2x4 SPF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-3-12 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(lb/size)	8=642/0-3-8, 11=642/0-3-8
	Max Horiz	11=138 (LC 6)
	Max Uplift	8=91 (LC 9), 11=91 (LC 8)

FORCES	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=0/39, 2-3=-1244/144, 3-4=-1083/252, 4-5=-1075/203, 5-6=-1244/83, 6-7=0/39, 2-11=-962/130, 6-8=-962/88
BOT CHORD	10-11=-135/1066, 9-10=-21/507, 8-9=-26/989
WEBS	4-9=-124/539, 5-9=0/226, 4-10=-160/608, 3-10=0/226

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 2x4 MT20 unless otherwise indicated.
- 5) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 6) Gable studs spaced at 1-4-0 oc.

- 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 9) Bearing at joint(s) 11, 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 91 lb uplift at joint 11 and 91 lb uplift at joint 8.
- 11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss C4	Truss Type Piggyback Base Structural Gable	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794665
--------------	-------------	---	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:36
ID:Hr0UoluygMORZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWkRCoD7J4zJC7f

Page: 1



Scale = 1:86.2

[6:0-3-8,0-3-0], [7:0-8-4,0-1-12], [7:0-3-0,0-2-7], [8:0-4-8,0-2-0], [8:0-1-1,0-2-0], [17:0-5-0,0-2-8], [17:0-1-6,0-1-8], [20:0-3-0,0-6-4], [21:0-1-12,0-0-4], [23:0-1-12,0-0-4],
Plate Offsets (X, Y): [24:0-1-8,0-1-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.76	Vert(LL)	-0.18	18-19	>835	360	MT18HS	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.54	Vert(CT)	-0.37	18-19	>409	240	MT20	197/144
BCLL	0.0*	Rep Stress Incr	YES	WB	0.77	Horz(CT)	0.03	17	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.03	13-14	>999	240	Weight: 321 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2 *Except*
19-3,18-5,17-5,18-4,19-4,19-2,14-9,13-10,14-10,13-11:2x3 SPF No.2
OTHERS
2x4 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-7-6 oc purlins, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 7-8.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 8-16, 7-16, 7-17

REACTIONS (lb/size)
12=628/ Mechanical,
16=1567/0-3-8, 17=1109/0-3-8,
20=317/0-3-8
Max Horiz 20=287 (LC 5)
Max Uplift 12=138 (LC 9), 16=144 (LC 9),
17=327 (LC 8), 20=49 (LC 9)
Max Grav 12=733 (LC 16), 16=1662 (LC 2),
17=1393 (LC 15), 20=352 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/36, 2-3=661/65, 3-4=706/180,
4-5=131/690, 5-7=79/860, 7-8=0/660,
8-9=501/358, 9-10=515/187,
10-11=938/202, 12-20=374/73,
11-12=671/155
BOT CHORD 19-20=302/321, 18-19=239/132,
17-18=504/196, 16-17=462/197,
14-16=227/159, 13-14=136/747,
12-13=23/81

WEBS
3-19=-211/152, 5-18=-18/263,
5-17=-593/194, 4-18=-431/188,
4-19=-242/1015, 8-16=-1096/193,
7-16=-382/70, 2-19=-20/523, 7-17=-550/168,
9-14=-466/279, 8-14=-294/1080,
10-13=-10/167, 10-14=-549/182,
11-13=-114/676



- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Refer to girder(s) for truss to truss connections.
 - Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.

13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 49 lb uplift at joint 20, 327 lb uplift at joint 17, 138 lb uplift at joint 12 and 144 lb uplift at joint 16.

14) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard




November 15, 2021

Job MN112	Truss C5	Truss Type Piggyback Base	Qty 3	Ply 1	Lot 112 MN Job Reference (optional)	148794666
--------------	-------------	------------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:37
ID: Hr0UoloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:71

Plate Offsets (X, Y): [1:Edge,0-1-8], [5:0-8-4,0-1-12], [6:0-4-8,0-2-0], [9:Edge,0-1-8], [15:0-5-0,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.76	Vert(LL)	-0.18	16-17	>840	360	MT18HS	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.60	Vert(CT)	-0.37	16-17	>410	240	MT20	197/144
BCLL	0.0*	Rep Stress Incr	YES	WB	0.77	Horz(CT)	0.03	15	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.03	11-12	>999	240	Weight: 185 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2 *Except*
14-5,14-6,5-15,6-12:2x4 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-7-2 oc purlins, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 5-14, 6-14, 5-15


REACTIONS (lb/size)
10=624/ Mechanical,
14=1575/0-3-8, 15=1124/0-3-8,
18=235/0-3-8
Max Horiz 18=277 (LC 5)
Max Uplift 10=138 (LC 9), 14=146 (LC 9),
15=330 (LC 8), 18=45 (LC 9)
Max Grav 10=738 (LC 16), 14=1750 (LC 2),
15=1398 (LC 15), 18=285 (LC 16)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-667/67, 2-3=-722/185, 3-4=-135/716,
4-5=-79/886, 5-6=0/580, 6-7=-514/358,
7-8=-509/187, 8-9=-946/204, 1-18=-299/47,
9-10=-673/156
BOT CHORD 17-18=-299/325, 16-17=-254/132,
15-16=-522/196, 14-15=-479/198,
12-14=-235/160, 11-12=-136/754,
10-11=-22/78
WEBS 2-17=-227/157, 3-17=-250/1055,
3-16=-436/189, 4-16=-18/261,
4-15=-591/193, 5-14=-387/72,
6-14=-1109/194, 1-17=-26/522,
5-15=-565/171, 6-12=-294/1125,
7-12=-465/279, 8-12=-544/184, 8-11=-5/167,
9-11=-116/685

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 18 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 45 lb uplift at joint 18, 330 lb uplift at joint 15, 146 lb uplift at joint 14 and 138 lb uplift at joint 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss C6	Truss Type Piggyback Base	Qty 2	Ply 1	Lot 112 MN Job Reference (optional)	148794667
--------------	-------------	------------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:37
 ID: Hr0UoloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCDoi7J4zJC?f

Page: 1




Plate Offsets (X, Y): [1:Edge,0-2-8], [4:0-1-12,0-5-0], [6:0-3-0,0-1-12], [9:Edge,0-1-8], [10:Edge,0-2-8], [19:0-2-0,0-3-15]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.85	Vert(LL)	-0.27	12-13	>879	360	MT18HS	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.78	Vert(CT)	-0.42	12-13	>556	240	MT20	197/144
BCLL	0.0*	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.03	10	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.06	16-17	>999	240	Weight: 184 lb	FT = 10%

LUMBER
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except* 5-13:2x3 SPF No.2
 WEBS 2x3 SPF No.2 *Except* 13-6,12-6:2x4 SPF No.2

BRACING
 TOP CHORD Structural wood sheathing directly applied or 3-8-12 oc purlins, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 4-6.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
 3-7-9 oc bracing: 13-14
 6-0-0 oc bracing: 12-13.

1 Row at midpt 5-14
 WEBS 1 Row at midpt 4-14, 6-13, 3-15

REACTIONS (lb/size) 10=779/ Mechanical, 13=1977/0-3-8, 18=802/0-3-8
 Max Horiz 18=222 (LC 5)
 Max Uplift 10=76 (LC 9), 18=28 (LC 8)
 Max Grav 10=961 (LC 14), 13=2061 (LC 13), 18=880 (LC 13)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-2450/192, 2-3=-1279/95, 3-4=-432/164, 4-5=-79/211, 5-6=-81/209, 6-7=-933/284, 7-8=-898/167, 8-9=-1280/134, 1-18=-944/82, 9-10=-886/95
 BOT CHORD 17-18=-236/315, 16-17=-232/2156, 15-16=-84/1207, 14-15=-2/230, 13-14=-1165/86, 5-14=-264/71, 12-13=-14/181, 11-12=-82/1045, 10-11=-10/100

WEBS 2-17=-57/577, 3-16=0/454, 4-15=0/689, 4-14=-1049/42, 1-17=-141/1974, 7-12=-463/171, 8-11=-43/119, 9-11=-73/958, 8-12=-454/86, 6-13=-837/18, 6-12=-119/1140, 2-16=-961/150, 3-15=-1100/154

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BC DL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) All plates are MT20 plates unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Bearing at joint(s) 18 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 18 and 76 lb uplift at joint 10.
 - 10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss C7	Truss Type Piggyback Base	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794668
--------------	-------------	------------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:38
 ID: Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCDoi7J4zJC7f

Page: 1



Scale = 1:69.1

Plate Offsets (X, Y): [5:0-3-0,0-1-12], [7:0-3-0,0-1-12], [10:Edge,0-1-8], [11:Edge,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.27	13-14	>874	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.83	Vert(CT)	-0.43	13-14	>550	240	MT18HS	197/144
BCLL	0.0*	Rep Stress Incr	YES	WB	0.85	Horz(CT)	-0.08	14	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.05	18-19	>999	240	Weight: 187 lb	FT = 10%

LUMBER
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except* 18-3-6-14:2x3 SPF No.2
 WEBS 2x3 SPF No.2 *Except* 20-1:2x6 SPF No.2, 14-7,13-7:2x4 SPF No.2

WEBS
 2-17=0/66, 3-16=676/107, 2-19=-240/86, 17-19=-107/967, 4-16=-316/122, 5-16=-111/1078, 5-15=-960/46, 8-13=-464/172, 9-12=-42/125, 10-12=-84/908, 9-13=-462/84, 7-14=-870/7, 7-13=-119/1148

BRACING
 TOP CHORD Structural wood sheathing directly applied or 4-11-7 oc purlins, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 5-7.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
 2-10-9 oc bracing: 14-15
 6-0-0 oc bracing: 13-14.

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) All plates are MT20 plates unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 45 lb uplift at joint 20 and 85 lb uplift at joint 11.
 - 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

1 Row at midpt 6-15
 WEBS 1 Row at midpt 5-15, 7-14
REACTIONS (lb/size) 11=770/ Mechanical, 14=1989/0-3-8, 20=788/0-3-8
 Max Horiz 20=220 (LC 5)
 Max Uplift 11=85 (LC 9), 20=-45 (LC 8)
 Max Grav 11=923 (LC 14), 14=2148 (LC 13), 20=861 (LC 13)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-1080/81, 2-3=-1079/138, 3-4=-618/145, 4-5=-586/215, 5-6=-34/266, 6-7=-37/261, 7-8=-866/300, 8-9=-830/183, 9-10=-1221/147, 1-20=-708/69, 10-11=-848/104
 BOT CHORD 19-20=-112/989, 18-19=-9/59, 17-18=0/91, 3-17=-3/384, 16-17=-99/1039, 15-16=-43/158, 14-15=-1241/68, 6-15=-293/65, 13-14=-34/133, 12-13=-93/994, 11-12=-10/98

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSITPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss C8	Truss Type Piggyback Base	Qty 3	Ply 1	Lot 112 MN Job Reference (optional)	148794669
--------------	-------------	------------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:38
 ID: Hr0UoluygMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:69.1
 Plate Offsets (X, Y): [1:0-2-15,0-1-12], [4:0-4-8,0-2-0], [6:0-3-0,0-1-12], [9:Edge,0-1-8], [15:0-3-12,0-4-12]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	-0.20	14-15	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.90	Vert(CT)	-0.33	14-15	>733	240		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.87	Horz(CT)	-0.06	13	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.05	16-17	>999	240	Weight: 194 lb	FT = 10%

LUMBER
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except* 16-3:2x3 SPF No.2, 15-14:2x6 SPF No.2, 13-10:2x4 SPF 2100F 1.8E
 WEBS 2x3 SPF No.2 *Except* 18-1:2x6 SPF No.2, 13-6,12-6,15-4:2x4 SPF No.2


BRACING
 TOP CHORD Structural wood sheathing directly applied or 4-11-11 oc purlins, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 4-6.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing. Except:
 1 Row at midpt 5-14
 WEBS 1 Row at midpt 6-13, 4-14

REACTIONS (lb/size) 10=688/ Mechanical, 13=2147/0-3-8, 18=712/0-3-8
 Max Horiz 18=220 (LC 5)
 Max Uplift 10=91 (LC 9), 18=52 (LC 8)
 Max Grav 10=803 (LC 14), 13=2391 (LC 13), 18=763 (LC 13)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-949/89, 2-3=-788/144, 3-4=-911/275, 4-5=0/468, 5-6=0/462, 6-7=-651/311, 7-8=-639/194, 8-9=-1038/156, 1-18=-630/72, 9-10=-729/109
 BOT CHORD 17-18=-119/883, 16-17=-97/37, 15-16=0/97, 3-15=-501/176, 14-15=-150/67, 13-14=-1367/45, 5-14=-273/68, 12-13=-171/44, 11-12=-101/836, 10-11=-12/92
 WEBS 2-15=-142/30, 2-17=-135/85, 15-17=-88/934, 6-13=-993/2, 6-12=-120/1156, 7-12=-463/172, 8-12=-493/82, 8-11=-29/145, 9-11=-90/756, 4-15=-147/1320, 4-14=-1022/69

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 52 lb uplift at joint 18 and 91 lb uplift at joint 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard




November 15, 2021

Job MN112	Truss C9	Truss Type Piggyback Base Girder	Qty 1	Ply 4	Lot 112 MN Job Reference (optional)	148794670
--------------	-------------	-------------------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:39
 ID: Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBGKwCrDcoi7J4zJC7f

Page: 1



Scale = 1:72.2

Plate Offsets (X, Y): [5:0-3-0,0-1-12], [9:0-5-8,Edge], [10:0-4-0,0-4-8], [11:0-1-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.64	Vert(LL)	-0.12	9-10	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.76	Vert(CT)	-0.21	9-10	>999	240	M18AHS	142/136
BCLL	0.0*	Rep Stress Incr	NO	WB	0.60	Horz(CT)	0.03	7	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.07	7-8	>999	240		Weight: 567 lb FT = 10%

LUMBER
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x6 SP 2400F 2.0E *Except* 9-4:2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except* 11-1:2x8 SP DSS

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 6-7

REACTIONS (lb/size) 7=6728/0-3-8, 11=7303/0-3-8
 Max Horiz 11=314 (LC 20)
 Max Uplift 7=-967 (LC 5), 11=-765 (LC 8)
 Max Grav 7=7842 (LC 13), 11=8648 (LC 13)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-11359/883, 2-4=-6042/541, 4-5=-6070/637, 5-6=-122/85, 6-7=-129/50, 1-11=-6465/505
 BOT CHORD 10-11=-691/3856, 9-10=0/1119, 8-9=-12/2264, 4-8=-401/147, 7-8=-267/2226
 WEBS 2-10=-329/4603, 8-10=-948/8827, 2-8=-5191/458, 5-8=-865/8938, 5-7=-5947/557, 1-10=-254/6049

NOTES
 1) 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x8 - 2 rows staggered at 0-9-0 oc.
 Bottom chords connected as follows: 2x6 - 3 rows staggered at 0-4-0 oc, 2x4 - 1 row at 0-9-0 oc.
 Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
 Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.

- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BC DL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 967 lb uplift at joint 7 and 765 lb uplift at joint 11.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Use Simpson Strong-Tie HUS26 (14-10d Girder, 6-10d Truss) or equivalent spaced at 2-0-0 oc max. starting at 1-11-4 from the left end to 5-11-4 to connect truss(es) to back face of bottom chord.
- Use Simpson Strong-Tie HUS26 (14-10d Girder, 6-10d Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 7-11-4 from the left end to 11-11-4 to connect truss(es) to back face of bottom chord.
- Use Simpson Strong-Tie HUS26 (14-10d Girder, 4-10d Truss) or equivalent spaced at 2-2-8 oc max. starting at 13-11-4 from the left end to 20-1-12 to connect truss(es) to back face of bottom chord.

- Fill all nail holes where hanger is in contact with lumber.
- LOAD CASE(S)** Standard
- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
 Uniform Loads (lb/ft)
 Vert: 1-5=-70, 5-6=-70, 9-11=-20, 7-8=-20
 Concentrated Loads (lb)
 Vert: 7=-831 (B), 12=-1456 (B), 13=-1460 (B), 14=-1460 (B), 15=-1460 (B), 16=-1460 (B), 17=-1456 (B), 18=-1016 (B), 20=-823 (B), 21=-823 (B)



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSITPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job MN112	Truss D1	Truss Type Common Supported Gable	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794671
--------------	-------------	--------------------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:39
ID: Hr0UoloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:42

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	14	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-R							Weight: 79 lb	FT = 10%

LUMBER	
TOP CHORD	2x4 SPF No.2
BOT CHORD	2x4 SPF No.2
WEBS	2x4 SPF No.2
OTHERS	2x4 SPF No.2

WEBS	
7-20	=122/0, 6-21=-151/74, 5-22=-139/73,
4-23	=139/67, 3-24=-146/90, 8-19=-151/74,
9-17	=139/73, 10-16=-139/68, 11-15=-146/87

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 25, 33 lb uplift at joint 14, 50 lb uplift at joint 21, 49 lb uplift at joint 22, 41 lb uplift at joint 23, 72 lb uplift at joint 24, 50 lb uplift at joint 19, 49 lb uplift at joint 17, 42 lb uplift at joint 16 and 66 lb uplift at joint 15.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size)	
14=177/20-9-8, 15=192/20-9-8, 16=177/20-9-8, 17=179/20-9-8, 19=188/20-9-8, 20=162/20-9-8, 21=188/20-9-8, 22=179/20-9-8, 23=177/20-9-8, 24=192/20-9-8, 25=177/20-9-8	
Max Horiz	25=68 (LC 9)
Max Uplift	14=-33 (LC 5), 15=-66 (LC 9), 16=-42 (LC 9), 17=-49 (LC 9), 19=-50 (LC 9), 21=-50 (LC 8), 22=-49 (LC 8), 23=-41 (LC 8), 24=-72 (LC 8), 25=-33 (LC 4)
Max Grav	14=177 (LC 1), 15=192 (LC 22), 16=177 (LC 22), 17=179 (LC 1), 19=191 (LC 22), 20=162 (LC 1), 21=191 (LC 21), 22=179 (LC 1), 23=177 (LC 21), 24=192 (LC 21), 25=177 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension	
TOP CHORD	2-25=-157/47, 1-2=0/27, 2-3=-72/50, 3-4=-45/68, 4-5=-33/89, 5-6=-33/110, 6-7=-36/130, 7-8=-36/123, 8-9=-33/90, 9-10=-33/69, 10-11=-34/48, 11-12=-57/35, 12-13=0/27, 12-14=-157/47
BOT CHORD	24-25=-8/57, 23-24=-8/57, 22-23=-8/57, 21-22=-8/57, 20-21=-8/57, 19-20=-8/57, 17-19=-8/57, 16-17=-8/57, 15-16=-8/57, 14-15=-8/57



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss D2	Truss Type Common	Qty 4	Ply 1	Lot 112 MN Job Reference (optional)	148794672
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:40
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:43.9

Plate Offsets (X, Y): [8:0-2-13,0-6-6], [12:0-1-8,0-3-9]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.91	Vert(LL)	-0.17	9-11	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.64	Vert(CT)	-0.39	9-11	>621	240		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.16	Horz(CT)	0.04	8	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.10	9-11	>999	240	Weight: 68 lb	FT = 10%

LUMBER
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x3 SPF No.2 *Except* 12-2,8-6:2x8 SP DSS

6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING
 TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 8=991/0-3-8, 12=991/0-3-8
 Max Horiz 12=66 (LC 9)
 Max Uplift 8=143 (LC 9), 12=143 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=0/32, 2-3=-1541/197, 3-4=-1394/220, 4-5=-1394/220, 5-6=-1541/197, 6-7=0/32, 2-12=-907/170, 6-8=-907/170
 BOT CHORD 11-12=-185/1326, 9-11=-59/968, 8-9=-119/1326
 WEBS 4-9=-89/469, 5-9=-251/176, 4-11=-88/469, 3-11=-251/176

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 143 lb uplift at joint 12 and 143 lb uplift at joint 8.



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601





Job MN112	Truss D3	Truss Type Roof Special Girder	Qty 1	Ply 2	Lot 112 MN Job Reference (optional)	148794673
--------------	-------------	-----------------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:40
ID: Hr0UoluygMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCoI7J4zJC7f

Page: 1



Scale = 1:71.5

Plate Offsets (X, Y): [2:0-5-8,Edge], [16:0-3-8,0-3-12], [17:0-5-11,0-4-0], [25:0-4-0,0-5-4], [33:0-3-8,0-2-8], [39:0-1-15,1-0-1]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.60	Vert(LL)	-0.14	27-29	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.46	Vert(CT)	-0.24	26-28	>999	240		
BCLL	0.0*	Rep Stress Incr	NO	WB	0.83	Horz(CT)	0.04	7	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S		Wind(LL)	0.10	27-29	>999	240		

LUMBER		BOT CHORD			
TOP CHORD	2x4 SPF No.2 *Except* 4-2:2x4 SPF 2100F 1.8E	33-35=-325/206, 31-33=-1341/8921, 29-31=-1341/8921, 27-29=-1341/8921, 25-27=-1341/8921, 23-25=-1184/8456, 21-23=-1184/8456, 18-21=-1184/8456, 16-18=-1158/8277, 14-16=-539/4363, 12-14=-539/4363, 8-12=-539/4363, 7-8=-539/4363, 32-34=-1546/197, 30-32=-1431/302, 28-30=-1431/302, 26-28=-1431/302, 24-26=-1431/302, 22-24=-987/154, 20-22=-987/154, 17-20=-987/154, 15-17=-533/76, 13-15=-513/57, 11-13=-513/57, 10-11=-513/57, 9-10=-513/57			
BOT CHORD	2x6 SP 2400F 2.0E				
WEBS	2x4 SPF No.2 *Except* 33-1:2x4 SPF 2100F 1.8E	1-34=-962/8312, 33-34=-1124/9589, 32-33=-3676/403, 2-32=-3240/390, 24-25=-310/2180, 3-24=-345/3483, 3-17=-4277/643, 16-17=-4804/733, 15-16=-337/3306, 5-15=-479/5288, 5-9=-5540/703, 7-9=-6610/807, 30-31=-32/68, 28-29=-118/694, 26-27=-109/482, 22-23=-34/188, 20-21=-43/329, 13-14=-146/1106, 11-12=-36/116, 8-10=-131/1038, 17-18=-146/989			
OTHERS	2x4 SPF No.2				
BRACING					
TOP CHORD	Structural wood sheathing directly applied or 5-5-8 oc purlins, except end verticals, and 2-0-0 oc purlins (4-8-5 max.): 1-2.				
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.				
WEBS	1 Row at midpt 6-7, 3-16, 5-7				
JOINTS	1 Brace at Jt(s): 1, 30, 28, 26, 22, 20, 13, 11, 10, 34				
REACTIONS	(lb/size) 7=4878/0-3-8, (req. 0-4-2), 35=5161/0-3-8, (req. 0-4-6) Max Horiz 35=282 (LC 8) Max Uplift 7=-682 (LC 8), 35=-730 (LC 8) Max Grav 7=5236 (LC 18), 35=5607 (LC 18)				
FORCES	(lb) - Maximum Compression/Maximum Tension				
TOP CHORD	1-35=-4813/587, 1-2=-7099/815, 2-3=-8207/858, 3-5=-4279/380, 5-6=-111/56, 6-7=-179/91				

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BC DL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- WARNING: Required bearing size at joint(s) 35, 7 greater than input bearing size.

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-6-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-4-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.



November 15, 2021

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

Job MN112	Truss D3	Truss Type Roof Special Girder	Qty 1	Ply 2	Lot 112 MN Job Reference (optional)	148794673
--------------	-------------	-----------------------------------	----------	-----------------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:40
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 2

- 12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 730 lb uplift at joint 35 and 682 lb uplift at joint 7.
- 13) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 15) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 763 lb down and 149 lb up at 0-11-3, 769 lb down and 150 lb up at 3-0-12, 769 lb down and 150 lb up at 5-0-12, 769 lb down and 150 lb up at 7-0-12, 976 lb down and 88 lb up at 9-0-12, 976 lb down and 88 lb up at 11-0-12, 937 lb down and 97 lb up at 13-2-15, 837 lb down and 103 lb up at 15-0-12, 837 lb down and 103 lb up at 17-0-12, 837 lb down and 103 lb up at 19-0-12, and 291 lb down and 57 lb up at 5-0-12, and 291 lb down and 57 lb up at 7-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 16) Studding applied to ply: 1(Front)

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15,
Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-70, 2-6=-70, 7-35=-20, 9-34=-20
Concentrated Loads (lb)
Vert: 31=-671 (B), 29=-920 (F=-249, B=-671),
27=-920 (F=-249, B=-671), 23=-806 (B), 21=-806
(B), 14=-741 (B), 12=-741 (B), 8=-741 (B), 18=-797
(B), 50=-674 (B)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job MN112	Truss P1	Truss Type Piggyback	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794674
--------------	-------------	-------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:41
ID:Hr0UloylGMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCDoi7J4zJC?f

Page: 1

-0-9-15	2-7-3	5-2-6	6-0-5
0-9-15	2-7-3	2-7-3	0-9-15



Scale = 1:26.8

Plate Offsets (X, Y): [4:0-2-0,Edge], [5:0-0-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	6	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 17 lb	FT = 10%

LUMBER

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS

(lb/size) 2=113/5-2-6, 6=113/5-2-6, 8=159/5-2-6, 9=159/5-2-6
Max Horiz 2=-48 (LC 6)
Max Uplift 2=-5 (LC 8), 6=-8 (LC 9), 8=-49 (LC 9), 9=-52 (LC 8)
Max Grav 2=114 (LC 21), 6=114 (LC 22), 8=164 (LC 16), 9=166 (LC 15)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/17, 2-3=-51/54, 3-4=-20/6, 4-5=-20/7, 5-6=-47/50, 6-7=0/17
BOT CHORD 2-9=-26/68, 8-9=-26/68, 6-8=-26/68
WEBS 3-9=-130/73, 5-8=-128/71

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 1-4-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 5 lb uplift at joint 2, 8 lb uplift at joint 6, 52 lb uplift at joint 9 and 49 lb uplift at joint 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss P2	Truss Type Piggyback	Qty 9	Ply 1	Lot 112 MN Job Reference (optional)	148794675
--------------	-------------	-------------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:41
ID: Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1

-0-9-15	2-7-3	5-2-6	6-0-5
0-9-15	2-7-3	2-7-3	0-9-15



Scale = 1:24.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.06	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 16 lb	FT = 10%

LUMBER

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=168/5-2-6, 4=168/5-2-6, 6=207/5-2-6
Max Horiz 2=-48 (LC 6)
Max Uplift 2=-43 (LC 8), 4=-49 (LC 9)


FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/17, 2-3=-74/41, 3-4=-71/29, 4-5=0/17
BOT CHORD 2-6=-8/36, 4-6=-8/36
WEBS 3-6=-142/35

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 43 lb uplift at joint 2 and 49 lb uplift at joint 4.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
- LOAD CASE(S)** Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss V2	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794677
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:42
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:42.2

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.31	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.14	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.15	Horiz(TL)	0.00	6	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S						Weight: 46 lb	FT = 10%

LUMBER
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x3 SPF No.2
 OTHERS 2x3 SPF No.2

BRACING
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size)
 1=70/15-1-11, 6=142/15-1-11, 7=392/15-1-11, 8=360/15-1-11, 9=326/15-1-11
 Max Horiz 1=261 (LC 5)
 Max Uplift 6=33 (LC 5), 7=104 (LC 8), 8=96 (LC 8), 9=87 (LC 8)
 Max Grav 1=117 (LC 16), 6=172 (LC 2), 7=440 (LC 2), 8=364 (LC 2), 9=336 (LC 2)

FORCES (lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-223/42, 2-3=-184/53, 3-4=-150/53, 4-5=-126/52, 5-6=-110/43
 BOT CHORD 1-9=-85/64, 8-9=-85/64, 7-8=-85/64, 6-7=-85/64
 WEBS 4-7=-306/143, 3-8=-280/147, 2-9=-251/128

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) All plates are 2x4 MT20 unless otherwise indicated.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) Gable studs spaced at 4-0-0 oc.

- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 6, 104 lb uplift at joint 7, 96 lb uplift at joint 8 and 87 lb uplift at joint 9.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss V3	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794678
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:42
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxBGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:37.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.13	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.09	Horiz(TL)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 36 lb	FT = 10%

LUMBER	
TOP CHORD	2x4 SPF No.2
BOT CHORD	2x4 SPF No.2
WEBS	2x3 SPF No.2
OTHERS	2x3 SPF No.2

BRACING	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(lb/size)	1=130/12-4-2, 5=143/12-4-2, 6=388/12-4-2, 7=377/12-4-2
Max Horiz	1=210 (LC 5)	
Max Uplift	5=-29 (LC 5), 6=-103 (LC 8), 7=-101 (LC 8)	
Max Grav	1=159 (LC 16), 5=170 (LC 2), 6=415 (LC 2), 7=384 (LC 2)	

FORCES	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=-172/54, 2-3=-135/51, 3-4=-116/40, 4-5=-110/43
BOT CHORD	1-7=-68/51, 6-7=-68/51, 5-6=-68/51
WEBS	3-6=-304/148, 2-7=-287/147

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Gable studs spaced at 4-0-0 oc.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 5, 103 lb uplift at joint 6 and 101 lb uplift at joint 7.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss V4	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794679
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:42
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:30

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.30	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.16	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.07	Horiz(TL)	0.00	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 26 lb	FT = 10%

LUMBER

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2
OTHERS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=174/9-6-8, 4=121/9-6-8, 5=491/9-6-8
Max Horiz 1=159 (LC 5)
Max Uplift 4=-23 (LC 5), 5=-130 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-123/72, 2-3=-106/29, 3-4=-96/39
BOT CHORD 1-5=-51/39, 4-5=-51/39
WEBS 2-5=-372/183

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCCL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) Gable requires continuous bottom chord bearing.
- 4) Gable studs spaced at 4-0-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 4 and 130 lb uplift at joint 5.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss V5	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794680
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:43
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:24.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.70	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.38	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 17 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-9-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=267/6-8-14, 3=267/6-8-14
Max Horiz 1=108 (LC 5)
Max Uplift 1=-39 (LC 8), 3=-61 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-97/64, 2-3=-208/96
BOT CHORD 1-3=-35/27

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Gable studs spaced at 4-0-0 oc.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 39 lb uplift at joint 1 and 61 lb uplift at joint 3.



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss V6	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794681
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:43
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCdoi7J4zJC?f

Page: 1



Scale = 1:19.7

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.17	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.09	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 9 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-11-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=141/3-11-5, 3=141/3-11-5
Max Horiz 1=57 (LC 5)
Max Uplift 1=-21 (LC 8), 3=-32 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-51/34, 2-3=-110/51
BOT CHORD 1-3=-19/14

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Gable studs spaced at 4-0-0 oc.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 1 and 32 lb uplift at joint 3.



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss V7	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794682
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:43
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCdoi7J4zJC?f

Page: 1



Scale = 1:41.4												
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.45	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.27	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.11	Horiz(TL)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 44 lb	FT = 10%

LUMBER	
TOP CHORD	2x4 SPF No.2
BOT CHORD	2x4 SPF No.2
WEBS	2x3 SPF No.2
OTHERS	2x3 SPF No.2

BRACING	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS	(lb/size)	1=221/14-8-2, 5=154/14-8-2, 6=326/14-8-2, 7=547/14-8-2
	Max Horiz	1=253 (LC 5)
	Max Uplift	5=-34 (LC 5), 6=-86 (LC 8), 7=-145 (LC 8)
	Max Grav	1=248 (LC 16), 5=185 (LC 2), 6=371 (LC 2), 7=557 (LC 2)

FORCES		(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=-200/88, 2-3=-155/37, 3-4=-123/49, 4-5=-118/46	
BOT CHORD	1-7=-82/62, 6-7=-82/62, 5-6=-82/62	
WEBS	3-6=-260/123, 2-7=-410/207	

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Gable studs spaced at 4-0-0 oc.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 34 lb uplift at joint 5, 86 lb uplift at joint 6 and 145 lb uplift at joint 7.
 - 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss V8	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794683
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:43
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:36.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.19	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.11	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 34 lb	FT = 10%

LUMBER	
TOP CHORD	2x4 SPF No.2
BOT CHORD	2x4 SPF No.2
WEBS	2x3 SPF No.2
OTHERS	2x3 SPF No.2

BRACING	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size)	
1=109/11-10-8, 5=142/11-10-8, 6=395/11-10-8, 7=350/11-10-8	
Max Horiz	1=202 (LC 5)
Max Uplift	5=-29 (LC 5), 6=-104 (LC 8), 7=-93 (LC 8)
Max Grav	1=121 (LC 16), 5=142 (LC 1), 6=395 (LC 1), 7=350 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-166/48, 2-3=-130/52, 3-4=-113/38, 4-5=-109/43
BOT CHORD	1-7=-65/49, 6-7=-65/49, 5-6=-65/49
WEBS	3-6=-309/151, 2-7=-267/138

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Gable studs spaced at 4-0-0 oc.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 5, 104 lb uplift at joint 6 and 93 lb uplift at joint 7.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss V9	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794684
--------------	-------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:43
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:29.2

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.14	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.07	Horiz(TL)	0.00	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 25 lb	FT = 10%

LUMBER

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2
OTHERS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=155/9-0-14, 4=129/9-0-14, 5=460/9-0-14
Max Horiz 1=151 (LC 5)
Max Uplift 4=-23 (LC 5), 5=-122 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-117/64, 2-3=-103/27, 3-4=-101/42
BOT CHORD 1-5=-48/37, 4-5=-48/37
WEBS 2-5=-350/173

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) Gable requires continuous bottom chord bearing.
- 4) Gable studs spaced at 4-0-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 4 and 122 lb uplift at joint 5.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss V10	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794685
--------------	--------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:44
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.58	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.32	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 16 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-3-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=246/6-3-5, 3=246/6-3-5
Max Horiz 1=100 (LC 5)
Max Uplift 1=-36 (LC 8), 3=-56 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-89/59, 2-3=-191/89
BOT CHORD 1-3=-32/25

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) Gable requires continuous bottom chord bearing.
 - 4) Gable studs spaced at 4-0-0 oc.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 36 lb uplift at joint 1 and 56 lb uplift at joint 3.



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss V11	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794686
--------------	--------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:44
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:19

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.12	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.07	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 8 lb	FT = 10%

LUMBER

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-6-5 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=120/3-5-11, 3=120/3-5-11
Max Horiz 1=49 (LC 5)
Max Uplift 1=-17 (LC 8), 3=-27 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-44/29, 2-3=-93/43
BOT CHORD 1-3=-16/12

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) Gable requires continuous bottom chord bearing.
- 4) Gable studs spaced at 4-0-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 17 lb uplift at joint 1 and 27 lb uplift at joint 3.



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job MN112	Truss V12	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794687
--------------	--------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:44
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.17	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 37 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x3 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=85/13-9-0, 5=85/13-9-0, 6=340/13-9-0, 7=298/13-9-0, 8=340/13-9-0
Max Horiz 1=97 (LC 5)
Max Uplift 1=-11 (LC 9), 6=-125 (LC 9), 8=-126 (LC 8)
Max Grav 1=94 (LC 16), 5=85 (LC 1), 6=353 (LC 16), 7=298 (LC 1), 8=353 (LC 15)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-104/74, 2-3=-128/93, 3-4=-124/73, 4-5=-77/37
BOT CHORD 1-8=-22/63, 7-8=-22/63, 6-7=-22/63, 5-6=-22/63
WEBS 3-7=-214/28, 2-8=-282/167, 4-6=-282/167

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BC DL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) Gable studs spaced at 4-0-0 oc.

- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 11 lb uplift at joint 1, 126 lb uplift at joint 8 and 125 lb uplift at joint 6.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss V13	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794688
--------------	--------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:44
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:30.9

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.34	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.21	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 28 lb	FT = 10%

LUMBER

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=218/10-10-11, 3=218/10-10-11, 4=452/10-10-11
Max Horiz 1=75 (LC 5)
Max Uplift 1=-43 (LC 8), 3=-53 (LC 9), 4=-21 (LC 8)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-151/73, 2-3=-150/54
BOT CHORD 1-4=-14/68, 3-4=-14/68
WEBS 2-4=-302/78

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 43 lb uplift at joint 1, 53 lb uplift at joint 3 and 21 lb uplift at joint 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss V14	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794689
--------------	--------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:44
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDOI7J4zJC?f

Page: 1



Scale = 1:26.3

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.11	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 20 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x3 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=171/8-0-7, 3=171/8-0-7, 4=290/8-0-7
Max Horiz 1=-54 (LC 4)
Max Uplift 1=-39 (LC 8), 3=-45 (LC 9)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-97/50, 2-3=-93/37
BOT CHORD 1-4=-10/44, 3-4=-10/44
WEBS 2-4=-202/52

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 39 lb uplift at joint 1 and 45 lb uplift at joint 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



November 15, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job MN112	Truss V15	Truss Type Valley	Qty 1	Ply 1	Lot 112 MN Job Reference (optional)	148794690
--------------	--------------	----------------------	----------	----------	--	-----------

Wheeler Lumber, Waverly, KS - 66871,

Run: 8.43 S Oct 11 2021 Print: 8.430 S Oct 11 2021 MiTek Industries, Inc. Fri Nov 12 16:26:45
ID:Hr0UloylgMOrZQ4rpild7XzssyG-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:22.7

Plate Offsets (X, Y): [2:0-2-0,0-2-5], [3:0-2-0,0-2-5]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.14	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-R							Weight: 11 lb	FT = 10%

LUMBER
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-3-0 oc purlins, except 2-0-0 oc purlins: 2-3.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=188/5-2-2, 4=188/5-2-2
Max Horiz 1=-16 (LC 4)
Max Uplift 1=-13 (LC 5), 4=-13 (LC 4)


FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-261/54, 2-3=-221/43, 3-4=-261/54
BOT CHORD 1-4=-44/221

- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 1 and 13 lb uplift at joint 4.
- 10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) Provide adequate drainage to prevent water ponding.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 4-0-0 oc.
- 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.



November 15, 2021


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MITek 20/20 software** or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI 1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability/bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T or I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020