

PLANS REVIEW CONDITIONS

Permit No: PRCOM20213548 Date: January 03, 2022
Project Title: SIGNATURE AT WEST PRYOR PHASE 2 - Applicant:
BUILDING 1
Location: AEGIS FIRE PROTECTION LLC
2100 NW LOWENSTEIN DR, LEES SUMMIT, MO 64081 11936 W 119TH ST #262
Type of Work: OVERLAND PARK, KS 66213
Occupancy Group: R-2
Description: NEW APARTMENT BUILDING Primary: (913) 825-0343
Construction Type: Type VA (1 hour)
Map Page:

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Sprinkler Plan Review

Reviewed By: Michael Weissenbach

Released for Construction

1. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

(Informational Purposes)

Call (816)969-1300 to schedule a hydrostatic test and alarm/water flow test.

2. 1. Provide signage above the FDC's to pump at 175.

2. Hydrant to be within 100 feet of the FDC's

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.