

### **PLANS REVIEW CONDITIONS**

Permit No:	PRCOM20215684	Date:	January 11, 2022
Project Title:	F.I.T. MUSCLE AND JOINT CLINIC	Applicant:	
Location:	401 NW MURRAY RD, LEES SUMMIT, MO 64081		TECH ELECTRONICS OF KANSAS
Type of Work:			8202 MARSHAL DR
Occupancy Group:	B		LENEXA, KS 66214
Description:	TENANT FINISH FOR PHYSICAL THERAPY	Primary:	(785) 379-0300
**EXTERIOR WORK HAS BEEN OMITTED UNTIL APPROVED BY PLANNING DEPARTMENT			
Construction Type:	Type IIB (Unprotected)		
Map Page:			

**Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.**

#### **Alarm Plan Review**

**Reviewed By: Jim Eden**

**Released for Construction**

1. 2018 IFC 903.4.2- Alarms. Approved audible and visual devices shall be connected to every automatic sprinkler system. Such sprinkler water-flow alarm devices shall be activated by water flow equivalent to the flow of a single sprinkler of the smallest orifice size installed in the system. Listed alarm notification devices shall be provided on the exterior and interior of the building in an approved location. Where a fire alarm system is installed, actuation of the automatic sprinkler system shall actuate the building fire alarm system.

Will confirm that sprinkler system is monitored by the alarm system at time of inspection.

2. 2018 IFC 904.4.2- Alarm testing. Notification appliances, connections to fire alarm systems, and connections to approved supervising stations shall be tested in accordance with this section and Section 907 to verify proper operation.

Call (816) 969-1300 to schedule an alarm test.

**The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.**