



Summary List of Materials

9/1/2021

Work Request: 1014218

Service Center: LSMT

Work Order: 50030726

Job Address: MONARCH ACQUISITIONS,
NW LOWENSTEIN DR
STREETS OF WEST PRYOR
LEE'S SUMMIT, MO

In-Service Date: 10/31/2021

Planner: Williams, Jeff

Material Item	QTY	UOM	Description
000096001628	1	EA	CONNECTOR OVRHD:PARALLEL GROOVE;SHEARBOLT;NON TENSION;2
000096001629	2	EA	CONNECTOR OVRHD:PARALLEL GROOVE;SHEARBOLT;NON TENSION;6
000096002049	6	EA	CONNECTOR OVRHD:WEDGE;SHEARBOLT;#4 - 350;.292 - .398IN;
000096002307	2	EA	GRIP CABLE:CNDT;3;4IN;450LB;VENTILATING SPLIT;1/0 AL -
203083	14	EA	SCREW LAG:0.5;1/2;4;STL;BLK
405001	3	EA	INSULATOR:SUSP;15KV;POLYMER;12.5IN;15000LB;15KV
405053	3	EA	INSULATOR:GUY STRAIN;CLEVIS TO CLEVIS;FBRGLS;15000LB;13
406005	2	EA	BRACKET MOUNTING:EQUIPMENT;3;3;1-1/2;FBRGLS;13;36;0;3-P
406084	14	EA	BRACKET:CONDUIT STAND OFF;6IN;STL;SINGLE 2" - 5" CONDUIT
406101	9	EA	BRACKET:EXTENDED L
407001	5	EA	CONNECTOR GROUNDING:GROUND ROD CLAMP;#10AWG SOL 1/0 A
407007	5	EA	ROD GROUND:0.5INX96FT;STL;ASTM A370;NEMA GR-1;COPPER BO
409030	9	EA	BOLT MACHINE:SQ;0.5IN;ROLLED THREADS;10;STL;ROLLED THRE
409037	10	EA	BOLT MACHINE:SQ;0.625IN;ROLLED THREADS;12;STL;ROLLED TH
409117	1.29	EA	STAPLE INDUSTRIAL:GROUND WIRE;3/8IN;0.13IN;1-1/2IN;STL;
409128	9	EA	WASHER FLAT:1/2IN;0.5625IN;2IN;2IN;0.125IN;SQ;STL;GALVA
409130	8	EA	WASHER FLAT:0.687IN;0.6875IN;2-1/4IN;2-1/4IN;0.1875IN;S
409143	12	EA	STAPLE INDUSTRIAL:MOULDING;1.0625IN;1/4IN;3IN;STL;GALVA
409173	4	EA	BOLT EYE:DEADEND
409203	9	EA	SCREW LAG:FETTER DRIVE/GIMLET POINT;SQ;3/8;3/8;3;STL;GA
409254	9	EA	NUT LOCK:CRV;SQ;0.5;1/2;UNC;0.812;0.812;STL;GALVANIZED
409263	8	EA	NUT LOCK:CRV;SQ;0.625IN;5/8;UNC;1IN;1IN;STL;GALVANIZED
409492	8	EA	SCREW LAG:GIMLET POINT;SQ;1/4;1/4;1-1/2;STL;GALVANIZED;
409535	3	EA	LINK CHAIN:5/8IN;1IN;3-1/4IN
409631	2	EA	HOOK:7/16X5-1/4IN;ZINC COATED
410055	12	EA	TAG IDENTIFICATION:MARKER BOARD;PE;11 POSITION/HORIZONT
420087	174	FT	WIRE OVRHD:BARE;4;CU;200FT;SLD
420204	45	FT	WIRE OVRHD:COVERED;4AWG;1;SOFT COPPER;0.178LB/FT;HMPE;1
420227	28	FT	WIRE OVRHD:BARE;1/0AWG;19;SOFT DRAWN COPPER;1000FT;STRA
421228	6	EA	FUSE MOUNTING:CUTOUT;15KV;100A;POLYMER;10000A
423010	3	EA	ARRESTER SURGE:ELBOW;10KV;8.4KV;15KV;METAL OXIDE VARIST
423072	3	EA	ARRESTER SURGE:HD;10KV;8.4KV;SI;METAL OXIDE VARISTOR;IS
423094	6	EA	ARRESTER SURGE:RISER POLE;10KV;8.4KV;POLYMER;METAL OXID
427031	1	EA	DEADEND:BOLTED;SIDE OPENING;0.19 - 0.57IN;4 - 4/0;AL;80
427046	24	FT	MOLDING:8FT;WOOD
427054	29	EA	CONNECTOR OVRHD:SPLIT BOLT;1/0AWG;BRNZ/CU
427062	3	EA	CONNECTOR OVRHD:SPLIT BOLT;4SOLAWG;BRNZ/CU



Summary List of Materials

9/1/2021

Work Request: 1014218

Service Center: LSMT

Work Order: 50030726

Job Address: MONARCH ACQUISITIONS,
NW LOWENSTEIN DR
STREETS OF WEST PRYOR
LEE'S SUMMIT, MO

In-Service Date: 10/31/2021

Planner: Williams, Jeff

Material Item	QTY	UOM	Description
427365	3	EA	DEADEND:BOLTED;3/0 ACSR & 4/0 STR - 477 ACSR & 556 STR;
427367	6	EA	CLAMP HOT LINE:HOT LINE;8 - 2/0 ACSR;8 - 2/0 ACSR;TINNE
427645	24	EA	TIE CABLE:LOCKING;0.3IN;15IN;4IN;NYL 6.6;BLK;WEATHER RE
427741	6	EA	CONNECTOR PIN TERMINAL:CMPSN;1/0 AA/ACSR AND NO 2 BARE
427806	6	EA	CLAMP HOT LINE:HOT LINE;6 - 400;6 - 3/0;TINNED ALUMINUM
427807	3	EA	CLAMP HOT LINE:HOT LINE;4/0 - 795;4 - 266;TINNED ALUMIN
430817	6	EA	LINK FUSE:CUTOUT;65A;K
450004	10	FT	CONDUIT:PVC;0.5IN;RGD;40;10FT
450059	157	FT	CONDUIT:PVC;4IN;SCH 40;10FT;W/ ONE DEEP BELLED END
450065	2	EA	COUPLING CONDUIT:4IN;PVC;SOC;SCH 40
450078	6	EA	BEND CONDUIT:4IN;90DEG;36IN;SCH 40;PVC;ASTM F512;NON BE
453014	4	EA	STRAP CONDUIT:EMT;0.5IN;STL;ZN;1HOLES
453070	35	FT	BAND:1/2INX100FT;SS
453072	14	EA	BUCKLE FASTENER:1/2IN
455013	2	EA	ENCLOSURE SECTIONALIZING:LDBRK;200A;3PH;FBRGLS;W/ 4-WAY
460019	218	FT	CABLE UG:HV;1/0AWG;19STR;STRANDED;3/4 HARD ALUMINUM;3C;
465083	9	EA	CAP INSULATING:15KV
465268	3	EA	FEED-THRU:LDBRK;15KV;PARKING STAND;2
465327	6	EA	TERMINATION KIT:COLD SHRINK;2-4/0AWG;OUTDR;15KV
465336	9	EA	INDICATOR FAULT:UG;NON-COMMUNICATING;LOAD TRACKER;SNAP
465706	6	EA	CONNECTOR CABLE:LOADBREAK ELBOW;1/0AWG;200A;AL/CU;AL;15
467098	7.50	EA	TAPE INSULATING:ELEC;3/4INX76FTX7MIL;VINYL;BLK
467156	3	EA	TAPE INSULATING:PUTTY;1-1/2X60IN
467163	12	EA	KIT:CABLE PREPARATION;3X WET TOWEL;1X36IN STRIP OF 120
468052		QT	ADHESIVE:PVC SOLVENT/CEMENT;1QT;BRUSH TOP CAN
598250	6	EA	TAPE INSULATING:SPLICING;3/4INX30FT;RBR;TRADE NAME 130C