





SHEET INDEX	
Sheet	Sheet Name
A100	COVER SHEET
S100	FOUNDATION PLAN
S101	FIRST FLOOR FRAMING PLAN
S102	SECOND FLOOR FRAMING PLAN
S103	ROOF FRAMING PLAN
S500	GENERAL NOTES
S501	DETAILS
S502	DETAILS
S503	DETAILS
S504	DETAILS
S505	DETAILS

SQUARE FOOTAGES	
Name	Area
FIRST FLOOR	1217 SF
SECOND FLOOR	1493 SF
GARAGE	643 SF
UNFINISHED BASEMENT	1092 SF
	4445 SF



# THE LEXINGTON II



**Norton & Schmidt**

Consulting Engineers, L.L.C.

311 East 11th Avenue  
North Platte City, MO  
68116

Phone: (816) 421-4232  
Fax: (816) 421-1956  
www.nortonschmidt.com

N&S JOB NUMBER: 2021-27720  
© 2020 Norton & Schmidt Consulting Engineers

PROJECT INFORMATION

THE LEXINGTON II - WALKOUT

LOT 138

4728 JAMESTOWN DRIVE

LEE'S SUMMIT, MO 64064


[illegible]

DRAWN BY: MLR  
CHECKED BY: BSS  
ISSUED FOR:

SHEET TITLE
COVER SHEET
RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
02/03/2022

SHEET NUMBER  
A100





FOOTING SCHEDULE				
MARK	SIZE L X W x THK	REINFORCING (NO) SIZE LOCATION	TOF EL	COLUMN
F1	2'-0" x 2'-0" x 1'-0"	(4) #4 EW BOTTOM	8" BELOW TOP OF SLAB	3'0" STD (SCHED 40) STEEL PIPE COLUMN (3.5'OD, 3.07" ID)
F2	2'-6" x 2'-6" x 1'-0"	(5) #4 EW BOTTOM	8" BELOW TOP OF SLAB	3'0" STD (SCHED 40) STEEL PIPE COLUMN (3.5'OD, 3.07" ID)
F3	3'-0" x 3'-0" x 1'-0"	(6) #4 EW BOTTOM	8" BELOW TOP OF SLAB	3'0" STD (SCHED 40) STEEL PIPE COLUMN (3.5'OD, 3.07" ID)
F4	4'-0" x 4'-0" x 1'-4"	(8) #4 EW BOTTOM	8" BELOW TOP OF SLAB	3'0" STD (SCHED 40) STEEL PIPE COLUMN (3.5'OD, 3.07" ID)

[illegible]

DRAWN BY: MLR  
CHECKED BY: BSS  
ISSUED FOR:

SHEET NUMBER

S100

RELEASE FOR CONSTRUCTION  
AS NOTED FOR PLAN REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI  
02/03/2022

**Norton & Schmidt**  
Consulting Engineers, L.L.C.  
311 East 11th Avenue  
North Kansas City, MO  
64116  
Phone: (816) 421-1422  
Fax: (816) 421-1368  
www.nortonschmidt.com

**STATE OF MISSOURI**  
**BRANDON**  
**SCHWABAUER**  
*Brandon Schwabauer*  
**NUMBER**  
PE-2015003020  
**1/11/2022**  
**PROFESSIONAL ENGINEER**

**NKS JOB NUMBER: 2021-27720**  
© 2020 Norton & Schmidt Consulting Engineers

PROJECT INFORMATION

THE LEXINGTON II - WALKOUT


LOT 138

4728 JAMESTOWN DRIVE  
LEE'S SUMMIT, MO 64064

N&S JOB NUMBER: 2021-2720  
© 2020 Norton & Schmidt Consulting Engineers

1 FOUNDATION PLAN  
SCALE: 1/4" = 1'-0"





**Norton & Schmidt**  
Consulting Engineers, L.L.C.  
311 East 11th Avenue  
North Kansas City, MO  
64106  
Phone: (816) 421-1432  
Fax: (816) 421-1958  
www.nortonschmidt.com

STATE OF MISSOURI  
BRANDON SCHWABAUER  
NUMBER  
PE-2015003020  
1/11/2022  
PROFESSIONAL ENGINEER

© 2020 Norton & Schmidt Consulting Engineers  
N&S JOB NUMBER 2021-2720

PROJECT INFORMATION

THE LEXINGTON II - WALKOUT

LOT 138

4728 JAMESTOWN DRIVE  
LEE'S SUMMIT, MO 64064

[illegible]

DRAWN BY: MLR  
CHECKED BY: BSS  
ISSUED FOR:


SHEET TITLE
FIRST FLOOR FRAMING PLAN

SHEET NUMBER
S101

RELEASE FOR CONSTRUCTION  
AS NOTED FOR PLAN REVIEW  
UNLESS OTHERWISE SPECIFIED  
LEE'S SUMMIT, MISSOURI  
02/03/2022

# 1 FIRST FLOOR FRAMING PLAN


SCALE: 1/4" = 1'-0"



SCALE: 1/4" = 1'-0"

RELEASE FOR CONSTRUCTION  
AS NOTED FOR PLAN REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI  
02/03/2022





**NOTE:**

- RAFTERS TO BE 2x6 DF-L No. 2 AT 16" O.C. U.N.O.
- HIP, VALLEY, AND RIDGE MEMBERS SHALL BE (1)2x8 DF-L No. 2 U.N.O.
- REF. 12/S503 FOR PURLING BRACING

**Norton & Schmidt**  
Consulting Engineers, L.L.C.  
311 East 11th Avenue  
North Kansas City, MO  
64116  
Phone: (816) 421-4232  
Fax: (816) 421-1868  
www.nortonschmidt.com

**STATE OF MISSOURI**  
**BRANDON SCHWABAUER**  
*Brandon Schwabauer*  
**NUMBER**  
PE-2015003020  
**1/11/2022**  
**PROFESSIONAL ENGINEER**

**N&S JOB NUMBER: 2021-27720**  
© 2020 Norton & Schmidt Consulting Engineers

PROJECT INFORMATION  
THE LEXINGTON II - WALKOUT  
LOT 138  
4728 JAMESTOWN DRIVE  
LEE'S SUMMIT, MO 64064

[illegible]

DRAWN BY: MLR  
CHECKED BY: BSS  
ISSUED FOR:

SHEET TITLE
ROOF FRAMING PLAN

**SHEET NUMBER**

**S103**

RELEASE FOR CONSTRUCTION  
AS NOTED FOR PLAN REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI  
02/03/2023

N&S JOB NUMBER: 2021-2720  
© 2020 Norton & Schmidt Consulting Engineers



GENERAL NOTES

GOVERNING BUILDING CODE: 2018 INTERNATIONAL RESIDENTIAL CODE (IRC) AND ITS APPROPRIATE SUPPLEMENTS

DESIGN LOADS:

- ROOF DEAD LOAD: \_\_\_\_\_ 10 PSF
- ROOF LIVE LOAD: \_\_\_\_\_ 20 PSF
- FLOOR DEAD LOAD: \_\_\_\_\_ 10 PSF
- FLOOR LIVE LOAD: \_\_\_\_\_
- BEDROOMS: \_\_\_\_\_ 30 PSF
- ALL OTHER LIVING AREAS: \_\_\_\_\_ 40 PSF
- WIND LOADS: \_\_\_\_\_ Vu11=115 MPH, EXPOSURE C
- SEISMIC LOADS: \_\_\_\_\_ SITE CLASS "B"
- ASSUMED ALLOWABLE SOIL BEARING PRESSURE: \_\_\_\_\_ 1500 PSF

GENERAL:

1. FURNISH ALL LABOR, MATERIAL AND EQUIPMENT NECESSARY TO COMPLETE THE WORK SHOWN OR INFERRED BY THESE DRAWINGS.
2. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DIMENSIONS AND ELEVATIONS SHOWN ON THE PLANS AND FOR COORDINATING ALL DIMENSIONS AND ELEVATIONS SHOWN WITH THE EXISTING CONDITIONS. IF ERRORS OR DISCREPANCIES IN THE DIMENSIONS OCCUR, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO BRING ALL DISCREPANCIES TO THE ATTENTION OF THE ENGINEER BEFORE PROCEEDING WITH THE WORK.
3. THE CONTRACTOR SHALL PROVIDE ALL TEMPORARY BRACING AND SHORING AS REQUIRED DURING CONSTRUCTION TO ENSURE THE SAFETY OF ALL INDIVIDUALS INVOLVED.
4. ALL MECHANICAL, ELECTRICAL, AND PLUMBING ELEMENTS SHALL BE INSTALLED PER THE REQUIREMENTS OF THE GOVERNING BUILDING CODE AND THE LOCAL MUNICIPALITY.
5. NORTON & SCHMIDT CONSULTING ENGINEERS, L.L.C. HAS DESIGNED THE STRUCTURAL FLOOR FRAMING AND WALL BRACING SYSTEM OF THESE PLANS FOR THE CONSTRUCTION OF A RESIDENCE AT THE ADDRESS REFERENCED IN THE PLANS. NORTON & SCHMIDT CONSULTING ENGINEERS, L.L.C. WILL NOT TAKE RESPONSIBILITY FOR ANY RE-USE OF ANY PORTION OF THE DESIGN, PLANS OR SPECIFICATIONS AT ANY OTHER PROPERTY OR ADDRESS WITHOUT OUR PRIOR WRITTEN CONSENT.

BUILDER'S PLANS:

THE TERM "BUILDER'S PLANS" REFERS TO A CERTAIN LEVEL OF DEVELOPMENT OF THE DRAWINGS. AS THE NAME IMPLIES, THESE PLANS REQUIRE THAT THE CONTRACTOR POSSESSES COMPETENCE IN RESIDENTIAL CONSTRUCTION AND A THOROUGH UNDERSTANDING OF THE INTERNATIONAL RESIDENTIAL CODE (IRC). THE CONTRACTOR WARRANTS TO NORTON & SCHMIDT CONSULTING ENGINEERS, L.L.C., THAT HE POSSESSES THE PARTICULAR COMPETENCE AND SKILL IN CONSTRUCTION NECESSARY TO BUILD THIS PROJECT WITHOUT FULL ENGINEERING AND DESIGN SERVICES, AND FOR THAT REASON THE CONTRACTOR OR HOME OWNER HAS RESTRICTED THE SCOPE OF PROFESSIONAL SERVICES. THE CONSTRUCTION DOCUMENTS PROVIDED BY THE LIMITED SERVICES SHALL BE TERMED "BUILDER'S PLANS" IN RECOGNITION OF THE CONTRACTOR'S SOPHISTICATION. ALTHOUGH NORTON & SCHMIDT CONSULTING ENGINEERS, L.L.C. AND OUR CONSULTANTS HAVE PERFORMED THEIR SERVICES WITH DUE CARE AND DILIGENCE, WE CANNOT GUARANTEE PERFECTION. ANY AMBIGUITY OR DISCREPANCY DISCOVERED BY THE USE OF THESE PLANS SHALL BE REPORTED IMMEDIATELY TO NORTON & SCHMIDT CONSULTING ENGINEERS, L.L.C. CONSTRUCTION MAY REQUIRE THAT THE CONTRACTOR ADAPT THE "BUILDER'S PLANS" TO THE FIELD CONDITIONS ENCOUNTERED AND MAKE LOGICAL ADJUSTMENTS IN FIT, FORM, DIMENSION AND QUANTITY. CHANGES MADE FROM THE PLANS WITHOUT THE CONSENT OF NORTON & SCHMIDT CONSULTING ENGINEERS, L.L.C. ARE UNAUTHORIZED. IT IS ALSO UNDERSTOOD THAT THE CONTRACTOR WILL BE RESPONSIBLE FOR MEETING ALL APPLICABLE BUILDING CODES INCLUDING BUT NOT LIMITED TO MECHANICAL, ELECTRICAL, AND PLUMBING CODE REQUIREMENTS (WHICH IS EXCLUDED FROM THESE PLANS). IN THE EVENT ADDITIONAL DETAIL, OR GUIDANCE IS NEEDED BY THE CONTRACTOR OR HOMEOWNER FOR CONSTRUCTION OF ANY ASPECT OF THE PROJECT, NORTON & SCHMIDT CONSULTING ENGINEERS, L.L.C. OR A QUALIFIED ARCHITECT/ENGINEER SHALL IMMEDIATELY BE RETAINED. FAILURE TO NOTIFY US OF THESE NEEDS OR OF CHANGES TO THE PLANS SHALL RELIEVE NORTON & SCHMIDT CONSULTING ENGINEERS, L.L.C. OF ALL RESPONSIBILITIES OF THE CONSEQUENCES.

ARCHITECTURAL NOTES:

1. WATER RESISTIVE EXTERIOR WALL COVERING, FREE FROM HOLES AND BREAKS, SHALL BE APPLIED TO STUDS OR SHEATHING OF ALL EXTERIOR WALLS. WRAP SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS AND SHALL BE IN COMPLIANCE WITH SECTION R703.2.
2. BUILDING SHALL COMPLY WITH SECTIONS 802.3 AND 802.3.1 OF THE 2018 IRC FOR RAFTER AND CEILING JOIST CONNECTIONS.
3. "UFER" GROUND SHALL BE PROVIDED PER IRC SECTION 3608.1
4. GUTTERS, DOWNSPOUTS, AND SPLASH BLOCKS SHALL BE PROVIDED TO INSURE ALL ROOF DRAINAGE IS DIRECTED 5 FEET MINIMUM FROM HOUSE BEFORE TOUCHING SOIL.

STAIR NOTES:

1. MAXIMUM RISER AT STAIRWAYS IS 7 3/4" AND MINIMUM TREAD IS 10" WITH A MINIMUM 6"-8" HEADROOM. PER 2018 IRC SEC. R311.7.
2. PLACE HANDRAILS ON ALL STAIRS AND/OR LEVELS THAT EXCEED 30" ABOVE THE FLOOR OR GRADE. RAILINGS TO BE MIN. 36" HIGH AND HAVE INTERMEDIATE RAILS THAT DO NOT ALLOW THE PASSAGE OF A 4" DIAMETER SPHERE AND SHALL COMPLY W/ 2018 IRC SEC. R312.
3. ENCLOSE ACCESSIBLE SPACE BENEATH STAIRS SHALL HAVE WALLS AND THE UNDERSIDE OF THE STAIR AND LANDING PROTECTED WITH 1/2" GYPSUM BOARD ON ENCLOSURE SIDE PER SECTION R302.7.
4. STAIRWAYS CONSISTING OF 3 OR MORE RISERS SHALL HAVE A CONTINUOUS HANDRAIL ON AT LEAST ONE SIDE BETWEEN 34" AND 38" ABOVE THE STAIR NOSINGS.
5. HANDRAILS SHALL HAVE A CIRCULAR CROSS SECTION OF 1 1/4" MINIMUM TO 2" MAXIMUM OR OTHER APPROVED GRASPABLE SHAPE PER SECTION R311.7.8.3.
6. SPIRAL STAIRS SHALL BE CONSTRUCTED PER SECTION R311.7.10.11.

EMERGENCY EGRESS NOTES:

1. ALL SLEEPING ROOMS AND BASEMENT SHALL BE PROVIDED WITH PROPER EMERGENCY ESCAPE AND RESCUE OPENINGS PER 2018 IRC SEC R310. PROVIDE (1) WINDOW IN EACH BEDROOM THAT HAS A MINIMUM OPERABLE AREA OF 5.7 SQ. FT. WITH A MINIMUM OPERABLE HEIGHT OF 24" AND WIDTH OF 21".
2. PROVIDE SMOKE ALARMS IN EACH SLEEPING ROOM, OUTSIDE OF EACH SLEEPING AREA IN THE IMMEDIATE VICINITY OF THE BEDROOMS AND ON EACH ADDITIONAL FLOOR, INCLUDING BASEMENTS AND STAIRWAYS. ALARMS SHALL BE INTERCONNECTED IN SUCH A MANNER THAT THE ACTIVATION OF ONE ALARM ACTIVATES ALL OTHERS AND BE HARD WIRED WITH A BATTERY BACKUP, PER 2018 IRC SEC. R314 AND NFPA 72.
3. CARBON MONOXIDE DETECTORS SHALL BE PROVIDED PER R315.

WINDOWS AND SAFETY GLAZING NOTES:

1. GLAZING IN HAZARDOUS LOCATIONS AS IDENTIFIED IN IRC SECTION R308.4 SHALL BE OF APPROVED SAFETY GLAZING MATERIALS. GLASS IN STORM DOORS, INDIVIDUAL FIXED OR OPERABLE PANELS ADJACENT TO A DOOR WHERE THE NEAREST VERTICAL EDGE IS WITHIN A 24" ARCH OF THE DOOR IN A CLOSED POSITION AND WHOSE BOTTOM EDGE IS WITHIN 60" OF THE FLOOR; WALLS ENCLOSING STAIRWAYS AND LANDINGS WHERE THE GLAZING IS WITHIN 60" OF THE TOP OR BOTTOM OF THE STAIR, ENCLOSURES FOR SPAS, TUBS, SHOWERS AND WHIRLPOOLS; GLAZING IN FIXED OR OPERABLE PANELS EXCEEDING 9 SQ. FT. AND WHOSE BOTTOM EDGE IS LESS THAN 18" ABOVE THE FLOOR OR WALKING SURFACE WITHIN 36".
2. ALL WINDOWS SHALL MEET THE FALL PROTECTION REQUIREMENTS OF SECTION R312.2.

GARAGE:

1. GARAGE FLOORS SHALL SLOPE TOWARDS THE GARAGE DOORWAYS.
2. DOORS BETWEEN THE GARAGE AND THE DWELLING SHALL BE A MINIMUM 1 3/8" SOLID CORE OR HONEY COMBED STEEL DOOR OR A 20 MINUTE FIRE RATED DOOR.
3. THE GARAGE SHALL BE SEPARATED FROM THE DWELLING AND ITS UNFINISHED ATTIC AREAS BY A MINIMUM 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE. WHERE UNFINISHED ATTIC AREAS ARE PROVIDED ABOVE THE GARAGE, THE SUPPORTING COLUMNS AND BEAMS SHALL ALSO BE PROTECTED WITH 1/2" GYPSUM BOARD OR EQUIVALENT. WHERE HABITABLE SPACE OCCURS ABOVE THE GARAGE THE FLOOR/CEILING ASSEMBLY SHALL BE PROTECTED WITH A MINIMUM 5/8" TYPE X GYPSUM BOARD ON THE GARAGE CEILING, SHALL COMPLY WITH IRC SEC. R309.
4. GARAGE DOOR AND FRAME (IF FRAME) FOR THE ATTACHMENT OF THE TRACK AND COUNTER BALANCE SHALL CONSIST OF THE FOLLOWING: 2X6 VERTICAL JAMBS RUNNING FROM THE FLOOR TO CEILING ATTACHED WITH 1 3/4"x0.12" NAILS @ 7"OC STAGGERED WITH (7) 3 1/4"x0.102" NAILS THRU THE JAMB INTO THE HEADER, MINIMUM 2X8 HEADER FOR ATTACHMENT FOR COUNTER BALANCE SYSTEM.
5. BUILDING SHALL COMPLY WITH THE REQUIREMENTS FOR A SELF CLOSING DOOR BETWEEN RESIDENCE AND GARAGE.
6. GARAGE DOORS SHALL MEET THE REQUIREMENTS OF DASMA 115 MPH.

STRUCTURAL STEEL:

1. ALL STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING:
  - a. STRUCTURAL STEEL \_\_\_\_\_ ASTM A992, FY = 50 KSI
  - b. MISCELLANEOUS STEEL \_\_\_\_\_ ASTM A36
  - c. HOLLOW STRUCTURAL STEEL (HSS) \_\_\_\_\_ ASTM A500, GRADE B
  - d. STEEL PIPE \_\_\_\_\_ ASTM A53, GRADE B (SCHED 40 MIN)
2. ALL BEAM CONNECTIONS SHALL BE DESIGNED BY THE STEEL FABRICATOR UNDER THE DIRECTION OF A REGISTERED PROFESSIONAL ENGINEER UNLESS SPECIFIC CONNECTIONS ARE SHOWN ON THE DRAWINGS. CONNECTIONS SHALL BE DESIGNED TO 50% U.D.L. OR THE REACTION PROVIDED ON THE DRAWINGS, WHICH EVER IS GREATER, CONNECTIONS SHALL BE WELDED OR BOLTED PER AISI STEEL CONSTRUCTION MANUAL. BOLTS SHALL BE ASTM A325N.
3. ALL COLUMN ANCHOR BOLTS SHALL BE ASTM F1554 GRADE 36.
4. WELDING SHALL CONFORM TO THE LATEST PUBLICATION OF APPLICABLE CODES SET FORTH BY THE AMERICAN WELDING SOCIETY. NO UNAUTHORIZED WELDS WILL BE ACCEPTED.
5. PROVIDE 30# FELT BOND BREAK AROUND ALL STEEL COLUMNS WHERE IN CONTACT WITH SLAB-ON-GRADE.
6. ALL EXTERIOR STEEL EXPOSED TO THE ELEMENTS SHALL BE HOT DIPPED GALVANIZED UNLESS NOTED OTHERWISE.
7. ALL STRUCTURAL STEEL SHALL HAVE ONE COAT OF RUST INHIBITIVE PRIMER CONFORMING TO SPECIFICATIONS. FIELD TOUCHUP ALL UNPAINTED AREAS AND WELD AREAS.

WOOD FRAMING NOTES:

1. ALL STRUCTURAL LUMBER (RAFTERS, CEILING JOISTS, PURLINS AND HEADERS) SHALL BE DOUGLAS FIR LARCH #2 OR BETTER UNLESS OTHERWISE NOTED ON THE DRAWINGS. ALL LOAD BEARING WALL STUDS AND PURLIN STRUTS SHALL BE DOUGLAS FIR STUD GRADE OR BETTER.
2. GLUE LAMINATED MEMBERS MARKED "LVL" (LAMINATED VENEER LUMBER) SHALL HAVE A MINIMUM ALLOWABLE BENDING STRESS (FB) OF 2800 PSI, A MINIMUM ALLOWABLE SHEAR STRESS (FV) OF 285 PSI, AND A MINIMUM MODULUS OF ELASTICITY (E) OF 2,000 KSI. ALL MANUFACTURER'S RECOMMENDATIONS FOR NAILING AND CONNECTIONS SHALL BE FOLLOWED.
3. FLOOR JOISTS BELOW PARTITION WALLS RUNNING PARALLEL TO THE JOIST SPAN SHALL BE DOUBLED. ALL DOUBLED MEMBERS SHALL BE NAILED TOGETHER WITH 16D NAILS 16" ON CENTER IN TWO ROWS STAGGERED OR PER MANUFACTURER SPECS.
4. SOLID BLOCKING BETWEEN FLOOR JOISTS SHALL BE INSTALLED WHERE JOISTS BEAR ON TOP OF BEAMS OR HEADERS AND BELOW POINT LOADS. ALL SOLID BLOCKING AND RIM JOIST MATERIAL SHALL BE THE SAME SIZE AND GRADE AS THE JOISTS.
5. ALL FLOOR AND CEILING JOISTS THAT BUTT INTO THE SIDE OF A HEADER OR STEEL BEAM SHALL BE ANCHORED TO THE HEADER OR STEEL BEAM WITH STANDARD JOIST HANGERS.
6. ALL SUPPORTS FOR WOOD TRUSSES, RAFTERS AND PURLINS, UNLESS SHOWN OTHERWISE ON THE DRAWINGS, SHALL BEAR ON LOAD BEARING WALLS (WALLS LOCATED DIRECTLY ABOVE A BEAM LINE OR CONTINUOUS FOOTING) ALL CONCENTRATED LOADS SHALL BE CARRIED THROUGH THE FLOOR SYSTEM THICKNESS WITH SOLID BLOCKING OR WITH 2X4 STUB COLUMNS (SQUASH BLOCKS) THAT TRANSFER THE LOAD DOWN TO THE SUPPORT WALL OR BEAM BELOW.
7. ALL NAILING NOT INDICATED ON THE DRAWINGS SHALL CONFORM TO THE NAILING SCHEDULE OF THE GOVERNING BUILDING CODE. SPACING, END DISTANCES AND EDGE DISTANCES OF NAILS AND SPIKES SHALL BE SUCH AS TO AVOID THE UNUSUAL SPLITTING OF THE WOOD.
8. ALL NON-LOADBEARING STUD WALLS IN THE BASEMENT SHALL BE PROVIDED WITH A 1" MINIMUM VERTICAL EXPANSION JOINT TO ALLOW FOR HEAVE IN THE FLOOR SLAB.
9. WALLS SHALL NOT BE TIGHT BETWEEN THE SLAB AND THE FRAMING ABOVE!
10. SHEATHING FOR HORIZONTAL DIAPHRAGMS SHALL BE EXTERIOR GRADE, C/D, STRUCTURAL GROUP II OR BETTER. ROOF AND WALL FRAMING SHALL BE OF DOUGLAS FIR-LARCH OR SOUTHERN PINE. PROVIDE SOLID BLOCKING AT ALL PANEL EDGES UNLESS OTHERWISE NOTED. WHERE PANELS ARE APPLIED ON BOTH FACES OF A WALL, PANEL JOINTS SHALL BE OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS.
11. ALL WOOD STRUCTURAL PANELS SHALL BE IDENTIFIED WITH THE APPROPRIATE GRADE TRADEMARK OF THE AMERICAN PLYWOOD ASSOCIATION (APA) AND SHALL MEET THE REQUIREMENTS OF PRODUCT STANDARD PS-1.
12. WOOD STRUCTURAL PANELS SHALL BE SET WITH FACE GRAIN PERPENDICULAR TO SUPPORTING MEMBERS AND STAGGER END JOINTS 4'-0".
13. STANDARD WASHERS SHALL BE USED WITH ALL BOLTS FASTENING WOOD MEMBERS.
14. ALL SAWN LUMBER EXPOSED TO WEATHER OR IN CONTACT WITH CONCRETE OR MASONRY SHALL BE PRESSURE TREATED.
15. ROOF FRAMING - RIDGE BEAMS, VALLEY AND HIP RAFTERS SHALL HAVE A MINIMUM NOMINAL THICKNESS OF 2" AND MINIMUM DEPTH NOT LESS THAN THE END CUT OF THE RAFTERS. HIP AND VALLEY RAFTERS SHALL BE SUPPORTED AT THE RIDGE BY A 2X6 "TEE" BRACE TO A BEARING PARTITION. WHERE ROOF BRACING IS USED TO PERMIT LONGER RAFTERS SPAN, USE 2X6 "TEE" BRACES AT 4'-0" O.C. WITH CONTINUOUS 2X6 PURLIN UNDER THE RAFTERS. BRACE RAFTERS TO BEARING PARTITIONS.
16. PROVIDE CONTINUOUS STRONG BACKS FOR CEILING JOIST SPANS 12'-0" OR GREATER.
17. MAXIMUM FLOOR JOIST SPANS SHALL BE AS FOLLOWS FOR THE SIZE AND SPACING OF THE JOISTS INDICATED (40 PSF LIVE LOAD, 10 PSF DEAD LOAD):
  - a. 2X8'S AT 16" O.C. - 12'-7"
  - b. 2X10'S AT 16" O.C. - 15'-4"
  - c. 2X10'S AT 12" O.C. - 16'-10"
  - d. 2X12'S AT 16" O.C. - 17'-10"
18. CEILING JOISTS (C.J.'S) ARE DFL#2, AT 16" O.C., WITH AN ALLOWABLE SPAN AS FOLLOWS, OR AS SHOWN ON PLANS:
  - a. 2X8'S AT 16" O.C. - 12'-10"
  - b. 2X8'S AT 16" O.C. - 16'-3"
  - c. 2X10'S AT 16" O.C. - 19'-10"
  - d. 2X12'S AT 16" O.C. - 22'-0"
19. ROOF RAFTERS (R.R.'S) ARE DFL#2, WITH AN ALLOWABLE RAFTER SPAN AS FOLLOWS:
  - a. 2X8'S AT 24" O.C. - 10'-0"
  - b. 2X8'S AT 16" O.C. - 12'-0"
  - c. 2X8'S AT 24" O.C. - 12'-4"
  - d. 2X8'S AT 16" O.C. - 15'-1"
20. BRACE THE COMPRESSION FLANGE OF ALL BEAMS UNLESS NOTED OTHERWISE.
21. ALL BEAMS OR HEADERS THAT BEAR ON WOOD FRAMING SHALL BE SUPPORTED BY ANOTHER BEAM OR HEADER OR A BUILT-UP STUD COLUMN THE FULL WIDTH OF THE BEAM CONTINUOUS TO THE FOUNDATION OR OTHER STRUCTURAL FRAMING MEMBER, U.N.O.
22. ALL LIGHT GAGE METAL FRAMING ACCESSORIES NOTED SHALL BE AS MANUFACTURED BY "SIMPSON STRONG TIE" OR APPROVED EQUAL, ATTACH FRAMING ACCESSORIES TO WOOD FRAMING IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
23. PROVIDE HEADERS AS SHOWN ON PLAN, FOR HEADERS NOT MARKED REFERENCE TYPICAL BEARING WALL HEADER SCHEDULE.
24. FLOOR SHEATHING SHALL BE 3/4" TONGUE & GROOVE WOOD STRUCTURAL PANEL. GLUE & NAIL TO FLOOR JOISTS WITH 8D NAILS AT 6" O.C. AT ALL PANEL EDGES AND AT 12" O.C. AT INTERMEDIATE SUPPORTS.
25. ALL EXTERIOR WOOD WALL FRAMING SHALL BE 2X6 DOUG-FIR NO. 2 AT 16"OC. UNO.
26. ALL INTERIOR BEARING WALL FRAMING SHALL BE 2X4 DOUG-FIR NO. 2 AT 16"OC. UNO. WOOD TRUSSES AND THEIR CONNECTIONS SHALL BE DESIGNED BY THE TRUSS MANUFACTURER FOR THE LOADS STIPULATED ON THE DRAWINGS. SHOP DRAWINGS AND CALCULATIONS WITH AN ENGINEER'S SEAL FOR THE STATE OF MISSOURI SHALL BE SUBMITTED FOR REVIEW PRIOR TO FABRICATION. CONNECTION PLATES SHALL MEET THE REQUIREMENTS OF THE GOVERNING BUILDING CODE.
27. TEMPORARY STABILITY OF WOOD TRUSSES DURING ERECTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR IN CONJUNCTION WITH ALL RECOMMENDATIONS OF THE MANUFACTURER.
28. WOOD TRUSSES SHALL NOT BE FIELD CUT.

ENERGY REQUIREMENTS:

1. THE BUILDING THERMAL ENVELOPE SHALL BE SEALED WITH AN AIR BARRIER PER 2018 IRC SEC N102.
2. LIGHTING FIXTURES PENETRATING THE THERMAL ENVELOPE SHALL BE IC-RATED, LEAKAGE RATED AND SEALED TO THE GYPSUM WALLBOARD AS REQUIRED PER N102.
3. PROGRAMMABLE THERMOSTATS SHALL BE INSTALLED AS REQUIRED PER N103.1.1.
4. AIR HANDLERS SHALL BE RATED FOR MAXIMUM 2% AIR LEAKAGE RATE PER N103.2.2.1.
5. BUILDING CAVITIES USED AS RETURN AIR PLENUMS SHALL BE SEALED TO PREVENT LEAKAGE ACROSS THE THERMAL ENVELOPE AS REQUIRED PER N103.
6. BUILDING CAVITIES IN A THERMAL ENVELOPE WALL SHALL NOT BE USED AS RETURN AIR PLENUMS UNLESS THE REQUIRED INSULATION BARRIER IS MAINTAINED PER M1601.1.1.
7. HOT WATER PIPES SHALL BE INSULATED AS REQUIRED PER N103.4.1.
8. ALL EXHAUST FANS SHALL TERMINATE TO THE BUILDING EXTERIOR AS REQUIRED PER M1505.2.
9. MAKEUP AIR SYSTEMS SHALL BE INSTALLED FOR KITCHEN EXHAUST HOODS THAT EXCEED 400 CFM AS REQUIRED PER M1503.6.
10. AN AIR HANDLING SYSTEM SHALL NOT SERVE BOTH THE LIVING SPACE AND THE GARAGE PER M1601.6.
11. MINIMUM MECHANICAL EFFICIENCY RATING FOR AC EQUIPMENT IS 13 SEER AS REQUIRED PER IRC.
12. MINIMUM MECHANICAL EFFICIENCY RATING FOR FORCED AIR FURNACE IS 78% AS REQUIRED PER IRC.
13. CONTRACTOR SHALL PROVIDE COMPLIANCE REPORT PER N105.4.3 TO THE BUILDING OFFICIAL.

ABBREVIATIONS LEGEND

AB	ANCHOR BOLT	MECH	MECHANICAL
ACI	AMERICAN CONCRETE INSTITUTE	MFR	MANUFACTURER
AFF	ABOVE FINISH FLOOR	MIN	MINIMUM
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION	MISC	MISCELLANEOUS
AISI	AMERICAN IRON AND STEEL INSTITUTE	MTL	METAL
ARCH	ARCHITECTURAL	NO	NUMBER
ASTM	AMERICAN SOCIETY FOR TESTING AND	NS	NEAR SIDE
AWS	MATERIALS	NTS	NOT TO SCALE
BFF	AMERICAN WELDING SOCIETY	OC	ON CENTER
BFS	BELOW FINISH FLOOR	OH	OPPOSITE HAND
BO	BOTTOM OF FOOTING STEP	PAF	POWDER ACTUATED
BOS	BOTTOM OF	PCF	FASTENERS
BRG	BOTTOM OF STEEL	PL	POUNDS PER CUBIC FEET
BWP	BEARING	PLF	PLATE
CIP	BRACED WALL PANEL	PSF	POUNDS PER LINEAR FOOT
CL	CAST-IN-PLACE CONCRETE	PSI	POUNDS PER SQUARE FOOT
CJ	CONTROL JOINT (WALL)	QTY	POUNDS PER SQUARE INCH
CLR	CENTER LINE	REF	QUANTITY
COL	CLEAR	REIN	REFERENCE
CONC	COLUMN	REQD	REINFORCING
CONST	CONCRETE	REV	REQUIRED
CONT	CONSTRUCTION	RO	REVERSE
DIA	CONTINUOUS	SIM	ROUGH OPENING
EIFS	DIAMETER	T&B	SIMILAR
EL	EXTERIOR INSULATION AND FINISH SYSTEM	TFS	TOP AND BOTTOM
ELEV	ELEVATION	THK	TOP OF FOOTING STEP
EQ	ELECTRICAL	TO	THICK
EW	EQUAL	TOC	TOP OF
FDN	EACH WAY	TOF	TOP OF CONCRETE
FF	FOUNDATION	TOP	TOP OF FOOTING
FS	FINISH FLOOR	TOS	TOP OF PAVING
FTG	FAR SIDE	TRANS	TOP OF STEEL
GA	FOOTING	TYP	TRANSVERSE
GC	GAGE	UNO	TYPICAL
GYP BD	GENERAL CONTRACTOR	VERT	UNLESS NOTED OTHERWISE
HORIZ	GYPSUM BOARD	W	VERTICAL
HSA	HORIZONTAL	WBM	WIDTH
INFO	HEADED STUD ANCHOR	WP	WALL BRACE METHOD
JST	INFORMATION	WS	WORK POINT
JT	JOIST	WWF	WALL STEP
KSI	JOINT		WELDED WIRE FABRIC
LBS	KIPS PER SQUARE INCH		
LONG	POUNDS		
MAX	LONGITUDINAL		
	MAXIMUM		

SYMBOLS LEGEND

	ELEVATION DESCRIPTION		ELEVATION DESIGNATION N		REVISION DESIGNATION
	CUT SYMBOL		PLAN NOTE SYMBOL		SLAB JOINT DESIGNATION
	TYPE NO/SHEET		SECTION CUT		SPOT ELEVATION
	TYPE NO/SHEET		ELEVATION DETAIL		CONCRETE WALL
	TYPE NO/SHEET		BLOWUP DETAIL		WOOD NON-LOAD BEARING STUD WALL
	WOOD STRUCTURAL PANEL		BRACED WALL PANEL		BRACED WALL LINE
	ALTERNATE BRACED WALL PANEL		WOOD STUD BEARING WALL		
	PORTAL FRAME WITH HOLD-DOWNS				
	PORTAL FRAME AT GARAGE				
	SMOKE DETECTOR				

INSULATION AND FENESTRATION REQUIREMENTS - IRC TABLE N102.1.2

THESE VALUES ARE BASED ON CLIMATE ZONE 4 PER IRC FIGURE N1101.7 OR TABLE N1101.7. REFERENCE IRC FOR DIFFERENT CLIMATE ZONE VALUES

COMPONENT	VALUE
FENESTRATION	U ≤ TO 0.32 (b)
SKYLIGHT	U ≤ TO 0.55 (b)
GLAZED FENESTRATION SHGC	U ≤ TO 0.40 (b)(e)
CEILING	R-49
CEILING WITH ATTIC SPACES (OVER 100% OF THE CEILING)	R-38
CEILING- VAULTED (600 SQ.FT. OR 20% OF THE TOTAL INSULATED CEILING AREA, WHICHEVER IS LESS)	R-30
WOOD FRAME WALL	R-20 OR R-13 + 5 (h)
MASS WALL	R-8 / R-13 (i)
FLOOR	R-19
BASEMENT WALL	R-10 / R-13 (c)
SLAB (R VALUE/DEPTH)	R-10 / 2 FT (d)
CRAWLSPACE WALL W/ FLOOR INSULATION	R-10 / R-13 (c)
DUCTS OUTSIDE OF THE	R-8
CONDITIONED SPACE	IN FLOOR & CEILING ASSEMBLY R-6

- a. R VALUES ARE MINIMUMS. U - FACTORS AND SHGC ARE MAXIMUMS. WHEN INSULATION IS INSTALLED IN A CAVITY WHICH IS LESS THAN THE LABEL OR DESIGN THICKNESS OF THE INSULATION, THE INSTALLED R-VALUE OF THE INSULATION SHALL NOT BE LESS THAN THE R-VALUE SPECIFIED IN THE TABLE.
- b. THE FENESTRATION U - FACTOR EXCLUDES SKYLIGHTS. THE SHGC APPLIES TO ALL GLAZED FENESTRATION.
- c. "1013" MEANS R-10 CONTINUOUS INSULATION ON THE INTERIOR OR EXTERIOR OF THE HOME OR R-13 CAVITY INSULATION ON THE INTERIOR OF THE BASEMENT WALL.
- d. R - 5 SHALL BE PROVIDED UNDER THE FULL SLAB AREA OF A HEATED SLAB IN ADDITION TO THE REQUIRED SLAB EDGE INSULATION R-VALUE FOR SLABS, AS INDICATED IN THE TABLE. THE SLAB EDGE INSULATION FOR HEATED SLABS SHALL NOT BE REQUIRED TO EXTEND BELOW THE SLAB.
- e. THERE ARE NO SHGC REQUIREMENTS IN THE MARINE ZONE.
- f. BASEMENT WALL INSULATION IS NOT REQUIRED IN WARM-HUMID LOCATIONS AS DEFINED BY FIGURE N1101.10 AND TABLE N101.10.
- g. ALTERNATIVELY, INSULATION SUFFICIENT TO FILL THE FRAMING CAVITY PROVIDING NOT LESS THAN AN R-VALUE OF R-19.
- h. FIRST VALUE IS CAVITY INSULATION, SECOND VALUE IS CONTINUOUS INSULATION. THEREFORE, AS AN EXAMPLE, "13+5" MEANS R-13 CAVITY INSULATION PLUS R-5 CONTINUOUS INSULATION.
- i. MASS WALLS SHALL BE IN ACCORDANCE WITH SECTION N1102.2.5. THE SECOND R-VALUE APPLIES WHEN MORE THAN HALF OF THE INSULATION IS ON THE INTERIOR OF THE MASS WALL.

Consulting Engineers, L.L.C.  
311 East 11th Avenue  
North Kansas City, MO 64116  
Phone: (816) 442-3232  
Fax: (816) 421-1866  
www.nortonschmidt.com

**Norton & Schmidt**

STATE OF MISSOURI  
BRANDON SCHWABAUER  
NUMBER  
PE-2018003020  
1/11/2022  
PROFESSIONAL ENGINEER

N&S JOB NUMBER: 2021-2720  
© 2020 Norton & Schmidt Consulting Engineers

PROJECT INFORMATION

THE LEXINGTON II - WALKOUT

LOT 138

4728 JAMESTOWN DRIVE

LEE'S SUMMIT, MO 64064


ISSUES & REVISIONS		
#	DATE	DESCRIPTION
1	10/20/2021	Permit

DRAWN BY: MLR  
CHECKED BY: BSS  
ISSUED FOR:


SHEET TITLE  
GENERAL NOTES

SHEET NUMBER  
S500









PROJECT INFORMATION  
THE LEXINGTON II - WALKOUT  
LOT 138  
4728 JAMESTOWN DRIVE  
LEE'S SUMMIT, MO 64064

DRAWN BY: MLR  
CHECKED BY: BSS  
ISSUED FOR:

[illegible]









TABLE R802.5.1(9) RAFTER/CEILING JOIST HEEL JOINT CONNECTIONS (a,b,c,d,e,f,g)														
RAFTER SLOPE	RAFTER SPACING	GROUND SNOW LOAD (PSF)												
		30				50				70				
		ROOF SPAN (FEET)												
		12	20	28	36	12	20	28	36	12	20	28	36	
		REQUIRED NUMBER OF 16d COMMON NAILS(a,b) PER HEEL JOINT SPLICES (c,d,e,f)												
3:12	12	4	6	8	11	5	8	12	15	6	11	15	20	
	16	5	8	11	14	6	10	15	20	8	14	20	26	
	24	7	11	16	21	9	16	23	30	12	21	30	39	
4:12	12	3	5	6	8	4	6	9	11	5	8	12	15	
	16	4	6	8	11	5	8	12	15	6	11	15	20	
	24	5	9	12	16	7	12	17	22	9	16	23	29	
5:12	12	3	4	5	7	3	5	7	9	4	7	9	12	
	16	3	5	7	9	4	7	9	12	5	9	12	16	
	24	4	7	10	13	6	10	14	18	7	13	18	23	
7:12	12	3	3	4	5	3	4	5	7	3	5	7	9	
	16	3	4	5	6	3	5	7	9	4	6	9	11	
	24	3	5	7	9	4	7	10	13	5	9	13	17	
9:12	12	3	3	3	4	3	3	4	5	3	4	5	7	
	16	3	3	4	5	3	4	5	7	3	5	7	9	
	24	3	4	6	7	3	6	8	10	4	7	10	13	
12:12	12	3	3	3	3	3	3	3	4	3	3	4	5	
	16	3	3	3	4	3	3	4	5	3	4	5	7	
	24	3	3	4	6	3	4	6	8	3	6	8	10	

- a. 40d BOX NAILS SHALL BE PERMITTED TO BE SUBSTITUTED FOR 16d COMMON NAILS.  
b. NAILING REQUIREMENTS SHALL BE PERMITTED TO BE REDUCED 25% IF NAILS ARE CLINCHED.  
c. HEEL JOINT CONNECTIONS ARE NOT REQUIRED WHEN THE RIDGE IS SUPPORTED BY A LOAD-BEARING WALL, HEADER, OR RIDGE BEAM.  
d. WHEN INTERMEDIATE SUPPORT OF THE RAFTER IS PROVIDED BY VERTICAL STRUTS OR PURLINS TO A LOAD-BEARING WALL, THE TABULATED HEEL JOINT CONNECTION REQUIREMENTS SHALL BE PERMITTED TO BE REDUCED PROPORTIONALLY TO THE REDUCTION IN SPAN.  
e. EQUIVALENT NAILING PATTERNS ARE REQUIRED FOR CEILING JOIST TO CEILING JOIST LAP SPLICES.  
f. WHEN RAFTER TIES ARE SUBSTITUTED FOR CEILING JOISTS, THE HEEL JOINT CONNECTION REQUIREMENT SHALL BE TAKEN AS THE TABULATED HEEL JOINT CONNECTION REQUIREMENT FOR TWO-THIRDS OF THE ACTUAL RAFTER-SLOPE. TABULATED HEEL JOINT CONNECTION REQUIREMENTS ASSUME THAT CEILING JOISTS OR RAFTER TIES ARE LOCATED AT THE BOTTOM OF THE ATTIC SPACE. WHEN CEILING JOISTS OR RAFTER TIES ARE LOCATED HIGHER IN THE ATTIC, HEEL JOINT CONNECTION REQUIREMENTS SHALL BE INCREASED BY THE FOLLOWING FACTORS:

Hc/Hr	HEEL JOINT CONNECTION ADJUSTMENT FACTOR
1/3	1.5
1/4	1.33
1/5	1.25
1/6	1.2
1/10 OR LESS	1.11

WHERE:  
Hc= HEIGHT OF CEILING JOISTS OR RAFTER TIES MEASURED VERTICALLY ABOVE THE TOP OF THE RAFTER SUPPORT WALLS.  
Hr=HEIGHT OF ROOF RIDGE MEASURED VERTICALLY ABOVE THE TOP OF THE RAFTER SUPPORT WALLS.


ROOF RAFTER SCHEDULE						
GRADE	MEMBER SIZE / SPACING	MAX SPAN CEILING JSTS AT TOP PLATE	MAX SPAN H <sub>c</sub> /H <sub>r</sub> 0.16	MAX SPAN H <sub>c</sub> /H <sub>r</sub> 0.20	MAX SPAN H <sub>c</sub> /H <sub>r</sub> 0.25	MAX SPAN H <sub>c</sub> /H <sub>r</sub> 0.33
#2 DF/L	2x6 / 16"oc	14'-1"	12'-8"	11'-8"	10'-8"	9'-5"
#2 DF/L	2x8 / 16"oc	18'-2"	16'-4"	15'-1"	13'-9"	12'-2"
#2 DF/L	2x10 / 16"oc	22'-3"	20'-0"	18'-5"	16'-10"	14'-10"
#2 DF/L	2x12 / 16"oc	25'-9"	23'-2"	21'-4"	19'-7"	17'-3"
SPANS ABOVE ARE FOR ROOF LIVE LOAD OF 20 PSF AND DEAD LOAD OF 10 PSF WITH CEILINGS ATTACHED TO RAFTERS. RE: TABLES R802.5.1(1) THROUGH R802.5.1(8) FOR ADDITIONAL RAFTER SPAN INFORMATION.						
THE ROOF FRAMING ON THIS HOME UTILIZES RAFTERS SPACED AT 16" ON CENTER IN EXPOSURE B WITH A ROOF SPAN LESS THAN 42' ON IN 90 MPH WIND ZONE. THEREFORE THE UPLIFT FORCE ON THE RAFTER IS LESS THAN 200 LBS. AND CAN BE CONNECTED PER TO THE WALL FRAMING PER TABLE 602.3(1) (ON SHEET 6.0).						



REQUIREMENTS

RETURN PANEL:  
24\"/>

FASTENING SCHEDULE				IRC 2018 TABLE R602.3(1)				ITEM		DESCRIPTION OF BUILDING ELEMENTS		NUMBER AND TYPE OF FASTENER (a)(b)(c)		SPACING AND LOCATION	
ITEM	DESCRIPTION OF BUILDING ELEMENTS		NUMBER AND TYPE OF FASTENER (a)(b)(c)		SPACING AND LOCATION										
Roof						Floor									
1	Blocking between ceiling joists or rafters to top plate	4-8d box (2-1/2" × 0.113"); or 3-8d common (2-1/2" × 0.131"); or 3-10d box (3" × 0.128"); or 3-3" × 0.131" nails		Toe nail		21	Joist to sill, top plate or girder	4-8d box (2-1/2" × 0.113"); or 3-8d common (2-1/2" × 0.131"); or 3-10d box (3" × 0.128"); or 3-3" × 0.131" nails		Toe nail					
		4-8d box (2-1/2" × 0.113"); or 3-8d common (2-1/2" × 0.131"); or 3-10d box (3" × 0.128"); or 3-3" × 0.131" nails		Per joist, toe nail		22	Rim joist, band joist or blocking to sill or top plate (roof applications also)	8d box (2-1/2" × 0.113")		4" o.c. toe nail					
2	Ceiling joists to top plate	4-8d box (2-1/2" × 0.113"); or 3-8d common (2-1/2" × 0.131"); or 3-10d box (3" × 0.128"); or 3-3" × 0.131" nails		Per joist, toe nail		23	1" × 6" subfloor or less to each joist	3-8d box (2-1/2" × 0.113"); or 2-8d common (2-1/2" × 0.131"); or 3-10d box (3" × 0.128"); or 2 staples, 1" crown, 16 ga., 1-3/4" long		Face nail					
3	Ceiling joist not attached to parallel rafter, laps over partitions (see Section R802.5.2 and Table R802.5.2)	4-10d box (3" × 0.128"); or 3-16d common (3-1/2" × 0.162"); or 4-3" × 0.131" nails		Face nail		24	2" subfloor to joist or girder	3-16d box (3-1/2" × 0.135"); or 2-16d common (3-1/2" × 0.162")		Blind and face nail					
4	Ceiling joist attached to parallel rafter (heel joint) (see Section R802.5.2 and Table R802.5.2)	Table R802.5.2		Face nail		25	2" planks (plank & beam—floor & roof)	3-16d box (3-1/2" × 0.135"); or 2-16d common (3-1/2" × 0.162")		At each bearing, face nail					
5	Collar tie to rafter, face nail or 11/4" × 20 ga. ridge strap to rafter	4-10d box (3" × 0.128"); or 3-10d common (3" × 0.148"); or 4-3" × 0.131" nails		Face nail each rafter		26	Band or rim joist to joist	3-16d common (3-1/2" × 0.162") 4-10 box (3" × 0.128"), or 4-3" × 0.131" nails; or 4-3" × 14 ga. staples, 7/16" crown		End nail					
6	Rafter or roof truss to plate	3-16d box (3-1/2" × 0.135"); or 3-10d common nails (3" × 0.148"); or 4-10d box (3" × 0.128"); or 4-3" × 0.131" nails		2 toe nails on one side and 1 toe nail on opposite side of each rafter or truss(i)		27	Built-up girders and beams, 2-inch lumber layers	20d common (4" × 0.192"); or 10d box (3" × 0.128"); or 3" × 0.131" nails		Nail each layer as follows: 32" o.c. at top and bottom and staggered.					
		4-16d (3-1/2" × 0.135"); or 3-10d common (3" × 0.148"); or 4-10d box (3" × 0.128"); or 4-3" × 0.131" nails		Toe nail				24" o.c. face nail at top and bottom staggered on opposite sides							
7	Roof rafters to ridge, valley or hip rafters or roof rafter to minimum 2" ridge beam	3-16d box (3-1/2" × 0.135"); or 2-16d common (3-1/2" × 0.162"); or 3-10d box (3" × 0.128"); or 3-3" × 0.131" nails		End nail				And: 2-20d common (4" × 0.192"); or 3-10d box (3" × 0.128"); or 3-3" × 0.131" nails		Face nail at ends and at each splice					
		16d common (3-1/2" × 0.162") 10d box (3" × 0.128"); or 3" × 0.131" nails		24" o.c. face nail											
8	Stud to stud (not at braced wall panels)	16d common (3-1/2" × 0.162") 10d box (3" × 0.128"); or 3" × 0.131" nails		24" o.c. face nail		28	Ledger strip supporting joists or rafters	4-16d box (3-1/2" × 0.135"); or 3-16d common (3-1/2" × 0.162"); or 4-10d box (3" × 0.128"); or 4-3" × 0.131" nails		At each joist or rafter, face nail					
9	Stud to stud and abutting studs at intersecting wall corners (at braced wall panels)	16d box (3-1/2" × 0.135"); or 3" × 0.131" nails		12" o.c. face nail		29	Bridging or blocking to joist	2-10d box (3" × 0.128"); or 2-8d common (2-1/2" × 0.131"); or 2-3" × 0.131" nails		Each end, toe nail					
10	Built-up header (2" to 2" header with 1/2" spacer)	16d common (3-1/2" × 0.162") 16d box (3-1/2" × 0.135")		16" o.c. edge face nail 12" o.c. each edge face nail		ITEM DESCRIPTION OF BUILDING ELEMENTS		NUMBER AND TYPE OF FASTENER (a)(b)(c)		SPACING OF FASTENERS Edges (inches)(h) Intermediate supports(c)(e) (inches)					
11	Continuous header to stud	5-8d box (2-1/2" × 0.113"); or 4-8d common (2-1/2" × 0.131"); or 4-10d box (3" × 0.128")		Toe nail		Wood structural panels, subfloor, roof and interior wall sheathing to framing and particleboard wall sheathing to framing [see Table R602.3(3) for wood structural panel exterior wall sheathing to wall framing]									
12	Top plate to top plate	16d common (3-1/2" × 0.162") 10d box (3" × 0.128"); or 3" × 0.131" nails		16" o.c. face nail 12" o.c. face nail		30	3/8" – 1/2"	6d common (2" × 0.113") nail (subfloor, wall)(i) 8d common (2-1/2" × 0.131") nail (roof); or RRSR-01 (2-3/8" × 0.113") nail (roof)(j)		6	12(f)				
13	Double top plate splice	8-16d common (3-1/2" × 0.162"); or 12-16d box (3-1/2" × 0.135"); or 12-10d box (3" × 0.128"); or 12-3" × 0.131" nails		Face nail on each side of end joint (minimum 24" lap splice length each side of end joint)		31	19/32" – 1"	8d common nail (21/2" × 0.131"); or RRSR-01; (2-3/8" × 0.113") nail (roof)(j)		6	12(f)				
14	Bottom plate to joist, rim joist, band joist or blocking (not at braced wall panels)	16d common (3-1/2" × 0.162") 16d box (3-1/2" × 0.135"); or 3" × 0.131" nails		16" o.c. face nail 12" o.c. face nail		32	1-1/8" – 1-1/4"	10d common (3" × 0.148") nail; or 8d (21/2" × 0.131") deformed nail		6	12				
15	Bottom plate to joist, rim joist, band joist or blocking (at braced wall panel)	3-16d box (3-1/2" × 0.135"); or 2-16d common (3-1/2" × 0.162"); or 4-3" × 0.131" nails		3 each 16" o.c. face nail 2 each 16" o.c. face nail 4 each 16" o.c. face nail		Other wall sheathing(g)									
16	Top or bottom plate to stud	4-8d box (2-1/2" × 0.113"); or 3-16d box (3-1/2" × 0.135"); or 4-8d common (2-1/2" × 0.131"); or 4-10d box (3" × 0.128"); or 4-3" × 0.131" nails		Toe nail		33	1/2" structural cellulose fiberboard sheathing	1-1/2" galvanized roofing nail, 7/16" head diameter, or 1-1/2" long 16 ga. staple with 7/16" or 1" crown		3	6				
		3-16d box (3-1/2" × 0.135"); or 2-16d common (3-1/2" × 0.162"); or 3-10d box (3" × 0.128"); or 3-3" × 0.131" nails		End nail		34	25/32" structural cellulose fiberboard sheathing	1-3/4" galvanized roofing nail, 7/16" head diameter, or 1-1/2" long 16 ga. staple with 7/16" or 1" crown		3	6				
17	Top plates, laps at corners and intersections	3-10d box (3" × 0.128"); or 2-16d common (3-1/2" × 0.162"); or 3-3" × 0.131" nails		Face nail		35	1/2" gypsum sheathing(d)	1-1/2" galvanized roofing nail; staple galvanized, 1-1/2" long; 1-1/4" screws, Type W or S		7	7				
		3-8d box (2-1/2" × 0.113"); or 2-8d common (2-1/2" × 0.131"); or 2-10d box (3" × 0.128"); or 2 staples 1-3/4"		Face nail		36	5/8" gypsum sheathing(d)	1-3/4" galvanized roofing nail; staple galvanized, 1-5/8" long; 1-5/8" screws, Type W or S		7	7				
18	1" brace to each stud and plate	3-8d box (2-1/2" × 0.113"); or 2-8d common (2-1/2" × 0.131"); or 2-10d box (3" × 0.128"); or 2 staples 1-3/4"		Face nail		Wood structural panels, combination subfloor underlayment to framing									
19	1" × 6" sheathing to each bearing	3-8d box (2-1/2" × 0.113"); or 2-8d common (2-1/2" × 0.131"); or 2-10d box (3" × 0.128"); or 2 staples, 1" crown, 16 ga., 1-3/4" long		Face nail		37	3/4" and less	6d deformed (2" × 0.120") nail; or 8d common (2-1/2" × 0.131") nail		6	12				
		3-8d box (2-1/2" × 0.113"); or 2-8d common (2-1/2" × 0.131"); or 2-10d box (3" × 0.128"); or 2 staples 1-3/4"		Face nail		38	7/8" – 1"	8d common (2-1/2" × 0.131") nail; or 8d deformed (2-1/2" × 0.120") nail		6	12				
20	1" × 8" and wider sheathing to each bearing	3-8d box (2-1/2" × 0.113"); or 3-8d common (2-1/2" × 0.131"); or 3-10d box (3" × 0.128"); or 3 staples, 1" crown, 16 ga., 1-3/4" long		Face nail		39	1-1/8" – 1-1/4"	10d common (3" × 0.148") nail; or 8d deformed (2-1/2" × 0.120") nail		6	12				
		3-8d box (2-1/2" × 0.113"); or 3-8d common (2-1/2" × 0.131"); or 3-10d box (3" × 0.128"); or 4 staples, 1" crown, 16 ga., 1-3/4" long		Face nail		a. Nails are smooth-common, box or deformed shanks except where otherwise stated. Nails used for framing and sheathing connections shall have minimum average bending yield strengths as shown: 80 ksi for shank diameter of 0.192 inch (20d common nail), 90 ksi for shank diameters larger than 0.142 inch but not larger than 0.177 inch, and 100 ksi for shank diameters of 0.142 inch or less. b. Staples are 16 gage wire and have a minimum 7/16-inch on diameter crown width. c. Nails shall be spaced at not more than 6 inches on center at all supports where spans are 48 inches or greater. d. Four-foot by 8-foot or 4-foot by 9-foot panels shall be applied vertically. e. Spacing of fasteners not included in this table shall be based on Table R602.3(2). f. For wood structural panel roof sheathing attached to gable end roof framing and to intermediate supports within 48 inches of roof edges and ridges, nails shall be spaced at 6 inches on center where the ultimate design wind speed is less than 130 mph and shall be spaced 4 inches on center where the ultimate design wind speed is 130 mph or greater but less than 140 mph. g. Gypsum sheathing shall conform to ASTM C1396 and shall be installed in accordance with GA 253. Fiberboard sheathing shall conform to ASTM C208. h. Spacing of fasteners on floor sheathing panel edges applies to panel edges supported by framing members and required blocking and at floor perimeters only. Spacing of fasteners on roof sheathing panel edges applies to panel edges supported by framing members and required blocking. Blocking of roof or floor sheathing panel edges perpendicular to the framing members need not be provided except as required by other provisions of this code. Floor perimeter shall be supported by framing members or solid blocking. i. Where a rafter is fastened to an adjacent parallel ceiling joist in accordance with this schedule, provide two toe nails on one side of the rafter and toe nails from the ceiling joist to top plate in accordance with this schedule. The toe nail on the opposite side of the rafter shall not be required. j. RRSR-01 is a Roof Sheathing Ring Shank nail meeting the specifications in ASTM F1667.									
(continued)															



3 TRAY CEILING  
SCALE: 3/4\"/>

Consulting Engineers, L.L.C.  
311 East 11th Avenue  
North Kansas City, MO 64116  
Phone: (816) 442-4232  
Fax: (816) 921-1866  
www.nortonschmidt.com

STATE OF MISSOURI  
BRANDON SCHWABAUER  
NUMBER  
PE-2015003020  
1/11/2022  
PROFESSIONAL ENGINEER

Norton & Schmidt

NAS JOB NUMBER: 2021-2720  
© 2020 Norton & Schmidt Consulting Engineers

PROJECT INFORMATION

THE LEXINGTON II - WALKOUT

LOT 138

4728 JAMESTOWN DRIVE

LEE'S SUMMIT, MO 64064

ISSUES & REVISIONS		
#	DATE	DESCRIPTION
1	10/20/2021	Permit

DRAWN BY: MLR  
CHECKED BY: BSS  
ISSUED FOR:

SHEET TITLE


DETAILS

SHEET NUMBER



S504

RELEASE FOR CONSTRUCTION  
AS NOTED FOR PLAN REVIEW  
02/03/2022  
LEE'S SUMMIT, MISSOURI





NOTE: ALL SHADED AREAS SHALL BE SHEATHED WITH 15/32" WOOD STRUCTURAL PANEL AND FASTENED WITH 10d COMMON NAILS AT 3" O.C., EDGES AND 6" O.C. IN THE FIELD. BLOCK ALL PANEL EDGES



**Norton & Schmidt**  
Consulting Engineers, L.L.C.  
311 East 11th Avenue  
North Kansas City, MO  
64116  
Phone: (816) 442-4232  
Fax: (816) 421-1866  
www.nortonschmidt.com

STATE OF MISSOURI  
BRANDON  
SCHWABAUER  
NUMBER  
PE-2015003020  
1/11/2022  
PROFESSIONAL ENGINEER

N&S JOB NUMBER: 2021-2720  
© 2020 Norton & Schmidt Consulting Engineers

**PROJECT INFORMATION**

THE LEXINGTON II - WALKOUT  
LOT 138  
4728 JAMESTOWN DRIVE  
LEE'S SUMMIT, MO 64064

ISSUES & REVISIONS		
#	DATE	DESCRIPTION
1	10/20/2021	Permit

DRAWN BY: MLR  
CHECKED BY: BSS  
ISSUED FOR:

**SHEET TITLE**

DETAILS

**SHEET NUMBER**

S505

RELEASE FOR CONSTRUCTION  
AS NOTED FOR PLAN REVIEW  
- FINAL CHANGES -  
LEE'S SUMMIT, MISSOURI  
02/03/2022