

establish property lines for fences or other structures. House staked as shown on this plot plan. House dimensions may have been assumed and contractor must check house dimensions shown and compare to the final house plans. Contractor to verify all elevations at job site. Builder must make final decision as to cuts and foundation heights at the job site, any floor elevations shown are shown as a quide only. Sanitary sewer and lateral elevations cannot be verified at time of staking, and it may be necessary to verify sanitary sewer elevation and location (BY DIGGING UP THE SEWER LATERAL) prior to excavation for foundation. Underground utilities and un-platted easements may not be shown. This does not constitute a boundary survey and builder must check to make sure description shown is correct with the deed for the property. It is recommended that no work be done until building permits are obtained and plot plan has been verified by local building codes authorities to comply with all setback and other restrictions. = DRAINAGE PATTERN



 Decal building codes authorities to comply with all setback and other

 CONSTRUCTION ENGINEERING SERVICES, INC.

 16810-C East 40 Highway

 Independence, MO 64055

 (816)478-2323

 Ise@engineeringkc.com

 NUMBER

 Is-2114

 DATE:

 6/17/2022

 JOB NO:

 18416P