



HILLCREST BEAD & BOARD


FRONT EL. STUCCO, BOARD & BATT, AND STONE



3 SIDES LP PANEL SIDING







LEFT EL. 1/8 = 1-0



1/8 = 1-0

7-10-22 PLAN NO. 3882

SCALE

1/4" = 1-0


DATE

BUILD IN ACCORDANCE WITH 2018 INTERNATIONAL RESIDENTIAL CODE AND LOCAL CODES.

TRUMARK HOMES KYLE I LOT 152 HIGHLAND MEADOWS 2758 SW 12 ST LEE SUMMIT MO

SHEET NO.

1 OF 5



BUILD IN ACCORDANCE WITH 2018 INTERNATIONAL RESIDENTIAL CODE AND LOCAL CODES.

TRUMARK HOMES KYLE I LOT 152 HIGHLAND MEADOWS 2758 SW 12 ST LEE SUMMIT MO

SCALE 1/4" = 1-0

> DATE 7-10-22


PLAN NO.

3882

SHEET NO.

2 OF 5

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
Development Services
LEE'S SUMMIT, MISSOURI



BUILD IN ACCORDANCE WITH 2018 INTERNATIONAL RESIDENTIAL CODE AND LOCAL CODES.

TRUMARK HOMES KYLE I LOT 152 HIGHLAND MEADOW 2758 SW 12 ST LEE SUMMIT MO

SCALE 1/4" = 1-0

> DATE 7-10-22

PLAN NO.

3882


SHEET NO.

3 OF 5
RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
Development Services
LEE'S SUMMIT, MISSOURI


VAULT INSULATION DETAIL 2 X 10 VAULT RAFTER 1. DWELLING / GARAGE OPENINGS BETWEEN GARAGE AND SLEEPING PURPOSES SHALL NOT BE PERMITTED. OTHER OPENINGS SHALL BE 1" AIR SPACE WITH FOAM AIR EQUIPPED WITH SOLID WOOD OR STELL DOORS NOT LESS THAN 1-3/8" ENERGY CONSERVATION CODE CHUTES 2 X 2 NAILED TO BOTTOM OF THICK OR 20 MINUTE RATED DOORS, WITH SELF CLOSING DEVICES REQUIRED FOR GARAGE / DWELLING SEPERATION DOORS R302.5.1 THE FOLLOWING VALUES ARE NEEDED RAFTERS 12" O.C. WITH 12 D 2. WHOLE HOUSE MECHANICAL VENTILATION SYSTEM IS REQUIRED FOR R-15 IN WALLS ANY DWELLING IN COMPLIANCE WITH IRC M 1505 3. CARBON MONOXIDE DETECTORS REQUIRED IRC R 315 R-49 IN ATTICS R-38 HIGH DENSITY 4. STEEL COLUMNS SHALL BE MINIMUM SCHEDULE 40 R407.3 INSULATION R-30 REDUCTION FOR VAULTS IS ONLY FOR 500 SF 5. DECK SHALL BE BUILT PER TABLES 507.2, 507.2.1, 507.3, 507.6, INTERCONNECTED HARD WIRED SMOKE DETECTORS SHALL BE INSTALLED IN EACH 507.5.1(1)&(2), 507.5, AND 507.6 BEDROOM AND OUTSIDE OF EACH BEDROOM 6. STUDS SHALL BE CONTINUOUS BETWEEN FLOOR, CEILING AND OR R-19 IN FLOORS OVER UNCONDITIONED SPACES ROOF DIAPHRAGMS R602.3 ALL PLUMBING IF EXISITING SHALL BE CAPPED AND AIR TESTED PRIOR TO ROUGH-IN 7. ADDED REQUIREMENTS FOR WINDOW FALL PROTECTION R312.2 R-10 IN CRAWL SPACE WALLS INSPECTION FOR LEAK VERIFICATION 8. NEW PROVISIONS FOR ATTACHMENT OF RAFTERS, TRUSSES AND BASEMENT WALLS R-13 CAVITY OR R-10 CONTINOUS ROOF BEAMS R802.3.1. R802.11 9. INSULATION REQUIRED FOR ALL BASEMENT WALLS (INCLUDING SLABS SHALL BE R-10 FOR A DEPTH OF 2 FOOT UNFINISHED BASEMENTS) N1102.1 A WINDOW U FACTOR OF .35 OR BETTER 10. EXTERIOR WINDOWS/DOORS SHALL HAVE U-FACTOR 0.35 AND ICE & WATER SHEILD REQUIRED ON ALL GLAZING SHALL HAVE SOLAR HEIGHT GAIN FACTOR OF 0.40 N1102.1 DUCTWORK NEEDS TO HAVE AN R-8 VALUE 11. HOUSE LEAKAGE AND DUCT LEAKAGE PERFORMANCE STANDARDS EFFECTIVE JANUARY 1, 2014. A SAMPLE TESTING PROGRAM WILL BE ROOF IS DESIGNED FOR 25 P.S.F. SNOW LOAD MIN. IMPLEMENTED OCTOBER 1, 2012 KCBRC N1102.4.1.2 N1103.2.2 COMP. SHINGLES OVER 12. LIGHTING FIXTURES PENETRATING THE THERMAL ENVELOPE (E.G. RIDGE BOARDS AND HIPS ARE TO BE 2 CAN LIGHTS IN ATTIC) SHALL BE IC-RATED, LEAKAGE-RATED AND X MATERIAL, AND NOT LESS THAN SEALED TO THE GYPSUM WALLBOARD N1102.4.4 THE END CUT OF RAFTER RAFTERS AND CEILING 7/16" APA 2 X 6 DF NO. 2 JOISTS CONNECTIONS IN 13.PROGRAMMABLE THERMOSTAT REQUIRED N1103.1.1 AT 16" OC RATED ROOF ACCORDANCE IRC 802.3 SHEATHING 14. AIR HANDLERS SHALL BE RATED FOR MAXIMUM 2 % AIR LEAKAGE RATE N1103.2.2.1 PROVIDE RAFTER TIES PER SECTION 802.3 DRIP EDGE AND GUTER AND 802.3.1 WHEN UNABLE TO CONNECT RAFTERS TO CEILING JOISTS 1 X 8 FASCIA OVER 2 X 6 15. BUILDING CAVITIES USED AS RETURN AIR PLENUMS SHALL BE 2 X 6 DF NO. 2 SUBFASCIA SEALED TO PREVENT LEAKAGE ACROSS THE THERMAL ENVELOPE KCBRC AT 16" OC SOFFIT 1/2 GYP. BOARD 16. CERTAIN HOT WATER PIPES SHALL BE INSULATED N1103.4 WITH GARAGE SHALL HAVE 5/8 TYPE X **VENTS** 17. ALL EXHAUST FANS SHALL TERMINATE TO THE BUILDING EXTERIOR SHEET ROCK CEILING AND WALLS 7/16 APA RATED SIDING OVER 18. MAKEUP AIR SYSTEM REQUIRED FOR KITHCHEN EXHAUST HOODS 2 - 2 X 10 DF NO 2 WATER RESISTIVE HOUSE WRAP IN THAT EXCEED 400 CFM M1503.4 HEADERS TYP. U.N.O. WALLS OVER 10-2 TO 18-0 COMPLIANCE WITH SECTION 703.2 OF THE IRC 2 X 4 DF NO. 2 STUDS SHALL BE 2 X 6 DF 19. BUILDING CAVITIES IN A THERMAL ENVELOPE WALL (INCLUDING NO 2 @ 16" O.C. TYP. AT 16" OC THE WALL BETWEEN THE HOUSE AND GARAGE ) SHALL NOT BE USED AS 3/4" T & G SUB FLOOR GLUED AND NAILED 1/2 " ANCHOR BOLTS AT 5-0 OC MIN. , AND BE ALL STUDS GO FROM FLOOR TO 20. AN AIR HANDLING SYSTEM SHALL NOT SERVE BOTH THE LIVING LOCATED WITHIN 12" FROM THE ENDS OF EACH CEILING OR RAFTER DIAFRAM TYP. PLATE SECTION. SHALL EXTEND A MINIMUM OF SPACE AND THE GARAGE M1601.6 2 X 10 DF NO 2 @ 7" INTO CONCRETE 21. A CONCRETE- ENCASED GROUNDING ELECTRODE ( 'UFER' GROUND ) 2 X4 TREATED PLATE OVER REINFORCEMNT AT MIN. CONCRETE STRENGTH CONNECTION SHALL BE PROVIDED TO THE ELECTRICAL SERVICE E3608.1 CORNERS OF OPENINGS SILL SEALER 2,500 PSI BASEMENT FLOOR SLABS UNDISTURBED GRADE AND STEP DOWNS 3,000 PSI FOR FOOTINGS, FOUNDATION WALLS, AND OTHER VERTICAL 22. COMPLIANCE WITH THE REQUIRMENT AND SHOW CONNECTION AS **REQUIRE 1 # 4 BAR 48"** NEEDED FOR ROOF BEAM, TRUS, RAFTER, AND GIRDER CONNECTION FOR LONG AT 45 DEGREE 3,500 PSI FOR CARPORT AND GARAGE FLOOR SLABS ON UNDISTURBED GRADE, AND STRUCTURAL FLOOR SLABS DAMPPROOF WALLS BELOW GRADE UPLIFT PER IRC 802.11. ALL RAFTERS BE IN COMPLIANCE WITH IRC 502.11 WITHIN 6" OF THE EDGE AMENDED RAYMORE CODE SPRAY ON TAR WITHIN CODE R-406.1 FILL ALL VIODS & HONEYCOMB AREAS OF INSIDE CORNERS BEFORE DAMPPROOFING 4" CONCRETE SLAB WITH NO SPREAD FOOTING 7.5" CONCRETE WALL WITH NO 4 BARS HORT. EVERY 18" OF WALL HEIGHT WITH # 4 BAR WITHIN 6" OF TOP AND BOTTOM OF WALL, 4 BARS AT 2-0 OC EACH WAY, MIN 8" DEEP X 16" OVER 6 ML VAPOR BARRIOR WIDE WITH TWO NO USE LSTA24 RIDGE STRAPS OVER CRUSHED ROCK HORT. REBAR SHALL BE INSTALLED ON SOIL SIDE OF VERTICAL 4 REBAR ON ALL VAULTS AT RIDGE REINFORCEMENT OR COLLAR TIES GRADE 40 TYP. VERTICAL REBAR SHALL BE WITHIN 8" OF THE TOP OF THE WALL, AND POSITIONED 2" FROM THE INSIDE FACE OF WALL VERTICAL REBAR SPACING WALL HEIGHT IN FEET INTERIOR DRAIN TILE MIN. 1-1/2" 6-0 OR LESS #4 @ 24" O.C. MIN. DRAIN TO DAYLIGHT, OR SUMP RADON VENTING OF SLAB 8-0 # 4 @ 16" O.C. PUMP IN ACCORDANCE TO R-405 ALL CONCRETE EXPOSED TO 9-0 #4@12"O.C. WEATHER GARAGE SLABS FOOTINGS WALLS AND FLATWORK 10-0 # 4 @ 8" O.C 8 X 16 FOOTING WITH TWO NO 4 BARS HORIZONTAL 3" FROM THE 10-0 WALL 9.5" #4 @ 12" O.C. MUST HAVE 6% AIR ENTRAINMENT BOTTOM, ALL FOOTINGS TO 4" DRAIN TILE IN WITH MIN 6" TYP VAULT WITH STRAPS EXCEED MIN. FROST DEPTH OF 36' ASSUMED SOIL \ CRUSHED ROCK OVER PIPE, DRAIN TO PRESSURE DAYLIGHT, OR SUMP PUMP IN MIN. STAIR HEADROOM 6-8 PIER PADS ACCORDANCE TO R-405 ALL STAIRS TYP. U.N.O. 3-0 X 3-0 X 12" PEIR PADS  $\,$  MIN. STUDS OVER 10-0 SHALL HAVE MAX. RISE 7-3/4" TYPICAL WALL SECTION WITH # 4 REBAR, 6 EACH WAY BLOCKING ALONG WALL MAX MIN. RUN 10" OF 6-0 O.C. WINDOW EGRESS WINDOW SAFETY GLAZING PER 308 REQUIREMENTS SAFETY GLAZING REQUIRED ALONG WALKING SURFACES AND OVERHEAD GARAGE DOORS BEDROOM WINDOW EGRESS MINIMUM FOR A DOUBLE HUNG STAIRS LOCATED WITHIN 36 INCHES HORIZONTALLY OF THE STEPS. MUST MEET DASMA 115 MPH WINDOW IS 34 INCH CLEAR WIDTH MIN. AND 24 INCH CLEAR SAFETY GLAZING REQUIRED IF EXPOSED SINGLE PANEL IS IN OR IRC 2018 REQUIRMENTS HEIGHT MIN. WITH A CLEAR OPENABLE AREA OF 5.7 SQUARE FEET EXCESS OF 9 SQUARE FEET OR THE BOTTOM EDGE OF THE GLAZING LADDER IS LESS THAN 18 INCHES ABOVE THE FINISHED FLOOR. A CASEMENT OR SLIDER WINDOW MINIMUMS ARE 20 INCH CLEAR 3'-0" → WIDTH MINIMUM AND 41 INCH CLEAR HEIGHT MINIMUM. WITH A SAFETY GLAZING REQUIRD WHERE THE NEAREST EXPOSED EDGE OF MINIMUM 5.7 SQUARE FOOT OF OPENABLE AREA. EGRESS WINDOW WELL AS NEEDED THE GLAZING IS WITHIN 24 INCHES OF EITHER VERTICAL EDGE OF OPENING OF EGRESS WINDOW NOT MORE THAN 42" PER SECTION 308 MIN 3-0 X 3-0 THE DOOR IN A CLOSED POSITION AND WHERE THE BOTTOM FROM THE FLOOR WITHLADDER EXPOSED EDGE OF THE GLAZING IS LESS THAN 60 INCHES ABOVE A WALKING SURFACE, SAFETY OR TEMPERED GLAZING IS REQUIRED. WINDOWS ARE TO HAVE FALL


PROTECTION PER IRC 312.2

ALL POINT LOADS SHALL HAVE A MINIMUM OF 2 STUDS UNLESS NOTED OTHERWISE



EXPOSURE CATEGORY B 30-FOOT MEAN ROOF HEIGHT 10-FOOT WALL HEIGHT 2 BRACED WALL LINES DWB, WSP, SFB, PBS, PCP, HPS, BV-WSP, ABW, PFH PFC, CS-SFB 7.0 15.0 10.5 9.0 18.0 12.5 ≤ 115 13.5 29.0 20.0 17.0 34.5 10.0 18.5 20 13.0 17.0 35.0 20.0 21.0 43.0 50 25.0





4 mm, 1 foot = 304.8 mm.

FIGURE R602.10.6.2 METHOD PFH-PORTAL FRAME WITH HOLD-DOWNS

CONNECTION CRITERIA® METHODS, MATERIAL Spacing 3-8d (2<sup>1</sup>/<sub>2</sub>" long x 0.113" dia.) nails at 45° to 60° angles for maximum 16" Let-in-bracing  $2-8d (2^{1}/_{2}" long \times 0.113" dia.) nails$ Per stud  $2 - 1^3/4$  long staples stud spacing Exterior sheathing per Table R602.3(3) 6" edges 12" field 3/<sub>8</sub>" Interior sheathing per Table R602.3(1) or R602.3(2) structural panel (See Section R604 Varies by fastener 12" at intermediate supports 4" at braced wall panel end posts Wood structura See Figure R602.10.6.5 panels with stone 8d common  $(2^{1}/_{2}" \times 0.131)$  nails r masonry vened 1<sup>1</sup>/<sub>2</sub>" long × 0.12" dia. (for <sup>1</sup>/<sub>2</sub>" thick sheathing) 1<sup>3</sup>/<sub>4</sub>" long × 0.12" dia. (for <sup>25</sup>/<sub>32</sub>" thick sheathing) galvanized roofing nails sheathing Nails or screws per Table R602.3(1) for exterior locations

Nails or screws per Table R702.3.5 for interior locations For <sup>3</sup>/<sub>8</sub>", 6d common (2" long × 0.113" dia.) nails For <sup>1</sup>/<sub>2</sub>", 8d common 3/8" or 1/2" for maximum 16" 3" edges 6" field maximum 16 stud spacing  $(2^{1}/_{2}" \log \times 0.131" \text{ dia.})$  nails /<sub>2</sub>" long, 11 gage, <sup>7</sup>/<sub>16</sub>" dia. head nails or members maximum 16' <sup>1</sup>/<sub>8</sub>" long, 16 gage staples 0.092" dia., 0.225" dia. head nails with HPS length to accommodate 11/2" penetration into studs 4" edges 8" field //<sub>16</sub>" for maximum 16' Hardboard panel siding stud spacing See Section R602.10.6.1 See Section R602.10.6.1 3/8"

	MINIMUM LEN		MINI				
METHOD (See Table R602.10.4)		(inches)					CONTRIBUTING LENGTH (Inches)
		Wali Height					
		8 feet	9 feet	10 feet	11 feet	12 feet 58	Actual <sup>b</sup>
DWB, WSP, SFB, PBS, PCP, HPS, BV-WSP		48	48	48	53		Double sided = Actual
GB		48	48	48	53	58	Single sided = $0.5 \times Actus$
LIB		55	62	69	NP	NP	Actual <sup>6</sup>
ABW	SDC A, B and C, ultimate design wind speed < 140 mph	28	32	34	38	42	48
	SDC D <sub>0</sub> , D <sub>1</sub> and D <sub>2</sub> , ultimate design wind speed < 140 mph	32	32	34	NP	NP	
CS-G		24	27	30	33	36	Actual <sup>b</sup>
	Adjacent clear opening height (inches)						
	≤ 64	24	27	30	33	36	
	68	26	27	30	33	36	Actual <sup>b</sup>
	72	27	27	30	33	36	
CS-WSP, CS-SFB	76	30	29	30	33	36	
	80	32	30	30	33	36	
	84	35	32	32	33	36	
	88	38	35	33	33	36	
	92	43	37	35	35	36	
	96	48	41	38	36	36	
	100		44	40	38	38	
	104		49	43	40	39	
	108		54	46	43	41	
	112			50	45	43	
	116			55	48	45	
·	120		<u> </u>	60	52	48	
	124			<u> </u>	56	51 54	
	128				61	58	
	132				66	62	
	136	<u> </u>		<u> </u>	<del> </del>	66	
	140			<del>  -</del>		72	
	144		<u> </u>	rtal header	helaht	1 12	
METHOD (See Table R602,10.4)		8 fact	9 feet	10 feet	11 feet	12 feet	-
(See 1	Supporting roof only	16	16	16	Note c	Note c	40
PFH	Supporting one story and roo		24	24	Note c	Note c	48
	PFG	24	1 27	30	Note d	Note d	
CS-PF	SDC A, B and C	16	18	20	Note e	Note e	
	SDC D <sub>0</sub> , D <sub>1</sub> and D <sub>2</sub>	16	18	20	Note e	Note e	

For SI; 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 mile per hour = 0.447 m/s.

For St. 1 inch = 25.4 min, t foot = 50.45 min, t fine per near 1.00 min, the per near 1.00

BRACE WALL DETAILS WIND SPEED 115 MPH WIND EXPOSURE A SEISMIC DESIGN CAEGORY A TABLE R602.10.4—continued BRACING METHODS

		i i		CONNECTION CHITERIA			
M	ETHODS, MATERIAL	MINIMUM THICKNESS	FIGURE	Fastenero	Specing		
Methods	PFH Portal frame with hold-downs	³/g″		See Section R602.10.6.2	See Section R602.10.6.2		
Intermittent Bracing Methods	PFG Portal frame at garage	<sup>7</sup> / <sub>16</sub> "		See Section R602.10.6.3	See Section R602.10.6.3		
Continuous Sheathing Methods	CS-WSP Continuously sheathed wood structural panel	3/8"		Exterior sheathing per Table R602.3(3)	6" edges 12" field		
				Interior sheathing per Table R602.3(1) or R602.3(2)	Varies by fastener		
	CS-G <sup>b,c</sup> Continuously sheathed wood structural panel adjacent to garage openings	3/8"		See Method CS-WSP	See Method CS-WSP		
	CS-PF Continuously sheathed portal frame	7/16"		See Section R602.10.6.4	See Section R602.10.6.4		
	CS-SFB <sup>d</sup> Continuously sheathed structural fiberboard	1/2" or <sup>25</sup> / <sub>32</sub> " for maximum 16" stud spacing		$1\frac{1}{2}$ " long × 0.12" dia. (for $\frac{1}{2}$ " thick sheathing) $1\frac{3}{4}$ " long × 0.12" dia. (for $\frac{2}{3}$ " thick sheathing) galvanized roofing nails	3" edges 6" field		

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 degree = 0.0175 rad, 1 pound per square foot = 47.8 N/m², 1 mile per hour = 0.447 m/s.

a. Adhesive attachment of wall sheathing, including Method GB, shall not be permitted in Seismic Design Categories C, D<sub>0</sub>, D<sub>1</sub> and D<sub>2</sub>.

b. Applies to panels next to garage door opening where supporting gable end wall or roof load only. Shall only be used on one wall of the garage. In Seismic Design Categories D<sub>0</sub>, D<sub>1</sub> and D<sub>2</sub>, roof covering dead load shall not exceed 3 psf.

c. Garage openings adjacent to a Method CS-G panel shall be provided with a header in accordance with Table R602.7(1). A full-height clear opening shall not be permitted adjacent to a Method CS-G panel.

d. Method CS-SFR does not apply in Seismic Design Categories D<sub>0</sub>, D, and D<sub>0</sub>.

to be permitted adjacent to a metalloa use plate. At Method CS-SFB does not apply in Seismic Design Categories  $D_0$ ,  $D_1$  and  $D_2$ .

e. Method applies to detached one- and two-family dwellings in Seismic Design Categories  $D_0$  through  $D_2$  only.


EXTENT OF HEADER WITH SINGLE PORTAL FRAME (ONE BRACED WALL PANEL) 2'-18' FINISHED WIDTH OF OPENING FOR SINGLE OR DOUBLE PORTAL MIN. 3"x11½" NET HEADER STEEL HEADER PROHIBITED IF ½" SPACER IS USED, PLACE ON BACK-SIDE OF HEADER OVER CONCRETE OR MASONRY BLOCK FOUNDATION WOOD STRUCTURAL PANEL SHEATHING OV.

OVER RAISED WOOD FLOOR - FRAMING ANCHOR OPTION
(WHERE PORTAL SHEATHING DOES NOT LAP OVER BAND OR RIM JOIST) OVER RAISED WOOD FLOOR - OVERLAP OPTION (WHERE PORTAL SHEATHING LAPS OVER BAND OR RIM BOARD)

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm.

FRONT ELEVATION

FIGURE R602.10.6.4
METHOD CS-PF—CONTINUOUSLY SHEATHED PORTAL FRAME PANEL CONSTRUCTION



SECTION

ACCORDANCE WITH IONAL CODE BUILD IN ACCOI 2018 INTERNAT RESIDENTIAL C LOCAL CODES.

MEADOW AND HOWE TRUMARK HOME KYLE I LOT 152 HIGHLA 2758 SW 12 ST LEE SUMMIT MC

SCALE 1/4" = 1-0

> DATE 7-10-22

PLAN NO.

3882

SHEET NO.

5 OF 5 **RELEASE FOR** CONSTRUCTION **AS NOTED ON PLANS REVIEW Development Services** LEE'S SUMMIT, MISSOURI