



HILLCREST BEAD & BOARD

FRONT EL. STUCCO, BOARD & BATT, AND STONE



3 SIDES LP PANEL SIDING



RIGHT EL. 1/8 = 1-0



GENTIO PAUL

AMSWORTH

7-11-22

TRUMARK HOMES KYLE I LOT 202 HIGHLAND MEADOWS 1063 SW FIORD DR LEE SUMMIT MO

BUILD IN ACCORDANCE WITH 2018 INTERNATIONAL RESIDENTIAL CODE AND LOCAL CODES.

SCALE 1/4" = 1-0


DATE 7-10-22

PLAN NO.


3883

SHEET NO.

1 OF 5



LEFT EL. 1/8 = 1-0





BUILD IN ACCORDANCE WITH 2018 INTERNATIONAL RESIDENTIAL CODE AND LOCAL CODES.

TRUMARK HOMES KYLE I LOT 202 HIGHLAND MEADOW 1063 SW FIORD DR LEE SUMMIT MO

SCALE

1/4" = 1-0

DATE

7-10-22


PLAN NO.

3883

SHEET NO.

2 OF 5

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
07/14/2022



BUILD IN ACCORDANCE WITH 2018 INTERNATIONAL RESIDENTIAL CODE AND LOCAL CODES.

TRUMARK HOMES KYLE I LOT 202 HIGHLAND MEADOWS 1063 SW FIORD DR LEE SUMMIT MO

SCALE 1/4" = 1-0

> DATE 7-10-22


PLAN NO.

3883


SHEET NO.

3 OF 5

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
07/14/2022



ALL POINT LOADS SHALL HAVE A MINIMUM OF 2 STUDS UNLESS NOTED OTHERWISE



DE 00

 α

> AND α FIOI MIT 0

SCALE 1/4" = 1-0

> DATE 7-10-22


PLAN NO.


3883

SHEET NO.

4 OF 5

AS NOTED FOR PLAN REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOUR 07/14/2022 EXPOSURE CATEGORY B 30-FOOT MEAN ROOF HEIGHT 10-FOOT WALL HEIGHT 2 BRACED WALL LINES DWB, WSP, SFB, PBS, PCP, HPS, BV-WSP, ABW, PFH PFC, CS-SFB 7.0 50 15.0 10.5 9.0 18.0 12.5 ≤ 115 13.5 29.0 20.0 17.0 34.5 20 17.0 35.0 20.0 21.0 43.0 50 NP 25.0 29.0





4 mm, 1 foot = 304.8 mm.

FIGURE R602.10.6.2 METHOD PFH-PORTAL FRAME WITH HOLD-DOWNS

CONNECTION CRITERIA® METHODS, MATERIAL Spacing op and bottom plate 3-8d (2¹/₂" long x 0.113" dia.) nails at 45° to 60° angles fo maximum 16" Let-in-bracing $2-8d (2^{1}/_{2}" long \times 0.113" dia.) nails$ Per stud $2 - 1^3/4$ long staples stud spacing Exterior sheathing pe Table R602.3(3) 6" edges 12" field 3/₈" Interior sheathing per Table R602.3(1) or R602.3(2) structural panel (See Section R604 Varies by fastener 12" at intermediate supports 4" at braced wall panel end posts Wood structura See Figure R602.10.6.5 panels with stone 8d common $(2^{1}/_{2}^{"} \times 0.131)$ nails masonry vened 1¹/₂" long × 0.12" dia. (for ¹/₂" thick sheathing) 1³/₄" long × 0.12" dia. (for ²⁵/₃₂" thick sheathing) galvanized roofing nails sheathing Nails or screws per Table R602.3(1) for exterior locations

Nails or screws per Table R702.3.5 for interior locations For ³/₈", 6d common (2" long × 0.113" dia.) nails For ¹/₂", 8d common 3/8" or 1/2" for maximum 16" 3" edges 6" field stud spacing $(2^{1}/_{2}^{n}) \log \times 0.131^{n} \text{ dia.}) \text{ nails}$ /₂" long, 11 gage, ⁷/₁₆" dia. head nails 6" o.c. on all framing maximum 16' ¹/₈" long, 16 gage staples stud spacing 0.092" dia., 0.225" dia. head nails with HPS length to accommodate 11/2" penetration into studs 4" edges 8" field //₁₆" for maximum 16' Hardboard panel siding stud spacing See Section R602.10.6.1 See Section R602.10.6.1 3/8"

	TABLE R602.10.5 NGTH OF BRACED WALL PANELS MINIMUM LENGTH' (Inches) Wall Height					CONTRIBUTING LENGTH	
METHOD (See Table R602.10.4)							
		8 feet 9 feet 10 feet		11 feet 12 feet		·	
DWB, WSP, SFB, PBS, PCP, HPS, BV-WSP		48	48	48	53	58	Actual ^b
		48	48	48	53	58	Double sided = Actual Single sided = 0.5 × Actual
GB					NP	NP	Actual ⁶
LIB		55	62	69	NP	INF	710000
ABW	SDC A, B and C, ultimate design wind speed < 140 mph	28	32	34	38	42	- 48
	SDC D ₀ , D ₁ and D ₂ , ultimate design wind speed < 140 mph	32	32	34	NP	NP	
CS-G		24	27	30	33	36	Actual ^b
CS-WSP, CS-SFB	Adjacent clear opening height (inches)				l		
	≤ 64	24	27	30	33	36	
	68	26	27	30	33	36	Actual ^b
	72	27	27	30	33	36	
	76	30	29	30	33	36	
	80	32	30	30	33	36	
	84	35	32	32	33	36	
	88	38	35	33	33	36	
	92	43	37	35	35	36	
	96	48	41	38	36	36	
	100		44	40	38	38	
	104		49	43	40	39	
	108		54	46	43	41	
	112		_	50	45	43	
	116			55	48	45	
	120	_		60	52	48	
	124	_	_		56	51	
	128	_			61	54	
	132				66	58	
	136					62	
	140				<u> </u>	66 72	<u> </u>
	144					12	
METHOD		Portal header height 8 feet 9 feet 10 feet 11 feet 12 feet					-
(See Table R602,10.4)		8 fact	9 feet	10 feet	Note c	Note o	
PFH	Supporting roof only	16	16	24	Note c	Note	48
	Supporting one story and roof			30	Note d	Note	
PFG		24	27	20	Note e	Note	
CS-PF	SDC A, B and C SDC D ₀ , D ₁ and D ₂	16	18	20	Note e	Note	

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 mile per hour = 0.447 m/s. NP = Not Permitted.

a. Linear interpolation shall be permitted. a. Linear interpolation shall be permitted.
b. Use the actual length where it is greater than or equal to the minimum length.
c. Maximum header height for PFH is 10 feet in accordance with Figure R602.10.6.2, but wall height shall be permitted to be increased to 12 feet with pony wall.
d. Maximum header height for PFG is 10 feet in accordance with Figure R602.10.6.3, but wall height shall be permitted to be increased to 12 feet with pony wall.
e. Maximum header height for CS-PF is 10 feet in accordance with Figure R602.10.6.4, but wall height shall be permitted to be increased to 12 feet with pony wall.

BRACE WALL DETAILS WIND SPEED 115 MPH WIND EXPOSURE A SEISMIC DESIGN CAEGORY A

TABLE R602.10.4—continued BRACING METHODS METHODS, MATERIAL See Section R602.10.6.2 See Section R602.10.6.2 See Section R602.10.6.3 See Section R602.10.6.3 7/16" 6" edges 12" field CS-WSP Interior sheathing per Table R602.3(1) or R602.3(2) Varies by fastener CS-Gb,c See Method CS-WSP wood structural pan adjacent to garage openings See Section R602.10.6.4 7/₁₆" See Section R602.10.6.4 $1^{1}/_{2}^{"}$ long × 0.12" dia. (for $^{1}/_{2}^{"}$ thick sheathing) $1^{3}/_{4}^{"}$ long × 0.12" dia. (for $^{25}/_{22}^{"}$ thick sheathing) CS-SFB^d 3" edges 6" field

For Si: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 degree = 0.0175 rad, 1 pound per square foot = 47.8 N/m², 1 mile per hour = 0.447 m/s.

a. Adhesive attachment of wall sheathing, including Method GB, shall not be permitted in Seismic Design Categories C, D₀, D₁ and D₂,

b. Applies to panels next to garage door opening where supporting gable end wall or roof load only. Shall only be used on one wall of the garage. In Seismic Design Categories D₀, D₁ and D₂, roof covering dead load shall not exceed 3 psf.

c. Garage openings adjacent to a Method CS-Q panel shall be provided with a header in accordance with Table R602.7(1). A full-height clear opening shall not be permitted adjacent to a Method CS-G panel.

d. Method CS-SFR does not conty in Seismic Design Categories D., D. and D..

d. Method CS-SFB does not apply in Seismic Design Categories D_0 , D_1 and D_2 . e. Method applies to detached one- and two-family dwellings in Seismic Design Categories D_0 through D_2 only.

EXTENT OF HEADER WITH SINGLE PORTAL FRAME (ONE BRACED WALL PANEL) 2'-18' FINISHED WIDTH OF OPENING FOR SINGLE OR DOUBLE PORTAL MIN. 3"x11½" NET HEADER STEEL HEADER PROHIBITED IF ½" SPACER IS USED, PLACE ON BACK-SIDE OF HEADER OVER CONCRETE OR MASONRY BLOCK FOUNDATION WOOD STRUCTURAL PANEL SHEATHING OV.

OVER RAISED WOOD FLOOR - FRAMING ANCHOR OPTION
(WHERE PORTAL SHEATHING DOES NOT LAP OVER BAND OR RIM JOIST) OVER RAISED WOOD FLOOR - OVERLAP OPTION (WHERE PORTAL SHEATHING LAPS OVER BAND OR RIM BOARD) SECTION FRONT ELEVATION

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm.

FIGURE R802.10.6.4
METHOD CS-PF—CONTINUOUSLY SHEATHED PORTAL FRAME PANEL CONSTRUCTION



ACCORDANCE WITH BUILD IN ACCORDANCE 2018 INTERNATIONAL RESIDENTIAL CODE AN LOCAL CODES.

MEADOW AND DR HOWE 202 HIGHLA S SW FIORD I SUMMIT MO \checkmark AR .O.T .063 .EE

SCALE 1/4" = 1-0

DATE 7-10-22

PLAN NO.

3883

SHEET NO.

5 OF 5

AS NOTED FOR PLAN REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI 07/14/2022