



LIGHT HAZARD
WET SYSTEM

1. DESIGN IS BASED ON 2016 NFPA 13 FOR INSTALLATION & NFPA 25 FOR MAINTENANCE.
2. ALL SPRINKLER MATERIAL TO COMPLY WITH UL LISTINGS, ALL AHJ REQUIREMENTS, AND NFPA STANDARDS.
3. CONTINUOUS CENTRAL MONITORING OF SPRINKLER SYSTEMS PER NFPA 72 TO BE BY OTHERS.
4. ALL VALVES TO BE MONITORED BY TAMPER SWITCHES.
5. ALL ELECTRICAL WIRING TO BE BY OTHERS.
6. ANY UNDERGROUND PIPE WORK TO BE BY OTHERS.
7. ALL PAINTING OF SPRINKLER PIPE TO BE BY OTHERS.
8. PATCHING AND/OR PAINTING OF DEBRATED FIREWALL AND MASONRY WALLS TO BE BY OTHERS.
9. ADEQUATE HEAT TO BE MAINTAINED TO PREVENT PIPE FREEZING.
10. THIS BUILDING IS UNOBSTRUCTED NONCOMBUSTIBLE CONSTRUCTION.
11. WET TEST SYSTEM.
12. THREADED PIPE OF ANY DIAMETER TO BE BLACK SCHEDULE 40.
13. GROOVED PIPE OF DIAMETERS UP TO 4" TO BE BLACK DYNALOW.
13. GROOVED PIPE OF DIAMETERS OVER 4" TO BE BLACK SCHEDULE 10.

[illegible]

CONTRACTOR

PROJECT

AHJ
Lee's Summit Bldg Code
DESIGNER
AC
SCALE
3/16" = 1'-0
TOTAL SPRINKLERS ON JOB
32
JOB NUMBER
FP 24590
DATE
04/14/22
SHEET NUMBER
FP 1 OF 1