

SCOPE OF WORK DETAIL: Refer to all attachments in ORCA for specific requirements.
Specific Requirements: Reach info: Bill Coday 816-803-4924 [/wc7681@att.com](mailto:wc7681@att.com). Please update via email with what is placed and upon finishing project. All work to be done as shown on work prints unless otherwise noted here in scope of work detail. Final walk through or pics required for final billing. All changes must be pre-approved prior to work being done (Codes and Cost w/ email approval from LCE).

Project Number: A023126

Project Name:	WHISPERING WOODS 2 PHASE-EE416
Estimated In-Service Date:	26-AUG-2022
Project Description:	FOTP-DST-EE4160-D3215PB; WHISPERING WOODS SUBDIVISION - PHASE 2 -- CCU #: QTC1902081006
Project Notes:	<p>WHAT: THIS PROJECT PLACES 766' OF 5BQ2MT-48 , 1122' OF 5BQ1M6-006 AND (1) 3X2X3 HANDHOLES, 9 PEDISTALS, 5 BFGNNS6 TERMINALS. THIS PROJECT TAKE FIBER TO PHASE 2 OF WHISPERING WOODS SUBDIVISION.</p> <p>SWPPP Y OR N: = N LESS THAN ONE LINEAR MILE OF CABLE BEING PLACED DEVLOG ID = 226249 CPCT Y OR N: = N/A</p> <p>WHERE: SW PRYOR & SW HOOK RD ADDRESS LOCATION: 1713 SW 27th St CITY/STATE: LEE'S SUMMIT, MO NPANNX: 816524 WC NAME: LEE'S SUMMIT DA: 3215PB</p> <p>WHY: PHASE 2 OF A NEW SUBDIVISION BEING DEVELOPED</p> <p>WHY THIS WAY: PHASE 2 OF A NEW SUBDIVISION BEING DEVELOPED</p> <p>WHY NOW: PHASE 2 OF A NEW SUBDIVISION BEING DEVELOPED AND WILL REQUIRE SERVICE SOON ENG REQ CONST COMP DATE: 07-09-2021</p>

PLACE GRD ROD AT EACH PED, PLACE LOCATEABLE MULETAPE AT ALL DROP CONDUITS. MARK EACH FIBER IN HANDHOLE AS TO WHERE THEY GO.