



MiTek USA, Inc.
16023 Swingley Ridge Rd
Chesterfield, MO 63017
314-434-1200

Re: 220056-A
320 PR 2032 NE BLUESTONE DR Lees Summit MO 64064

The truss drawing(s) referenced below have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by KC Truss & Panel Inc. (Urich, MO).

Pages or sheets covered by this seal: I53684827 thru I53684827

My license renewal date for the state of Missouri is December 31, 2023.

Missouri COA: Engineering 001193



Scott M. Sevier

August 17, 2022

Sevier, Scott, Engineer

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job 220056-A	Truss D9	Truss Type Roof Special Girder	Qty 1	Ply 1	320 PR 2032 NE BLUESTONE DR Lees Summit MO 64064 153684827
-----------------	-------------	-----------------------------------	----------	----------	---

KC Truss & Panel Inc. (Urich, MO), Urich, MO - 64788,

8.530 s Jul 18 2022 MiTek Industries, Inc. Tue Aug 16 09:59:46 2022 Page 1
ID:3YzUEFuTXpusHba?0tpUTHzCdai-7odJSARREvkH5f0p4tVRmmCjHRNBjF72RcrjJynJ2R

1-4-12	6-3-12	11-9-12	17-3-12	22-3-0	27-0-9	32-1-4	33-6-0
1-4-12	4-11-0	5-6-0	5-6-0	4-11-4	4-9-9	5-0-11	1-4-12

Scale = 1:57.7




Plate Offsets (X,Y)-- [3:0-4-0,0-1-12], [5:0-3-6,Edge], [16:0-5-0,0-4-8], [17:0-3-8,0-2-8]									
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	I/defl	L/d
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.23 14-16	>999	240
Snow (Pf/Pg)	20.4/20.0	Lumber DOL	1.15	BC	0.77	Vert(CT)	-0.43 14-16	>852	180
TCDL	10.0	Rep Stress Incr	NO	WB	0.52	Horz(CT)	0.08 10	n/a	n/a
BCLL	0.0 *	Code IRC2018/TPI2014		Matrix-S					
BCDL	10.0								
								Weight: 216 lb FT = 20%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1 *Except* 3-5: 2x6 SP No.1	TOP CHORD	Structural wood sheathing directly applied or 2-11-1 oc purlins, except 2-0-0 oc purlins (2-10-15 max.): 3-5.
BOT CHORD	2x6 SP No.1	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.1	WEBS	1 Row at midpt 5-12

REACTIONS. (size) 18=0-3-8, 10=0-3-8
Max Horz 18=82(LC 10)
Max Grav 18=2496(LC 37), 10=1759(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-426/0, 2-3=-3904/0, 3-4=-5867/0, 4-5=-5873/0, 5-6=-2478/0, 6-7=-2480/0,
7-8=-2485/0, 8-9=-356/0
BOT CHORD 1-18=0/416, 17-18=0/416, 16-17=0/3482, 14-16=0/4829, 12-14=0/4835, 11-12=0/2160,
10-11=0/334, 9-10=0/334
WEBS 2-18=-2250/11, 2-17=0/3158, 3-16=0/2748, 4-16=-817/54, 5-16=-110/1203,
5-12=-3331/0, 6-12=0/1898, 7-11=-297/36, 8-11=0/1866, 8-10=-1486/0

NOTES-

- 1) Repair Condition: Missing or damaged plate(s) on both side(s) of truss at joint(s) 14.
- 2) Attach 14"H X 13"W X 7/16" OSB (APA Rated Sheathing 24/16 Exposure 1) gusset to both sides of truss at joint 14 with 10d (0.131"x3") nails from each face, driven through both sheets of plywood and clinched. Connected together as follows: 2x6 - 2 rows 0-10-0 o.c., 2x4 - 2 rows 0-4-0 o.c. Minimum 0-3-0 end distance.
- 3) N/A
- 4) Unbalanced roof live loads have been considered for this design.
- 5) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; B=45ft; L=34ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 6) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=20.0 psf; Pf=20.4 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10, Lu=50-0-0; Min. flat roof snow load governs. Rain surcharge applied to all exposed surfaces with slopes less than 0.500/12 in accordance with IBC 1608.3.4.
- 7) Unbalanced snow loads have been considered for this design.
- 8) Provide adequate drainage to prevent water ponding.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

Continuous truss representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



August 17, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**
Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	320 PR 2032 NE BLUESTONE DR Lees Summit MO 64064
220056-A	D9	Roof Special Girder	1	1	I53684827
Job Reference (optional)					

- NOTES-**
- 13) Use Simpson Strong-Tie LUS26 (4-10d Girder, 3-10d Truss, Single Ply Girder) or equivalent at 12-2-4 from the left end to connect truss(es) to front face of bottom chord.
 - 14) Fill all nail holes where hanger is in contact with lumber.
 - 15) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 457 lb down and 96 lb up at 6-3-12, and 203 lb down and 33 lb up at 8-4-8, and 203 lb down and 33 lb up at 10-4-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - 16) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-3=-51, 3-5=-61, 5-6=-51, 6-9=-51, 1-9=-20


Concentrated Loads (lb)

Vert: 17=-457 24=-203 25=-203 26=-802(F)




Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.


* Plate location details available in **MiTek 20/20** software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MiTek® All Rights Reserved



MiTek Engineering Reference Sheet: MII-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.