

# LEE'S SUMMIT FIRE DEPARTMENT

FIRE HEADQUARTERS  
207 SE DOUGLAS STREET  
LEE'S SUMMIT, MISSOURI 64063-2372  
(816) 969-1300  
FAX (816) 969-1313  
TDD (816) 969-7407

## PLANS REVIEW CONDITIONS

Permit No:	PRCOM20110307	Date:	April 11, 2011
Project Title:	Saint Lukes 1st Floor Lab Expansion	Applicant:	JAYHAWK FIRE SPRINKLERS
Location:	100 NE SAINT LUKES BLVD. LEES SUMMIT, MO 64086		10629 SUMMIT STREET LENEXA, KS 66215 (913) 422-3770
Type of Work:	Sprinkler Alteration		
Occupancy Group:	I-2		
Description:	Expansion of existing hospital lab on first floor Remodel of old respiratory therapy area for accounting		
Construction Type:	Type IA		
Map Page:	175X		

**Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.**

### **Sprinkler Plan Review**

**Reviewed By: Jim Eden**

**Released for Construction**

1. 2006 IFC 901.2- Construction documents. The fire code official shall have the authority to require construction documents and calculations for all fire protection systems and to require permits be issued for the installation, rehabilitation or modification of any fire protection system. Construction documents for fire protection systems shall be submitted for review and approval prior to system installation.

Plans received April 8, 2011.

2. 2006 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

Action required: Provide adocumentation of any required testing for the system per NFPA 25 and 13. Visual inspection to be completed at occupancy inspection.