

SCOPE OF WORK DETAIL: Refer to all attachments in ORCA for specific requirements.
 Specific Requirements: Reach info: Bill Coday 816-803-4924 [/wc7681@att.com](mailto:wc7681@att.com). Please update via email with what is placed and upon finishing project. All work to be done as shown on work prints unless otherwise noted here in scope of work detail. Final walk through or pics required for final billing. All changes must be pre-approved prior to work being done (Codes and Cost w/ email approval from LCE).

Project Number: A022RQY

Project Name:	3RD ST JEFFERSON TO 50
Estimated In-Service Date:	10-FEB-2023
Project Description:	GOV-FND--EE4160-; 3RD ST ROAD IMPROVEMENT PLAN
Project Notes:	<p>EAC 7/25/2022 AFTER RECIEVING POT HOLE RESULTS THIS IS TURNING INTO A CAPITAL PROJECT. THE EAC STARTS ON PRINT 7. ALL COPPER CABLES HAVE BEEN DOWNSIZED AND OR SHEATHS COMBINED. PER WILLIAM HASHMAN THE FIBER DID NOT NEED TO BE UPSIZED BUT REQUESTED 3 SPARE DUCT WITH MAXCELL WHICH HAVE BEEN INCLUDED IN THIS PROJECT. THIS PROJECT WILL PLACE 4 MH12X6X7 PRE CAST MAN HOLES. IT WILL PLACE THE FOLLOWING COPPER CABLES 6159' OF ANMW 1200, 20,454' OF ANMW 900, 8304' OF ANMW 600, 245' OF ANMW 400, 605' OF ANMW 300, 620' OF ANMW 200, 758' OF ANMW 100, 1180' OF ANMW 50, AND 600' OF ANMW 25. IT WILL ALSO PLACE 5504' OF TRACER WIRE. IT WILL PLACE THE FOLLOWING FIBER CABLES, 3460' OF 5BQ2MR 432, 8290' OF 5BQ2MT 216, 4064' OF 5BQ2MT 144, 430' OF 5BQ2MT 072, 4064' OF 5BQ2MT 048, AND 630' OF 5BQ2MT 024. THIS PROJECT WILL ALSO PLACE 1 MLMNF 50/20 LOAD COIL AND 1 MLMNF 100/20 LOAD COIL. IT WILL PLACE THE FOLLOWING STUBS, 3 10D1-1200/30, 7 10D1-900/30, 6 10D1-600/30, 1 10D1-200/30. IT WILL ALSO RIP ALL UG CABLES, FIBER AND COPPER AND IT WILL REMOVE THE AERIAL CABLE ON THE NORTH SIDE OF 3RD ST. IT WILL REMOVE 24 POLES ON THE NORTH SIDE OF 3RD ST.</p> <p>SWPPP Y or N: NO, LESS THAN 1 ACRE OF SOIL WILL BE DISTURBED Where: Work Location/Address: 3RD ST BETWEEN JEFFERSON AND 50 HWY City/State: LEE'S SUMMIT, MO WC Name: LEE'S SUMMIT</p> <p>Why: TO DETERMINE THE AMOUNT OF CONFLICTS AT&T WILL HAVE WITH THE CITIES ROAD IMPROVEMENT PROJECT Buy America source: THIS PROJECT DOES NOT QUALIFY FOR BUY AMERICA Governmental Entity Requesting Work: CITY OF LEES SUMMIT Governmental Contact Person (Name & Number): KAREN QUACKENBUSH, 816-969-1800 Customer Requesting Work: CITY OF LEES SUMMIT Customer approved letter of agreement: NA Why Not Reimbursable: AT&T FACILITIES ARE IN PUBLIC ROW. IT IS THE RESPONSIBILITY OF AT&T TO REMOVE CONFLICTS WITH CITY AND STATE ROAD AND SEWER IMPROVEMENT PLANS Why now: THE CITY IS READY TO PROCEED WITH THEIR PROJECT</p> <p>ENGINEER REQUESTED COMPLETION DATE: 02/10/2023</p>

Pre construction meeting required by city of LS before starting any work.

Any changes need to be approved before working.