
GENERAL NOTES

- A. REFER TO P0.1 FOR GENERAL NOTES, SYMBOLS, AND ABBREVIATIONS.
- B. REFER TO PLUMBING RISER DIAGRAMS AND SCHEDULES FOR ADDITIONAL PIPE ROUTING AND SIZING.
- PROVIDE ASSE-1070 CERTIFIED THERMOSTATIC MIXING VALVES AT ALL LAVATORIES AND HANDSINKS. RE: PLUMBING SCHEDULES.
- D. ALL DOMESTIC COLD AND HOT WATER PIPING SHALL BE COPPER.



ms consultants, inc. engineers, architects, planners 2221 Schrock Road Columbus, Ohio 43229 p 614.898.7100 f 614.898.7570 www.msconsultants.com

HW 150 AND YWOOD ST

KEYNOTES

- NORMALLY CLOSED BALL VALVE
 1-1/2" DOMESTIC WATER ENTRY, RE: DETAILS COORDINATE FINAL LOCATION WITH GC. ^ ROUTE DOMESTIC HOT WATER LOOP DOWN IN WALL TO BEHIND FIXTURES STOPS. ROUTE 3/8" DCW DOWN IN WALL TO SHAKE MACHINE. PROVIDE STUB-OUT AT 24" AFF 5' FROM
- ROUTE 1/2" FW DOWN IN WALL AND PROVIDE STUB-OUT WITH SHUT-OFF VALVE AT ICE MACHINE
- CONNECTION(S), APPROXIMATELY 62" AFF. ROUTE 1/2" FW DOWN IN WALL AND PROVIDE (1) 3/8" SUTB-OUT CONNECTIONS WITH SHUT-OFF
- VALVES AT 48" AFF FOR COFFEE AND TEA BREWERS. PROVIDE 3/4" DCW STUB-OUT CONNECTION WITH SHUT-OFF VALVE AT 84" AFF FOR FILTER SYSTEM. 1" DCW UP TO ROOF HYDRANT. ROUTE DRAIN FULL-SIZED TO DISCHARGE INTO MOP SINK.
- PROVIDE 1/2" CW & HW TO WF-1 WALL MTD FAUCET AT 60" A.F.F. (WITH SHUT-OFF VALVES). CENTERED 3'-9" FROM CORNER. PROVIDE SEPARATE 1/2" CW WITH STUB OUT AND SHUT OFF VALVE FOR CHEMICAL DISPENSER AT
- 60" A.F.F., COORDINATE LOCATION WITH EQUIPMENT PLAN. MS-1 + 48" AFF 1" BLACK IRON USED GREASE PIPING TO STORAGE TANK. ROUTE ABOVE CEILING. TERMINATE 6"



NOTICE: THIS ARCHITECTURAL AND ENGINEERING DRAWING IS GIVEN IN CONFIDENCE AND SHALL BE USED ONLY PURSUANT TO THE AGREEMENT WITH THE ARCHITECT. NO OTHER USE, DISSEMINATION, OR

DUPLICATION MAY BE MADE WITHOUT PRIOR WRITTEN CONSENT OF THE ARCHITECT. ALL COMMON LAW RIGHTS OF COPYRIGHT AND OTHERWISE ARE HEREBY SPECIFICALLY RESERVED.



04/12/19 PROFESSIONAL OF RECORD: JASON E. CHRISTOFF No.2012002143 EXP DATE: 12/31/2022

REV	DESCRIPTION	DATE
1	BUILDING PERMIT RESUBMITTAL	09/15/2022

Project No.: 62-40497-21

Client Project No.:

Drawing Title:

PLUMBING DOMESTIC WATER PLAN

Phase: PERMIT SET Date: 06.29.2022 Designed: JPF Drawing No.:

Drawn: JPF Checked: KFF