
DEVELOPMENT SERVICES

Building Permit - Commercial Project Title: SAINT LUKES EAST - MEDICAL OFFICE BUILDING RENOVATION OF THERAPY SPACE INTO OUTPATIENT PULMONARY CLINIC Work Desc: ALTERATION COMMERCIAL	Permit No: PRCOM20223920 Date Issued: September 19, 2022
---	---

Project Address: 20 NE SAINT LUKES BLVD, LEES SUMMIT, MO 64086 Legal Description: SAINT LUKES HOSPITAL OF LEES SUMMIT LOTS 1 & 2---LOT 1 Parcel No: 52440044000000000 County: JACKSON	Permit Holder: rellis@derossconstruction.com rellis@derossconstruction.com
--	---

Activities Included for this Project: zAlteration Commercial, License Tax, License Tax Credit, Alarm Permit, Sprinkler Permit, Fire Rated Assemblies Permit,
--

THIS PERMIT IS ISSUED IN RELIANCE UPON INFORMATION SUBMITTED BY THE APPLICANT. THE BUILDING OFFICIAL MAY SUSPEND OR REVOKE WHENEVER THE PERMIT IS ISSUED IN ERROR, OR ON THE BASIS OF INCORRECT INFORMATION SUPPLIED, OR IN VIOLATION OF ANY ADOPTED CODE, CITY ORDINANCE OR REGULATIONS. NOTICE: THE DISPOSAL OF DEMOLITION WASTE IS REGULATED BY THE DEPARTMENT OF NATURAL RESOURCES UNDER CHAPTER 260 RSMO. SUCH WASTE, IN TYPES AND QUANTITIES ESTABLISHED BY THE DEPARTMENT, SHALL BE TAKEN TO A DEMOLITION LANDFILL OR A SANITARY LANDFILL FOR DISPOSAL.

CONDITIONS

One or more divisions have conditions that have not been addressed during the review period. The outstanding conditions provided below shall be met as indicated during the construction period.

Fire Plan Review

1 2018 IFC 901.2- Construction documents. The fire code official shall have the authority to require construction documents and calculations for all fire protection systems and to require permits be issued for the installation, rehabilitation or modification of any fire protection system. Construction documents for fire protection systems shall be submitted for review and approval prior to system installation.

Action required- Provide shop drawings for review and approval.

2 2018 IFC 903.4.2- Alarms. Approved audible and visual devices shall be connected to every automatic sprinkler system. Such sprinkler water-flow alarm devices shall be activated by water flow equivalent to the flow of a single sprinkler of the smallest orifice size installed in the system. Listed alarm notification devices shall be provided on the exterior and interior of the building in an approved location. Where a fire alarm system is installed, actuation of the automatic sprinkler system shall actuate the building fire alarm system.

Action required-Provide shop drawings for review and approval.

3 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

Call (816) 969-1300 to schedule alarm testing.

Building Plan Review

2 2017 NEC Article 517.13 Grounding of Receptacles and Fixed Electrical Equipment in Patient Care Spaces. Wiring in patient care spaces shall comply with 517.13(A) and (B).

(A) Wiring methods. All branch circuits serving patient care spaces shall be provided with an effective ground-fault current path by installation in a metal raceway system, or a cable having a metallic armor or sheath assembly. The metal raceway system, metallic cable armor, or sheath assembly shall itself qualify as an equipment grounding conductor in accordance with 250.118.

(B) Insulated Equipment Grounding Conductors and Insulated Equipment Bonding Jumpers.

(1) General. The following shall be directly connected to an insulated copper equipment grounding conductor that is clearly identified along its entire length by green insulation and installed with the branch circuit conductors in the wiring methods as provided in 517.13(A).

1. The grounding terminals of all receptacles other than isolated ground receptacles.

2. Metal outlet boxes, metal device boxes, or metal enclosures.

3. All non-current-carrying conductive surfaces of fixed electrical equipment likely to become energized that are subject to personal contact, operating at over 100 volts. (see code for exceptions)

(2) Sizing. Equipment grounding conductors and equipment bonding jumpers shall be sized in accordance with 250.122.

Action required: Redundant grounding method verified at inspections.

Licensed Contractors

Signature of

Applicant: _____

Date: _____

Print name: _____

Company Name: _____
