SCOPE OF WORK DETAIL: Refer to all attachments in ORCA for specific requirements. Specific Requirements: Reach info: Bill Coday 816-803-4924 /wc7681@att.com. Please update via email with what is placed and upon finishing project. All work to be done as shown on work prints unless otherwise noted here in scope of work detail. Final walk through or pics required for final billing. All changes must be pre-approved prior to work being done (Codes and Cost w/ email approval from LCE).

Project Number: A01XE9D

Troject Number: AVIXE2D	
Project Name:	COLBERN RD WIDENING
Estimated In- Service Date:	07-OCT-2022
Project Description:	GOV-ROUEE4160-D1321-; COLBERN ROAD WIDENING PROJECT
Project Notes:	7/8/2022 PER ENG, TOOK PROJECT OUT OF DEFERRED STATUS, READY TO GO 4/7/22 CONFIRMATION RECEIVED UPLOADED TO EXCEPTION TABLE
	4/6/22 REQUEST SUBMITTED TO ADD TO EXCEPTION TABLE
	2/1/22 - ENG STILL PLANS TO ISSUE 1/26/2022 - ENG WILL ISSUE 12/1/2021 - INACTIVE PRELIM - PER ENG WILL ISSUE, WAITING ON PROPOSED ROW
	What: THIS PROJECT WILL PLACE 20' OF ANMW 400 PR COPPER CABLE, 395' OF ANMW 50 PR COPPER CABLE, 995' OF ANMW 900 PAIR COPPER CABLE, 275' OF ANMW 200 PR COPPER CABLE, 6270' OF 5BQ2MT 144 FIBER CABLE AND 2650' OF 5BQ2MT 048 FIBER CABLE. IT WILL ALSO PLACE 6 HAND HOLES SWPPP Y or N: NO, LESS THAN 1 ACRE OF SOIL WILL BE DISTURBED Where: Work Location/Address: COLBERN RD 350 HWY TO EAST OF DOUGLAS City/State: LEES SUMMIT MO WC Name: LEES SUMMIT Why: Buy America source: THIS PROJECT DOES NOT QUALIFY FOR BUY AMERICA Governmental Entity Requesting Work: LEES SUMMIT Governmental Contact Person (Name & Number): JON HALEY, 816-969-1800 Customer Requesting Work: CITY OF LEES SUMMIT Customer approved letter of agreement: NA Why Not Reimbursable: AT&T FACILITIES ARE IN PUBLIC ROW. IT IS THE RESPONSIBILITY OF
	AT&T TO REMOVE CONFLICTS WITH CITY AND STATE ROAD AND SEWER IMPROVEMENT PROJECTS Why this way: TO REMOVE CONFLICTS WITH THE ROAD WIDENING PROJECT Why now: CITY WILL BEGIN CONSTRUCTION DEC OF 2022
	ENGINEER REQUESTED COMPLETION DATE: 10/07/2022