



The platforms above are structurally built/ framed using 2x6 joists, ledger and rim joist. They'll be tied together with joist hangers, and deck will be 3/4" OSB/ subfloor. Platforms will be tied into the wall framing. The goal of the platform deck is to support the size and weight of a fire fighter and his/her equipment in the case of an emergency entry into the space. Exiting on these would obviously also be easily accomplished by anyone.

Platform Construction

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

11/04/2022

4 steps

6" rise
11" run

