

DRAWINGS

COVER

CIVIL

REFER TO CIVIL SHEET C1.00 FOR CIVIL DRAWING INDEX

ARCHITECTURAL

A001	SCOPE NOTES & CODE SUMMARY
A002	TYPICAL ACCESSIBILITY DETAILS
A100	LIFE SAFETY PLAN
A101	OVERALL FLOOR PLAN
A102	FLOOR PLAN - AREA A
A103	FLOOR PLAN - AREA B
A104	FLOOR PLAN - AREA C
A120	ROOF PLAN
A201	EXTERIOR ELEVATIONS
A202	EXTERIOR ELEVATIONS
A203	EXTERIOR ELEVATIONS
A204	EXTERIOR ELEVATIONS
A301	WALL SECTIONS
A302	WALL SECTIONS
A303	WALL SECTIONS
A304	WALL SECTIONS
A501	SECTIONS AND DETAILS
A502	SECTIONS AND DETAILS
A601	DOOR SCHEDULE

STRUCTURAL

S0.0	GENERAL NOTES
S0.1	GENERAL NOTES
S1.0	OVERALL FOUNDATION PLAN
S1.1	ENLARGED PARTIAL FOUNDATION PLAN
S1.2	ENLARGED PARTIAL FOUNDATION PLAN
S1.3	ENLARGED PARTIAL FOUNDATION PLAN
S2.0	OVERALL FRAMING PLAN
S2.1	ENLARGED PARTIAL FRAMING PLAN
S2.2	ENLARGED PARTIAL FRAMING PLAN
S2.3	ENLARGED PARTIAL FRAMING PLAN
S2.4	ROOF DECK ATTACHMENT PLAN
S2.5	LATERAL LOAD PLAN
S3.0	FOUNDATION DETAILS
S3.1	FOUNDATION DETAILS
S3.2	FOUNDATION DETAILS
S3.3	FOUNDATION DETAILS
S4.0	FRAMING DETAILS
S4.1	FRAMING DETAILS
S4.2	FRAMING DETAILS
S4.3	FRAMING DETAILS

MECHANICAL

M1.1
M2.1

PLUMBING

P300	PLUMBING PLAN AREA A
P301	PLUMBING PLAN AREA B
P302	PLUMBING PLAN AREA C
P303	PLUMBING SPECIFICATIONS

ELECTRICAL

E1.00	LIGHTING PLAN
E2.00	POWER PLAN
E3.00	UNDERGROUND
E4.00	PHOTOMETRIC
E5.00	SITE
E6.00	RISER DIAGRAM
E7.00	PANEL SCHEDULE

FIRE PROTECTION

FP 0.0	GENERAL INFORMATION
FP 0.1	DETAILS
FP 1.0	HYDRAULIC SITE PLAN
FP 2.0	OVERHEAD PIPING PLAN AND SECTION VIEW
FP 2.1	SYSTEM 1 WEST
FP 2.2	SYSTEM 1 EAST
FP 2.3	SYSTEM 2 WEST
FP 2.4	SYSTEM 2 EAST
FP 2.5	SYSTEM 3-4 WEST
FP 2.6	SYSTEM 3-4 EAST
FP 2.7	SYSTEM 5
FP 2.9	SYSTEM 6 WEST
FP 2.10	SYSTEM 6 EAST
FP 2.11	SYSTEM 7 WEST
FP 2.12	SYSTEM 7 EAST
FP 3.0	FIRE PUMP DETAILS

LEE'S SUMMIT LOGISTICS
BUILDING C

NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO
64086

11.02.22
CONSTRUCTION SET


OWNER

SCANNELL PROPERTIES
8801 RIVER CROSSING BLVD. SUITE 300
INDIANAPOLIS, IN 46240
O : 317 . 218 . 1648

CIVIL ENGINEER

OLLSON
7301 W. 133RD ST. SUITE 200
OVERLAND PARK, KS 66213
O : 913 . 381 . 1170

ARCHITECT



CURRAN
ARCHITECTURE


5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O : 317 . 288 . 0681
CONTACT : SHAWN CURRAN

STRUCTURAL ENGINEER

WALLACE DESIGN
COLLECTIVE
1741 MCGEE STREET
KANSAS CITY, MO 64108
O : 816 . 421 . 8282

CONTRACTOR

KADEAN CONSTRUCTION
1821 MCGEE STREET
KANSAS CITY, MO 64108
O : 816 . 708 . 1199



LEE'S SUMMIT LOGISTICS BUILDING C
220019



CURRAN
ARCHITECTURE
5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3
X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES	
PERMIT SET	09.16.22
PERMIT COMMENTS	11.01.22

220019

SCOPE NOTES &
WALL TYPES

A001

SYMBOLS

(NOT ALL MAY APPLY)

	KEYED NOTE
	WINDOW OR GLAZED OPENING TAG IF WINDOW - WH IF STOREFRONT - SF# IF CURTAINWALL - CWH#
	ACCESSORY TAG
	EQUIPMENT TAG
	FINISH TAG
	ROOM TAG
	ELEVATION TAG - INTERIOR OR EXTERIOR
	SECTION CUT AT AREAS SHOWN SMALL SCALE
	ENLARGED PLAN
	ELEVATION TARGET. FINISHED FLOOR = 0'-0" UNO
	REVISION
	PLAN OR TRUE NORTH
	BATT INSULATION - WIDTH OF FRAMING UNO
	FIRE EXTINGUISHER IN SEMI-RECESSED CABINET PROVIDED / INSTALLED BY GC
	SURFACE MOUNTED FIRE EXTINGUISHER PROVIDED / INSTALLED BY GC
	DOOR WITH DOOR NUMBER
	WINDOW OR GLAZED OPENING
	STUD FRAMED WALL - REFER TO INDEX SHEET FOR INFORMATION
	CMU WALL - REFER TO SECTIONS AND DETAILS
	BRICK WALL - REFER TO SECTIONS AND DETAILS
	CONCRETE WALL - REFER TO SECTIONS AND DETAILS
	EFS OVER SUBSTRATE - REFER TO SECTIONS FOR WIDTH AND PROFILE
	EXISTING DOOR - REFER TO DOOR SCHEDULE
	EXISTING FRAMED WALL
	EXISTING WINDOW WITH SILL AND / OR STOOL
	DEMO'D DOOR
	DEMO'D WALL
	WALL TYPE WALL HEIGHT IF DESIGNATED ON PLANS. IF NOT, SEE WALL TYPES THIS SHEET

ABBREVIATIONS

ACT	ACOUSTICAL CEILING TILE	FLR	FLOOR	PS	PROJECTION SCREEN
ADDL	ADDITIONAL	FR	FIRE RETARDANT	QT	QUARRY TILE
AFF	ABOVE FINISHED FLOOR	FT	FEET	R	RISER
ALUM	ALUMINUM	GA	GAUGE	RA	RETURN AIR
ANOD	ANODIZED	GB	GRAB BAR	RB	RESILIENT BASE
APP	APPROXIMATE	GC	GENERAL CONTRACTOR	RD	ROOF DRAIN
ARCH	ARCHITECT	GYP BD	GYPSUM BOARD	REF	REFERENCE
AWT	ACOUSTICAL WALL TREATMENT	HDWR	HARDWARE	REFR	REFRIGERATOR
BLDG	BUILDING	HGT	HEIGHT	REQD	REQUIRED
BLKG	BLOCKING	HM	HOLLOW METAL	RO	ROUGH OPENING
B.O.	BOTTOM OF	HORIZ	HORIZONTAL	SA	SUPPLY AIR
BOT	BOTTOM	HP	HIGH POINT	SCHED	SCHEDULE
BRG	BEARING	HVAC	HEATING, VENTILATING, AIR CONDITIONING	SCMD	SOLID CORE METAL DOOR
CAB	CABINET	HW	HOT WATER	SCVD	SOLID CORE WOOD DOOR
CJ	CONTROL JOINT	INSUL	INSULATION	SEC	SECTION
CL	CENTER LINE	JAN	JANITOR	SF	SQUARE FOOT
CLR	CLEAR	JST	JOIST	SIM	SIMILAR
CMU	CONCRETE MASONRY UNIT	JT	JOINT	SPCS	SPECIFICATIONS
CONST	CONSTRUCTION	KD	KNOCKDOWN	SO	SQUARE
COL	COLUMN	KIT	KITCHEN	SS	STAINLESS STEEL
CONC	CONCRETE	LAM	LAMINATE	STD	STANDARD
CONT	CONTINUOUS	LAV	LAVATORY	STL	STEEL
CPT	CARPET	LLH	LONG LEG HORIZONTAL	STOR	STORAGE
CT	CERAMIC TILE	LLV	LONG LEG VERTICAL	STRUCT	STRUCTURAL
CW	COLD WATER	MAS	MASONRY	SUSP	SUSPENDED
DET, DTL	DETAIL	MAT	MATERIAL	TB	TACK BOARD
DF	DRINKING FOUNTAIN	MAX	MAXIMUM	TEL	TELEPHONE
DIA	DIAMETER	MB	MARKER BOARD	TLT	TOILET
DIM	DIMENSION	MECH	MECHANICAL	T.O.	TOP OF
DWG(S)	DRAWING(S)	MEZZ	MEZZANINE	TRTD	TREATED
EA	EACH	MFR	MANUFACTURER	TV	TELEVISION
EC	EXPOSED CEILING	MIN	MINIMUM	TYP	TYPICAL
EFS	EXTERIOR INSULATION FINISH SYSTEM	MO	MASONRY OPENING	UNO	UNLESS NOTED OTHERWISE
EJ	EXPANSION JOINT	MTL	METAL	UR	URINAL
EL	ELEVATION	NIC	NOT IN CONTRACT	YCT	VINYL COMPOSITION TILE
ENG	ENGINEER	NR	NOT RATED	VERT	VERTICAL
EQ	EQUAL	OC	ON CENTER	VIF	VERIFY IN FIELD
EQUIP	EQUIPMENT	OD	OUTSIDE DIAMETER	VT	VINYL TILE
EXIST	EXISTING	OFD	OVERFLOW DRAIN	W/	WITH
EXP	EXPANSION	OH	OPPOSITE HAND	W/O	WITHOUT
EXT	EXTERIOR	OPNG	OPENING	WB	WOOD BASE
FD	FLOOR DRAIN	OPP	OPPOSITE	WC	WATER CLOSET
FE	FIRE EXTINGUISHER	OTO	OUT TO OUT	WD	WOOD
FEC	FIRE EXTINGUISHER CABINET	PLAS LAM	PLASTIC LAMINATE	WH	WATER HEATER
FIN	FINISH	PLWD	PLYWOOD	WP	WORKING POINT

CODE ANALYSIS

APPLICABLE CODES		ACTUAL BUILDING HEIGHT AND AREA	
BUILDING CODE	2018 INTERNATIONAL BUILDING CODE	BUILDING AREA:	253,289 SF
		BUILDING HEIGHT (FEET / # FLOORS):	42' / 1 FLR
PLUMBING CODE	2017 INTERNATIONAL PLUMBING CODE	TABULAR OCCUPANT LOAD (1004.1.2)	
ELECTRICAL CODE	2017 NATIONAL ELECTRICAL CODE	OCCUPANT LOAD FACTOR:	1 / 500
		SQUARE FOOTAGE / OCCUPANT LOAD FACTOR:	253289 / 500
		TOTAL OCCUPANTS:	507
FIRE CODE	2018 INTERNATIONAL FIRE CODE	ACTUAL OCCUPANT LOAD (1004.1.2)	
			0 (SHELL)
MECHANICAL CODE	2014 INTERNATIONAL MECHANICAL CODE	FIRE RESISTIVE REQUIREMENTS (601 AND 602)	
FUEL GAS CODE	2018 FUEL GAS CODE	CONSTRUCTION TYPE:	II-B
HANDICAPPED ACCESSIBILITY CODE	2009 ANSI A117.1 ADA ACCESSIBILITY GUIDELINES	STRUCTURAL FRAME:	NR
		EXTERIOR BEARING WALLS:	NR
		INTERIOR BEARING WALLS:	NR
		EXTERIOR NON-BEARING WALLS:	NR
		INTERIOR NON-BEARING WALLS:	NR
		FLOOR CONSTRUCTION:	NR
		ROOF CONSTRUCTION:	NR
		SHAFTS:	N/A
OCCUPANCY (OVERALL BUILDING)		FIRE RESISTANCE RATED CONSTRUCTION (704, 601, 602)	
CLASSIFICATION (302.1):	S-I	RATED EXTERIOR WALLS:	N/A
		FIRE SEPARATION DISTANCE	60+
		UNPROTECTED OPENING AREA:	N/A
OCCUPANCY (TENANT SPACE)		INTERIOR WALL AND CEILING FINISH REQUIREMENTS (803)	
CLASSIFICATION (302.1):	S-I	SEE FINISH SCHEDULE FOR MATERIALS	
ACCESSORY USES (508.2.1):	B	ALL MATERIALS ARE CLASS A RATED	
NON-SEPARATED USES (508.3.2):	N/A		
SEPARATED USES (508.3.3):	N/A		
AUTOMATIC SPRINKLER SYSTEM		FIRE PROTECTION SYSTEMS	
SPRINKLER SYSTEM REQUIRED (903):	YES	STANDPIPE SYSTEM (905):	YES
SPRINKLER SYSTEM PROVIDED:	YES	PORTABLE FIRE EXTINGUISHERS (906.1):	SEE PLAN
		FIRE ALARM AND DETECTION SYSTEMS (907):	YES
		SMOKE CONTROL SYSTEMS (909):	N/A
		SMOKE AND HEAT VENTS (910):	N/A
ALLOWABLE BUILDING HEIGHT		EGRESS	
TABULAR HEIGHT (503):	2 STORY	MINIMUM WIDTH FACTOR (1005.1):	0.20"
		REQUIRED MINIMUM WIDTH FROM SPACE (1005.1):	101.4"
ALLOWABLE BUILDING AREA		MINIMUM NUMBER OF EXITS (1015):	3
TABULAR AREA (503):	17,500 SF	ACTUAL NUMBER OF EXITS:	20
		ACTUAL WIDTH OF EXITS:	864"
BUILDING AREA INCREASE		ALLOWABLE TRAVEL DISTANCE (1016.2):	400'
INCREASE FOR SPRINKLERED BUILDING (506.3):	300%	CORRIDOR CONSTRUCTION (1018.1):	NR
UNLIMITED AREA (507):	UNLIMITED	MINIMUM CORRIDOR WIDTH (1018.2):	44"
FRONTAGE INCREASE (506.2):	N/A	MAXIMUM DEAD END CORRIDOR (1018.4):	50'
IF = (FIP - 25) x W / 30			
TOTAL ALLOWABLE AREA WITH INCREASES:	UNLIMITED		
A ₂ = A _c + (A _t x I _f) + (A _t x I _s)			
A ₂ = FILL IN			

SCOPE NOTES

IN THE EVENT OF QUESTIONS REGARDING THE CONTRACT DOCUMENTS, SPECIFICATIONS, EXISTING CONDITIONS OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING CLARIFICATION FROM THE ARCHITECT PRIOR TO BID SUBMITTAL AND PROCEEDING WITH ANY WORK IN QUESTION.

THESE CONTRACT DOCUMENTS ARE INTENDED TO DESCRIBE ONLY THE SCOPE AND APPEARANCE OF THE REAL PROPERTY IMPROVEMENTS, INCLUDING THE PERFORMANCE AND LEVEL OF QUALITY EXPECTED OF ITS COMPONENTS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSURE THAT ALL WORK COMPLETED AND MATERIALS INSTALLED BE IN FULL COMPLIANCE AT A MINIMUM, WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES HAVING JURISDICTIONAL AUTHORITY OVER THE PROJECT.

THESE CONTRACT DOCUMENTS DO NOT ATTEMPT TO INSTRUCT THE CONTRACTOR IN THE DETAILS OF HIS TRADE. THEY ARE PERFORMANCE SPECIFICATIONS IN THAT THEY DO REQUIRE THAT ALL MANUFACTURED ITEMS, MATERIALS AND EQUIPMENT BE INSTALLED IN STRICT CONFORMANCE TO THE MANUFACTURER'S RECOMMENDED SPECIFICATIONS, EXCEPT IN THE CASE WHERE THE CONTRACT DOCUMENTS ARE MORE STRINGENT. ANY MISCELLANEOUS ITEMS OR MATERIALS NOT SPECIFICALLY NOTED, BUT REQUIRED FOR PROPER INSTALLATION SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR.

ALL WORK SHALL BE WARRANTED SATISFACTORY, IN MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE (1) YEAR, OR FOR THE PERIOD OF WARRANTY CUSTOMARY, OR STIPULATED FOR THE TRADE, CRAFT, OR PRODUCT, WHICHEVER IS LONGER. ONLY COMPETENT MECHANICS CAPABLE OF PRODUCING GOOD WORKMANSHIP CUSTOMARY TO THE TRADE SHOULD BE USED. COMMENCING WORK BY A CONTRACTOR OR SUBCONTRACTOR CONSTITUTES ACCEPTANCE OF THE CONDITIONS AND SURFACES CONCERNED. IF ANY SUCH CONDITIONS ARE UNACCEPTABLE, THE GENERAL CONTRACTOR SHALL BE NOTIFIED IMMEDIATELY, AND NO WORK SHALL BE PERFORMED UNTIL THE CONDITIONS ARE CORRECTED.

THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ALL FABRICATED ITEMS, AND PHYSICAL SAMPLES OF ALL FINISH MATERIALS SPECIFIED TO THE ARCHITECT FOR REVIEW.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH THE PROJECT SCOPE OF WORK, BUILDING STANDARDS, SCHEDULE AND DEADLINES. THE CONTRACTOR SHALL FURTHER BE RESPONSIBLE FOR ADVISING THE OWNER OF ALL LONG LEAD ITEMS AFFECTING THE PROJECT SCHEDULE AND SHALL, UPON REQUEST FROM THE OWNER, SUBMIT ORDER CONFIRMATIONS AND DELIVERY DATES FOR SUCH LONG LEAD ITEMS TO THE OWNER.

ALL CONTRACTOR OR SUPPLIER REQUESTS FOR SUBSTITUTIONS OF SPECIFIED ITEMS SHALL BE SUBMITTED, IN WRITING, ACCOMPANIED BY THE ALTERNATIVE PRODUCT INFORMATION, TO THE ARCHITECT, NO LATER THAN TEN (10) BUSINESS DAYS, PRIOR TO BID OPENING DATE. SUBSTITUTIONS SHALL ONLY BE CONSIDERED IF THEY DO NOT SACRIFICE QUALITY, FUNCTIONALITY, APPEARANCE OR WARRANTY. UNDER NO CIRCUMSTANCES WILL THE OWNER BE REQUIRED TO PROVE THAT A PRODUCT PROPOSED FOR SUBSTITUTION IS OR IS NOT OF EQUAL QUALITY TO THE PRODUCT SPECIFIED. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR SCALE THE DRAWINGS TO DETERMINE DIMENSIONS. REFER TO PLANS, SECTIONS AND DETAILS FOR ALL DIMENSIONAL INFORMATION.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION OF ALL SELECTED MATERIALS WHICH SHALL BE COMPLETE IN ALL RESPECTS PRIOR TO THE FINAL ACCEPTANCE, UNLESS OTHERWISE NOTED.

THE CONTRACTOR SHALL PRESERVE ALL PRINTED INSTRUCTIONS AND WARRANTY INFORMATION THAT IS PROVIDED WITH EQUIPMENT OR MATERIALS USED, AND DELIVER SAID PRINTED MATTER TO THE OWNER AT THE TIME OF SUBSTANTIAL COMPLETION. THE CONTRACTOR SHALL INSTRUCT THE OWNER IN THE PROPER USE OF THE EQUIPMENT FURNISHED BY THEIR TRADE.

GENERAL CONTRACTOR SHALL PROVIDE A THOROUGH CONSTRUCTION CLEANING AT PROJECT CLOSE OUT, PRIOR TO PUNCH LIST WALK THROUGH.

THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ALL FABRICATED ITEMS, AND PHYSICAL SAMPLES OF ALL FINISH MATERIALS SPECIFIED TO THE ARCHITECT FOR REVIEW.

REVIEWED SHOP DRAWINGS AND SUBMITTALS BY OTHERS SHALL NOT BE CONSIDERED AS PART OF THE CONTRACT DOCUMENTS. THE ARCHITECT ASSUMES NO RESPONSIBILITY FOR DRAWINGS, SCHEDULES, AND/OR SPECIFICATIONS FOR WORK ON THE PROJECT PREPARED BY OTHERS.

THE ARCHITECT WILL REVIEW ALL SHOP DRAWINGS, SUBMITTALS AND SAMPLES FOR CONFORMITY WITH THE CONTRACT DOCUMENTS AND RETURN THEM TO THE CONTRACTOR WITHIN SEVEN (7) WORKING DAYS EXCEPT AS MAY OTHERWISE BE PROVIDED FOR BY THE OWNER.

THE CONTRACTOR SHALL NOT REPRODUCE AND MARK UP ANY PART OF THE CONTRACT DOCUMENTS FOR SUBMITTAL AS A SHOP DRAWING. ANY SUCH SUBMITTAL WILL BE REJECTED.

ANY SUBMITTAL REQUIRED TO BE REVIEWED MORE THAN THE INITIAL REVIEW AND ONE (1) ADDITIONAL REVIEW, WILL BE CONSIDERED TO BE IN EXCESS OF THE SCOPE OF THE PROJECT. THE TIME REQUIRED FOR THIRD AND SUBSEQUENT REVIEWS OF A SUBMITTAL WILL BE PAID FOR BY THE CONTRACTOR TO THE ARCHITECT AT THE ARCHITECT'S STANDARD BILLING RATES, PLUS REIMBURSABLE EXPENSES.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ANY EXISTING CONDITIONS AND ALL CRITICAL DIMENSIONS ASSOCIATED WITH THE PROPOSED WORK. THE CONTRACTOR SHALL CONFIRM THAT ALL WORK OUTLINED WITHIN THE CONTRACT DOCUMENTS CAN BE ACCOMPLISHED AS SHOWN, PRIOR TO BID OPENING. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY CONDITIONS ENCOUNTERED WHICH MAY AFFECT BUILDING CODE COMPLIANCE, LIFE SAFETY, ISSUANCE OF CERTIFICATE OF OCCUPANCY, OR COMPLETION OF THE PROJECT AS DIRECTED IN THE CONTRACT DOCUMENTS.

NO ADDITIONAL FUNDS WILL BE APPROVED FOR WORK OMITTED FROM THE CONTRACTOR'S BID DUE TO LACK OF VERIFICATION BY THE CONTRACTOR, EXCEPT AS OTHERWISE APPROVED BY THE OWNER FOR WORK ASSOCIATED WITH HIDDEN CONDITIONS WHICH ARE NOT ACCESSIBLE PRIOR TO CONSTRUCTION.

REFER TO PROJECT MANUAL (WHEN APPLICABLE) FOR ADDITIONAL REQUIREMENTS AND DIRECTIONS. ALL INTERIOR FINISHES SHALL COMPLY WITH CHAPTER EIGHT (8) OF THE 2012 INTERNATIONAL BUILDING CODE WITH INDIANA AMENDMENTS.

LIGHT GAGE METAL STUDS, STUDS, THEIR COMPONENTS AND THEIR CONNECTIONS SHALL BE ENGINEERED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED. THE ENGINEER SHALL AFFIX THEIR SEAL AND SIGNATURE TO SHOP DRAWINGS AND CALCULATIONS SUBMITTED FOR REVIEW.

STEEL REQUIRED TO TRANSMIT GRAVITY AND/OR LATERAL LOADS TO THE STRUCTURE NOT DETAILED ON THE STRUCTURAL DRAWINGS IS THE RESPONSIBILITY OF THE METAL STUD SUPPLIER TO DESIGN, DETAIL, PROVIDE AND INSTALL.


METAL STUDS SHALL BE DESIGNED TO SUPPORT THE LOADS SHOWN IN THE DESIGN DATA IN ADDITION TO THE WEIGHT OF THE MATERIALS ATTACHED TO THE METAL STUDS. METAL STUDS SHALL BE DESIGNED USING THE LOAD COMBINATIONS IN SECTION 1605.3.1 OF THE INTERNATIONAL BUILDING CODE, 2012 EDITION. NO INCREASE IN ALLOWABLE STRESS IS ALLOWED.

DEFLECTION DUE TO LATERAL LOAD SHALL BE LIMITED TO $\frac{1}{160}$ OF THE STUD SPAN. FOR CANTILEVERS, THE DEFLECTION DUE TO LATERAL LOAD AT THE END OF THE CANTILEVER SHALL BE LIMITED TO $\frac{1}{160}$ OF THE CANTILEVER DIMENSION.

METAL STUD MANUFACTURER SHALL DETERMINE FINAL LAYOUT AND GAUGE OF STUDS TO MEET THE ARCHITECTURAL AND STRUCTURAL REQUIREMENTS.

WHERE ROUGH CARPENTRY IS IN CONTACT WITH THE GROUND, EXPOSED TO WEATHER OR IN AREAS OF HIGH RELATIVE HUMIDITY PROVIDE FASTENERS AND ANCHORAGES WITH A HOT DIP ZINC COATING OF G90 COMPLYING WITH ASTM A153 OR PROVIDE FASTENERS AND ANCHORAGES OF TYPE 304 STAINLESS STEEL.

ALL WOOD SHEATHING TO BE FIRE TREATED UNLESS NOTED OTHERWISE.



WALL TYPE GENERAL NOTES	
A. NOTE: WALL HEIGHT AS MARKED ON PLANS IN CONJUNCTION WITH WALL TYPE SYMBOL WILL SUPERCEDE WALL HEIGHTS AS SHOWN ABOVE. SEE SYMBOLS LEGEND THIS SHEET.	D. BRACE METAL STUD WALLS TO TOP OF STRUCTURAL STEEL ELEMENTS ABOVE CEILING PLANE. COORDINATE REQUIRED BRACE SPACING WITH STRUCTURAL ENGINEER PRIOR TO BEGINNING CONSTRUCTION.
B. PROVIDE DEEP LEG DEFLECTION TRACK AT TOP OF ALL METAL STUD WALLS WHERE STUDS EXTEND TO UNDERSIDE OF ROOF DECK OR STRUCTURE ABOVE.	E. REFER TO ROOM FINISH SCHEDULE FOR ALL FINISH SELECTIONS; CEILING TYPES AND HEIGHTS; AND TYPES, SIZES AND LOCATIONS ETC.
C. USE MOLD AND MILDEW RESISTANT GYPSUM WALLBOARD ON ALL PLUMBING WALLS. USE 5/8" CEMENT BOARD INSTEAD OF GYP BOARD BEHIND ALL TILE FINISHES.	F. ALL STUD WALLS CREATING A CONCEALED WALL SPACE TO HAVE FIREBLOCKING AT INTERVALS NOT EXCEEDING 10'-0" PER 718.2.2 IBC 2012

WALL TYPES

NOT TO SCALE



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET	09.16.22

220019

TYPICAL ACCESSIBILITY
DETAILS

A002

TYPICAL ADA INFO

WATER CLOSET: WATER CLOSETS SHALL BE 17" TO 19" AFF WHEN MEASURED TO THE TOP OF THE TOILET SEAT AND THE CENTER FOR THE FIXTURE SHALL BE 18" FROM ONE WALL WITH A CLEAR FLOOR SPACE OF 60" WIDE AND 59" DEEP FOR FLOOR MOUNT AND 56" DEEP FOR WALL MOUNT. FLUSH CONTROLS SHALL BE LOCATED ON THE OPEN SIDE OF THE WATER CLOSET.

SINK: SINK SHALL BE MOUNTED WITH THE RIM OR COUNTER NO HIGHER THAN 34" AFF PROVIDE A CLEARANCE OF AT LEAST 29" TO THE BOTTOM OF THE APRON WITH AN 8"X27" KNEE SPACE AND 6"X9" TOE SPACE. EXPOSED HOT WATER AND DRAIN PIPES UNDER SINKS SHALL BE INSULATED. FAUCETS SHALL BE LEVER-OPERATED, PUSH-TYPE AND MOTION SENSOR.

URINALS: URINALS SHALL BE STALL-TYPE OR WALL HUNG WITH THE RIM AT A MAXIMUM OF 17" AFF AND A 30" X 48" CLEAR FLOOR SPACE.


GRAB BARS: GRAB BARS SHALL BE 33" TO 36" AFF. THE GRAB BAR BEHIND THE WATER CLOSET SHALL BE 36" LONG AND NO MORE THAN 6" OF OF THE SIDE WALL. THE SIDE WALL GRAB BAR SHALL BE 42" LONG AND 12" OFF THE BACK WALL.

MIRROR: MIRRORS SHALL BE MOUNTED SO THE BOTTOM OF THE REFLECTING SURFACE IS NO MORE THAN 40" AFF.


PAPER TOWEL/DRYER: PAPER TOWEL/ DRYERS SHALL BE MOUNTED NO HIGHER THAN 48" AFF.

SOAP DISPENSER: SOAP DISPENSERS SHALL BE MOUNTED NO HIGHER THAN 48" AFF.


TOILET PAPER: TOILET PAPER DISPENSERS SHALL BE INSTALLED WITHIN 36" MAX. OF THE BACK WALL.




SHOWER STALL DIMENSIONS 8
1/2" = 1'-0"




FLOOR TRANSITIONS 9
6" = 1'-0"




REACH RANGES 10
1/4" = 1'-0"




TYPICAL MOUNTING HEIGHTS 1
1/2" = 1'-0"




ACCESSIBLE ROUTES 6
1/2" = 1'-0"




URINAL CLEAR SPACE 4
3/4" = 1'-0"




TOILET STALL DIMENSIONS 2
1/2" = 1'-0"




VERTICAL CLEARANCES 7
1/2" = 1'-0"



GRAB BAR DIMENSIONS 5
3" = 1'-0"



SINK CLEAR SPACE 3
3/4" = 1'-0"




LIFE SAFETY PLAN

1" = 50'-0" N

KEYED NOTES

1. EXIT, EXIT SIGN, AND EMERGENCY LIGHTING ABOVE DOOR INTERIOR WITH BATTERY BACKUP. EXTERIOR EGRESS LIGHTING ABOVE DOOR TIED TO BATTERY BACK UP.
2. PROPOSED FIRE EXTINGUISHER LOCATION. VERIFY WITH FIRE MARSHAL. FINAL QUANTITY AND LOCATIONS TO BE DETERMINED WITH FINAL RACKING PLAN AND FIRE DEPARTMENT REVIEW.
3. SEE CIVIL AND FIRE PROTECTION PLANS FOR FIRE DEPT. LEAD IN LOCATION.
4. PROVIDE BUILDING ADDRESS SIGNAGE @ THIS LOCATION.
5. THIS DOOR LABELED 'PUMP ROOM'.




CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086


ISSUE DATES

PERMIT SET	09.16.22
PUMP ROOM REVISIONS	07.25.22

220019


FLOOR PLAN

A100



KEY PLAN

CURRAN
ARCHITECTURE



SCANNELL
PROPERTIES

PROJECT INFORMATION


X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086


220019

AIOI



KEY PLAN






CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET 09.16.22
PUMP ROOM REVISION 07.25.22

220019

FLOOR PLAN - AREA A

A102

GENERAL NOTES



- CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL DIMENSIONS AND JOB CONDITIONS. ANY DEVIATION FROM WHAT IS NOTED IN DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT IMMEDIATELY.
- ALL DIMENSIONS SHOWN ARE FACE OF BRICK, MASONRY OR METAL STUD FRAMING, UNLESS OTHERWISE NOTED.
- PROVIDE APPROVED FIRE RATED STOPPING MATERIALS IN ANY OPENINGS IN FIRE RATED ASSEMBLIES.
- REFER TO DOOR AND WINDOW SCHEDULES FOR ALL MATERIALS, FINISHES, AND HARDWARE INFORMATION.
- REFER TO EXTERIOR ELEVATIONS FOR ALL BRICK, MASONRY, AND OTHER EXPANSION JOINT LOCATIONS.
- PRIOR TO ORDERING ANY PRODUCTS, CONTRACTOR SHALL SUBMIT SAMPLES TO THE ARCHITECT OF ALL FINISH MATERIALS TO BE USED ON THE PROJECT. THE CONTRACTOR SHALL BEAR SOLE RESPONSIBILITY FOR ANY MATERIALS ORDERED INCORRECTLY WHEN THAT MATERIAL WAS NOT REVIEWED BY THE ARCHITECT.
- PROVIDE CONCRETE FILLED STEEL PIPE BOLLARDS AT ALL REQUIRED UTILITY EQUIPMENT LOCATIONS SUCH AS GAS METERS, ELECTRICAL TRANSFORMER PANELS, ETC. COORDINATE WITH UTILITY COMPANY AND CONTRACTORS, WHEN APPLICABLE, FOR NECESSARY LOCATIONS. REFER TO CIVIL DRAWINGS FOR BOLLARD SPECIFICATIONS AND ADDITIONAL INFORMATION.
- ALL DOORS, UNLESS OTHERWISE NOTED, TO HAVE HINGE SIDE SET 4" FROM CORNER SHOWN TO OUTSIDE OF FRAME.
- UNLESS SPECIFIED ELSEWHERE, ALL INTERIOR SLABS AND SLAB INFILLS TO BE FF-50FL-35 OVERALL AND FF-35FL-25 LOCAL.
- ALL EXIT DOORS TO HAVE TACTILE EXIT SIGNAGE PER 703.4 OF THE ANSI 117.1 2009

KEYED NOTES

- STEEL COLUMN WITH PAINTED FINISH, REFER TO STRUCTURAL. PAINT SAFETY YELLOW TO 12'-0" AND WHITE TO DECK. PAINT COLUMNS W/ FIRE EXTINGUISHERS RED FULL HEIGHT.
- OVERHEAD DRIVE-IN DOOR. REFER TO ELEVATIONS AND DOOR SCHEDULE.
- RECESSED DOCK LEVELER WITH DOCK SEALS AND OVERHEAD DOCK DOOR. REFER TO ELEVATIONS, WALL SECTIONS, AND DOOR SCHEDULE.
- LOCATION OF FUTURE DOCK LEVELER AND OVERHEAD DOCK DOOR. PRECAST PANELS TO BE FABRICATED TO ALLOW FOR FUTURE REMOVAL OF CONCRETE IN THESE LOCATIONS. REFER TO ELEVATIONS FOR ADDITIONAL INFORMATION.
- STEEL DOCK STAIRS. REFER TO WALL SECTIONS AND DETAILS.
- INSULATED STEEL DOOR AND HOLLOW METAL FRAME. SEE ELEVATIONS AND DOOR SCHEDULE.
- THERMALLY BROKEN ANODIZED ALUMINUM AND INSULATED GLASS STOREFRONT SYSTEM.
- CONCRETE SLAB ON GRADE. SEE STRUCTURAL.
- CONCRETE FILLED STEEL BOLLARD - PAINTED. SEE DETAILS ON A502.
- 18" WIDE ROOF ACCESS LADDER WITH 1 INCH DIAMETER STEEL RUNGS AT 12" O.C. SECURE STRINGERS TO FLOOR TYPICAL BOTH SIDES PER LADDER SUPPLIER REQUIREMENTS. SEE STRUCTURAL PLANS.
- NOT USED.
- NOT USED.
- CMU WALL TO 12'-0" AFF WITH STUD AND DRYWALL TO DECK. REFER TO DETAIL 11A304.
- TYPICAL TILT WALL CONCRETE PANELS WITH INTERIOR INSULATION.
- SF3 WINDOW TO BE CENTERED IN PANEL, SEE WINDOW DETAILS FOR SIZE.
- CANOPY ABOVE. SEE ELEVATIONS AND WALL SECTIONS.
- ROOF DRAIN LEADERS. SIZE BY PLUMBING ENGINEER. COORDINATE PLACEMENT TO BE CENTERED ON PANEL JOINTS.
- INTERIOR OF TILT-UP WALL PANELS TO BE PAINTED SEMI GLOSS WHITE FULL HEIGHT.




KEY PLAN




FLOOR PLAN

1/16" = 1'-0" N




CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET 09.16.22
PUMP ROOM REVISION 07.25.22

220019

FLOOR PLAN - AREA B


A103

GENERAL NOTES


- CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL DIMENSIONS AND JOB CONDITIONS. ANY DEVIATION FROM WHAT IS NOTED IN DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT IMMEDIATELY.
- ALL DIMENSIONS SHOWN ARE FACE OF BRICK, MASONRY OR METAL STUD FRAMING, UNLESS OTHERWISE NOTED.
- PROVIDE APPROVED FIRE RATED STOPPING MATERIALS IN ANY OPENINGS IN FIRE RATED ASSEMBLIES.
- REFER TO DOOR AND WINDOW SCHEDULES FOR ALL MATERIALS, FINISHES, AND HARDWARE INFORMATION.
- REFER TO EXTERIOR ELEVATIONS FOR ALL BRICK, MASONRY, AND OTHER EXPANSION JOINT LOCATIONS.
- PRIOR TO ORDERING ANY PRODUCTS, CONTRACTOR SHALL SUBMIT SAMPLES TO THE ARCHITECT OF ALL FINISH MATERIALS TO BE USED ON THE PROJECT. THE CONTRACTOR SHALL BEAR SOLE RESPONSIBILITY FOR ANY MATERIALS ORDERED INCORRECTLY WHEN THAT MATERIAL WAS NOT REVIEWED BY THE ARCHITECT.
- PROVIDE CONCRETE FILLED STEEL PIPE BOLLARDS AT ALL REQUIRED UTILITY EQUIPMENT LOCATIONS SUCH AS GAS METERS, ELECTRICAL TRANSFORMER PANELS, ETC., COORDINATE WITH UTILITY COMPANY AND CONTRACTORS, WHEN APPLICABLE, FOR NECESSARY LOCATIONS. REFER TO CIVIL DRAWINGS FOR BOLLARD SPECIFICATIONS AND ADDITIONAL INFORMATION.
- ALL DOORS, UNLESS OTHERWISE NOTED, TO HAVE HINGE SIDE SET 4" FROM CORNER SHOWN TO OUTSIDE OF FRAME.
- UNLESS SPECIFIED ELSEWHERE, ALL INTERIOR SLABS AND SLAB INFILLS TO BE FF-50/FL-35 OVERALL AND FF-35/FL-25 LOCAL.
- ALL EXIT DOORS TO HAVE TACTILE EXIT SIGNAGE PER 703.4 OF THE ANSI 117.1 2009

KEYED NOTES

- STEEL COLUMN WITH PAINTED FINISH. REFER TO STRUCTURAL. PAINT SAFETY YELLOW TO 12'-0" AND WHITE TO DECK. PAINT COLUMNS W/ FIRE EXTINGUISHERS RED FULL HEIGHT.
- OVERHEAD DRIVE-IN DOOR. REFER TO ELEVATIONS AND DOOR SCHEDULE.
- RECESSED DOCK LEVELER WITH DOCK SEALS AND OVERHEAD DOCK DOOR. REFER TO ELEVATIONS, WALL SECTIONS, AND DOOR SCHEDULE.
- LOCATION OF FUTURE DOCK LEVELER AND OVERHEAD DOCK DOOR. PRECAST PANELS TO BE FABRICATED TO ALLOW FOR FUTURE REMOVAL OF CONCRETE IN THESE LOCATIONS. REFER TO ELEVATIONS FOR ADDITIONAL INFORMATION.
- STEEL DOCK STAIRS. REFER TO WALL SECTIONS AND DETAILS.
- INSULATED STEEL DOOR AND HOLLOW METAL FRAME. SEE ELEVATIONS AND DOOR SCHEDULE.
- THERMALLY BROKEN ANODIZED ALUMINUM AND INSULATED GLASS STOREFRONT SYSTEM.
- CONCRETE SLAB ON GRADE. SEE STRUCTURAL.
- CONCRETE FILLED STEEL BOLLARD - PAINTED. SEE DETAILS ON A502.
- 18" WIDE ROOF ACCESS LADDER WITH 1 INCH DIAMETER STEEL RUNGS AT 12" O.C. SECURE STRINGERS TO FLOOR TYPICAL BOTH SIDES PER LADDER SUPPLIER REQUIREMENTS. SEE STRUCTURAL PLANS.
- NOT USED.
- NOT USED.
- CMU WALL TO 12'-0" AFF WITH STUD AND DRYWALL TO DECK. REFER TO DETAIL 11A304.
- TYPICAL TILT WALL CONCRETE PANELS WITH INTERIOR INSULATION.
- SF3 WINDOW TO BE CENTERED IN PANEL. SEE WINDOW DETAILS FOR SIZE.
- CANOPY ABOVE. SEE ELEVATIONS AND WALL SECTIONS.
- ROOF DRAIN LEADERS. SIZE BY PLUMBING ENGINEER. COORDINATE PLACEMENT TO BE CENTERED ON PANEL JOINTS.
- INTERIOR OF TILT-UP WALL PANELS TO BE PAINTED SEMI GLOSS WHITE FULL HEIGHT.




KEY PLAN



FLOOR PLAN
1/16" = 1'-0"






CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET 09.16.22
PUMP ROOM REVISION 07.25.22

220019

FLOOR PLAN - AREA C

A104

GENERAL NOTES

- CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL DIMENSIONS AND JOB CONDITIONS. ANY DEVIATION FROM WHAT IS NOTED IN DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT IMMEDIATELY.
- ALL DIMENSIONS SHOWN ARE FACE OF BRICK, MASONRY OR METAL STUD FRAMING, UNLESS OTHERWISE NOTED.
- PROVIDE APPROVED FIRE RATED STOPPING MATERIALS IN ANY OPENINGS IN FIRE RATED ASSEMBLIES.
- REFER TO DOOR AND WINDOW SCHEDULES FOR ALL MATERIALS, FINISHES, AND HARDWARE INFORMATION.
- REFER TO EXTERIOR ELEVATIONS FOR ALL BRICK, MASONRY, AND OTHER EXPANSION JOINT LOCATIONS.
- PRIOR TO ORDERING ANY PRODUCTS, CONTRACTOR SHALL SUBMIT SAMPLES TO THE ARCHITECT OF ALL FINISH MATERIALS TO BE USED ON THE PROJECT. THE CONTRACTOR SHALL BEAR SOLE RESPONSIBILITY FOR ANY MATERIALS ORDERED INCORRECTLY WHEN THAT MATERIAL WAS NOT REVIEWED BY THE ARCHITECT.
- PROVIDE CONCRETE FILLED STEEL PIPE BOLLARDS AT ALL REQUIRED UTILITY EQUIPMENT LOCATIONS SUCH AS GAS METERS, ELECTRICAL TRANSFORMER PANELS, ETC., COORDINATE WITH UTILITY COMPANY AND CONTRACTORS, WHEN APPLICABLE, FOR NECESSARY LOCATIONS. REFER TO CIVIL DRAWINGS FOR BOLLARD SPECIFICATIONS AND ADDITIONAL INFORMATION.
- ALL DOORS, UNLESS OTHERWISE NOTED, TO HAVE HINGE SIDE SET 4" FROM CORNER SHOWN TO OUTSIDE OF FRAME.
- UNLESS SPECIFIED ELSEWHERE, ALL INTERIOR SLABS AND SLAB INFILLS TO BE FF-50/FL-35 OVERALL AND FF-35/FL-25 LOCAL.
- ALL EXIT DOORS TO HAVE TACTILE EXIT SIGNAGE PER 703.4 OF THE ANSI 117.1 2009

KEYED NOTES


- STEEL COLUMN WITH PAINTED FINISH. REFER TO STRUCTURAL. PAINT SAFETY YELLOW TO 12'-0" AND WHITE TO DECK. PAINT COLUMNS W/ FIRE EXTINGUISHERS RED FULL HEIGHT.
- OVERHEAD DRIVE-IN DOOR. REFER TO ELEVATIONS AND DOOR SCHEDULE.
- RECESSED DOCK LEVELER WITH DOCK SEALS AND OVERHEAD DOCK DOOR. REFER TO ELEVATIONS, WALL SECTIONS, AND DOOR SCHEDULE.
- LOCATION OF FUTURE DOCK LEVELER AND OVERHEAD DOCK DOOR. PRECAST PANELS TO BE FABRICATED TO ALLOW FOR FUTURE REMOVAL OF CONCRETE IN THESE LOCATIONS. REFER TO ELEVATIONS FOR ADDITIONAL INFORMATION.
- STEEL DOCK STAIRS. REFER TO WALL SECTIONS AND DETAILS.
- INSULATED STEEL DOOR AND HOLLOW METAL FRAME. SEE ELEVATIONS AND DOOR SCHEDULE.
- THERMALLY BROKEN ANODIZED ALUMINUM AND INSULATED GLASS STOREFRONT SYSTEM.
- CONCRETE SLAB ON GRADE. SEE STRUCTURAL.
- CONCRETE FILLED STEEL BOLLARD - PAINTED. SEE DETAILS ON A502.
- 18" WIDE ROOF ACCESS LADDER WITH 1 INCH DIAMETER STEEL RUNGS AT 12" O.C. SECURE STRINGERS TO FLOOR TYPICAL BOTH SIDES PER LADDER SUPPLIER REQUIREMENTS. SEE STRUCTURAL PLANS.
- NOT USED.
- NOT USED.
- CMU WALL TO 12'-0" AFF WITH STUD AND DRYWALL TO DECK. REFER TO DETAIL 11A304.
- TYPICAL TILT WALL CONCRETE PANELS WITH INTERIOR INSULATION.
- SF3 WINDOW TO BE CENTERED IN PANEL. SEE WINDOW DETAILS FOR SIZE.
- CANOPY ABOVE. SEE ELEVATIONS AND WALL SECTIONS.
- ROOF DRAIN LEADERS. SIZE BY PLUMBING ENGINEER. COORDINATE PLACEMENT TO BE CENTERED ON PANEL JOINTS.
- INTERIOR OF TILT-UP WALL PANELS TO BE PAINTED SEMI GLOSS WHITE FULL HEIGHT.


FLOOR PLAN

1/16" = 1'-0"



KEY PLAN






CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES


PERMIT SET	09.16.22
PUMP ROOM REVISION	07.25.22

220019


ROOF PLAN

A120

ROOF PLAN LEGEND



DENOTES TAPERED INSULATION OR ROOF
CRICKETS TO ROOF DRAIN LOCATIONS. SLOPE
MIN OF 1/4" FOOT AS INDICATED BY ARROWS OR
TWICE THE AMOUNT OF THE UNDERLYING
DECK WHICHEVER IS GREATER.




DENOTES ROOF SLOPE AT 1/4" / FOOT MINIMUM.

MECHANICALLY FASTENED 45 MIL TPO
MEMBRANE WITH RIGID POLYISOCYANURATE
INSULATION AT MINIMUM OF R-20. INSULATION
TO BE TWO LAYERS WITH STAGGERED JOINTS.
MEMBRANE SHEETS RUN PERPENDICULAR TO
THE DECK FLUTES. FOAM PERIMETER OF
INSULATION. SEE DETAIL.



ROOF TYPE #1

KEYED NOTES


- 4' x 4' INSULATED ROOF HATCH, COORDINATE LOCATION WITH
ROOF FRAMING BELOW. REFER TO A304 FOR DETAIL.
- MANUFACTURED PAN & GUTTER AWING W/ SCUPPER DIRECTED
TO LANDSCAPE BELOW. MAPES ILLUMIDECK OR EQUAL.
- PRERNISHED METAL CORING WITH CONTINUOUS HOLD DOWN
CLIP AT EDGE OF PANEL.
- ROOF DRAINS, REFER TO ENGINEERING DRAWINGS.
- OVERFLOW SCUPPER OPENING IN WALL. WRAP WITH ROOF
MEMBRANE. BOTTOM OF OPENING TO BE AT 2" ABOVE ROOF
MEMBRANE. COORDINATE FINAL LOCATION.
- ROOF MANUFACTURER'S TYPICAL EXPANSION JOINT DETAIL
COORDINATE PLACEMENT WITH ROOF FRAMING.
- TAPERED INSULATION TO DIRECT WATER TO ROOF DRAINS.
- LINE INDICATES APPROXIMATE LOCATION OF ROOF FRAMING.
SLOPE TO DRAIN. SEE ROOF FRAMING PLANS.



ROOF PLAN




KEY PLAN



CURRAN
ARCHITECTURE
5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3
X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086





ISSUE DATES


PERMIT SET	09.16.22
PUMP ROOM REVISION	07.25.22

220019

OVERALL
EXTERIOR ELEVATIONS

A200





CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE. AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET	09.16.22

220019
EXTERIOR ELEVATIONS


A201

GENERAL TILT WALL PAINT NOTES


- CONCRETE TO CURE 30 DAYS PRIOR TO PAINT OR VERIFY PH LEVEL IS BETWEEN 6-8. IF PH IS HIGHER THAN 8, A PRIMER THAT IS TOLERANT OF A HIGH ALKALINE SUBSTRATE IS REQUIRED. VERIFY PRODUCT WITH PAINT MANUFACTURER DATA SHEETS FOR ACCEPTABLE MATERIALS TO MEET THE PH OF THE PANELS. TYPICAL LOXON PRIMERS. PROVIDE REPORT STATING PH LEVEL OF PANEL PRIOR TO PAINT APPLICATION.
- TILT WALL CONTRACTOR TO VERIFY AND CONFIRM TO GENERAL CONTRACTOR THAT ALL BOND BREAKERS HAVE BEEN REMOVED FROM THE FACE OF THE CONCRETE VIA PRESSURE WASHING OR SAND BLASTING. PROCESS IS DEPENDENT ON THE TYPE OF BOND BREAKER USED. TILT WALL CONTRACTOR TO SUPPLY A LETTER CONFIRMING THAT BOND BREAKER IS REMOVED.
- PRIOR TO PAINTING, VERIFY THAT PRECAST CONCRETE MOISTURE LEVEL IS 15% OR LOWER.
- ALL ACRYLIC PAINTS TO BE 100% ACRYLIC SHERWIN WILLIAMS A-100, SUPER PAINT OR EQUAL.
- ELASTOMERIC PAINTS WILL BE ACCEPTABLE. CONPLEX OR SHERLASTIC OR EQUAL. MUST BE APPLIED AT 10 MILS RO 30+ MILS WET. MUST APPLY TWO COATS. VERIFY PH REQUIREMENTS WITH DATA SHEETS.
- BASE LINE SPECIFICATION FOR THIS PROJECT:
PRIMER COAT: LOXON SEALER A34V8300
SECOND COAT: A-100 EXTERIOR LATEX FLAT A6 SERIES

KEYED NOTES


- INSULATED STEEL DOOR. SEE DOOR SCHEDULE. VERIFY PAINT COLOR WITH OWNER.
- TYPICAL DOCK DOOR AND EQUIPMENT. SEE DOOR SCHEDULE
- TILT WALL CONCRETE PANEL W/ PAINTED FINISH. REVEALS CAST IN AS SHOWN. REFER TO WALL SECTIONS FOR ADDITIONAL DETAIL.
- TYPICAL OVERHEAD DRIVE IN DOOR. SEE DOOR SCHEDULE.
- DOCK STAIR AND BOLLARDS.
- ANODIZED ALUMINUM STOREFRONT. LOW-E GLASS.
- TYPICAL ANODIZED ALUMINUM STOREFRONT DOOR. GLASS AND ALUMINUM COLOR TO MATCH STOREFRONT. SEE DOOR SCHEDULE.
- PRE-FINISHED COPING/ROOF EDGE. SEE ROOF PLAN.
- ANODIZED ALUMINUM STOREFRONT CLERESTORY. LOW-E GLASS. SEE DOOR SCHEDULE. CENTERED IN PANEL.
- GRADE LEVEL. SEE CIVIL PLANS FOR MORE INFORMATION.
- MANUFACTURED PAN & GUTTER AWNING EQUAL TO MAPES LUMIDECK OR EQUAL. COORDINATE SCUPPER/DRAIN LOCATIONS IN THE FIELD WITH FINAL LANDSCAPE PLAN.
- KNOCK OUT PANEL IN TILT WALL. CENTERED IN PANEL. SIZED FOR 9'-0" x 10'-0" W/ REVEALS. PROVIDE REVEAL ALONG KNOCKOUT; 6" SOLID SECTION OF PANEL CENTERED ON REVEAL.
- REVEALS @ CAST IN PANEL. SEE WALL SECTIONS FOR DETAIL & HEIGHTS.
- WALL MOUNTED WALL PACK LIGHT FIXTURE MOUNTED AT 29'-8" AFF TO CENTER OF FIXTURE. SEE ELECTRICAL PLANS AND SITE LIGHTING PHOTOMETRIC PLANS FOR FURTHER INFORMATION. CENTER ON PANEL.
- TYPICAL PAINTED STEEL BOLLARDS.
- DASHED LINE INDICATES SLOPE OF ROOF LINE BEYOND. SEE ROOF PLAN FOR MORE INFORMATION.
- 24" WIDE x 8" TALL OVERFLOW SCUPPER OPENING IN WALL. BOTTOM TO BE AT 34'-0" AFF WITH CENTER OF OPENING 48" AWAY FROM COLUMN LINE AS SHOWN. COORDINATE WITH FINAL ROOF FRAMING ELEVATIONS.
- ROOF DRAIN ON INTERIOR SIDE OF PANEL. COORDINATE LOCATION TO BE CENTERED BETWEEN DOORS / KNOCKOUTS. AND TO AVOID CLERESTORY WINDOWS.




PARTIAL SOUTH ELEVATION 1
1/16" = 1'-0"



PARTIAL SOUTH ELEVATION 2
1/16" = 1'-0"



PARTIAL SOUTH ELEVATION 3
1/16" = 1'-0"



CURRAN
ARCHITECTURE
5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE. AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

**LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3**

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET	09.16.22
PUMP ROOM REVISION	07.25.22

220019

EXTERIOR ELEVATIONS


A202

**GENERAL TILT WALL
PAINT NOTES**


- CONCRETE TO CURE 30 DAYS PRIOR TO PAINT OR VERIFY PH LEVEL IS BETWEEN 8-8. IF PH IS HIGHER THAN 8, A PRIMER THAT IS TOLERANT OF A HIGH ALKALINE SUBSTRATE IS REQUIRED. VERIFY PRODUCT WITH PAINT MANUFACTURER DATA SHEETS FOR ACCEPTABLE MATERIALS TO MEET THE PH OF THE PANELS. TYPICAL LOXON PRIMERS. PROVIDE REPORT STATING PH LEVEL OF PANEL PRIOR TO PAINT APPLICATION.
- TILT WALL CONTRACTOR TO VERIFY AND CONFIRM TO GENERAL CONTRACTOR THAT ALL BOND BREAKERS HAVE BEEN REMOVED FROM THE FACE OF THE CONCRETE VIA PRESSURE WASHING OR SAND BLASTING. PROCESS IS DEPENDENT ON THE TYPE OF BOND BREAKER USED. TILT WALL CONTRACTOR TO SUPPLY A LETTER CONFIRMING THAT BOND BREAKER IS REMOVED.
- PRIOR TO PAINTING, VERIFY THAT PRECAST CONCRETE MOISTURE LEVEL IS 15% OR LOWER.
- ALL ACRYLIC PAINTS TO BE 100% ACRYLIC SHERWIN WILLIAMS A-100, SUPER PAINT OR EQUAL.
- ELASTOMERIC PAINTS WILL BE ACCEPTABLE. CONFLX OR SHERASTIC OR EQUAL. MUST BE APPLIED AT 10 MILS RO 30+ MILS WET. MUST APPLY TWO COATS. VERIFY PH REQUIREMENTS WITH DATA SHEETS.
- BASE LINE SPECIFICATION FOR THIS PROJECT:
PRIMER COAT: LOXON SEALER A34VIB300
SECOND COAT: A-100 EXTERIOR LATEX FLAT A6 SERIES

KEYED NOTES


- INSULATED STEEL DOOR. SEE DOOR SCHEDULE. VERIFY PAINT COLOR WITH OWNER.
- TYPICAL DOCK DOOR AND EQUIPMENT. SEE DOOR SCHEDULE
- TILT WALL CONCRETE PANEL W/ PAINTED FINISH. REVEALS CAST IN AS SHOWN. REFER TO WALL SECTIONS FOR ADDITIONAL DETAIL.
- TYPICAL OVERHEAD DRIVE IN DOOR. SEE DOOR SCHEDULE.
- DOCK STAIR AND BOLLARDS.
- ANODIZED ALUMINUM STOREFRONT. LOW-E GLASS.
- TYPICAL ANODIZED ALUMINUM STOREFRONT DOOR. GLASS AND ALUMINUM COLOR TO MATCH STOREFRONT. SEE DOOR SCHEDULE.
- PRE-FINISHED COPING/ROOF EDGE. SEE ROOF PLAN.
- ANODIZED ALUMINUM STOREFRONT CLERESTORY. LOW-E GLASS. SEE DOOR SCHEDULE. CENTERED IN PANEL.
- GRADE LEVEL. SEE CIVIL PLANS FOR MORE INFORMATION.
- MANUFACTURED PAN & GUTTER AWNING EQUAL TO MAPES LUMIDECK OR EQUAL. COORDINATE SCUPPER/DRAIN LOCATIONS IN THE FIELD WITH FINAL LANDSCAPE PLAN.
- KNOCK OUT PANEL IN TILT WALL. CENTERED IN PANEL. SIZED FOR 9'-0" x 10'-0" W/ REVEALS. PROVIDE REVEAL ALONG KNOCKOUT. 6" SOLID SECTION OF PANEL. CENTERED ON REVEAL.
- REVEALS @ CAST IN PANEL. SEE WALL SECTIONS FOR DETAIL & HEIGHTS.
- WALL MOUNTED WALL PACK LIGHT FIXTURE MOUNTED AT 29'-8" AFF TO CENTER OF FIXTURE. SEE ELECTRICAL PLANS AND SITE LIGHTING PHOTOMETRIC PLANS FOR FURTHER INFORMATION. CENTER ON PANEL.
- TYPICAL PAINTED STEEL BOLLARDS.
- DASHED LINE INDICATES SLOPE OF ROOF LINE BEYOND. SEE ROOF PLAN FOR MORE INFORMATION.
- 24" WIDE x 8" TALL OVERFLOW SCUPPER OPENING IN WALL. BOTTOM TO BE AT 34'-0" AFF WITH CENTER OF OPENING 48" AWAY FROM COLUMN LINE AS SHOWN. COORDINATE WITH FINAL ROOF FRAMING ELEVATIONS.
- ROOF DRAIN ON INTERIOR SIDE OF PANEL. COORDINATE LOCATION TO BE CENTERED BETWEEN DOORS / KNOCKOUTS. AND TO AVOID CLERESTORY WINDOWS.




PARTIAL NORTH ELEVATION 1
1/16" = 1'-0"



PARTIAL NORTH ELEVATION 2
1/16" = 1'-0"



PARTIAL NORTH ELEVATION 3
1/16" = 1'-0"




CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE. AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET	09.16.22
PUMP ROOM REVISION	07.25.22

220019

EXTERIOR ELEVATIONS


A203

GENERAL TILT WALL
PAINT NOTES

- CONCRETE TO CURE 30 DAYS PRIOR TO PAINT OR VERIFY PH LEVEL IS BETWEEN 6-8. IF PH IS HIGHER THAN 8, A PRIMER THAT IS TOLERANT OF A HIGH ALKALINE SUBSTRATE IS REQUIRED. VERIFY PRODUCT WITH PAINT MANUFACTURER DATA SHEETS FOR ACCEPTABLE MATERIALS TO MEET THE PH OF THE PANELS, TYPICAL LOXON PRIMERS. PROVIDE REPORT STATING PH LEVEL OF PANEL PRIOR TO PAINT APPLICATION.
- TILT WALL CONTRACTOR TO VERIFY AND CONFIRM TO GENERAL CONTRACTOR THAT ALL BOND BREAKERS HAVE BEEN REMOVED FROM THE FACE OF THE CONCRETE VIA PRESSURE WASHING OR SAND BLASTING. PROCESS IS DEPENDENT ON THE TYPE OF BOND BREAKER USED. TILT WALL CONTRACTOR TO SUPPLY A LETTER CONFIRMING THAT BOND BREAKER IS REMOVED.
- PRIOR TO PAINTING, VERIFY THAT PRECAST CONCRETE MOISTURE LEVEL IS 15% OR LOWER.
- ALL ACRYLIC PAINTS TO BE 100% ACRYLIC SHERWIN WILLIAMS A-100, SUPER PAINT OR EQUAL.
- ELASTOMERIC PAINTS WILL BE ACCEPTABLE. CONPLEX OR SHERLASTIC OR EQUAL. MUST BE APPLIED AT 10 MILS RO 30+ MILS WET. MUST APPLY TWO COATS. VERIFY PH REQUIREMENTS WITH DATA SHEETS.
- BASE LINE SPECIFICATION FOR THIS PROJECT:
PRIMER COAT: LOXON SEALER A34V8300
SECOND COAT: A-100 EXTERIOR LATEX FLAT A6 SERIES

KEYED NOTES

- INSULATED STEEL DOOR. SEE DOOR SCHEDULE. VERIFY PAINT COLOR WITH OWNER.
- TYPICAL DOCK DOOR AND EQUIPMENT. SEE DOOR SCHEDULE
- TILT WALL CONCRETE PANEL W/ PAINTED FINISH. REVEALS CAST IN AS SHOWN. REFER TO WALL SECTIONS FOR ADDITIONAL DETAIL.
- TYPICAL OVERHEAD DRIVE IN DOOR. SEE DOOR SCHEDULE.
- DOCK STAIR AND BOLLARDS.
- ANODIZED ALUMINUM STOREFRONT. LOW-E GLASS.
- TYPICAL ANODIZED ALUMINUM STOREFRONT DOOR. GLASS AND ALUMINUM COLOR TO MATCH STOREFRONT. SEE DOOR SCHEDULE.
- PRE-FINISHED COPING/ROOF EDGE. SEE ROOF PLAN.
- ANODIZED ALUMINUM STOREFRONT CLERESTORY. LOW-E GLASS. SEE DOOR SCHEDULE. CENTERED IN PANEL.
- GRADE LEVEL. SEE CIVIL PLANS FOR MORE INFORMATION.
- MANUFACTURED PAN & GUTTER AWNING EQUAL TO MAPES LUMIDECK OR EQUAL. COORDINATE SCUPPER/DRAIN LOCATIONS IN THE FIELD WITH FINAL LANDSCAPE PLAN.
- KNOCK OUT PANEL IN TILT WALL. CENTERED IN PANEL. SIZED FOR 9'-0" x 10'-0" W/ REVEALS. PROVIDE REVEAL ALONG KNOCKOUT. 6" SOLID SECTION OF PANEL. CENTERED ON REVEAL.
- REVEALS @ CAST IN PANEL. SEE WALL SECTIONS FOR DETAIL & HEIGHTS.
- WALL MOUNTED WALL PACK LIGHT FIXTURE MOUNTED AT 29'-4" AFF TO CENTER OF FIXTURE. SEE ELECTRICAL PLANS AND SITE LIGHTING PHOTOMETRIC PLANS FOR FURTHER INFORMATION. CENTER ON PANEL.
- TYPICAL PAINTED STEEL BOLLARDS.
- DASHED LINE INDICATES SLOPE OF ROOF LINE BEYOND. SEE ROOF PLAN FOR MORE INFORMATION.
- 24" WIDE x 8" TALL OVERFLOW SCUPPER OPENING IN WALL. BOTTOM TO BE AT 34'-0" AFF WITH CENTER OF OPENING 48" AWAY FROM COLUMN LINE AS SHOWN. COORDINATE WITH FINAL ROOF FRAMING ELEVATIONS.
- ROOF DRAIN ON INTERIOR SIDE OF PANEL. COORDINATE LOCATION TO BE CENTERED BETWEEN DOORS / KNOCKOUTS. AND TO AVOID CLERESTORY WINDOWS.




CURRAN
ARCHITECTURE
5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3
X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET	09.16.22


220019

WALL SECTIONS


A301

KEYED NOTES


1. ROOF MEMBRANE AND INSULATION BOARD. SEE ROOF PLAN FOR INFORMATION. UNDERSIDE OF DECKING FACTORY FINISHED, COLOR WHITE. MINIMUM SLOPE 1/4 INCH PER FOOT. TYPICAL BUILDING ROOFING UNLESS NOTED OTHERWISE.
2. WRAP ROOF MEMBRANE UP BACK SIDE OF TILTWALL PANEL, OVER TREATED 2x BLOCKING ATTACHED TO TILTWALL PANEL. PROVIDE PRE-FINISHED METAL COPING WITH CONTINUOUS HOLD-DOWN CLIP. FOR ALL ROOF EDGES UNLESS NOTED OTHERWISE.
3. DOCK SEAL AND DOCK BUMPER.
4. PRE-FINISHED INSULATED STEEL OVERHEAD DOOR. REFER TO DOOR SCHEDULE.
5. TYPICAL WALL PANELS: TILTWALL CONCRETE PANELS WITH STEEL FORM PAINT READY EXTERIOR FINISH. REFER TO 11/A301 FOR TYPICAL VERTICAL SPACING OF REVEALS. REFER TO ELEVATIONS FOR SPECIFIC REVEAL LAYOUT PER PANEL.
6. STRUCTURAL STEEL FRAMING. REFER TO ENGINEERING DRAWINGS. COORDINATE STRUCTURAL WITH TILTWALL MANUFACTURER. ORIENTATION OF FRAMING MAY VARY PER SECTION. REFER TO STRUCTURAL DRAWINGS FOR MORE INFORMATION.
7. THERMALLY BROKEN ALUMINUM STOREFRONT FRAMING WITH 1" INSULATED TINTED GLASS. REFER TO STOREFRONT ELEVATIONS FOR MORE INFORMATION.
8. CONCRETE SLAB ON GRADE. SEE STRUCTURAL.
9. REINFORCED CONCRETE FOUNDATION. SEE STRUCTURAL.
10. SEE CIVIL FOR EXTERIOR GRADING, SIDEWALKS, ETC..
11. PROVIDE HINGED LOCKING GATE ON LADDER.
12. 1/2" EXPANSION JOINT.
13. 2" RIGID INSULATION BOARD, TYPICAL. UNDERSIDE OF SLAB TO TOP OF FOOTING. AT DOORS AND LOCATIONS WHERE DOORS OR STOREFRONT EXTENDS TO FLOOR SLAB, EXTEND THE INSULATION HORIZONTALLY UNDER THE SLAB A MINIMUM OF 4'.
14. DOCK LEVELER PIT. VERIFY DIMENSIONS WITH SUBMITTAL PACKAGE OF LEVELER UNIT. SEE STRUCTURAL FOR REINFORCEMENT INFORMATION.
15. MANUFACTURED PAN AND GUTTER AWNING SYSTEM WITH SCUPPER DIRECTED TO LANDSCAPE BELOW, MAPS LUNDECK OR EQUAL. FINISH AND SCUPPER LOCATION TO BE SELECTED BY ARCHITECT.
16. REVEALS CAST IN TILTWALL WALL. REFER TO 8/A501. SEE ELEVATIONS FOR LOCATIONS OF REVEALS ON EACH PANEL.
17. TYPICAL SEALANT JOINT.
18. INSULATED STEEL DOOR AND HOLLOW METAL FRAME. REFER TO FLOOR PLAN FOR NUMBER AND DOOR SCHEDULE FOR SIZE, HARDWARE, AND FINISH.
19. FOAM ENCLOSURE, TYPICAL ENTIRE PERIMETER OF DECK. VERIFY MATERIAL AND DETAILS. COORDINATE WITH DECK MANUFACTURER/SUPPLIER. FOAM BETWEEN BLOCKING AND TOP LAYER OF ROOF INSULATION. EXTEND DOWN TO DECK AND JOIST ANGLES.
20. PRE-FINISHED METAL COPING WITH CONT. HOLD-DOWN CLIP. COLOR SELECTED BY ARCHITECT FROM FULL RANGE OF MANUFACTURER'S COLORS.
21. INSULATION IS TO EXTEND TO BACK OF DOCK LEVELER PIT, AND EXTEND VERTICALLY UP SIDES AND BACK OF PIT TO COMPLETELY INSULATE PIT PERIMETER.
22. GALVANIZED STEEL DOCK STAIR ASSEMBLY. REFER TO 11 AND 12/A501 FOR INFORMATION.
23. 4' X 4' INSULATED ROOF HATCH. COORDINATE PLACEMENT WITH ROOF FRAMING. LADDER TO BE CENTERED BELOW HATCH.
24. "LADDER UP" SUPPORT POST.
25. PROVIDE BRACING AS REQUIRED BY LADDER SUPPLIER.
26. OSHA COMPLIANT ROOF ACCESS LADDER CAGE.
27. LADDER BRACKETS. ANCHOR TO SLAB, ROOF FRAMING AND PLATFORM.
28. 18 INCH WIDE STEEL LADDER WITH 1 INCH DIAMETER STEEL RUNGS AT 12 INCHES O.C. SECURE STRINGERS TO FLOOR - TYPICAL BOTH SIDES PER LADDER SUPPLIER REQUIREMENTS.
29. 1 1/2" DIA STEEL 2 LINE GUARD RAIL WITH 4" TALL TOE BOARD AT PLATFORM LEVEL.
30. PROVIDE ADD ALTERNATE PRICING TO PROVIDE CONDUIT FOR FUTURE TRAILER RESTRAINT.
31. CONCRETE FILLED PIPE BOLLARDS, PAINTED SAFETY YELLOW. REFER TO CIVIL DRAWINGS FOR MORE INFORMATION.
32. FLASHING TO EXTEND OVER EDGE OF CONCRETE. PROVIDE HEMMED EDGE.
33. STICK PIN INSULATION W/ MINIMUM R-13 VALUE. USE ADHESIVES & FASTENERS TO SECURE INSULATION.
34. 8" REINFORCED CMU WALL. REFER TO STRUCTURAL DWGS.
35. HONEYWELL GUIDELOC VERTICAL RAIL AND FALL ARRESTER SYSTEM MOUNTED TO CENTER OF RUNGS, OR EQUAL.
36. CONSTRUCT 1 HR RATED WALL ON TOP OF CMU TO ROOF DECK. REFER TO WALL TYPE W4A ON A501.
37. TYPICAL DEFLECTION TRACK. REFER TO A501 FOR DETAIL.
38. CONTRACTOR TO COORDINATE REQUIRED OVERHEAD DOOR CLEARANCES WITH INSULATION PLACEMENT.




SECTION 4
3/8" = 1'-0"




SECTION 3
3/8" = 1'-0"



SECTION 2
3/8" = 1'-0"




SECTION 1
3/8" = 1'-0"




CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET	09.16.22


220019

WALL SECTIONS


A302

KEYED NOTES


1. ROOF MEMBRANE AND INSULATION BOARD. SEE ROOF PLAN FOR INFORMATION. UNDERSIDE OF DECKING FACTORY FINISHED. COLOR WHITE. MINIMUM SLOPE 1/4 INCH PER FOOT. TYPICAL BUILDING ROOFING UNLESS NOTED OTHERWISE.
2. WRAP ROOF MEMBRANE UP BACK SIDE OF TILTWALL PANEL. OVER TREATED 2x BLOCKING ATTACHED TO TILTWALL PANEL. PROVIDE PRE-FINISHED METAL COPING WITH CONTINUOUS HOLD DOWN CLIP. FOR ALL ROOF EDGES UNLESS NOTED OTHERWISE.
3. DOCK SEAL AND DOCK BUMPER.
4. PRE-FINISHED INSULATED STEEL OVERHEAD DOOR. REFER TO DOOR SCHEDULE.
5. TYPICAL WALL PANELS: TILTWALL CONCRETE PANELS WITH STEEL FORM PAINT READY EXTERIOR FINISH. REFER TO I/A301 FOR TYPICAL VERTICAL SPACING OF REVEALS. REFER TO ELEVATIONS FOR SPECIFIC REVEAL LAYOUT PER PANEL.
6. STRUCTURAL STEEL FRAMING. REFER TO ENGINEERING DRAWINGS. COORDINATE STRUCTURAL WITH TILTWALL MANUFACTURER. ORIENTATION OF FRAMING MAY VARY PER SECTION. REFER TO STRUCTURAL DRAWINGS FOR MORE INFORMATION.
7. THERMALLY BROKEN ALUMINUM STOREFRONT FRAMING WITH 1" INSULATED TINTED GLASS. REFER TO STOREFRONT ELEVATIONS FOR MORE INFORMATION.
8. CONCRETE SLAB ON GRADE. SEE STRUCTURAL.
9. REINFORCED CONCRETE FOUNDATION. SEE STRUCTURAL.
10. SEE CIVIL FOR EXTERIOR GRADING, SIDEWALKS, ETC...
11. PROVIDE HINGED LOCKING GATE ON LADDER.
12. 1/2" EXPANSION JOINT.
13. 2" RIGID INSULATION BOARD, TYPICAL UNDERSIDE OF SLAB TO TOP OF FOOTING. AT DOORS AND LOCATIONS WHERE DOORS OR STOREFRONT EXTENDS TO FLOOR SLAB, EXTEND THE INSULATION HORIZONTALLY UNDER THE SLAB A MINIMUM OF 4'.
14. DOCK LEVELER PIT. VERIFY DIMENSIONS WITH SUBMITTAL PACKAGE OF LEVELER UNIT. SEE STRUCTURAL FOR REINFORCEMENT INFORMATION.
15. MANUFACTURED PAN AND GUTTER AWNING SYSTEM WITH SCUPPER DIRECTED TO LANDSCAPE BELOW, MAPS LUMIDECK OR EQUAL. FINISH AND SCUPPER LOCATION TO BE SELECTED BY ARCHITECT.
16. REVEALS CAST IN TILTWALL WALL. REFER TO 8/A501. SEE ELEVATIONS FOR LOCATIONS OF REVEALS ON EACH PANEL.
17. TYPICAL SEALANT JOINT.
18. INSULATED STEEL DOOR AND HOLLOW METAL FRAME. REFER TO FLOOR PLAN FOR NUMBER AND DOOR SCHEDULE FOR SIZE, HARDWARE, AND FINISH.
19. FOAM ENCLOSURE, TYPICAL ENTIRE PERIMETER OF DECK. VERIFY MATERIAL AND DETAILS. COORDINATE WITH DECK MANUFACTURER/SUPPLIER. FOAM BETWEEN BLOCKING AND TOP LAYER OF ROOF INSULATION. EXTEND DOWN TO DECK AND JOIST ANGLES.
20. PRE-FINISHED METAL COPING WITH CONT. HOLD DOWN CLIP. COLOR SELECTED BY ARCHITECT FROM FULL RANGE OF MANUFACTURER'S COLORS.
21. INSULATION IS TO EXTEND TO BACK OF DOCK LEVELER PIT, AND EXTEND VERTICALLY UP SIDES AND BACK OF PIT TO COMPLETELY INSULATE PIT PERIMETER.
22. GALVANIZED STEEL DOCK STAIR ASSEMBLY. REFER TO I1 AND I2/A501 FOR INFORMATION.
23. 4' X 4' INSULATED ROOF HATCH. COORDINATE PLACEMENT WITH ROOF FRAMING. LADDER TO BE CENTERED BELOW HATCH.
24. "LADDER UP" SUPPORT POST.
25. PROVIDE BRACING AS REQUIRED BY LADDER SUPPLIER.
26. OSHA COMPLIANT ROOF ACCESS LADDER CAGE.
27. LADDER BRACKETS. ANCHOR TO SLAB, ROOF FRAMING AND PLATFORM.
28. 18 INCH WIDE STEEL LADDER WITH 1 INCH DIAMETER STEEL RUNGS AT 12 INCHES O.C. SECURE STRINGERS TO FLOOR - TYPICAL BOTH SIDES PER LADDER SUPPLIER REQUIREMENTS.
29. 1 1/2" DIA STEEL 2 LINE GUARD RAIL WITH 4" TALL TOE BOARD AT PLATFORM LEVEL.
30. PROVIDE ADD ALTERNATE PRICING TO PROVIDE CONDUIT FOR FUTURE TRAILER RESTRAINT.
31. CONCRETE FILLED PIPE BOLLARDS, PAINTED SAFETY YELLOW. REFER TO CIVIL DRAWINGS FOR MORE INFORMATION.
32. FLASHING TO EXTEND OVER EDGE OF CONCRETE. PROVIDE HEMMED EDGE.
33. STICK PIN INSULATION W/ MINIMUM R-13 VALUE. USE ADHESIVES & FASTENERS TO SECURE INSULATION.
34. 8" REINFORCED CMU WALL. REFER TO STRUCTURAL DWGS.
35. HONEYWELL GUIDELock VERTICAL RAIL AND FALL ARRESTER SYSTEM MOUNTED TO CENTER OF RUNGS, OR EQUAL.
36. CONSTRUCT 1 HR RATED WALL ON TOP OF CMU TO ROOF DECK. REFER TO WALL TYPE W4A ON A001.
37. TYPICAL DEFLECTION TRACK. REFER TO A501 FOR DETAIL.
38. CONTRACTOR TO COORDINATE REQUIRED OVERHEAD DOOR CLEARANCES WITH INSULATION PLACEMENT.




SECTION 4
3/8" = 1'-0"



SECTION 3
3/8" = 1'-0"




SECTION 2
3/8" = 1'-0"




SECTION 1
3/8" = 1'-0"

CURRAN
ARCHITECTURE



CERTIFICATION






PROJECT INFORMATION


LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

PERMIT SET 09.16.22

WALL SECTIONS


A303






CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

ISSUE DATES

PERMIT SET 09.16.22


220019

WALL SECTIONS

A304

KEYED NOTES


1. ROOF MEMBRANE AND INSULATION BOARD. SEE ROOF PLAN FOR INFORMATION. UNDERSIDE OF DECKING FACTORY FINISHED, COLOR WHITE. MINIMUM SLOPE 1/4 INCH PER FOOT. TYPICAL BUILDING ROOFING UNLESS NOTED OTHERWISE.
2. WRAP ROOF MEMBRANE UP BACK SIDE OF TILTWALL PANEL, OVER TREATED 2x BLOCKING ATTACHED TO TILTWALL PANEL. PROVIDE PRE-FINISHED METAL COPING WITH CONTINUOUS HOLD-DOWN CLIP, FOR ALL ROOF EDGES UNLESS NOTED OTHERWISE.
3. DOCK SEAL AND DOCK BUMPER.
4. PRE-FINISHED INSULATED STEEL OVERHEAD DOOR. REFER TO DOOR SCHEDULE.
5. TYPICAL WALL PANELS: TILTWALL CONCRETE PANELS WITH STEEL FORM PAINT READY EXTERIOR FINISH. REFER TO I/A301 FOR TYPICAL VERTICAL SPACING OF REVEALS. REFER TO ELEVATIONS FOR SPECIFIC REVEAL LAYOUT PER PANEL.
6. STRUCTURAL STEEL FRAMING. REFER TO ENGINEERING DRAWINGS. COORDINATE STRUCTURAL WITH TILTWALL MANUFACTURER. ORIENTATION OF FRAMING MAY VARY PER SECTION. REFER TO STRUCTURAL DRAWINGS FOR MORE INFORMATION.
7. THERMALLY BROKEN ALUMINUM STOREFRONT FRAMING WITH 1" INSULATED TINTED GLASS. REFER TO STOREFRONT ELEVATIONS FOR MORE INFORMATION.
8. CONCRETE SLAB ON GRADE. SEE STRUCTURAL.
9. REINFORCED CONCRETE FOUNDATION. SEE STRUCTURAL.
10. SEE CIVIL FOR EXTERIOR GRADING, SIDEWALKS, ETC..
11. PROVIDE HINGED LOCKING GATE ON LADDER.
12. 1/2" EXPANSION JOINT.
13. 2" RIGID INSULATION BOARD, TYPICAL UNDERSIDE OF SLAB TO TOP OF FOOTING. AT DOORS AND LOCATIONS WHERE DOORS OR STOREFRONT EXTENDS TO FLOOR SLAB, EXTEND THE INSULATION HORIZONTALLY UNDER THE SLAB A MINIMUM OF 4'.
14. DOCK LEVELER PIT. VERIFY DIMENSIONS WITH SUBMITTAL PACKAGE OF LEVELER UNIT. SEE STRUCTURAL FOR REINFORCEMENT INFORMATION.
15. MANUFACTURED PAN AND GUTTER AWNING SYSTEM WITH SCUPPER DIRECTED TO LANDSCAPE BELOW, MAPES LUMIDECK OR EQUAL. FINISH AND SCUPPER LOCATION TO BE SELECTED BY ARCHITECT.
16. REVEALS CAST IN TILTWALL WALL. REFER TO 8/A501. SEE ELEVATIONS FOR LOCATIONS OF REVEALS ON EACH PANEL.
17. TYPICAL SEALANT JOINT.
18. INSULATED STEEL DOOR AND HOLLOW METAL FRAME. REFER TO FLOOR PLAN FOR NUMBER AND DOOR SCHEDULE FOR SIZE, HARDWARE, AND FINISH.
19. FOAM ENCLOSURE, TYPICAL ENTIRE PERIMETER OF DECK. VERIFY MATERIAL AND DETAILS. COORDINATE WITH DECK MANUFACTURER/SUPPLIER. FOAM BETWEEN BLOCKING AND TOP LAYER OF ROOF INSULATION. EXTEND DOWN TO DECK AND JOIST ANGLES.
20. PRE-FINISHED METAL COPING WITH CONT. HOLD-DOWN CLIP. COLOR SELECTED BY ARCHITECT FROM FULL RANGE OF MANUFACTURER'S COLORS.
21. INSULATION IS TO EXTEND TO BACK OF DOCK LEVELER PIT, AND EXTEND VERTICALLY UP SIDES AND BACK OF PIT TO COMPLETELY INSULATE PIT PERIMETER.
22. GALVANIZED STEEL DOCK STAIR ASSEMBLY. REFER TO I1 AND I2/A501 FOR INFORMATION.
23. 4' X 4' INSULATED ROOF HATCH. COORDINATE PLACEMENT WITH ROOF FRAMING. LADDER TO BE CENTERED BELOW HATCH.
24. "LADDER UP" SUPPORT POST.
25. PROVIDE BRACING AS REQUIRED BY LADDER SUPPLIER.
26. OSHA COMPLIANT ROOF ACCESS LADDER CAGE.
27. LADDER BRACKETS. ANCHOR TO SLAB, ROOF FRAMING AND PLATFORM.
28. 18 INCH WIDE STEEL LADDER WITH 1 INCH DIAMETER STEEL RUNGS AT 12 INCHES O.C. SECURE STRINGERS TO FLOOR - TYPICAL BOTH SIDES PER LADDER SUPPLIER REQUIREMENTS.
29. 1 1/2" DIA STEEL 2 LINE GUARD RAIL WITH 4" TALL TOE BOARD AT PLATFORM LEVEL.
30. PROVIDE ADD ALTERNATE PRICING TO PROVIDE CONDUIT FOR FUTURE TRAILER RESTRAINT.
31. CONCRETE FILLED PIPE BOLLARDS, PAINTED SAFETY YELLOW. REFER TO CIVIL DRAWINGS FOR MORE INFORMATION.
32. FLASHING TO EXTEND OVER EDGE OF CONCRETE. PROVIDE HEMMED EDGE.
33. STICK PIN INSULATION W/ MINIMUM R-13 VALUE. USE ADHESIVES & FASTENERS TO SECURE INSULATION.
34. 8" REINFORCED CMU WALL. REFER TO STRUCTURAL DWGS.
35. HONEYWELL GUIDELOC VERTICAL RAIL AND FALL ARRESTER SYSTEM MOUNTED TO CENTER OF RUNGS, OR EQUAL.
36. CONSTRUCT 1 HR RATED WALL ON TOP OF CMU TO ROOF DECK. REFER TO WALL TYPE W4A ON A001.
37. TYPICAL DEFLECTION TRACK. REFER TO A501 FOR DETAIL.
38. CONTRACTOR TO COORDINATE REQUIRED OVERHEAD DOOR CLEARANCES WITH INSULATION PLACEMENT.



SECTION

2


3/8" = 1'-0"



SECTION

1

3/8" = 1'-0"




CURRAN ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL PROPERTIES

CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086


ISSUE DATES

PERMIT SET 09.16.22


220019

SECTIONS AND DETAILS


A501




DRIVE IN DOOR JAMB DETAIL **13**
1 1/2" = 1'-0"




DOOR JAMB SECTION **10**
3" = 1'-0"




TILT WALL OVERLAP WALL DETAIL **7**
1 1/2" = 1'-0"




**TILT WALL TO WALL SECTION DETAIL
DRYWALL "LID" CONDITION** **4**
1 1/2" = 1'-0"




TILT WALL TO WALL PLAN DETAIL **1**
1 1/2" = 1'-0"




DOCK DOOR JAMB DETAIL **14**
1 1/2" = 1'-0"




WALL AT MULLION DETAIL **11**
3" = 1'-0"




TYPICAL REVEAL DETAIL **8**
3" = 1'-0"




TILT WALL BOX CORNER DETAIL **5**
1 1/2" = 1'-0"




TILT WALL TO WALL PLAN DETAIL **2**
1 1/2" = 1'-0"




STOREFRONT/CURTAINWALL **15**
1 1/2" = 1'-0"




DRIVE IN DOOR DETAIL **12**
1 1/2" = 1'-0"



DEFLECTION TRACK DETAIL **9**
3" = 1'-0"



TILT WALL MITER CORNER DETAIL **6**
1 1/2" = 1'-0"



TILT WALL TO WALL PLAN DETAIL **3**
1 1/2" = 1'-0"


CURRAN

ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086


ISSUE DATES

PERMIT SET	09.16.22


220019

SECTIONS AND DETAILS


A503




DOOR THRESHOLD 4
1 1/2" = 1'-0"




TILT WALL PLAN DETAIL 1
1 1/2" = 1'-0"




TYPICAL PARAPET DETAIL 5
1 1/2" = 1'-0"



TILT WALL PLAN DETAIL 2
1 1/2" = 1'-0"



OVERFLOW SCUPPER DETAIL 6
1 1/2" = 1'-0"



TILT WALL PLAN DETAIL 3
1 1/2" = 1'-0"

GENERAL DOOR AND
GLAZING NOTES

- A. ALL PRE-FINISHED WOOD DOORS SHALL BE SOLID CORE WITH WOOD VENEER, MARSHFIELD OR EQUIVALENT. PROVIDE FINISH SAMPLE AND DOOR CONSTRUCTION DIAGRAM FOR APPROVAL AND HARDWARE BLOCKING COORDINATION. VENEER TO BE WHITE BIRCH OR MAPLE, FREE OF DARK GRAINS UNLESS OTHERWISE NOTED.
- B. WOOD DOORS SHALL ONLY BE INSTALLED IN CONDITIONED SPACE.
- C. ALL HARDWARE TO BE MINIMUM 6 PIN BEST COMPATIBLE SYSTEM. COORDINATE KEYING WITH OWNER.
- D. TEMPERED AND ANNEALED GLASS TO BE CLEANED PER MANUFACTURER REQUIREMENTS. NYLON CLOTH METHODS PREFERRED. DO NOT USE RAZOR BLADES ON GLASS.
- E. GLASS AROUND DOORS AND IN DOORS SHALL BE TEMPERED UNLESS OTHERWISE NOTED IN ELEVATIONS.
- F. ANY RATED DOORS TO HAVE LABEL INSTALLED IN JAMB.
- G. ALL EXITS DOORS TO HAVE TACTILE EXIT SIGNAGE PER 703.4 OF THE ANSI 117.1 2009.
- H. INSTALL OWNER PROVIDED ADA COMPLIANT RESTROOM SIGNAGE. VERIFY WITH ARCHITECT.

GLAZING TYPES

- A. SECTION OF GLAZING REQUIRED TO BE 1" INSULATED GREY TINTED GLASS.
- B. SECTION OF GLAZING REQUIRED TO BE 1" INSULATED TEMPERED GLASS.
- C. SECTION OF GLAZING REQUIRED TO BE 1/4" GLASS.
- D. SECTION OF GLAZING REQUIRED TO BE 1/4" TEMPERED GLASS.
- E. SECTION OF GLAZING REQUIRED TO BE 1" INSULATED TEMPERED GREY TINTED SPANDREL GLASS.

EXTERIOR GLAZING MUST MEET THE FOLLOWING SPECIFICATIONS FOR ENERGY CODE COMPLIANCE:

LOW "E" COATING
"U" VALUE - MINIMUM OF 0.28
"SHGC" VALUE - MAXIMUM OF 0.47

DOOR HARDWARE

HARDWARE SET 1

- 2 CONTINUOUS HINGES
2 PANIC DEVICES
1 PERIMETER SEAL
1 THRESHOLD
2 SWEEPS
2 HD CLOSERS
2 PULLS

FINISH: MATCH STOREFRONT

HARDWARE SET 2

- 3 BALL BEARING HINGES
1 PANIC DEVICE W/ LEVER
1 PERIMETER SEAL
1 THRESHOLD W/ DRAINAGE SUBSILL
1 SWEEP
1 HD CLOSER
1 DRIP TRIM

FINISH: US26D


HARDWARE SET 3

- 3 BALL BEARING HINGES
1 STOREROOM LOCKSET
1 PERIMETER SEAL
1 THRESHOLD W/ DRAINAGE SUBSILL
1 SWEEP
1 HD CLOSER
1 DRIP TRIM

FINISH: US26D


DOOR SCHEDULE												
MARK	DOOR	SIZE	MATERIAL	GLAZING	FINISH	RATING	FRAME	MATERIAL	FINISH	RATING	HARDWARE	REMARKS
101	OV1	12-0 X 14-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
102	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
103	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
104	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
105	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
106	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
107	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
108	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
109	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
110	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
111	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
112	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
113	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
114	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
115	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
116	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
117	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
118	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
119	OV1	12-0 X 14-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
120	F	3-6 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	3	
121	OV1	12-0 X 14-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
122	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
123	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
124	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
125	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
126	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
127	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
128	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
129	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
130	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
131	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
132	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
133	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
134	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
135	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
136	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
137	OV2	9-0 x 10-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
138	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
139	OV1	12-0 X 14-0	INSUL STL	B	PREFINISHED	-	BY MFR	BY MFR	BY MFR	-	BY MFR	
140	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
141	FG	(2) 3-0 x 7-0	ALUM	B	CLEAR ANOD	-	SFI	ALUM	CLEAR ANOD	-	I	
142	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
143	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
144	FG	(2) 3-0 x 7-0	ALUM	B	CLEAR ANOD	-	SFI	ALUM	CLEAR ANOD	-	I	
145	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
146	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
147	FG	(2) 3-0 x 7-0	ALUM	B	CLEAR ANOD	-	SFI	ALUM	CLEAR ANOD	-	I	
148	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
149	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	
150	FG	(2) 3-0 x 7-0	ALUM	B	CLEAR ANOD	-	SFI	ALUM	CLEAR ANOD	-	I	
151	F	3-0 x 7-0	INSUL STL	-	PAINT	-	FI	HM	PAINT	-	2	

- REMARKS:
1. ALUMINUM STOREFRONT FRAMING WITH DOOR. DOOR IS RESPONSIBILITY OF ALUMINUM STOREFRONT FRAMING MANUFACTURER AND MUST BE SIZED TO FIT INTO FRAMING AS DETAILED. PROVIDE WIDE STILE DOOR, WITH MINIMUM 10" BOTTOM RAIL FOR ADA COMPLIANCE.
2. SEE STOREFRONT ELEVATIONS FOR FRAME INFORMATION.
3. PROVIDE INSULATED STEEL DOOR AND FRAME. PAINT TO MATCH ADJACENT MATERIALS. COLOR TO BE SELECTED BY ARCHITECT.
4. PROVIDE AUTOMATIC OPENER. COORDINATE WITH ENGINEERING DRAWINGS FOR POWER.
5. GLAZING IN EXTERIOR DOOR TO BE TEMPERED INSULATED GLASS SIMILAR TO GLAZING TYPE 1b.
6. REFER TO SHEET A502 FOR TYPICAL HOLLOW METAL HEAD/JAMB DETAIL.
7. REFER TO SHEET A501 FOR TYPICAL OVERHEAD DOOR JAMB DETAIL.
8. REFER TO A502 FOR TYPICAL STOREFRONT HEAD/JAMB DETAIL.




DOOR TYPES

NOT TO SCALE




DOOR FRAME TYPES

NOT TO SCALE



STOREFRONT ELEVATIONS

NOT TO SCALE



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

wallace



Wallace Engineering
Structural Consultants, Inc.

Structural and Civil Consultants
1741 McGee Street
Kansas City, Missouri 64108
816.421.8282, Fax 816.421.8338

CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300

S0.0

GENERAL NOTES

DESIGN PARAMETERS

1.	BUILDING CODE	2018 INTERNATIONAL BUILDING CODE (IBC)
	OCCUPANCY CATEGORY	II
2.	LIVE LOADS	
	A. ROOF – NON–REDUCIBLE	20 PSF
	B. SLAB–ON–GRADE	350 PSF
3.	ROOF SNOW LOAD	
	A. GROUND SNOW LOAD, Pg	20 PSF
	B. FLAT ROOF SNOW LOAD, Pf	20 PSF
	C. SNOW EXPOSURE FACTOR, Ce	1.0
	D. SNOW LOAD IMPORTANCE FACTOR, I	1.0
	E. THERMAL FACTOR, Ct (BUILDING)	1.0
	F. SNOW DRIFT	PER REFERENCED CODE
4.	WIND DESIGN DATA	
	A. ULTIMATE WIND SPEED (3 SECOND GUST), V	109 MPH
	B. WIND IMPORTANCE FACTOR, I	1.00
	C. WIND EXPOSURE CATEGORY	C
	D. INTERNAL PRESSURE COEFFICIENT, Gcpi	+/- 0.18
	E. DESIGN WIND PRESSURE ON COMPONENTS AND CLADDING (1.0W)	
	1) WALLS (500 SQUARE FEET EFFECTIVE WIND AREA)	
	END ZONES	23.7 PSF
	INTERIOR ZONES	23.7 PSF
	2) ROOF (10 SQUARE FEET EFFECTIVE WIND AREA FOR DECK ATTACHMENT)	
	CORNER ZONES	89.1 PSF
	END ZONES	65.4 PSF
	INTERIOR ZONE 1	49.6 PSF
	INTERIOR ZONE 2	28.5 PSF
	F. WIDTH OF END ZONES, α	18.9 FT
5.	EARTHQUAKE DESIGN DATA	
	A. SEISMIC IMPORTANCE FACTOR, I	1.0
	B. MAPPED SPECTRAL RESPONSE ACCELERATION, Ss	9.9 %
	C. MAPPED SPECTRAL RESPONSE ACCELERATION, S1	6.8 %
	D. SITE CLASS	C
	E. SPECTRAL RESPONSE COEFFICIENT, Sds	0.086
	F. SPECTRAL RESPONSE COEFFICIENT, Sd1	0.068
	G. SEISMIC DESIGN CATEGORY	B
	H. STRUCTURAL SYSTEM (DUAL SYSTEM)	
	1) BASIC SEISMIC FORCE–RESISTING SYSTEM TYPE	H. STEEL SYSTEM
	2) VERTICAL ELEMENT TYPE	1) STEEL SYSTEM NOT SPECIFICALLY DETAILED FOR SEISMIC RESISTANCE
	3) BASIC SEISMIC FORCE–RESISTING SYSTEM TYPE	A. BEARING WALL SYSTEMS
	4) VERTICAL ELEMENT TYPE	2) ORDINARY PRECAST SHEAR WALLS
	5) DESIGN BASE SHEAR, LRFD	0.029 W
	6) SEISMIC RESPONSE COEFFICIENT, Cs	0.029
	7) CONTROLLING RESPONSE MODIFICATION FACTOR, R	3
J.	ANALYSIS PROCEDURE	EQUIVALENT LATERAL FORCE
6.	DEAD LOAD	
	A. EPDM MEMBRANE	0.3 PSF
	B. RIGID INSULATION	0.7 PSF
	C. ROOF DECK	2.0 PSF
	D. LIGHTS, PLUMBING, & HVAC	3.0 PSF
	E. SPRINKLERS	2.0 PSF
	F. STEEL JOISTS	2.0 PSF
	G. STEEL GIRDERS	2.0 PSF
	H. TOTAL DEAD LOAD ON JOISTS	10.0 PSF
	J. TOTAL DEAD LOAD ON COLUMNS	12.0 PSF

GENERAL NOTES

GENERAL

- STRUCTURAL ELEMENTS ARE NON–SELF SUPPORTING AND REQUIRE INTERACTION WITH OTHER ELEMENTS FOR STABILITY AND RESISTANCE TO LATERAL FORCES. FRAMING AND WALLS SHALL BE TEMPORARILY BRACED BY THE CONTRACTOR UNTIL PERMANENT BRACING, ROOF DECKS, AND WALLS HAVE BEEN INSTALLED AND CONNECTIONS BETWEEN THESE ELEMENTS HAVE BEEN MADE.
- THE STRUCTURAL DRAWINGS REPRESENT THE FINISHED STRUCTURE AND DO NOT INDICATE THE METHOD OF CONSTRUCTION, UNLESS NOTED OTHERWISE. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE MEANS, METHODS, TECHNIQUES, SEQUENCES, AND OPERATION OF CONSTRUCTION AND SAFETY PRECAUTIONS AND PROGRAMS INCIDENTAL THERETO.
- THE SIZE AND LOCATION OF EQUIPMENT PADS AND PENETRATIONS THROUGH THE STRUCTURE FOR MECHANICAL, ELECTRICAL, AND PLUMBING WORK SHALL BE VERIFIED BY THE CONTRACTOR. PENETRATIONS SHALL BE SUBJECT TO APPROVAL BY THE STRUCTURAL ENGINEER. REFER TO MECHANICAL, ELECTRICAL, AND PLUMBING DRAWINGS FOR OPENING LOCATIONS NOT SHOWN ON THE STRUCTURAL DRAWINGS.
- USE ONLY DIMENSIONS INDICATED ON THE DRAWINGS. DO NOT SCALE DRAWINGS OR USE ANY DIMENSIONS TAKEN FROM ELECTRONIC DRAWING FILES. CONTRACTOR SHALL COORDINATE IN–PLACE DIMENSIONS BASED ON TOLERANCES OF THE RESPECTIVE TRADES.
- ASSUME EQUAL SPACING IF NOT INDICATED ON DRAWINGS.
- THE GENERAL NOTES ARE AN INTEGRAL PART OF THE CONTRACT DOCUMENTS AND SHALL BE USED IN CONJUNCTION WITH THE STRUCTURAL DRAWINGS. WHERE REQUIREMENTS INDICATED ON THE STRUCTURAL DRAWINGS DIFFER FROM THE GENERAL NOTES, NOTIFY THE ARCHITECT AND THE STRUCTURAL ENGINEER.
- THE STRUCTURAL DRAWINGS ARE NOT INTENDED TO BE AN INDEPENDENT SET OF THE CONSTRUCTION DOCUMENTS. SEE ARCHITECTURAL, MEP, CIVIL AND OTHER DRAWINGS FOR INFORMATION RELATED TO THE STRUCTURAL WORK. THE CONTRACTOR SHALL VERIFY COORDINATION OF THE DESIRED DETAILS PRIOR TO CONSTRUCTION AND NOTIFY THE ARCHITECT AND THE STRUCTURAL ENGINEER IF ADDITIONAL COORDINATION IS REQUIRED.
- ARCHITECTURAL, MECHANICAL AND ELECTRICAL COMPONENTS AND SYSTEMS SHALL BE DESIGNED AND CONSTRUCTED TO RESIST SEISMIC FORCES AS DETERMINED IN CHAPTER 13 OF ASCE 7.

FOUNDATIONS

- FOUNDATION DESIGNS, SUBGRADE PREPARATION NOTES, AND STRUCTURAL EARTH MOVING SPECIFICATION ARE BASED ON THE RECOMMENDATIONS PROVIDED IN THE GEOTECHNICAL REPORT, BY: OLSSON, INC. OF 1700 E 123RD ST., OLATHE, KANSAS 64080 (PHONE NO. 913–829–0078) DATED: FEBRUARY 2022.
- FOOTING DESIGNS ARE BASED ON AN ASSUMED STABLE, NON–EXPANSIVE SOIL WITH AN ALLOWABLE FOUNDATION PRESSURE OF 2500 PSF WITH A MAXIMUM DIFFERENTIAL SETTLEMENT OF 3/4 INCH. CONTRACTOR SHALL HIRE A GEOTECHNICAL ENGINEER TO DETERMINE WHETHER OR NOT SOIL MEETS THIS MINIMUM CRITERIA AND IF IT DOES NOT, SHALL NOTIFY ENGINEER SO THAT THE FOUNDATION MAY BE REDESIGNED ACCORDINGLY.
- CONTRACTOR AND TESTING LABORATORY REPRESENTATIVE SHALL READ THE GEOTECHNICAL REPORT AND BECOME THOROUGHLY FAMILIAR WITH SITE AND SUBGRADE INFORMATION GIVEN THEREIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING EXACT QUANTITIES OF CUT AND FILL FOR ESTIMATING AND CONSTRUCTION. SUBGRADE SHALL BE PREPARED AS NOTED IN THE GEOTECHNICAL REPORT.
- A QUALIFIED AND REGISTERED GEOTECHNICAL ENGINEER, LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED, AND WORKING FOR THE TESTING LABORATORY, SHALL DETERMINE CONFORMANCE OF THE FOUNDATION BEARING STRATA WITH THE FOUNDATION DESIGN CRITERIA ABOVE, AND ALL OTHER CONTRACT DOCUMENTS. TESTING LABORATORY SHALL NOTIFY CONTRACTOR, ARCHITECT AND CONSULTING ENGINEER OF ANY CONDITIONS NOT IN ACCORDANCE WITH FOUNDATION DESIGN CRITERIA OR CONTRACT DOCUMENTS.

- USE ONLY STRUCTURAL FILL MATERIAL AS NOTED IN THE GEOTECHNICAL REPORT FOR FILL BELOW BUILDING AND FIVE FEET BEYOND THE EDGES OF THE BUILDING.
- FOUNDATION WALLS SHALL HAVE ADEQUATE TEMPORARY BRACING INSTALLED BY THE CONTRACTOR BEFORE BACKFILL IS PLACED AGAINST THEM. TEMPORARY BRACING SHALL NOT BE REMOVED UNTIL WALL IS PERMANENTLY BRACED.
- FOOTINGS SHALL BE POURED AGAINST UNDISTURBED SOIL, UNLESS NOTED OTHERWISE.
- AVOID DAMAGE TO UNDERGROUND UTILITIES SUCH AS WATER MAINS, SANITARY SEWERS, BURIED CABLES, ETC., WHICH MIGHT EXTEND ACROSS OR ADJOIN SITE.

CONCRETE

- MINIMUM COMPRESSIVE STRENGTH (f'c) AT THE END OF 28 DAYS SHALL BE AS FOLLOWS:
A. FOOTINGS (GRADE BEAMS) 3000 PSI U.N.O. ON PLAN
B. FOUNDATION WALLS 3000 PSI
C. SLABS–ON–GRADE 4000 PSI
D. CONCRETE WALL PANELS (MINIMUM STRENGTH) 4000 PSI
MAXIMUM WATER/CEMENT RATIO = 0.48 TO 0.50 FOR FOOTINGS AND 0.52 FOR SLABS–ON–GRADE AND PRECAST WALLS PANELS
SLUMP LIMITS = 4" + 1"
CONCRETE SHALL BE NORMAL WEIGHT (145 PCF), UNLESS NOTED OTHERWISE.
CEMENTITIOUS MATERIALS CONTENT SHALL NOT BE LESS THAN 520 POUNDS PER CUBIC YARD. USE OF ANY FLY ASH IN FLOOR SLAB MIXES SHALL BE NO MORE THAN 20%.
AIR–ENTRAINED IS NOT REQUIRED FOR STRUCTURAL CONCRETE.
- AGGREGATES SHALL COMPLY WITH ASTM C 33 AND SHALL BE FREE OF DELETERIOUS MATTER AND SHALL BE MADE OF COARSE LIMESTONE OR GRANITE AGGREGATES.
- MATERIALS OR ADMIXTURES SHALL NOT CONTAIN ANY CALCIUM CHLORIDE. IF ADMIXTURES ARE UTILIZED, THEY SHALL BE COMPATIBLE WITH OTHER ADMIXTURES AND MUST NOT CONTRIBUTE WATER–SOLUBLE CHLORIDE IONS EXCEEDING THOSE PERMITTED IN HARDENED CONCRETE.
- REINFORCING STEEL SHALL MEET THE FOLLOWING:
A. DEFORMED BARS ASTM A615, GRADE 60
B. WELDABLE DEFORMED BARS ASTM A706, GRADE 60
C. WELDED WIRE FABRIC ASTM A185
- WHERE DOWELS ARE INDICATED BUT NOT SIZED, PROVIDE DOWELS THAT MATCH SIZE AND LOCATION OF MAIN REINFORCING STEEL AND LAP SPLICE WITH THE MAIN REINFORCING STEEL. REINFORCING BARS SHALL BE SPLICED AS NOTED IN THE REINFORCING LAP SCHEDULE.
- REFER TO ACI 318 LATEST EDITION FOR CONCRETE COVER, ACI 315 LATEST EDITION FOR DETAILING, FABRICATION, PLACEMENT AND SUPPORT PRACTICES, ACI 347 FOR FORMWORK, ACI 305 FOR HOT WEATHER CONCRETING, ACI 306 FOR COLD WEATHER CONCRETING, AND ACI 301 LATEST EDITION FOR STANDARD PRACTICE FOR MIXING AND PLACING CONCRETE. PROVIDE CONCRETE COVER DIMENSIONS IN SHOP DRAWINGS FOR STRUCTURAL ENGINEER REVIEW.
- "C.J." INDICATES SAW CUT CONTRACTION JOINT OR DOWELED CONSTRUCTION JOINT IN SLAB–ON–GRADE. SLAB POURS SHALL BE SEPARATED BY A DOWELED CONSTRUCTION JOINT. CONTRACTION/CONSTRUCTION JOINTS SHALL BE LOCATED AS SHOWN ON PLANS OR AS DIRECTED BY THE STRUCTURAL ENGINEER.
- PROVIDE CORNER BARS THAT MATCH CONTINUOUS REINFORCEMENT SIZE AND QUANTITY AT INTERSECTIONS AND CORNERS OF FOUNDATIONS.
- REINFORCING BAR SUPPORTS SHALL BE BOLSTERS, CHAIRS, SPACERS AND OTHER DEVICES TO HOLD REINFORCING BARS AND WELDED WIRE REINFORCEMENT IN PLACE. MANUFACTURE BAR SUPPORTS FROM STEEL, PLASTIC OR PRECAST CONCRETE ACCORDING TO CRSI'S "MANUAL OF STANDARD PRACTICE" OF GREATER COMPRESSIVE STRENGTH THAN THE CONCRETE PLACED IN.
- FORM–FACING PANELS THAT WILL BE EXPOSED TO VIEW SHALL BE CONSTRUCTED TO MINIMIZE THE NUMBER OF JOINTS AND SHALL BE MADE OF PLYWOOD, METAL OR OTHER APPROVED PANEL MATERIAL. PLYWOOD MUST COMPLY WITH DOC PS 1 AND BE CLASS 1 OR BETTER.
- CHAMFER EXTERIOR CORNERS AND EDGES OF PERMANENTLY EXPOSED CONCRETE.
- THE CONCRETE SLABS SHOWN ON THE STRUCTURAL DRAWINGS HAVE BEEN DESIGNED FOR THE FINISHED STRUCTURE AND HAVE NOT BEEN DESIGNED FOR MEANS AND METHODS OF CONSTRUCTION, INCLUDING BUT NOT LIMITED TO, FORK LIFTS, MAN LIFTS, AND OTHER VEHICULAR TRAFFIC.
- A VAPOR RETARDER NOT LESS THAN 10 MILS THICK SHALL BE INSTALLED ONLY AT AREAS NOTATED ON THE CONSTRUCTION DOCUMENTS. THE RETARDER SHALL BE INSTALLED PER THE MANUFACTURER'S RECOMMENDATION WITH JOINTS USING THE MANUFACTURER'S RECOMMENDED ADHESIVE OR PRESSURE SENSITIVE JOINT TAPE AND INCLUDING THE MANUFACTURER'S PROPRIETARY PENETRATION FLASHING FOR ALL THROUGH–SLAB PENETRATIONS. LAP VAPOR RETARDER JOINTS 6 INCHES MINIMUM.
- CONCRETE SLABS–ON–GRADE SHALL BE CONSTRUCTED WITH A HARD TROWEL FINISH AND BE FINISHED ACCORDING TO ASTM E 1155 TO ACHIEVE THE MINIMUM TOLERANCES BELOW:
OVERALL VALUES: FF = 50 FL = 35
LOCAL VALUES: FF = 25 FL = 20
- THE CONCRETE SLAB–ON–GRADE SHALL BE CURED WITH AN APPROVED CURING MATERIAL THAT HAS BEEN SUBMITTED AND APPROVED BY THE ARCHITECT AND ENGINEER OF RECORD. THE FLOOR SHALL BE CURED WITH ONE COAT OF HARDENER/DENSIFIER (ASHFORD FORMULA SEALER OR APPROVED ALTERNATE).
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS, OPENINGS, BLOCKOUTS, RECESSES, ELEVATIONS, ANCHOR RODS AND EMBED LOCATIONS PRIOR TO CONCRETE PLACEMENT. THE CONTRACTOR SHALL VERIFY WITH ARCHITECTURAL, STRUCTURAL AND MEP DRAWINGS FOR LOCATIONS OF REQUIRED COORDINATION ITEMS. CONTRACTOR SHALL CONTACT THE ARCHITECT OR ENGINEER IF AN ERROR OR OMISSION OCCURS AFTER CONCRETE PLACEMENT.
- ANCHOR BOLTS AND EMBED PLATES SHALL BE TIED INTO THE REBAR CAGE AND HELD IN PLACE WITH A RIGID TEMPLATE TO PREVENT MOVEMENT DURING CONCRETE PLACEMENT.
- NON–SHRINK GROUT SHALL BE PRE–MIXED, NON–SHRINKING WITH A MINIMUM COMPRESSIBE STRENGTH OF 5000 PSI IN 28 DAYS CONFORMING TO USACE SPECIFICATIONS NO. CRD–C621.

CONCRETE WALL PANELS

- THE STRUCTURAL DRAWINGS REPRESENT THE REQUIRED FINAL IN PLACE LOADINGS FOR THE CONCRETE WALL PANELS. THE PANELS SHALL BE DESIGNED BY THE TILT–UP SUPPLIER FOR THE FINAL IN PLACE LOADINGS ALONG WITH BEING DESIGNED FOR ERECTION STRESSES, TEMPORARY BRACING OR LIFTING OF THE WALL PANELS. WALL PANELS SHALL BE DESIGNED AND DETAILED TO ADHERE TO ALL LOCAL CODES.
- THE CONTRACTOR SHALL PROVIDE SHOP DRAWINGS FOR THE TILT–UP WALL PANELS. SHOP DRAWINGS SHALL INCLUDE CALCULATIONS FOR FINAL IN PLACE LOADINGS, ERECTION, LIFTING AND TEMPORARY BRACING OF THE WALL PANELS ALONG WITH ANY OTHER ADDITIONAL CONSTRUCTION CONSIDERATIONS. SHOP DRAWINGS AND CALCULATIONS FOR THE CONSTRUCTION CONSIDERATIONS SHALL BE DESIGNED, SEALED AND SIGNED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED. DESIGN CALCULATIONS SHALL SHOW STRESSES IN THE PANELS FOR THE LOADS PRESCRIBED IN THE CONSTRUCTION DOCUMENTS ALONG WITH THERMAL DIFFERENTIAL AND ERECTION AND LIFTING FORCES. THE DEFERRED SUBMITTAL DOCUMENTS SHALL BE SUBMITTED TO THE ARCHITECT OR ENGINEER OF RECORD WHO SHALL REVIEW THEM AND FORWARD THEM TO THE BUILDING OFFICIAL AS REQUESTED WITH A NOTATION INDICATING THAT THE DEFERRED SUBMITTAL DOCUMENTS HAVE BEEN REVIEWED AND BEEN FOUND TO BE IN GENERAL CONFORMANCE TO THE DESIGN OF THE BUILDING. THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THE DESIGN AND SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL.
- THE CONTRACTOR SHALL VERIFY THAT THE PROPOSED TILT–UP WALL PANELS ARE CAPABLE OF MEETING THE FINAL IN PLACE AND ERECTION REQUIREMENTS PRIOR TO BEGINNING THE WORK. ANY DEVIATIONS FROM THE WALL PANELS SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE QUALIFIED IN THE CONTRACTOR'S BID.
- THE CONTRACTOR SHALL PROVIDE ADEQUATE VERTICAL AND LATERAL SYSTEM COMPONENTS TO SUPPORT THE LOADINGS STIPULATED IN THE CONSTRUCTION DOCUMENTS. THE FOUNDATIONS HAVE BEEN DESIGNED BASED ON THESE LOADING REQUIREMENTS. ANY DEVIATIONS IN THE LOADINGS SHALL BE APPROVED BY THE ENGINEER OF RECORD PRIOR TO PROCEEDING.
- THE CONCRETE WALL PANELS SHALL CONFORM TO ACI 301, ACI 318, ACI 551, CONCRETE REINFORCING STEEL INSTITUTE (CRSI) "MANUAL OF STANDARD PRACTICE", AND AWS D1.4 STRUCTURAL WELDING CODE FOR REINFORCING STEEL. SEE THE CONCRETE GENERAL NOTES FOR ADDITIONAL CONFORMANCE SPECIFICATIONS.
- SEE THE CONCRETE GENERAL NOTES AND SPECIFICATIONS FOR MIX DESIGN DATA AND REQUIREMENTS.
- THE TILT–UP WALL PANEL SHALL ADHERE TO THE MECHANISMS SET FORTH IN THE STRUCTURAL CONSTRUCTION DOCUMENTS. ADDITIONALLY, THE DESIGN SHALL INCLUDE ALL BOLTS, EMBEDMENT PLATES, BLOCKOUTS, FUTURE KNOCKOUT PANEL LOCATIONS, BRACING AND SUPPORTING STRUCTURE.
- SEE THE STEEL GENERAL NOTES AND SPECIFICATIONS FOR SECTION PROPERTY REQUIREMENTS. ALL STEEL SHAPES, PLATES, ANCHORS, BOLTS, NUTS AND WASHERS SHALL BE HOT DIP GALVANIZED AFTER FABRICATION.
- CAST–IN–PLACE ANCHORS SHALL BE HEADED STUDS OR DEFORMED BAR ANCHORS. ASTM 615 REINFORCING BARS SHALL NOT BE USED AS ANCHORS.
- ALL WELDS SHALL BE PERFORMED BY A AWS CERTIFIED WELDER AND IN ACCORDANCE WITH AWS D1.1 "STRUCTURAL WELDING CODE" AND AWS D1.4 "STRUCTURAL WELDING CODE FOR REINFORCING STEEL". ALL WELDS SHALL BE PAINTED WITH ZINC RICH REPAIR PAINT AFTER WELDING.
- ALL WELDS FOR DEFORMED BAR ANCHORS SHALL USE E90XX ELECTRODES.
- PROVIDE BEARING PADS AND GROUT MATERIALS AS REQUIRED PER CODE AND INDUSTRY STANDARDS.
- COORDINATE WITH THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS ANY ADDITIONAL REQUIREMENTS FOR DIMENSIONS, FINISH, REVEALS AND ANY OTHER REQUIREMENTS OF THE CONCRETE WALL PANELS.

- CONTRACTOR SHALL ERECT THE CONCRETE WALL PANELS SUCH THAT IT IS SAFE FOR PERSONNEL AND PROPERTY AND PROVIDE BRACING TO PROTECT THE PANELS AGAINST WIND, SEISMIC AND FORCES THAT MAY OCCUR THROUGHOUT THE CONSTRUCTION PROCESS. TEMPORARY BRACING SHALL REMAIN IN PLACE UNTIL ALL PERMANENT BRACING, DECKING, CONNECTIONS AND WALL PANELS HAVE BEEN FULLY INSTALLED.
- CONCRETE WALL PANELS SHALL BE ERECTED TO ADHERE TO THE TOLERANCES OF THE LATEST AMERICAN CONCRETE INSTITUTE SPECIFICATIONS. ERECTION TOLERANCES SHALL BE COORDINATED WITH THE STEEL SUPPLIER TO PROVIDE PROPER FIT–UP. DEFLECTIONS OF THE STRUCTURAL STEEL SYSTEM MAY OCCUR DURING CONCRETE WALL PANEL ERECTION. THESE DEFLECTIONS MAY REQUIRE ADJUSTMENT AND RESETTING OF CONCRETE WALL PANELS IN ORDER TO MEET THE TOLERANCES. THE CONTRACTOR SHALL BE AWARE OF THIS ITERATION PROCESS IN HIS BID AND IS RESPONSIBLE FOR THE TOLERANCES BEING MET.
- THE CONCRETE SLABS SHOWN ON THE STRUCTURAL DRAWINGS HAVE BEEN DESIGNED FOR THE FINISHED STRUCTURE AND HAVE NOT BEEN DESIGNED FOR CRANE USE AND CONCRETE WALL PANEL BRACING. THE CONTRACTOR SHALL VERIFY THE SLAB ADEQUACY AND SUBMIT PROPOSED DESIGNED, IF REQUIRED, TO THE STRUCTURAL ENGINEER FOR REVIEW.
- ALL CONCRETE WALL PANELS COMPONENTS SHALL ADHERE TO THE DETAILING, FABRICATION AND ERECTION REQUIREMENTS OF THE LATEST EDITIONS OF ACI 301 (SPECIFICATIONS FOR CONCRETE), ACI 318 (STRUCTURAL CONCRETE BUILDING CODE), AWS D1.4 (WELDING CODE FOR REINFORCING STEEL), CRSI (MANUAL OF STANDARD PRACTICE), PCI MNL 116 (MANUAL FOR QUALITY CONTROL FOR PLANS AND PRODUCTION OF PRECAST CONCRETE PRODUCTS), PCI MNL 120 (PCI DESIGN HANDBOOK) AND PCI MNL 135 (TOLERANCE MANUAL FOR PRECAST PRESTRESSED CONCRETE CONSTRUCTION).
- CONCRETE WALL PANELS SHALL PROVIDE EXPANSIONS JOINTS AT THE ROOF EXPANSION JOINT TO ALLOW FOR THERMAL EXPANSION AND CONTRACTION. ADDITIONALLY, THE PRECAST SUPPLIER SHALL ALLOW FOR DIFFERENTIAL MOVEMENT BETWEEN WALL PANELS BY ALLOWING EXPANSION EVERY FIFTH WALL PANEL.
- CONCRETE WALL PANELS SHALL BE SOLID CORE BELOW FINISH FLOOR ELEVATION.

STRUCTURAL STEEL

- STRUCTURAL STEEL SHALL MEET THE FOLLOWING MINIMUM YIELD STRESS (Fy), UNLESS NOTED OTHERWISE:

	YIELD	ASTM SPECIFICATION
A. W, WT SHAPES:	50 KSI	A992
B. BARS, PLATES, CHANNELS, ANGLES:	36 KSI	A36
C. SQUARE, RECTANGULAR HSS:	50 KSI	A500, GRADE C
D. ANCHOR RODS:	36 KSI OR 55 KSI	F1554
E. ALL–THREAD RODS:	36 KSI	A36
F. HEADED STUD ANCHORS:	65 KSI TENSILE STRESS	A108, GRADES 1010–1020
- ALL STRUCTURAL STEEL SHALL ADHERE TO THE DETAILING, FABRICATION AND ERECTION REQUIREMENTS OF THE LATEST EDITIONS OF THE AISC SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS AND THE AISC CODE OF PRACTICE.
- BOLTS FOR STEEL BEAM AND COLUMN CONNECTIONS SHALL BE 3/4-INCH DIAMETER ASTM A325–N HIGH–STRENGTH BOLTS UNLESS NOTED OTHERWISE. ALL BOLTED CONNECTIONS ARE BEARING TYPE AND SHALL BE SNUG TIGHTENED UNLESS NOTED OTHERWISE. FOR PRETENSIONED OR SLIP–CRITICAL JOINTS, THE METHOD OF INSTALLATION SHALL BE TURN–OF–NUT WITH MATCH MARKING, TWIST–OFF–TYPE TENSION CONTROL BOLT ASSEMBLIES (ASTM F1852), OR DIRECT TENSION INDICATORS (ASTM F959).
- WELDING SHALL MEET ANSI / AWS D1.1, STRUCTURAL WELDING CODE LATEST REVISION. ELECTRODES SHALL BE E70XX, LOW HYDROGEN. ALL STRUCTURAL STEEL WELDS SHALL BE PERFORMED BY A AWS CERTIFIED WELDER.
- WELDS NOT SPECIFICALLY SIZED ON THE STRUCTURAL DRAWINGS SHALL BE THE MINIMUM SIZE PER THE LATEST AWS D1.1.
- PROVIDE DOUBLE NUTS AND DOUBLE WASHERS FOR STEEL COLUMN ANCHOR BOLTS TO ALLOW FOR ADJUSTMENT IN BASE PLATE ELEVATION. PROVIDE 1 1/2 INCH NON–SHRINK GROUT UNDER BASE PLATE AFTER ERECTION. USE 2 1/2 INCHES NON–SHRINK GROUT WHEN COLUMN ANCHOR BOLTS ARE 1 1/4 INCH DIAMETER OR LARGER. NON–SHRINK GROUT SHALL BE NON–METALLIC WITH A MINIMUM COMPRESSIVE STRENGTH OF 5,000 PSI AT 28 DAYS.
- SHEAR CONNECTORS SHALL BE A CARBON STEEL HEADED STUD TYPE ASTM A108 GRADES 1010 THRU 1020, AWS D1.1, TYPE B WITH ARC SHIELDS.
- ALL CONNECTIONS ON THE STRUCTURAL DRAWINGS, UNLESS NOTED OTHERWISE, SHALL BE DESIGNED AND DETAILED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED, EMPLOYED OR RETAINED BY THE STEEL FABRICATOR. THE DESIGN AND DETAILING SHALL COMPLY WITH ALL APPLICABLE CODES AND SPECIFICATION SECTIONS.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR INCLUDING THE COSTS FOR ALL MISCELLANEOUS STEEL IN THEIR BID REGARDLESS OF WHETHER THOSE ITEMS ARE INDICATED ON THE STRUCTURAL DRAWINGS. THESE COSTS SHALL INCLUDE BUT ARE NOT LIMITED TO MISCELLANEOUS STEEL ITEMS SHOWN ON ARCHITECTURAL, CIVIL, MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS SUCH AS SHELF ANGLES, GLAZING SUPPORTS AND LINTELS.
- LEDGER ANGLES AND LINTELS IN EXTERIOR WALL SYSTEMS SHALL BE HOT DIPPED GALVANIZED PER ASTM A123.
- ALL STRUCTURAL STEEL SHALL HAVE A COAT OF LIGHT GRAY PAINT TO PROVIDE PROTECTION AND GOOD APPEARANCE.

STEEL JOISTS

- STEEL JOISTS SHALL BE AS INDICATED ON THE PLANS AND SHALL BE IN ACCORDANCE WITH THE LATEST SPECIFICATIONS OF THE STEEL JOIST INSTITUTE (SJI) AND MEET THE FOLLOWING:
A. JOISTS SHALL BE DESIGNED FOR THE UNIFORM LOAD CAPACITY (AS SPECIFIED IN THE SJI STANDARD LOAD TABLES) IN ADDITION TO THE CONCENTRATED LOADS SHOWN ON PLANS AND DETAILS.
B. JOISTS THAT SUPPORT CONCENTRATED LOADS SHALL HAVE THEIR CHORDS DESIGNED TO WITHSTAND ALL BENDING STRESSES, OR THE LOADS SHALL OCCUR WITHIN 3 INCHES OF JOIST PANEL POINTS, OR THE JOIST SHALL BE REINFORCED PER THE "JOIST REINFORCING DETAIL" SHOWN HEREIN. CONCENTRATED LOADS SHALL BE CENTERED ON JOISTS AND NOT ATTACHED TO THE EDGE OF CHORD ANGLES.
C. JOISTS SHALL RESIST THE NET UPLIFT PRESSURE AS INDICATED ON THE DETAILS 7 & 8/S4.1. THIS PRESSURE SHALL ACT ALONE. AN ALLOWABLE STRESS INCREASE IS NOT PERMITTED.
D. FOR ALL MEMBERS THAT REQUIRE SPECIFIC ORIENTATION, PROVIDE TAG AT ONE END AND DEFINE LOCATION OF TAGGED END ON ERECTION DRAWINGS.
E. JOIST MANUFACTURER SHALL DETERMINE THE SEAT DEPTH AND WIDTH OF BEARING AND COORDINATE THE SAME WITH THE STEEL FABRICATOR. THE FOLLOWING SEAT DEPTHS ARE ASSUMED ON THE DRAWINGS: 2 1/2 INCHES FOR K–SERIES JOISTS, 5 INCHES FOR LH SERIES JOISTS).
F. JOISTS SHALL BE FABRICATED TO PROVIDE OPENINGS FOR DUCTS AS SHOWN IN THE REQUIRED OPENING IN JOIST DETAIL.
- K–SERIES AND LH–SERIES JOISTS SHALL BE WELDED TO SUPPORTING STEEL WITH MINIMUM 1/8 INCH FILLET WELDS 2 INCHES LONG EACH SIDE OR WITH TWO 1/2 INCH DIAMETER ASTM A307 BOLTS OR THE EQUIVALENT, UNLESS NOTED OTHERWISE. WHEN NEAR OR AT A COLUMN, BOLT JOIST TO SUPPORTING STEEL IN CONFORMANCE WITH OSHA.
- JOIST BRIDGING AND ERECTION STABILITY SHALL BE PROVIDED IN ACCORDANCE WITH THE OCCUPATIONAL SAFETY AND HAZARD ADMINISTRATION (OSHA) AND THE SPECIFICATIONS OF THE STEEL JOIST INSTITUTE (SJI).
- JOIST RTU LOADS ARE PROVIDED ON THE ROOF FRAMING PLAN, REFERENCE PLANS AND DETAILS FOR LOAD LOCATIONS, VALUES AND SUPPORT FRAMING.
- JOIST MANUFACTURER SHALL DESIGN THE COMPRESSION CHORD OF ALL JOISTS SUPPORTING ROOF TOP UNITS, SKY LIGHTS, AND OTHER STRUCTURES FOR AN UNBRACED LENGTH APPLICABLE TO THE CONDITIONS AT THE PROJECT WHERE THE UNBRACED LENGTH IS GREATER THAN THE SJI MAXIMUM. (REFERENCE ARCHITECTURAL AND MECHANICAL DRAWINGS)
- DESIGN JOISTS FOR INTERNAL ROOF DRAINLINE AND FIRE SPRINKLER LINE LOCATIONS, IF REQUIRED, ADD 50 PLF FOR 8 INCH DIAMETER AND SMALLER, ADD 75 PLF FOR 10 INCH DIAMETER, ADD 102 PLF FOR 12 INCH DIAMETER, ADD 122 PLF FOR 14 INCH DIAMETER, ADD 200 PLF FOR 18 INCH DIAMETER. REFERENCE MECHANICAL DRAWINGS FOR EXACT LOCATION. CONTRACTOR SHALL OBTAIN FIRE LINE LOCATIONS AND SIZES PRIOR TO SUBMITTAL OF JOIST SHOP DRAWINGS.
- JOIST DESIGNS SHALL BE PERFORMED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED, EMPLOYED OR RETAINED BY THE JOIST MANUFACTURER.
- SHOP DRAWING SHALL BE REVIEWED BY THE ARCHITECT AND STUCTURAL ENGINEER OF RECORD PRIOR TO JOIST FABRICATION.
- PROVIDE JOISTS CAPABLE OF WITH STANDING DESIGN LOADS INDICATED WITH LIVE LOAD DEFLECTIONS NO GREATER THAN L/240 OF THE SPAN.
- JOISTS SHALL BE CAMBERED ACCORDING TO SJI'S "SPECIFICATIONS". JOIST AND JOIST GIRDERS SHALL BE SHOP PRIMED WITH MANUFACTURER'S STANDARD SHOP PRIMER.

STEEL DECK

- ROOF DECK
A. ROOF DECK SHALL BE GALVANIZED TYPE "B". DEPTH SHALL BE AS SHOWN ON DRAWINGS. ROOF DECK SHALL BE BOTTOM PRIMED WHITE
B. ROOF DECK IS REQUIRED TO ACT AS A DIAPHRAGM. CONNECTIONS SHALL BE IN ACCORDANCE WITH STEEL DECK INSTITUTE SPECIFICATIONS. REFER TO THE ROOF DIAPHRAGM CONNECTION DIAGRAM FOR ATTACHMENT.
C. DECKING SHALL BE CONTINUOUS OVER A MINIMUM OF (3) SPANS UNLESS NOTED OTHERWISE.
D. NO HANGING LOADS SHALL BE ATTACHED TO ROOF DECK.



CURRAN

ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES


wallace



Wallace Engineering
Structural Consultants, Inc.

Structural and Civil Consultants
1741 McGee Street
Kansas City, Missouri 64108
816.421.8282, Fax 816.421.8338

CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300

S0.1

GENERAL NOTES

POST INSTALLED ANCHORS:

- ANCHORS SHALL ONLY BE INSTALLED WHERE SPECIFIED ON THE CONTRACT DRAWINGS. THE CONTRACTOR SHALL OBTAIN APPROVAL FROM THE STRUCTURAL ENGINEER PRIOR TO INSTALLING POST INSTALLED ANCHORS IN PLACE OF MISSING OR MIS-PLACED CAST-IN-PLACE ANCHORS. CARE SHALL BE TAKEN IN PLACING POST-INSTALLED ANCHORS TO AVOID CONFLICTS WITH EXISTING REINFORCING.
- THE CONTRACTOR SHALL SUBMIT PRODUCT DATA WITH DESIGN VALUES AND PHYSICAL PROPERTIES FOR ALL POST INSTALLED ANCHORS. ADDITIONALLY, THE CONTRACTOR SHALL SUBMIT CERTIFIED ICC ES OR ESR REPORTS WHICH VERIFY COMPLIANCE WITH THE SPECIFIED CRITERIA.
- SUBSTITUTION REQUESTS FOR PRODUCTS OTHER THAN THOSE SPECIFIED ON THE CONTRACT DRAWINGS SHALL BE SUBMITTED BY THE CONTRACTOR TO THE STRUCTURAL ENGINEER ALONG WITH CALCULATIONS THAT ARE SIGNED AND SEALED BY A QUALIFIED PROFESSIONAL ENGINEER RESPONSIBLE FOR THEIR PREPARATION AND LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED. THE CALCULATIONS SHALL DEMONSTRATE THAT THE SUBSTITUTED PRODUCT IS CAPABLE OF ACHIEVING THE PERTINENT EQUIVALENT PERFORMANCE VALUES OF THE SPECIFIED PRODUCT USING THE APPROPRIATE DESIGN PROCEDURE AND/OR STANDARDS AS REQUIRED BY THE BUILDING CODE.
- ALL HOLES SHALL BE DRILLED, DRY AND CLEANED AND ANCHORS SHALL BE INSTALLED IN ACCORDANCE PER ANCHOR MANUFACTURER'S WRITTEN SPECIFICATIONS. THE LATEST VERSION OF THE WRITTEN SPECIFICATION SHALL BE ON-SITE AND FOLLOWED DURING THE INSTALLATION OF THE ANCHORS.
- THE ANCHOR EMBEDMENT DEPTH SHALL BE DEFINED AS THE DEPTH FROM THE SURFACE FACE OF THE LOAD BEARING BASE MATERIAL TO THE DEEPEST PART OF THE ANCHOR AFTER THE ANCHOR HAS BEEN DRIVEN INTO THE HOLE, BUT NOT YET EXPANDED, IF APPLICABLE.
- ANCHORS AT ALL WEATHER EXPOSED LOCATIONS SHALL BE STAINLESS STEEL.
- NON-EPOXY BASED ADHESIVES SHALL BE USED WHEN BASE MATERIAL TEMPERATURE IS BELOW 40 DEGREES FAHRENHEIT.
- THE FOLLOWING CONCRETE MECHANICAL ANCHORS ARE ALLOWED FOR USE IN CRACKED AND UNCRACKED CONCRETE AND HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ACI 355.2 AND ICC-ES AC193.
 - SIMPSON STRONG-TIE "STRONG BOLT 2" (ICC-ES ESR-3037)
 - SIMPSON STRONG-TIE "TITEN HD" (ICC-ES ESR-2713)
 - HILTI "KWIK BOLT TZ" EXPANSION ANCHOR (ICC-ES ESR 1917)
 - HILTI "HSL-3" HEAVY DUTY EXPANSION ANCHOR (ICC-ES ESR 1545)
 - HILTI "HDA" UNDERCUT ANCHOR (ICC-ES ESR 1546)
 - HILTI "KWIK HUS EZ" EXPANSION ANCHOR (ICC-ES ESR 3027)
- THE FOLLOWING CONCRETE ADHESIVE ANCHORS ARE ALLOWED FOR USE IN CRACKED AND UNCRACKED CONCRETE AND HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ACI 355.4 AND ICC-ES AC308.
 - SIMPSON STRONG-TIE "SET-XP" (ICC-ES ESR-2508)
 - HILTI "HIT-HY200" (ICC-ES ESR-1385)
 - HILTI "HIT-RE 500 V3" (ICC-ES ESR-3814)

MASONRY

- CONCRETE MASONRY UNITS SHALL MEET ASTM SPECIFICATION C90, WITH A MINIMUM UNIT COMPRESSIVE STRENGTH = 1900 PSI. THE SPECIFIED DESIGN COMPRESSIVE STRENGTH OF THE CONCRETE MASONRY ASSEMBLY (f'm) SHALL BE 1900 PSI.
- MORTAR SHALL BE A PREBLENDED DRY MIX CONFORMING TO ASTM C1714 AND MEETING THE PROPERTY SPECIFICATIONS OF ASTM C270 TYPE "S" MORTAR FOR BELOW GRADE. TYPE "N" MORTAR FOR ABOVE GRADE. MASONRY CEMENT SHALL NOT BE USED FOR MORTAR.
- GROUT SHALL MEET ASTM SPECIFICATION C476 AND HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 2000 PSI.
 - LIMIT THE HEIGHT OF VERTICAL GROUT POURS TO 4'-0" OR THE DISTANCE BETWEEN BOND BEAMS, WHICHEVER IS LESS.
 - GROUTING SHALL BE A CONTINUOUS PROCEDURE FOR EACH LIFT. DO NOT ALLOW HORIZONTAL CONSTRUCTION JOINT TO FORM BY DISCONTINUING GROUTING.
 - VERTICAL GROUT POUR EXCEEDING 12 INCHES SHALL BE MECHANICALLY CONSOLIDATED USING A VIBRATOR WITH A MAXIMUM 3/4 INCH DIAMETER HEAD.
- CONTRACTOR SHALL CLEAN THE GROUT SPACES SUCH THAT THEY ARE FREE OF MORTAR DROPPINGS, DEBRIS, LOOSE AGGREGATES AND ANY MATERIAL THAT WOULD PREVENT CONTINUITY OF THE GROUT.
- HORIZONTAL JOINT REINFORCEMENT SHALL BE LADDER TYPE. JOINT REINFORCEMENT SHALL BE SPACED AT 8 INCHES ON CENTER BELOW FINISHED FLOOR AND IN PARAPETS, AND 16 INCHES ON CENTER ABOVE FINISHED FLOOR.
- CONCRETE MASONRY SHALL BE LAID IN RUNNING BOND.
- CONCRETE MASONRY BELOW FINISHED FLOOR SHALL BE NORMAL WEIGHT UNITS AND SHALL HAVE ALL THE CELLS FULLY GROUTED. CONCRETE MASONRY ABOVE FINISHED FLOOR SHALL BE MEDIUM WEIGHT AND IS TO BE GROUTED ONLY AT REINFORCED CELLS AND BOND BEAMS, UNLESS NOTED OTHERWISE. ALL CELLS WITH REINFORCING OR EMBEDDED ITEMS SHALL BE GROUTED SOLID.
- REFERENCE WALL SECTIONS AND DETAILS FOR MISCELLANEOUS BOND BEAM LOCATIONS AND EMBEDDED ITEMS. USE OPEN KNOCK OUT BOND BEAM BLOCK. DO NOT USE TROUGH TYPE BLOCKS FOR BOND BEAMS. DO NOT CONTINUE BOND BEAM REINFORCING THROUGH CONTROL JOINTS, UNLESS NOTED OTHERWISE.
- REINFORCING STEEL SHALL MEET ASTM SPECIFICATION A615, GRADE 60. REINFORCING STEEL SHALL BE SPLICED AS NOTED IN THE REINFORCING LAP SCHEDULE.
- PROVIDE TEMPORARY BRACING FOR WALLS, LINTELS, AND OTHER MASONRY DURING ERECTION. BRACING SHALL BE DESIGNED IN ACCORDANCE WITH THE MASON CONTRACTORS ASSOCIATION OF AMERICA STANDARD PRACTICE FOR BRACING MASONRY WALLS UNDER CONSTRUCTION. DESIGN SHALL BE PERFORMED BY AN ENGINEER LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED. BRACING SHALL REMAIN UNTIL ROOFING AND OTHER STRUCTURAL ELEMENTS ARE COMPLETE AND PROVIDE PERMANENT STABILITY.

DEFERRED STRUCTURAL SUBMITTALS

- THE FOLLOWING STRUCTURAL COMPONENTS SHALL BE DESIGNED AND SUBMITTED BY OTHERS FOR APPROVAL IN ACCORDANCE WITH DRAWINGS AND SPECIFICATIONS.
 - STRUCTURAL STEEL CONNECTIONS OF FRAMING AND BRACING ELEMENTS
 - STEEL JOISTS AND JOIST GIRDERS (CONTRACTOR SHALL OBTAIN FIRE LINE LOCATIONS AND SIZES PRIOR TO SUBMITTAL OF JOIST SHOP DRAWINGS.)
 - STEEL, SELF-SUPPORTING STAIRS AND HANDRAIL FRAMING
 - STOREFRONT AND CURTAINWALL FRAMING, ACCESSORIES AND ATTACHMENTS TO STRUCTURE
 - EXCAVATION SUPPORT
 - TEMPORARY BRACING AND SUPPORT
 - CONCRETE WALL PANEL REINFORCING
 - ROOF ACCESS LADDERS AND SAFETY CAGES
 - SEISMIC ANCHORAGE AND BRACING OF MEP COMPONENTS
- DOCUMENTS FOR DEFERRED STRUCTURAL SUBMITTAL ITEMS SHALL BE DESIGNED, SEALED AND SIGNED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED. THE DEFERRED SUBMITTAL DOCUMENTS SHALL BE SUBMITTED TO THE ARCHITECT OR ENGINEER OF RECORD WHO SHALL REVIEW THEM AND FORWARD THEM TO THE BUILDING OFFICIAL AS REQUESTED WITH A NOTATION INDICATING THAT THE DEFERRED SUBMITTAL DOCUMENTS HAVE BEEN REVIEWED AND BEEN FOUND TO BE IN GENERAL CONFORMANCE TO THE DESIGN OF THE BUILDING. THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THE DESIGN AND SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL.

SHOP DRAWINGS

- SHOP DRAWINGS AND SUBMITTALS SHALL BE REVIEWED AND APPROVED BY THE CONTRACTOR PRIOR TO SUBMITTAL FOR THE ENGINEER'S REVIEW. THE STRUCTURAL ENGINEER'S REVIEW IS TO CHECK THE GENERAL CONFORMANCE OF THE SHOP DRAWINGS WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR IS RESPONSIBLE FOR ANY ALTERATIONS FROM THE CONTRACT DOCUMENTS WHICH MAY INCLUDE QUANTITIES, DIMENSIONAL ERRORS OR OTHER ERRORS AND OMISIONS IN THE SHOP DRAWINGS.
- SHOP DRAWINGS SHALL NOT BE REPRODUCTIONS OF THE CONTRACT DOCUMENTS.
- THE FOLLOWING STRUCTURAL COMPONENTS SHALL BE SUBMITTED AS A SHOP DRAWING FOR REVIEW:
 - CONCRETE MIX DESIGN AND MATERIALS
 - CONCRETE REINFORCING STEEL
 - CONCRETE FORMWORK
 - STRUCTURAL STEEL
 - STEEL JOISTS
 - STEEL ROOF DECK AND THEIR ATTACHMENTS.
 - ALL DEFERRED SUBMITTAL ITEMS

SPECIAL INSPECTIONS

- THE OWNER SHALL EMPLOY ONE OR MORE SPECIAL INSPECTORS TO PROVIDE INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK LISTED IN THE STATEMENT OF SPECIAL INSPECTIONS PER SECTION 1704 OF THE IBC. THE SPECIAL INSPECTOR SHALL BE A QUALIFIED PERSON WHO SHALL DEMONSTRATE COMPETENCE, TO THE SATISFACTION OF THE BUILDING OFFICIAL, FOR INSPECTION OF THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION REQUIRING SPECIAL INSPECTION. THESE INSPECTIONS ARE IN ADDITION TO THE INSPECTIONS SPECIFIED IN THE PROJECT SPECIFICATIONS.
- SPECIAL INSPECTORS SHALL KEEP RECORDS OF INSPECTIONS. THE SPECIAL INSPECTOR SHALL FURNISH INSPECTION REPORTS TO THE BUILDING OFFICIAL, AND TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE. REPORTS SHALL INDICATE THAT WORK INSPECTED WAS DONE IN CONFORMANCE TO APPROVED CONSTRUCTION DOCUMENTS. DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION. IF THE DISCREPANCIES ARE NOT CORRECTED, THE DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE BUILDING OFFICIAL AND TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE PRIOR TO COMPLETION OF THAT PHASE OF WORK. A FINAL REPORT DOCUMENTING REQUIRED SPECIAL INSPECTIONS AND CORRECTION OF ANY DISCREPANCIES NOTED IN THE INSPECTIONS SHALL BE SUBMITTED AT A POINT IN TIME AGREED UPON BY THE PERMIT APPLICANT AND THE BUILDING OFFICIAL PRIOR TO THE START OF WORK.
- THE CONTRACTOR IS RESPONSIBLE FOR NOTIFYING THE SPECIAL INSPECTOR REGARDING INDIVIDUAL INSPECTION FOR ITEMS LISTED ON THE STATEMENT OF SPECIAL INSPECTIONS AND AS NOTED ON THE BUILDING DEPARTMENT APPROVED PLANS. ADEQUATE NOTICE AND ACCESS TO APPROVED PLANS SHALL BE PROVIDED SO THAT THE SPECIAL INSPECTOR HAS TIME TO BECOME FAMILIAR WITH THE PROJECT.
- FABRICATORS OF STRUCTURAL LOAD-BEARING MEMBERS AND ASSEMBLIES SHALL CONFORM TO THE REQUIREMENTS OF SECTION 1704.2 OF THE IBC.
- THE FOLLOWING ITEMS REQUIRE SPECIAL INSPECTION PER SECTION 1700 OF THE REFERENCED BUILDING CODE.

- BOLTS & ANCHORS EMBEDDED IN CONCRETE
- PLACEMENT OF REINFORCING STEEL IN CONCRETE
- CONCRETE MIX DESIGN
- CONCRETE FORMWORK
- STRUCTURAL STEEL FABRICATIONS
- STRUCTURAL STEEL BOLTING AND WELDING
- ON SITE STRUCTURAL FRAMING
- INSPECTION OF ROOF DECK ATTACHMENTS
- SHEAR WALL ATTACHMENTS AND ANCHORS
- POST INSTALLED ANCHORS
- ON SITE SOILS, EXCAVATIONS, FILLING AND COMPACTION
- ERECTION OF PRECAST CONCRETE MEMBERS

ABBREVIATIONS

A.B.	ANCHOR BOLTS
ACI	AMERICAN CONCRETE INSTITUTE
AESS	ARCHITECTURALLY EXPOSED STRUCTURAL STEEL
A.F.F.	ABOVE FINISHED FLOOR
ARCH.	ARCHITECTURAL
BAL.	BALANCE
B.L.	BLOCK LINTEL
BLDG.	BUILDING
B.O.	BOTTOM OF
B.O.D.	BOTTOM OF DECK
BRG.	BEARING
C.J.	CONTRACTION JOINT
C.L.	CENTER LINE
CLR.	CLEAR
CMU	CONCRETE MASONRY UNIT
COL.	COLUMN
CONC.	CONCRETE
CONST.	CONSTRUCTION
CONT.	CONTINUOUS
D.B.A.	DEFORMED BAR ANCHOR
DIA.	DIAMETER
DWG.	DRAWING
E.F.	EACH FACE
E.J.	EXPANSION JOINT
ELEV.	ELEVATION
E.O.D.	EDGE OF DECK
E.O.S.	EDGE OF SLAB
EQ.	EQUH FACE
E.W.	EACH WAY
EXIST.	EXISTING
FDN.	FOUNDATION
F.F.E.	FINISHED FLOOR ELEV.
F.S.	FAR SIDE
FTG.	FOOTING
GA.	GAGE
GALV.	GALVANIZED
G.B.	GRADE BEAM
HORIZ.	HORIZONTAL
H.S.A.	HEADED STUD ANCHOR
IBC	INTERNATIONAL BUILDING CODE
INFO.	INFORMATION
J.B.E.	JOIST BEARING ELEVATION
JT.	JOINT
K	UNIT OF 1,000 POUNDS (KIP)

KSI	KIPS PER SQUARE INCH
LBS.	POUNDS
L.H.	LONG LEG HORIZONTAL
LV.	LONG LEG VERTICAL
LONG.	LONGITUDINAL
MAX.	MAXIMUM
MECH.	MECHANICAL
MFR.	MANUFACTURER
MIN.	MINIMUM
MISC.	MISCELLANEOUS
N.I.C.	NOT IN CONTRACT
NO.	NUMBER
N.T.S.	NOT TO SCALE
N.S.	NEAR SIDE
O.C.	ON CENTER
O.H.	OUTSIDE DIAMETER
O.P.	OPPOSITE HAND
P.A.F.	POWER ACTUATED FASTENER
PCF	POUNDS PER CUBIC FOOT
PLF	POUNDS PER LINEAR FOOT
P.M.E.J.	PREMOLDED EXPANSION JOINT
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
QTY.	QUANTITY
RE.	REFER
REINF.	REINFORCING
REQD.	REQUIRED
R.O.	ROUGH OPENING
RTU	ROOF TOP UNIT
SCHED.	SCHEDULE
S.D.S.	SELF-DRILLING SCREWS
SIM.	SIMILAR
SPECS.	SPECIFICATIONS
STD.	STANDARD
STL.	STEEL
T&B	TOP AND BOTTOM
T.O.	TOP OF
T.O.P.	TOP OF PIER
T.O.W.	TOP OF WALL
TRANS.	TRANSVERSE
TYP.	TYPICAL
U.N.O.	UNLESS NOTED OTHERWISE
VERT.	VERTICAL
W.P.	WORK POINT
WT.	WEIGHT
W.W.R.	WELDED WIRE REINFORCEMENT

NOTE: THE CONTRACTOR SHALL PROVIDE A BASE BID PRICING BASED ON THE PANEL THICKNESS SHOWN ON THE DRAWINGS. ADDITIONALLY, THE BASE BID SHALL REFLECT 3.5 LBS PER SQUARE FEET OF REINFORCING STEEL WITH UNIT PRICING OF ANY ADD OR DEDUCT FROM AFOREMENTIONED TONNAGE. ANY VALUE ENGINEERING DEVIATIONS FOR THE WALLS PANELS FOR PANEL THICKNESS SHALL BE QUALIFIED AS A SEPARATE LINE ITEM IN THE CONTRACTOR'S BID.



CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY OF
CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO


ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022


210300

S1.0

OVERALL FOUNDATION PLAN



1 OVERALL FOUNDATION PLAN
SCALE: 1"=40'-0"




CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY OF
CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300

S1.1

ENLARGED PARTIAL
FOUNDATION PLAN

PLAN NOTES:

1. CONCRETE SLAB-ON-GRADE, U.N.O., SHALL BE A 7" THICK UNREINFORCED SLAB (U.N.O.) OVER 4" ROCK, RE: THE GEOTECHNICAL REPORT. T.O. SLAB ELEV = 100'-0". SLAB TO BE SEALED WITH SINGLE COAT OF ASHFORD (OR EQUAL) FLOOR SEALANT.
2. THE CONCRETE SLABS SHOWN ON THE STRUCTURAL DRAWINGS HAVE BEEN DESIGNED FOR THE FINISHED STRUCTURE AND HAVE NOT BEEN DESIGNED FOR MEANS AND METHODS OF CONSTRUCTION, INCLUDING BUT NOT LIMITED TO, FORK LIFTS, MAN LIFTS, AND OTHER VEHICULAR TRAFFIC. THE CONTRACTOR SHALL VERIFY THE SLAB DESIGN MEETS THE CONSTRUCTION NEEDS AND SHALL SUBMIT TO THE ENGINEER OF RECORD FOR REVIEW.
3. TOP OF FOOTING ELEV. = 99'-0, UNLESS NOTED OTHERWISE.
4. ALL PIPING OR CONDUITS THAT OCCUR THROUGH OR UNDER A GRADE BEAM OR FOOTING SHALL BE APPROVED BY THE ENGINEER OF RECORD PRIOR TO PLACEMENT. (RE: 4 & 5/S3.0)
5. RE: 1/S3.0 FOR REINFORCING LAP SCHEDULE.
6. RE: SHEET S3.0 FOR ADDITIONAL CONCRETE FOUNDATION DETAILS
7. ALL PRECAST PANELS SHALL BE 9 1/4" THICK, U.N.O.

PLAN REFERENCE NOTES:

- Ⓐ DRAIN BLOCKOUT IN FOOTING, RE: 10&11/S3.0
- Ⓑ DOCK PIT, RE: 5/S3.2. RE: ARCH. FOR LOCATIONS.
- Ⓒ DOCK STAIRS RE: 1/S3.1. REFER TO ARCH DWGS FOR LOCATIONS AND TYPE OF STAIR
- Ⓓ FOOTING STEP, RE: 6/S3.0
- Ⓔ RAMP, RE: CIVIL DWGS.


LEGEND

1. F# = FOOTING MARK; RE: FOOTING SCHEDULE
2. C.J. = SAW CUT CONTROL JOINT; RE: DETAIL 2/S3.0
3. B.P. = BASE PLATE; RE: DETAIL 9/S3.0

SPOT FOOTING SCHEDULE

MARK	SIZE	REINFORCEMENT
M7.0	7'-0"x7'-0"x2'-6"	NO REINF. REQUIRED
F6.5	6'-6x6'-6"x1'-3"	(6)-#6 EA. WAY
F7.0	7'-0"x7'-0"x1'-3"	(7)-#6 EA. WAY
F10.0	10'-0"x10'-0"x3'-0"	(10)-#7 EA. WAY, TOP AND BOTTOM
F10.0B	10'-0"x10'-0"x3'-0"	RE: 6/S3.3

NOTE: PROVIDE f'c=4,000 PSI AT FOOTING TYPE F10.0 AND F10.0B



1 ENLARGED PARTIAL FOUNDATION PLAN
SCALE: 1"=20'-0"





CURRAN
ARCHITECTURE
5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



08/15/2022
Missouri COA #001268
THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3
NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300

S1.2
ENLARGED PARTIAL
FOUNDATION PLAN

PLAN NOTES:

- CONCRETE SLAB-ON-GRADE, U.N.O., SHALL BE A 7" THICK UNREINFORCED SLAB (U.N.O.) OVER 4" ROCK, RE: THE GEOTECHNICAL REPORT. T.O. SLAB ELEV = 100'-0". SLAB TO BE SEALED WITH SINGLE COAT OF ASHFORD (OR EQUAL) FLOOR SEALANT. THE CONCRETE SLABS SHOWN ON THE STRUCTURAL DRAWINGS HAVE BEEN DESIGNED FOR THE FINISHED STRUCTURE AND HAVE NOT BEEN DESIGNED FOR MEANS AND METHODS OF CONSTRUCTION, INCLUDING BUT NOT LIMITED TO, FORK LIFTS, MAN LIFTS, AND OTHER VEHICULAR TRAFFIC. THE CONTRACTOR SHALL VERIFY THE SLAB DESIGN MEETS THE CONSTRUCTION NEEDS AND SHALL SUBMIT TO THE ENGINEER OF RECORD FOR REVIEW.
- TOP OF FOOTING ELEV. = 99'-0", UNLESS NOTED OTHERWISE. ALL PIPING OR CONDUITS THAT OCCUR THROUGH OR UNDER A GRADE BEAM OR FOOTING SHALL BE APPROVED BY THE ENGINEER OF RECORD PRIOR TO PLACEMENT. (RE: 4 & 5/S3.0)
- RE: 1/S3.0 FOR REINFORCING LAP SCHEDULE.
- RE: SHEET S3.0 FOR ADDITIONAL CONCRETE FOUNDATION DETAILS
- ALL PRECAST PANELS SHALL BE 9 1/4" THICK, U.N.O.

PLAN REFERENCE NOTES:

- (A) DRAIN BLOCKOUT IN FOOTING, RE: 10&11/S3.0
(B) DOCK PIT, RE: 5/S3.2. RE: ARCH. FOR LOCATIONS.
(C) DOCK STAIRS RE: 1/S3.1. REFER TO ARCH DWGS FOR LOCATIONS AND TYPE OF STAIR
(D) FOOTING STEP, RE: 6/S3.0
(E) RAMP, RE: CIVIL DWGS.


LEGEND

1. F# = FOOTING MARK; RE: FOOTING SCHEDULE
2. C.J. = SAW CUT CONTROL JOINT; RE: DETAIL 2/S3.0
3. B.P. = BASE PLATE; RE: DETAIL 9/S3.0

SPOT FOOTING SCHEDULE

MARK	SIZE	REINFORCEMENT
M7.0	7'-0"x7'-0"x2'-6"	NO REINF. REQUIRED
F6.5	6'-6"x6'-6"x1'-3"	(6)-#6 EA. WAY
F7.0	7'-0"x7'-0"x1'-3"	(7)-#6 EA. WAY
F10.0	10'-0"x10'-0"x3'-0"	(10)-#7 EA. WAY, TOP AND BOTTOM
F10.0B	10'-0"x10'-0"x3'-0"	RE: 6/S3.3

NOTE: PROVIDE f'c=4,000 PSI AT FOOTING TYPE F10.0 AND F10.0B



1 ENLARGED PARTIAL FOUNDATION PLAN
SCALE: 1"=20'-0"






CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300

S1.3

ENLARGED PARTIAL
FOUNDATION PLAN

PLAN NOTES:

- CONCRETE SLAB-ON-GRADE, U.N.O., SHALL BE A 7" THICK UNREINFORCED SLAB (U.N.O.) OVER 4" ROCK, RE: THE GEOTECHNICAL REPORT. T.O. SLAB ELEV = 100'-0". SLAB TO BE SEALED WITH SINGLE COAT OF ASHFORD (OR EQUAL) FLOOR SEALANT.
- THE CONCRETE SLABS SHOWN ON THE STRUCTURAL DRAWINGS HAVE BEEN DESIGNED FOR THE FINISHED STRUCTURE AND HAVE NOT BEEN DESIGNED FOR MEANS AND METHODS OF CONSTRUCTION, INCLUDING BUT NOT LIMITED TO, FORK LIFTS, MAN LIFTS, AND OTHER VEHICULAR TRAFFIC. THE CONTRACTOR SHALL VERIFY THE SLAB DESIGN MEETS THE CONSTRUCTION NEEDS AND SHALL SUBMIT TO THE ENGINEER OF RECORD FOR REVIEW.
- TOP OF FOOTING ELEV. = 99'-0", UNLESS NOTED OTHERWISE.
- ALL PIPING OR CONDUITS THAT OCCUR THROUGH OR UNDER A GRADE BEAM OR FOOTING SHALL BE APPROVED BY THE ENGINEER OF RECORD PRIOR TO PLACEMENT. (RE: 4 & 5/S3.0)
- RE: 1/S3.0 FOR REINFORCING LAP SCHEDULE.
- RE: SHEET S3.0 FOR ADDITIONAL CONCRETE FOUNDATION DETAILS
- ALL PRECAST PANELS SHALL BE 9 1/4" THICK, U.N.O.

PLAN REFERENCE NOTES:

- (A) DRAIN BLOCKOUT IN FOOTING, RE: 10&11/S3.0
(B) DOCK PIT, RE: 5/S3.2. RE: ARCH. FOR LOCATIONS.
(C) DOCK STAIRS RE: 1/S3.1. REFER TO ARCH DWGS FOR LOCATIONS AND TYPE OF STAIR
(D) FOOTING STEP, RE: 6/S3.0
(E) RAMP, RE: CIVIL DWGS.


LEGEND

1. F# = FOOTING MARK; RE: FOOTING SCHEDULE
2. C.J. = SAW CUT CONTROL JOINT; RE: DETAIL 2/S3.0
3. B.P. = BASE PLATE; RE: DETAIL 9/S3.0

SPOT FOOTING SCHEDULE

MARK	SIZE	REINFORCEMENT
M7.0	7'-0"x7'-0"x2'-6"	NO REINF. REQUIRED
F6.5	6'-6"x6'-6"x1'-3"	(6)-#6 EA. WAY
F7.0	7'-0"x7'-0"x1'-3"	(7)-#6 EA. WAY
F10.0	10'-0"x10'-0"x3'-0"	(10)-#7 EA. WAY, TOP AND BOTTOM
F10.0B	10'-0"x10'-0"x3'-0"	RE: 6/S3.3

NOTE: PROVIDE f'c=4,000 PSI AT FOOTING TYPE F10.0 AND F10.0B



1 ENLARGED PARTIAL FOUNDATION PLAN

SCALE: 1"=20'-0"






5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO


ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022


210300

S2.0

OVERALL FRAMING PLAN



1 OVERALL FRAMING PLAN
SCALE: 1"=40'-0"




CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3
NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300

S2.1
ENLARGED PARTIAL
FRAMING PLAN


PLAN REFERENCE NOTES:

- (A) ROOF HATCH, RE: ARCH. PROVIDE ANGLE FRAME AT OPENING, RE: 8/54.0
- (B) JOIST SUPPLIER SHALL DESIGN JOISTS FOR AXIAL LOAD SHOWN.
- (C) DRAG STRUT SPLICE, RE: 9/54.0.
- (D) ROOF TOP EQUIPMENT, RE: ARCH./MEP. PROVIDE ANGLE FRAME AND CURB RE: 5/54.0 JOIST SUPPLIER SHALL ACCOUNT FOR LOAD SHOWN ON PLAN IN JOIST DESIGN.


PLAN NOTES

- 1. ALL EDGE ANGLES SHALL BE CONTINUOUS AND SPLICED PER 6/54.0.
- 2. VERIFY ALL WALL OPENING, DIMENSIONS, JOINTS, BLOCKOUTS, REVEALS AND FUTURE KNOCK OUT PANELS WITH ARCHITECTURAL DRAWINGS.
- 3. NOTE TO JOIST MANUFACTURER: PROVIDE STANDARD BRIDGING COMPLYING WITH THE APPLICABLE STEEL JOIST INSTITUTE SPECIFICATIONS TYPICAL FOR GRAVITY AND UPLIFT LOADS SUPERIMPOSED ON ALL JOISTS. DIAGONAL BRIDGING SHALL BE PROVIDED BETWEEN ADJACENT JOISTS WHENEVER BOTTOM CHORD HORIZONTAL BRIDGING IS DISCONTINUOUS. (RE: 1 & 2/54.0)
- 4. ROOF DECK AND ROOF DECK ATTACHMENT SHALL BE PER SHEET S2.5.
- 5. RE: 3 AND 4/54.1 FOR ADDITIONAL PRECAST PANEL CONNECTION DETAILS
- 6. JOIST SHALL BE DESIGNED FOR ROOF TOP EQUIPMENT, RE: ARCH./MEP. PROVIDE ANGLE FRAME AND CURB, RE: 5/54.0. JOIST SUPPLIER SHALL ACCOUNT FOR LOAD SHOWN ON PLAN IN JOIST DESIGN.
- 7. JOIST AND JOIST GIRDER DEPTHS SHALL BE LIMITED SO THAT 32'-0" CLEAR HEIGHT TO BOTTOM OF STRUCTURE IS MAINTAINED

JOIST LEGEND





JOIST GIRDER LEGEND




BEAM REACTION LEGEND

STEEL FABRICATOR SHALL DESIGN THE BEAM CONNECTIONS FOR THE STRENGTH LEVEL LOADS (ASD) SHOWN ON THIS PLAN, TYP. (RE: 1/54.0)

USE MINIMUM TWO BOLT CONNECTION



1 ENLARGED PARTIAL FRAMING PLAN
SCALE: 1"=20'-0"




CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300

S2.2
ENLARGED PARTIAL
FRAMING PLAN


PLAN REFERENCE NOTES:

- (A) ROOF HATCH, RE: ARCH. PROVIDE ANGLE FRAME AT OPENING, RE: 8/54.0
- (B) JOIST SUPPLIER SHALL DESIGN JOISTS FOR AXIAL LOAD SHOWN.
- (C) DRAG STRUT SPLICE, RE: 9/54.0.
- (D) ROOF TOP EQUIPMENT, RE: ARCH./MEP. PROVIDE ANGLE FRAME AND CURB RE: 5/54.0 JOIST SUPPLIER SHALL ACCOUNT FOR LOAD SHOWN ON PLAN IN JOIST DESIGN.


PLAN NOTES

1. ALL EDGE ANGLES SHALL BE CONTINUOUS AND SPLICED PER 6/54.0.
2. VERIFY ALL WALL OPENING, DIMENSIONS, JOINTS, BLOCKOUTS, REVEALS AND FUTURE KNOCK OUT PANELS WITH ARCHITECTURAL DRAWINGS.
3. NOTE TO JOIST MANUFACTURER: PROVIDE STANDARD BRIDGING COMPLYING WITH THE APPLICABLE STEEL JOIST INSTITUTE SPECIFICATIONS TYPICAL FOR GRAVITY AND UPLIFT LOADS SUPERIMPOSED ON ALL JOISTS. DIAGONAL BRIDGING SHALL BE PROVIDED BETWEEN ADJACENT JOISTS WHENEVER BOTTOM CHORD HORIZONTAL BRIDGING IS DISCONTINUOUS. (RE: 1 & 2/54.0)
4. ROOF DECK AND ROOF DECK ATTACHMENT SHALL BE PER SHEET S2.5.
5. RE: 3 AND 4/54.1 FOR ADDITIONAL PRECAST PANEL CONNECTION DETAILS
6. JOIST SHALL BE DESIGNED FOR ROOF TOP EQUIPMENT, RE: ARCH./MEP. PROVIDE ANGLE FRAME AND CURB, RE: 5/54.0. JOIST SUPPLIER SHALL ACCOUNT FOR LOAD SHOWN ON PLAN IN JOIST DESIGN.
7. JOIST AND JOIST GIRDER DEPTHS SHALL BE LIMITED SO THAT 32'-0" CLEAR HEIGHT TO BOTTOM OF STRUCTURE IS MAINTAINED

JOIST LEGEND





JOIST GIRDER LEGEND




BEAM REACTION LEGEND

STEEL FABRICATOR SHALL DESIGN THE BEAM CONNECTIONS FOR THE STRENGTH LEVEL LOADS (ASD) SHOWN ON THIS PLAN, TYP. (RE: 1/54.0)

USE MINIMUM TWO BOLT CONNECTION



1 ENLARGED PARTIAL FRAMING PLAN
SCALE: 1"=20'-0"



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



CERTIFICATION



08/15/2022
Missouri COA #001268
THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3
NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300

S2.3
ENLARGED PARTIAL
FRAMING PLAN


PLAN REFERENCE NOTES:

- ROOF HATCH, RE: ARCH. PROVIDE ANGLE FRAME AT OPENING, RE: 8/54.0
- JOIST SUPPLIER SHALL DESIGN JOISTS FOR AXIAL LOAD SHOWN.
- DRAG STRUT SPLICE, RE: 9/54.0.
- ROOF TOP EQUIPMENT, RE: ARCH./MEP. PROVIDE ANGLE FRAME AND CURB RE: 5/54.0 JOIST SUPPLIER SHALL ACCOUNT FOR LOAD SHOWN ON PLAN IN JOIST DESIGN.


PLAN NOTES

- ALL EDGE ANGLES SHALL BE CONTINUOUS AND SPLICED PER 6/54.0.
- VERIFY ALL WALL OPENING, DIMENSIONS, JOINTS, BLOCKOUTS, REVEALS AND FUTURE KNOCK OUT PANELS WITH ARCHITECTURAL DRAWINGS.
- NOTE TO JOIST MANUFACTURER: PROVIDE STANDARD BRIDGING COMPLYING WITH THE APPLICABLE STEEL JOIST INSTITUTE SPECIFICATIONS TYPICAL FOR GRAVITY AND UPLIFT LOADS SUPERIMPOSED ON ALL JOISTS. DIAGONAL BRIDGING SHALL BE PROVIDED BETWEEN ADJACENT JOISTS WHENEVER BOTTOM CHORD HORIZONTAL BRIDGING IS DISCONTINUOUS. (RE: 1 & 2/54.0)
- ROOF DECK AND ROOF DECK ATTACHMENT SHALL BE PER SHEET S2.5.
- RE: 3 AND 4/54.1 FOR ADDITIONAL PRECAST PANEL CONNECTION DETAILS
- JOIST SHALL BE DESIGNED FOR ROOF TOP EQUIPMENT, RE: ARCH./MEP. PROVIDE ANGLE FRAME AND CURB, RE: 5/54.0. JOIST SUPPLIER SHALL ACCOUNT FOR LOAD SHOWN ON PLAN IN JOIST DESIGN.
- JOIST AND JOIST GIRDER DEPTHS SHALL BE LIMITED SO THAT 32'-0" CLEAR HEIGHT TO BOTTOM OF STRUCTURE IS MAINTAINED



JOIST LEGEND



JOIST GIRDER LEGEND



BEAM REACTION LEGEND




1 ENLARGED PARTIAL FRAMING PLAN
SCALE: 1"=20'-0"




• DECK TO STEEL MEMBER
CONNECTORS WELDS AT
6" O.C. AROUND ALL
OPENINGS, AT INTERIOR AND
EXTERIOR SUPPORTS, AND AT
ALL CONT. ANGLES, U.N.O.


* RE. PLAN FOR NUMBER
AND TYPE OF SIDELAPS




NOTE:
CONTRACTOR SHALL COORDINATE THE TYPE OF
PINS USED WITH THE THICKNESS OF THE JOISTS
AND JOIST GIRDERS. FOR AREAS IN WHICH THE
SUPPORTING STRUCTURE IS THICKER THAN 3/8",
THE X-HSN24 PINS SHALL BE SUBSTITUTED FOR
X-ENP-19-L15 PINS AT THE SAME FASTENING
PATTERNS SPECIFIED.



CONNECTOR PATTERN DIAGRAM (36/4)



CONNECTOR PATTERN DIAGRAM (36/5)




CONNECTOR PATTERN DIAGRAM (36/9)

1 1/2" TYPE B ROOF DECK

40 KSI

ROOF DIAPHRAGM CONNECTION DIAGRAM




1 ROOF DECK ATTACHMENT

SCALE: 1"=40'-0"

LOAD PLAN NOTES:


THE LATERAL SYSTEM OF THE BUILDING IS A COMBINATION OF SHEAR WALLS AND BRACED FRAMES. THE LOADS SHOWN ON THIS PLAN ARE THE ASD SEISMIC AND ASD WIND LOADS THAT ARE IMPARTED ON THE CONCRETE WALL PANELS, WHICH SHALL BE DESIGN AND DETAILED AS SHEAR WALLS. THE CONCRETE WALL SUPPLIER SHALL DESIGN THE PANELS TO RESIST THE LATERAL LOADS APPLIED AT THE ROOF DIAPHRAGM ELEVATION AS SHOWN PER OTHER DETAILS. THE ADDITIONAL SEISMIC LOAD INDUCED BY THE WEIGHT OF THE IN-PLANE PANELS AND OUT-OF-PLANE PANELS HAVE BEEN ACCOUNTED FOR IN THE FORCES SHOWN ON THE PLAN. THE CONCRETE WALL SUPPLIER SHALL DESIGN AND DETAIL THE CONNECTION OF THE CONCRETE PANELS TO THE FOUNDATION IN ORDER TO RESIST THE SHEAR AND UPLIFT FORCES FROM THE CONCRETE PANEL INTO THE FOUNDATION SYSTEM. THE FOUNDATION SYSTEM HAS BEEN DESIGNED FOR THE CONCRETE PANELS SHOWN TO ACT AS A COMPLETE SYSTEM ANY DEVIATIONS FROM THIS SHALL BE APPROVED BY THE ENGINEER OF RECORD.










1 LATERAL LOAD PLAN
SCALE: 1"=40'-0"

ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022




10 EXTERIOR FOOTING AT OVERFLOW DRAIN
3/4" = 1'-0"



STEEL REINF. LAP SCHEDULE (INCHES)						
BAR SIZE	CONCRETE					
	f'c = 3000 PSI		f'c = 4000 PSI		f'c = 5000 PSI	
	TOP	OTHER	TOP	OTHER	TOP	OTHER
#3	22	17	20	16	17	13
#4	29	22	27	21	23	17
#5	36	28	33	26	28	22
#6	43	33	40	31	34	26
#7	63	48	58	45	49	38
#8	72	55	66	51	56	43
#9	91	70	79	61	71	54

1 CONC. LAP SCHEDULE
3/4" = 1'-0"



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



Wallace Engineering
Structural Consultants, Inc.
Structural and Civil Consultants
1741 McGee Street
Kansas City, Missouri 64108
816.421.8282, Fax 816.421.8338

CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3


NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES


ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300


S3.1
FOUNDATION DETAILS




5 SLAB CONNECTION TO CONCRETE WALL PANEL OPTIONS
3/4" = 1'-0"



4 FOUNDATION SECTION
3/4" = 1'-0"



3 FOUNDATION SECTION
3/4" = 1'-0"



2 FOUNDATION SECTION
3/4" = 1'-0"


NOTE:

STAIR FRAMING IS FOR GRAPHICAL PURPOSES ONLY. STEEL FABRICATOR SHALL COORDINATE DIMENSIONS AND LOCATION OF STAIR WITH THE ENTIRE CONSTRUCTION DOCUMENTS AND NOT SOLELY THE STRUCTURAL PORTION ONLY.


STAIR FRAMING, STRINGERS, TREADS, HANDRAILS, LANDINGS AND CONNECTION DETAILING AND DESIGN SHALL BE THE RESPONSIBILITY OF THE STEEL FABRICATOR. STEEL FABRICATOR SHALL INCLUDE THE DESIGN FOR ANY ATTACHMENTS TO THE BUILDINGS, FOUNDATIONS OR DIAPHRAGMS. DESIGN LOADS SHALL BE COORDINATED WITH THE ENGINEER OF RECORD. IF ADDITIONAL COLUMNS OR POSTS ARE REQUIRED WHERE NOT EXPLICITLY SHOWN, STEEL FABRICATOR SHALL COORDINATE ADDITIONAL FOOTINGS OR ATTACHMENT TO BEAMS WITH GENERAL CONTRACTOR AND ENGINEER OF RECORD. THE DESIGN IS A DEFERRED SUBMITTAL AND SHALL BE SUBMITTED FOR REVIEW AS SET FORTH IN THE STRUCTURAL GENERAL NOTES.

MINIMUM MEMBER SIZES ARE AS NOTED BELOW:

STRINGER:	GALV. C12x20.7
HEADER:	GALV. C12x20.7
TREADS:	1 1/4" DEEP BAR GRATING
LANDING DECK:	1 1/4" DEEP BAR GRATING



STEEL STAIR



CONCRETE STAIRS-ON-GRADE

1 STAIR DETAILS
3/4" = 1'-0"



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753




SCANNELL
PROPERTIES



Wallace Engineering
Structural Consultants, Inc.
Structural and Civil Consultants
1741 McGee Street
Kansas City, Missouri 64108
816.421.8282, Fax 816.421.8338

CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3


NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES


ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300


S3.2
FOUNDATION DETAILS




5 DOCK PIT SECTION
3/4" = 1'-0"




4 FOUNDATION SECTION
3/4" = 1'-0"




3 FOUNDATION SECTION
3/4" = 1'-0"



2 FOUNDATION SECTION AT DOCK WALL
3/4" = 1'-0"




1 FOUNDATION SECTION AT OVERHEAD DOOR
3/4" = 1'-0"




6

BRACED FRAME FOOTING REINFORCEMENT DETAIL
N.T.S.




5

FOUNDATION SECTION
 $3/4'' = 1'-0''$




4

FOUNDATION SECTION
 $3/4'' = 1'-0''$




3

FOUNDATION SECTION
 $3/4'' = 1'-0''$




2

TYPICAL BRACED FRAME FOOTING DETAIL
 $3/4'' = 1'-0''$




1

FOUNDATION SECTION
 $3/4'' = 1'-0''$




9 TYPICAL DRAG STRUT DETAIL AT EXPANSION JOINT


8 ROOF OPENING DETAIL



7 JOIST REINFORCING DETAIL



6 SPLICE DETAIL





TYP. AT UNIT SPANNING MULTIPLE JOISTS



TYP. AT UNIT BETWEEN JOISTS



OPENING IN ROOF LARGER THAN 10"x10"




- NOTES:
1. INSTALL CURBS, HEADERS, AND FRAMES AND WELD TO SUPPORT STEEL BEFORE DECK IS PLACED.
2. DESIGN JOISTS SUPPORTING RTU'S FOR TWO POINT LOADS. THE LOCATION OF THE LOADS AND THE SPACING BETWEEN THEM VARY.
RE: RTU JOIST DIAGRAM THIS DETAIL AND ROOF FRAMING PLAN FOR POINT LOADS AND LOCATIONS.
3. RTU CURBS SHALL BE STRUCTURAL, DESIGNED TO SPAN BETWEEN JOISTS AND SUPPORT EDGES OF DECK. CURBS TO BE FABRICATED
WITH LEDGE ANGLES (L2x2x1/4) AT MECHANICAL OPENINGS TO SUPPORT METAL DECK INSIDE OPENING NOT USED BY SUPPLY OR
RETURN DUCT WORK. HEADERS ARE NOT REQUIRED FOR STRUCTURAL CURBS EXCEPT WHEN THE CURB DOES NOT SPAN BETWEEN TWO
JOISTS OR THE CURB CANTILEVERS MORE THAN TWO FEET PAST JOIST.
4. ATTACH DECK AROUND OPENING PER ROOF DIAPHRAGM CONNECTION DETAIL.
5. IF CURB IS NOT PLACED WITHIN 3" OF A JOIST PANEL POINT, RE: JOIST REINFORCING DETAIL RE: 7/54.00.
6. GENERAL CONTRACTOR SHALL COORDINATE RTU DIMENSIONS AND FRAMING LOCATIONS WITH THE STEEL FABRICATOR, MECHANICAL,
AND ERECTION SUBCONTRACTORS.
7. STEEL SUPPLIER TO FURNISH STOCK ANGLE FOR FIELD FABRICATED SUPPORT FRAMES.
8. RE: DETAIL 1 FOR CONN. OF DECK PARALLEL TO CURB (WHERE REQ'D.).
9. RE: MECH. FOR ROOF TOP UNIT ANCHORAGE TO CURBS.


5 MECHANICAL UNIT SUPPORT DETAIL




4 EDGE ANGLE CONNECTION DETAIL




3 ANGLE CONNECTION DETAILS




2 BOTTOM FLANGE BRACING DETAIL



1 BEAM CONNECTION DETAIL



- NOTES:**
1. ALL CONNECTIONS ON THE STRUCTURAL DRAWINGS, UNLESS NOTED OTHERWISE, SHALL BE DESIGNED AND DETAILED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED, EMPLOYED OR RETAINED BY THE STEEL FABRICATOR. THE DESIGN AND DETAILING SHALL COMPLY WITH ALL APPLICABLE CODES AND SPECIFICATION SECTIONS.
 2. CONNECTIONS SHOWN ARE FOR REFERENCE ONLY. FABRICATOR MAY USE OTHER AISI APPROVED CONNECTIONS.
 3. ALL BOLTS SHALL BE 3/4" DIAMETER A325 W/ HEAVY HEX NUTS, UNLESS NOTED OTHERWISE.
 4. ALL CONNECTIONS SHALL BE BEARING TYPE CONNECTIONS AND SHALL BE SNUG TIGHTENED UNLESS NOTED OTHERWISE.
 5. FOR BEAMS WITH AXIAL REACTIONS PER PLAN, CONNECTIONS SHALL BE DESIGNED AS FULLY TENSIONED SLIP CRITICAL PER AISI SPECIFICATIONS.



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753




SCANNELL
PROPERTIES

wallace



Wallace Engineering
Structural Consultants, Inc.
Structural and Civil Consultants
1741 McGee Street
Kansas City, Missouri 64108
816.421.8282, Fax 816.421.8338

CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO


ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022


210300

S4.1


FRAMING DETAILS




8 FRAMING DETAIL AT OPENING
3/4" = 1'-0"



7 FRAMING DETAIL
3/4" = 1'-0"




OPTION #2




OPTION #1

6 FRAMING DETAIL
3/4" = 1'-0"




OPTION #2




OPTION #1



5 FRAMING DETAIL
3/4" = 1'-0"




4 TYPICAL PANEL TO PANEL CONNECTION DETAILS
1 1/2" = 1'-0"




3 DECK CORNER DETAIL
3/4" = 1'-0"



2 GIRDER NET WIND UPLIFT DIAGRAM
NO SCALE



1 JOIST NET WIND UPLIFT DIAGRAM
NO SCALE




CURRAN ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



Wallace Engineering
Structural Consultants, Inc.
Structural and Civil Consultants
1741 McGee Street
Kansas City, Missouri 64108
816.421.8282, Fax 816.421.8318

CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO

ISSUE DATES


ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300

S4.2


FRAMING DETAILS

SPECIAL JOIST LOADS		
MARK	SNOW DRIFT (PSF)	SNOW WIDTH (X)
SP1	52.5	15'-0"
SP2	44.5	17'-8"
SP3	17.0	8'-0"




8 SPECIAL JOIST SCHEDULE

3/4" = 1'-0"



7 JOIST TO GIRDER DETAIL AT EXPANSION JOINT

3/4" = 1'-0"




PL5/8"x8"x1'-6" LONG WITH (4)-3/4" DIA. BOLTS EA. PLATE AT THIS BAY ONLY AT QUARTER POINTS. PROVIDE 13/16"x1 7/8" SLOTTED HOLES PERPENDICULAR TO JOIST AND BEAM EACH SIDE OF PLATE. HAND TIGHTEN AND BACK OFF 3/4" DIA A325 BOLTS THEN UPSET THREADS AT CENTER OF SLOT.

NOTE:
AT CONTRACTOR'S OPTION, WELDS MAY BE FIELD WELDS.


CONT. PLATE TO JOIST CENTERED ON PL. 5/8"

BEAM RE: PLAN. CAMBER BEAM TO MATCH CAMBER OF ADJACENT JOIST




6 JOIST TO BEAM DETAIL AT EXPANSION JOINT

3/4" = 1'-0"




5 GIRDER DETAIL AT EXPANSION JOINT

3/4" = 1'-0"




4 JOIST DETAIL AT EXPANSION JOINT

3/4" = 1'-0"




3 JOIST/JOIST GIRDER SECTION

3/4" = 1'-0"




2 GIRDER TO WALL PANEL FRAMING DETAIL

3/4" = 1'-0"




OPTION #2



1 JOIST GIRDER/COLUMN CONNECTION

3/4" = 1'-0"



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



Wallace Engineering
Structural Consultants, Inc.
Structural and Civil Consultants
1741 McGee Street
Kansas City, Missouri 64108
816.421.8282, Fax 816.421.8338

CERTIFICATION



08/15/2022
Missouri COA #001268

THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

NW CORNER TUDOR RD & MAINST
LEE'S SUMMIT, MO


ISSUE DATES

ISSUE	DATE
ISSUE FOR PERMIT	05.06.2022
ISSUE FOR PERMIT	08.15.2022

210300


S4.3

FRAMING DETAILS




5 BRACING CONNECTIONS

N.T.S.




4 BRACING CONNECTIONS

N.T.S.




3 BRACING CONNECTIONS

3/4" = 1'-0"




2 BRACING CONNECTIONS

N.T.S.



1 BRACED FRAME ELEVATIONS

1/8" = 1'-0"



1 Overall Mechanical Floor Plan
scale: 1" = 40'-0"



THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF CURRAN ARCHITECTURE, AND ARE NOT TO BE USED OR REPRODUCED, WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086




ISSUE DATES


PERMIT SET 04.26.22

220019

M1.1



2 Pump Room Mechanical Plan
scale: 1/8" = 1'-0"



3 MAU Curb Plan
scale: 1/8" = 1'-0"



MECHANICAL GENERAL NOTES:

1. ALL MECHANICAL DUCTWORK SHALL BE GALVANIZED STEEL, CONSTRUCTED ACCORDING TO SMACNA STANDARDS.
2. ALL RECTANGULAR SUPPLY, RETURN AND EXHAUST AIR DUCTWORK SHALL BE UNINSULATED. DUCTWORK DIMENSIONS SHOWN ARE ACTUAL SIZES.
3. HVAC CONTRACTOR WILL CHECK EACH SYSTEM FOR PROPER OPERATION UPON START-UP.
4. MAINTAIN MINIMUM 10'-0" FROM ALL PLUMBING VENTS AND EXHAUST VENTS TO ALL OUTSIDE AIR INTAKES.

MECHANICAL PLAN NOTES:

1. ELECTRIC UNIT HEATER FURNISHED BY MECHANICAL, INSTALLED BY ELECTRICAL CONTRACTOR.
2. GAS-FIRED MAKE-UP AIR UNIT PER SCHEDULE. ELECTRICIAN TO INSTALL THERMOSTAT/CONTROLLER ON NEAREST COLUMN AT 10'-0" A.F.F. (OR PER TENANT) SUPPLY AIR 32"X32", RETURN AIR 62"X14"
3. EXTEND 16X16 EXHAUST DUCT DOWN BELOW STRUCTURE WITH MESH OPENING. EXHAUST FAN TO BE CONTROLLED BY LINE VOLTAGE THERMOSTAT.
4. ROOF MOUNTED RELIEF AIR HOOD WITH BACKDRAFT DAMPER PER LEGEND. PROVIDE 36"X36" DUCTWORK DROP THRU ROOF WITH DAMPER INSTALLED AT BOTTOM.

LEGEND

- UH 1** DAYTON UNIT HEATER 10 KW, 460/3 PHASE - PROVIDE WITH UNIT MOUNTED THERMOSTAT. MOUNT BOTTOM OF HEATER 8'-0" A.F.F.
- L A** GREENHECK (OR EQUAL) INTAKE LOUVER MODEL ESD635, 24"X24" WITH BIRDSCREEN AND MOTORIZED 120V DAMPER. MOUNT BOTTOM OF LOUVER 6'-0" A.F.F. LOUVER TO BE INTERLOCKED WITH ROOF MOUNTED EXHAUST FAN EF-A.
- EF A** GREENHECK (OR EQUAL) ROOF MOUNTED EXHAUST FAN MODEL G-123, 1/3 HP @ 120/1 PHASE. PROVIDE WITH BACKDRAFT DAMPER, 14" ROOF CURB AND LINE VOLTAGE THERMOSTAT. FAN SIZED FOR 1,500 CFM @ 0.25 ESP.
- RH 1 THRU 4** GREENHECK (OR EQUAL) ROOF MOUNTED RELIEF HOOD FGR-36X36. PROVIDE WITH BACKDRAFT DAMPER & 14" ROOF CURB APPROXIMATELY 200 LBS WITH CURB. PROVIDE WITH 1/2" ARMAFLEX OR MANUFACTURER'S STANDARD INSULATION.
- MAU X** MAKE-UP AIR UNIT ON ROOF REFER TO EQUIPMENT SCHEDULE.

SYSTEM DESIGN:
253.96 SF
ROOF - R-20
WALLS - UN-INSULATED
ASHRAE DESIGN TEMPERATURE - (+)5° F
INDOOR DESIGN TEMPERATURE - 55° F

THIS PRINT IS CONFIDENTIAL TO METRO AIR CONDITIONING CO.
REPRODUCTION OR DISCLOSURE TO OUTSIDE PARTIES IS
PROHIBITED WITHOUT OUR WRITTEN CONSENT.
© 2022 METRO AIR CONDITIONING CO.




LEE'S SUMMIT LOGISTICS BLDG. #3		
NE TUDOR RD AND MAIN ST - LEE'S SUMMIT, MO		
SCALE: AS NOTED	DATE: 8/1/22	DRAWN BY: M.D.K.
APPROVED BY: M.D.K.	DWG #	M1
PERMIT		OF 2



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

8/24/2022



LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3


X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

PRELIMINARY SET	07.01.22
PERMIT SET	08.24.22

220018

PLUMBING PLAN
AREA A

P300



PLUMBING GENERAL NOTES:

1. INSTALL ALL PIPE, ETC., AS HIGH AS POSSIBLE.
2. COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
3. REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATIONS AND MOUNTING HEIGHTS OF FIXTURES.
4. REFER TO ARCHITECTURAL & STRUCTURAL DRAWINGS FOR REQUIREMENTS FOR SUPPORTING PIPING, EQUIPMENT, ETC., FROM THE STRUCTURE. PROVIDE ADDITIONAL STEEL AS REQUIRED TO PROPERLY SUPPORT SYSTEMS FROM THE STRUCTURE.
5. NO PIPING SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.

PLUMBING SYMBOLS


- | | |
|--|--|
| | SOL AND WASTE PIPING BELOW FLOOR/GRADE |
| | SOL AND WASTE PIPING ABOVE FLOOR/GRADE |
| | SANITARY VENT PIPING ABOVE GRADE |
| | SANITARY VENT PIPING BELOW GRADE |
| | DOMESTIC COLD WATER PIPING |
| | GAS PIPING |
| | FORCE MAIN PIPING BELOW FLOOR/GRADE |
| | PIPING TURNING DOWN |
| | PIPING TURNING UP |
| | TEE TOP CONNECTION |
| | UNION |
| | FLOOR CLEAN OUT |
| | WALL CLEAN OUT |
| | GRADE CLEAN OUT |
| | VALVE |
| | PRESSURE REGULATOR |
| | CONNECT TO EXISTING |
| | INVERT ELEVATION OF PIPE |

PLUMBING PLAN NOTES:

1. REFER TO CIVIL FOR 8" STORM PIPE. MAINTAIN A MIN. OF 24" COVER.
2. REFER TO CIVIL FOR 8" WASTE PIPE. MAINTAIN A MIN. OF 30" COVER.
3. CAP 1" WATER PIPE WITH SHUT-OFF VALVE FOR FUTURE CONNECTION.
4. INSTALL FREEZE PROOF WALL HYDRANT 18" ABOVE GRADE.
5. CONNECT GAS PIPING TO EQUIPMENT AS DETAILED.
6. GAS PIPE UP THROUGH ROOF TO MAUI CONNECTION. SEAL PENETRATION WEATHER TIGHT.
7. GAS PIPING BELOW ROOF SUPPORT AS REQUIRED.
8. GAS PIPING ON ROOF. SUPPORT AS REQUIRED AND DETAILED.
9. REFER TO CIVIL FOR CONTINUATION OF 3" DOMESTIC WATER. MAINTAIN A MIN. 48" COVER.



PARTIAL PLUMBING FLOOR PLAN "UNIT A"
SCALE: 1/16" = 1'-0"
FFE = 973.25'




KEY PLAN
SCALE: NTS

CENTRAL
PLUMBING, HEATING & AIR CONDITIONING, INC.
201 East Walnut
Cleveland, MO 64734
816-942-6355

BC PROJECT #:22522
MISSOURI PE COA #2009003629
This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, plans and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.


BC ENGINEERS
INCORPORATED

5720 Reeder Shawnee, KS 66203 (913)262-1772



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

8/24/2022



LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3


X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

PRELIMINARY SET	07.01.22
PERMIT SET	08.24.22

220018

PLUMBING PLAN
AREA B

P301



PLUMBING PLAN NOTES:

- REFER TO CIVIL FOR 8" STORM PIPE. MAINTAIN A MIN. OF 24" COVER.
- REFER TO CIVIL FOR 8" WASTE PIPE. MAINTAIN A MIN. OF 30" COVER.
- CAP 1" WATER PIPE WITH SHUT-OFF VALVE FOR FUTURE CONNECTION.
- INSTALL FREEZE PROOF WALL HYDRANT 18" ABOVE GRADE.
- CONNECT GAS PIPING TO EQUIPMENT AS DETAILED.
- GAS PIPE UP THROUGH ROOF TO MAU CONNECTION. SEAL PENETRATION WEATHER TIGHT.
- GAS PIPING BELOW ROOF SUPPORT AS REQUIRED.
- GAS PIPING ON ROOF. SUPPORT AS REQUIRED AND DETAILED.



PARTIAL PLUMBING FLOOR PLAN "UNIT B"

SCALE: 1/16" = 1'-0"

FFE = 973.25'



KEY PLAN
SCALE: NTS

CENTRAL

PLUMBING, HEATING & AIR CONDITIONING, INC.
201 East Walnut
Cleveland, MO 64734
816-942-6355

BC PROJECT #:22522
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, plans and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.


BC ENGINEERS
INCORPORATED

5720 Reeder Shawnee, KS 66203 (913)262-1772



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

8/24/2022



LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3


X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

PRELIMINARY SET 07.01.22
PERMIT SET 08.24.22

220018


PLUMBING PLAN
AREA C

P302



PLUMBING PLAN NOTES:

- 1 REFER TO CIVIL FOR 8" STORM PIPE. MAINTAIN A MIN. OF 24" COVER.
- 2 REFER TO CIVIL FOR 8" WASTE PIPE. MAINTAIN A MIN OF 30" COVER.
- 3 CAP 1" WATER PIPE WITH SHUT-OFF VALVE FOR FUTURE CONNECTION.
- 4 INSTALL FREEZE PROOF WALL HYDRANT 18" ABOVE GRADE.
- 5 CONNECT GAS PIPING TO EQUIPMENT AS DETAILED.
- 6 GAS PIPE UP THROUGH ROOF TO MAU CONNECTION. SEAL PENETRATION WEATHER TIGHT.
- 7 GAS PIPING BELOW ROOF SUPPORT AS REQUIRED.
- 8 GAS PIPING ON ROOF. SUPPORT AS REQUIRED AND DETAILED.



PARTIAL PLUMBING FLOOR PLAN "UNIT C"

SCALE: 1/16" = 1'-0" FFE = 973.25'



KEY PLAN
SCALE: NTS

CENTRAL
PLUMBING, HEATING & AIR CONDITIONING, INC.
201 East Walnut
Cleveland, MO 64734
816-942-6355

BC PROJECT #:22522
MISSOURI PE COA #2009003629
This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of space and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.


BC ENGINEERS
INCORPORATED

5720 Reeder Shawnee, KS 66203 (913)262-1772



CURRAN ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317.288.0681
F :: 317.288.0753



SCANNELL PROPERTIES

8/24/2022



LEE'S SUMMIT LOGISTICS BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086

PRELIMINARY SET	07.01.22
PERMIT SET	08.24.22

220018

PLUMBING
SPECIFICATIONS


P303

PLUMBING SPECIFICATIONS

- GENERAL PROVISIONS:
 - PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, NECESSARY FOR THE COMPLETE INSTALLATION OF THE PLUMBING AND MECHANICAL SYSTEMS OUTLINED.
 - OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE AUTHORITIES.
 - ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION OVER THE SITE.
 - ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.
 - DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, PIPE, DUCT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNDAMAGED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERINGS SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.
 - PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS AS NECESSARY. PATCH AROUND ALL OPENINGS SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.
 - CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
- OPERATION AND MAINTENANCE MANUALS:
 - DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, WIRING DIAGRAMS, CATALOG CUTS, LUBRICATION AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.
 - ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATION AND MAINTENANCE MANUALS.
 - ALL LITERATURE LISTED ABOVE AND ALL PAPERS LISTING WARRANTIES, ETC. SHALL BE BOUND IN A 3-RING BINDER AND LABELED WITH THE PROJECT NAME, ADDRESS, ARCHITECT, ENGINEER, CONTRACTORS, ETC.
- MANUFACTURERS:
 - MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSTRUED AS LIMITING COMPETITION. ARTICLES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO STRUCTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN, UNLESS NOTED OTHERWISE.
- TESTING, BALANCING, AND CLEANING:
 - ALL PIPING SHALL BE TESTED FOR LEAKS BEFORE BEING CONCEALED IN WALL CONSTRUCTION OR COVERED WITH INSULATION.
 - SEWER AND VENT PIPING SHALL BE HYDROSTATICALLY TESTED WITH NO LESS THAN 10 FEET OF HEAD FOR A PERIOD OF NOT LESS THAN 18 MINUTES, PER THE LOCAL PLUMBING CODE, WITH NO LEAKS.
 - DOMESTIC WATER PIPING SHALL BE HYDROSTATICALLY TESTED AT A PRESSURE OF NOT LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE, BUT NOT LESS THAN 60 PSI, FOR A PERIOD OF NOT LESS THAN 2 HOURS, WITH NO LEAKS.
 - NATURAL GAS PIPING SHALL BE PNEUMATICALLY TESTED AT A PRESSURE OF NOT LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE, BUT NOT LESS THAN 60 PSI, FOR A PERIOD OF NOT LESS THAN 2 HOURS, WITH NO LEAKS.
- BEFORE DOMESTIC WATER PIPING IS PLACED IN SERVICE, ALL DOMESTIC WATER DISTRIBUTION SYSTEMS, INCLUDING THOSE FOR COLD WATER AND HOT WATER SYSTEMS, SHALL BE FLUSHED, STERILIZED AND CHLORINATED IN ACCORDANCE WITH HEALTH DEPARTMENT REGULATIONS. THE SYSTEMS SHALL BE THOROUGHLY FLUSHED OF ALL DIRT AND FOREIGN MATTER, THEN FILLED WITH WATER TREATED WITH 50 PPM OF CHLORINE. DURING THE FILLING PROCESS, VALVES AND FAUCETS SHALL BE OPENED SEVERAL TIMES TO ASSURE TREATMENT OF THE ENTIRE SYSTEM. THE TREATED WATER SHALL BE LEFT IN THE SYSTEM FOR 24 HOURS AFTER WHICH THE SYSTEM SHALL BE FLUSHED. IF THE RESIDUAL CHLORINE IS NOT LESS THAN 10 PPM, THE FLUSHING SHALL BE REPEATED. AFTER STERILIZATION, SAMPLES OF WATER IN THE SYSTEM SHALL BE APPROVED BY THE BOARD OF HEALTH.
- PLUMBING:
 - PROVIDE AN APPROVED WATER HAMMER ARRESTOR FOR EACH PLUMBING FIXTURE SUPPLY AS REQUIRED BY FIXTURE MANUFACTURER.
 - ALL EXPOSED NASTE PIPE SHALL BE CHROME PLATED BRASS PIPE, NO FERROUS PIPE.
 - PROVIDE CLEANOUTS AT EACH CHANGE OF DIRECTION AND AT 100 FOOT INTERVALS IN STRAIGHT RUNS.
 - PROVIDE ACCESS PANELS FOR ALL CONCEALED VALVES AND TRAPS.
 - CLEANOUTS:
 - VINYL TILE FLOOR: JR SMITH #4140, OR EQUAL.
 - QUARRY TILE FLOOR: JR SMITH #4200, OR EQUAL.
 - CARPETED FLOOR: JR SMITH #4020, OR EQUAL.
 - UNFINISHED FLOOR: JR SMITH #4020, OR EQUAL.
 - WALL: JR SMITH #4410, OR EQUAL, 24" ABOVE THE FLOOR.
 - WAREHOUSE FLOORS/FORK TRUCK AREAS: JR SMITH #4100, OR EQUAL, WITH HEAVY DUTY CAST IRON BODY AND ROUND ADJUSTABLE SCORRATED EXTRA HEAVY DUTY NICKEL BRONZE TOP.
 - GRADE: JR SMITH #4250, OR EQUAL, WITH HEAVY DUTY CAST IRON BODY AND COVER.
 - PROVIDE DIELECTRIC UNIONS WITH APPROPRIATE END CONNECTIONS TO MATCH THE PIPE SYSTEM IN WHICH INSTALLED (SCREWED, SOLDERED, OR FLANGED). PROVIDE DIELECTRIC UNIONS ON ALL PIPING CONNECTIONS TO HOT WATER HEATERS AND EXPANSION TANKS.
 - WATER HEATERS:
 - EVERY WATER HEATER SHALL HAVE AN APPROVED MEANS INSTALLED ON THE COLD WATER SUPPLY LINE ABOVE THE EQUIPMENT TO PREVENT SIPHONING OF A STORAGE WATER HEATER OR TANK.
 - BOTTOM FED WATER HEATERS AND TANKS CONNECT TO WATER HEATERS SHALL HAVE A VACUUM RELIEF VALVE INSTALLED ANSI Z21.22.
 - STORAGE HEATERS OPERATING ABOVE ATMOSPHERIC PRESSURE SHALL HAVE AN APPROVED PRESSURE RELIEF VALVE AND/OR TEMPERATURE RELIEF VALVE.
 - ALL SEWER PIPING LOCATED INSIDE THE BUILDING SHALL BE INSTALLED WITH THE FOLLOWING SLOPES:
 - INSTALL 2-1/2" AND SMALLER PIPE AT 1/4" PER FOOT FALL.
 - INSTALL 3" - 6" PIPE AT 1/8" PER FOOT FALL.
 - INSTALL 2" AND LARGER PIPE AT 1/16" PER FOOT FALL.
- PIPING:
 - DOMESTIC COLD, HOT, AND HOT WATER REGULATOR (ABOVEGROUND).
 - TYPE L HARD DRAWN COPPER TUBING, ASTM B-88.
 - WROUGHT COPPER SOLDERED FITTINGS, ASTM B75 ALLOY C12200, ANSI B16.22, MSS SP-104.
 - MECHANICAL PRESS COPPER FITTINGS FOR USE IN PLUMBING OR MECHANICAL APPLICATIONS, ASME B16.22, ASME B16.51, OR ASME B16.10. MECHANICAL PRESS COPPER FITTINGS SHALL CONFORM TO JAWMO PS-117 OR ASME B16.51.
 - PEX, HIGH-DENSITY CROSS-LINKED POLYETHYLENE TUBING SHALL BE MANUFACTURED TO THE REQUIREMENTS OF ASTM F876 AND MEET THE STANDARD GRADE HYDROSTATIC PRESSURE RATINGS FROM PLASTIC PIPE INSTITUTE IN ACCORDANCE WITH TR-4/C23.
 - PEX-A AND PEX-B MEETING ANSI/NSF61 AND ANSI/NSF312 STANDARDS FOR POTABLE WATER SAFETY AND LEAD-FREE STANDARDS AND MUST BE MARKED WITH "PPH-G", "NSF-61-G" OR OTHER NSF-APPROVED MARKING. ASTM F2023 FOR USE WITH CHLORINATED WATER.
 - PEX MECHANICAL CRIMP/INSERT OR EXPANSION FITTINGS INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. PIPE SIZES GIVEN ON THE DRAWINGS ARE NOMINAL COPPER PIPE SIZE, INCREASE PEX PIPING SIZE TO EQUAL OR EXCEED COPPER PIPE INSIDE DIAMETER FOR SUPPLY MAINS.
 - VALVES:
 - TO BE INSTALLED ON THE FIXTURE SUPPLY TO EACH PLUMBING FIXTURE.
 - TO BE INSTALLED ON THE WATER SUPPLY SIDE TO EACH APPLIANCE OR MECHANICAL EQUIPMENT.
 - TYPES:
 - GATE VALVE: JOMAR TYS-301G OR EQUAL. LEAD-FREE NSF 61, ANSI B1.20.1.
 - GLOBE VALVE: JOMAR T65G OR EQUAL.
 - BALL VALVE: JOMAR JF100PXP OR EQUAL. COMPACT LEAD FREE BRASS BALL VALVE. UL842, CSA B371-12 & B371-12, FM, CALIFORNIA CODE AB189, NSF61 ANNEX 5 APPROVED.
 - BALL VALVE: JOMAR T100NE OR EQUAL. UL842, FM, CSA, NSF 61-G, MSS SP-110.
- DOMESTIC COLD, HOT, AND HOT WATER (UNDERGROUND).
 - TYPE L HARD DRAWN COPPER TUBING, ASTM B-88.
 - WROUGHT COPPER SOLDERED FITTINGS, ASTM B75 ALLOY C12200, ANSI B16.22, MSS SP-104.
 - MECHANICAL PRESS COPPER FITTINGS FOR USE IN PLUMBING OR MECHANICAL APPLICATIONS, ASME B16.22, ASME B16.51, OR ASME B16.10. MECHANICAL PRESS COPPER FITTINGS SHALL CONFORM TO JAWMO PS-117 OR ASME B16.51.
 - PEX, HIGH-DENSITY CROSS-LINKED POLYETHYLENE TUBING SHALL BE MANUFACTURED TO THE REQUIREMENTS OF ASTM F876 AND MEET THE STANDARD GRADE HYDROSTATIC PRESSURE RATINGS FROM PLASTIC PIPE INSTITUTE IN ACCORDANCE WITH TR-4/C23.
 - PEX-A AND PEX-B MEETING ANSI/NSF61 AND ANSI/NSF312 STANDARDS FOR POTABLE WATER SAFETY AND LEAD-FREE STANDARDS AND MUST BE MARKED WITH "PPH-G", "NSF-61-G" OR OTHER NSF-APPROVED MARKING. ASTM F2023 FOR USE WITH CHLORINATED WATER.
 - PEX MECHANICAL CRIMP/INSERT OR EXPANSION FITTINGS INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. PIPE SIZES GIVEN ON THE DRAWINGS ARE NOMINAL COPPER PIPE SIZE, INCREASE PEX PIPING SIZE TO EQUAL OR EXCEED COPPER PIPE INSIDE DIAMETER FOR SUPPLY MAINS.
 - HOPE, PIGMENTED BLUE THROUGHOUT, CTS SIZES 1"-2" ANVVA C401 4110 DR4 DR250 IPS SIZES 2"-3", ANVVA C401 4110 DR4 DR250.
- DOMESTIC WATER SERVICE, 1"-3"
 - TYPE K SOFT DRAWN COPPER TUBING, ASTM B-88.
 - Cast Copper Alloy Fittings for Flared Copper Tube, ASME/ANSI B16.26:
- HOPE, PIGMENTED BLUE THROUGHOUT, CTS SIZES 1"-2" ANVVA C401 4110 DR4 DR250 IPS SIZES 2"-3", ANVVA C401 4110 DR11 PC200 MATERIAL AND INSTALLATION MUST CONFORM TO WATER DEPARTMENT REQUIREMENTS.
- LEAD CONTENT OF WATER SUPPLY PIPE AND FITTINGS:
 - PIPE AND PIPE FITTINGS, INCLUDING VALVES AND FAUCETS, UTILIZED IN THE WATER SUPPLY SYSTEM SHALL NOT HAVE MORE THAN 0% LEAD CONTENT.
 - PIPE, PIPE FITTINGS, JOINTS, VALVES, FAUCETS, AND FIXTURE FITINGS UTILIZED TO SUPPLY WATER FOR DRINKING OR COOKING PURPOSES SHALL COMPLY WITH NSF 312 AND SHALL HAVE A NEIGHED AVERAGE LEAD CONTENT OF 0.25% OR LESS.

PLUMBING SPECIFICATIONS (CONTINUED)

- STORM SEWER, SANITARY SEWER, GREASE WASTE, SAND OIL WASTE, AND VENTS (UNDERGROUND, INTERIOR TO THE BUILDING).
 - ABS SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DNV FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM ABS COMPOUND WITH A CELL CLASS OF 42222 FOR PIPE AND 32222 FOR FITTINGS AS PER ASTM D 3965 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620. FITTINGS SHALL CONFORM TO ANY ACTIVATED PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.
 - PVC SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DNV FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 11432 PER ASTM D 4396 FOR PIPE AND 12484 PER ASTM D 1184 FOR FITTINGS AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 641. INJECTION MOLDED FITTINGS SHALL CONFORM TO ASTM D 2665. FABRICATED FITTINGS SHALL CONFORM TO ASTM F 1066. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564.
 - PVC SCHEDULE 40 SOLID WALL PIPE AND DNV FITTING SYSTEM (ASTM D 2665) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 12454 PER ASTM D 1184 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM D 1185 AND ASTM D 2665. INJECTION MOLDED FITTINGS SHALL CONFORM TO ASTM D 2665. FABRICATED FITTINGS SHALL CONFORM TO ASTM F 1066. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564.
 - HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 889 AND CSPI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO CSPI STANDARD 310 AND BE CERTIFIED BY NSF6 INTERNATIONAL.
 - HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
- STORM SEWER, SANITARY SEWER, GREASE WASTE, SAND OIL WASTE, AND VENTS (ABOVE GROUND, INTERIOR TO THE BUILDING).
 - ABS SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DNV FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM ABS COMPOUND WITH A CELL CLASS OF 42222 FOR PIPE AND 32222 FOR FITTINGS AS PER ASTM D 3965 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620. FITTINGS SHALL CONFORM TO ASTM D 2665. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2235. (NOT FOR USE IN A RETURN AIR PLENUM)
 - PVC SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DNV FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 11432 PER ASTM D 4396 FOR PIPE AND 12484 PER ASTM D 1184 FOR FITTINGS AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM D 1185 AND ASTM D 2665. INJECTION MOLDED FITTINGS SHALL CONFORM TO ASTM D 2665. FABRICATED FITTINGS SHALL CONFORM TO ASTM F 1066. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564. (WHERE APPROVED BY LOCAL JURISDICTIONS) (NOT FOR USE IN A RETURN AIR PLENUM)
 - PVC SCHEDULE 40 SOLID WALL PIPE AND DNV FITTING SYSTEM (ASTM D 2665) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 12454 PER ASTM D 1184 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM D 1185 AND ASTM D 2665. INJECTION MOLDED FITTINGS SHALL CONFORM TO ASTM D 2665. FABRICATED FITTINGS SHALL CONFORM TO ASTM F 1066. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564. (WHERE APPROVED BY LOCAL JURISDICTIONS) (NOT FOR USE IN A RETURN AIR PLENUM)
 - HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 889 AND CSPI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO CSPI STANDARD 310 AND BE CERTIFIED BY NSF6 INTERNATIONAL.
 - HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
- STORM SEWER, SANITARY SEWER, GREASE WASTE, SAND OIL WASTE, AND VENTS (UNDERGROUND, EXTERIOR TO THE BUILDING).
 - ABS SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DNV FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM ABS COMPOUND WITH A CELL CLASS OF 42222 FOR PIPE AND 32222 FOR FITTINGS AS PER ASTM D 3965 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620. FITTINGS SHALL CONFORM TO ASTM D 2665. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2235. (NOT FOR USE IN A RETURN AIR PLENUM)
 - PVC SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DNV FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 11432 PER ASTM D 4396 FOR PIPE AND 12484 PER ASTM D 1184 FOR FITTINGS AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 641. INJECTION MOLDED FITTINGS SHALL CONFORM TO ASTM D 2665. FABRICATED FITTINGS SHALL CONFORM TO ASTM F 1066. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564.
 - PVC SCHEDULE 40 SOLID WALL PIPE AND DNV FITTING SYSTEM (ASTM D 2665) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 12454 PER ASTM D 1184 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 174. FITTINGS SHALL CONFORM TO ASTM F 174.
 - SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564.
 - HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 889 AND CSPI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO CSPI STANDARD 310 AND BE CERTIFIED BY NSF6 INTERNATIONAL.
 - HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
 - COPPER DNV: DRAINAGE TUBE SHALL CONFORM TO ASTM B306, WROUGHT COPPER FITTINGS, ANSI B16-24.
 - GALVANIZED STEEL PIPE WITH MALLEABLE IRON, THREADED FITTINGS, DRAINAGE PATTERN FOR SEWERS SHALL CONFORM TO ASTM A 53.
- NATURAL GAS.
 - BLACK STEEL PIPE, SCHEDULE 40, ASTM A53.
 - PIPE 3" AND SMALLER, 150 LB. MALLEABLE IRON, THREADED FITTINGS.
 - PIPE 4" AND SMALLER, WEGA MEGA PRESS 6" FOR WATER AND GAS, CSA C14, T55A/ASME B31 FOR USE WITH ASTM A53 SCHEDULE 40 BLACK IRON PIPE.
 - PIPE 2-1/2" AND LARGER, WELDED.
 - PLUG VALVE: ROCKWELL NORDSTROM FIGURE NO. 143 OR 143.
 - BALL VALVE: JOMAR T100NE APPROVALS: UL842, FM, CSA, NSF 61-G, MSS SP-110.
 - GAS PIPING LABELING:
 - ALL ELEVATED PRESSURE GAS PIPING SHALL BE LABELED EVERY 40 FEET WITH SIGNS INDICATING "ELEVATED PRESSURE".
 - GAS PIPING PAINTING:
 - ALL BLACK STEEL GAS PIPING LOCATED EXTERIOR TO THE BUILDING SHALL BE PRIMED AND PAINTED TO EITHER MATCH ADJACENT EXTERIOR WHERE LOCATED OR NEAR EXTERIOR WALL AND PAINTED SAFETY YELLOW WHEN LOCATED ON THE ROOF.
- ALL PIPE HANGERS AND SUPPORTS SHALL BE STANDARD PRODUCTS OF GRINNELL, FEE AND MASON, OR EUGEN. HANGER SPACING SHALL BE IN ACCORDANCE WITH MSS-SP-64.
- SLEEVES
 - PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK. ALL SLEEVES SHALL BE OF SUFFICIENT SIZE TO PERMIT PIPE MOVEMENT DUE TO EXPANSION AND CONTRACTION AND TO ACCOMMODATE PIPE AND FITTING.
 - INTERIOR PARTITIONS: 16 GAGE GALVANIZED STEEL, PACK BETWEEN PIPE AND SLEEVE WITH FIRE RATING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.
 - ROOF: PROSET OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WATERPROOF SEAL. COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF WARRANTY.
 - PROTECTION AGAINST CONTACT: METALLIC PIPING, EXCEPT FOR CAST IRON, DUCTILE IRON AND GALVANIZED STEEL, SHALL NOT BE PLACED IN DIRECT CONTACT WITH STEEL, FRAMING MEMBERS, CONCRETE, OR OTHER WALLS AND FLOORS OR OTHER MASONRY. METALLIC PIPING SHALL NOT BE PLACED IN DIRECT CONTACT WITH CORROSIVE SOIL. SHEATHING USED TO PREVENT DIRECT CONTACT SHALL HAVE A THICKNESS OF GREATER THAN .005" AND THE SHEATHING SHALL BE MADE OF PLASTIC. ANY PIPE THAT PASSES THROUGH A FOUNDATION WALL OR FOOTING SHALL BE PROVIDED WITH A RELIEVING ARCH, OR A PIPE SLEEVE SHALL BE BUILT INTO THE FOUNDATION WALL. THE SLEEVE SHALL BE TWO SIZES GREATER THAN THE PIPE PASSING THROUGH THE WALL OR FOOTING.
 - PLUMBING VENTS: FLASH ROOF VENT INTO ROOFING SYSTEM AS REQUIRED BY THE ROOFING CONTRACTOR TO MAINTAIN EXISTING ROOF WARRANTY. ALL PLUMBING VENT TERMINALS SHALL TERMINATE A MINIMUM OF 12" ABOVE ROOF OR EQUAL TO HEIGHT OF PARAPET, WHICHEVER IS GREATER.
- INSULATION:
 - ALL INSULATIONS AND ACCESSORIES SHALL HAVE A FIRE HAZARD CLASSIFICATION WITH A FLAME SPREAD RATING OF NOT OVER 25, A FUEL CONTRIBUTION RATING OF NOT OVER 50, AND A SMOKE DEVELOPED RATING OF NOT OVER 50, IN ACCORDANCE WITH NFPA.
- PIPE INSULATION - ABOVE GRADE:
 - THE PIPING INSULATION USED SHALL HAVE A THERMAL CONDUCTIVITY OF 0.21 Btu PER IN/FT²°F" OR LESS.
 - FIBERGLASS INSULATION WITH FACTORY APPLIED VAPOR BARRIER, ASJ JACKET, FACTORY APPLIED PRESSURE SEALING LONGITUDE LAP JOINT AND STAPLES, TESTED PREMOULDED PVC FITTING COVERS. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
 - FLEXIBLE CLOSED CELL ELASTOMERIC THERMAL INSULATION, INSULT OR PRESILT WITH PRESSURE SENSITIVE ADHESIVE SYSTEM FOR CLOSURE AND VAPOR SEALING, EQUAL TO ARMSTRONG AF ARMATLEX OR ARMALEX 2000.
 - FOR NON REGULATING SYSTEMS, THE FIRST 8 FEET OF INLET AND OUTLET PIPING BETWEEN THE TANK AND THE HEAT TRAP (INCLUDING THE HEAT TRAP) MUST BE INSULATED.
 - FOR CIRCULATING SYSTEMS, ALL HOT WATER PIPING IN THE CIRCULATION LOOP MUST BE INSULATED AS SPECIFIED BELOW.
 - INSULATION SCHEDULE:
 - DOMESTIC COLD WATER 1/2"
 - DOMESTIC HOT WATER 1" FOR PIPING UP TO 1-1/4", 1-1/2" FOR PIPING 1-1/2" AND LARGER
 - HOT WATER REGULATING 1"
 - CONDENSATE DRAINS INSIDE BUILDING 1/2"
 - REFRIGERANT SUCTION 3/4" FOR PIPING UP TO 1-1/4", 1" FOR PIPING 1-1/2" AND LARGER
 - HORIZONTAL STORM PIPE 1/2"
 - HORIZONTAL STORM OVERFLOW PIPE 1/2"
 - ROOF DRAINS 1" INSULATION SHALL BE PROVIDED AT ROOF DRAIN BODY AND A MINIMUM OF 10" OF HORIZONTAL PIPING OR A MINIMUM OF 5' IF COMBINATION OF HORIZONTAL AND VERTICAL STORM PIPING DOWNSTREAM OF ROOF DRAIN BODY.




GAS PRESSURE REGULATORS FOR ROOFTOP UNITS (RTU) AND MAKE-UP AIR UNITS (MAU) SHALL BE SENSUS #143-80-2, 2 PSI INLET / 1" VC OUTLET PRESSURE WITH THE ORIFICE 1 SPRING SIZE AS RECOMMENDED BY THE MANUFACTURER.

GAS CONNECTION DETAIL


SCALE: NONE

FOR ROOFTOP UNITS, MAKE-UP AIR UNITS, ETC. WITH 2 PSI GAS PRESSURE




ROOF PIPE SUPPORT DETAIL

SCALE: NONE



HOT & COLD WATER



WASTE & VENT

PLUMBING RISER DIAGRAMS

SCALE: NONE

PLUMBING FIXTURE SCHEDULE: (OR EQUAL)


FD	FLOOR DRAIN: JR SMITH #200B-A, CAST IRON FLOOR DRAIN WITH ADJUSTABLE TOP, 6" NIKALOY STRAINER. PROVIDE WITH #2642 QUAD CLOSE TRAP SEAL DEVICE.
FCO	WAREHOUSE FLOOR FLOOR CLEANOUT: JR SMITH #4100, OR EQUAL
GCO	GRADE CLEANOUT: JR SMITH #4256, OR EQUAL
FFWH	FREEZEPROOF WALL HYDRANT: JR SMITH #5609, 3/4" SIZE, NICKEL-BRONZE FACE, KEY OPERATED, INTEGRAL VACUUM BREAKER.
HB	HOSE BIBB: WOODFORD, #24, 3/4" HOSE NOZZLE OUTLET, BRASS FINISH, HANDWHEEL OPERATED, INTEGRAL VACUUM BREAKER.
RPZ	REDUCED ZONE PRESSURE BACKFLOW PREVENTOR: MATTS #LF009, LEAD FREE BRONZE BODY CONSTRUCTION, TWO, IN-LINE INDEPENDENT CHECK VALVES, REPLACEABLE CHECK SEATS WITH AN INTERMEDIATE RELIEF VALVE, AND BALL VALVE TEST COCKS.

BC PROJECT #:22522
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, views and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.

CENTRAL
PLUMBING, HEATING & AIR CONDITIONING, INC.
201 East Walnut
Cleveland, MO 64734
816-942-6355

BC ENGINEERS
INCORPORATED
5720 Reeder Shawnee, KS 66203 (913)262-1772



CURRAN
ARCHITECTURE
5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES


CERTIFICATION

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086




ISSUE DATES

PERMIT SET	04.26.22
PUMP ROOM MOVE	08.16.22


220019

LIGHTING PLAN

EI.00



1 LIGHTING PLAN
1" = 40'




2 ENLARGED FIRE PUMP ROOM
1/4" = 1'

HERITAGE ELECTRIC, L.L.C.
841 N. MARTWAY
Olathe, Kansas
phone (913) 747 0528
fax (913) 747 0539



THIS DRAWING HAS BEEN PRODUCED BY HERITAGE
ELECTRIC, LLC. FOR THEIR COORDINATION OF THE
ELECTRICAL INSTALLATION AND MAY NOT BE USED
FOR ANY OTHER PURPOSE.
COPYRIGHT 2008, HERITAGE ELECTRIC, LLC.

THE SEAL OF THE ELECTRICAL P.E. APPLIES
TO ONLY THIS DRAWING. SPECIFICATIONS AND OTHER
DOCUMENTS BEARING THE PERSONAL SEAL OF THE
UNDERSIGNED PROFESSIONAL AND DISCLAIM ANY
RESPONSIBILITY FOR ALL OTHER DRAWINGS.
SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER
DOCUMENTS WHICH DO NOT CONTAIN THE PERSONAL
SEAL OF THE UNDERSIGNED PROFESSIONAL.



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753

SCANNELL
PROPERTIES

CERTIFICATION

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086



7/16/22


ISSUE DATES

PERMIT SET	04.26.22
PUMP ROOM MOVE	08.16.22


220019

POWER PLAN

E2.00



1 POWER PLAN
1" = 40'




2 ENLARGED FIRE PUMP ROOM
1/4" = 1'



HERITAGE ELECTRIC, L.L.C.
841 N. MARTWAY
Olathe, Kansas
phone (913) 747 0528
fax (913) 747 0539

THIS DRAWING HAS BEEN PRODUCED BY HERITAGE
ELECTRIC, LLC. FOR THEIR COORDINATION OF THE
ELECTRICAL INSTALLATION AND MAY NOT BE USED
FOR ANY OTHER PURPOSE.
COPYRIGHT 2008, HERITAGE ELECTRIC, LLC.

THE SEAL OF THE ELECTRICAL P.E. APPLIES
TO ONLY THIS DRAWING. SPECIFICATIONS AND OTHER
DOCUMENTS BEARING THE PERSONAL SEAL OF THE
UNDERSIGNED PROFESSIONAL AND DISCLAIM ANY
RESPONSIBILITY FOR ALL OTHER DRAWINGS.
SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER
DOCUMENTS WHICH DO NOT CONTAIN THE PERSONAL
SEAL OF THE UNDERSIGNED PROFESSIONAL.



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES


CERTIFICATION

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086




ISSUE DATES

PERMIT SET	04.26.22
PUMP ROOM MOVE	08.16.22

220019

UNDERGROUND

E3.00




 **1 UNDERGROUND PLAN**
1" = 40'



HERITAGE ELECTRIC, L.L.C.
841 N. MARTWAY
Olathe, Kansas
phone (913) 747 0528
fax (913) 747 0539

THIS DRAWING HAS BEEN PRODUCED BY HERITAGE
ELECTRIC, LLC. FOR THEIR COORDINATION OF THE
ELECTRICAL INSTALLATION AND MAY NOT BE USED
FOR ANY OTHER PURPOSE.
COPYRIGHT 2008, HERITAGE ELECTRIC, LLC.

THE SEAL OF THE ELECTRICAL P.E. APPLIES
TO ONLY THIS DRAWING, SPECIFICATIONS AND OTHER
DOCUMENTS BEARING THE PERSONAL SEAL OF THE
UNDERSIGNED PROFESSIONAL AND DISCLAIM ANY
RESPONSIBILITY FOR ALL OTHER DRAWINGS,
SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER
DOCUMENTS WHICH DO NOT CONTAIN THE PERSONAL
SEAL OF THE UNDERSIGNED PROFESSIONAL.



CURRAN ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL PROPERTIES

CERTIFICATION

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086



9/16/22

ISSUE DATES

PERMIT SET 04.26.22
PUMP ROOM MOVE 08.16.22



THIS DRAWING HAS BEEN PRODUCED BY HERITAGE
ELECTRIC, LLC. FOR THEIR COORDINATION OF THE
ELECTRICAL INSTALLATION AND MAY NOT BE USED
FOR ANY OTHER PURPOSE.
COPYRIGHT 2008, HERITAGE ELECTRIC, LLC.

THE SEAL OF THE ELECTRICAL P.E. APPLIES
TO ONLY THIS DRAWING. SPECIFICATIONS AND OTHER
DOCUMENTS BEARING THE PERSONAL SEAL OF THE
UNDERSIGNED PROFESSIONAL AND DISCLAIM ANY
RESPONSIBILITY FOR ALL OTHER DRAWINGS,
SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER
DOCUMENTS WHICH DO NOT CONTAIN THE PERSONAL
SEAL OF THE UNDERSIGNED PROFESSIONAL.

220019

PHOTOMETRIC

E4.00



BIRKDALE
LEE'S SUMMIT LOGISTICS
BUILDING C
SITE LIGHTING


Designer
SJD
Date
3/27/2022
Scale
See Drawing
Drawing No.
Summary
1 of 1

HERITAGE ELECTRIC, L.L.C.
841 N. MARTWAY
Olathe, Kansas
phone (913) 747 0528
fax (913) 747 0539


Schedule							
Symbol	Label	Quantity	Manufacturer	Catalog Number	Number Lumens	Lumens Per Lamp	Wattage
P2		1	Hubbell Lighting Inc, dbe Beacon Products	VP-S-48L-110- 4K7-2	1	12514	0.9
P3		10	Hubbell Lighting Inc, dbe Beacon Products	VP-S-48L-110- 4K7-3	1	12275	0.9
W		22	Beacon Products	VP-L-96L-280- 4K7-4	1	31891	0.9

Statistics						
Description	Symbol	Max	Min	Max/Min	Avg/Min	Avg
NORTH TRAILER COURT	+	5.7 fc	0.3 fc	19.0:1	6.7:1	2.0 fc
ROADS	+	5.2 fc	0.2 fc	26.0:1	10.5:1	2.1 fc
SOUTH EMPLOYEE PARKING	+	5.2 fc	0.4 fc	13.0:1	4.8:1	1.9 fc

1/8"=1'-0"



1 PHOTOMETRIC PLAN
N.T.S



CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753




CERTIFICATION

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086




ISSUE DATES

PERMIT SET	04.26.22
PUMP ROOM MOVE	08.16.22

220019
SITE

E5.00



1 SITE PLAN
1" = 500'

HERITAGE ELECTRIC, L.L.C.
841 N. MARTWAY
Olathe, Kansas
phone (913) 747 0528
fax (913) 747 0539




THIS DRAWING HAS BEEN PRODUCED BY HERITAGE
ELECTRIC, LLC. FOR THEIR COORDINATION OF THE
ELECTRICAL INSTALLATION AND MAY NOT BE USED
FOR ANY OTHER PURPOSE.
COPYRIGHT 2008, HERITAGE ELECTRIC, LLC.

THE SEAL OF THE ELECTRICAL P.E. APPLIES
TO ONLY THIS DRAWING. SPECIFICATIONS AND OTHER
DOCUMENTS BEARING THE PERSONAL SEAL OF THE
UNDERSIGNED PROFESSIONAL AND DISCLAIM ANY
RESPONSIBILITY FOR ALL OTHER DRAWINGS.
SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER
DOCUMENTS WHICH DO NOT CONTAIN THE PERSONAL
SEAL OF THE UNDERSIGNED PROFESSIONAL.

CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216
O :: 317 . 288 . 0681
F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086



9/16/22


ISSUE DATES


PERMIT SET 04.26.22
PUMP ROOM MOVE 08.16.22

220019

RISER DIAGRAM

E6.00





CURRAN
ARCHITECTURE

5719 LAWTON LOOP E. DR. #212
INDIANAPOLIS, IN 46216

O :: 317 . 288 . 0681

F :: 317 . 288 . 0753



SCANNELL
PROPERTIES

CERTIFICATION

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF CURRAN ARCHITECTURE, AND ARE NOT
TO BE USED OR REPRODUCED, WHOLE OR
IN PART, WITHOUT THE WRITTEN
CONSENT OF CURRAN ARCHITECTURE.
© COPYRIGHT 2021, CURRAN ARCHITECTURE

PROJECT INFORMATION

LEE'S SUMMIT LOGISTICS
BUILDING C LOT 3

X CORNER OF
NE TUDOR RD & MAIN ST
LEE'S SUMMIT, MO 64086



8/16/22

ISSUE DATES

PERMIT SET 04.16.22
PUMP ROOM MOVE 08.16.22



THIS DRAWING HAS BEEN PRODUCED BY HERITAGE
ELECTRIC, LLC, FOR THEIR COORDINATION OF THE
ELECTRICAL INSTALLATION AND MAY NOT BE USED
FOR ANY OTHER PURPOSE.
COPYRIGHT 2008, HERITAGE ELECTRIC, LLC.

THE SEAL OF THE ELECTRICAL P.E. APPLIES
TO ONLY THIS DRAWING. SPECIFICATIONS AND OTHER
DOCUMENTS BEARING THE PERSONAL SEAL OF THE
UNDERSIGNED PROFESSIONAL AND DISCLAIM ANY
RESPONSIBILITY FOR ALL OTHER DRAWINGS,
SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER
DOCUMENTS WHICH DO NOT CONTAIN THE PERSONAL
SEAL OF THE UNDERSIGNED PROFESSIONAL.

220019

PANEL SCHEDULE

E7.00

PANEL: H1 400A MB 277/ 480 V, 3PH, 4W, +GRND. NEW									
CCT	SERVICES	VA	DCP	WIRE	PHASE	WIRE	DCP	VA	SERVICES
1	PANEL HA	10683	1003	4#4 AL-1#63	A	4#4 AL-1#63	1063	10198	PANEL HC
2		10683			B			10683	
3		7668			C			7668	
5		10158	1003	4#4 AL-1#63	A	4#4 AL-1#63	1003	10158	PANE HD
6		9858			B			9858	
9		7668			C			7668	
11		9017	1003	4#4 AL-1#63	A		7668		
13	PANEL HA				A				
15		8361			B				
17		8213			A				
19					A				
21					B				
23					A				
25					A				
27					B				
29					A				
31					A				
33					B				
35					C				
37					A				
39					B				
41					C				
NOTES: 1 NEMA 3R ENCLOSURE 2 PROVIDE BOLT ON BREAKERS 3									
LOAD SUMMARY									
1 LIGHTING 0 1.25 6300 PHASE A 4889									
2 RECEPTACLES 13308 NEC 2001 7344 PHASE B 6254									
3 SWITCHEN 0 0.65 0 PHASE C 2966									
4 HVAC 0 1 1994 LOWEST PHASE PLUS 10% 1994									
5 SNON CONT 0 1 0 3005 3005 + 10% 4265.5									
6 LARGEST MOTOR 0 0.25 0 REBALANCE LOADS									
TOTAL VA 137080 7344									
TOTAL AMPS 564.9 88.1									

PANEL: HA 100A MLO 277/ 480 V, 3PH, 4W, +GRND. NEW PANEL									
CCT	SERVICES	VA	DCP	WIRE	PHASE	WIRE	DCP	VA	SERVICES
1	WAREHOUSE LIGHTS	250	201	2#12-1#103	A	3#8-1#103	403	668	MAU1
2		250	201	2#12-1#103	B			668	
3	WAREHOUSE LIGHTS	250	201	2#12-1#103	C			668	
5	OVERHEAD DOOR	200	203	4#10-1#103	A				
7		200			B				
9		200			A				
11		200			B				
13					C				
15					A				
17					B				
19					A				
21					B				
23					C				
25					A				
27					B				
29					C				
31					A				
33					B				
35					C				
37					A	3#8-1#103	503	1000	TRANSFORMER
39					B			800	TRANSFORMER
41					C			800	TRANSFORMER
NOTES: 1 NEMA 1 ENCLOSURE 2 PROVIDE BOLT ON BREAKERS 3									
LOAD SUMMARY									
1 LIGHTING 500 1.25 6300 PHASE A 1038									
2 RECEPTACLES 2800 NEC 2001 2800 PHASE B 10168									
3 SWITCHEN 0 0.65 0 PHASE C 7668									
4 HVAC 1994 1 1994 LOWEST PHASE PLUS 10% 1994									
5 SNON CONT 600 1 600 7668 7668 + 10% 8412.8									
6 LARGEST MOTOR 0 0.25 0 REBALANCE LOADS									
TOTAL VA 28104 2844									
TOTAL AMPS 31.9 35.4									

PANEL: LB 100 MB 120/ 208 V, 3PH, 4W, +GRND. NEW PANEL									
CCT	SERVICES	VA	DCP	WIRE	PHASE	WIRE	DCP	VA	SERVICES
1	DOCK POWER	80	201	2#12-1#103	A			200	GFCI RECP
3	DOCK POWER	1200	201	2#12-1#103	B			200	
5	SPARE		201		A		201	SPARE	
7	SPARE		201		A		201	SPARE	
9	SPARE		201		B		201	SPARE	
11	SPARE		201		C		201	SPARE	
13	SPARE		201		A		201	SPARE	
15	SPACE				B	-			
17	SPACE				C	-			
19	SPACE				A	-			
21	SPACE				B	-			
23	SPACE				C	-			
25	SPACE				A	-			
27	SPACE				B	-			
29	SPACE				C	-			
31	SPACE				A	-			
33	SPACE				B	-			
35	SPACE				C	-			
37	SPACE				A	-			
39	SPACE				B	-			
41	SPACE				C	-			
NOTES: 1 NEMA 1 ENCLOSURE 2 PROVIDE BOLT ON BREAKERS 3									
LOAD SUMMARY									
1 LIGHTING 0 1.25 6300 PHASE A 1038									
2 RECEPTACLES 2800 NEC 2001 2800 PHASE B 10168									
3 SWITCHEN 0 0.65 0 PHASE C 7668									
4 HVAC 1994 1 1994 LOWEST PHASE PLUS 10% 1994									
5 SNON CONT 600 1 600 7668 7668 + 10% 8412.8									
6 LARGEST MOTOR 0 0.25 0 REBALANCE LOADS									
TOTAL VA 2280 2280									
TOTAL AMPS 6.1 6.1									

PANEL: HD 100 MLO 277/ 480 V, 3PH, 4W, +GRND. NEW PANEL									
CCT	SERVICES	VA	DCP	WIRE	PHASE	WIRE	DCP	VA	SERVICES
1	WAREHOUSE LIGHTS	2510	201	2#12-1#103	A	3#8-1#103	503	668	MAU1
3	WAREHOUSE LIGHTS	2510	201	2#12-1#103	B			668	
5	OVERHEAD DOOR	200	203	4#10-1#103	A				
7		200			B				
9		200			C				
11					A				
13					B				
15					C				
17					A				
19					B				
21					A				
23					B				
25					A				
27					B				
29					C				
31					A				
33					B				
35					C				
37					A	3#8-1#103	503	1000	TRANSFORMER
39					B			800	TRANSFORMER
41					C			800	TRANSFORMER
NOTES: 1 NEMA 1 ENCLOSURE 2 PROVIDE BOLT ON BREAKERS 3									
LOAD SUMMARY									
1 LIGHTING 4600 1.25 5770 PHASE A 10198									
2 RECEPTACLES 0 NEC 2001 0 PHASE B 0									
3 SWITCHEN 0 0.65 0 PHASE C 7668									
4 HVAC 1994 1 1994 LOWEST PHASE PLUS 10% 1994									
5 SNON CONT 600 1 600 7668 7668 + 10% 8412.8									
6 LARGEST MOTOR 0 0.25 0 REBALANCE LOADS									
TOTAL VA 29164 2630									
TOTAL AMPS 36.3 31.7									

PANEL H1A					100A	277/	480 V,3PH,4W,+GRND.	NEW				
CCT	SERVICES	VA	DCP	WIRE	PHASE	WIRE	DCP	VA	SERVICES	CCT		
1	WALL PACKS	1987	201	2#12-1#103	A	2#12-1#103	201	1000	POLE LIGHTS	2		
3	WALL PACKS	1987	201	2#12-1#103	B	2#12-1#103	201	1000	POLE LIGHTS	4		
5	WALL PACKS	2213	201	2#12-1#103	C					6		
7	UNIT HEATER	5000	303	2#12-1#103	A					8		
9		5000			B					10		
11		5000			C					12		
13					A					14		
15					B					16		
17					C					18		
19					A					20		
21					B					22		
23					A					24		
25					C					26		
27					B					28		
29					C					30		
31					A					32		
33					B					34		
35					C					36		
37					A	3#6,1#103	523	1000	TRANSFORMER	38		
39					B		-	1000	TRANSFORMER	40		
41					C		-	1000	TRANSFORMER	42		
NOTES:					LOAD SUMMARY							
1 NEMA 1 ENCLOSURE					LIGHTING		6491	1.25	5263.75	PHASE A		
2 PROVIDE BOLT ON BREAKERS					2-RECEPTACLES		3000	NED	3000	PHASE B		
					3-KITCHEN		0	0.65	0	PHASE C		
					4-HVAC		15000	1	15000	LOWEST PHASE PLUS 10%		
					5-NEMA CONT		0	1	0	SPD 1-10%		
					LARGEST MOTOR		0	0.25	0	PHASES ARE BALANCED		
					TOTAL VA		25491		27763.75			
					TOTAL AMP'S		38.7		32.5			