



# LSR7 Robotics, GiC & Phys Education: Construction Documents

owner:  
Lee's Summit R-7 School District  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4200 Pennsylvania Avenue  
Kansas City, MO 64111  
816.931.6655  
www.multi.studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

MEPFT/Code::  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

structural engineer:  
Bob D. Campbell & Company,  
4338 Belleview  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

LSW: 2600 SW Ward Rd,  
Lee's Summit MO 64082

Project Number: 0121-0100  
Issue Date: September 9, 2022

**multistudio**  
the evolution of gould evans



LSR7 Robotics, GiC & Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com


structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

General Notes:

1. THE INTENT OF THE CONTRACT DOCUMENTS IS TO INCLUDE ALL ITEMS NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF THE WORK BY THE CONTRACTOR. THE CONTRACT DOCUMENTS ARE COMPLEMENTARY, AND WHAT IS REQUIRED BY ONE SHALL BE AS BINDING AS IF REQUIRED BY ALL. PERFORMANCE BY THE CONTRACTOR SHALL BE REQUIRED ONLY TO THE EXTENT CONSISTENT WITH THE CONTRACT DOCUMENTS AND REASONABLY INFERRABLE FROM THEM AS BEING NECESSARY TO PRODUCE THE INDICATED RESULTS.
2. ORGANIZATION OF THE SPECIFICATIONS INTO DIVISIONS, SECTIONS AND ARTICLES, AND ARRANGEMENT OF DRAWINGS SHALL NOT CONTROL THE CONTRACTOR IN DIVIDING THE WORK AMONG SUBCONTRACTORS OR IN ESTABLISHING THE EXTENT OF WORK TO BE PERFORMED BY ANY TRADE.
3. DRAWINGS, SPECIFICATIONS, GENERAL AND SUPPLEMENTARY CONDITIONS ARE ESSENTIAL PARTS OF THE CONTRACT. IN THE EVENT OF ANY DISCREPANCY BETWEEN A DRAWING AND FIGURES WRITTEN THEREON, THE FIGURES, UNLESS OBVIOUSLY INCORRECT, ARE TO GOVERN OVER SCALED DIMENSIONS. IN THE CASE OF ANY DISCREPANCY BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE SPECIFICATIONS ARE TO GOVERN. IF THERE IS A DISCREPANCY BETWEEN LARGE AND SMALL SCALE DETAILS, THE LARGER SCALE DETAILS ARE TO GOVERN. SUPPLEMENTARY CONDITIONS SHALL GOVERN OVER SPECIFICATIONS, DRAWINGS AND GENERAL CONDITIONS. THE CONTRACTOR SHALL ADVISE THE ARCHITECT OF ANY DISCREPANCIES OR CONFLICTS BETWEEN CONTRACT DOCUMENTS AS SOON AS THEY ARE DISCOVERED.
4. NOTWITHSTANDING THE ABOVE, IN THE CASE OF INCONSISTENCY BETWEEN DRAWINGS AND SPECIFICATIONS, OR WITHIN EITHER DOCUMENT NOT CLARIFIED BY ADDENDUM OR BY ARCHITECT'S SUPPLEMENTAL INSTRUCTION, THE BETTER QUALITY OR GREATER QUANTITY SHALL BE PROVIDED.
5. DRAWINGS SHALL NOT BE SCALED TO DETERMINE DIMENSIONS. IF DIMENSIONS APPEAR TO BE INSUFFICIENT OR INCORRECT, THE CONTRACTOR SHALL REQUEST CLARIFICATION FROM THE ARCHITECT.
6. WHENEVER CONTRACT DOCUMENTS REASONABLY IMPLY MATERIALS OR INSTALLATION AS NECESSARY TO PRODUCE THE INTENDED RESULTS, BUT DO NOT FULLY DETAIL OR SPECIFY SUCH MATERIALS, THE CONTRACTOR SHALL PROVIDE THE MATERIALS AND LABOR REQUIRED FOR INSTALLATION NONETHELESS.
7. PROVIDE ALL WORK INDICATED UNLESS SPECIFICALLY INDICATED AS "NOT IN CONTRACT" (NIC), "FURNISHED BY OTHERS" (FBO) OR "EXISTING".
8. CONTRACT DOCUMENTS ARE INTENDED TO CONVEY DESIGN INTENT ONLY. PROVIDE PRODUCTS COMPLETE WITH ACCESSORIES, TRIM, FINISH, FASTENERS, AND OTHER ITEMS NEEDED FOR A COMPLETE INSTALLATION AND INDICATED USE AND EFFECT.
9. THESE NOTES ARE NOT INTENDED TO LIMIT THE RESPONSIBILITIES OF THE CONTRACTOR AS DEFINED ELSEWHERE IN THE CONTRACT DOCUMENTS

SITE LOCATION MAP - LEE'S SUMMIT WEST HIGH SCHOOL



SITE LOCATION MAP - LEE'S SUMMIT NORTH HIGH SCHOOL



LSN/LSW Index of Drawings

Volume 1

Volume 2

00 Covers		06.1 Plumbing	
VOLUME 1 OF 1 Construction Documents		P000 Plumbing Legend & General Notes	
01.0 General Information		P101-A LSW - Plumbing Plan - Level 1	
G001 Index of Drawings & General Project Notes		P101-B LSN - Plumbing Plan - Level 1	
		P501 Plumbing Details	
01.1 Code Information		P601 Plumbing Schedules	
G100-A Code Review			
G100-B Code Review.		07.1 Mechanical	
G101 Code Plan		M000 Mechanical General Notes & Legend	
		M101-A LSW - HVAC Plan - Level 1	
02.0 Civil		M101-B LSN - HVAC Plan - Level 1	
C100-A LSW Site & Dimension Plan		M102-A LSW - Mechanical Plan - Roof	
C100-B LSN Site & Dimension Plan		M102-B LSN - Mechanical Plan - Roof	
C101-A LSW Truck Turning Template		M201 Mechanical Details	
C101-B LSN Truck Turning Template		M301 Mechanical Schedules	
C190-A LSW Site Details		M401 Mechanical Controls	
C190-B LSN Site Details		M402 Mechanical Controls	
C200-A LSW Demolition & Erosion Control Plan		M403 Mechanical Controls	
C200-B LSN Demolition & Erosion Control Plan			
C290-A LSW Erosion Control Details		08.1 Electrical	
C290-B LSN Erosion Control Details		E000 Electrical General Notes & Legend	
C300-A LSW Grading Plan		E100-A LSW - Electrical Site Plan	
C300-B LSN Grading Plan		E100-B LSN - Electrical Site Plan	
C310-A LSW Retaining Wall Plan & Profile		E101-A LSW - Lighting RCP	
C500-A LSW Utility Plan		E101-B LSN - Lighting RCP	
C500-B LSN Utility Plan		E201-A LSW - Power Plan	
C600-A LSW Storm Sewer Plan & Profile		E201-B LSN - Power Plan	
C600-B LSN Storm Sewer Plan & Profile		E301-A LSW - Equipment Connection Plan	
C690-A LSW Storm Sewer Details		E301-B LSN - Equipment Connection Plan	
C690-B LSN Storm Sewer Details		E302-A LSW - Electrical Roof Plan	
C700-A LSW Sanitary Sewer Plan & Profile		E302-B LSN - Electrical Roof Plan	
C700-B LSN Sanitary Sewer Plan & Profile		E500 Electrical Details	
C790-A LSW Sanitary Sewer Details		E600-A LSW - Panelboard Schedules	
C790-B LSN Sanitary Sewer Details		E600-B LSN - Panelboard Schedules	
C800-A LSW Water Line Plan & Profile		E700 Lighting Schedules	
C800-B LSN Water Line Plan & Profile		E800-A LSW - Electrical One-Line Diagram & Calculations	
C890-A LSW Water Line Details		E800-B LSN - Electrical One-Line Diagram & Calculations	
C890-B LSN Water Line Details			
03.1 Architectural Site		09.0 Fire Protection	
AS100-A LSW - Architectural Site Plan		FA000 Fire Alarm General Notes & Legend	
AS100-B LSN - Architectural Site Plan		FA101 Fire Alarm Plan	
04.1 Structural		10.1 Technology	
S001 General Notes		TN000 Technology General Notes & Legend	
S002 CMU Details		TN101-A LSW - Technology Plan - Level 1	
S101-B Foundation Plan		TN101-B LSN - Technology Plan - Level 1	
S111-B Low Roof and Roof Framing Plan		TN201-A LSW - Technology RCP - Level 1	
S200 Foundation Sections		TN201-B LSN - Technology RCP - Level 1	
S201 Foundation Sections		TN400-A LSW - Technology Enlarged Plans & Details	
S300 Framing Sections		TN400-B LSN - Technology Enlarged Plans & Details	
S301 Framing Sections			
S400 Framing Elevations		10.3 Security	
		TY000 Security General Notes & Legend	
05.1 Architectural		TY101-A Security Plan - Level 1 - LSW	
A001 Graphic Symbols, Abbreviations, and General Information		TY101-B Security Plan - Level 1 - LSN	
A002 Accessibility Standards		TY500 Security Details	
A020 Exterior Enclosure Types			
A030 Interior & Exterior Window Schedule & Types			
A031 Interior & Exterior Storefront Details			
A032 Interior & Exterior Storefront Details			
A080 Door Types & Details.			
A090 Interior Partition Types			
A100 Slab Plan			
A101 Floor Plan			
A111 Roof Plan			
A151 Reflected Ceiling Plan			
A201 Exterior Elevations			
A301 Building Sections			
A310 Wall Sections			
A311 Wall Sections			
A320 Exterior Section Details - Foundation			
A321 Exterior Section Details			
A322 Exterior Section Details			
A330 Exterior Plan & Section Details			
A331 Exterior Envelope Section & Details			
A501 Enlarged Restroom Plans & Elevations			
A502 Enlarged Classroom Plans & Elevations			
A503 Interior Elevations			
A504 Interior Elevations			
A540 Interior Details			
A600 Casework Standards			
05.2 Architectural Finishes			
AF101 Finish Plan			
AF102-A Furniture Plan - LSW			
AF102-B Furniture Plan - LSN			
05.3 Signage & Graphics			
SG001 Signage Types			

Issue Date: September 9, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



Index of Drawings & General Project Notes

G001



CODE ANALYSIS:

Based on Building Code Summary  
Prepared by: Clinton J. Armstrong  
**1.0 INTRODUCTION**

**1.1 SCOPE**  
This documentation outlines major fire and life safety issues affecting the design of the renovations and additions to Lee's Summit West High School. Fire and life safety criteria are summarized from the 2018 International Building Code (IBC) as adopted by the City of Lee's Summit, and with approval from the State of Missouri Fire Marshal (DFS), and the 2018 International Existing Building Code (IEBC).

The new building is a single story vocational shop building with (2) classroom spaces within. Vocational classroom areas do not have enough hazardous materials to be classified as Group H occupancy. These spaces have hazardous materials; however, each has quantities which do not exceed the maximums as permitted by IBC Tables 307.1 (1) and 307.1(2). Construction will take place in a single phase.

**1.2 APPLICABLE CODES:**  
This code summary utilized the following codes as adopted by the City of Lee's Summit, Missouri and the DFS's office (with approval by DFS to be noted on code footprint):

- 2018 International Building Code (IBC)
- 2018 International Existing Building Code (IEBC)
- 2018 International Plumbing Code (IPC)
- 2017 National Electrical Code (NEC)
- 2018 International Fire Code (IFC)
- 2018 International Mechanical Code (IMC)
- 2018 International Fuel Gas Code (IFGC)
- ICC/ANSI A117.1-2009, Accessible and Usable Buildings and Facilities.
- Referenced Standards within each of the above codes

**2.0 CONSTRUCTION CLASSIFICATIONS:**

- 2.1 OCCUPANCY GROUP CLASSIFICATIONS**  
• Vocational Shop Group E (Section 305.1)
- 2.2 TYPES OF CONSTRUCTION CLASSIFICATION**  
• Type II-B (Section 602.2)

**2.3 ALLOWABLE AREA AND HEIGHT (TABLE 504.3, 504.4, 506.2):**

Type IIB Construction	Allowable
	Group E
Area/story (square feet)	14,500
Total area (square feet)	29,000
Height (feet)	55
Height (number of stories)	2

**3.0 FIRE RESISTIVE OCCUPANCY AND USE SEPARATIONS:**

**3.1 USE SEPARATIONS**  
Fire resistive separations and enclosures are intended to address individual use hazards and are identified below.

**Use/Occupancy**  
Service entrance conductors. Encased in 2 inches of concrete, listed 2-hour electrical circuit protective system, or in a vault - NEC Article 230.6  
Information technology equipment room (Not Data Closets) Room is required to be separated with 1-hour fire resistant rated walls, floors and ceilings with protected openings; ducts extending through assembly are required to be provided with fire/smoke dampers - NEC Article 654.2

**3.2 OCCUPANCY SEPARATIONS**  
The new construction is classified throughout as a Group E Occupancy. No occupancy separations are required except as follows:  
• Group E to Group S-2: 1-hour  
**4.0 FIRE RESISTIVE REQUIREMENTS FOR ELEMENTS OF THE STRUCTURE**

**4.1 ACCEPTABLE MATERIALS**  
Structural elements Type II-B resistive buildings are limited to non-combustible materials (IBC Section 602.2).

Fire retardant plywood or other wood products are permitted with sheathing or applied directly on studs within non-bearing partitions where the required fire rating is 2-hour or less (IBC Section 603.1, Exception 1 & 7).

Interior wood products installed as part of wall or ceiling finishes are required to meet the following Flame Spread Index:

- Non-Sprinklered Buildings:
  - Corridors and enclosures for exit access stairways and ramps: Class B
  - Rooms and enclosed spaces: Class C

Incidental 2 x blocking is permitted if of fire retardant treated wood. Fire retardant treated plywood is permitted within 1-hour or 2-hour walls that are not part of a shaft. Specific instances should be evaluated individually.

**4.2 STRUCTURAL, INTERIOR, AND EXTERIOR ELEMENTS**  
Passive fire resistance for the structural frame insures that stability of the building, as a whole, can be maintained during the anticipated fire condition. The structural frame is defined as columns, as well as trusses, girders, and beams, having direct connection to columns. Beams and trusses not having direct connection to columns are considered secondary elements. Depending on where they occur, these secondary elements may be classified as an element of either a roof or floor assembly for purposes of determining fire resistance requirements.

Restrained versus unrestrained designations: All fire resistive assemblies should be viewed as unrestrained, except where the Structural Engineer has demonstrated otherwise.  
Exterior walls provide exposure protection based on fire separation distances.  
New construction will be required to follow seismic, wind, snow, and dead-end line loads as required for new buildings. Any new construction that affects existing structural conditions by more than five percent, that portion of the existing structure is required to be brought up to current code.

Type IIB Construction	Allowable
	Group E
Area/story (square feet)	14,500
Total area (square feet)	29,000
Height (feet)	55
Height (number of stories)	2

**3.0 FIRE RESISTIVE OCCUPANCY AND USE SEPARATIONS:**

**3.1 USE SEPARATIONS**  
Fire resistive separations and enclosures are intended to address individual use hazards and are identified below.

**Use/Occupancy**  
Service entrance conductors. Encased in 2 inches of concrete, listed 2-hour electrical circuit protective system, or in a vault - NEC Article 230.6  
Information technology equipment room (Not Data Closets) Room is required to be separated with 1-hour fire resistant rated walls, floors and ceilings with protected openings; ducts extending through assembly are required to be provided with fire/smoke dampers - NEC Article 654.2

**FIRE RESISTANCE RATED CONSTRUCTION**  
**Building Element**  
Corridors 0-hour - IBC Section 1020.1, Exception 1.  
Other permanent partitions 0-hour - IBC Table 601  
Roof covering Class C - Table 1505.1  
Projections (e.g., canopies) 0-hour, non-combustible - Section 705.2.1

**5.0 FIRE RESISTANCE RATINGS**

Distances (x) to Center Line of Street or Property Line	Non-Rated Openings as Percent Area of Exterior Wall
10' < x < 15'	45%

This table assumes the building is considered as non-sprinklered - Section 705.1.1

**5.2 OPENINGS IN FLOORS/CEILING AND ROOF/CEILING ASSEMBLIES**

Ceilings Where the ceiling is part of a fire resistive floor/ceiling or roof/ceiling assembly, HVAC duct openings are required to be provided with ceiling type fire dampers - Section 716.6.2  
Roofs Roofs may have unprotected openings - Section 712.4

**5.3 PENETRATIONS**  
Roofs Roofs may have unprotected penetrations - Section 712.4

**6.0 FIRE RESISTIVE INTERIOR FINISHES**

**6.1 WALL AND CEILING FINISHES** SECTION 803

Flame Spread Classifications	
WALL & CEILING FINISH	
Flame spread 0-25, smoke developed 0-450	Class A
Flame spread 26-75, smoke developed 0-450	Class B
Flame spread 76-200, smoke developed 0-450	Class C

**Maximum Flame Spread Class (Table 803.13)**

Occupancy Group	Vertical Exits and Exit Passageways	Exit Access Corridors and Other Exit Ways	Room or Enclosed Spaces
E	A	B	C

**6.2 FLOOR FINISH**

Rooms, exit stairs, exit passageways, rated and non-rated corridors Material complying with DOC FF-1 "pill test" (CPS 16 CFR 1030)

**6.3 PLENUMS**

Penums are defined as any space used for air movement - IMC Section 602.1

Exposed materials within plenums are required to have a flame spread index of 25 & a smoke developed rating of 50 - IMC Section 602.2

For requirements on wiring, plastic sprinkler piping, & pneumatic tubing see Section 602.2, Exceptions of the IMC

Use of corridor as plenum  
Use of corridor as a source of make-up air for exhaust systems that open directly onto such corridors is permitted provided make-up air rate is less than supply of outdoor air to the corridor - Section 1020.5, Exception 1  
Corridors are permitted to serve as supply, return, exhaust, relief, or ventilation because the corridors are not required to be rated - Section 1020.5.1  
**6.4 FOAM PLASTIC (E.G., RIGID INSULATION)**  
Required to have a flame spread rating of 75 or less & a maximum smoke developed rating of 450 - Section 2603.3  
Required to be separated from the building interior by a thermal barrier of 15 1/4 inch regular gypsum board or other material that will limit the average temperature rise of the unexposed surface to not more than 250°F after 15-minutes - Section 2603.4  
May be used in roofing & exterior walls if part of a fire resistive assembly - Sections 2603.4.1.5 & 2603.5.1  
May be used as interior trim if covering is no more than 10% of walls or ceilings - Section 2604.2

**7.0 EXIT REQUIREMENTS**  
**7.1 GENERAL EXIT CRITERIA**  
**Occupant Load Factors**  
Mechanical or storage spaces 300 square feet gross/person - Table 1004.5  
Vocational classrooms (i.e., computers, industrial arts, etc.) 50 square feet net/person - Table 1004.5

**Number of Exits**  
2 exits from each floor required; 3 exits required in areas where there are 501 to 1,000 persons; 4 exits required in areas where there is more than 1,000 people - Table 1006.3.2  
2 exit doors required from a room in the following conditions - Table 1006.3.3(2):  
Mechanical or storage rooms serving 29 or more people  
Office/classroom serving 49 or more people

**Arrangement of Exits**  
Where 2 exits are required, they must be placed a minimum distance apart of 1/3 the overall diagonal dimension of the room or building; 1/2 diagonal if fully sprinklered (also see Section 7.9 of this report)  
Doors Where 3 or more exits are required, at least 2 must be separated by 1/2 the diagonal; 1/3 diagonal if fully sprinklered - Section 1007.1.2  
Additional exits are required to be separated such that if 1 becomes blocked, the others remain available

**Capacity of Exits**  
Groups E and S-2  
Doors/ramps 60 people/foot (0.2 inches/person) - Section 1005.3.2  
**Travel Distance**  
Non-Smoke Protected  
Group E 200 feet to an exit - Table 1017.2  
Group S-2 300 feet to an exit - Table 1017.2  
Note: Travel distance is measured to an "exit". By definition, an "exit" is one of the following: an exterior door, a stair enclosure, an exit passageway, or a horizontal exit (i.e., a 2-hour wall subdividing a floor plate).  
**Common Path of Travel**  
Group E 75 feet - Table 1006.2.1  
Group S-2 100 feet - Table 1006.2.1

**7.2 DOOR CRITERIA**  
Maximum leaf width 48 inches - Section 1010.1.1  
Minimum leaf width Wide enough to allow minimum clearance width of 32 inches when open - Section 1010.1.1  
Minimum clear height 6 feet, 8 inches - Section 1010.1.1

Exit door swing type Exit doors are required to be swinging type - Section 1010.1.2  
Exit doors serving 50 or more people or high hazard or refrigeration uses are required to swing in the direction of egress - Section 1010.1.2

Doors in series Doors in series required to swing in the same direction or away from the space in between a minimum of 48 inches plus 1 door width between doors - Section 1010.1.8  
Panic hardware requirements Required on latched doors serving assembly areas having an occupant load of 50 or more & electrical rooms with equipment rated 1,200 amps or more & greater than 6 feet wide that contain over-current devices, switching devices, or control devices with exit access doors - Section 1010.1.10

**7.3 CORRIDORS**  
Minimum height 7 feet, 6 inches - Section 1208.2  
Minimum width 44 inches serving an occupant load of more than 50 - Section 1020.2  
72 inches serving a Group E occupancies with 100 or more people - Section 1020.2

Maximum allowable dead-end corridor 20 feet or 2.5 times the least width of the corridor - Section 1020.4

Construction 0-hour - Section 1020.1, Exception 1

Projections Not permitted except when doors are fully opened; exception may project no more than 7 inches into the required width - Section 1005.7  
Doors in any position cannot reduce the required width by more than half  
Fixtures & furnishings may project up to 4 inches on either side into the required width between heights of 27 & 80 inches - Section 1003.3.3 & ADAAG Section 4.4.1  
Ceiling projections may extend below the ceiling but not less than 80 inches above the finished floor for not more than 50% of the ceiling - Section 1003.3.1

**7.4 STAIRWAY CRITERIA**

**Access to Roof** Required - IMC Section 306.5  
If roof is unoccupied, access may be by a roof hatch providing a minimum of 16 square feet with a 2 feet minimum dimension - Section 1011.12.2

**7.5 OTHER EXIT ISSUES**

Exit access through adjoining spaces Permitted  
No limitations on number of exits or number of occupants limited by travel distance provided the space is accessory & not a storage room, kitchen, closet, or other room of similar use - Section 1016.2, Part 2

**7.5 EXIT PROVISIONS FOR THE DISABLED**  
Number of exits 2 accessible exits are required when 2 or more exits are required - Section 1009.1  
Required to be provided in the same number as required for exits - ADAAG Section 4.1.3(9)  
Not required - ADAAG Section 4.1.3(9)  
Elevator pits & similar areas accessed only by ladders & frequented only by service personnel & the like are not required to be accessible - ADAAG Section 4.1.3 (5), Exception 2

**7.6 EXIT SIGNS AND EXIT LIGHTING**

Exit lighting requirements Required for means of egress with a minimum intensity of 1 footcandle at floor level; emergency power is required - Section 1008.2.1  
Exit sign requirements Required for means of egress from a room or space where 2 or more exits are required & placed no greater than 100 feet apart in corridors - Section 1013.1

Required to be illuminated at all times & be provided with emergency power - Section 1013.5

Tactile exit signs Required at exit doors - Section 1013.4  
Tactile sign requirements Exterior exit doors are to be identified with a tactile sign with the word "EXIT" - Section 1013.4

**8.0 FIRE PROTECTION ISSUES**

**8.1 FIRE SUPPRESSION**  
Automatic sprinklers Not required - Section 903.2.3  
Portable Fire Extinguishers Required by Local Authority Required per IFC 906.1

**8.3 FIRE ALARMS**

Manual pull stations Required - Section 907.2.3  
Visual Visual alarms are required to be installed in accordance with ADAAG & NFPA 72, Audible Audible alarms are required by the ADAAG to provide a sound intensity exceeding the average ambient sound level by 15 dBA or a level which exceeds the maximum sound level by 5 dBA with a duration of 60


The average sound pressure for notification appliances shall provide a sound pressure level of 15 decibels above average ambient sound level or 5 dBA above maximum sound level having a duration of not less than 60 seconds. - Section 907.5.2.1.1

Maximum sound pressure level for audible alarm notification appliances shall be 110 dBA. Where ambient noise is greater than 95 dBA, visible alarm shall be provided and audible alarm shall not be required. - Section 907.5.2.1.2

**8.4 FIRE AND SMOKE DETECTION**  
Smoke detection required to shut off heating or cooling air systems 2,000 cfm capacity or serving more than 1 occupancy - IMC  
Duct smoke detectors are required to initiate a visible & supervisory signal at a constantly attended location - Section 907.11; the supervisory signal is not required when the duct smoke detectors activate the building's alarm notification system  
Smoke detection is required at elevator lobbies & machine rooms to initiate fireman's service (Phase I) recall - Section 3003.2  
Heat detector with a shunt trip device required in sprinklered machine rooms - ANSI A17.1, Section 2.8.2.3  
Smoke detector(s) provided in conjunction with smoke dampers & hold openers at rated doors - NFPA 72

**8.5 BACK-UP POWER**  
Fire alarm system Emergency power is required per NFPA 72  
Exit signs & exit lights Emergency power is required; may be unit batteries - Sections 1006.3 & Not required - Section 1007.2.1  
**9.0 MISCELLANEOUS ISSUES**  
**9.1 ROOM HEIGHT CRITERIA**  
Classroom, assembly and office spaces 7 feet, 6 inches - Section 1208.2  
Corridors 7 feet, 6 inches; means of egress (i.e., including rooms) - Section 1208.2  
Doors 7 feet, 6 inches - Section 1208.2  
Bathrooms 7 feet - Section 1208.2

General Notes (Code Plans):  
1. ALL WORK, MATERIALS, AND METHODS SHALL BE IN CONFORMANCE WITH THE CODES, ORDINANCES AND REGULATIONS OF ALL GOVERNMENTAL AGENCIES HAVING JURISDICTION AT THE PROJECT LOCATION.  
2. CONTRACTOR SHALL PROVIDE AND IS SOLELY RESPONSIBLE AND LIABLE FOR PUBLIC AND EMPLOYEE PROTECTION AS NECESSARY AND AS REQUIRED BY THE CODES, INCLUDING EXTERIOR PEDESTRIAN AND TRAFFIC BARRIERS. ALL WORK SHALL CONFORM TO ORDINANCES AND REGULATIONS OF GOVERNMENTAL AGENCIES HAVING JURISDICTION AT THE PROJECT LOCATION.  
3. THE SIZE, TYPE, QUANTITY, AND LOCATION OF ALL TEMPORARY FIRE EXTINGUISHERS SHALL BE DETERMINED BY THE AUTHORITY HAVING JURISDICTION.  
4. COORDINATE LOCATION OF KNOX BOX WITH ARCHITECT, OWNER'S REPRESENTATIVE, AND THE AUTHORITY HAVING JURISDICTION IN THE FIELD.



Code Site Plan - Lee's Summit West A3  
1" = 20'-0"

Issue Date: September 9, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION





**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect: Multistudio  
4300 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio


civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvang.com

structural engineer: Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEP/IT Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

**General Notes (Site Plan):**

- COORDINATE ALL SPOT ELEVATIONS AND DIMENSIONS WITH CIVIL/LANDSCAPE/STRUCTURAL DRAWINGS
- PROVIDE POSITIVE DRAINAGE OF 1% MINIMUM / 2% MAXIMUM AT ALL EXTERIOR PAVED PEDESTRIAN AREAS SUCH AS SIDEWALKS, PATIOS, STAIRS, ETC. UNLESS NOTED OTHERWISE
- PROVIDE POSITIVE DRAINAGE AWAY FROM THE BUILDING OF 5% FOR A DISTANCE OF 10 FEET UNLESS NOTED OTHERWISE
- FINISH GRADE SLOPES SHALL BE NO STEEPER THAN 1 FOOT VERTICAL IN 3 FEET HORIZONTAL UNLESS NOTED OTHERWISE.



**Section Detail - Pipe Bollard K3**  
1" = 1'-0"





LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64083  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R 7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio.com  
civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com  
structural engineer:  
Bob D. Campbell &  
4388 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com  
MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

STRUCTURAL ABBREVIATIONS

@	AT	GA	GAGE	RAD	RADIUS
&	AND	GALV	GALVANIZE(D)	RD-#	ROOF DECK TYPE
Ø	ROUND, DIAMETER	GEN	GENERAL	REF	REFERENCE
ADTL	ADDITIONAL	GR	GRADE	REINCR	REINFORCEMENT
AFF	ABOVE FINISHED FLOOR	HORIZ	HORIZONTAL	REQD	REQUIRED
ARCH	ALTERNATE	HSS	HOLLOW STRUCTURAL SECTION	REV	REVISION
BLDG	INSIDE FACE	I#	ARCHITECTURAL JOINT	RLH	ROOF LIVE LOAD
B/	BUILDING	INFO	INFORMATION	RTU	ROOF TOP UNIT
BL	BOTTOM OF	INT	INTERIOR	SC	SLIP CRITICAL
BM	BEAM	JOIST	JOIST	SCHED	SCHEDULE(D)
BOTT	BOTTOM	JT	JOINT	SECT	SECTION
BRG	BEARING	K	KIPS (1000 LBS)	SHT	SHEET
C	CAMBER	KSF	KIPS PER SQUARE FOOT	SS	STAINLESS STEEL
CD-#	CONCRETE DECK TYPE	KSI	KIPS PER SQUARE INCH	SJ	SAW JOINT
CS	CONSTRUCTION/CONTROL JOINT	LBS, #	POUNDS	SL	SNOW LOAD
CJ	COMPLETE JOINT PENETRATION	LONG	DEVELOPMENT LENGTH	SOG	SLAB-ON-GRADE
CL	CENTERLINE	LL	LIVE LOAD	SOG-#	SLAB-ON-GRADE TYPE
CMU	CONCRETE MASONRY UNIT	LLV	LONG LEG VERTICAL	SPACING	SPACING
COL	COLUMN	LONG	LONG LEG HORIZONTAL	SPEC	SPECIFICATION
CONC	CONCRETE	LONG	LONG	SPRT	SUPPORT
CONN	CONNECTION	LSLT	LONG-SLOTTED HOLE TRANSVERSE	SQ	SQUARE
CONT	CONTINUOUS	LTWT	LIGHTWEIGHT	SS	STAINLESS STEEL
COORD	COORDINATE	M	MOMENT FORCE	SST	SHORT-SLOTTED HOLE TRANSVERSE
COV, CVR	COVER	MAX	MAXIMUM	STD	STANDARD
DBL	DOUBLE	MECH	MECHANICAL	STIFF	STIFFENER
DET	DETAIL	MFR	MANUFACTURER	STIR	STIRRUP
DIA	DIAMETER	MIN	MINIMUM	STRUCT	STRUCTURE, STRUCTURAL
DIM	DIMENSION	MS	MISCELLANEOUS	THRU	THROUGH
DWL	DEAD LOAD	MSRY	MASONRY	T	TOP OF
DWG	DRAWING	MTL	METAL	THRU	THROUGH
E	EACH	NF	NEAR FACE	TOP OF	TOP OF STEEL, TOP OF SLAB
EF	EACH FACE	NTS	NEAR SIDE	TRANS	TRANSVERSE
EJ	ELEVATION	NTS	NOT TO SCALE	TYPICAL	TYPICAL
EL, ELEV	EXPANSION JOINT	NO	NORMAL WEIGHT	UNO	UNLESS NOTED OTHERWISE
EMBED	EMBEDMENT, EMBEDDED	OC	ON CENTER	V	SHEAR FORCE
ENGR	ENGINEER	OP	OUTSIDE FACE	VERT	VERTICAL
ENG	EDGE OF DECK	OPENING	OPENING	WITH	WITH
EOR	ENGINEER OF RECORD	OPP	OPPOSITE	W/O	WITHOUT
EOS	EDGE OF SLAB	OVS	OVERSIZED HOLE	WL	WIDE FLANGE
EQUAL	EQUAL	PAF	AXIAL FORCE	WIND LOAD	WIND LOAD
EQUIP	EQUIPMENT	PCF	POWDER ACTUATED FASTENER	WP	WORK POINT
EXP	EXPANSION	PC	PRECAST	WWF	WELDED WIRE FABRIC
EXT	EXTERIOR	PCF	POUNDS PER CUBIC FOOT		
EXTG, EXIST	EXISTING	PEMB	PRE-ENGINEERED METAL BUILDING		
FD	FLOOR DECK TYPE	PERP	PERPENDICULAR		
FDN	FOUNDATION	PL	PLATE		
FF	FAR FACE	PJP	POUNDS PER LINEAR FOOT		
FIN	FINISH	PJP	PARTIAL JOINT PENETRATION		
FLR	FLOOR	PSI	POUNDS PER SQUARE INCH		
FS	FAR SIDE	PSI	POUNDS PER SQUARE INCH		
FTG	FOOTING	QTY	QUANTITY		
FV	FIELD VERIFY				

LEGEND:

RD-1	.....	SPAN DIRECTION OF DECK
RD-1	.....	2" 20ga GALVANIZED TYPE II ROOF DECK (3 SPAN CONTINUOUS) ATTACH TO STRUCTURE TO DEVELOP 325psi DIAPHRAGM SHEAR (ASD LOAD).
RD-2	.....	2" 20ga GALVANIZED DEEP ACOUSTIC DOVETAIL DECK EQUIVALENT CRAFT 2.0DA (3 SPAN CONTINUOUS) ATTACH TO STRUCTURE TO DEVELOP 325psi DIAPHRAGM SHEAR (ASD LOAD).
(3.0)	.....	FOOTING MARK - SEE SCHEDULE ON SHEET S101-B
(1)	.....	HS88x8x5/16 ..... COLUMN SIZE
(1)	.....	BASE PLATE MARK - SEE SCHEDULE ON SHEET S101-B


LEVEL BEAM DESIGNATION	W14x22	STEEL BEAM SIZE
	T 117'-6"	TOP OF BEAM ELEVATION
SLOPING BEAM DESIGNATION	W14x22	STEEL BEAM SIZE
	T 133'-0" T 132'-5"	TOP OF BEAM ELEVATION EACH END

Issue Date: September 5, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR REPRESENTATION



GENERAL NOTES - STRUCTURAL

1. General Information

- The contractor shall verify dimensions and conditions before construction and notify the engineer of any discrepancies, inconsistencies, or difficulties affecting the work before proceeding.
- The contractor shall coordinate all disciplines, verifying size and location of all openings, whether shown on structural drawings or not, as called for on architectural, mechanical, or electrical drawings. In the case of work in an existing building the contractor shall scan existing structure to locate all rebar in the area of the new core/opening using ground penetrating radar and notify the engineer of record for review prior to continuing. Conflicts, inconsistencies, or other difficulties affecting structural work shall be called to the architect or engineer's attention for direction before proceeding.
- All design and construction work for this project shall conform to the requirements of the following governing design codes:
  - International Building Code (IBC 2018) as amended by the city of Lee Summit, MO.
  - Minimum Design Loads for Buildings and Other Structures (ASCE7-16)
  - Specification for Structural Steel Buildings (AISC 360-16)
  - Member Design Basis is Allowable Stress Design (ASD)
  - Correction Design Basis is Allowable Stress Design (ASD)
  - Structural Welding Code (AWS D1.4-2017)
  - Building Code Requirements for Structural Concrete (ACI 318-14)
  - Building Code Requirements for Masonry Structures (TMS 402-2016)
  - North American Specification for the Design of Cold-Formed Steel Structural Members (AISI S100-16)
- These drawings are for this specific project and no other use is authorized.

2. Structural Load Design Criteria

- Roof Live = 30 psf, Roof Dead = 25psf
- Snow: Ps = 20psf, Pf = 14psf, Is = 1.0, Ce = 1.0, Ct = 1.0, Drift per ASCE/SEI 7
- C. Lateral Loads:
  - Wind: V = 109 mph, Exposure C, Occupancy (Risk) Category I, Iw=1.0 GCp=-0.18 Design wind pressures to be used for the design of exterior component and cladding materials on the designated zones of wall and roof surfaces shall be per section 30.7 and Table 30.7.2 of ASCE/SEI 7. Tabulated pressures shall be multiplied by effective area reduction factors, exposure adjustment factors, and topographic factors where applicable.
  - Seismic: Sa = 0.101, S1 = 0.069 Occupancy (Risk) Category I, Iw=1.0, Site Classification D, Sds = 0.108, Sd1 = 0.110 Seismic Design Category B Basic Seismic Force-resisting System: Steel system not specifically detailed for seismic resistance Equivalent Lateral Force Procedure R = 3, V = 0.036W, Omega = 3, Cd = 3
- This project is designed to resist the most critical effects resulting from the load combinations of section 1605.3 of the International Building Code.

3. Concrete

- All concrete for foundations (walls, grade beams, footings and piers) shall develop minimum ultimate compressive design strength of 3500 psi in 28 days, but not less than 500 pounds of cement shall be used per cubic yard of concrete regardless of strengths obtained, not over 5 gallons of water per 100 pounds of cement and not over 4 inches of slump.
- All concrete for interior flatwork (without floor covering) shall develop minimum ultimate compressive design strength of 4000 psi in 28 days, but not less than 525 pounds of cement shall be used per cubic yard of concrete regardless of strengths obtained, not over 5.75 gallons of water per 100 pounds of cement and not over 4 inches of slump. Concrete mix shop drawing shall contain testing data proving concrete design mix shrinkage is less than 0.034% at 28 days when tested according to ASTM C157 (air drying method only).
- All concrete for exterior flatwork (with floor covering) shall develop minimum ultimate compressive design strength of 4000 psi in 28 days, but not less than 540 pounds of cement shall be used per cubic yard of concrete regardless of strengths obtained, not over 5.40 gallons of water per 100 pounds of cement and not over 4 inches of slump. Concrete mix shop drawing shall contain testing data proving concrete design mix shrinkage is less than 0.034% at 28 days when tested according to ASTM C157 (air drying method only).
- All concrete for exterior flatwork shall have a minimum design compressive strength of 4500 psi in 28 days, with not less than 560 pounds of cement per cubic yard of concrete, not over 5 gallons of water per 100 pounds of cement, with 6% +/- 1% air entrainment, and a maximum of 4 inches of slump.
- The preceding minimum mix requirements may have water-reducing admixtures conforming to ASTM C494 added to the mix at manufacturer's dosage rates for improved workability.
- The preceding minimum mix requirements may have up to 15% maximum of the cement content replaced with an approved ASTM C018 Class C fly ash, provided the total minimum cementitious content is not reduced.
- Combined aggregate (coarse plus fine) for all concrete shall be well graded from coarsest to finest with no less than 16 percent and not less than 8 percent retained on an individual sieve, except that less than 8 percent may be retained on coarsest sieve and on No. 50 and finer sieves. Submit this gradation report with the concrete mix design shop drawings.
- All interior concrete slabs on grade shall be placed over 1/2" Class A Vapor Barrier per ASTM E1745 with less than 0.01 perms, tested after mandatory conditioning. All joints shall be lapped and sealed per manufacturer's recommendations. All penetrations, as well as damaged vapor barrier material shall also be sealed per manufacturer's recommendation prior to concrete placement. Install barrier per manufacturer recommended details at all discontinuous edges (at interior columns, exterior edge of slab, etc.) to ensure tensile forces are followed. The vapor barrier shall be well graded from coarsest to finest with no less than 16 percent and not less than 8 percent retained on an individual sieve, except that less than 8 percent may be retained on coarsest sieve and on No. 50 and finer sieves. Submit this gradation report with the concrete mix design shop drawings.
- Control joints in dirt formed slab to be as shown on plans. Where not shown, limit controlled areas to not more than 144 square feet, or 12 feet on any side. Slab panel side ratio shall not exceed 1 1/2 to 1.
- Contractor shall verify that all concrete inserts, reinforcing and embedded items are correctly located and rigidly secured prior to concrete placement.
- Construction joints in beams, slabs, and grade beams shall occur at midspan (middle third) unless noted otherwise. Provide 2 x 4 horizontal keys at construction joints for shear transfer.
- No aluminum items shall be embedded in any concrete.

4. Reinforcing Steel

- All reinforcing steel shall conform to the requirements of ASTM A615 or A706 grade 60 steel. Welded plain wire fabric shall be supplied in sheets and conform to the requirements of ASTM A195.
- Clear coverage of concrete over reinforcing steel shall be as follows:
  - Concrete placed against earth: 3"
  - Formed concrete against earth: 2"
  - Slabs: 1"
  - Beams or Columns: 1-1/2"
  - Other: 2"All coverage shall be nominal bar diameter minimum.
- All dowels shall be the same size and spacing as adjoining main bars (splice lap 48 bar diameters or 24" minimum unless noted otherwise).
- At corners of all walls, beams, and grade beams supply corner bars (minimum 2'-0" in each direction or 48 bar diameters) in outside face of wall, matching size and spacing of horizontal bars. Where there are no vertical bars in outside face of wall, supply 3 - #4 vertical support bars for corner bars.
- Bars marked continuous and all vertical steel shall be lapped 48 bar diameters (2'-0" minimum) at splices and embedments, unless shown otherwise. Splice top bars near midspan and splice bottom bars over supports, unless noted otherwise.
- At all holes in concrete walls and slabs, add 2 - #5 bars (opening dimension plus 96 diameters long) at each of four sides and add 2 - #5 x 5'-0" diagonally at each of four corners of hole. Openings in 8" thick walls are reinforced similar, but with 1 - #5 instead of 2 - #5, respectively.
- Unless otherwise covered on architectural plans or specifications, vertical control joints in concrete wall shall be spaced at a maximum of 20'-0" on center and coordinated with the architect. Every other horizontal wall reinforcing bar shall be discontinuous at control joints except heavy top and bottom bars unless noted otherwise. Provide base seal waterstop style number 772 (by Greenstreak Inc. or approved equal) on dirt face side of wall at all walls below grade.
- Accessories shall be as specified in latest edition of the ACI Detailing Handbook and the concrete Reinforcing Steel Institute Design Handbook. Maximum accessory spacing shall be 4'-0" on center, and all accessories on exposed surfaces are to have plastic coated feet.
- All slabs and stairs not shown otherwise shall be 6" thick with #4 bars at 12" on center each way. All exterior porches and stoops not otherwise detailed may be constructed in any standard manner, solid or hollow, but must be reinforced with #4 bars at 12" on center each way minimum. Porches shall be doweled to adjacent walls or grade beams with #4 bars at 12" on center, hooked or embedded 48 diameters into both members. Slope porches 10" per foot for drainage unless noted otherwise.
- Allow 2 ton of reinforcing bars #4 or larger to be used as directed in the field for special conditions by the engineer of record (labor for placing same to be included).

5. Structural Steel

- All structural steel beams and columns shall be ASTM A992, grade 50 steel and all miscellaneous steel shall be ASTM A36 grade steel (except at moment connections where plates shall be ASTM A572, grade 50). Hollow Structural Sections (HSS) shall be ASTM A500, grade C. Fabrication and erection shall be in accordance with AISC 303-05 "Code of Standard Practice for Steel Buildings and Bridges" in the 13th Edition of the AISC Steel Construction Manual.
- All welding shall conform to the recommendations of the AWS.
- All exterior steel and connections, and brick relief angles shall be hot-dip galvanized.
- All bolts not otherwise specified shall be 3/4" diameter high strength (ASTM A325-N). All bolts shall be fully pretensioned. All beam connections shall be designed per the AISC Manual of Steel Construction "Framed Beam Connections" for the indicated reactions or at least 0.4 x beam total shear capacity. Vw/Omega, shown in the maximum total uniform load tables, whichever is greater, and shall account for eccentricity when the bolt line is more than 2" from the center of the support. All connections must be two bolt minimum. Additional connection elements may not be specifically shown in the conceptual details in this set but may be required by the final connection design, such as stiffener plates, doubler plates, supplement/reinforcing plates or other connection material. Connection design and shop drawing preparation shall be completed under the direct supervision of a professional engineer licensed in the state the project is located and shop drawings and connection calculations shall bear his/her seal.
- All anchor bolts shall be 3/4" diameter, ASTM F1554, Grade 36 unless noted otherwise. Washers of minimum size and thickness for the given anchor diameter in Table 14-2 of the AISC Steel Construction Manual shall be provided at every column anchor bolt. Washers shall have a standard size hole for the anchor bolt. At braced frames washers shall be welded all around to the column base plate with 3/16" fillet weld.
- All openings in steel beam roof to have L6x4x5/16 (LLV) frame laid between beams. Support mechanical equipment with L6x4x3/8 (LLV) frame laid between beams.
- Design and installation of steel decking shall comply with the recommendations of the Steel Deck Institute (SDI). All decking shall be galvanized unless noted otherwise.
- Allow 2.0 tons structural steel to be used as directed in field for special conditions by the engineer of record. Cost for shop drawings, fabrication, delivery, detailing, and erection shall be included. 50% of structural steel allowance shall be bid as miscellaneous galvanized angle and plate.

6. Post Installed Anchors

- Post-installed anchors shall be used only where specified on the drawings unless approved in writing by the engineer of record. See drawings for anchor diameter, spacing and embedment. Performance values of the anchors shall be obtained for specific products using appropriate design procedures and/or standards as required by the governing building code. Anchors installed in concrete shall have an ICC-ES Evaluation Service Report. Special inspection is required for all post installed anchors. The contractor shall coordinate an on-site meeting with the post installed anchor manufacturer field representative to educate the construction team on the anchor installation guidelines and requirements including admixtures and compounds applied to the concrete after placement.
- Reinforcing steel shop drawings including erection drawings and bending details but list will not be reviewed for correct quantities.
- Elevations of all reinforced concrete masonry walls at a scale no smaller than 3/8" = 1'-0" showing all required reinforcing.
- Grout mix designs (for CMU).
- Construction and control joint plans and/or elevations.
- Structural steel shop drawings including erection drawings and plate details. Include joint, decking and connector submittals. Include miscellaneous framing specified on the structural drawings, but do not submit framing specified on non-structural drawings for Bob D. Campbell and Company, Inc. review.
- Deferred Submittal: Exterior curtain wall.
- Deferred Submittal: Structural steel connection design calculations submitted concurrently with structural steel shop drawings.
- Miscellaneous anchors shown on the structural drawings.
- Deferred Submittal: Light gage framing design calculations and detailed erection and fabrication drawings.

7. Foundations

- Lee's Summit North:
- The soil investigation was prepared by Cook, Flat & Strobel Engineers, P.A., the report number is 22-5545 and the telephone number is 913-627-9040.
  - Spread footings and grade beams are designed to bear on engineered fill or undisturbed soil capable of safely sustaining 2,500 psf.
- Lee's Summit West:
- The soil investigation was prepared by Cook, Flat & Strobel Engineers, P.A., the report number is 22-5547 and the telephone number is 913-627-9040.
  - Spread footings and grade beams are designed to bear on engineered fill or undisturbed soil capable of safely sustaining 3,000 psf.
  - Contractor shall provide for dewatering at excavations from either surface water or seepage.
  - All foundation excavations shall be inspected by a qualified soil engineer, approved by the architect and/or structural engineer, prior to placement of steel or concrete. This inspection shall be at the owner's expense.
  - All concrete in the structural portion retaining the backfill shall have attained its design strength prior to being backfilled.
  - Moisture content in soils beneath building locations should not be allowed to change after footing excavations and after grading for slabs on grade are completed. If subgrade materials become desiccated or softened by water or other conditions, recompact materials to the density and water content specified for engineered fill. Do not place concrete on frozen ground.

8. Concrete Masonry Units

- Concrete block used in exterior walls or load bearing walls shall meet the requirements of ASTM C90 and have a minimum net compressive strength of 2650 psi and laid up using type N mortar such that fm equals 2000 psi. Mortar shall be volume proportion based cement lime mortar. Proportioning shall be completed by box measure. Any block in contact with earth shall be normal weight units, laid using type "S" mortar and grouted solid.
- The contractor shall provide adequate temporary bracing for all masonry walls during construction.
- All concrete block shall have 9 gage (or larger) horizontal joint reinforcing (ladder or truss) per architectural drawings and specifications (16" maximum vertical spacing).
- Cavity wall construction shall be reinforced as designed for specific concrete block used. The horizontal joint reinforcing shall be of the ladder or truss style per specification and continuous between brick and block, as prescribed by the architectural drawings.
- Concrete block shall be reinforced as follows in 6", 8", 10", and 12" walls:
  - Vertical reinforcing shall be a minimum of 1 - #4 bar in 6" and 8" walls and 2 - #4 bars in 10" and 12" walls at 4'-0" on center, at each corner, at each door and window jamb, each side of control joints and in the end void of each length of wall. Lap splices for masonry vertical reinforcing shall be 48 bar diameters, 24" minimum.
  - Horizontal reinforcing:
    - Horizontal joint reinforcing as noted above.
    - Continuous horizontal bars shall be included per section or detail in bond beam or optional running bond beam where noted. Where bond beams are continuous at corners of walls, supply corner bars matching size of horizontal bars (minimum 2'-0" or 40 bar diameters in each direction).
- Grout, where noted above, shall have a minimum design ultimate compressive strength of 2500 psi at 28 day test and 3/8" maximum aggregate size.
- Non-load bearing concrete block walls shall be isolated from adjacent structural elements with vertical 3/8" control joints and at the top of the wall with 1" air space or compressible material and support per architectural detail.
- Unless otherwise covered on architectural plans or specifications, vertical control joints in masonry construction shall be 3/8" wide, full height of wall. Joints shall be spaced at a maximum of 24'-0" on center and coordinated with the architect. All horizontal joint reinforcing shall be discontinuous at control joints in masonry. All bond beam horizontal reinforcing shall be continuous through control joints.
- Limits over all openings up to 8'-0" wide in new and existing masonry walls not otherwise covered shall be one 6x3 1/2x5/16 angle for each 4" width of masonry. All exterior lintels to be galvanized.
- Walls shall be anchored top and bottom by dowels matching wall vertical reinforcing (unless noted otherwise) from floor slab bottom and bracing angles at the top, per details on the drawings.

9. Light Gage Metal Structural Framing

- All load bearing, light gage structural studs, track, and bridging shall be of the type, size, gage and spacing as shown on the plans, minimum:
  - All materials shall be 33,000 psi minimum yield, except studs of 16 gage or heavier shall have a minimum yield of 50,000 psi.
  - All framing components shall be cut squarely or at an angle to fit squarely against existing framing and erection shall be in accordance with latest editions of the AISI "Specifications for the Design of Cold-Formed Structural Members."
  - All framing components shall be welded, screw attachment, or bolting. Wire variation unless the GC advises Bob D. Campbell and Company, Inc. with written documentation.
- Tracks shall be securely anchored to floor and overhead members. Special anchorage requirements required for wind bracing shall be as shown on the plans.
- Prior to fabrication and erection, the contractor shall submit shop drawings complete with detail of erection, fabrication, attachments, anchorages, lintels, etc., for review by the architect/engineer.

10. Deferred Submittal and Shop Drawing

- Bob D. Campbell and Company, Inc. will review the General Contractor's (GC) shop drawings and related submittals (as indicated below) with respect to the ability of the detailed work, when complete, to be a properly functioning integral element of the overall structural system designed by Bob D. Campbell and Company, Inc.
- Deferred submittals shall be submitted to the architect of record for review who shall forward to the building official for review and approval. Design calculations for deferred submittals shall be submitted at the same time as the shop drawings for review. Design calculations shall be prepared and sealed by a Professional Engineer licensed in the state of the project. The deferred submittal items shall not be installed until the deferred submittal documents have been approved by the building official.
- Prior to submittal of a shop drawing or any related material to Bob D. Campbell and Company, Inc. the GC shall:
  - Review each submission for conformance with the means, methods, techniques, sequences and operations of construction and safety precautions and programs incidental thereto, all of which are the sole responsibility of the GC.
  - Review and approve each submission.
  - Stamp each submission as approved.
- Bob D. Campbell and Company, Inc. shall assume that no submission comprises a variation unless the GC advises Bob D. Campbell and Company, Inc. with written documentation.
- Bob D. Campbell and Company, Inc. shall review shop drawings and related materials with comments provided that each submission has met the above requirements. Bob D. Campbell and Company, Inc. shall return without comment unrequired material or submissions without GC approval stamp.
- Shop drawings and related material (if any) required are indicated below. Should Bob D. Campbell and Company, Inc. require more than ten (10) working days to perform the review, Bob D. Campbell and Company, Inc. shall so notify the GC.
  - Concrete mix designs and material certificates including admixtures and compounds applied to the concrete after placement.
  - Reinforcing steel shop drawings including erection drawings and bending details but list will not be reviewed for correct quantities.
  - Elevations of all reinforced concrete masonry walls at a scale no smaller than 3/8" = 1'-0" showing all required reinforcing.
  - Grout mix designs (for CMU).
  - Construction and control joint plans and/or elevations.
  - Structural steel shop drawings including erection drawings and plate details. Include joint, decking and connector submittals. Include miscellaneous framing specified on the structural drawings, but do not submit framing specified on non-structural drawings for Bob D. Campbell and Company, Inc. review.
  - Deferred Submittal: Exterior curtain wall.
  - Deferred Submittal: Structural steel connection design calculations submitted concurrently with structural steel shop drawings.
  - Miscellaneous anchors shown on the structural drawings.
  - Deferred Submittal: Light gage framing design calculations and detailed erection and fabrication drawings.

11. Statement of Structural Special Inspections

- The structural design for this project is based on completion of special inspections during construction in accordance with section 1704 of the International Building Code. The owner shall employ one or more qualified special inspectors to provide the required special inspections.
- The special inspector shall furnish inspection reports to the building official, owner, architect and structural engineer, and any other designated person.
- All discrepancies shall be brought to the immediate attention of the contractor for correction, then, if uncorrected, to the proper design authority, building official and structural engineer.
- The special inspector shall submit a final signed report stating that the work requiring special inspection was, to the best of the inspector's knowledge, in conformance with the approved plans and specifications and the applicable workmanship provisions of the building code.
- The following inspections and tests are required with the frequency (continuous or periodic) as defined within the itemized section or standard listed below. The General Contractor shall provide notification to the inspector when items requiring inspection are ready to be inspected and provide access for those inspections.
  - Shop Fabrication - structural steel and steel bar joint per Section 1704.2.5 unless AISI certified shop
  - Steel Construction per Section 1705.2 and the quality assurance requirements of AISI 341 Chapter J (as referenced by AISI 360)
  - Cold-Formed Steel Deck per Section 1705.2.2 and the quality assurance requirements of SDI Q4/QC
  - Concrete Construction per Section 1705.3 and Table 1705.3
    - Reinforcing Steel Placement
    - Cast in Place Anchors
    - Post Installed Anchors
    - Design Mix Verification
    - Concrete Sampling and Testing
    - Concrete Placement
    - Concrete Curing
  - Masonry Construction per Section 1705.4 and the quality assurance requirements of TMS 602 Level 2
  - Verification of Soils per Table 1705.6

12. Copyright and Disclaimer

- All drawings in the structural set (S-series drawings) are the copyrighted work of Bob D. Campbell and company, Inc. These drawings may not be photocopied, traced, or copies in any manner without the written permission of Bob D. Campbell and Company, Inc. Exception: Original drawings may be printed for distribution to the owner, architect, and general contractor for coordination, bidding, and construction. Subcontractors may not reproduce these drawings for any purpose or in any manner.
- Wayne E. Davis, P.E., registered engineer and a representative of Bob D. Campbell and Company, Inc., do hereby accept professional responsibility as required by the professional registration laws of this state for the structural design drawings consisting of S-series drawings. I hereby disclaim responsibility for all other drawings in the construction document package, they being the responsibility of other design professionals whose seals and signed statements may appear elsewhere in the construction document package.



LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:	architect:
<b>Lee's Summit R-7 School</b>	<b>Multistudio</b>
301 NE Tudor Road	4200 Pennsylvania
Lee's Summit, MO 64086	Kansas City, MO 64111
	816.931.6655

civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com


structural engineer:  
**Bob D. Campbell &**  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEPFT/Code::  
**Henderson Engineers**  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
[www.hendersonengineers.com](http://www.hendersonengineers.com)

NOTES:


1. IN ADDITION TO SPACING SHOWN IN SCHEDULE, VERTICAL REINFORCING SHALL BE PROVIDED IN GROUTED CELLS AT THE FOLLOWING LOCATIONS
  - A.) IN THE FIRST 2 CELLS ADJACENT TO EACH OPENING
  - B.) IN THE END CELLS ON EACH SIDE OF VERTICAL CONTROL JOINTS
  - C.) IN THE END CELLS OF EACH LENGTH OF WALL
  - D.) AT EACH CORNER OF WALLS
2. ALL MASONRY VOIDS AND BOND BEAMS TO BE GROUTED SHALL BE FREE OF DEBRIS AND MORTAR DROPPINGS PRIOR TO GROUTING. ANY MASONRY w/ DROPPINGS OR DEBRIS OBSERVED IN VOIDS SHALL BE REJECTED.

## A CMU WALL ELEVATION




### 3 SECTION

**B SECTION**  
1 1/2" = 1'-0"




# 1 SECTION


ALL INTERIOR & EXTERIOR MASONRY WALLS SHOWN ON ARCHITECTURAL AND STRUCTURAL DRAWINGS ARE TO BE REINFORCED HORIZONTALLY WITH BOND BEAMS (2" #5 BOTTOM) AT BOTTOM COURSE, TOP COURSE, JOIST BEARING ELEVATION AND AT 8'-0" MAXIMUM O.C. AND VERTICALLY AS INDICATED ON DRAWINGS. THESE WALLS ARE TO BE ANCHORED TOP AND BOTTOM TO THE FOUNDATION, FLOOR, OR ROOF PER TYPICAL DETAILS. THE VERTICAL REINFORCING IS CONTINUOUS (IN 6'-6" MAXIMUM LENGTHS, LAPPED 2'-6" MINIMUM). FILL BLOCK CELLS AND BOND BEAMS WITH 2,500psi GROUT. RE: DETAILS "A" THROUGH "E" ON THIS SHEET.




## C SECTION




## 2 SECTION



## 5 SECTION



## 4 SECTION



## CMU DETAILS

# S002




**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


Project Number: 0121-0100

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect: Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio  
civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
816.485.0318  
kveeng.com  
structural engineer: Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/T/Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com



**2 LSN/LSW FOUNDATION PLAN**  
1/4" = 1'-0"



**1 LSN/LSW FOUNDATION PLAN**  
1/8" = 1'-0"

NOTES:  
1. REFER TO GENERAL NOTES AND LEGEND ON SHEET S001.  
2. TOP OF EXTERIOR FOOTING ELEVATION = 99'-4" U.N.O.  
3. TOP OF INTERIOR FOOTING ELEVATION = 99'-3" U.N.O.  
4. NOTE "A" - POUR STOOFF SLAB WITH ADJACENT SIDEWALK. COORDINATE STOOFF WITH SIDEWALK JOINT PATTERN.

**Structural Foundation Schedule**

NOTE:  
1) EXTERIOR FOOTINGS OR FOOTING AT GRADE BEAM SHALL MATCH GRADE BEAM DEPTH AND BE PLACED WITH GRADE BEAM. PROVIDE SPECIFIED REBAR TOP AND BOTTOM WITH 4 STANDEES TO SUPPORT MATS.  
2) PROVIDE REINFORCING PER SCHEDULE EACH WAY IN TOP OF FTG. AT ALL MOMENT FRAME AND BRACED BAY COLUMNS.  
3) CENTER FOOTINGS ON COLUMNS AND/OR WALL CENTER LINES PER PLAN UNLESS NOTED OTHERWISE (U.N.O.).


Type Mark	Length	Width	Footing Thickness	Bottom Bars	Quantity (E.W. Top & Bott)	
4.5	4'-6"	4'-6"	2'-8"	Rebar : # 4	9	
5.5A	5'-6"	5'-6"	2'-8"	Rebar : # 5	7	
6.0A	6'-0"	6'-0"	2'-8"	Rebar : # 5	8	

**COLUMN BASE PLATE SCHEDULE**

TYPE	COLUMN	BASE PLATE (MBXN)	SHAPE	ANCHOR RODS	EMBEDMENT
1	PER PLAN	3/4"x11"x11"	A	(4) 3/4"Ø	9"
2	PER PLAN	3/4"x12"x12"	A	(4) 3/4"Ø	9"
3	PER PLAN	1"x12"x18"	B	(6) 3/4"Ø	1'-6"
4	PER PLAN	3/4"x9"x10"	C	(4) 3/4"Ø	9"

NOTES:  
1. SEE PLAN FOR ORIENTATION OF COLUMNS.  
2. PROVIDE PLATE WASHER & EMBEDDED PLATE PER SCHEDULE @ ALL ANCHOR BOLTS.  
3. U.N.O. ALL THREADED ROD A.B's SHALL BE F1554 (36ksi) MATERIAL.

**BASE PLATE SHAPE (NOT TO SCALE)**



**COLUMN BASE PLATE AND ANCHOR-ROD CRITERIA**

ANCHOR-ROD DIAMETER	MAX. BASE PLATE HOLE DIAMETER	MIN. PLATE WASHER SIZE	MIN. PLATE WASHER THICKNESS	EMBEDDED ANCHOR PLATE SIZE
3/4"	1 5/16"	2"	1/4"	1/2"x2 1/2"x2 1/2"
7/8"	1 9/16"	2 1/2"	5/16"	1/2"x2 1/2"x2 1/2"
1"	1 7/8"	3"	3/8"	5/8"x3"x3"
1 1/4"	2 1/8"	3 1/2"	1/2"	5/8"x3 1/2"x3 1/2"
1 1/2"	2 3/8"	4"	1/2"	5/8"x3 1/2"x3 1/2"
1 3/4"	2 7/8"	4 1/2"	5/8"	3/4"x3 1/2"x3 1/2"
2"	3 1/4"	5"	3/4"	3/4"x3 1/2"x3 1/2"
2 1/2"	3 3/4"	5 1/2"	7/8"	3/4"x3 1/2"x3 1/2"

NOTES:  
1. HOLE SIZES PROVIDED ARE BASED ON ANCHOR ROD SIZE AND CORRELATE WITH ACI 117 (ACI, 2010).  
2. CIRCULAR OR SQUARE WASHERS MEETING THE WASHER SIZE ARE ACCEPTABLE.  
3. HOLE IN PLATE WASHER SHALL BE 1/16" LARGER THAN ANCHOR DIAMETER.


**PLAN**

**ELEVATION**

Issue Date: September 9, 2022

Revisions  
NUMBER DESCRIPTION DATE

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION.




**FOUNDATION PLAN**  
**S101-B**





**LOW ROOF AND ROOF  
FRAMING PLAN**  
**S111-B**







## LSR7 Robotics, GiC &amp; Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

**owner:**  
**Lee's Summit R-7 School**  
301 NE Tudor Road  
Lee's Summit, MO 64086

**architect:**  
**Multistudio**  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

**civil engineer:**  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

**structural engineer:**  
**Bob D. Campbell &**  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engr.com

MEPFT/Code::  
**Henderson Engineers**  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
[www.hendersonengineers.com](http://www.hendersonengineers.com)

Issue Date: September 9, 2022


## Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------


UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION




**FOUNDATION  
SECTIONS  
S201**




# 1 SECTION




## 2 SECTION



### 3 SECTION



## 4 SECTION



## 5 SECTION



LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

owner:  
**Lee's Summit R-7 School**  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
**Multistudio**  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio.com

civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
**Bob D. Campbell &**  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEPFT/Code::  
**Henderson Engineers**  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
[www.hendersonengineers.com](http://www.hendersonengineers.com)



## 1 DETAIL




## 2 DETAIL




### 3 DETAIL




#### 4 DETAIL




## 5 SECTION



## 6 SECTION



## 7 SECTION



## 8 SECTION

Issue Date: September 9, 2022

## Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------


## BEAM SHEAR CONNECTION SCHEDULE

BEAM SIZE	MINIMUM ROWS OF BOLTS	END REACTION (kips)(U.N.O.)
W8,C8	2	16
W10,C10	2	16
W12,C12	2	16
W14	3	24
W16, C15	3	24
W18	4	32
W21	5	40
W24	5	40
W27	6	48
W30	7	56
W33	8	64
W36	8	64

STEEL CONNECTION NOTES

1. REFER TO GENERAL NOTES ON SHEET 001.
2. CONNECTIONS SHOWN IN THESE DETAILS ARE MINIMUM REQUIREMENTS.
3. FABRICATOR SHALL BE RESPONSIBLE FOR THE ENGINEERING, DESIGNING, AND DETAILING OF EACH CONNECTION FOR LOADS AND THE DRAWING SHALL BE IN ACCORDANCE WITH ALL AISC SPECIFICATIONS AND THE STRUCTURAL GENERAL NOTES.
4. SUGGESTED CONNECTION DETAILS ARE SHOWN. FINAL CONNECTIONS SHALL BE IN ACCORDANCE WITH WHAT IS COMPLETED BY THE CONNECTION ENGINEER. CONNECTION DESIGN SHALL INCLUDE COLUMN OR BEAM CONTINUITY PLATES, WEB STIFFENERS, AND/OR OTHER DETAILS REQUIRED FOR THE FORCES INDICATED.
5. CONTRACTOR MAY OPT TO USE OTHER AISI APPROVED CONNECTIONS IN LIEU OF THOSE SHOWN HEREIN TO MEET END REACTION REQUIREMENTS (I.E. DOUBLE ANGLE CONNECTION).
6. PROVIDE THE FOLLOWING DETAILING INFORMATION FOR THE DETAILS SHOWN IN THE LATEST EDITION OF THE AISI MANUAL OF STEEL CONSTRUCTION.
  - A. ALL BOLTS SHALL BE 1/2" ASTM A305 MINIMUM.
  - B. ALL BOLTS SHALL BE SPACED AT 3X3" MINIMUM.
  - C. ALL BOLTS SHALL HAVE HEAVY HEX NUTS.
  - D. ALL BOLTS SHALL BE PRELUBRICATED.
  - E. BOLT SPACING AND EDGE DISTANCES SHALL BE ADJUSTED PER AISI MANUAL FOR BOLTS LARGER THAN 3/4" DIAMETER.
  - F. ALL BOLTS SHALL BE PRELUBRICATED AND COATED WITH AISC. FOR BEAMS WITH AXIAL LOADS PER DRAWINGS, BOLTS AND NUTS SHALL BE GALVANNEAL COATED TO PREVENT CORROSION. INCREASE NUMBER OF BOLTS AND/OR PROVIDE EXTENDED SHEAR PLATE CONNECTION W/ AN ADDITIONAL COLUMN OF BOLTS TO ACHIEVE THE COMBINED REQUIREMENTS.
  - G. PROVIDE ASTM A490 BOLTS IF REQUIRED TO MEET END REACTION LOAD REQUIREMENTS.
7. PROVIDE THE FOLLOWING INFORMATION ON SHEET \_\_\_\_ FOR BRACE FORCES.
  - A. REFER TO PLANS FOR ADDITIONAL BEAM AXIAL FORCES. BRACE AND BEAM FORCES INDICATED ARE UNFACTORED (ASD) LOADS.
  - B. PROVIDE THE CONNECTIONS TO BE USED TO RESIST THE BEAR DESIGN FORCES LISTED IN THE BEAM SHEAR CONNECTION SCHEDULE.
  - C. PROVIDE THE BRACED FRAME CONNECTION W/ ARCHITECTURAL WALLS AS REQUIRED TO AVOID CONFLICT OR EXPOSURE OUTSIDE OF THE FINISH.
  - D. ALL END REACTIONS INDICATED ARE UNFACTORED (ASD) LOADS.

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



## FRAMING SECTIONS



**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com


structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66314  
816.742.5000  
www.hendersonengineers.com

Issue Date: September 9, 2022


Revisions		
NUMBER	DESCRIPTION	DATE

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION




**FRAMING SECTIONS**


**S301**




**1 SECTION**  
3/4" = 1'-0"




**2 SECTION**  
3/4" = 1'-0"




**3 SECTION**  
3/4" = 1'-0"




**4 SECTION**  
3/4" = 1'-0"




**5 SECTION**  
3/4" = 1'-0"




**6 SECTION**  
3/4" = 1'-0"




**7 SECTION**  
3/4" = 1'-0"




**8 SECTION**  
3/4" = 1'-0"




**9 SECTION**  
3/4" = 1'-0"




**10 SECTION**  
3/4" = 1'-0"




**11 SECTION**  
3/4" = 1'-0"



**12 SECTION**  
3/4" = 1'-0"



**13 SECTION**  
3/4" = 1'-0"



**14 SECTION**  
3/4" = 1'-0"




**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio  
civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com  
structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEP/T/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com




**1 ELEVATION**  
1/8" = 1'-0"




**2 ELEVATION**  
1/8" = 1'-0"




**3 ELEVATION**  
1/8" = 1'-0"




**4 ELEVATION**  
1/8" = 1'-0"




**5 ELEVATION**  
1/8" = 1'-0"




**6 ELEVATION**  
1/8" = 1'-0"




**7 ELEVATION**  
1/8" = 1'-0"




**8 ELEVATION**  
1/8" = 1'-0"




**9 ELEVATION**  
1/8" = 1'-0"




**A DETAIL**  
3/4" = 1'-0"



**B DETAIL**  
3/4" = 1'-0"




**C DETAIL**  
3/4" = 1'-0"



NOTE: GRIND ALL WELDS SMOOTH

**D SECTION**  
3/4" = 1'-0"



NOTE: GRIND ALL WELDS SMOOTH

**E SECTION**  
3/4" = 1'-0"

Issue Date: September 9, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------



181716151413121110987654321																	
Abbreviations																	
A	AT	D	DEEP, DEPTH	H	HB	HOSE BIBB	P	PUBLIC ADDRESS	T	TREAD							
@		DBL	DOUBLE	HC	HANDICAP, HOLLOW CORE	PAR	PARALLEL	PAR	T & B	TOP AND BOTTOM							
A/C	AIR CONDITION(ING) (ED)	DEG	DEGREE	HCP	HANDICAPPED	PART	PARTIAL	PAT	T & G	TONGUE AND GROOVE							
A/C UNIT	AIR CONDITIONING UNIT	DEM	DEMOLITION	HD	HEAVY DUTY	PAT	PATTERN	PC	PLUMBING CONTRACTOR	TECH	TECHNICAL, TECHNOLOGY						
AB	ANCHOR BOLT	DET	DETAIL	HDWD	HARDWOOD	PERF	PERFORATED	PERIM	PERIMETER	TEMP	TEMPORARY, TEMPERATURE						
ABVR		DH	DOUBLE HUNG	HO	HOLD OPEN	PL	PLATE, PROPERTY LINE	PL GL	PLATE GLASS	THRM	THERMAL						
ACC	ACCESSIBLE	DIA or Ø	DIAMETER	HORIZ	HORIZON	PLAM	PLASTIC LAMINATE	PLAS	PLASTER, PLASTIC	THK	THICKNESS						
ACCU	AIR COOLED CONDENSING UNIT	DIFF	DIFFERENCE	HR	HOUR	PLBG	PLUMBING	PLYWD	PLYWOOD	TK BD	TACK BOARD						
ACI	AMERICAN CONCRETE INSTITUTE	DIM	DIMENSION	HSS	HOLLOW STRUCTURAL SECTION	PLWVD	PLYWOOD	PNL	PANEL	TMPD	TEMPERED						
ACOUS	ACOUSTICAL INSULATION	DIR	DIRECTION	HT	HEIGHT	PNL	PANEL	POL	POLISHED	TMPD GL	TEMPERED GLASS						
INSUL		DISP	DISPENSER	HVAC	HEATING, VENTILATING AND	POL	POLISHED	POLY	POLYETHYLENE (PLASTIC)	TOC	TOP OF CONCRETE						
ACOUS PNL	ACOUSTICAL PANEL	DIST	DISTANCE	HW	HOT WATER	PORC	PORCELAIN	PORT	PORTABLE	TOD	TOP OF FOOTING, TOP OF FLOOR, TOP OF FRAME						
ACST	ACOUSTIC	DIV	DIVIDE, DIVISION	HYD	HYDRANT	PR	PAIR	POS	POSITIVE	TOM	TOP OF MASONRY						
ACT	ACOUSTICAL CEILING TILE	DL	DEAD LOAD	I	INSIDE DIAMETER	PRCST	PRECAST	POS	POSITIVE	TOPO	TOPOGRAPHY						
ADA	AMERICANS WITH DISABILITIES	DMPF	DAMP-PROOFING	INCL	INCLUDE	PREFAB	PREFABRICATED	PR	PAIR	TOS	TOP OF STEEL						
ADDL	ADDITIONAL	DMPR	DAMPER	INFO	INFORMATION	PREFIN	PREFINISHED	PRCST	PRECAST	TPD	TOILET PAPER DISPENSER						
ADDM	ADDENDUM	DN	DOWN	INSUL	INSULATION	PRELUM	PRELIMINARY	PREFAB	PREFABRICATED	TV	TELEVISION						
ADH	ADHESIVE	DO	DITTO	INT	INTERIOR	PRELUM	PRELIMINARY	PREFIN	PREFINISHED	TYP	TYPICAL						
ADJ	ADJUSTABLE, ADJACENT	DOZ	DOZEN	INTERM	INTERMEDIATE	PRKG	PARKING	PORT	PORTABLE	UC	UNDERCUT						
AE	ARCHITECT/ ENGINEER	DW	DISH WASHER	J	JANITOR	PSF	POUNDS PER SQUARE FOOT	PROP	PROPERTY	UGND	UNDERGROUND						
AFF	ABOVE FINISHED FLOOR	DWG	DRAWING	JAN	JANITOR	PSI	POUNDS PER SQUARE INCH	PSF	POUNDS PER SQUARE FOOT	UH	UNIT HEATER						
AGGR	AGGREGATE	E	EAST	JAN CLO	JANITOR CLOSET	PT	POST TENSIONED	PSI	POUNDS PER SQUARE INCH	UL	UNDERWRITERS LABORATORIES						
AHU	AUTHORITY HAVING JURISDICTION	EA	EACH	JNT	JOINT	PTD	PAPER TOWER DISPENSER	PT	POST TENSIONED	UNFIN	UNFINISHED						
AHS	AIR HANDLING UNIT	EC	ELECTRICAL CONTRACTOR	JR	JUNIOR	PTN	PARTITION	PTD	PAPER TOWER DISPENSER	UNO	UNLESS NOTED OTHERWISE						
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION	EF	EACH FACE	JST	JOIST	PVC	POLYVINYL CHLORIDE (PLASTIC)	PTN	PARTITION	UTIL	UTILITY						
		EIFS	EXTERIOR INSULATION AND FINISH SYSTEM	K	KNOCK DOWN	PWR	POWER	PVC	POLYVINYL CHLORIDE (PLASTIC)	UV	UNIT VENTILATOR						
ALT	ALTERNATE	EQ	EQUAL	KD	KNOCK DOWN	Q	QUARRY TILE	Q	QUANTITY	V	VOLT						
ALUM	ALUMINUM	EJ	EXPANSION JOINT	KIP	1000 POUNDS	QT	QUARTER	QTR	QUARTER	VAR	VARIABLE, VARIATION						
ANOD	ANNODIZED	EL	ELEVATION	KIT	KITCHEN	QTR	QUARTER	QTY	QUANTITY	VB	VINYL BASE						
APC	ACOUSTICAL PANEL CEILING	ELEC	ELECTRIC(AL)	KO	KNOCK OUT	QTY	QUANTITY			VCT	VINYL COMPOSITE TILE						
ARCH	ARCHITECT(URAL)	ELEM	ELEMENTARY	KPL	KICK PLATE					VENT	VENTILATION						
ASL	ABOVE STRUCTURAL LEVEL	ELEV	ELEVATOR	L	LITER, ANGLE					VERT	VERTICAL						
AWT	ACOUSTICAL WALL TREATMENT	ENAM	ENAMEL	L	LITER, ANGLE					VEST	VESTIBULE						
		ENCL	ENCLOSURE	LAB	LABORATORY					VIF	VERIFY IN FIELD						
B		ENGR	ENGINEER	LAM	LAMINATE(D)					VOC	VOLATILE ORGANIC COMPOUND						
B BD	BASE BOARD	ENVR	ENVIRONMENT	LAV	LAVATORY					VOL	VOLUME						
B/B	BACK-TO-BACK	EOS	EDGE OF SLAB	LAV	LAVATORY					VR	VAPOR RETARDER						
BAT	BATTEN	EP	ELECTRIC PANEL	LBL	LABEL					VUH	VERTICAL UNIT HEATER						
BD	BOARD	EPDM	ETHYLENE PROPYLENE DIENE MONOMER	LBS	POUND					VWC	VERTICAL WALL COVERING						
BDRM	BEDROOM	EPS	EXPANDED POLYSTYRENE BOARD	LD	LOAD					W	WATT, WEST						
BITUM	BITUMINOUS	EQ	EQUAL	LF	LINEAR FEET					W/O	WITHOUT						
BLDG	BUILDING	EQUIP	EQUIPMENT	LH	LATENT HEAT, LEFT HAND					W/W	WALL TO WALL						
BLKG	BLOCKING	EQUV	EQUIVALENT	LIB	LIBRARY					WB	WOOD BASE						
BM	BENCHMARK, BEAM	ETC	ET CETERA	LKR	LOCKER					WC	WALL COVERING, WATER CLOSET						
BOT	BOTTOM	ETR	EXISTING TO REMAIN	LKR RM	LOCKER ROOM					WD	WOOD						
BRG	BEARING	EW	EACH WAY	LL	LIVE LOAD					WDW	WINDOW						
BRZ	BRONZE	EWV	ELECTRIC WATER COOLER	LLH	LONG LEG HORIZONTAL					WF	WIDE FLANGE						
BSMT	BASEMENT	EXC	EXCAVATE	LLV	LONG LEG VERTICAL					WH	WATER HEATER, WALL HUNG						
BTWN	BETWEEN	EXH	EXHAUST	LT	LINOLEUM TILE, LIGHT LIGHTING					WI	WROUGHT IRON						
BUR	BUILT-UP ROOFING	EXH	EXHAUST	LTG	LIGHTING					WM	WIRE MESH						
BW	BOTH WAYS	EXIST	EXISTING	M	MATCHLINE					WP	WATER PROOFING, WEATHERPROOF						
		EXT	EXTERIOR	MACH	MACHINE ROOM					WR	WATER REPLENT, WEATHER RESISTANT						
C		EXP	EXPAND, EXPANSION	MAHOG	MAHOGANY					WSCT	WAINSCOT						
CAB	CABINET	EXTR	EXISTING TO REMAIN	MACH RM	MACHINE ROOM					WT	WEIGHT						
CB	CARRIAGE BOLT, CATCH BASIN	FA	FIRE ALARM	MAINT	MAINTENANCE					WWF	WELDED WIRE FABRIC						
CCTV	CLOSED-CIRCUIT TELEVISION	FAAP	FIRE ALARM ANNUNCIATOR PANEL	MATL	MATERIAL					WWW	WELDED WIRE MESH						
CD	CONSTRUCTION DOCUMENTS, CONTRACT DOCUMENTS	F	FACE-TO-FACE	MAX	MAXIMUM												
CEM	CEMENT	FACP	FIRE ALARM CONTROL PANEL	MB or MKR	MARKERBOARD												
CERT	CERTIFY, CERTIFICATE, CERTIFICATION	MC	MECHANICAL CONTRACTOR	BD	BOARD												
CF/CI	CONTRACTOR FURNISHED/ CONTRACTOR INSTALLED	FCU	FAN COIL UNIT	MECH	MECHANICAL CONTRACTOR												
CF/OI	CONTRACTOR FURNISHED/ OWNER INSTALLED	FD	FLOOR DRAIN	MDF	MEDIUM DENSITY FIBERBOARD												
CG	CORNER GUARD	FEC	FIRE EXTINGUISHER CABINET	MDO	MEDIUM DENSITY OVERLAY												
CH	CHALK BOARD	FE	FIRE EXTINGUISHER	ME	MATCH EXISTING												
CHBD		FIN	FINISH	MECH	MECHANICAL												
CHEM	CHEMICAL	FIXT	FIXTURE	MECH RM	MECHANICAL ROOM												
CI	CAST IRON	FLOR	FLUORESCENT	MFR	MANUFACTURER												
CIP	CAST-IN-PLACE	FLR	FLOOR	MIN	MINIMUM												
CJ	CONTROL JOINT, CONSTRUCTION JOINT	FNDN	FOUNDATION	MISC	MISCELLANEOUS												
CL	CENTER LINE	FO	FINISHED OPENING	MM	MILIMETER												
CLG	CEILING	FRIS	FIRE RESISTIVE JOINT SYSTEM	MO	MASONRY OPENING												
CLO	CLOSET	FRP	FIBERGLASS REINFORCED PLASTIC	MOD BIT	MODIFIED BITUMEN												
CLR	CLEAR	FTW	FIRE RETARDANT TREATED WOOD	MTD	MOUNTED												
CLRM	CLASSROOM	FT	FOOT, FEET	MTL	METAL, MATERIAL												
CMU	CONCRETE MASONRY UNIT	FTG	FOOTING	MULL	MULLION												
CNR	CORNER	FURN	FURNITURE	N													
CNTR	COUNTER	FW	FIRE WALL	N													
COL	COLUMN	FWC	FABRIC WALL COVERING	N													
CONC	CONCRETE	G		N													
CONF	CONFERENCE	GA	GAGE	N													
CONN	CONNECTION(ION)	GAL	GALLON	N													
CONSTR	CONSTRUCTION	GALV	GALVANIZED	N													
CONT	CONTINUOUS	GALV STL	GALVANIZED STEEL	N													
CONTR	CONTRACT(OR)	GB	GRAB BAR	N													
COORD	COORDINATE, COORDINATION	GC	GENERAL CONTRACTOR	N													
CORR	CORRIDOR	GEN	GENERAL, GENERATOR	N													
CPT	CARPET	GFCI	GROUND FAULT CIRCUIT INTERRUPTER	N													
CSK	COUNTERSINK	GFRG	GLASS FIBER REINFORCED CONCRETE	N													
CSWK	CASEWORK	GL	GLASS, GROUND LEVEL	N													
CT	CERAMIC TILE	GL BLK	GLASS BLOCK	N													
CTR	CENTER	GLU LAM	GLUED LAMINATED BEAM	N													
CTRL	CONTROL	GLZ	GLAZING	N													
CU	CUBIC	GWT	GLAZED WALL TILE	N													
CUH	CABINET UNIT HEATER	GTM	GYMNASIUM	N													
CUST	CUSTODIAL	GYP	GYPSUM	N													
CW	COLD WATER, CASEMENT WINDOW	GYP BD	GYPSUM BOARD	N													
		GYP PLAS	GYPSUM PLASTER	N													
Graphic Symbols																	
01 GENERAL																	
NEW WALL																	
EXISTING WALL TO BE REMOVED																	
EXISTING WALL																	
BUILDING SECTION																	
WALL SECTION																	
DETAIL SECTION																	
DETAIL REFERENCE																	
EXTERIOR ELEVATION TAG																	
INTERIOR ELEVATION TAG																	
BREAK LINE																	
ROOM TAG																	
INTERIOR PARTITION TYPE SYMBOL																	
WINDOW TYPE SYMBOL																	
BENCHMARK/SPOT ELEV. SYMBOL																	
COLUMN LINE/GRID INDICATOR																	
REVISION INDICATOR																	
DOOR TAG																	
CEILING LEVEL SYMBOL																	
CEILING HEIGHT SYMBOL																	
NORTH ARROWS																	
DIMENSION																	
ALIGN TWO WALLS OR OBJECTS																	
Materials Graphics																	
02 SITE CONSTRUCTION																	
E																	



LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

owner:	architect:
<b>Lee's Summit R-7 School</b>	<b>Multistudio</b>
301 NE Tudor Road	4200 Pennsylvania
Lee's Summit, MO 64086	Kansas City, MO 64111
	816.931.6655
	multi.studio



civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveing.com

structural engineer:  
**Bob D. Campbell &**  
4338 Belleview  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com




MEPFT/Code::  
**Henderson Engineers**  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
[www.hendersonengineers.com](http://www.hendersonengineers.com)

Specialty Equipment Schedule		
Mark	Description	Comments
102600 - WALL AND DOOR PROTECTION		
CG01	3/4" X 3/4" ANODIZED ALUMINUM CORNER GUARD 8" TALL	
102800 - TOILET, BATH, AND LAUNDRY ACCESSORIES		
GB-18V	STRAIGHT GRAB BAR 18" (VERTICAL)	CONTRACTOR PROVIDED AND INSTALLED
GB-36	STRAIGHT GRAB BAR 36"	CONTRACTOR PROVIDED AND INSTALLED
GB-42	STRAIGHT GRAB BAR 42"	CONTRACTOR PROVIDED AND INSTALLED
MR01	MIRROR	CONTRACTOR PROVIDED AND INSTALLED
PTD01	PAPER TOWEL DISPENSER	OWNER PROVIDED, CONTRACTOR INSTALLED
SD01	AUTOMATIC SOAP DISPENSER	OWNER PROVIDED, CONTRACTOR INSTALLED
SDN01	SURFACE MOUNTED SANITARY NAPKIN DISPOSAL	CONTRACTOR PROVIDED AND INSTALLED
TPD01	TOILET TISSUE DISPENSER	OWNER PROVIDED, CONTRACTOR INSTALLED
104413 - FIRE PROTECTION CABINET		
FE01	FIRE EXTINGUISHER CABINET	SEMI-RECESSED
FE02	FIRE EXTINGUISHER CABINET	WALL MOUNTED


1. THIS PROJECT WILL COMPLY WITH ALL AMERICAN WITH DISABILITIES REGULATIONS AND ALL LOCAL ACCESSIBILITY CODE REQUIREMENTS.
2. ALL MOUNTING HEIGHTS ARE TO COMPLY WITH ICC/ANSI-A117.1. REFER TO FOUNTINE HEIGHT GUIDELINES FOR TYPICAL MOUNTING HEIGHTS. COORDINATE WITH OWNER/ARCHITECT FOR ANY ITEMS IN CONFLICT OR NOT EXPLICITLY INDICATED.
3. PROVIDE WOOD BLOCKING AT ALL EQUIPMENT FIXTURES, AND ACCESSORIES INCLUDED OWNER PROVIDED ITEMS WHETHER OR NOT SUCH BLOCKING IS NOTED OR SPECIFIED.
4. ACCESSORIES SHOWN ARE GENERIC. REFER TO SCHEDULE SPECIFIED MODEL.
5. FIXTURES ACCESSORIES SHOWN ARE GENERIC. REFER TO FOUNTINE DRAWINGS FOR SCHEDULED FIXTURES.





Miscellaneous Heights **G1**  
3/8" = 1'-0"



## Drinking Fountain Guidelines **D5**



\* 12 INCH ONLY REQUIRED WHERE USED FOR ACCESSIBLE TOE CLEARANCE



## Revisions

## Revisions

NUMBER	DESCRIPTION	DATE
2	Addendum 02	09/23/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



## Accessibility Standards

# A002

## Fixture Height Guidelines **A1**



LSR7 Robotics, GiC & Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


Project Number: 0121-0100

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect: Multistudio  
4300 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio  
civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveg.com  
structural engineer: Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEP/T/Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

General Notes (Exterior Enclosure):

- ALL OPENINGS, FLASHING, COUNTER FLASHING, AND EXPANSION JOINTS SHALL BE WATERTIGHT.
- ALL OPEN JOINTS, PENETRATIONS, AND OTHER OPENINGS IN THE ENVELOPE SHALL BE SEALED, GASKETED, OR WEATHER-STRIPPED TO LIMIT AIR LEAKAGE.
- PROVIDE MOLD RESISTANT GYPSUM BOARD AT ALL EXTERIOR WALLS.




SPM1  
SINGLE PLY MEMBRANE ON METAL STUDS




M8

INSULATED CMU WALL




MWP02  
CONCEALED FASTENER METAL WALL PANEL ON METAL STUDS




MWP01  
PERFORATED CORRUGATED METAL PANEL OVER FORMED METAL WALL PANEL ON METAL STUDS

NOTE: REFER TO SHEET A331 FOR CUSTOM METAL PANEL PROFILE AND PERFORATION PATTERNS.




Exterior Envelope Mockup - Back Face F11




NOTE:  
MOCKUP DIAGRAM SHOWS INTENTION FOR ON-SITE MOCK-UP PANEL. PROVIDE ALL BUILDING COMPONENTS SHOWN WHETHER CALLED OUT OR NOT. MOCK-UP PANEL SHALL REMAIN ON-SITE AND PROTECTED FOR FIELD REFERENCE. REFERENCE THE DETAILS AND SPECIFICATIONS FOR FULL ASSEMBLY REQUIREMENTS.


Exterior Envelope Mockup - Front Face A11



ROOF03  
STANDING SEAM METAL ROOFING (INSULATED R30 MINIMUM) OVER METAL DECK



ROOF02  
STANDING SEAM METAL ROOFING (INSULATED R30 MINIMUM) OVER METAL DECK



ROOF01  
(EPDM) (INSULATED R30 MINIMUM) OVER METAL DECK

Roof Types A7

1 1/2" = 1'-0"

Exterior Wall Types A3

1 1/2" = 1'-0"



**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect: multistudio  
4300 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio.com  
civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvweng.com  
structural engineer: Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/FIT Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

**General Notes (Windows):**

1. ALL EXTERIOR GLAZING SHALL BE SCHEDULED IN PROJECT MANUAL.
2. CONTRACTOR TO COORDINATE SILL HEIGHTS AND FIELD VERIFY ALL CORNER CONDITIONS WITH ELEVATIONS AND WALL SECTIONS.
3. CONTRACTOR TO VERIFY ALL WINDOW COUNTS AND TYPES.
4. PROVIDE SAFETY GLAZING IN ALL OPERABLE OR FIXED PANELS WHERE REQUIRED.
5. BUTT-GLAZED JOINTS SHALL BE 3/8" NOMINAL, UNLESS NOTED OTHERWISE.

**Glazing Schedule - Basic**

Mark	Description
GL01	1/4" CLEAR (TEMPERED)
IGU01	1" INSULATED GLASS
IGU01SF	1" INSULATED GLASS (SECURITY GLASS)

Issue Date: September 9, 2022


NUMBER	DESCRIPTION	DATE
2	ADDENDUM 02	09/29/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION.




**Interior & Exterior Window Schedule & Types**


**A030**




Interior Storefront Glazing - Type G **J15**  
3/16" = 1'-0"




Interior Storefront Glazing - Type F **J11**  
3/16" = 1'-0"




Exterior Storefront Glazing - Type E.4 **J7**  
3/16" = 1'-0"




Exterior Storefront Glazing - Type E.3 **J3**  
3/16" = 1'-0"




Exterior Storefront Glazing - Type E.2 **E15**  
3/16" = 1'-0"




Exterior Storefront Glazing - Type E.1 **E11**  
3/16" = 1'-0"




Exterior Storefront Glazing - Type D **E7**  
3/16" = 1'-0"



Exterior Storefront Glazing - Type C **E3**  
3/16" = 1'-0"



Exterior Storefront Glazing - Type B **A11**  
3/16" = 1'-0"



Exterior Storefront Glazing - Type A **A3**  
3/16" = 1'-0"



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveg.com

structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

Issue Date: September 9, 2022


Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/09/2022
2	Addendum 02	09/28/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
APPROVED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION




**Interior & Exterior  
Storefront Details**


**A031**




**Window Jamb Detail @ Type E Jamb J15**  
3" x 1'-0"




**Window Jamb Detail @ Corner Glass K10**  
3" x 1'-0"




**Window Jamb Detail @ Entry K6**  
3" x 1'-0"




**Window Jamb Detail @ Canopy Metal Panel K1**  
3" x 1'-0"




**Window Head Detail @ Custom Metal Panel, Typ. E10**  
3" x 1'-0"




**Window Head Detail @ Entry E6**  
3" x 1'-0"




**Window Head Detail @ Canopy Metal Panel, Typ. E1**  
3" x 1'-0"




**Sill Detail @ Grade A15**  
3" x 1'-0"



**Horizontal Mullion Detail @ Metal Panel A10**  
3" x 1'-0"



**Window Sill Detail @ Entry A6**  
3" x 1'-0"



**Window Sill Detail @ CMU Typ. A1**  
3" x 1'-0"








General Notes (Door Schedule):

Note: SHADED CELLS IN THE SCHEDULE ARE ELEMENTS OF THE DOOR THAT ARE EXISTING TO REMAIN AND FOR INFORMATION ONLY.


- THRESHOLDS SHALL COMPLY WITH ACCESSIBILITY REGULATIONS.
- ALL DOOR FRAMES ARE TO BE WELDED.
- EDGE CLEARANCES IN ACCORDANCE WITH AIA QUALITY STANDARDS.
- DOORS LOCATED IN CORNERS ARE TO HAVE THE INSIDE FACE OF JAMB LOCATED 4 INCHES FROM THE ADJACENT WALL FINISH (8 INCHES IN MASONRY WALLS) UNLESS NOTED OTHERWISE.
- PROVIDE BLOCKING AT ALL WALL MOUNTED DOOR STOPS.
- GLAZING STOPS IN WOOD DOORS: SAME SPECIES AS DOOR FACE, MITERED CORNERS, CONCEALED FASTENERS.
- FACTORY FINISH WOOD DOORS.
- ALL EXIT DOORS SHALL BE OPERABLE FROM INSIDE WITHOUT THE USE OF A KEY OR ANY SPECIAL KNOWLEDGE OR EFFORT AND SHALL BE LABELED "THIS DOOR TO REMAIN UNLOCKED DURING BUSINESS HOURS." THIS SIGN SHALL BE IN LETTERS NOT LESS THAN ONE INCH HIGH ON A CONTRASTING BACKGROUND. SPECIAL LOCKING DEVICES SHALL BE OF AN APPROVED TYPE, MANUALLY OPERATED. FLUSH BOLTS OR SURFACE BOLTS ARE PROHIBITED.
- PROVIDE CLOSERS AT ALL FIRE RATED AND EXTERIOR DOORS. COORDINATE WITH HARDWARE SETS.
- PROVIDE SAFETY GLAZING IN ALL DOORS AND ASSOCIATED ACTIVE/FIXED PANELS.
- PROVIDE SAFETY GLAZING IN FIXED OR OPERABLE PANELS WHERE WITHIN 24 INCHES OF EITHER EDGE OF AN OPERABLE DOOR.
- PROVIDE SAFETY GLAZING IN FIXED OR OPERABLE PANELS WHERE WITHIN 18 INCHES FROM AND RAMP/STAIR LANDING OR HAND/GUARDRAIL.
- ANY DOOR CARRYING A U.L. RATING SHALL BE INSTALLED IN A U.L. RATED FRAME CARRYING THE SAME DESIGNATION.
- PROVIDE FIRE RATED GLAZING IN PANELS LOCATED WITHIN A RATED WALL.
- CONTRACTOR TO COORDINATE SILL HEIGHTS WITH ELEVATIONS AND WALL SECTIONS.
- PAINT METAL DOORS AND FRAMES TO MATCH ADJACENT WALLS UNLESS OTHERWISE NOTED. REFER TO FINISH LEGEND FOR ADDITIONAL INFORMATION.
- REFER TO "PROJECT MANUAL" FOR HARDWARE SETS AND ADDITIONAL DOOR REQUIREMENTS.

DOOR LEGEND:


- AL ALUMINUM  
ANNO ANODIZED  
CA CARD ACCESS DEVICE  
CL CLOSER  
FRP FIBERGLASS  
GL GLASS  
HC HOLLOW CORE  
HM HOLLOW METAL  
IMP INSULATED METAL PANEL  
L LOUVER  
PF PRE-FINISHED/FACTORY FINISHED  
PH PANIC HARDWARE  
PR PAIR  
PTD PAINTED  
SD SMOKE & DRAFT CONTROL  
SS STAINLESS STEEL  
STL STEEL  
T TEMPERED GLASS  
V VISION  
WD WOOD




Door Types - LSN M3  
1/4" = 1'-0"




Frame Types  
1/4" = 1'-0"



Assembly Detail - Type C A11  
1 1/2" = 1'-0"



Assembly Detail - Type B A8  
1 1/2" = 1'-0"



Assembly Detail - Type A A3  
1 1/2" = 1'-0"

Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE
2	Addendum 02	09/29/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION.



Door Types & Details.  
A080







LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
303 NE Tudor Road  
Lee's Summit, MO 64086  
multi-studio

architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell &  
4338 Belview  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

Issue Date: September 9, 2022


Revisions		
NUMBER	DESCRIPTION	DATE

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



Slab Plan  
A100

LSN / LSW - Level 1 Slab Plan A1  
3/16" = 1'-0"





LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveg.com

structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT Codes:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

General Notes (Floor Plans):

1. ALL WALL TYPES TO BE G4.1 UNLESS OTHERWISE NOTED.
2. ALL WALL DIMENSIONS ARE TO FACE OF WALL UNLESS OTHERWISE NOTED.
3. MASONRY WALLS ARE NOMINALLY CENTERED ON GRID LINES AND MASONRY DIMENSIONS ARE NOMINAL UNLESS OTHERWISE NOTED.
4. DOORS IN STUD WALLS NEAR PERPENDICULAR WALLS ARE LOCATED 4" OFF FACE OF PERPENDICULAR WALL UNLESS OTHERWISE NOTED.
5. DOORS IN MASONRY WALLS ARE LOCATED IN ROUGH OPENINGS DIMENSIONED ON SHEET.
6. SEE GENERAL ACCESSIBILITY SHEET FOR HEIGHTS AND LOCATIONS OF TOILET ACCESSORIES NOT SHOWN ON ELSEWHERE.
7. CONTRACTOR TO FIELD VERIFY ALL MEASUREMENTS AND CONDITIONS NEW AND EXISTING. NOTIFY THE ARCHITECT/OWNER'S REPRESENTATIVE OF ANY DISCREPANCIES.
8. ENLARGED PLANS MAY BE ROTATED OR MIRRORED COORDINATE WITH MAIN FLOOR PLAN.
9. CONTRACTOR TO PROVIDE 4'-0" HIGH PLYWOOD BACKER BOARD IN ALL MECHANICAL AND ELECTRICAL ROOMS MOUNTED 3'-6" A.F.F. FOR PERIMETER OF ROOM.

Issue Date: September 9, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION.



Floor Plan

A101

LSN / LSW - Level 1 Floor Plan A3  
3/16" = 1'-0"



LSR7 Robotics, GIC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio


civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66314  
816.742.5000  
www.hendersonengineers.com

General Notes: (Roof Plan)

1. REFER TO EXTERIOR ENCLOSURE TYPES FOR ROOF DETAILS.
2. MINIMUM SLOPES ON ROOF SHALL BE 1/4" PER FOOT IN DIRECTION OF DRAINS OR ROOF EDGE.
3. ELEVATION ABBREVIATIONS AS FOLLOWS: **BOD** = BOTTOM OF DECK, **TOS** = TOP OF STEEL, **TOP** = TOP OF PARAPET.
4. OBJECT ABBREVIATIONS AS FOLLOWS: **RD** = ROOF DRAIN, **RTU** = ROOFTOP UNIT, **RH** = ROOF HATCH.
5. PROVIDE ALL ROOFING DETAILS BY MANUFACTURERS WARRANTED SYSTEMS.
6. PROVIDE WALKWAY PADS AT ALL ROOF LADDERS AND AT ALL ROOFTOP EQUIPMENT WORKING AREAS.
7. PROVIDE CRICKETS AT ALL ROOFTOP EQUIPMENT TO FACILITATE DRAINAGE.



Section Detail - Typical Roof Drain **M3**  
1 1/2" = 1'-0"



Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION.



Roof Plan

**A111**

LSN / LSW - Roof Plan **A3**  
3/16" = 1'-0"



**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect: Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer: **Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com










structural engineer: **Bob D. Campbell &**  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEP/PT/Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

**General Notes (Reflected Ceiling Plans):**


1. ALL CEILING AND SOFFIT HEIGHTS ARE GIVEN ABOVE FINISHED FLOOR ELEVATION - (EL. 0'-0")
2. GENERALLY ONLY CEILING MOUNTED FIXTURES ARE SHOWN ON THIS PLAN. COORDINATE WITH MEP PLANS FOR ADDITIONAL INFORMATION.
3. SOME OR ALL SPRINKLERS MAY NOT BE SHOWN ON THIS PLAN. COORDINATE WITH MEP DRAWINGS FOR ADDITIONAL INFORMATION. SPRINKLER HEADS TO BE CENTERED ON CEILING TILE, TYP.
4. VERIFY LOCATIONS OF ALL CEILING ACCESS PANELS WITH MEP DRAWINGS. COORDINATE LOCATIONS OF PANELS WITH ARCHITECT PRIOR TO INSTALLATION. ACCESS PANEL FIRE RATINGS MUST MATCH CEILING ASSEMBLY FIRE RATINGS.
5. LIGHTING FIXTURES TO BE CENTERED AND SPACED EQUALLY UNLESS NOTED OTHERWISE.
6. LIGHT FIXTURES ARE SHOWN FOR DIMENSIONAL PURPOSES ONLY COORDINATE WITH ELECTRICAL DRAWINGS FOR FIXTURE DESIGNATIONS.
7. IF PROJECT INCLUDES FIRE RATED CEILINGS, LIGHT FIXTURES LOCATED IN RATED CEILING ASSEMBLIES ARE TO BE TENTED OR OTHERWISE RATED TO MATCH THE CEILING.

**Lighting Fixture Legend:**


-  2X4 FLORESCENT
-  2X2 FLORESCENT
-  STRIP FLORESCENT
-  RECESSED CAN LIGHT
-  CEILING FAN
-  EMERGENCY WALL PACK
-  TRACK LIGHTING
-  STEP LIGHT
-  COVE LIGHT



**Restroom Ceiling Detail @ Recessed Light L11**  
3\"/>



**Classroom Ceiling Detail @ Recessed Light L3**  
3\"/>



LSN / LSW - Level 1 RCP **A3**  
3/16\"/>

Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/19/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



Reflected Ceiling Plan

**A151**



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
**Lee's Summit R-7 School**  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
**MultiStudio**  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveg.com

structural engineer:  
**Bob D. Campbell &**  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEPFT/Code::  
**Henderson Engineers**  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
[www.hendersonengineers.com](http://www.hendersonengineers.com)

General Notes (Exterior Elevations):

1. MATERIALS AND FINISHES INDICATED APPLY TO ALL SIMILAR ELEMENTS.
2. COORDINATE EXTERIOR LIGHTING FIXTURE TYPES AND LOCATIONS WITH ELECTRICAL DRAWINGS.

LSN / LSW - East Exterior Elevation **L11**  
1/8" = 1'-0"

LSN / LSW - West Exterior Elevation L3  
1/8" = 1'-0"LSN / LSW - South Exterior Elevation F3  
1/8" = 1'-0"

LSN / LSW - North Exterior Elevation **A3**  
1/8" = 1'-0"

Finish Legend - Exterior	
MARK	MODEL
042200 CONCRETE MASONRY UNIT	
M8	CONCRETE MASONRY UNIT
074113 STANDING SEAM METAL ROOF PANELS	
ROOF02	STANDING SEAM METAL ROOF
074213.13 FORMED METAL WALL PANEL	
MWP02	CORRUGATED METAL PANEL
074219 CUSTOM PERFORATED ALUMINUM PANEL	
MWP01	METAL RAINSCREEN PANEL - CUSTOM
088000 GLAZING	
IGU01	1" INSULATED GLASS
IGU01SF	1" INSULATED GLASS (SECURITY GLASS)

(074219) ALUMINUM RAINSCREEN GIRTS  
- 2'-0" O.C. START AT POINT INDICATED ON  
ELEVATIONS

Issue Date: September 9, 2022

## Revisions

NUMBER	DESCRIPTION	DATE
2	Addendum 02	09/23/2022
3	AS01 - Code Comments	11/09/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



## Exterior Elevations

# A201



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086


architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com


structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT Codes:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

LSN / LSW - Building Section 3 **L1**  
3/16" = 1'-0"



LSN / LSW - Building Section 2 **F1**  
3/16" = 1'-0"



LSN / LSW - Building Section 1 **A1**  
3/16" = 1'-0"

Issue Date: September 9, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



**Building Sections**  
**A301**




**LSR7 Robotics, GIC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio  
civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvereng.com  
structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEP/IT Codes:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com




Wall Section @ North Entry H14  
1/2" = 1'-0"




Wall Section @ Mechanical Roof H10  
1/2" = 1'-0"




Wall Section @ Metal Panel & Storefront H5  
1/2" = 1'-0"



Wall Section @ Metal Panel H1  
1/2" = 1'-0"



Wall Section @ GIC Canopy A10  
1/2" = 1'-0"



Wall Section @ Robotics Canopy A1  
1/2" = 1'-0"

Issue Date: September 9, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100


owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
multi-studio

architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio


civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com




Wall Section - Steel Penetration at Truss **H1**  
1/2" = 1'-0"




Wall Section @ Canopy Metal Skin Extension **A14**  
1/2" = 1'-0"



Wall Section @ Robotics Canopy Garage Door **A9**  
1/2" = 1'-0"



Wall Section @ South Window High Roof **A5**  
1/2" = 1'-0"



Wall Section @ South Window Low Roof **A1**  
1/2" = 1'-0"

Issue Date: September 9, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100


owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
multi-studio

architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio


civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvenrg.com

structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEP/IT Codes:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com




Foundation Detail @ Overhead Door **F13**  
1 1/2" = 1'-0"




Foundation Detail @ Lee's Summit North **F7**  
1 1/2" = 1'-0"




Foundation Detail @ Lee's Summit West **F1**  
1 1/2" = 1'-0"



Foundation Detail @ Storefront Entry **A13**  
1 1/2" = 1'-0"



Typical Foundation Detail @ Grade **A7**  
1 1/2" = 1'-0"



Typical Foundation Detail @ Exterior Concrete **A1**  
1 1/2" = 1'-0"

Issue Date: September 9, 2022

**Revisions**

NUMBER	DESCRIPTION	DATE
--------	-------------	------

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



**Exterior Section Details  
- Foundation**

**A320**





LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64086

owner: architect:  
**Lee's Summit R-7 School** **Multistudio**  
 301 NE Tudor Road 4200 Pennsylvania  
 Lee's Summit, MO 64086 Kansas City, MO 64111  
 816.931.6655


civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
**Bob D. Campbell &**  
4338 Belleview  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEPFT/Code::  
**Henderson Engineers**  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
[www.hendersonengineers.com](http://www.hendersonengineers.com)



NUMBER	DESCRIPTION	DATE
2	Addendum 02	08/23/



UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR



### Exterior Section Detail

# A321




**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


Project Number: 0121-0100

owner: Lee's Summit R-7 School 301 NE Tudor Road Lee's Summit, MO 64086 multi-studio	architect: Multistudio 4200 Pennsylvania Kansas City, MO 64111 816.931.6655
civil engineer: Kaw Valley Engineering 14700 West 114th Terrace Lenexa, KS 66215 913.485.0318 kveng.com	structural engineer: Bob D. Campbell & 4338 Bellevue Kansas City, MO 64111 816.531.4144 www.bdc-engrs.com


MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com




**Truss Penetrations Through M5  
MWP02 1 1/2" x 1'-0"**




**Truss Penetrations Through H5  
MWP02 1 1/2" x 1'-0"**




**Section Detail @ Top of Metal Skin at H1  
Canopy 1 1/2" x 1'-0"**



**Section Detail @ Roof Hatch A5  
1 1/2" x 1'-0"**



**Section Detail @ Bottom of Metal Skin at D1  
Canopy 1 1/2" x 1'-0"**



**Section Detail @ Top of CMU at Canopy A1  
1 1/2" x 1'-0"**

Issue Date: September 9, 2022

NUMBER	DESCRIPTION	DATE
3	AS01 - Code Comments	11/09/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



**Exterior Section Details  
A322**



LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner: **Lee's Summit R-7 School**  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect: **Multistudio**  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
**Bob D. Campbell &**  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEPFT/Code::  
**Henderson Engineers**  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
[www.hendersonengineers.com](http://www.hendersonengineers.com)



Issue Date: September 9, 2022

## Revisions

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



# A330



LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
303 NE Tudor Road  
Lee's Summit, MO 64086  
architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio  
civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvang.com  
structural engineer:  
Bob D. Campbell &  
4338 Belview  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

Issue Date: September 9, 2022

NUMBER	DESCRIPTION	DATE
--------	-------------	------


UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



Exterior Envelope  
Section & Details


A331

Axon Detail @ Typical Skin Panel E1  
1 1/2" = 1'-0"



Plan Detail @ Typical Perforation Pattern Prior To Break Forming A12  
1 1/2" = 1'-0"

Section Detail @ Typical Skin Panel A1  
6" = 1'-0"



NOTE: 40% PERFORATION

SLOPE AT TOP OF PANEL  
TO MATCH ADJACENT  
ROOF SLOPE, REF A111-B

HOLD CLEAR  
NO PERFORATIONS

DOTTED LINES TO  
REPRESENT BREAK FORM  
LINES FOR TYP PANEL

HOLD CLEAR  
NO PERFORATIONS

VARIES BASED ON LOCATION ALONG ROOF SLOPE

END SECTION 1: 1 ROW OF  
PERFORATIONS CENTERED  
BETWEEN NO PERF LINE  
AND BREAK FORM LINE, TYP  
PANEL TYPE 2: 3 ROWS OF  
PERFORATIONS CENTERED  
ON PANEL, TYP  
PANEL TYPE 3: 2 ROWS OF  
PERFORATIONS CENTERED  
ON SECTION, TYP  
PANEL TYPE 4: 2 ROWS OF  
PERFORATIONS CENTERED  
ON SECTION, TYP  
PANEL TYPE 1: 4 ROWS OF  
PERFORATIONS CENTERED  
ON SECTION, TYP

3' - 11 3/4"

TYP DIMENSION PRIOR TO BREAK FORMING



LSR7 Robotics, GiC & Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


Project Number: 0121-0100

owner: Lee's Summit R-7 School 301 NE Tudor Road Lee's Summit, MO 64086 multi-studio	architect: Multistudio 4205 Pennsylvania Kansas City, MO 64111 816.931.6655 multi-studio
civil engineer: Kaw Valley Engineering 14700 West 114th Terrace Lenexa, KS 66215 913.485.0318 kvang.com	structural engineer: Bob D. Campbell & 4338 Bellevue Kansas City, MO 64111 816.531.4144 www.bdc-engrs.com


MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

General Notes (Interior Elevations):


- REFER TO FINISH LEGEND/SCHEDULE FOR COMPLETE LISTING OF FINISHES
- REFER TO PROJECT STANDARDS FOR INSTALLATION INFORMATION FOR ACCESSORIES, TOILET FIXTURES, ETC.
- REFER TO PROJECT STANDARDS FOR DEVICES FOR TYPICAL INSTALLATION INFORMATION.
- AT GYP SOFFIT CONTROL JOINTS, CONTINUE CONTROL JOINT UP BOTH VERTICAL FACES OF SOFFIT.




LSN/LSW Men's Restroom - Interior Elevation 2 **F9**  
1/4" = 1'-0"




LSN/LSW Women's Restroom - Interior Elevation 2 **F3**  
1/4" = 1'-0"



LSN/LSW Women's Restroom - Interior Elevation 1 **A14**  
1/4" = 1'-0"



LSN/LSW Men's Restroom - Interior Elevation 1 **A9**  
1/4" = 1'-0"



LSN / LSW - Enlarged Restroom Plan **A3**  
1/4" = 1'-0"

Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/19/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



Enlarged Restroom  
Plans & Elevations

**A501**



**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
multi-studio

architect: Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvang.com

structural engineer: Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/PT/Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

Issue Date: September 9, 2022


Revisions		
NUMBER	DESCRIPTION	DATE

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION




**Enlarged Classroom Plans & Elevations**


**A502**



Elevation - Classroom D7  
1/4" = 1'-0"



Elevation - Classroom - South A7  
1/4" = 1'-0"



LSN / LSW - Enlarged Classroom Floor Plan A1  
3/8" = 1'-0"



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
**Bob D. Campbell &**  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com


Issue Date: September 9, 2022

Revisions	DESCRIPTION	DATE
NUMBER	ADDENDUM 01	09/19/2022
1		


UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION




**Interior Elevations  
A503**




Interior Elevation - LSN / LSW Robotics North **L1**  
1/4" = 1'-0"




Interior Elevation - LSN / LSW Robotics South **G1**  
1/4" = 1'-0"




Interior Elevation - LSN / LSW Robotics West **D10**  
1/4" = 1'-0"



Interior Elevation - LSN / LSW Robotics Corridor West **A10**  
1/4" = 1'-0"



Interior Elevation - LSN / LSW Robotics East **D1**  
1/4" = 1'-0"



Interior Elevation - LSN / LSW Robotics Corridor East **A1**  
1/4" = 1'-0"



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
multi-studio

architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
**Bob D. Campbell &**  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

Issue Date: September 9, 2022


Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/19/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION




**Interior Elevations**


**A504**




Interior Elevation - LSN / LSW GiC North **E10**  
1/4" = 1'-0"



Interior Elevation - LSN / LSW GiC South **E1**  
1/4" = 1'-0"



Interior Elevation - LSN / LSW GiC West **A10**  
1/4" = 1'-0"



Interior Elevation - LSN / LSW GiC East **A1**  
1/4" = 1'-0"



**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect: Multistudio  
4300 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio.com  
civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com  
structural engineer: Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

Issue Date: September 9, 2022


Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/09/2022
2	Addendum 02	09/28/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION.




Interior Details


**A540**




Plan Detail @ 1 Hour Rated Column **J13**  
3" = 1'-0"




Plan Detail @ Wood Corner Reveal **E13**  
3" = 1'-0"



Plan Detail @ Plywood Panel Vertical Joint **A13**  
3" = 1'-0"



Section Detail @ Restroom Vestibule **A6**  
1 1/2" = 1'-0"



Section Detail @ Classroom Ceiling Edge **A1**  
1 1/2" = 1'-0"



LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4300 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/EIT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com


General Notes (Casework Standards):

1. ALL CASEWORK IS TO BE CONSTRUCTED TO MEET OR EXCEED ARCHITECTURAL WOODWORK INSTITUTE (AWI) STANDARDS.
2. FIELD VERIFY ALL DIMENSIONS PRIOR TO FABRICATION.
3. PROVIDE RUBBER BASE AT ALL CABINET BASES, UNLESS NOTED OTHERWISE.
4. REFER TO INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR SPECIFIC MATERIAL LOCATIONS.
5. PROVIDE MOISTURE RESISTANT PLYWOOD AT COUNTERTOPS WITH SINKS.
6. SINKS SHOWN ON THESE DRAWINGS INDICATE LOCATIONS ONLY AND MAY NOTE REFLECT ACTUAL SIZES OR TYPES.
7. COORDINATE LOCATIONS OF ALL EQUIPMENT AND CONFIRM PROPER CLEARANCES. NOTIFY ARCHITECT OF ANY DISCREPANCIES.
8. CENTER ALL SINKS IN THE ASSOCIATED CASEWORK, UNLESS NOTED OTHERWISE.
9. PROVIDE SIDE SPLASH WHERE COUNTERTOP ABUTS WALL, OR AT COUNTERTOPS WITH DIFFERENT HEIGHTS ABUT.
10. SEAL ALL JOINTS BETWEEN WORK SURFACES/CABINETS AND ADJOINING SURFACES.
11. PROVIDE IN WALL BLOCKING AS REQUIRED FOR UPPER CABINETS.
12. CONTRACTOR WILL BE RESPONSIBLE FOR PROTECTING FINISHED FLOORING SURFACES FROM DAMAGE DURING ALL CONSTRUCTION PHASES.
13. FIELD COORDINATE LOCATIONS OF GROMMETS IN COUNTERTOPS WITH OWNER/ARCHITECT.
14. PROVIDE FINISHED CLOSURE PANELS AT EXPOSED END CONDITIONS.
15. PROVIDE FILLER PANEL/SCRIBE AT ALL LOCATIONS WHERE CASEWORK MEETS A WALL.
16. PROVIDE LOCKS AT ALL CABINET DOORS. FINAL LOCK COORDINATION WILL BE DONE BY OWNER/ARCHITECT DURING SHOP DRAWING PROCESS.
17. ALL PENETRATIONS THROUGH CASEWORK SHALL BE SEALED OR COVERED WITH AN ESCUTCHEON.

CASEWORK CABINET GROUPS:

B BASE CABINET  
BS BASE SCRIBE  
T TALL CABINET  
U UPPER CABINET  
US UPPER SCRIBE

Casework Legend



Casework Schedule

Mark	Width	Height	Depth
Base - 301 - Open Cubby Shelving (34 inch)			
B301	36"	32 1/2"	23"
Base-101 Single-Plywood			
B101	17 1/2"	53"	12"
Base-102 Double			
B154	36"	32 1/2"	24"
Base-154 Double for ADA Sink			
B154	36"	32 1/2"	23"
T525 - Open Shelving Stack (9") 2' Depth			
T501	44"	100"	25 3/8"
Upper-301 Single-Plywood			
U301	17 1/2"	48 3/4"	12"
Upper-302 Double			
U302	36"	49"	12"

Issue Date: September 9, 2022

Revisions


NUMBER	DESCRIPTION	DATE
2	Addendum 02	09/29/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION.




Casework Standards


A600




Plan Detail - Typical Scribe K14  
12" = 1'-0"




Section Detail @ CAD Station D14  
1" = 1'-0"




Section Detail @ Classroom Shelving D9  
3/4" = 1'-0"



Cabinet Types - Upper K3  
3/4" = 1'-0"



Cabinet Types - Tall D3  
3/4" = 1'-0"



Cabinet Types - Base A3  
3/4" = 1'-0"



LSR7 Robotics, GiC & Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect: Multistudio  
4300 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio.com  
civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kweg.com  
structural engineer: Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/FIT/Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

Finish Legend - LSN & LSW

Mark	Manufacturer	Model	Material Color	Comments
033000	CAST-IN-PLACE CONCRETE			CONCRETE WITH SURFACE SEALER
062023	INTERIOR ARCHITECTURAL WOODWORK			
WD01	MURPHY PLYWOOD	3/4" PLYWOOD WALL PANEL WITH TYPE "A" VENEER CORE	WHITE OAK, PLAIN SLICED	REF ELEVATIONS AND RCP FOR LOCATIONS
064116	PLASTIC LAMINATE-CLAD ARCHITECTURAL CABINETS			
PL01	FORMICA	N/A	STORM 912	CLASSROOM CASEWORK, REF ELEVATIONS
081416	FLUSH WOOD DOORS			
WD02	-	N/A	WHITE OAK, PLAIN SLICED	DOOR FINISH
096513	RESILIENT BASE AND ACCESSORIES			
RB01	ROPPE	PINNACLE	123 CHARCOAL	6" COVE WALL BASE
RB02	ROPPE	PINNACLE	123 CHARCOAL	6" FLAT WALL BASE
RB03	ROPPE	PINNACLE	123 CHARCOAL	4" FLAT WALL BASE
096723	EPOXY RESINOUS FLOORING			
EP01	DESCO COATINGS	GRANITE SERIES	GUNMETAL	EPOXY RESINOUS FLOORING IN RESTROOMS, WITH INTEGRAL 6" BASE
096813	TILE CARPET			
CTP01	MATS INC	SUPER NOP 52	GRUUS/CHARCOAL	WALK OFF CARPET
099123	INTERIOR PAINTING			
PT01	SHERWIN WILLIAMS	N/A	LAZY GRAY SW6254	EPOXY PAINT REQUIRED FOR ALL WET WALL LOCATIONS IN RESTROOMS.
PT02	SHERWIN WILLIAMS	N/A	PEPPER CORN SW7674	ALL STRUCTURE TO BE PAINTED, TYP. EPOXY PAINT REQUIRED FOR ALL WET WALL LOCATIONS: KITCHEN, WATER FOUNTAINS, SHOP SINK ALCOVE.
101100	VISUAL DISPLAY UNITS			
WB01	CLARIDGE	LCS DELUXE PORCELAIN WHITEBOARD	WHITE	60" ROLL MOUNTED HORIZONTALLY. 3'-0" ALUM TRAY AT BASE. J TRIM CONTINUOUS AT TOP. 5'-6" HIGH STARTING 2'-6" AFF
123661	SIMULATED STONE COUNTERTOPS			
SS01	CORIAN SOLID SURFACE	N/A	CARBON AGGREGATE	CLASSROOM COUNTERTOPS

General Finish Notes:

- ALL FINISH MATERIALS MUST MEET THE FLAME SPREAD RATINGS PER THE BUILDING CODE.
- REFER TO INTERIOR ELEVATIONS AND PLANS FOR SPECIFIC MATERIAL LOCATIONS.
- REFERENCED FLOOR/WALL/CEILING TYPES ARE FOR TOP FINISH LAYER DETAILS ONLY. REFER TO ARCHITECTURAL AND STRUCTURAL DRAWINGS FOR FLOOR/WALL CEILING ASSEMBLY DETAILS PER LOCATION.
- PAINT ALL EXPOSED DUCTWORK, CONDUIT, ELECTRICAL EQUIPMENT, ETC TO MATCH ADJACENT SURFACES.
- PAINT ALL NON-FACTORY FINISHED EXPOSED METAL TO MATCH ADJACENT WALL COLOR, UNO.
- REFER TO TYPICAL FLOORING TRANSITION DETAILS FOR ALL FLOORING MATERIALS.
- FLOORING TRANSITIONS AT DOORS SHOULD BE LOCATED UNDER THE DOOR IN THE CLOSED POSITION, UNLESS NOTED OTHERWISE.
- CONTRACTOR WILL BE RESPONSIBLE FOR PROTECTING FINISHED FLOORING SURFACES FROM DAMAGE DURING ALL CONSTRUCTION PHASES.
- PROVIDE BULLNOSE TRIM AT TRANSITIONS FROM CERAMIC WALL TILE TO OTHER MATERIAL, UNLESS NOTED OTHERWISE.
- REFER TO REFLECTED CEILING PLANS FOR CEILING HEIGHTS.
- ALL ELECTRICAL DEVICE COVERS ARE TO BE WHITE UNLESS NOTED OTHERWISE.
- ALL HOLLOW METAL DOORS, FRAMES AND LITE KITS TO BE PAINTED TO MATCH ADJACENT WALL COLOR.
- WALLS AND COLUMNS TO BE PT01 UNO.

Room name


WALL FINISH  
BASE FINISH  
FLOOR FINISH

- Signage Schedule -

Type Mark	Type Comments
A	Room ID (Standard)
R1.A	Restroom - Men
R2.A	Restroom - Women
A	Room ID (Standard)
C	Exterior Door Vinyl Sign
C	Exterior Door Vinyl Sign
C	Exterior Door Vinyl Sign

Wall Base Details J12  
6" = 1'-0"

Flooring Transitions J9  
12" = 1'-0"



Issue Date: September 9, 2022

NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/09/2022
2	Addendum 02	09/28/2022

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION.



Finish Plan

AF101

LSN / LSW - Level 1 Finish Plan A3  
3/16" = 1'-0"



LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
multi-studio

architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

General Notes (Furniture Plans):

1. FURNITURE SHOWN FOR COORDINATION PURPOSES ONLY. OWNER TO FINALIZE AND PROVIDE UNDER SEPARATE CONTRACT.

GiC Equipment List:

1. AIR COMPRESSOR
2. MITER SAW
3. PANEL SAW
4. 6' X 2' ROLLING TABLES
5. 6' X 3' WORK TABLES
6. 3' X 10' TOOL CRIB
7. BUTCHER BLOCK WORK COUNTER

LSW Equipment List:

1. BRIDGEPORT 3-AXIS CNC
2. BIRMINGHAM YCL-1440GH LATHE
3. HYDRAULIC PRESS
4. ROLAND MDX-40A MILLING MACHINE
5. WELLS HORIZONTAL METAL BANDSAW
6. DELTA MILWAUKEE BAND SAW
7. KAWASAKI CUT OFF SAW
8. MITACHI MITER SAW
9. BALDOR BELT SANDER
10. DELTA MILWAUKEE DRILL PRESS
11. BELT AND DISC SANDER
12. RYOBI BENCH GRINDER
13. PORTER CABLE BENCH GRINDER
14. BUFFING WHEEL
15. HAND BREAK METAL SHEAR
16. PEXTO METAL FOOT SHEAR
17. OPEN TABLE CNC
18. WELDING TABLE & TIG WELDER
19. 4.5' X 1.5' SHELVING
20. 8' X 3' SHELVING
21. 4' X 4' WORK TABLE
22. LARGE CRAFTSMAN TOOL BOX
23. SMALL CRAFTSMAN TOOL BOX
24. CRAFTSMAN 17" DRILL PRESS
25. CRAFTSMAN 8" DRILL PRESS

Issue Date: September 9, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION



Furniture Plan - LSW

AF102-A

LSW - Level 1 Furniture Plan A3

3/16" = 1'-0"



LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
multi-studio

architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell &  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66314  
816.742.5000  
www.hendersonengineers.com

General Notes (Furniture Plans):

1. FURNITURE SHOWN FOR COORDINATION PURPOSES ONLY. OWNER TO FINALIZE AND PROVIDE UNDER SEPARATE CONTRACT.

GiC Equipment List:

1. AIR COMPRESSOR
2. MITER SAW
3. PANEL SAW
4. 6' X 2' ROLLING TABLES
5. 6' X 3' WORK TABLES
6. 3' X 10' TOOL CRIB
7. BUTCHER BLOCK WORK COUNTER

EXTERIOR TOOL CRIB  
BY OWNER

LSN Equipment List:

1. BRIDGEPORT 3-AXIS CNC
2. BRIDGEPORT TORQ-CUT 22
3. BIRMINGHAM YCL-1340GH LATHE
4. WEN 3975T HORIZONTAL METAL BANDSAW
5. CRAFTSMAN VERTICAL METAL BANDSAW
6. CENTRAL MACHINERY METAL CUTTING BAND SAW
7. GRIZZLY G7947 DRILL PRESS
8. OPEN TABLE CNC ROUTER
9. BALDOR BUFFER
10. BALDOR DISC SANDER
11. CRAFTSMAN MITER SAW
12. CRAFTSMAN BENCHTOP/DISC SANDER
13. GRIZZLY DUST COLLECTOR
14. AIR COMPRESSOR
15. ARBOR PRESS
16. KARDEX STORAGE SYSTEM
17. RVORBI BENCH GRINDER
18. WELDING TABLE & TIG WELDER
19. 4.5' X 1.5' SHELVING
20. 8' X 3' SHELVING
21. 4' X 4' WORK TABLE
22. LARGE CRAFTSMAN TOOL BOX
23. SMALL CRAFTSMAN TOOL BOX

Issue Date: September 9, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS  
AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR  
CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION




Furniture Plan - LSN

AF102-B

LSN - Level 1 Furniture Plan A3  
3/16" = 1'-0"





RELEASED FOR CONSTRUCTION  
As Noted on Plans Review  
Development Services Department  
Lee's Summit, Missouri  
11/18/2022

**multistudio**  
the evolution of gould evans

**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

Project Number: 0121-0100

owner: Lee's Summit R-7 School 301 NE Tudor Road Lee's Summit, MO 64086	architect: Multistudio 4200 Pennsylvania Kansas City, MO 64111 816.931.6655 multi.studio
civil engineer: Kaw Valley Engineering 14700 West 114th Terrace Lenexa, KS 66215 913.485.0318 kveng.com	structural engineer: Bob D. Campbell & 4338 Bellevue Kansas City, MO 64111 816.531.4144 www.bdc-engrs.com

MEP/IT/Codes:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

Issue Date: September 9, 2022

Revisions	NUMBER	DESCRIPTION	DATE
-----------	--------	-------------	------

Signage Notes:

- Solid Color Insert
- Clear non-glass lens over paper insert
- Printed paper text insert
- Tactile Lettering
- 3/32" Grade 2 Braille, match color to background

UNLESS A PROFESSIONAL SEAL WITH SIGNATURE AND DATE IS AFFIXED, THIS DOCUMENT IS PRELIMINARY AND IS NOT INTENDED FOR CONSTRUCTION, RECORDING PURPOSES OR IMPLEMENTATION

**Signage Types**  
**SG001**



LSR7 Robotics, GiC & Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com


MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

**HENDERSON**  
ENGINEERS  
8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM  
2150005255  
MO. CORPORATE NO. E-5680  
EXPIRES 12/31/2022

Issue Date: September 5, 2022

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------



09/09/2022  
CARL J. HOLDEN  
LICENSE # PE-2020016283

PLUMBING LEGEND  
AND GENERAL NOTES  
P000

GENERAL NOTES:

- PROVIDE A CONSTRUCTION RECORD SET OF "AS-BUILT" DOCUMENTS TO THE ARCHITECT REFLECTING ANY VARIANCES OF INSTALLED PIPING LOCATIONS OR EQUIPMENT CONTRARY TO THE CONSTRUCTION DOCUMENTS. REFER TO SPECIFICATIONS.
- DRAWINGS ARE DIAGRAMMATIC ONLY AND REPRESENT THE GENERAL SCOPE OF THE WORK. REVIEW THE GENERAL NOTES, SPECIFICATIONS AND PLANS FOR ADDITIONAL REQUIREMENTS THAT MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY THE ARCHITECT OF ANY CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
- PROVIDE TO THE ARCHITECT A COPY OF INSPECTION REPORTS AND APPROVAL CERTIFICATES FROM LOCAL AND STATE INSPECTIONS. REFER TO SPECIFICATIONS.
- INSTALLATION SHALL COMPLY WITH LEGALLY CONSTITUTED CODES AND THE REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
- PLANS AND SPECIFICATIONS GOVERN WHERE THEY EXCEED CODE REQUIREMENTS.
- VERIFY LOCATION AND DEPTH OF UTILITIES AT POINTS OF CONNECTION BEFORE START OF PIPING INSTALLATION.
- REFER TO ARCHITECTURAL PLANS FOR EXACT LOCATION AND MOUNTING HEIGHTS OF PLUMBING FIXTURES.
- DO NOT SCALE FLOOR PLANS FOR EXACT HORIZONTAL LOCATION OF PIPE ROUTING.
- INSTALL CONCEALED PIPING TIGHT TO THE STRUCTURE AND AS HIGH AS POSSIBLE.
- VALVES SHALL BE LINE SIZE UNLESS OTHERWISE NOTED.
- INSTALL EXPOSED PIPING, WHERE NECESSARY, IN FINISHED AREAS TIGHT TO THE STRUCTURE, WALL OR CEILING AND AS HIGH AS POSSIBLE. INSTALL PIPING PARALLEL AND / OR PERPENDICULAR TO WALLS.
- INSTALL VALVES AND APPURTENANCES A MAXIMUM OF 24" ABOVE CEILING IN ACCESSIBLE LOCATION WITHIN 24" OF ACCESS DOORS OR ACCESSIBLE CEILING TILES. PROVIDE PIPE AND FITTINGS TO INSTALL VALVES AND APPURTENANCES AT REQUIRED HEIGHT AND WITHIN 24" OF ACCESS DOORS OR ACCESSIBLE CEILING TILES.
- INSTALL NO PLASTIC PIPE OF ANY KIND ABOVE SLAB INSIDE THE BUILDING. INSTALL NO PLASTIC PIPE IN THE CEILING RETURN AIR PLENUM.
- COORDINATE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
- COORDINATE PIPING INSTALLATION WITH STRUCTURAL GRADE BEAMS, FOOTINGS, COLUMN PIERS, ETC. SLEEVE PIPING THROUGH GRADE BEAMS, FOOTINGS, ETC. WHERE REQUIRED AND AS NOTED ON PLANS. COORDINATE SLEEVE INSTALLATIONS WITH THE ARCHITECT, STRUCTURAL ENGINEER, STRUCTURAL CONTRACTOR AND GENERAL CONTRACTOR BEFORE CONCRETE IS INSTALLED.
- CLEAN FAUCET AERATORS AND PIPE STRAINERS PRIOR TO TURNING BUILDING OVER TO THE OWNER.
- PROVIDE TRAP PRIMERS WHERE REQUIRED BY LOCAL AUTHORITIES.
- COORDINATE PIPE ROUTING AWAY FROM ELECTRICAL PANELS. DO NOT INSTALL PIPING OVER ELECTRICAL PANELS.
- PAINT ALL EXPOSED GAS AND WATER PIPING USING RUST INHIBITOR PAINT. PAINT AND COLOR SHALL BE COORDINATED WITH THE ARCHITECT AND / OR OWNER.
- COORDINATE ALL ROOF PENETRATIONS WITH OTHER TRADES. MAINTAIN 10' MINIMUM CLEARANCE FROM ALL AIR INTAKES. MAINTAIN 2' CLEARANCE FROM ALL OTHER EQUIPMENT.
- INSULATE PIPING ROUTED IN EXTERIOR BUILDING WALLS WITH MINIMUM 2" BATT INSULATION TO PREVENT FREEZING.
- PROVIDE "HEAVY-DUTY" NO-HUB COUPLINGS ON SANITARY PIPING 4" AND LARGER. SEE DIVISION 22 SPECIFICATION SECTION "SANITARY DRAINAGE AND VENT AND PIPING SPECIALTIES" FOR MORE INFORMATION.
- PROVIDE "HEAVY-DUTY" NO-HUB COUPLINGS ON STORM PIPING, INCLUDING CONNECTIONS TO ROOF DRAINS. SEE DIVISION 22 SPECIFICATION SECTION "STORM DRAINAGE PIPING AND SPECIALTIES" FOR MORE INFORMATION.
- PROVIDE TRANSITION ADAPTER COUPLINGS FOR CONNECTION OF PVC DWV TO CAST IRON AT SLAB ON GRADE. SEE DIVISION 22 SPECIFICATION FOR MORE INFORMATION.
- PROVIDE TRANSITION ADAPTER COUPLINGS FOR CONNECTION OF PVC DWV TO CAST IRON SANITARY, WASTE AND VENT PIPE AT SLAB ON GRADE. SEE DIVISION 22 SPECIFICATION SECTION "SANITARY DRAINAGE AND VENT PIPING AND SPECIALTIES" FOR MORE INFORMATION.
- PROVIDE TRANSITION ADAPTER COUPLINGS FOR CONNECTION OF PVC DWV TO CAST IRON STORM PIPE AT SLAB ON GRADE. SEE DIVISION 22 SPECIFICATION SECTION "STORM DRAINAGE PIPING AND SPECIALTIES" FOR MORE INFORMATION.
- FLOW CONTROL VALVES SHALL BE SIZE 1/2" AND SET AT 0.5 GPM UNLESS NOTED OTHERWISE.
- WATER HAMMER ARRESTORS SHALL BE SIZE "A" UNLESS NOTED OTHERWISE.
- PROVIDE VERTICAL LIFT SPRING LOADED CHECK VALVES IN HOT AND COLD WATER SUPPLIES FOR MOP SINK FAUCETS DOWNSTREAM OF SHUTOFF VALVES.
- PROVIDE WALL PIPES AT PIPING PENETRATIONS OF ELEVATED WATERPROOF FLOOR SLABS, REFER TO SPECIFICATIONS.
- PROVIDE SIZE AND LENGTH OF HOT WATER FIXTURE SUPPLY PIPE FROM CIRCULATED HOT WATER BRANCH OR MAIN TO TERMINATION OF HOT WATER FIXTURE SUPPLY PIPE AT EACH FIXTURE PER 2015 INTERNATIONAL ENERGY CONSERVATION CODE, TABLE C404.3.1. FOR 1/2" HOT WATER FIXTURE SUPPLY PIPE SIZE TO INDIVIDUAL LAVATORIES, PROVIDE MAXIMUM LENGTH OF TWO FEET. FOR 1/2" HOT WATER FIXTURE SUPPLY PIPE SIZE TO INDIVIDUAL SINKS, PROVIDE MAXIMUM LENGTH OF 45 FEET. FOR 3/4" HOT WATER FIXTURE SUPPLY PIPE SIZE TO INDIVIDUAL SINKS, PROVIDE MAXIMUM LENGTH OF 21 FEET.

PLUMBING SYMBOLS

THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS OR ABBREVIATIONS ARE USED.

V2.02

STANDARD MOUNTING HEIGHTS

HOSE BIBB (CENTERLINE)	36"
ICE MAKER OUTLET BOX (CENTER OF BOX)	24"
JANITOR'S SINK FAUCET FITTINGS (CENTERLINE)	42"
NON FREEZE WALL HYDRANT (AFG TO CENTERLINE)	18"
WASHING MACHINE OUTLET BOX (RIM)	42"

INSTALL PLUMBING FIXTURES AT THE MOUNTING HEIGHTS SHOWN ABOVE UNO IN THE ARCHITECTURAL DRAWINGS OR ELSEWHERE IN THE CONSTRUCTION DOCUMENTS. FINAL APPROVAL OF LOCATIONS BY ARCHITECT. MOUNTING HEIGHTS LISTED ABOVE, OR ELSEWHERE IN THE CONSTRUCTION DOCUMENTS, ARE AFF. UNO. ALL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH CURRENT ADA AND LOCAL REQUIREMENTS.

ANNOTATION

	PLUMBING PLAN NOTE CALLOUT
	PLUMBING EQUIPMENT DESIGNATION. (CONTRACTOR FURNISHED AND INSTALLED). REFER TO PLUMBING FIXTURE OR EQUIPMENT SCHEDULES
	EQUIPMENT DESIGNATION (OWNER FURNISHED, CONTRACTOR INSTALLED)
	MECHANICAL EQUIPMENT DESIGNATION (CONTRACTOR FURNISHED AND INSTALLED UNLESS NOTED OTHERWISE)
	CONNECTION POINT OF NEW WORK TO EXISTING
	DETAIL REFERENCE UPPER NUMBER INDICATES DETAIL NUMBER LOWER NUMBER INDICATES SHEET NUMBER
	SECTION CUT DESIGNATION
	DEDICATED EQUIPMENT ACCESS TILE
	ACCESS PANEL

ABBREVIATIONS

ADA	AMERICANS WITH DISABILITIES ACT	MIN	MINIMUM
AFF	ABOVE FINISHED FLOOR	N/C	NORMALLY CLOSED
AFG	ABOVE FINISHED GRADE	N/O	NORMALLY OPEN
AHU	AIR HANDLING UNIT	NIC	NOT IN CONTRACT
AP	ACCESS PANEL	ORD	OVERFLOW ROOF DRAIN
BAS	BUILDING AUTOMATION SYSTEM	POI	PLUMBING DRAINAGE INSTITUTE
BFF	BELOW FINISHED FLOOR	PHQ	PHASE
BFG	BELOW FINISHED GRADE	PRV	PRESSURE REDUCING VALVE
BOP	BOTTOM OF PIPE	PVC	POLYVINYL CHLORIDE
BOS	BOTTOM OF STRUCTURE	RCP	REINFORCED CONCRETE
BTU	BRITISH THERMAL UNIT	PIPE	PIPE
CP	CONDENSATE PUMP	RD	ROOF DRAIN
CPVC	CHLORINATED POLYVINYL CHLORIDE	RPM	REVOLUTIONS PER MINUTE
CJ	COPPER	RTU	ROOFTOP UNIT
DI	DUCTILE IRON	SF	SQUARE FEET
DN	DOWN	SP	SUMP
DFU	DRAINAGE FIXTURE UNIT	SS	STAINLESS STEEL
DS	DOWNSPOUT	SS	SANITARY SEWER, SOIL STACK
(E)	EXISTING	TDH	TOTAL DYNAMIC HEAD
EMS	ENERGY MANAGEMENT SYSTEM	TFA	TO FLOOR ABOVE
ETR	EXISTING TO REMAIN	TFB	TO FLOOR BELOW
EWG	ELECTRIC WATER COOLER	TYP	TYPICAL
FD	FLOOR DRAIN	UL	UNDERWRITERS LABORATORIES, INC. UNLESS NOTED OTHERWISE
FFA	FROM FLOOR ABOVE	UNO	UNINTERRUPTIBLE
FFB	FROM FLOOR BELOW	UPS	UNINTERRUPTIBLE POWER SUPPLY
FF	FINISHED FLOOR	VCP	VITRIFIED CLAY PIPE
FL	FLOW LINE	VFD	VARIABLE FREQUENCY DRIVE
FLA	FULL LOAD AMPS	VS	VENT STACK
FLR	FLOOR	VTR	VENT THROUGH ROOF
GPM	GALLONS PER MINUTE	W	WITH
HD	HEAD, HUB DRAIN	W/O	WITHOUT
HZ	HERTZ	WC	WATER COLUMN
IE	INVERT ELEVATION	WS	WASTE STACK
IN WC	INCHES OF WATER COLUMN	WSFU	WATER SUPPLY FIXTURE UNIT
JB	JUNCTION BOX	WVS	WASTE VENT STACK
J-BOX	JUNCTION BOX		
KW	KILOWATT		
MAU	MAKE-UP AIR UNIT		
MAX	MAXIMUM		
MBH	1000 BTU PER HOUR		
MH	MANHOLE		

PIPING SYMBOLS

	OXYGEN OUTLET
	NITROUS OXIDE OUTLET
	MEDICAL AIR OUTLET
	NITROGEN OUTLET
	MEDICAL VACUUM INLET
	FLOOR SINK (FS), SIZE & TYPE
	FLOOR DRAIN (FD), SIZE & TYPE
	ROOF DRAIN (RD), SIZE & TYPE
	BALL VALVE
	CONTROL VALVE
	SHUTOFF VALVE
	CHECK VALVE
	BALANCING VALVE WITH PRESSURE PORTS
	WATER METER
	STRAINER
	STRAINER WITH BLOWOFF
	RELIEF/SAFETY VALVE
	SOLENOID VALVE
	PRESSURE REDUCING VALVE
	GAS PRESSURE REGULATOR
	THERMOSTATIC MIXING VALVE
	PIPE ANCHOR
	EXPANSION JOINT
	BACKFLOW PREVENTER
	PRESSURE GAUGE
	THERMOMETER
	UNION
	FLANGE CONNECTION
	HOSE BIBB (HB)
	NON-FREEZING WALL HYDRANT (NW)
	MANUAL / AUTOMATIC AIR VENT OR VACUUM RELIEF VALVE
	PRESSURE / VACUUM SWITCH
	CLEANOUT
	CAP
	WALL CLEANOUT (WCO)
	FLOOR CLEANOUT (FCO)
	EXTERIOR CLEANOUT (ECO)
	ELBOW UP
	ELBOW DOWN
	TEE UP
	TEE DOWN
	ELBOW UP WITH SHUT-OFF VALVE (SOV)
	ELBOW DOWN WITH SHUT-OFF VALVE (SOV)
	TEE UP WITH SHUT-OFF VALVE (SOV)
	TEE DOWN WITH SHUT OFF VALVE (SOV)
	WATER HAMMER ARRESTER (WHA) WITH PDI SIZES, (A, B, C, D, & E)
	RECIRCULATION PUMP
	P-TRAP
	GAS COCK
	TRAP PRIMER
	TRAP PRIMER WITH DISTRIBUTION UNIT

LINETYPE LEGEND

THROUGHOUT THE DRAWINGS DIFFERENT LINETYPES ARE USED IN COMBINATION WITH THE SYMBOLS TO INDICATE THE STATUS OF ITEMS AS EXISTING, TO BE DEMOLISHED, TO BE INCLUDED AS PART OF NEW WORK AND/OR ITEMS WHICH ARE ANTICIPATED TO BE PROVIDED IN THE FUTURE. THE STATUS OF ITEMS USING THESE LINETYPES ARE RELATIVE TO THE VIEW IN WHICH THEY APPEAR. PHASING SHOWN IN DRAWINGS IS NOT INTENDED TO FULLY DESCRIBE ALL NECESSARY CONSTRUCTION PHASING, WHICH IS DETERMINED BY THE CONTRACTOR AS PART OF THEIR RESPONSIBILITIES. ANY SUCH PHASES DESCRIBED IN THE CONSTRUCTION DOCUMENTS ARE GENERAL AND ONLY INTENDED TO INDICATE A BROAD ORDER FOR THE SAKE OF DESCRIBING THE PROJECT. THE FOLLOWING LINETYPES MAY BE USED ON ANY DEVICE, EQUIPMENT, NOTE, LINE, SHAPE, ETC.

EXISTING

NEW

DEMOLISH


FUTURE

PIPING LINETYPES

	DOMESTIC COLD WATER (CW)
	SOFTENED COLD WATER (SCW)
	DOMESTIC HOT WATER (HW)
	DOMESTIC HOT WATER RECIRC. (HWR)
	DOMESTIC HOT WATER (140°)
	TRAP PRIMER LINE (T)
	SOIL PIPING - ABOVE FLOOR (S)
	SOIL PIPING - BELOW FLOOR (S)
	WASTE PIPING - ABOVE FLOOR (W)
	WASTE PIPING - BELOW FLOOR (W)
	GREASE WASTE - ABOVE FLOOR (GW)
	GREASE WASTE - BELOW FLOOR (GW)
	COMBINATION GREASE WASTE AND VENT (CGWV)
	COMBINATION WASTE AND VENT (CWV)
	STORM DRAIN - ABOVE FLOOR (ST)
	STORM DRAIN - BELOW FLOOR (ST)
	OVERFLOW STORM DRAIN - ABOVE FLOOR (OST)
	VENT BELOW GRADE (VBG)
	VENT BELOW FLOOR (VBF)
	INDIRECT DRAIN (ID)
	CONDENSATE DRAIN - HIGH EFFICIENCY RTU (CDH)
	CONDENSATE DRAIN (CD)
	AUXILIARY CONDENSATE DRAIN (ACD)
	SUMP OR SEWAGE PUMP DISCHARGE (SPD)
	NATURAL GAS (G)
	NATURAL GAS ON ROOF (G)
	MEDIUM PRESSURE NATURAL GAS (MPG)
	MEDIUM PRESSURE NATURAL GAS ON ROOF (MPG)
	NON-POTABLE WATER (NPW)
	LIQUEFIED PETROLEUM GAS (LPG)
	WATER SERVICE (WS)
	FIRE PROTECTION SPRINKLER DRY (DFP)
	FIRE PROTECTION SPRINKLER WET (FP)
	FIRE PROTECTION STANDPIPE DRY (DSP)
	FIRE PROTECTION STANDPIPE WET (WSP)
	CONDENSATE PUMP DISCHARGE (PD)
	VENT PIPING (V)
	ACID WASTE - ABOVE FLOOR (AW)
	ACID WASTE - BELOW FLOOR (AW)
	ACID VENT (AV)
	GRAY WATER (GWS)
	COMPRESSED AIR (CA)
	MEDICAL AIR (MA)
	MEDICAL VACUUM (VE)
	HELIUM (HE)
	INSTRUMENT AIR (IA)
	INSTRUMENT VACUUM (IV)
	NITROGEN (N2)
	NITROUS OXIDE (N2O)
	OXYGEN (O2)
	EVAC/WAGD (EV)
	CARBON DIOXIDE (CO2)
	MEDICAL AIR INTAKE (AI)
	MEDICAL VACUUM EXHAUST (VE)
	DENTAL AIR (DA)
	DENTAL VACUUM (DV)
	FILTERED WATER (FW1)
	FILTERED WATER W/ SCALE INHIBITOR (FW2)
	REVERSE OSMOSIS (RO)
	REVERSE OSMOSIS REMINERALIZATION (ROR)

CALL OUTS

ENLARGED PLAN CALLOUT



NOT IN SCOPE





**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio


civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com


MEP/T/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

**PLUMBING PLAN NOTES:**


- P1 COORDINATE WATER PIPE ROUTING AWAY FROM ELECTRIC PANELS. MAINTAIN CLEARANCES PER NEC.  
P2 ROUTE PIPE TIGHT TO WALL.  
P4 1/2" CA PROVIDE SHUTOFF VALVE AND CAP FOR FUTURE CONNECTION.  
P7 PIPE BELOW WINDOWS TIGHT TO WALL. SLOPE PIPE DOWN TOWARD THE WALL FOR RAIN.  
P8 1/2" CA DROP WITH SHUTOFF VALVE. DROP TO 4" AFF.




① LSW - PLUMBING ENLARGED SANITARY & VENT PLAN  
1/4" = 1'-0"



③ LSW - PLUMBING ENLARGED WATER & GAS PLAN  
1/4" = 1'-0"



② LSW - PLUMBING ROOF PLAN  
1/8" = 1'-0"



① LSW - PLUMBING PLAN - LEVEL 1  
3/16" = 1'-0"

**HENDERSON**  
ENGINEERS  
8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM

2150005255  
MO. CORPORATE NO. E-6680  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

NUMBER	DESCRIPTION	DATE
2	Addendum 02	09/23/2022



CARL J. HOLDEN  
LICENSE # PE-2020016283

**LSW - PLUMBING PLAN - LEVEL 1**

**P101-A**



LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
**Bob D. Campbell & Company**  
4338 Belleview  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com



---

Issue Date: September 9, 202



## PLUMBING DETAILS

### P501







LSR7 Robotics, GiC & Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

GENERAL NEW NOTES:

- PRIOR TO SUBMITTING BID, VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH THE EXISTING CONDITIONS OF THE PROJECT. REVIEW THE GENERAL NOTES, SPECIFICATIONS AND OTHER DRAWINGS FOR ADDITIONAL REQUIREMENTS WHICH MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY ARCHITECT, ENGINEER AND/OR OWNER OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
- EXISTING CONDITIONS WERE TAKEN FROM ORIGINAL DRAWINGS AND SITE VISITS AND MAY NOT REFLECT EXACT "AS-BUILT" CONDITIONS. FIELD VERIFY EXISTING CONDITIONS PRIOR TO SUBMITTING FINAL BIDS. COORDINATE NEW WORK AND DEMOLITION WITH OTHER DISCIPLINES AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION.
- COORDINATE THE INSTALLATION OF THE MECHANICAL SYSTEMS WITH OTHER TRADES TO ENSURE A NEAT AND ORDERLY INSTALLATION. INSTALL DUCTWORK AND PIPING AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE WITH OTHER TRADES TO AVOID CONFLICTS. COORDINATE INSTALLATION OF DUCTWORK AND PIPING TO AVOID CONFLICTS WITH ELECTRICAL PANELS, LIGHTING FIXTURES, ETC. ANY MODIFICATIONS REQUIRED DUE TO LACK OF COORDINATION WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AT NO EXTRA COST TO THE OWNER.
- DURING INSTALLATION OF NEW WORK, AVOID DAMAGING EXISTING SURFACES AND EQUIPMENT TO REMAIN. REPAIR DAMAGE CAUSED DURING CONSTRUCTION AT NO EXTRA COST TO THE OWNER.
- PROVIDE TEMPORARY BARRIERS TO CONTAIN DUST AND DEBRIS RESULTING FROM THE PERFORMANCE OF THE WORK TO THE AREA WHERE WORK IS BEING PERFORMED.
- ALL MECHANICAL EQUIPMENT SHOWN ON THE MECHANICAL PLANS SHALL BE PROVIDED BY DIVISION 23 UNLESS OTHERWISE NOTED.
- NEW MECHANICAL EQUIPMENT, DUCTWORK AND PIPING ARE SHOWN AT APPROXIMATE LOCATIONS. FIELD MEASURE FINAL DUCTWORK AND PIPING LOCATIONS PRIOR TO FABRICATION AND MAKE ADJUSTMENTS AS REQUIRED TO FIT THE DUCTWORK AND PIPING WITHIN THE AVAILABLE SPACE. VERIFY THAT FINAL EQUIPMENT LOCATIONS MEET MANUFACTURER'S RECOMMENDATIONS REGARDING SERVICE CLEARANCE AND PROPER AIRFLOW CLEARANCE AROUND EQUIPMENT.
- REFER TO ARCHITECTURAL DRAWINGS FOR RELATED CONSTRUCTION DETAILS AS APPLICABLE TO THE HVAC SYSTEM. VERIFY CHASES AND PENETRATIONS SHOWN ON ARCHITECTURAL DRAWINGS THAT ARE INTENDED FOR DUCTWORK AND PIPING MEET REQUIREMENTS.
- COORDINATE LOCATION OF ROOF MOUNTED HVAC EQUIPMENT AND ROOF PENETRATIONS WITH THE ARCHITECTURAL AND STRUCTURAL DRAWINGS.
- INDOOR AIR QUALITY MEASURES: PROTECT INSIDE OF (INSTALLED AND DELIVERED) DUCTWORK AND HVAC UNITS FROM EXPOSURE TO DUST, DIRT, PAINT AND MOISTURE. REPLACE INSULATION THAT HAS BECOME WET AT ANY TIME DURING CONSTRUCTION. DRYING THE INSULATION IS NOT ACCEPTABLE. SEAL ANY TEARS OR JOINTS OF INTERNAL FIBERGLASS INSULATION. REMOVE DEBRIS FROM CEILING/RETURN AIR PLENUM INCLUDING DUST. VACUUM CLEAN ANY DUCTWORK CONNECTED TO HVAC UNITS THAT WERE OPERATED DURING THE CONSTRUCTION PERIOD AFTER NEW FILTERS ARE INSTALLED AND PRIOR TO TURNING SYSTEM OVER TO THE OWNER. THE INTERNAL SURFACES AND ASSOCIATED COILS OF ANY HVAC UNITS THAT WERE OPERATED SHALL ALSO BE CLEANED.
- INSTALL DUCTWORK AND PIPING PARALLEL TO BUILDING COLUMN LINES UNLESS OTHERWISE SHOWN OR NOTED.
- OVERHEAD HANGERS AND SUPPORTS FOR EQUIPMENT, DUCTWORK AND PIPING SHALL BE FASTENED TO BUILDING JOISTS OR BEAMS. DO NOT ATTACH HANGERS AND SUPPORTS TO THE ABOVE FLOOR SLAB OR ROOF EXCEPT WHERE CONCRETE INSERTS IN CONCRETE SLABS ARE ALLOWED BY THE SPECIFICATIONS.
- COORDINATE LOCATION OF EQUIPMENT SUPPORTS WITH LOCATION OF EQUIPMENT ACCESS PANELS/DOORS TO ENABLE SERVICE OF EQUIPMENT AND/OR FILTER REPLACEMENT.
- SEAL PENETRATIONS THROUGH THE BUILDING COMPONENTS IN ACCORDANCE WITH THE CONTRACT SPECIFICATIONS. FIREPROOF PENETRATIONS THROUGH FIRE RATED COMPONENTS IN ACCORDANCE WITH U.L. REQUIREMENTS.
- DRAIN, FLUSH, AND REFILL ALL PIPING SYSTEMS NECESSARY TO PERFORM THE WORK. REFERENCE SPECIFICATIONS FOR FLUSHING PERFORMANCE REQUIREMENTS AND SUBMIT FLUSHING PLAN TO ENGINEER FOR REVIEW. PROVIDE CHEMICAL TREATMENT FOR ALL PIPING SYSTEMS AFTER FLUSHING AND REFILLING THE SYSTEM.
- COORDINATE THE EXACT MOUNTING SIZE AND FRAME TYPE OF DIFFUSERS, REGISTERS AND GRILLES WITH THE SUPPLIER TO MEET THE CEILING, WALL AND DUCT INSTALLATION REQUIREMENTS.
- ADJUST LOCATION OF CEILING DIFFUSERS, REGISTERS AND GRILLES AS REQUIRED TO ACCOMMODATE FINAL CEILING GRID AND LIGHTING LOCATIONS.
- PAINT PORTIONS OF DUCTWORK AND INSULATION THAT ARE EXPOSED TO VIEW BY THE INSTALLATION OF DIFFUSERS, REGISTERS, AND GRILLES IN CEILINGS OR WALLS FLAT BLACK. PORTIONS INCLUDE BOTH THE INTERIOR OF UNLINED DUCTWORK AND THE EXTERIOR OF DUCTWORK AND INSULATION.
- DUCTWORK CROSSING FIRE RATED WALLS OR OTHER FIRE RATED ASSEMBLIES SHALL BE MINIMUM 26 GAUGE SHEET METAL.
- PROVIDE FIRE OR FIRE/SMOKE DAMPERS, AS APPLICABLE, IN DUCTWORK AT CEILINGS AND WALLS AT LOCATIONS SHOWN ON THE PLANS. FIRE AND FIRE/SMOKE DAMPERS SHALL CONFORM TO NFPA AS APPLICABLE. COORDINATE SLEEVE LENGTH WITH REQUIREMENTS OF INSTALLED LOCATION.
- PROVIDE WALL OR DUCT ACCESS PANELS OR DOORS FOR ACCESS TO FIRE AND FIRE/SMOKE DAMPERS. ACCESS PANEL OR DOOR SHALL BE MINIMUM SIZE OF 10" BY 10" AND SHALL BE INSTALLED WITHIN 12" OF DAMPER. PROVIDE A REMOVABLE DUCT SECTION WHERE DUCT SIZE TOO SMALL FOR A 10" BY 10" ACCESS DOOR.
- LOCATE AND SET THERMOSTATS AND HUMIDISTATS AT LOCATIONS SHOWN ON PLANS. VERIFY EXACT LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION. INSTALL DEVICES WITH TOP OF DEVICE AT MAXIMUM 48" APT TO MEET ADA REQUIREMENTS UNLESS NOTED OTHERWISE ON PLANS. PROVIDE INSULATED BACKING FOR THERMOSTATS MOUNTED ON EXTERIOR BUILDING WALLS. INSTALL WIRING IN CONDUIT PROVIDED BY DIVISION 26. AT A MINIMUM, PROVIDE CONDUIT IN THE WALL FROM THE JUNCTION BOX TO 6" ABOVE THE CEILING.
- COORDINATE THE LOCATION AND ELEVATION OF WALL-MOUNTED DEVICES WITH PRESENTATION BOARDS, DISPLAY CABINETS, SHELVES OR OTHER COMPONENTS SHOWN ON THE ARCHITECTURAL DRAWINGS THAT ARE TO BE INSTALLED UNDER OTHER DIVISIONS. CONTRACTOR WILL NOT BE REIMBURSED FOR RELOCATION OF WALL-MOUNTED DEVICES CAUSED BY A LACK OF COORDINATION.
- PROVIDE A MANUAL BALANCING DAMPER IN EACH DUCT TAKEOFF FROM SUPPLY, RETURN, OUTDOOR AND EXHAUST AIR DUCTS.
- PROVIDE A PREFABRICATED 45 DEGREE, HIGH EFFICIENCY, RECTANGULAR/ROUND BRANCH DUCT TAKEOFF FITTING FOR BRANCH DUCT CONNECTIONS AND TAKE-OFFS TO INDIVIDUAL DIFFUSERS, REGISTERS AND GRILLES. PROVIDE WITH INTEGRAL MANUAL BALANCING DAMPER AND LOCKING QUADRANT WHERE INDICATED ON PLANS.
- BRANCH DUCTWORK TO AIR OUTLETS SHALL BE SAME SIZE AS OUTLET NECK SIZE UNLESS OTHERWISE NOTED.
- REFER TO SPECIFICATIONS FOR DUCTWORK AND PIPING INSULATION REQUIREMENTS. DUCT SIZES ON MECHANICAL PLANS INDICATE CLEAR INSIDE AIRFLOW DIMENSIONS. INCREASE SHEET METAL SIZES ACCORDINGLY TO ACCOUNT FOR THICKNESS OF DUCT LINER.
- FLEXIBLE DUCTWORK SHALL NOT EXCEED 5'-0" IN LENGTH AND SHALL BE INSTALLED AND SUPPORTED TO AVOID SHARP BENDS AND SAGGING. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- PROVIDE EQUIPMENT VENTS AND FLUES PER EQUIPMENT MANUFACTURERS RECOMMENDATIONS AND EQUIPMENT SPECIFICATIONS. KEEP PENETRATIONS THROUGH ROOF A MINIMUM OF 10'-0" FROM HVAC EQUIPMENT FRESH AIR INLETS AND 2'-0" FROM ROOF PARAPETS.
- PROVIDE WALL MOUNTED LOUVERS AND DAMPERS WITH SUITABLE MOUNTING FRAME TO MATCH WALL CONSTRUCTION. COORDINATE WITH ARCHITECTURAL DRAWINGS.
- PROVIDE A NEW SET OF AIR FILTERS IN UNITS PRIOR TO TESTING, ADJUSTING AND BALANCING AND BEFORE TURNING SYSTEM(S) OVER TO OWNER.

MECHANICAL SYMBOLS

THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS OR ABBREVIATIONS ARE USED.

STANDARD MOUNTING HEIGHT

THERMOSTATS (USER ADJUSTABLE) CONTROLS 46" 48"

INSTALL DEVICES AT THE MOUNTING HEIGHTS SHOWN ABOVE UNO IN THE CONSTRUCTION DOCUMENTS. MOUNTING HEIGHTS LISTED ABOVE OR ELSEWHERE IN THE CONSTRUCTION DOCUMENTS ARE AFF OR AFG TO TOP OF THE DEVICE UNO. ALL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH CURRENT ADA AND LOCAL REQUIREMENTS.

ANNOTATION

- MECHANICAL PLAN NOTE CALLOUT
- MECHANICAL EQUIPMENT DESIGNATION (CONTRACTOR FURNISHED AND INSTALLED UNLESS NOTED OTHERWISE)
- CONNECTION POINT OF NEW WORK TO EXISTING
- DETAIL REFERENCE. UPPER NUMBER INDICATES DETAIL NUMBER LOWER NUMBER INDICATES SHEET NUMBER
- SECTION CUT DESIGNATION
- DEDICATED EQUIPMENT ACCESS TILE
- ACCESS PANEL

ABBREVIATIONS

AIC AIR CONDITIONING  
ACC AIR COOLED CHILLER  
ACCU AIR COOLED CONDENSING UNIT  
AFC ABOVE FINISHED CEILING  
AFF ABOVE FINISHED FLOOR  
AFG ABOVE FINISHED GRADE  
AHJ AUTHORITY HAVING JURISDICTION  
AHU AIR HANDLING UNIT  
AI ANALOG INPUT  
AO ANALOG OUTPUT  
AP ACCESS PANEL  
APD AIR PRESSURE DROP  
AWG AMERICAN WIRE GAUGE  
B BOILER  
BAS BUILDING AUTOMATION SYSTEM  
BB BACKBONE  
BD BACKDRAFT DAMPER  
BD BLOWDOWN  
BFC BELOW FINISHED CEILING  
BFF BELOW FINISHED FLOOR  
BFG BELOW FINISHED GRADE  
BFP BOILER FEED PUMP  
BHP BRAKE HORSEPOWER  
BI BINARY INPUT  
BO BINARY OUTPUT  
BOD BOTTOM OF DUCT  
BOS BOTTOM OF STRUCTURE  
BTU BRITISH THERMAL UNIT  
CFM CUBIC FEET PER MINUTE  
CH CHILLER  
CLG COOLING  
CP CONDENSATE PUMP  
CPT CONTROL POWER  
CRAC TRANSFORMER  
CRU COMPUTER ROOM AIR  
CT COOLING TOWER  
CV CONTROL VALVE  
CWP CONDENSER WATER PUMP  
CU CONDENSING UNIT  
CHWP CHILLED WATER PUMP  
DB DECIBELS  
DBA DECIBEL AVERAGE  
DDC DIRECT DIGITAL CONTROL  
DI DIGITAL INPUT  
DISC DISCONNECT  
DN DOWN  
DS DUCT SILENCER  
DX DIRECT EXPANSION  
(E) EXISTING  
EA EXHAUST AIR  
EAT ENTERING  
ET AIR TEMPERATURE  
EDB EXHAUST DRY BULB  
EF EXHAUST FAN  
EFF EFFICIENCY  
EMS ENERGY MANAGEMENT SYSTEM  
ESP EXTERNAL STATIC PRESSURE  
ETR EXISTING TO REMAIN  
EWB ENTERING WET BULB  
EWT ENTERING WATER TEMPERATURE  
FCU FAN COIL UNIT  
FFA FROM FLOOR ABOVE  
FFB FROM FLOOR BELOW  
FF FINISHED FLOOR  
FFI FINS PER INCH  
FPM FEET PER MINUTE  
GC GENERAL CONTRACTOR  
GPM GALLONS PER MINUTE  
HCA HAND-OFF-AUTOMATIC  
HP HORSEPOWER  
HTG HEATING

HWP HEATING WATER PUMP  
IN WC INCHES OF WATER COLUMN  
L LOUVER  
LAT LEAVING AIR TEMPERATURE  
LDB LEAVING DRY BULB  
LP LOW PRESSURE  
LWB LEAVING WET BULB  
LWT LEAVING WATER TEMPERATURE  
MAU MAKE-UP AIR UNIT  
MAX MAXIMUM  
MBH 1000 BTU PER HOUR  
MD MOTORIZED DAMPER  
MFR MANUFACTURER  
MIN MINIMUM  
N/A NOT APPLICABLE  
NIC NORMALLY CLOSED  
NO NORMALLY OPEN  
NOM NOMINAL  
NC NOISE CRITERIA  
NF NON-FUSED  
NIC NOT IN CONTRACT  
CA OUTSIDE AIR  
PICV PRESSURE INDEP. CONTROL VALVE  
PROVIDE FURNISH AND INSTALL  
QTY QUANTITY  
RA RETURN AIR  
RC ROOM CRITERIA  
RD RETURN DUCT  
REA RETURN AIR RELIEF AIR  
RF RETURN FAN  
RFR REFRIGERANT  
RH RELATIVE HUMIDITY  
RH ROOF HOOD  
RPM REVOLUTIONS PER MINUTE  
RTU ROOFTOP UNIT  
SA SUPPLY AIR  
SCP STEAM CONDENSATE PUMP  
SD SMOKE DUCT DETECTOR  
SD SUPPLY DUCT  
SF SUPPLY FAN  
SH SENSIBLE HEAT CAPACITY  
SOW SCOPE OF WORK  
SP STATIC PRESSURE  
ST STEAM TRAP  
STM STEAM  
TBD TO BE DETERMINED  
TCC CONTRACTOR TEMPERATURE CONTROLS  
TCP TEMPERATURE CONTROL PANEL  
TF TRANSFER FAN  
TFA TO FLOOR ABOVE  
TFB TO FLOOR BELOW  
TH TOTAL HEAT CAPACITY  
TSP TOTAL STATIC PRESSURE  
TT TEMPERATURE TRANSMITTAL  
TYP TYPICAL  
UF UNDERFLOOR  
UG UNDERGROUND  
US UNDERSLAB  
UH UNIT HEATER  
UNO UNLESS NOTED OTHERWISE  
VAV VARIABLE AIR VOLUME  
VEL VELOCITY  
VFD VARIABLE FREQUENCY DRIVE  
VRF VARIABLE REFRIGERANT FLOW  
VRV VARIABLE REFRIGERANT VOLUME  
W/ WITH  
WO WITHOUT  
WB WET BULB  
WC WATER COLUMN  
WPD WATER PRESSURE DROP  
XP EXPLOSION PROOF

HVAC DUCTWORK AND ACCESSORIES

- DUCTWORK/EQUIPMENT TO BE REMOVED OR RELOCATED
- EXISTING DUCTWORK/EQUIPMENT TO REMAIN
- LINEAR SLOT DIFFUSER
- INSULATED FLEXIBLE DUCT (MAX. 5'-0" LONG)
- BRANCH DUCT WITH 45° RECTANGLE-ROUND BRANCH FITTING AND MANUAL VOLUME DAMPER
- ELBOW WITH TURNING VANES
- BRANCH DUCT WITH BELL-MOUTH FITTING & MANUAL VOLUME CONTROL DAMPER
- DUCT UP
- DUCT DOWN
- EXHAUST AIR
- EXHAUST AIR - GREASE
- OUTSIDE AIR
- RELIEF AIR
- RETURN AIR
- SPECIAL EXHAUST
- SUPPLY AIR
- EQUIPMENT WITH FLEXIBLE DUCT CONNECTION
- 10" (NECK SIZE) CSD-1 (TYPE) 300 CFM (CFM OF SUPPLY DIFFUSER OR REGISTER)
- 24x24 (NECK SIZE) CEG-1 (TYPE) 800 CFM (CFM OF EXHAUST GRILLE)
- EQUIPMENT ACCESS TILE (IN ACT CEILINGS)
- ACCESS PANEL (IN GYPSUM)
- MANUAL VOLUME DAMPER
- SQUARE TO ROUND TRANSITION
- DUCT MOUNTED SMOKE DETECTOR (SD=SUPPLY/RD=RETURN)
- ROUND DUCT TAG INDICATING DIAMETER
- RECTANGULAR DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS.
- FLAT OVAL DUCT TAG INDICATING INTERNAL DUCT DIMENSIONS
- RISER DESIGNATION
- FIRE DAMPER
- FIRE SMOKE DAMPER
- SMOKE DAMPER
- VOLUME DAMPER
- MOTORIZED DAMPER
- BACKDRAFT DAMPER

ALL DUCT DIMENSIONS SHOWN ON DRAWINGS ARE INSIDE DIMENSIONS. REFER TO DUCTWORK SPECIFICATIONS FOR DUCTWORK INSULATION AND LINER INFORMATION.

HVAC CONTROL DEVICES

- HUMIDISTAT
- THERMOSTAT
- CARBON MONOXIDE SENSOR
- CARBON DIOXIDE SENSOR
- DIFFERENTIAL PRESSURE SENSOR
- FLOW SWITCH
- HUMIDITY SENSOR
- PULL STATION
- REMOTE TESTING STATION WITH INDICATING LIGHT
- STATIC PRESSURE
- TEMPERATURE SENSOR

PIPING SYMBOLS


- DIRECTION OF FLOW
- CONTROL VALVE
- THREE-WAY CONTROL VALVE
- SHUTOFF VALVE
- CHECK VALVE
- BALANCING VALVE WITH PRESSURE PORTS
- TRIPLE DUTY VALVE WITH PRESSURE PORTS
- STRAINER
- STRAINER WITH BLOWOFF
- RELIEF / SAFETY VALVE
- SOLENOID VALVE
- PRESSURE REDUCING VALVE
- GAS PRESSURE REGULATOR
- THERMOSTATIC MIXING VALVE
- PIPE ANCHOR
- EXPANSION JOINT
- PIPE GUIDE
- PIPING SUPPORT
- F & T TRAP
- BUCKET TRAP
- THERMOSTATIC TRAP
- BACKFLOW PREVENTER
- PRESSURE GAUGE
- THERMOMETER
- PRESSURE AND TEMPERATURE TEST PLUG
- UNION
- FLANGE CONNECTION
- VACUUM RELIEF VALVE
- AUTOMATIC AIR VENT
- MANUAL AIR VENT
- PRESSURE / VACUUM SWITCH
- CLEANOUT
- CAP
- ELBOW UP
- ELBOW DOWN
- TEE UP
- TEE DOWN
- ELBOW UP WITH SHUT-OFF VALVE (SOV)
- ELBOW DOWN WITH SHUT-OFF VALVE (SOV)
- TEE UP WITH SHUT-OFF VALVE (SOV)
- TEE DOWN WITH SHUT-OFF VALVE (SOV)
- REDUCER
- RECIRCULATION PUMP
- P-TRAP
- GAS COCK
- TOP BEAM CLAMP
- TRAPEZE HANGER
- FLEXIBLE CONNECTION

PIPING LINETYPES


- EXISTING PIPING TO BE REMOVED OR RELOCATED
- EXISTING PIPING TO REMAIN
- CONDENSATE DRAIN (CD)
- AUXILIARY CONDENSATE DRAIN (ACD)
- NON-POTABLE WATER (NPW)
- NATURAL GAS (G)
- NATURAL GAS ON ROOF (G)
- MEDIUM PRESSURE NATURAL GAS (MPG)
- MEDIUM PRESSURE NATURAL GAS ON ROOF (MPG)
- FUEL OIL SUPPLY (FOS)
- FUEL OIL RETURN (FOR)
- FUEL OIL VENT (FOV)
- LIQUEFIED PETROLEUM GAS (LPG)
- BOILER FEED WATER (BFW)
- HIGH PRESSURE STEAM SUPPLY (HPS)
- HIGH PRESSURE STEAM CONDENSATE (HPC)
- LOW PRESSURE STEAM SUPPLY (LPS)
- LOW PRESSURE STEAM CONDENSATE (LPC)
- CONDENSATE PUMP DISCHARGE (CPD)
- HEATING HOT WATER SUPPLY (HWS)
- HEATING HOT WATER RETURN (HWR)
- CHILLED WATER SUPPLY (CHWS)
- CHILLED WATER RETURN (CHWR)
- HOT / CHILLED WATER SUPPLY (HCS)
- HOT / CHILLED WATER SUPPLY (HCR)
- CONDENSER WATER SUPPLY (CWS)
- CONDENSER WATER RETURN (CWR)
- REFRIGERANT LIQUID (RL)
- REFRIGERANT DISCHARGE (HOT GAS) (RD)
- REFRIGERANT SUCTION (RS)
- REFRIGERANT DISCHARGE BYPASS (RDB)
- REFRIGERANT VENT (RV)

CALL OUTS

ENLARGED PLAN CALLOUT



NOT IN SCOPE



LINETYPE LEGEND

THROUGHOUT THE DRAWINGS DIFFERENT LINETYPES ARE USED IN COMBINATION WITH THE SYMBOLS TO INDICATE THE STATUS OF ITEMS AS EXISTING, TO BE DEMOLISHED, TO BE INCLUDED AS PART OF NEW WORK AND/OR ITEMS WHICH ARE ANTICIPATED TO BE PROVIDED IN THE FUTURE. THE STATUS OF ITEMS USING THESE LINETYPES ARE RELATIVE TO THE VIEW IN WHICH THEY APPEAR. PHASING SHOWN IN DRAWINGS IS NOT INTENDED TO FULLY DESCRIBE ALL NECESSARY CONSTRUCTION PHASING, WHICH IS DETERMINED BY THE CONTRACTOR AS PART OF THEIR RESPONSIBILITIES. ANY SUCH PHASES DESCRIBED IN THE CONSTRUCTION DOCUMENTS ARE GENERAL AND ONLY INTENDED TO INDICATE A BROAD ORDER FOR THE SAKE OF DESCRIBING THE PROJECT. THE FOLLOWING LINETYPES MAY BE USED ON ANY DEVICE, EQUIPMENT, NOTE, LINE, SHAPE, ETC.

EXISTING  
DEMOLISH

NEW  
FUTURE

Issue Date: September 5, 2022

Revisions

NUMBER DESCRIPTION DATE



09/09/2022

CARL J. HOLDEN  
LICENSE # PE-2020016283

MECHANICAL GENERAL NOTES AND LEGEND

M000



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio


civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/T/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

**MECHANICAL PLAN NOTES:**

- M1 COORDINATE INSTALLATION OF EQUIPMENT, DUCTWORK, AND PIPING WITH ALL TRADES. DO NOT ROUTE DUCTWORK OR PIPING OVER ELECTRICAL PANELS AND EQUIPMENT.
- M2 ALL FULLY AND PARTIALLY EXPOSED SUPPLY SPIRAL AND RECTANGULAR DUCT SHALL BE INTERNALLY LINED AND FIELD PAINTED, COLOR BY ARCHITECT.
- M3 PROVIDE BUILDING BAS PANEL(S); QUANTITY OF PANELS TO BE DETERMINED BY CONTROL'S CONTRACTOR; COORDINATE LOCATIONS WITH ARCHITECT AND OTHER TRADES.
- M4 INSTALL BUILDING DIFFERENTIAL PRESSURE SENSOR, EXTEND LOW PORT TUBING UP THRU ROOF TO MATCH MANUFACTURER RECOMMENDATIONS/REQUIREMENTS.
- M5 REFRIGERANT PIPING IS SCHEMATIC, ACTUAL ROUTING AND SIZING OF REFRIGERANT LINES SHALL BE DETERMINED PER MANUFACTURER'S RECOMMENDATIONS.
- M7 ALL PIPING SHALL BE ROUTED AS HIGH AS POSSIBLE TO ALLOW MAXIMUM CLEARANCES BELOW.
- M8 COORDINATE PIPING, CONDUIT, AND DUCT ROUTINGS THROUGH EXPOSED AREAS TO CLEANLY ROUTE/GROUP TOGETHER. COORDINATE WITH ALL OTHER TRADES.
- M9 ROUTE SUPPLY/RETURN DUCT UP THROUGH ROOF, TRANSITION TO DUCT/RTU CONNECTION SIZE IN CURB, SEAL ROOF PENETRATION AIR AND WATER TIGHT.
- M10 ROUTE EXHAUST DUCT UP THROUGH ROOF, TRANSITION TO DUCT/ROOF CONNECTION SIZE IN CURB, SEAL ROOF PENETRATION AIR AND WATER TIGHT.
- M11 ROUTE REFRIGERANT PIPE UP THROUGH ROOF, SEAL ROOF PENETRATION AIR AND WATER TIGHT.
- M14 ROUTE DUCT UP INTO SOFFIT AND ELBOW OUT INTO SHOP SPACE.
- M15 DO NOT INSTALL ANY DUCTWORK OR PIPING BELOW 12'-6" AFF IN ROBOTICS FIELD.
- M16 INSTALL BOTTOM OF TRANSFER DUCT 12'-0" AFF. DUCT INTO SOFFIT AND INTO ELECTRICAL ROOM FOR TRANSFER AIR CIRCULATION.
- M18 INSTALL BOTTOM OF GRILLE AT 9'-6" AFF.
- M19 MOUNT TOP OF CRU 4" BELOW TOP OF LADDER RACK.
- M20 EXTEND DUCT THROUGH WALL TO DECK AND ELBOW DUCT UP TO PROVIDE TRANSFER AIR PATH FOR FAN.
- M21 INSTALL DUCTWORK/PIPING AWAY FROM ROOF HATCH/LADDER TO ENSURE ROOF ACCESS IS MAINTAINED.



1 HVAC LEVEL 1 PLAN - LSW  
3/16" = 1'-0"

**HENDERSON**  
ENGINEERS  
8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM

2150005255  
MO. CORPORATE NO. E-5580  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/16/2022



CARL J. HOLDEN  
LICENSE # PE-2020016283

**LSW - HVAC PLAN -  
LEVEL 1**

**M101-A**



LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086


architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

MECHANICAL PLAN NOTES:  
M13: INSTALL ALL SERVICEABLE ROOF MOUNTED EQUIPMENT AT  
MINIMUM 10'-0" AWAY FROM ROOF EDGE UNLESS  
SPECIFIED OTHERWISE.  
M27: REFER TO PLUMBING PLANS FOR GAS AND CONDENSATE  
PIPE SIZING.




1 MECHANICAL ROOF PLAN - LSW  
3/16" = 1'-0"

HENDERSON  
ENGINEERS  
8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM

2150005255  
MO. CORPORATE NO. E-8580  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/16/2022



CARL J. HOLDEN  
LICENSE # PE-2020016283

LSW - MECHANICAL  
PLAN - ROOF

M102-A



LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


owner:  
**Lee's Summit R-7 School**  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
**Multistudio**  
4200 Pennsylvania  
Kansas City, MO 64111  
816-931-6651  
multistudio.com

civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913-485-0318  
kaweng.com

structural engineer:  
**Bob D. Campbell & Company, Inc.**  
8343 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-emgs.com

NEPFT/Code:  
**Henderson Engineers**  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com



CONDENSING UNIT

SHUTOFF VALVES. OMIT IF THE CONDENSING UNIT IS EQUIPPED WITH INTEGRAL SHUTOFF VALVES

REFRIGERANT GAS LINE (SUCTION)

REFRIGERANT LIQUID LINE

PITCH REFRIGERANT GAS LINE TOWARDS THE INDOOR COIL AT 1 INCH PER 10 FEET.

GRADE OR ROOF

INSTALL RISER AT INDOOR COIL WITH TOP A MINIMUM OF 1 FOOT ABOVE THE LOWEST POINT.

FILTER-DRYER. OMIT IF THE CONDENSING UNIT IS EQUIPPED WITH AN INTEGRAL FILTER-DRYER IN THE LIQUID LINE AND THE PIPING CONFIGURATION IS WITHIN PARAMETERS PRESCRIBED BY THE MANUFACTURER FOR ITS USE. IF A FILTER-DRYER IS INSTALLED NEAR THE EVAPORATOR, THEN REMOVE ANY OTHER FILTER-DRYER THAT MAY EXIST.

SIGHT GLASS

THERMAL EXPANSION VALVE (TXV)

EXTERNAL EQUALIZER LINE (SEE NOTE 5)

EVAPORATOR COIL

LOCATE TXV SENSING BULB ON TOP OF PIPE FOR PIPE 7/8" AND SMALLER, 45° BELOW CENTERLINE OF PIPE FOR PIPE GREATER THAN 7/8".

NOTE 6.

- NOTES:
1. INSTALL REFRIGERANT PIPING AND COMPONENTS IN STRICT CONFORMANCE WITH ALL MANUFACTURER'S RECOMMENDATIONS AND REQUIREMENTS, WHICH SHALL TAKE PRECEDENT OVER INFORMATION PRESENTED IN THIS DETAIL.
  2. CONSULT THE INSTALLATION INSTRUCTIONS FOR THE MODEL RECOMMENDED BY THE MANUFACTURER.
  3. CONSULT THE MANUFACTURER REGARDING THE MODEL TO INSTALL A SOLENOID VALVE IN THE LIQUID LINE BETWEEN THE FILTER-DRIER AND SITE GLASS.
  4. INSTALL REFRIGERATION PIPE SIZES RECOMMENDED BY THE MANUFACTURER AND CONSULT THE MANUFACTURER REGARDING THE MINIMUM INSULATION THICKNESS BASED ON THE RECOMMENDED PIPE SIZES AND PIPING CONFIGURATION.
  5. PROVIDE EXTERNAL GAS LINE INSULATION TO PREVENT CONDENSATION AND EXTERNAL EQUALIZER LINES FOR ALL EVAPORATOR COILS EQUIPPED WITH A REFRIGERANT DISTRIBUTOR. MINIMUM EXTERNAL GAS LINE INSULATION SHALL BE 1" (25.4) MIN. TO 10" FEET.
  6. FILTER- DRIER MAY BE OMITTED IF NOT REQUIRED BY MANUFACTURER.
  7. SIGHT GLASS MAY BE OMITTED IF NOT REQUIRED BY MANUFACTURER AND SYSTEM IS LESS THAN 10'.

SCREEN, REFER TO SCHEDULE

ROOF HOOD

SECURE BASE TO CURB

TRANSITION DUCT TO CONNECT TO FAN CURB. EXTEND DUCTWORK OVER TOP OF CURB AND SECURE TO WOOD NAILER

ROOF DECK AND INSULATION PER ARCHITECTURAL DWGS

OVERSIZED GALVANIZED COVER

SECURE ROOF HOOD TO GALVANIZED COVER, SEAL CONNECTION WEATHER TIGHT

SEE NOTE 3

SEE NOTE 4

SECURE CURB TO ROOF WITH METHOD CONSISTENT WITH ROOF CONSTRUCTION

- NOTES:
1. ARRANGEMENT SHOWN IS SCHEMATIC, ADJUST TO SUIT FIELD CONDITIONS AND MEET LOCAL CODE REFERENCE ARCHITECTURAL DRAWINGS FOR ROOF CONSTRUCTION REQUIREMENTS.
2. REFERENCE ARCHITECTURAL DRAWINGS FOR ROOF CONSTRUCTION.
3. PREPARED INSULATED ROOF CURB WITH TREATED WOOD NALER, CANT, AND STEP AS REQUIRED TO ACCOMMODATE ROOF INSULATION.
4. IF DAMPER IS SPECIFIED IN EQUIPMENT SCHEDULE, INSTALL DAMPER AT BASE OF CURB AND SECURE FROM ABOVE TO ALLOW SERVICE THROUGH TOP OF CURB.

SEALING MATERIAL

SHEET METAL FLASHING RECEIVER

WOOD NAILER - OMIT WHERE WOOD NOT ALLOWED BY LOCAL BUILDING CODE

HIGH-DOMED, CARPED, GASKETED FASTENERS (APPROX. 18" O.C. AND MINIMUM TWO FASTENERS PER SIDE)

ROOF TOP UNIT BASE RAIL

SECURE UNIT TO CURB

SHEET METAL COUNTERFLASHING

ROOF CURB INSULATION

EXTENSION OF ROOF MEMBRANE ABOVE HEAD OF CANT (NOT SHOWN FOR CLARITY)

PROVIDE FLASHING AT ROOF CURB BASE

APPROX. 4"

ROOF MEMBRANE

CURB INSULATION - STRUCTURE

SECURE CURB TO STRUCTURE

FILL ENTIRE CURB FOOTPRINT, STARTING AT THE ROOF DECK, WITH 2" MINERAL WOOL OR SEMI-RIGID FIBERGLASS INSULATION; 2 LAYERS OF 5/8" SHEETROCK; 2" INSULATION; 2 LAYERS OF 5/8" SHEETROCK; AND 2" INSULATION.

CAULK OPENING AROUND DUCT

DUCT

ROOFTOP UNIT

CURB HEIGHT AS SPECIFIED

- NOTES:
1. CUT METAL DECKING TO ALLOW CURB INSTALLATION ON STEEL FRAMING. AFTER CURB IS SET IN PLACE, TRIM REMAINING METAL DECKING AND INSTALL WITHIN CURB. TACK WELD DECKING TO SUPPORT STEEL. DO NOT WELD INTERIOR DECKING TO ROOF CURB. PROVIDE ADDITIONAL CROSS FRAMING TO SUPPORT INTERIOR DECKING AND FILL MATERIAL AS REQUIRED.
  2. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR ROOF CURBS, ANCHORING AND SEISMIC/WIND RESISTANCE.

[illegible]

ANCHOR EQUIPMENT BASE PLATE TO CURB WITH LAG SCREWS

EQUIPMENT SUPPORT LEG (OR RAIL)

NEOPRENE WASHER

CAP FLASHING

BASE FLASHING

ROOF INSULATION

ROOFING

COUNTER FLASHING

ROOF STRUCTURE. SEE ARCHITECTURAL PLANS.

- NOTES
1. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR EQUIPMENT SUPPORTS, ANCHORING AND SEISMIC/WIND RESISTANCE.

CONDENSING UNIT

PROVIDE VIBRATION ISOLATION PER SPECIFICATIONS

SECURE CONDENSING UNIT TO EQUIPMENT SUPPORTS

UNIT MOUNTING HEIGHT SEE NOTE 3

ROOF

STRUCTURE

- NOTES:
1. SUPPORT AND ANCHOR OUTDOOR UNITS IN COMPLIANCE WITH LOCAL SEISMIC AND WIND RESTRAINT REQUIREMENTS.
  2. SEE MECHANICAL EQUIPMENT ANCHORS AND SUPPORT SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
  3. REFER TO THE EQUIPMENT SCHEDULE AND MANUFACTURER'S REQUIREMENTS FOR UNIT MOUNTING HEIGHT.

Diagram illustrating the installation of a Fan Coil Unit (FCU) showing connections to the ceiling and wall.

Labels and components shown:

- REFRIGERANT PIPING RE: COIL DETAILS
- CEILING
- FAN COIL UNIT
- NOTE 2' 0"
- AIRFLOW
- MANUFACTURER'S CONDENSATE PUMP (RE: EQUIPMENT SCHEDULE) AND CONDENSATE DRAIN CONNECTION (RE: PLUMBING DRAWINGS).
- WALL

- NOTES:
1. ARRANGEMENT SHOWN IS SCHEMATIC, ADJUST TO SUIT FIELD CONDITIONS AND MEET LOCAL CODE REQUIREMENTS.
  2. PROVIDE MINIMUM 3.5" OF CLEARANCE AT THE TOP OF THE UNIT.
  3. ATTACH FAN COIL UNIT TO MANUFACTURER'S PROVIDED INSTALLATION PLATE. MOUNT INSTALLATION PLATE TO WALL PER MANUFACTURER'S RECOMMENDATIONS.

The diagram is a schematic cross-section of a fan unit. It shows a central rectangular box representing the fan. On the left side, there is a transition from the fan's discharge to a duct of a larger size, indicated by a double-headed arrow. On the right side, there is a transition from the fan's inlet to a duct of a larger size, also indicated by a double-headed arrow. The fan unit is suspended from a structure above it by two vertical rods, one on each side. These rods are labeled as 'HANG UNIT FROM STRUCTURE WITH SPRING VIBRATION AND ALL-THREAD ROD. SEE NOTE 2.' The rods are connected to the fan unit by 'FLEX CONNECTOR' components. The entire assembly is labeled 'EXHAUST FAN'.

**NOTES:**

1. ARRANGEMENT SHOWN IS SCHEMATIC, ADJUST TO SUIT FIELD CONDITIONS AND MEET LOCAL CODE REQUIREMENTS.
2. FOR FANS 1 HP AND LESS, PROVIDE NEOPRENE RUBBER MOUNT HANGER (NR). FOR FANS LARGER THAN 1 HP, PROVIDE SPRING VIBRATION ISOLATION HANGER (SPNH).

12 FAN INLET  
NTS

- NOTES:**
1. ARRANGEMENT SHOWN IS SCHEMATIC, ADJUST TO SUIT FIELD CONDITIONS AND MEET LOCAL CODE REQUIREMENTS.
  2. FOR FANS 1 HP AND LESS, PROVIDE NEOPRENE RUBBER MOUNT HANGER (NR). FOR FANS LARGER THAN 1 HP, PROVIDE SPRING VIBRATION ISOLATION HANGER (SPNH).

The diagrams illustrate the correct and incorrect installation of a metal jacket over a pipe with insulation.

**Top Diagram (Correct Installation):**

- OVERLAP JACKETING A MINIMUM OF 1-1/2"**: The metal jacket is installed with the top lap facing down, ensuring a minimum overlap of 1-1/2 inches.
- BANDS TO SECURE INSULATION IN PLACE**: Bands are used to secure the insulation in place.
- PIPE**: The central pipe being jacketed.
- INSULATION**: The insulating material surrounding the pipe.
- RIVETS OR SCREWS AT SEAMS**: The metal jacket is secured with rivets or screws at the seams.
- METAL JACKET WITH TOP LAP FACING DOWN**: The metal jacket is installed with the top lap facing down.
- LONGITUDINAL JACKETING SEAMS POSITIONED AT 3 OR 9 O'CLOCK ONLY WITH TOP LAP FACING DOWN**: The longitudinal jacketing seams are positioned at 3 or 9 o'clock with the top lap facing down.
- INSULATION SEAM AT BOTTOM OR HORIZONTAL SEALED WITH ADHESIVE**: The insulation seam is at the bottom or horizontal and sealed with adhesive.
- METAL BAND OR BELT INSTALLED PER MANUFACTURER'S INSTRUCTIONS**: A metal band or belt is installed per the manufacturer's instructions.

**Bottom Diagram (Incorrect Installation):**

- PIPE**: The central pipe being jacketed.
- INSULATION**: The insulating material surrounding the pipe.
- METAL JACKET WITH TOP LAP FACING DOWN**: The metal jacket is installed with the top lap facing down.
- MINIMUM OF 1" BETWEEN FIRST BAND AND OVER LAPPING JOINT**: A minimum of 1 inch is required between the first band and the overlapping joint.

- 

- 
- THREADED EYE ROD
- STEEL TURNBUCKLE (TYP)
- THREADED STEEL ROD (TYP)
- REFER TO SPECIFICATIONS FOR REQUIREMENTS AND APPLICATION OF PIPE INSULATION, VAPOR BARRIER, PIPE SADDLE, HIGH DENSITY INSULATION INSERT, AND INSULATION SHEATH. (TYP)
- PIPE ROLLER HANGER (TYP)
- SWING JOINT
- ROLLER HANGER WITH SINGLE SUPPORT
- ROLLER HANGER WITH DOUBLE SUPPORT
- CLEVIS HANGER
- ADJUSTABLE BAND HANGER
- THE ADJUSTABLE BAND HANGER IS ONLY BE USED ON PIPING LESS THAN OR EQUAL TO 2 INCHES NOMINAL SIZE.


- ⑨ PIPE HANGERS DETAILS  
NTS

Issue Date: September 9, 2022

---

Revisions

NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/16/2022



CARL J. HOLDEN 09/15/2022  
LICENSE # PE-2020016283

## MECHANICAL DETAILS

# M201







LSR7 Robotics, GiC & Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

MECHANICAL SYMBOLS

NOTE: THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS, ABBREVIATIONS, ETC. ARE NECESSARILY USED ON THE DRAWINGS.

CONTROLS SYMBOLS AND NOMENCLATURE

	FLUE DAMPER (BOILERS)		HOT GAS REHEAT COIL		RISER DESIGNATION		MOTORIZED DAMPER
	BOILER		COOLING COIL		FIRE DAMPER		BACKDRAFT DAMPER
	COOLING TOWER		HEATING COIL		FIRE SMOKE DAMPER		VOLUME DAMPER
	CONDENSING UNIT		DAMPER - GENERIC BLADE TYPE		SMOKE DAMPER		HUMIDISTAT
	FLUID COOLER		DAMPER - OPPOSED BLADE TYPE		SMOKE DETECTOR		THERMOSTAT
	WATER-COOLED CHILLER		DAMPER - PARALLEL BLADE TYPE		SD (SD=Supply / RD=Return)		
	AIR-COOLED CHILLER		FLEXIBLE SENSING ELEMENT		BTU METER		PRESSURE SENSOR
	GENERIC HEAT EXCHANGER		AIRFLOW STATION		CARBON MONOXIDE SENSOR		POLLUTANT ALARM
	SHELL AND TUBE HEAT EXCHANGER		PUMP		CARBON DIOXIDE SENSOR		PULL STATION
	BASIN HEATER		FAN		CONTROL PANEL		REFRIGERANT LEAK SENSOR
	HEAT RECOVERY WHEEL		HUMIDIFIER		CURRENT CIRCUIT RELAY		SENSOR - GENERIC
			AIR FILTER		DIFFERENTIAL PRESSURE SENSOR		STATIC PRESSURE PORT
			3-WAY CONTROL VALVE		ELECTRIC METER		SWITCH
			2-WAY CONTROL VALVE		FLOW METER; FUEL METER		TEMPERATURE SENSOR
			AIR BYPASS DAMPER		FLOW SWITCH		WATER METER
			AIRFLOW MEASURING STATION		HUMIDITY SENSOR		
			DIRECT EXPANSION COOLING UNIT CONTROLLER				
			FURNACE BURNER CONTROLLER				
			SILICON-CONTROLLED RECTIFIER ELECTRIC HEATER CONTROL (MODULATING)				
			ELECTRIC HEATER CONTROLLER (ON/OFF)				
			ELECTRONIC COMMUTATED MOTOR				
			VARIABLE FREQUENCY DRIVE				
			MOTOR STARTER				
			LOW LIMIT TEMPERATURE CONTROLLER (FREEZE/STAT)				
			EMERGENCY PUSH BUTTON				

-X<>

NOT EQUAL TO

AI

ANALOG INPUT (MODULATING)

AO

ANALOG OUTPUT (MODULATING)

AV

ANALOG VIRTUAL (VALUE)

BI

BINARY INPUT (ON/OFF, OPEN/CLOSED, ETC)

BO

BINARY OUTPUT (ON/OFF, OPEN/CLOSED, ETC)

BV

BINARY VIRTUAL (VALUE)

BAS

BUILDING AUTOMATION SYSTEM

CHWS

CHILLED WATER SUPPLY

CHWR

CHILLED WATER RETURN

CMD

COMMAND

COM

COMMUNICATION LINK

CP

CONTROL PANEL

CV

CONTROL VALVE

CWS

CONDENSER WATER SUPPLY

CWR

CONDENSER WATER RETURN

DCW

DOMESTIC COLD WATER

DDC

DIRECT DIGITAL CONTROL

E/C

ELECTRICAL CONTRACTOR

EOA

ECONOMIZER OUTSIDE AIR

EQ

EQUALIZER

EM

EQUIPMENT MANUFACTURER

FAC

FIRE ALARM CONTRACTOR

FIP

FAIL IN POSITION

G

NATURAL GAS

HWS

HEATING WATER SUPPLY

HWR

HEATING WATER RETURN

HPWS

HEAT PUMP WATER SUPPLY

HPWR

HEAT PUMP WATER RETURN

LPS

LOW PRESSURE STEAM SUPPLY

LPC

LOW PRESSURE STEAM CONDENSATE

M/C

MECHANICAL CONTRACTOR

MIN

MINIMUM; MINUTES

MOA

MINIMUM OUTSIDE AIR

NC

NORMALLY CLOSED

NIA

NOT IN AUTO (IN HAND)

NO

NORMALLY OPEN

PID

PROPORTIONAL INTEGRAL DERIVATIVE

RA

RETURN AIR

REA

RELIEF/EXHAUST AIR

RH

RELATIVE HUMIDITY

SA

SUPPLY AIR

SCHE

AS SCHEDULED ON DRAWINGS

SPEC

SPECIFIED

SPT

SETPOINT

TBD

TO BE DETERMINED

TCC

TEMPERATURE CONTROLS CONTRACTOR

—/—

POWER WIRING

—/—

CONTROL WIRING

—/—

ETHERNET LAN WIRING

—/—

BAS COMMUNICATION WIRING

PROJECT DESIGN CONDITIONS - LSW/LSN

CLIMATE CONDITIONS				LEE'S SUMMIT MUNICIPAL, MO				BUILDING OPERATING HOURS:			
WEATHER STATION:								MONDAY - FRIDAY		TBD BY OWNER	
CLIMATE ZONE:				4A				SATURDAY		TBD BY OWNER	
HEATING (DB):				99.6%	4.7	'F		SUNDAY		TBD BY OWNER	
DESIGN HEATING CONDITIONS (DB):					0	'F		HOLIDAY		TBD BY OWNER	
HUMIDIFICATION (DPI HR/MCDB):				99.6%		'F	74.7	'F			
COOLING (DB/MCWB):				0.4%	96.4	'F	74.7	'F			
DESIGN COOLING CONDITIONS (DB/MCWB):					96.4	'F	74.7	'F			
DEHUMIDIFICATION (DPI HR/MCDB):				0.4%	79.9	'F	135.8	grlb	85.9	'F	

SPACE / UNIT DESCRIPTION	COOLING / DE-HUMIDIFICATION				HEATING				HUMIDIFICATION		ZONE VENTILATION RESET			SPACE OPERATING HOURS OCCUPIED / UNOCCUPIED				NOTES
	OCC	UNOCC	MAX RH %	MIN RH %	OCC	UNOCC	MIN RH %	MAX RH %	CONTROL METHOD	BASE	MAXIMUM	M-F	SAT	SUN				
GIC	75	80	60%	NA	70	60	NA	NA	CO2	400	900	TBD	TBD	TBD	A-C			
ROBOTICS	75	80	60%	NA	70	60	NA	NA	OCC	400	900	TBD	TBD	TBD	A-C			

NOTES:

ZONE LEVEL VENTILATION RESET / DEMAND CONTROL VENTILATION (DCV) CONTROL METHOD: CARBON DIOXIDE SENSOR (CO2).

ZONE LEVEL SET POINT CONDITIONS SHALL BE AS SCHEDULED UNLESS OTHERWISE SCHEDULED OR NOTED ON THE DRAWINGS FOR ROOM SPECIFIC SPACE CONDITIONS.

ZONE LEVEL OCCUPANCY HOUR SCHEDULE SHALL BE PER BUILDING OPERATING HOURS UNLESS OTHERWISE SCHEDULED.

POINTS LIST - GLOBAL BUILDING MONITORING - LSW/LSN

POINT ID	DESCRIPTION	POINT TYPE	UNITS	ACCURACY	TRENDING INTERVAL	ENERGY DASHBOARD DISPLAY	STATUS ALARM	ALARM RANGE	NOTES
BUILDING SENSORS									
BDP	BUILDING DIFFERENTIAL PRESSURE	AI	IN. W.G.	SPEC	15 MIN.	X	X	-0.15 > BDP > +0.20	A, B
OAC02	OUTSIDE AIR CARBON DIOXIDE LEVEL	AI	PPM	SPEC	15 MIN.				
OAT	OUTSIDE AIR DRY BULB TEMPERATURE	AI	'F	SPEC	15 MIN.	X			
OAH	OUTSIDE AIR RELATIVE HUMIDITY	AI	%	SPEC	15 MIN.	X			

NOTES:  
A. INITIAL SETPOINT SHALL BE 0.05 IN. W.G. COORDINATE FINAL SETPOINT AT BUILDING STARTUP.  
B. APPLY A MOVING TIME AVERAGE TO BUILDING DIFFERENTIAL PRESSURE USING A SLIDING 5-MINUTE WINDOW TO REDUCE DAMPER AND FAN CONTROL FLUCTUATIONS.

SEQUENCE OF OPERATIONS  
MISCELLANEOUS EQUIPMENT

This sequence of operations is organized into the following main categories:  
safeties, overrides and interlocks, and component control loops  
either enable or disable the various modes of operation. If a mode of operation is not listed within a component control loop section then that mode of operation has no direct influence on the operation of the component. The control setpoint reset section describes the logic and reference variables that will be used to reset control setpoints to a new value within its reset range. The safeties and interlocks section outlines the hardwired interlocks that will be required to meet life safety requirements. Safeties and interlocks take precedence over all other control strategies outlined in this document. The control responses of each component for the various modes of operation are described in the component control loop sections.

The sequence of operations, the points list and control diagrams shall be used to provide a complete description of the control philosophy for the controlled equipment. Individual setpoint values, reset ranges, and alarm action levels are listed in the points list. Components and control sensor locations are graphically depicted on the control diagram.

TRANSFER FANS (TF-XX)  
OPERATING MODES:

OCCUPIED MODE:  
The units shall be in occupied mode per the project design conditions schedule shown on the control drawings.

UNOCCUPIED MODE:  
The units shall be in unoccupied mode for all periods not included in the occupied hours of operation.

COMPONENT CONTROL LOOPS  
FAN CONTROL - CONSTANT VOLUME BMS SCHEDULED

When in Occupied Mode:  
The fan shall start upon an increase in room temperature above setpoint as measured by Z-T. When space temperature drops below setpoint, the fan shall stop.  
If space temperature rises 10 degrees F above setpoint, an alarm shall be generated.

When in Unoccupied Mode:  
The fan shall operate as it does in occupied mode.

EXHAUST FANS (EF-XX)  
OPERATING MODES:

OCCUPIED MODE:  
The units shall be in occupied mode per the project design conditions schedule shown on the control drawings.

UNOCCUPIED MODE:  
The units shall be in unoccupied mode for all periods not included in the occupied hours of operation.

COMPONENT CONTROL LOOPS  
FAN CONTROL - VARIABLE VOLUME FLOW OFFSET

When in Occupied Mode:  
The fan shall energize and slowly ramp to the initial minimum fan speed determined during system startup. The fan VFD shall vary to maintain the exhaust airflow setpoint as measured by the exhaust airflow sensor (EA-AF). The exhaust airflow setpoint shall be calculated as the RTU measured outdoor airflow minus the exhaust fan building differential offset (EF-BD).  
Exhaust Airflow Setpoint = RTU (OA-AF) - (EF-BD).

When in Unoccupied Mode:  
The fan shall be OFF.

SPLIT SYSTEM ROOM AC UNITS (CRU-XX)

COMPONENT CONTROL LOOPS

The space temperature sensor shall cycle the indoor unit and condensing unit as required to maintain the space temperature as indicated by the space temperature sensor (Z-T).  
If space temperature rises 5 degrees F above setpoint, an alarm shall be generated.


DOMESTIC HOT WATER HEATERS

The BAS shall monitor the domestic hot water leaving water temperature. Should the water temperature increase above 115F, an alarm shall be generated.


DOMESTIC HOT WATER RECIRCULATION SYSTEM

The BAS shall monitor the domestic hot water recirculation system. Should the domestic hot water pump error or malfunction, an alarm shall be generated. The pump shall be continuously operated between the hours of 5am and 7pm (adj.).


1 BUILDING GLOBAL WEATHER MONITORING STATION  
NONE




4 EXHAUST FANS (EF-XX)  
NTS




6 DOMESTIC WATER HEATER  
NTS



2 BUILDING DIFFERENTIAL PRESSURE SENSOR  
NONE



5 SPLIT SYSTEM ROOM AC UNITS (CRU-XX)  
NTS



MISCELLANEOUS CONTROL POINTS - LSW/LSN							
POINT ID	DESCRIPTION	POINT TYPE	DEFAULT SETPOINT	FAIL POSITION	STATUS ALARM	ALARM RANGE	NOTES
EXHAUST FANS (EF-XX)							
EF-C	EXHAUST FAN COMMAND (START/STOP)	BO					A
EA-AF	EXHAUST AIR FLOW QUANTITY	AI	CALC.				A,E
EF-BD	EXHAUST FAN BUILDING DIFFERENTIAL OFFSET	AV	100 CFM				A,B,E
TRANSFER FAN (TF-XX)							
Z-T	ZONE TEMPERATURE	AI			X	Z-T < STPT-15 DEG F	A
TF-C	TRANSFER FAN COMMAND (START/STOP)	BO	80 F		X	Z-T > 90 DEG F	A
TF-ST	TRANSFER FAN COMMAND (START/STOP)	BI			X	TF-C-X=ON, TF-ST-X=OFF	A
DOMESTIC HOT WATER RECIRCULATING PUMP							
DHW-T	DOMESTIC HOT WATER RETURN TEMPERATURE	AI					
DHW-T	DOMESTIC HOT WATER SUPPLY TEMPERATURE	AI	110 DEG F		X	DHW-T > 115 DEG F	A, D
HWCP-C	HOT WATER RECIRCULATING PUMP COMMAND (START/STOP)	BO			X	HWCP-C=ON, HWCP-ST=OFF	A, C
HWCP-ST	HOT WATER RECIRCULATING PUMP STATUS (CT)	BI					
WATER HEATER MONITORING							
DHW-T	DOMESTIC HOT WATER SUPPLY TEMPERATURE	AI	110 DEG F		X	DHW-T-X > 115 DEG F	A, D

NOTES:  
A. POINTS APPLY TO MULTIPLE UNITS. SEE CONTROL DIAGRAMS FOR NUMBER OF UNITS.  
B. DETERMINE SETPOINT DURING TESTING AND BALANCING. COORDINATE WITH THE TEST AND BALANCE CONTRACTOR.  
C. ALARM TO SIGNAL AFTER 30 SECOND TIME DELAY (ADJ.).  
D. ALARM TO SIGNAL AFTER 10 MINUTE TIME DELAY (ADJ.).  
E. POINT SHALL BE ADJUSTABLE.



09/22/2022  
CARL J. HOLDEN  
LICENSE # PE-2020016283



SEQUENCE OF OPERATIONS  
SINGLE ZONE VARIABLE AIR VOLUME  
ROOFTOP UNIT (RTU-1W/N)

This sequence of operations is organized into the following main categories: operating modes; control setpoint resets; safeties, overrides and interlocks; and component control loops. The operating modes describe the criteria that either enable or disable the various modes of operation. If a mode of operation is not listed within a component control loop section then that mode of operation has no direct influence on the operation of the component. The control setpoint reset section describes the logic and reference variables that will be used to reset control setpoints to a new value within its reset range. The safeties, overrides, and interlocks section outlines the hardwired interlocks that are required to meet life safety requirements. Safeties and interlocks take precedence over all other control strategies outlined in this document. The control responses of each component for the various modes of operation are described in the component control loop sections. Setpoints shall be adjustable (adj.) as noted.

The sequence of operations, the points list and control diagrams shall be used to provide a complete description of the control philosophy for the controlled equipment. Individual setpoint values, reset ranges, and alarm action levels are listed in the points list. Components and control sensor locations are graphically depicted on the control diagram. The controls contractor shall be responsible for coordinating any necessary time delay setpoints to establish stable system operation.

GENERAL DESCRIPTION

The rooftop unit described by this sequence of operations consist of a 100% OA DX/Gas RTU with modulating supply fan, modulating powered exhaust, and static core energy recovery device. The RTU shall be provided with refrigeration only and control to its own internal safeties and time delays. Controls shown in the diagram, points list, and described in the sequence are intended to be provided by controllers, sensors, and programming to achieve the specified sequence of operations indicated.

OPERATING MODES

OCCUPIED MODE:

The unit shall be in occupied mode per the Project Design Conditions Schedule shown on the control drawings.

UNOCCUPIED MODE:

The unit shall be in unoccupied mode for all periods not included in the occupied hours of operation. Overrides of unoccupied schedule are defined at the zone level control.

OCCUPIED STANDBY MODE:

The unit shall be in occupied standby mode when the associated zone is scheduled to be occupied and an occupant sensor indicates zero population within the zone subject to a 5-minute (adj.) delay. The unit shall exit occupied standby mode when occupancy is detected.

COOLING MODE:

The unit shall be in cooling mode when the outside air temperature (OAT) rises above the outside air cooling enable setpoint (OAT-C)

HEATING MODE:

The unit shall be in heating mode when the outside air temperature (OAT) falls below the outside air heating enable setpoint (OAT-H)

VENTILATION ONLY MODE:

The unit shall be in ventilation only mode when the outdoor air temperature is between the outdoor air cooling enable (OAT-C) and outdoor air heating enable (OAT-H) setpoints.

DEHUMIDIFICATION MODE:

The unit shall be in dehumidification mode when the outside air dewpoint (OADP) is greater than the setpoint. The unit shall exit dehumidification mode when the outside air dewpoint (OADP) is less than its setpoint minus the outside air dewpoint deadband (OADP-DB). Dehumidification mode shall take priority over other modes.

ENERGY RECOVERY COOLING MODE- TEMPERATURE ENABLED:

The unit shall be in energy recovery cooling mode when the outside air temperature (OAT) is greater than the return air temperature (RAT).

ENERGY RECOVERY HEATING MODE- TEMPERATURE ENABLED:

The unit shall be in energy recovery heating mode when:  
The outside air temperature (OAT) is lower than the return air temperature (RAT) and the outside air temperature (OAT) is colder than the supply air temperature (SAT) setpoint).

ENERGY RECOVERY FROST PREVENTION MODE- TEMPERATURE ENABLED:

The unit shall be in energy recovery frost prevention mode when the heat exchanger exhaust leaving air temperature (HX-LAT) falls below setpoint.  
The unit shall be in energy recovery frost prevention mode when the outside air temperature (OAT) is below 30 degrees F (adj).

CONTROL SETPOINT RESETS

SUPPLY AIR TEMPERATURE RESET - DIRECT OUTSIDE AIR RESET:

The supply air temperature (SAT) setpoint shall linearly reset within the range as listed in the "setpoint reset range" column of the points list based on the outside air temperature (OAT) according to the following schedule:

(OAT)	(SAT)
OAT-C setpoint	minimum value of the SAT setpoint range
OAT-H setpoint	maximum value of the SAT setpoint range

VENTILATION RESET (CO2):

The outside airflow CFM (OA-AF) setpoint shall be reset between the minimum and maximum values subject to the associated zone level CO2 value as scheduled in the Project Design Conditions Schedule.

The airflow setpoint shall be at its maximum value when the associated zone CO2 sensor detects levels at or above the maximum CO2 range.

The airflow setpoint shall be at its minimum value when the associated zone CO2 sensor detects levels at or below the minimum CO2 range.

The airflow setpoint shall vary between its minimum and maximum setpoint range linearly as the associated zone CO2 sensor varies between is minimum and maximum value.

SAFETIES, OVERRIDES AND INTERLOCKS

SMOKE DETECTOR INTERLOCK:

The unit shall be disabled via hard wired interlock on activation of a system smoke detector. Display smoke detector relay status (normal or alarm) at the BAS front end.

COMPONENT CONTROL LOOPS

SUPPLY FAN CONTROL - SINGLE ZONE VARIABLE VOLUME:

When the HOA switch is in hand position, the variable speed supply fan shall operate at a speed set manually by the operator at the user interface of the drive.

When the HOA switch is in off position, the fan shall be off.

When the HOA switch is in auto position, the variable speed supply fan shall operate subject to the unit enable signal, and unit operating modes.

When in Occupied Mode:

The fan shall energize and slowly ramp to the initial minimum fan speed determined during system startup. Minimum fan speed shall be established during balancing.

The fan VFD shall modulate to maintain the design outside airflow CFM (OA-AF) as measured by the outside airflow sensor.

When in Occupied Standby Mode:

The fan shall be OFF.

When in Unoccupied Mode:

The fan shall be OFF. On an override signal from the zone level, the fan shall operate as in occupied mode until the override is removed.

When in Pre-Occupancy Purge Mode:

The fan shall operate as in occupied mode.

RELIEF - EXHAUST FAN (REF) - BUILDING PRESSURE SENSOR CONTROL

When in Occupied Mode:

The fan shall be ON. When the building differential pressure (BDP) exceeds setpoint, the fan shall energize and slowly ramp to the initial minimum fan speed determined during system startup. The fan VFD speed shall vary to maintain the building differential pressure (BDP) setpoint.

When in Unoccupied Mode:

The fan shall be OFF.

When in Pre-Occupancy Purge Mode:

The fan shall operate as in occupied mode.

OUTSIDE AIR DAMPER (OA)

When in Occupied Mode:

The damper shall be open.

When in Unoccupied Mode:

The damper shall close after the supply fan is off and a time delay.

When in Pre-Occupancy Purge Mode:

The damper shall be open.

FILTER MONITORING

When in All Modes:

The controller shall monitor the differential pressure across each filter bank and shall provide a signal when the setpoint is exceeded.

ENERGY RECOVERY BYPASS DAMPERS

The supply and exhaust bypass dampers shall be linked together on a common actuator.

When in Occupied Mode:

The dampers shall be open unless unit is in one of the following modes.

When in Ventilation Mode

The dampers shall be open. This takes priority over other energy recovery modes listed below.

When in Energy Recovery Cooling Mode:

The dampers shall be closed.

When in Energy Recovery Heating Mode:

The dampers shall modulate to maintain the heat exchanger leaving air temperature (HX-SAT) setpoint.

When in Energy Recovery Frost Prevention Mode:

Capacity modulation: The energy recovery bypass dampers shall modulate to maintain the heat exchanger exhaust leaving air temperature (HX-LAT) setpoint.

When in Unoccupied Mode:

The dampers shall be open.

On an override signal from the zone level the dampers shall operate as in occupied mode until the override is removed.

HEATING COIL- GAS MODULATED

When in Occupied Mode:

When in Ventilation Only Mode:

The coil shall be OFF.

When in Cooling Mode:

The coil shall be OFF.

When in Heating Mode:

The controller shall modulate the heating to maintain the supply air temperature setpoint (SAT).

When in Dehumidification Mode:

The coil shall be OFF.

When in Unoccupied Mode:

The coil shall be OFF.

On an override signal from the zone level the coil shall operate as in occupied mode until the override is removed.

COOLING COIL DX STAGED + VARIABLE CONTROL (MULTIPLE COMPRESSORS)

When in Occupied Mode:

When in Ventilation Only Mode:

The compressors shall be OFF.

When in Cooling Mode:

The variable compressor shall modulate in coordination with the constant speed compressors (subject to the manufacturer's standard safeties) to maintain the supply air temperature setpoint (SAT).

When in Heating Mode:

The compressors shall be OFF.

When in Dehumidification Mode:

The variable compressor shall modulate in coordination with the constant speed compressors (subject to the manufacturer's standard safeties) to maintain the cooling coil leaving air temperature (CC-LAT).

The variable compressor represents the primary stage of cooling and shall vary continuously between minimum capacity and 100% capacity to maintain the supply air set point temperature. When the supply air temperature setpoint cannot be maintained and the variable compressor is at 100%, then the constant speed compressor shall be energized and the variable compressor shall return to minimum speed and modulate to maintain the supply air setpoint. Units with subsequent stages of cooling shall follow a similar loading and unloading logic.

When in Unoccupied Mode:

The compressors shall be OFF.

On an override signal from the zone level the compressors shall operate as in occupied mode until override is removed.

REHEAT COIL- DX HOT GAS REHEAT

When in Occupied Mode:

When in Ventilation Only Mode:

The coil shall be OFF.

When in Cooling Mode:

The coil shall be OFF.

When in Heating Mode:

The coil shall be OFF.

When in Dehumidification Mode:

The manufacturer onboard controller shall control the hot gas reheat coil valve to maintain the supply air temperature setpoint (SAT).

When in Unoccupied Mode:

The coil shall be OFF.

On an override signal from the zone level the coil shall operate as in occupied mode until the override is removed.

Issue Date: September 5, 2022

Revisions

NUMBER DESCRIPTION DATE

MECHANICAL

CONTROLS

M402



LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


owner: **Lee's Summit R-7 School**  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect: **Multistudio**  
4200 Pennsylvania  
Kansas City, MO 64111  
913.231.3333

<b>Kaw Valley Engineering</b>	<b>Bob D. Campbell &amp; Company,</b>
14700 West 114th Terrace	4338 Belleview
Lenexa, KS 66215	Kansas City, MO 64111
913.485.0318	816.531.4144
kveng.com	www.bdc-engrs.com

8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214

816.742.5000  
www.hendersonengineers.com



POINT ID	DESCRIPTION	POINT TYPE	DEFAULT SET POINT	SET POINT RESET RANGE	FAIL POSITION	STATUS ALARM	ALARM RANGE	NOTES
GLOBAL VALUES								
BDP	BUILDING DIFFERENTIAL PRESSURE	AV						A
OAT	OUTSIDE AIR TEMPERATURE	AV						A
OAHI	OUTSIDE AIR HUMIDITY	AV						A
OACO2	OUTSIDE AIR CO2 LEVEL	AV						A
AIR SENSING								
SAT	SUPPLY AIR TEMPERATURE	AI	55 F CLG, 90 F HTG	52 - 65 F CLG		X	50 F > SAT > 100 F	D
RAT	RETURN AIR TEMPERATURE	AI						
RAH	RETURN AIR HUMIDITY	AI	50 PCT	30-65 PCT		X	15RH > RAH >65RH	D
MAT	MIXED AIR TEMPERATURE	AI	55 F	52 - 65 F CLG				D
CC-IAT	COOLING COIL LEAVING AIR TEMPERATURE	AI	SCHED			X	50 F > CC-IAT > 100 F	D
OA-AF	OUTSIDE AIR FLOW QUANTITY ASSOL. MIN/ MIN(CFM)	AI	SCHED			X	MCA-AF < SCHED - 15%	D
ZONE LEVEL SENSORS								
Z-T	ZONE TEMPERATURE	AI	SCHED					C, D
Z-OR	MANUAL OCCUPANCY OVERRIDE	BI	2 HOURS					D
Z-T-DB	ZONE TEMPERATURE	BV	5 F	-2.5 F < Z-T < +2.5 F				D
Z-CO2	ZONE CO2	AI	SCHED				Z-CO2 > SPT	C, D
SUPPLY FAN								
SF-COM	SUPPLY FAN VFD COMMUNICATION	COM						
SF-C	SUPPLY FAN COMMAND (START/STOP)	BO						
SF-CO	SUPPLY FAN CONTROL OUTPUT - SPEED (PERCENT)	AO		SCHED				
SF-ST	SUPPLY FAN STATUS	BI				X	SF-ST <=> SF-C	
SF-FLT	SUPPLY FAN VFD FAULT	BI				X	COMMON ALARM	
RELIEF-EXHAUST FAN								
REF-COM	RELIEF-EXHAUSTFAN VFD COMMUNICATION	COM						
REF-C	RELIEF-EXHAUST FAN COMMAND (START/STOP)	BO						
REF-CO	RELIEF-EXHAUST FAN CONTROL OUTPUT - SPEED (PERCENT)	AO		SCHED.				
REF-ST	RELIEF-EXHAUST FAN STATUS	BI				X	REF-ST <=> REF-C	
REF-FLT	RELIEF-EXHAUST FAN VFD FAULT	BI				X	COMMON ALARM	
RETURN AIR DAMPER (MODULATING)								
RD-CO	RETURN AIR DAMPER CONTROL OUTPUT	AO				NO		
MINIMUM OUTSIDE AIR DAMPER (MODULATING)								
OD-CO	OUTSIDE AIR DAMPER CONTROL OUTPUT	AO				NC		
FILTERS								
DF-SAM	DIRTY FILTER INDICATION (SA MAIN FILTER)	BI	SCHED.			X	ON ACTIVATION	D
COOLING COIL - DX MODULATING AND BINARY STAGES								
DX-M-CO	DX MODULATING COMPRESSOR CONTROL OUTPUT	AO						J
DX-M-ST	DX MODULATING COMPRESSOR STATUS	AI				X	DX-M-ST <=> DX-M-CO	J
DX-C-X	DX COMPRESSOR STAGE "X" COMMAND	BO						J
DX-ST-X	DX COMPRESSOR STAGE "X" STATUS	BI				X	DX-ST-X <=> DX-C-X	J
HEATING COIL - GAS FURNACE MODULATING								
HIS-CO	GAS FURNACE HEAT MODULATION CONTROL OUTPUT	AO						
FIRE ALARMSMOKE DETECTORS								
SD	SMOKE DETECTOR STATUS	BI				X	ON ACTIVATION	K
ALL POINTS SHOWN SHALL BE PROVIDED BY BAS CONTRACTOR UNLESS NOTED OTHERWISE.								
NOTES:								
A. DISPLAY VALUE WITH AHU GRAPHIC AT BAS FRONT-END. REFERENCE GLOBAL BUILDING MONITORING SCHEDULE FOR CONTROL POINT.								
C. REFERENCE PROJECT DESIGN CONDITIONS SCHEDULE FOR SETPOINT.								
D. POINT SHALL BE ADJUSTABLE.								
J. COORDINATE NUMBER OF STAGES FOR CONTROL WITH EQUIPMENT FURNISHED.								
K. DEVICE AND RELAY FROM FIRE ALARM SYSTEM PROVIDED BY DIVISION 28. DISPLAY DETECTOR RELAY STATUS (NORMAL/ALARM) AT BAS FRONT-END.								

Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------

---



CARL J.

★ 11/24 ★

PR NUMBER BR



00/00/0000

CARL J. HOLDEN

LICENSE # PE-2020016283

---

## MECHANICAL

## CONTROLS

M4402

## IV403

---



# ELECTRICAL SYMBOLS

THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS OR ABBREVIATIONS ARE USED.

## STANDARD MOUNTING HEIGHTS

AUDIBLE APPLIANCE (CENTERLINE)	84"
ALARM (TOP OF DEVICE)	48"
ANNUNCIATOR PANEL (DISPLAY)	48"
CONTROLS (TOP OF DEVICE)	48"
DATA WALL OUTLET	48"
EXIT SIGNS (WALL MOUNTED)	SAME AS ADJACENT DEVICE, UNO
FIRE ALARM ANNUNCIATOR PANEL (TOP OF DISPLAY)	60"
FIRE ALARM BELL (EXTERIOR) (CENTERLINE)	120"
FIRE ALARM CONTROL PANEL/UNIT (TOP OF DISPLAY)	60"
INTERCOM (TOP OF DEVICE)	48"
PULL STATION (TOP OF DEVICE)	48"
RECEPTACLE	18"
RECEPTACLE (ABOVE COUNTER)	*6" ABOVE BACKSPASH/COUNTER, 40" MAX
RECEPTACLE (CLOCK/CENTERLINE)	84"
RECEPTACLE (EQUIPMENT ROOMS) (TOP OF DEVICE)	84"
RECEPTACLE (EXTERIOR)	24"
RECEPTACLE (GARAGES)	24"
REMOTE INDICATING LIGHT (EQUIPMENT ROOMS) (TOP OF DEVICE)	48"
REMOTE INDICATING LIGHT (FINISHED AREAS)	CEILING
SAFETY SWITCH (TOP OF DEVICE)	48"
STARTER (TOP OF DEVICE)	48"
SWITCH (TOP OF DEVICE)	48"
TELEPHONE WALL OUTLET (TOP OF DEVICE)	48"
TELECOMMUNICATIONS BACKBOARD	48"
TELEVISION OUTLET	REFER TO ARCH
VISIBLE APPLIANCE (CENTERLINE)	84"

INSTALL OUTLET BOXES AT THE MOUNTING HEIGHTS SHOWN ABOVE UNO IN THE CONSTRUCTION DOCUMENTS. MOUNTING HEIGHTS LISTED ABOVE, OR ELSEWHERE IN THE CONSTRUCTION DOCUMENTS, ARE AFF OR AFG TO BOTTOM OF OUTLET BOX. UNO, ALL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH CURRENT ADA AND LOCAL REQUIREMENTS.

## ABBREVIATIONS

AF	AMPERE FUSE SIZE	MCC	MOTOR CONTROL CENTER
AFB	ABOVE FINISHED CEILING	MFR	MANUFACTURER
AFD	ABOVE FINISHED FLOOR	MIN	MINIMUM
AFH	ABOVE FINISHED GRADE	NLO	MAIN LUGS ONLY
AFJ	AUTHORITY HAVING JURISDICTION	NLV	MAGNETIC LOW-VOLTAGE
AHU	AIR HANDLING UNIT	NOCOP	MAXIMUM OVERCURRENT PROTECTION
AIC	AMPERE INTERRUPTING CAPACITY	MTD	NOT APPLICABLE
AS	AMPERE SWITCH SIZE	NA	NON-FUSED
AT	AMPERE TRIP SETTING	NL	NIGHT LIGHT (24HR ON)
ATS	AUTOMATIC TRANSFER SWITCH	NRTL	NATIONALLY RECOGNIZED TESTING LABORATORY
AV	AUDIO VISUAL	NTS	(CSA, ETL, NSF, UL)
BAS	BUILDING AUTOMATION SYSTEM	OS	OCCUPANCY SENSOR
BKR	BREAKER	PART	PARTIAL CIRCUT
C	CATEGORY	PHIO	PHASE
CAT	CABLE TELEVISION SYSTEM	PINL	PANEL
CCTV	CLOSED CIRCUIT TELEVISION	PNLB	PANELBOARD
CD	CANDELA	PT	POTENTIAL TRANSFORMER
CKT	CIRCUIT	QTY	QUANTITY
CODE	APPLICABLE CODE ADOPTED BY JURISDICTION	R/REL	RELOCATE
CT	CURRENT TRANSFORMER	RCPT	RECEPTACLE
CTR	CENTER	RLA	RUNNING LOAD AMPS
CVD	CUMULATIVE VOLTAGE DROP	RTU	ROOFTOP UNIT
DDEMO	DEMOLITION	SCCR	SHORT-CIRCUIT CURRENT RATING
DDPT	DOUBLE-THROW	SD	SMOKE DUCT DETECTOR
DPST	DOUBLE-POLE, SINGLE-THROW	SF	SQUARE FEET
ET/REX	EXISTING TO REMAIN	SPDT	SINGLE-POLE, DOUBLE-THROW
EC	ELECTRICAL CONTRACTOR	SPST	SINGLE-POLE, SINGLE-THROW
EF	EXHAUST FAN	SSBJ	SUPPLY-SIDE BONDING JUMPER
EM	EMERGENCY	ST	SHUNT TRIP
EMS	ENERGY MANAGEMENT SYSTEM	SWBD	SWITCHBOARD
ELV	ELECTRONIC LOW-VOLTAGE	SWGR	SWITCHGEAR
EW	ELECTRIC WATER COOLER	TBB	TELECOMMUNICATIONS BONDING BACKBONE
FAAP	FIRE ALARM ANNUNCIATOR PANEL	TBD	TO BE DETERMINED
FACP	FIRE ALARM CONTROL PANEL	TGB	TELECOMMUNICATIONS GROUND BUS BAR
FCA	FAULT CURRENT AMPS AVAILABLE	TL	TWISTLOCK
FCU	FAN COIL UNIT	TMGB	TELECOMMUNICATIONS MAIN GROUND BUS BAR
FL	FINISHED FLOOR	TXFMR	TRANSFORMER
FLA	FULL LOAD AMPS	TY	TYPE
FLR	FLOOR	U/F	UNDERFLOOR
GC	GENERAL CONTRACTOR	UG	UNDERGROUND
GEC	GROUNDING ELECTRODE CONDUCTOR	UIS	UNDERINSULATED
GES	GROUNDING ELECTRODE SYSTEM	UH	UNIT HEATER
GFR	GROUND FAULT RELAY	UNO	UNLESS NOTED OTHERWISE
G	GROUND	UPS	UNINTERRUPTIBLE POWER SUPPLY
IG	ISOLATED GROUND	VD	VOLTAGE DROP
ISC	SHORT CIRCUIT CURRENT	VFD	VARIABLE FREQUENCY DRIVE
JUB-BOX	JUNCTION BOX	VS	VACUANCY SENSOR
LF	LINEAR FEET	W	WIRE
LRA	LOCKED ROTOR AMPS	W/	WITH
LTGLTS	LIGHTING LIGHTS	WP	WEATHER PROOF
MAU	MAKE-UP AIR UNIT	WR	WEATHER RESISTANT
MAX	MAXIMUM	WT	WATERTIGHT
MCA	MINIMUM CIRCUIT AMPACITY	XP	EXPLOSION PROOF
MCB	MAIN CIRCUIT BREAKER		

## LINE TYPE LEGEND

THROUGHOUT THE DRAWINGS DIFFERENT LINE TYPES ARE USED IN COMBINATION WITH THE SYMBOLS TO INDICATE THE STATUS OF ITEMS AS EXISTING, TO BE DEMOLISHED, TO BE INCLUDED AS PART OF NEW WORK AND OTHER ITEMS WHICH ARE ANTICIPATED TO BE PROVIDED IN THE FUTURE. THE STATUS OF ITEMS USING THESE LINE TYPES ARE RELATIVE TO THE VIEW IN WHICH THEY APPEAR. PHASING SHOWN IN DRAWINGS IS NOT INTENDED TO FULLY DESCRIBE ALL NECESSARY CONSTRUCTION PHASING, WHICH IS DETERMINED BY THE CONTRACTOR AS PART OF THEIR RESPONSIBILITIES. ANY SUCH PHASING DESCRIBED IN THE CONSTRUCTION DOCUMENTS ARE GENERAL AND ONLY INTENDED TO INDICATE A BROAD ORDER FOR THE SAKE OF DESCRIBING THE PROJECT. THE FOLLOWING LINE TYPES MAY BE USED ON ANY DEVICE, EQUIPMENT, NOTE, LINE, SHAPE, ETC.

EXISTING	ARTICLE 700 OR LIFE SAFETY
DEMOLISH	ARTICLE 701 OR CRITICAL / EQUIPMENT BRANCH
NEW	
FUTURE	ARTICLE 702 OR OPTIONAL

## APPLICABLE ELECTRICAL CODES:

NOTE: PROJECT IS DESIGNED IN COMPLIANCE WITH THE FOLLOWING CODES. THIS IS NOT AN EXHAUSTIVE LIST. PROJECT SHALL COMPLY WITH ALL APPLICABLE CODES, STANDARDS AND LOCAL REQUIREMENTS. REFER TO THE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

ELECTRICAL CODE: 2017 NATIONAL ELECTRICAL CODE, (NFPA 70)  
BUILDING CODE: 2018 INTERNATIONAL BUILDING CODE  
ENERGY CODE: N/A

ANNOTATION	
MECHANICAL OR FIRE PROTECTION PLAN NOTE CALLOUT	
PLUMBING PLAN NOTE CALLOUT	
ELECTRICAL OR FIRE ALARM PLAN NOTE CALLOUT	
TECHNOLOGY PLAN CALLOUT	
PLUMBING EQUIPMENT DESIGNATION, (CONTRACTOR FURNISHED AND INSTALLED). REFER TO PLUMBING FIXTURE OR EQUIPMENT SCHEDULES	
EQUIPMENT DESIGNATION (OWNER FURNISHED, CONTRACTOR INSTALLED)	
EQUIPMENT DESIGNATION (CONTRACTOR FURNISHED AND INSTALLED UNLESS NOTED OTHERWISE)	
CONNECTION POINT OF NEW WORK TO EXISTING	
DETAIL REFERENCE UPPER NUMBER INDICATES DETAIL NUMBER LOWER NUMBER INDICATES SHEET NUMBER	
SECTION CUT DESIGNATION	
DEDICATED EQUIPMENT ACCESS TILE	
ACCESS PANEL	

## CIRCUITING & WIRING

HOMERUN TO PANELBOARD, INFORMATION AT ARROWS ARE CIRCUIT NUMBERS AND PANELBOARD FOR TERMINATION. REFER TO PANELBOARD SCHEDULES FOR BRANCH CIRCUIT CONDUCTOR SIZES.	
INDICATES RELAY NUMBER	
CIRCUIT CONTINUATION OR PARTIAL CIRCUIT	
CONDUIT CONCEALED	
CONDUIT CONCEALED (EMERGENCY)	
CONDUIT IN UNDER FLOOR/GROUND CONSTRUCTION	
EXPOSED CONDUIT	
EXPOSED CONDUIT (EMERGENCY)	
FLEXIBLE CONDUIT	
LOW VOLTAGE CABLE (NOT ROUTED IN CONDUIT)	
CONDUIT TURNING DOWN	
CONDUIT TURNING UP	
CONNECTION POINT OR EQUIPMENT TERMINATION	
EQUIPMENT TERMINATION	

## CONDUCTOR TICK MARK LEGEND

WHERE TICK MARKS ARE SHOWN, THE FOLLOWING SHALL GOVERN:	
SWITCHED HOT (PHASE) CONDUCTORS (SHOWN TRAILING NEUTRAL)	
NEUTRAL (GROUNDED) CONDUCTOR	
UNSWITCHED HOT (PHASE) CONDUCTORS (SHOWN LEADING NEUTRAL)	
NOTE: HASH MARKS INDICATE QUANTITY OF CONDUCTORS	
EQUIPMENT GROUNDING CONDUCTOR IN CONDUIT (GREEN INSULATION OR BARE)	
ISOLATED GROUNDING CONDUCTOR IN CONDUIT (GREEN INSULATION WITH YELLOW TRACER)	

## BRANCH CIRCUIT CONDUCTOR TABLE

WHERE TICK MARKS ARE NOT SHOWN, THE FOLLOWING SHALL GOVERN:			
# OF POLES	HOT (PHASE)*	NEUTRAL (GROUNDED)	GROUNDING**
1P	(1)	(1) UNO	(1)
2P	(2)	(1) UNO	(1)
3P	(3)	(1) UNO	(1)

\* PROVIDE ADDITIONAL CONDUCTORS THROUGH ENTIRE CIRCUIT (SWITCHED, UNSWITCHED, ETC.) AS INDICATED THROUGHOUT CONSTRUCTION DOCUMENTS AND AS REQUIRED FOR A COMPLETE AND WORKING SYSTEM.

\*\* REFER TO SPECIFICATIONS FOR LIMITATIONS ON SHARING NEUTRAL (GROUNDED) CONDUCTORS. DO NOT CIRCUIT AS A MULTI-WIRE BRANCH CIRCUIT, UNO.

\*\*\* PROVIDE ADDITIONAL ISOLATED GROUNDING CONDUCTORS WHERE INDICATED.

REFER TO SPECIFICATIONS, PLANS, NOTES, WIRING AND CONTROL DIAGRAMS FOR ADDITIONAL CIRCUITING REQUIREMENTS.

LIGHTING	
LIGHT FIXTURE	
a = LOWER CASE LETTER IS SWITCH IDENTIFIER	
A = UPPER CASE LETTER INDICATES LIGHT FIXTURE TYPE	
= WALL MOUNT	
= ARROW INDICATED AIMING DIRECTION	
LIGHT FIXTURE CIRCUITED AS A NIGHT LIGHT (NL)	
EMERGENCY LIGHT FIXTURE WITH EMERGENCY LIGHTING BATTERY PACK OR CONNECTED TO EMERGENCY SOURCE	
NIGHT LIGHT/EMERGENCY LIGHT FIXTURE WITH EMERGENCY BATTERY PACK OR CONNECTED TO EMERGENCY SOURCE	
LIGHT FIXTURE WITH DUAL BALLASTS CIRCUITED SEPARATELY (SHADING IMPLIES EMERGENCY LIGHT FIXTURE)	
LIGHTING TRACK (# INDICATES RELAY NUMBER)	
MIRROR LIGHTS	
EXTERIOR PARKING LOT LIGHT FIXTURE	
EXTERIOR PEDESTRIAN POST TOP LIGHT FIXTURE	
EXTERIOR LOT BOLLARD LIGHT	
EXIT SIGN - CEILING / WALL MOUNTED, ARROWS AS INDICATED, FACE HATCHED	
EMERGENCY LIGHTING UNIT EQUIPMENT WITH BATTERY PACK - CEILING/WALL MOUNTED	
AFEA (AREA FOR EVACUATION ASSISTANCE) SIGN - CEILING/WALL MOUNTED, ARROWS AS INDICATED	

REFER TO LIGHT FIXTURE SCHEDULE FOR MORE INFORMATION

## POWER EQUIPMENT & DEVICES

ELECTRICAL PANELBOARD (SURFACE OR FLUSH MOUNT)	
ELECTRICAL CABINET (SURFACE OR FLUSH MOUNT), TYPE AS NOTED	
PLYWOOD TERMINAL BOARD FOR TELEPHONE SYSTEM, UNO, SIZE AS NOTED	
SWITCHBOARD OR MOTOR CONTROL CENTER ON HOUSEKEEPING PAD	
ELECTRICAL DISTRIBUTION PANELBOARD	
TRANSFORMER	
DISCONNECT SWITCH - "2003/150/3R" DENOTES AMPERES/POLE/FUSE/NEMA ENCLOSURE RATING, NF= NON-FUSED, CB= CIRCUIT BREAKER (2003/CB), NO VALUE (2003/150) FOR NEMA ENCLOSURE MEANS STANDARD NEMA 1 RATING	
COMBINATION DISCONNECT (SAFETY) SWITCH AND MOTOR STARTER "303/15/13R" DENOTES AMPERES/POLE/FUSE/NEMA STARTER SIZE/NEMA ENCLOSURE RATING, NF= NON-FUSED, CB= CIRCUIT BREAKER (303/CB/1), NO VALUE (2003/150/13) FOR NEMA ENCLOSURE MEANS STANDARD NEMA 1 ENCLOSURE RATING	
MAGNETIC MOTOR STARTER, NEMA SIZE AS NOTED, 3-POLE, UNO	
VARIABLE FREQUENCY DRIVE	
INDICATING LIGHT	
EMERGENCY POWER OFF BUTTON	
STOP-START PUSH BUTTON CONTROL STATION	
HAND-OFF-AUTO PUSH BUTTON CONTROL STATION	
MUSHROOM-TYPE PUSH BUTTON	
OVERHEAD PADDLE FAN	

BOXES, LIGHTING CONTROL & WIRING DEVICES	
SWITCH LETTER DESIGNATIONS AS FOLLOWS: BLANK = SINGLE 2 = TWO POLE 3 = THREE-WAY 4 = FOUR-WAY D = DIMMER F = FAN SPEED CONTROL FH = INTEGRAL HORSEPOWER MANUAL CONTROLLER IH = INTEGRAL HORSEPOWER MANUAL CONTROLLER K = KEYS LVH = LOW VOLTAGE / DIGITAL M = MANUAL MOTOR STARTER DISCONNECT OSH = OCCUPANCY SENSOR P = SPST PILOT LIGHT WP = WEATHER PROOF # = REFER TO LIGHTING CONTROL DEVICE SCHEDULE	
AUTOMATIC LOAD CONTROL RELAY	
BRANCH CIRCUIT TRANSFER SWITCH	
CEILING / WALL MOUNTED OCCUPANCY SENSOR (# INDICATES TYPE PER SCHEDULE)	
CORNER 90 DEGREE SENSING ONE-DIRECTION SENSING, CEILING/WALL MOUNT CEILING MOUNT, TWO DIRECTION SENSING CEILING MOUNT, FOUR DIRECTION SENSING	
CONTACTOR (SIZE, COIL VOLTAGE AND NUMBER OF POLES AS INDICATED)	
TRACK-MOUNTED CURRENT LIMITER (## INDICATES AMPERAGE)	
DAYLIGHT SENSOR (# INDICATES TYPE PER SCHEDULE)	
LIGHTING CONTROLS PROCESSOR AND/OR EQUIPMENT	
POWER PACK (# INDICATES TYPE PER SCHEDULE)	
PHOTOELECTRIC SWITCH	
ROOM CONTROLLER (# INDICATES TYPE PER SCHEDULE)	
TIME SWITCH	
SIMPLEX RECEPTACLE - NEMA 5-20R, UNO	
DUPLEX RECEPTACLE - NEMA 5-20R, UNO	
DOUBLE DUPLEX RECEPTACLE - NEMA 5-20R, UNO	
SPECIAL RECEPTACLE - NEMA TYPE AS NOTED	
TWIST-LOCK TYPE RECEPTACLE	
BLANK FACE GFCI FEED THROUGH DEVICE	
GFCI TYPE RECEPTACLE*	
ISOLATED GROUND TYPE RECEPTACLE*	
EMERGENCY RECEPTACLE*	
RECEPTACLE INSTALLED ABOVE COUNTER OR BACKSPASH*	
RECEPTACLE INSTALLED IN CEILING*	
RECEPTACLE INSTALLED IN FLOOR*	
RECEPTACLE INSTALLED VIA DROP CORD*	
RECEPTACLE LETTER DESIGNATIONS AS FOLLOWS: C = AUTOMATICALLY CONTROLLED CH = CLOCK HANGER TYPE G-RPCT PROTECTED BY GFCI CIRCUIT BREAKER OR UPSTREAM GFCI DEVICE H = HORIZONTALLY MOUNTED S = MANUALLY CONTROLLED SP TVSS = SURGE PROTECTION TRIP - TAMPER RESISTANT TV = TELEVISION USB = USB/DUPLEX WR = WEATHER PROOF COVER WR = WEATHER RESISTANT	
MULTI-OUTLET ASSEMBLY	
TELEPHONE OUTLET	
DATA OUTLET	
MULTI-SERVICE OUTLET; TELEPHONE AND DATA	
ABOVE COUNTER, TYP WALL, TYP FLOOR, TYP	
MULTI-SERVICE POWER POLE WITH TELEPHONE, DATA AND POWER OUTLETS A = TYPE, REFER TO PLANS, SCHEDULES AND SPECIFICATIONS	
MULTI-SERVICE FLOOR BOX WITH TELEPHONE, DATA AND POWER OUTLETS A = TYPE, REFER TO PLANS, SCHEDULES AND SPECIFICATIONS	
POKE THROUGH, A = TYPE, REFER TO PLANS, SCHEDULES AND SPECIFICATIONS	
THERMOSTAT	
CEILING/FLOOR MOUNT JUNCTION/OUTLET BOX	
WALL MOUNT JUNCTION/OUTLET BOX	

* SYMBOL DEMONSTRATED WITH DUPLEX RECEPTACLE. WHEN USED IN COMBINATION WITH OTHER DEVICES MEANING IS SIMILAR FOR THOSE DEVICE TYPES.	
REFER TO LIGHTING CONTROL DEVICE SCHEDULE FOR MORE INFORMATION.	

ELECTRICAL ONE-LINE & RISER DIAGRAM	
SWITCH (RATING AS INDICATED)	
DRAWOUT CIRCUIT BREAKER (RATINGS AS INDICATED)	
FUSED SWITCH (RATING, POLES AND FUSE TYPE AS INDICATED)	
COMBINATION FUSED SWITCH/STARTER AND STARTER SIZE	
CIRCUIT BREAKER (RATINGS AS INDICATED)	
COMBINATION CIRCUIT BREAKER/STARTER AND STARTER SIZE	
PANELBOARD, SINGLE OR MULTI-SECTION (REFER TO SCHEDULES)	
ISOLATED POWER PANELBOARD W/ INTEGRAL TRANSFORMER (REFER TO SCHEDULES)	
TRANSFORMER (TYPE AND RATINGS AS INDICATED)	
SHIELDED TRANSFORMER (TYPE AND RATINGS AS INDICATED)	
AUTOMATIC TRANSFER SWITCH (RATINGS AS INDICATED)	
AUTOMATIC TRANSFER SWITCH WITH BYPASS (RATINGS AS INDICATED)	
GENERATOR (RATINGS AS INDICATED)	
SWITCHGEAR, SWITCHBOARD AND/OR DISTRIBUTION PANELBOARD (TYPE, RATING, DEVICES AND ACCESSORIES AS INDICATED)	
COMBINATION DIGITAL VOLT METER/AMMETER	
CIRCUIT IDENTIFICATION (REFER TO CIRCUIT SCHEDULE)	
GROUND FAULT RELAY	
PHASE FAILURE RELAY	
KIRK-KEY INTERLOCK (# INDICATES KEY PAIR)	
SHUNT TRIP	
AMMETER (RANGE AS SPECIFIED OR REQUIRED)	
VOLTMETER (RANGE AS SPECIFIED OR REQUIRED)	
UTILITY METER (AS REQUIRED BY UTILITY)	
AMMETER SWITCH	
VOLTMETER SWITCH	
WATT-HOUR METER, "D" DENOTES DEMAND REGISTER, "15" DENOTES MINUTES OF DEMAND INTERVAL	
CURRENT TRANSFORMER RATING AS SPECIFIED OR REQUIRED	
POTENTIAL TRANSFORMER RATING AS SPECIFIED OR REQUIRED	
SURGE-PROTECTIVE DEVICE	
GROUND CONNECTION	
GROUND CONNECTION WITH TEST WELL	
GROUND ROD	
LIGHTNING ARRESTER	
CAPACITOR	
CONTACT (OPEN OR CLOSED)	
HEATER	
MOTOR	
BLOCK LOAD KW OR KVA	
FAULT POINT REFERENCED IN SHORT CIRCUIT CURRENT AND VOLTAGE DROP SPREADSHEET	
× FB × FPP	

## CALL OUTS

ENLARGED PLAN CALLOUT	
NOT IN SCOPE	

## SPECIAL SYSTEMS SUPPLEMENTAL SPECIFICATIONS:

- PROVIDE NECESSARY BOXES, CONDUIT AND MAKE FINAL CONNECTIONS TO TEMPERATURE CONTROL DEVICES PER MANUFACTURER'S RECOMMENDATIONS. THIS INCLUDES BUT IS NOT LIMITED TO: MAIN CONTROL PANELS, THERMOSTATS, HUMIDISTATS, AC SOLENOIDS, HEAT RECLAIM WIRING, AHU CONTROL WIRING, DUCT FURNACE CONTROL WIRING, TIMERS, AND SIMILAR CONTROLS. PROVIDE CONDUIT FOR ALL WIRING WITHIN WALLS. PROVIDE CONTROL AND INTERLOCK WIRING WHEN NOT PROVIDED BY OTHER TRADES. COORDINATE REQUIREMENTS WITH EQUIPMENT SUPPLIERS AND OTHER TRADES PRIOR TO ROUGH-IN.
- PROVIDE LINE VOLTAGE WIRING AND MAKE FINAL CONNECTIONS TO ALL DUCT-MOUNTED SMOKE DETECTORS, FIRE/SMOKE AND SMOKE DAMPERS WHERE APPLICABLE. COORDINATE REQUIREMENTS WITH OTHER TRADES PRIOR TO INSTALLATION.
- DEVICES MOUNTED ON ACOUSTICAL TILE CEILINGS SHALL BE CENTERED ON THE TILE, UNO.
- PROVIDE BOX AND 3/4" CONDUIT FROM EACH THERMOSTAT LOCATION TO MECHANICAL EQUIPMENT. (FLUSH MOUNT BOX WHEREVER PRACTICABLE). COORDINATE LOCATION OF ALL THERMOSTAT BOXES WITH MECHANICAL/CONTROLS CONTRACTOR AND OWNER PRIOR TO ROUGH-IN.
- PROVIDE BOXES AND CONDUITS FOR THE FIRE PROTECTION SYSTEM LOW VOLTAGE WIRING AS REQUIRED. THIS INCLUDES EXPOSED WIRING LESS THAN 96" AFF. AT A MINIMUM, PROVIDE 3/4" CONDUIT, UNLESS NOTED OTHERWISE. COORDINATE REQUIREMENTS AND LOCATIONS WITH SYSTEM INSTALLER.
- AT A MINIMUM, PROVIDE EXTRA DEEP, DOUBLE GANG COMMUNICATION OUTLET BOXES, (FLUSH MOUNTED WHEREVER PRACTICABLE), WITH SINGLE-GANG PLASTER RING AND 1" CONDUIT STUBBED-UP CONCEALED TO ACCESSIBLE CEILING SPACE, UNLESS NOTED OTHERWISE. PROVIDE SURFACE MOUNTED DATA BOXES WITH CABINETRY, AND SELECT OTHER LOCATIONS AS INDICATED ON THE DRAWINGS. COORDINATE TELEPHONE/DATA BOX AND CONDUIT LOCATIONS AND SIZES WITH OWNER AND OTHER TRADES PRIOR TO ROUGH-IN.

- PROVIDE NYLON BUSHINGS FOR ALL COMMUNICATIONS AND LOW VOLTAGE WIRING CONDUITS AND SLEEVES, UNLESS NOTED OTHERWISE.
- ALL COMMUNICATIONS AND LOW VOLTAGE WIRING CONDUIT SHALL BE INSTALLED WITH AN ACCESSIBLE PULLBOX BETWEEN EVERY 180 DEGREE CHANGE IN DIRECTION AND AT 100' INTERVALS OF CONTINUOUS RUNS.
- MINIMUM BEND RADIUS FOR COMMUNICATIONS CONDUIT IS 6 TIMES THE INSIDE DIAMETER FOR CONDUITS 2" IN DIAMETER AND SMALLER AND 10 TIMES THE INSIDE DIAMETER FOR CONDUITS GREATER THAN 2" IN DIAMETER, UNLESS NOTED OTHERWISE.
- ALL LOW VOLTAGE CLASS 2 OR 3 WIRING NOT IN CONDUIT SHALL BE PLENUM RATED WHERE APPLICABLE.
- LOW VOLTAGE CABLE SHEATH LABELS AND RELATED MANUFACTURER INFO SHALL REMAIN APPARENT IN ALL EXPOSED APPLICATIONS. PROTECT ALL EXPOSED CABLES FROM PAINTING AND OVERSPRAY (INCLUDES CABLE NOT ROUTED IN CONDUIT AND THAT IS IN CABLE TRAY).



LSR7 Robotics, GiC & Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

0121-0100


civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

SITE ELECTRICAL GENERAL NOTES:

1. REFER TO CIVIL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION. COORDINATE THE FINAL LOCATION OF UNDERGROUND UTILITIES, CONDUITS, CIRCUITRY, TRANSFORMERS AND OTHER EQUIPMENT WITH CIVIL DRAWINGS, LANDSCAPING DRAWINGS AND OWNER PRIOR TO INSTALLATION.
2. SITE ELECTRICAL CONDUITS SHALL BE 1" MINIMUM, UNLESS NOTED OTHERWISE. WHERE PRACTICABLE, ALL SITE ELECTRICAL CONDUITS SHALL BE INSTALLED A MINIMUM OF 24" BELOW GRADE, UNLESS NOTED OTHERWISE. COORDINATE FINAL CONDUIT ROUTING WITH EXISTING OBSTRUCTIONS AND OTHER TRADES AND ADJUST AS NECESSARY.
3. MINIMUM WIRE SIZE FOR SITE ELECTRICAL CIRCUITS SHALL BE #10 AWG CU, UNLESS NOTED OTHERWISE. ALL SITE ELECTRICAL BRANCH CIRCUIT WIRING SHALL BE SIZED SUCH THAT THE MAXIMUM BRANCH CIRCUIT VOLTAGE DROP IS LESS THAN 3 PERCENT.
4. PROVIDE SPLICE AND PULL BOXES FOR SITE ELECTRICAL POWER TO LIMIT MAXIMUM CONDUIT RUN TO 300'. PLACE BOXES IN A PLANTER AREA CLEAR OF VEGETATION WHEREVER PRACTICABLE. (COORDINATE FINAL LOCATION WITH CIVIL, LANDSCAPE CONTRACTOR AND OWNER). BOXES SHALL BE SUITABLE FOR LOCATION AND PROPERLY SIZED FOR QUANTITY AND SIZE OF CONDUITS IN AND OUT AND SHALL BE MARKED "ELECTRICAL". NOT ALL OF THESE BOXES ARE SHOWN ON SITE ELECTRICAL DRAWINGS; CONTRACTOR SHALL PROVIDE LOCATION ON AS-BUILT DRAWINGS AND SUBMIT TO OWNER. SPLICE BOX SHALL BE APPROPRIATE FOR LOCATION AND SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS. SPLICE BOX SHALL HAVE A MINIMUM NOMINAL SIZE OF 12"x12"x12". SHALL BE AN OPEN BOTTOM NRTL LISTED UNDERGROUND ENCLOSURE, AND SHALL AT A MINIMUM BE TIER 15 TRAFFIC RATED.
5. PROVIDE SPLICE AND PULL BOXES FOR ROOFTOP CONDUIT ROUTING. PROVIDE MAXIMUM LENGTHS OF CONDUIT RUNS AND BENDS NOT MORE THAN 360 DEGREES BETWEEN PULL BOXES PER CODE.
6. ALL CONDUIT ON ROOF SHALL BE MOUNTED AT A MINIMUM 7/8" ABOVE ROOFTOP.




1 ELECTRICAL SITE PLAN - LSW  
1" = 20'-0"



Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE



09/09/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

LSW - ELECTRICAL SITE PLAN  
E100-A



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveg.com


structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/T/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

NO EXPOSED CONDUITS SHALL PENETRATE FINISHED  
PLYWOOD ON WALLS. ALL CONDUITS SHALL ROUTE ABOVE  
PLYWOOD WHEN PENETRATING WALLS. REFER TO  
ARCHITECTURAL SHEETS FOR EXACT HEIGHTS OF FINISHED  
PLYWOOD.

**ELECTRICAL PLAN NOTES:**

- E34 PROVIDE EMERGENCY BATTERY PACK CAPABLE OF  
OPERATING 4' SECTION OF FIXTURE AT THIS LOCATION  
WITHIN CONTINUOUS FIXTURE RUN. REFER TO LIGHT  
FIXTURE SCHEDULE FOR ADDITIONAL INFORMATION.
- E36 SURFACE MOUNT OCCUPANCY SENSOR TO UNDERSIDE OF  
STRUCTURE.
- E37 SURFACE MOUNT EXIT SIGN TO SIDE OF COLUMN 10' AFF.
- E38 SURFACE MOUNT EXIT SIGN TO UNDERSIDE OF STRUCTURE.
- E39 MOUNT FIXTURE TO UNDERSIDE OF BLOCKING BETWEEN  
EXTERIOR METAL SKIN AND BUILDING EXTERIOR. CIRCUIT  
WITH REMOTE BATTERY IOTA ILB CP10 HE SD (OR  
APPROVED EQUIVALENT) FOR EMERGENCY OPERATION.  
MOUNT BATTERY IN ENCLOSURE TIGHT TO STRUCTURE IN  
PLUMBING R102. REFER TO ARCHITECTURAL DETAILS FOR  
ADDITIONAL MOUNTING REQUIREMENTS AND INFORMATION.
- E40 MOUNT EXIT SIGN 12' AFF.
- E41 CIRCUIT WITH REMOTE BATTERY IOTA ILB CP10 HE SD (OR  
APPROVED EQUIVALENT) FOR EMERGENCY OPERATION.  
MOUNT BATTERY IN ENCLOSURE TIGHT TO STRUCTURE.
- E52 REFER TO ROOF PLAN FOR LOCATION OF PHOTOELECTRIC  
SWITCH FOR CONTROL CANOPY FIXTURE.
- E53 SURFACE MOUNT FIXTURE TO UNDERSIDE OF STRUCTURE.
- E55 PENDANT MOUNT OCCUPANCY SENSOR NO HIGHER THAN  
12' AFF.
- E56 PROVIDE LABEL FOR ROOM CONTROLLERS NOTING THE  
ROOMS THEY SERVE. MOUNT ON WALL NO HIGHER THAN 10'  
AFF.




1 LIGHTING LEVEL 1 RCP - LSW  
3/16" = 1'-0"

**HENDERSON**  
ENGINEERS  
8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM

Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/16/2022
2	Addendum 02	09/23/2022



09/23/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

**LSW - LIGHTING RCP  
E101-A**



LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio  
civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveeng.com  
structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com  
MEP/T/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com



8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM  
2150005255  
MO. CORPORATE NO. E-8580  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

Revisions  
NUMBER DESCRIPTION DATE



09/09/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

LSW - POWER PLAN  
E201-A

GIC EQUIPMENT SCHEDULE


TAG	EQUIPMENT DESCRIPTION	VOLTAGE	PHASE	RECEPTACLE TYPE
2A	MITER SAW	120 V	1	5-20R
3A	PANEL SAW	120 V	1	5-20R

ROBOTICS EQUIPMENT SCHEDULE


TAG	EQUIPMENT DESCRIPTION	VOLTAGE	PHASE	RECEPTACLE TYPE
1B	BRIDGEPORT 3-AXIS CNC	208 V	1	15-20R
2B-1	BIRMINGHAM YCL-1440GH LATHE (MAIN)	208 V	3	15-30R
2B-2	BIRMINGHAM YCL-1440GH LATHE (CONTROLS)	120 V	1	5-20R
4B/14B	ROLAND MDX-40A MILLING MACHINE BUFFING WHEEL	120 V	1	RE-PLAN NOTE
5B	WELLS HORIZONTAL BANDSAW	208 V	1	6-20R
6B	DELTA MILWAUKEE BAND SAW	208 V	1	6-20R
9B	MITACHI MITER SAW	120 V	1	5-20R
9B/25B	BALDOR BELT SANDER CRAFTSMAN 8" DRILL PRESS BUFFING WHEEL	120 V	1	5-20R
10B	DELTA MILWAUKEE DRILL PRESS	208 V	1	6-20R
11B	BELT AND DISC SANDER	120 V	1	5-20R
12B/13B	RYOBI BENCH GRINDER PORTER CABLE BENCH GRINDER	120 V	1	RE-PLAN NOTE
17B	OPEN TABLE CNC	208 V	3	HARDWIRED
18B-1	TIG WELDER (MAIN)	208 V	1	6-30R
18B-2	TIG WELDER (MISC)	120 V	1	5-20R
24B	CRAFTSMAN 17" DRILL PRESS	120 V	1	5-20R

ELECTRICAL PLAN NOTES:


- E6 PROVIDE (2) DUAL CHANNEL ALUMINUM RACEWAYS, LEGRAND ALA4800 SERIES WITH RECEPTACLES AND DATA OUTLETS SPACED AT 1' INTERVALS. PROVIDE AT 4' AFF AND 5' AFF. REFER TO ARCHITECTURAL ELEVATIONS FOR ADDITIONAL INFORMATION.
- E11 PROVIDE KH INDUSTRIES RTB83L-WDD520-J12F RETRACTABLE CORD REEL OR APPROVED EQUIVALENT. 25' CORD LENGTH WITH #12/3 WIRES RATED FOR 20A AT 120V. (2) DUPLEX RECEPTACLES, NEMA 2 ENCLOSURE. 5JOW BLACK CORD. 12 POSITION ADJUSTABLE GUIDE ARM WITH ADJUSTABLE RATCHED AND BALL STOP. 6' FEEDER CORD.
- E12 PROVIDE KH INDUSTRIES RTAN3LW-WCL520-J12F RETRACTABLE CORD REEL OR APPROVED EQUIVALENT. 25' CORD LENGTH WITH #12/3 WIRES RATED FOR 20A AT 120V. (1) TWISTLOCK L5-20R RECEPTACLE, NEMA 2 ENCLOSURE. 5JOW BLACK CORD. 4 POSITION ADJUSTABLE ARM WITH (4) ROLLER GUIDES AND ADJUSTABLE BALL STOP. 6' FEEDER CORD. WHITE FINISH.
- E14 RECESS L5-20R TWISTLOCK RECEPTACLE IN WOOD CEILING.
- E22 PROVIDE POWER CONNECTION TO ACCESS CONTROL PANEL.
- E23 MOUNTED RECEPTACLE TO LADDER RACK AT 7'-0" AFF. COORDINATE FINAL LOCATION AND ROUTINGS WITH OWNER PRIOR TO ROUGH-IN.
- E28 PROVIDE JUNCTION BOX AND HARDWIRE CONNECTION TO MOTORIZED OVERHEAD GARAGE DOOR. COORDINATE ROUGH-IN AND CONTROL LOCATIONS WITH APPROVED MANUFACTURER PRIOR TO INSTALL.
- E45 PROVIDE LINE VOLTAGE CONNECTION TO ADA DOOR OPERATOR WITH LOW VOLTAGE WIRING TO PUSH BUTTON(S). COORDINATE WIRING CONFIGURATION WITH APPROVED MANUFACTURER PRIOR TO ROUGH-IN.



1 POWER LEVEL 1 PLAN - LSW  
3/16" = 1'-0"



3 POWER LEVEL 1 PLAN - LSW - TELECOM ROOM  
1/2" = 1'-0"



2 POWER LEVEL 1 PLAN - LSW - ELEC ROOM  
1/2" = 1'-0"



LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.591.6655  
multi.studio  
civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvereng.com  
structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com  
MEP/T/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com



8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM  
2150005255  
MO. CORPORATE NO. E-858D  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/16/2022
2	Addendum 02	09/19/2022



09/23/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

LSW - EQUIPMENT  
CONNECTION PLAN  
E301-A

NO EXPOSED CONDUITS SHALL PENETRATE FINISHED  
PLYWOOD ON WALLS. ALL CONDUITS SHALL ROUTE ABOVE  
PLYWOOD WHEN PENETRATING WALLS. REFER TO  
ARCHITECTURAL SHEETS FOR EXACT HEIGHTS OF FINISHED  
PLYWOOD.

ELECTRICAL PLAN NOTES:

- E44 PROVIDE CONNECTION TO BAS PANEL. COORDINATE FINAL  
LOCATION WITH MECHANICAL CONTRACTOR PRIOR TO  
ROUGH-IN.  
E63 PROVIDE PLUG AND CORD CONNECTION FOR ACD1. REFER  
TO PLUMBING PLANS FOR ADDITIONAL INFORMATION.  
COORDINATE FINAL REQUIREMENTS WITH DIVISION 22  
PRIOR TO ROUGH-IN.  
E64 PROVIDE HARDWIRE CONNECTION FOR RAD1. REFER TO  
PLUMBING PLANS FOR ADDITIONAL INFORMATION.  
COORDINATE FINAL REQUIREMENTS AND CONTROLS WITH  
DIVISION 22 PRIOR TO ROUGH-IN.

EQUIPMENT  
CONNECTION SCHEDULE


MARK	PANEL	CIRCUIT	NOTES
AIR COMPRESSOR	L1W	78,80,82	B
AC	L1W	14	B
Electric Storage Water Heater	H1W	14	B
FAN	L1W	94	A
Recirculation Pump	L1W	88	D
RP1	L1W	88	D
VRF INDOOR	L1W	74,76	C
CRU 1W	L1W	74,76	C

EQUIPMENT CONNECTION GENERAL NOTES:

- COORDINATE FINAL LOCATIONS WITH MECHANICAL  
CONTRACTOR PRIOR TO ROUGH-IN.
- REFER TO MECHANICAL SCHEDULES FOR ADDITIONAL  
INFORMATION WITHIN SCOPE OF DIVISION 26.
- COORDINATE WITH MECHANICAL CONTRACTOR TO  
PROVIDE FINAL POWER REQUIREMENTS FOR ALL  
SUBMITTED EQUIPMENT THAT DIFFERS FROM BASIS-OF-  
DESIGN.

EQUIPMENT CONNECTION SCHEDULE NOTES:

- A. DISCONNECTING MEANS (FRACTIONAL HP SWITCH, FUSED  
DISCONNECT SWITCH, ETC.) AND/OR CONTROLLER  
(STARTER, VFD, ETC.) IS FACTORY MOUNTED OR  
PROVIDED BY DIVISION 23.  
B. PROVIDE FUSED/NON-FUSED DISCONNECT SWITCH SIZED  
PER EQUIPMENT MANUFACTURER'S SPECIFICATIONS AND  
THE NEC. REFER TO ELECTRICAL SYMBOLS LEGEND FOR  
NAMING DESIGNATIONS.  
C. PROVIDE POWER AND CONTROL WIRING FROM  
ASSOCIATED CONDENSING UNIT PER MANUFACTURER'S  
INSTALLATION INSTRUCTIONS. PROVIDE FRACTIONAL HP  
SWITCH TO ACT AS DISCONNECTING MEANS.  
D. PROVIDE FRACTIONAL HP SWITCH SIZED PER EQUIPMENT  
MANUFACTURER'S SPECIFICATIONS AND THE NEC.





LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063


owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect: Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvang.com

structural engineer: Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/PT/Code: Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com



8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM

2150005255  
MO. CORPORATE NO. E-6880  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/16/2022



09/15/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

LSW - ELECTRICAL ROOF  
PLAN

E302-A

ELECTRICAL PLAN NOTES:

E51 PROVIDE PHOTOELECTRIC SWITCH ON ROOFTOP AND ORIENT NORTH PER MANUFACTURER'S INSTALLATION INSTRUCTIONS. SWITCH IS POWERED VIA LOW-VOLTAGE CONNECTION TO POWER PACK ON FIRST FLOOR. REFER TO LIGHTING CONTROL DEVICE SCHEDULE FOR ADDITIONAL INFORMATION.

EQUIPMENT  
CONNECTION SCHEDULE


MARK	PANEL	CIRCUIT	NOTES
RTU 1N	H1W	2,4,6	A,D
RTU 2N	H1W	8,10,12	A,D
COMPUTER ROOM - OUTDOOR			
CU 1W	L1W	74,76	B
FAN			
EF 1W	L1W	90	A

EQUIPMENT CONNECTION GENERAL NOTES:


- COORDINATE FINAL LOCATIONS WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN.
- REFER TO MECHANICAL SCHEDULES FOR ADDITIONAL INFORMATION WITHIN SCOPE OF DIVISION 26.
- COORDINATE WITH MECHANICAL CONTRACTOR TO PROVIDE FINAL POWER REQUIREMENTS FOR ALL SUBMITTED EQUIPMENT THAT DIFFERS FROM BASIS-OF-DESIGN.

EQUIPMENT CONNECTION SCHEDULE NOTES:

- DISCONNECTING MEANS (FRACTIONAL HP SWITCH, FUSED DISCONNECT SWITCH, ETC.) AND/OR CONTROLLER (STARTER, VFD, ETC.) IS FACTORY MOUNTED OR PROVIDED BY DIVISION 25.
- PROVIDE FUSED/NON-FUSED DISCONNECT SWITCH SIZED PER EQUIPMENT MANUFACTURER'S SPECIFICATIONS AND THE NEC. REFER TO ELECTRICAL SYMBOLS LEGEND FOR NAMING DESIGNATIONS.
- PROVIDE POWER AND CONTROL WIRING FROM ASSOCIATED CONDENSING UNIT PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- PROVIDE CONNECTION TO FACTORY PROVIDED 120V 20A GFCI RECEPTACLE.



1 ELECTRICAL ROOF PLAN - LSW  
3/16" = 1'-0"





LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect: Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio


civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer: Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/ET/Code: Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com


Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE



DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

ELECTRICAL DETAILS  
E500




NOTES:

1. REFER TO LIGHTING CONTROL DEVICE SCHEDULE FOR DEVICE AND EQUIPMENT SPECIFICATIONS.
2. QUANTITY OF RELAYS SHOWN IS GENERIC. REFER TO PLANS, LIGHTING CONTROL DEVICE SCHEDULE, AND SHOP DRAWINGS FOR FINAL QUANTITY PER ROOM CONTROLLER.
3. DETAIL IS DIAGRAMMATIC AND IS BASED ON LEGRAND. THIS REPRESENTS THE GENERAL SCOPE OF WORK AND LOCATION OF DEVICES IN RELATION TO EACH OTHER ALONG THE POWER CIRCUIT. DIAGRAMS MAY BE DIFFERENT FOR ALLOWED EQUIVALENT MANUFACTURERS. ELECTRICAL CONTRACTOR SHALL COORDINATE FULL SYSTEM REQUIREMENTS WITH SELECTED MANUFACTURER. PROVIDE ALL PARTS AND PIECES REQUIRED FOR A FULLY FUNCTIONAL SYSTEM. REFER TO FINAL APPROVED MANUFACTURER'S INSTALLATION INSTRUCTIONS AND WIRING DIAGRAMS FOR INSTALLATION.
4. CIRCUITING SHOWN ON THE PLAN CORRESPONDS TO THE LIGHTING CONTROL INTENT. IF CIRCUITING IS CHANGED IN THE FIELD, ENSURE THAT SYSTEM PROGRAMMING WITH REVISED CIRCUITING MEETS THE ORIGINAL LIGHTING CONTROL INTENT. UPDATE LIGHTING CONTROL PANEL SCHEDULES IN RECORD DRAWINGS.


⑥ ROOM CONTROLLER DETAIL - ON/OFF OR ON/OFF/0-10V DIMMING CONTROL  
NTS

ELECTRICAL NOTES:

1. PROVIDE SUFFICIENT LENGTH TO MOVE CENTER OF LUMINAIRE IN A 5'-0" RADIUS OF THE LOCATION SHOWN ON THE PLANS. RMC OR EMT (UNLESS TYPE MC CABLE IS ALLOWED BY SPECIFICATIONS. IF MORE THAN 4 CURRENT CARRYING CONDUCTORS INCLUDING NEUTRALS, MC CABLE IS NOT ALLOWED).
- 2.




⑤ LIGHTING STANDARD LUMINAIRE WIRING  
NTS



NOTES:

1. CONDUITS TURNED UP INSIDE WALLS MAY BE RNC FROM ABOVE THE SLAB TO RECESSED PANELBOARDS OR OUTLETS. FROM THE OUTLET UP IT SHALL BE EMT.
2. CONDUITS TURNED UP EXPOSED SHALL HAVE AN RMC ELBOW THROUGH THE SLAB. PROTECT THE ENTIRE ELBOW WITH RNC COATING OR MASTIC UP THROUGH THE TOP OF THE SLAB.  
  
EXCEPTION: IN LIEU OF RMC ELBOW, CONTRACTOR MAY USE RNC ELBOWS IF A CHANNEL STRUT OR STEEL ANGLE GUARD IS PROVIDED. GUARD SHALL STAND OFF THE WALL INDEPENDENT OF THE CONDUIT.
3. IN AREAS WITH VEHICULAR ACCESS, USE GALVANIZED RMC ELBOWS AND A STEEL GUARD.
4. APPLIES TO ALL STUB-UP LOCATIONS UNLESS NOTED OTHERWISE ON PLANS.

② CONDUIT STUB-UP AT WALLS  
NTS



REFER TO ARCHITECTURAL DRAWINGS FOR WALL LOCATIONS.  
REFER TO SPECIFICATIONS FOR ALTERNATIVE INSTALLATIONS.  
COORDINATE REQUIREMENTS WITH GENERAL CONTRACTOR.

① CONDUIT PENETRATION THRU NON-FIREWALL  
NTS



8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM  
2150005255  
MO. CORPORATE NO. E-8680  
EXPIRES 12/31/2022



LSR7 Robotics, GiC & Phys Education


LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
0121-0100  
architect:  
Multistudio  
4200 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multistudio  
civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveg.com  
structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com  
MEP/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

HENDERSON  
ENGINEERS  
8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM  
2150005255  
MO. CORPORATE NO. E-5680  
EXP/RES 12/31/2022

Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE
2	Addendum 02	09/23/2022



09/23/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

LSW - PANELBOARD  
SCHEDULES  
E600-A

PANELBOARD: H1W (NEW)										EQUIPMENT GROUND BUS										
BUS AMPS: 400A MAIN SIZE/TYPE: 400A MCB VOLTS/PHASE: 480Y/277 V 3P/4W SUPPLIED BY: MSB-W				SCHOOL BUILDING SQUARE FOOTAGE: 7000				FAULT CURRENT: AIC RATED: SERVES: MOUNTING: LOCATION:				REFER TO ONE-LINE FULLY RATED FCA +10% MINIMUM ROBOTICS / GIC SURFACE ELECTRICAL R106				SERVICE ENTRANCE RATED				
LINE-SIDE LUGS: MECHANICAL																				
CKT NO.	DESCRIPTION	LOAD TYPE	NOTES	WIRE SIZE	BKR AMP	P	PHASE A		PHASE B		PHASE C		P	BKR AMP	WIRE SIZE	NOTES	LOAD TYPE	DESCRIPTION	CKT NO.	
1	LTG - GIC, GIC CANOPY, N	LZ		12	20	1	1808	10641					3	50	8		C M	RTU-1W	2	
3	LTG - CENTRAL CORE	LZ		12	20	1			1269	10641									4	
5	LTG - ROBOTICS, E CANOPY	LZ		12	20	1					1894	10641							6	
7	SPARE			20	1		0	7593					3	35	8		C M	RTU-2W	8	
9	SPARE			20	1				0	7593					10				10	
11	SPARE			20	1						0	7593							12	
13	SPARE			20	1		0	6000					1	30	10		U	WH-1	14	
15	SPARE			20	1				0	0				1	20			SPARE	16	
17	SPARE			20	1						0	0		1	20			SPARE	18	
19	SPARE			20	1		0	0					1	20				SPARE	20	
21	SPARE			20	1				0	0				1	20			SPARE	22	
23	SPARE			20	1						0	0			1	20			SPARE	24
25	SPARE			20	1		0	0					1	20				SPARE	26	
27	SPARE			20	1				0	0				1	20			SPARE	28	
29	SPARE			20	1						0	0			1	20			SPARE	30
31	SPARE			20	1		0	0					1	20				SPARE	32	
33	SPARE			20	1				0	0				1	20			SPARE	34	
35	SPARE			20	1						0	0			1	20			SPARE	36
37	EQUIPPED SPACE			1			0	30937					3	175	OL		R Z M	TX-L1W	38	
39	EQUIPPED SPACE			1					0	28054									40	
41	EQUIPPED SPACE			1							0	33397							42	
TOTAL LOAD (VA):							56979 VA		47558 VA		53526 VA									
TOTAL AMPS:							209 A		172 A		197 A									
PANELBOARD NOTES																		PANELBOARD TOTALS		
LOAD TYPE		CONNECTED	DEMAND FACTOR	NEC DEMAND														TOTAL CONNECTED LOAD		176307 VA
EXISTING LOAD (E)		0 VA	100%	0 VA														TOTAL NEC LOAD <th>177146 VA</th>		177146 VA
COOLING (C)		31510 VA	100%	31510 VA																
HEATING (H)		0 VA	0%	0 VA																
LIGHTING (L) (PER NEC-220)		21000 VA	125%	26250 VA																
RECEPTACLES (R)		26180 VA	69%	18090 VA																
MOTORS (M)		43980 VA	100%	43980 VA																
SUPPLEMENTAL HEAT (U)		6000 VA	100%	6000 VA																
MISC EQUIP (Z)		32922 VA	100%	32922 VA																
REFRIGERATION (F)		0 VA	100%	0 VA																
SIGNAGE (S)		0 VA	125%	0 VA																
KITCHEN (K)		0 VA	100%	0 VA																
LARGEST MOTOR		14715 VA	125%	18394 VA																
SHOW WINDOW (W)		0 VA	125%	0 VA																
TRACK LIGHTING		0 VA	100%	0 VA																

PANELBOARD: L1W (NEW)										EQUIPMENT GROUND BUS																													
BUS AMPS: 400A MAIN SIZE/TYPE: 400A MCB VOLT/PHASE: 208Y/120 V 3P/4W SUPPLIED BY: HTW VIA TX-L1W										FAULT CURRENT: AIC RATED: SERVES: MOUNTING: LOCATION:										REFER TO ONE-LINE FULLY RATED FCA +10% MINIMUM ROBOTICS / GIC SURFACE ELECTRICAL R106										EQUIPMENT GROUND BUS									
										LINE-SIDE LUGS: MECHANICAL																													
CKT NO.	DESCRIPTION	LOAD TYPE	NOTES	WIRE SIZE	BKR AMP	P	PHASE A		PHASE B		PHASE C		P	BKR AMP	WIRE SIZE	NOTES	LOAD TYPE	DESCRIPTION	CKT NO.																				
1	RCPT - N ROBOTICS FIELD	R		12	20	1	1260	360					1	20	12	R	PLGMLD 1 - 3D PRINTERS	2																					
3	RCPT - E ROB FIELD CKT 1	R		12	20	1			540	360			1	20	12	R	PLGMLD 2 - 3D PRINTERS	4																					
5	RCPT - E ROB FIELD CKT 2	R		12	20	1					540	360	1	20	12	R	PLGMLD 3 - 3D PRINTERS	6																					
7	RCPT - TWSTLCK ROB FIELD	R		12	20	1	360	360					1	20	12	R	PLGMLD 4 - 3D PRINTERS	8																					
9	RCPT - ROB FIELD COL 1	R		12	20	1			720	720			1	20	12	R	RCPT - GIC SE WALL	10																					
11	RCPT - ROB FIELD COL 2	R		12	20	1					720	720	1	20	12	R	RCPT - GIC E WALL	12																					
13	EAST GARAGE DOOR	M		12	20	1	500	1800					1	20	10	VD	M RCPT - GIC PANEL SAW	14																					
15	WEST GARAGE DOOR	M		12	20	1			500	720			1	20	12	R	RCPT - GIC S WALL	16																					
17	RCPT - ROB CLSRM W WALL	R Z		12	20	1					1080	720	1	20	12	R	RCPT - CAD STATION CKT 3	18																					
19	RCPT - ROB CLSRM TWSTLCKS	R		12	20	1	720	900					1	20	12	R	RCPT - GIC W WALL	20																					
21	RCPT - MICROWAVE	Z		12	20	1			1200	720			1	20	12	R	RCPT - GIC CTR COLUMN	22																					
23	RCPT - ABV CTR 1	Z		12	20	1					1200	540	1	20	12	R	RCPT - GIC NW WALL	24																					
25	RCPT - ABV CTR 2	Z		12	20	1	1200	720					1	20	12	R	RCPT - GIC NE WALL	26																					
27	RCPT - FRIDGE	Z		12	20	1			800	800			1	20	12	R	RCPT - BIRMINGHAM LATHE CTRLS	28																					
29	RCPT - GIC TVS	Z		12	20	1					720	720	1	20	12	R	CRD REEL - GIC TABLES 1	30																					
31	RCPT - CAD STATION CKT 1	R		12	20	1	720	720					1	20	12	R	CRD REEL - GIC TABLES 2	32																					
33	RCPT - CAD STATION CKT 2	R		12	20	1				1080	720			1	20	12	R	CRD REEL - GIC TABLES 3	34																				
35	RCPT - W ROB FIELD	R		12	20	1					900	1800	1	20	10	VD	Z RCPT - GIC MITER SAW	36																					
37	RCPT - CORR PLMB ELEC	R		12	20	1	1080	500					1	20	12	Z	Z DROP RCPT - GEN ASSEMB COMP	38																					
39	RCPT - RESTROOMS, EWC	R Z		12	20	1			1200	180			1	20	12	R	RCPT - TiG WELDER MISC	40																					
41	CRD REEL - GEN ASSEMB 1	Z		12	20	1					1200	720	1	20	12	R	RCPT - ROB S WALL	42																					
43	CRD REEL - GEN ASSEMB 2	Z		12	20	1	1200	900			1200	900	2	20	12	Z	Z DROP RCPT - DELT MIL BANDSAW	44																					
45	CRD REEL - GEN ASSEMB 3	Z		12	20	1					1200	900						46																					
47	CRD REEL - GEN ASSEMB TL 1	Z		12	20	1					1200	1201						48																					
49	CRD REEL - GEN ASSEMB TL 2	Z		12	20	1	1200	1201					3	20	12	M	RCPT - BIRMINGHAM LATHE	50																					
51	CRD REEL - SHOP AREA 1	M		12	20	1			600	1201								52																					
53	CRD REEL - SHOP AREA 2	Z		12	20	1					1608	2500						54																					
55	DROP RCPT - CRFTS DRILL PRESS	Z	VD	10	20	1	1560	2500					3	30	10	M	OPEN TABLE CNC	56																					
57	DROP RCPT - BELT/DISC SANDER	Z	VD	10	20	1			1200	2500			2	30	8	VD	M RCPT - TiG WELDER MAIN	58																					
59	RCPT - EXTERIOR	R		12	20	1					720	2496	2	30	12	M	RCPT - TiG WELDER MAIN	60																					
61	RCPT - N EXTERIOR	R		12	20	1	360	2496					3	30	12	M	RCPT - TiG WELDER MAIN	62																					
63	RCPT - S EXTERIOR	R		12	20	1			360	640	720	640	3	30	12	M	RCPT - BRIDGEPORT 3 AXIS CNC	64																					
65	RCPT - W EXTERIOR	R		12	20	1					720	640	3	30	12	M	RCPT - BRIDGEPORT 3 AXIS CNC	66																					
67	FIRE RPS	Z		12	20	1	360	640					2	30	10	Z	RCPT - TELECOM RACK (208V)	68																					
69	CRD REEL - SHOP AREA 1	Z	VD	10	20	1			1600	1500			2	30	10	Z	RCPT - TELECOM RACK (208V)	70																					
71	DROP RCPT - MIT MITER SAW	Z	VD	10	20	1					1800	1500	2	20	12	M C	CU-1W/CRU-1W	72																					
73	DROP RCPT - WELLS HORIZ BANDSAW	Z		12	20	2	750	31					2	20	12	M C	CU-1W/CRU-1W	74																					
75									750	31								76																					
77	DROP RCPT - DELT MIL DRILL PRESS	Z		12	20	2					900	3699	3	60	6	M	GIC AIR COMPRESSOR	78																					
79							900	3699										80																					
81	SECURITY PANEL	Z		12	20	1			500	3699			1	20	12	M	SPARE	82																					
83	RCPT - TELECOM N WALL	R		12	20	1					1080	0	1	20	12	M	SPARE	84																					
85	RCPT - TELECOM S E WALL	R		12	20	1	1080	0					1	20	12	M	SPARE	86																					
87	RCPT - TELECOM RACK	R		12	20	1			360	58	894	0	1	20	12	M	SPARE	88																					
89	ACD1 & RAD1	Z		12	20	1							1	20	12	R	EXT RCPT - ROOFTOP	90																					
91	SPARE			20	1	0	360						1	20	12	Z	M TF-W	92																					
93	SPARE			20	1				0	696	0	500	1	20	12	Z	BAS PANEL	94																					
95	SPARE			20	1								1	20	12	Z	N DOOR ACTUATOR	96																					
97	SPARE			20	1	0	500						1	20	12	Z	EQUIPPED SPACE	98																					
99	EQUIPPED SPACE					1			0	0	0	0	1				EQUIPPED SPACE	100																					
101	EQUIPPED SPACE					1							1				EQUIPPED SPACE	102																					
103	EQUIPPED SPACE					1	0	0					1				EQUIPPED SPACE	104																					
105	EQUIPPED SPACE					1			0	0	0	0	1				EQUIPPED SPACE	106																					
107	EQUIPPED SPACE					1							1				EQUIPPED SPACE	108																					
TOTAL LOAD (VA):							30937 VA		28054 VA		33397 VA																												
TOTAL AMPS:							262 A		234 A		262 A																												
LOAD TYPE										PANELBOARD TOTALS																													
EXISTING LOAD (E)										TOTAL CONNECTED LOAD										94563 VA																			
COOLING (C)										2080 VA										TOTAL NEC LOAD										89247 VA									
HEATING (H)										0 VA																													
LIGHTING (L)										0 VA																													
RECEPTALS (R)										26180 VA										TOTAL CONNECTED CURRENT										262 A									
MOTORS (M)										22325 VA										TOTAL NEC DEMAND CURRENT										248 A									
SUPPLEMENTAL HEAT (U)										0 VA																													
MISC EQUIP (Z)										32882 VA																													
REFRIGERATION (F)										0 VA																													
SIGNAGE (S)										0 VA																													
KITCHEN (K)										0 VA																													
LARGEST MOTOR										11096 VA																													
SHOW WINDOW (W)										0 VA																													
TRACK LIGHTING										0 VA																													







ONE-LINE DIAGRAM GENERAL NOTES:

- THE INFORMATION SHOWN IN THE SHORT-CIRCUIT AND VOLTAGE DROP CALCULATIONS SCHEDULE IS SHOWN FOR CALCULATION PURPOSES ONLY. CONTRACTOR SHALL NOT USE THE CONDUIT TYPES, CONDUCTOR TYPES, SIZES, QUANTITIES OR LENGTHS FOR TAKEOFFS OR BIDDING PURPOSES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY CONFLICTS BETWEEN THIS SCHEDULE AND OTHER PORTIONS OF THE CONSTRUCTION DOCUMENTS. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY AS-BUILT CONDITIONS THAT CONSTITUTE A CHANGE FROM WHAT IS SHOWN BELOW. THIS INCLUDES CONDUCTOR LENGTHS DIFFERING BY MORE THAN 10%.
- REFER TO THE SHORT-CIRCUIT AND VOLTAGE DROP CALCULATIONS TABLE ON THIS SHEET. AVAILABLE FAULT CURRENT INFORMATION IS LISTED UNDER THE "FAULT CURRENT" COLUMN. VOLTAGE DROP VALUES ARE LISTED UNDER THE "CUMULATIVE VOLTAGE DROP" COLUMN. THE AVAILABLE 3-PHASE SYMMETRICAL FAULT CURRENT, ALL SERIES RATED EQUIPMENT SHALL BE PROPERLY LISTED AND LABELED PER CODE.
- FEEDER NUMBER DESIGNATIONS PRECEDED BY "V" INDICATE THAT THE CONDUCTORS ARE UP-SIZED DUE TO VOLT-DROP CONSIDERATIONS. PROVIDE LUG ADAPTERS AS NEEDED IN ORDER TO PROPERLY LAND CONDUCTORS AT TERMINATIONS(S).
- CONDUCTOR TYPES ARE BASED ON COPPER (CU) THHN/THWN-2 INSULATION, UNLESS NOTED OTHERWISE. CONDUIT SIZES SHOWN ARE APPROPRIATE FOR SCHEDULE 40 PVC, EMT, GRS, IMC AND RMC; ADJUST SIZE AS NEEDED FOR OTHER RACEWAY TYPES. ALL CONDUCTOR SIZES ARE BASED ON 75 DEG C RATED TERMINATIONS, UNLESS NOTED OTHERWISE. FOR ANY OTHER CONDITIONS MODIFY SIZES PER CODE. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.
- INSTALL FEEDERS OVERHEAD AS HIGH AS PRACTICABLE AND ORTHOGONALLY ALONG BUILDING STRUCTURE UNLESS NOTED OTHERWISE. COORDINATE FINAL ROUTINGS WITH OTHER TRADES.
- PROVIDE A PERMANENT LABEL ON FRONT OF EQUIPMENT ENCLOSURE; REFER TO SPECIFICATIONS FOR LABEL REQUIREMENTS. LABEL SHALL READ AS FOLLOWS (INCLUDE RESPECTIVE NAMES IN BLANKS):

SERVICE EQUIPMENT LABEL:

EXAMPLE:  
208Y/120V, 60HZ  
800A  
SCCR = 65,000A  
MAX AVAILABLE FAULT CURRENT = 58,815A  
CALCULATED: 01/01/2018

PANELBOARD/SWITCHBOARD LABEL:  
LINE 1: PANELBOARD " " SUPPLIED BY UPSTREAM  
LINE 2: PANELBOARD/SWITCHBOARD " "  
LINE 3: LOCATED IN " "  
LINE 4: PANELBOARD " " SUPPLIES DOWNSTREAM  
LINE 5: PANELBOARD(S) " "

TRANSFORMERS LABEL:  
LINE 1: TRANSFORMER " " SUPPLIED BY UPSTREAM  
LINE 2: PANELBOARD/SWITCHBOARD " "  
LINE 3: LOCATED IN " "  
LINE 4: TRANSFORMER " " SUPPLIES DOWNSTREAM  
LINE 5: PANELBOARD(S) " "

ELECTRICAL UTILITY CONTACT NOTE:

UTILITY COMPANY: EVERGY  
UTILITY CONTACT: PHILLIP INGRAM  
PHONE: 816-347-4339  
EMAIL: PHILLIP.INGRAM@EVERGY.COM

OVERCURRENT PROTECTIVE DEVICE COORDINATION STUDY GENERAL NOTE:

CONTRACTOR SHALL PROVIDE AN OVERCURRENT PROTECTIVE DEVICE COORDINATION STUDY TO DETERMINE THE CORRECT SETTINGS FOR THE ADJUSTABLE TRIP CIRCUIT BREAKERS TO DOCUMENT ARC-FLASH HAZARDS, PROVIDE ALL NECESSARY AS-BUILT INFORMATION REQUIRED FOR COMPLETION OF THE STUDY TO THE ENGINEER DOING THE STUDY. PROVIDE SUBMITTALS INDICATED WITHIN THE SPECIFICATIONS TO OWNER AND ARCHITECT/ENGINEER TO CONFIRM STUDY HAS BEEN COMPLETED. CONTRACTOR SHALL INCLUDE THE COST FOR THIS WORK IN THEIR BID. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.

FAULT CURRENT GENERAL NOTE (ESTIMATED VALUE):

THE MAXIMUM AVAILABLE 3-PHASE SYMMETRICAL FAULT CURRENT VALUE AT THE UTILITY TRANSFORMER SECONDARY/POINT OF SERVICE COULD NOT BE DETERMINED AT THE TIME OF THIS SUBMITTAL. THE ESTIMATED WORST CASE VALUE OF 23,131A IS BASED ON AN INFINITE BUS CALCULATION AT THE UTILITY TRANSFORMER. CONTRACTOR SHALL VERIFY ACTUAL AVAILABLE FAULT CURRENT VALUE WITH UTILITY PRIOR TO BEGINNING CONSTRUCTION. NOTIFY ENGINEER IF ACTUAL VALUE EXCEEDS ESTIMATED CALCULATED VALUE. ESTIMATED DESIGN VALUE IS BASED ON THE FOLLOWING:


UTILITY TRANSFORMER SECONDARY VOLTAGE: 480V  
UTILITY TRANSFORMER SIZE: 2000 KVA, 3PH 4W

ONE-LINE DIAGRAM GENERAL NOTES:

- COORDINATE WORK WITH ARCHITECTURAL PHASING DRAWINGS TO PROPERLY STAGE TRANSITION TO PROVIDE POWER TO EXISTING, NEW AND TEMPORARY LOADS. MONITOR LOADS ON DISTRIBUTION SYSTEM TO MAKE SURE SHIFTING OF LOADS DOES NOT OVERLOAD ELECTRICAL EQUIPMENT.
- PRIOR TO BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY THE EXISTING AIS/SCSR RATING OF EACH PANELBOARD/SWITCHBOARD. ALL NEW AND EXISTING OVER-CURRENT PROTECTION DEVICES (CIRCUIT BREAKERS AND FUSES) MUST HAVE AN AIS/SCSR RATING EXCEEDING THE AVAILABLE FAULT CURRENT AT THAT POINT IN THE SYSTEM. NOTIFY THE OWNER AND THE ENGINEER IF THE EXISTING EQUIPMENT DOES NOT COMPLY WITH THIS REQUIREMENT.
- VERIFY THE INTEGRITY OF THE EXISTING GROUNDING ELECTRODE SYSTEM AND THAT THE NEUTRAL AND GROUND ARE PROPERLY BONDED TOGETHER AT THE POINT OF SERVICE ENTRANCE. NOTIFY THE LANDLORD, OWNER AND THE ENGINEER OF ANY EXISTING DEFICIENCIES.

ONE-LINE DIAGRAM SUPPLEMENTAL SPECIFICATIONS:

- GROUNDING ELECTRODE SYSTEM SHALL BE PER LOCAL REQUIREMENTS AND SHALL NOT BE LESS STRINGENT THAN THAT SPECIFIED IN THE CONSTRUCTION DOCUMENTS.
- PROVIDE PROPERLY SIZED LUGS FOR ALL EQUIPMENT. CIRCUIT BREAKERS, AND OTHER ELECTRICAL DEVICES TO ACCOMMODATE INSTALLED CONDUCTORS, A LARGER FRAME, OVERSIZED LUGS OR NON-STANDARD PRODUCT MAY BE REQUIRED IN SOME INSTANCES. UTILIZE PIN ADAPTERS ONLY IF NECESSARY AND ONLY AS ALLOWED BY MANUFACTURER AND AHJ.
- PROVIDE ANY AVAILABLE SPACE IN SWITCHBOARDS/PANELBOARDS WITH BUSSING.
- PROVIDE TYPED FINAL CIRCUIT DIRECTORY FOR ALL PANELBOARDS TO REFLECT ACTUAL AS-BUILT CONDITIONS. COORDINATE FINAL ROOM NAMES, NUMBERS AND DESCRIPTIONS WITH OWNER PRIOR TO COMPLETION. CIRCUIT DESCRIPTIONS SHALL BE PER CODE AND SHALL BE DISTINGUISHABLE FROM ALL OTHERS.



DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

FEEDER SCHEDULE:

SIZES ARE BASED ON COPPER (CU) THHN/THWN-2 INSULATION, UNO. ALL CONDUCTOR SIZES ARE BASED ON 75 DEG C RATED TERMINATIONS, UNO. CONDUIT SIZES SHOWN ARE APPROPRIATE FOR SCHEDULE 40 PVC, EMT, GRS, IMC AND RMC; ADJUST SIZE AS NEEDED FOR OTHER RACEWAY TYPES. FOR ANY OTHER CONDITIONS MODIFY SIZES PER CODE. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.

FEEDER TAG	FEEDER DESCRIPTION
173	(3) #2/0, (1) #6 G, 1-1/2" C
203	(3) #3/0, (1) #6 G, 2" C
ETR	UNKNOWN FEEDER - EXISTING TO REMAIN
G10	#10 COPPER GROUND, 3/4" C
S3004	EXISTING (8) 3" C, EACH W/ (4) 500 kcmil
T403	(2) 2" C, EACH W/ (3) #3/0, (1) #4 SSBJ
T404	(2) 2" C, EACH W/ (4) #3/0, (1) #4 SSBJ
V202	(2) #300kcmil, (1) #3 G, 2-1/2" C
V404C	(2) 3" C, EACH W/ (4) 300 kcmil, (1) #1/0 G

LOAD SUMMARY: MSB-W

PANEL DESCRIPTION: 480Y/277 V			
LOAD TYPE	CONNECTED LOAD KVA	DEMAND FACTOR	NEC DEMAND KVA
EXISTING PEAK UTILITY (@ 0.9 pf)	747.78	125%	934.72
COOLING (C)	0.00	0%	0.00
HEATING (H)	0.00	100%	0.00
LIGHTING (L)	5.91	125%	7.38
RECEPTACLES (R)	0.00	0%	0.00
MOTORS (M)	0.00	100%	0.00
SUPPLEMENTAL HEAT (U)	0.00	100%	0.00
MISC EQUIP (Z)	0.04	100%	0.04
REFRIGERATION (F)	0.00	100%	0.00
SIGNAGE (S)	0.00	125%	0.00
KITCHEN (K)	0.00	100%	0.00
LARGEST MOTOR	0.00	125%	0.00
SHOW WINDOW (W)	0.00	125%	0.00
TRACK LIGHTING	0.00	100%	0.00
EXISTING LOAD TO BE DELETED	0.00	100%	0.00
ELEVATOR (V)	0.00	100%	0.00
TOTAL LOAD	753.72	KVA	942.14
TOTAL AMPACITY	906.59	AMPS	1133.23
PANEL AMPACITY		AMPS	3000.00
SPARE CAPACITY		AMPS	1866.77
*PER UTILITY COMPANY BILLING PEAK DEMAND OF:		673.00 KW	9/2021

1 ELECTRICAL PARTIAL ONE-LINE DIAGRAM - LSW NTS

Short-Circuit and Voltage Drop Calculations

Distances are for calculation purposes only and shall not be used for contractor takeoffs nor bidding - Contractor shall notify Engineer of any field condition that results in a change of 10% or greater circuit distance

The following calculations are based on the "Point-by-Point" method where:  
ISC (2) = ISC(1) x M(1)  
ISC (1) = short circuit current at fault point 1  
ISC (2) = short circuit current at fault point 2

E = Line to line volts  
IP = Primary short circuit current  
Vp = Primary voltage  
IS = Secondary short circuit current  
Vst = Secondary voltage  
L = Length of circuit  
C = "C" Factor from Bussman table where "C" = 1 / impedance per linear foot

Feeder Types: NM - Non Magnetic Conduit, M - Magnetic Conduit, FB - Feeder Busway, PB - Plug-in Busway, TX - Transformer

System Voltage: 480Y/277V - 3 phase															Date of Calculations: 09/07/2022															
Fault Point (F#)	Bus/Feeder Description	Source (Fault Point)	Phase	Source Isc (amps)	Conduit Type	Material	Feeder Quantity of Parallel Sets and Bus/Phase & Neutral Size	Conductor 'C' Value	Busway 'C' Value	L-L Voltage (E)	Circuit Length (L)	Load Power Factor (pf)	Circuit Load (Amperage)	Resistance (R)	Conductor Reactance (X)	Arccos (pf) (Radians)	Type	Degree Rise	kVA	Transformer New Xfmr Z	Transformer Existing Xfmr Z	Secondary Voltage	Tap Setting	f	M	Fault Current (amps)	Voltage Drop (%VD)	Cumulative Voltage Drop (%VD)	Fault Point (F#)	
1	Utility Service Point			23,131	at the secondary of the utility transformer										Source Isc + 6 Motor Contribution = 26,011															
Motor Contribution																														
2	MSB (LSW)	1	3	26,011	NM	CU	8 Set(s) of 500 kcmil	26706	--	480	180	0.9	1,000	0.000027	0.000039	0.451027									0.079	0.93	24,105	-0.34%	-0.34%	2
3	HW	2	3	24,105	M	CU	2 Set(s) of 300 kcmil	18177	--	480	435	0.9	230	0.000045	0.000051	0.451027									1.041	0.49	11,812	-1.13%	-1.47%	3
4	TO TX-L1W	3	3	11,812	M	CU	1 Set(s) of 1 AWG	7293	--	480	10	0.9	230	0.000160	0.000057	0.451027									0.058	0.94	11,159	-0.14%	-1.61%	4
5	TX-L1W	4	3	11,159	TX					480							DOE	150	75	3.61			208		4.466	0.16	4.712	-1.61%	-1.61%	5
6	L1W	5	3	4,712	M	CU	1 Set(s) of 40 AWG	15082	--	208	10	0.9	240	0.000063	0.000051	0.451027									0.026	0.97	4,592	-0.16%	-1.77%	6
7	RTU-1W	3	3	11,812	M	CU	1 Set(s) of 8 AWG	1557	--	480	75	0.85	38	0.000780	0.000065	0.554811									2.053	0.33	3,869	-0.72%	-2.18%	7
8	RTU-2W	3	3	11,812	M	CU	1 Set(s) of 8 AWG	1557	--	480	50	0.85	28	0.000780	0.000065	0.554811									1.369	0.42	4,967	-0.35%	-1.82%	8
9	TO TX-MC	2	1	24,105	M	CU	1 Set(s) of 300 kcmil	18177	--	480	435	0.9	142	0.000045	0.000051	0.451027									2.404	0.29	7,062	-1.61%	-1.95%	9
10	TX-MC	9	1	7,062	TX					480							DOE	150	75	5.7			240		2.584	0.28	3.953	-1.95%	-1.95%	10
11	TX-MC DISC	10	1	3,953	M	CU	2 Set(s) of 30 AWG	12844	--	240	10	0.9	282	0.000079	0.000052	0.451027									0.013	0.99	3,903	-0.11%	-2.06%	11
12	MODULAR CLASSROOM 1	11	1	3,903	M	CU	1 Set(s) of 30 AWG	12844	--	240	28	0.9	141	0.000079	0.000052	0.451027									0.071	0.93	3,844	-0.31%	-2.37%	12
13	MODULAR CLASSROOM 2	11	1	3,903	M	CU	1 Set(s) of 30 AWG	12844	--	240	80	0.9	141	0.000079	0.000052	0.451027									0.203	0.93	3,245	-0.88%	-2.94%	13



LSR7 Robotics, GiC & Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

owner:  
Lee's Summit 8-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

FIRE ALARM SCOPE NOTES:

1. FIRE ALARM SCOPE AT LSN AND LSW BOTH INCLUDES THE MODIFICATION OF THE EXISTING FIRE ALARM SYSTEM. PROVIDE NEW EMERGENCY VOICE ALARM NOTIFICATION IN THE NEW LSSD ROBOTICS FACILITY IN ACCORDANCE WITH NFPA 72 AND ANY LOCAL LAWS.

FIRE ALARM GENERAL NOTES:

1. PRIOR TO SUBMITTING BID, VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH THE EXISTING CONDITIONS OF THE PROJECT. REVIEW THE GENERAL NOTES, SPECIFICATIONS AND OTHER DRAWINGS FOR ADDITIONAL REQUIREMENTS WHICH MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY ARCHITECT, ENGINEER AND/OR OWNER OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
2. SYSTEM DESIGN, INSTALLATION AND MATERIALS SHALL BE IN ACCORDANCE WITH APPLICABLE NFPA STANDARDS. SYSTEM SHALL ALSO MEET ALL APPLICABLE BUILDING CODES, FIRE CODES AND THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION AND INSURANCE CARRIER. VERIFY REQUIREMENTS PRIOR TO BID SUBMITTAL.
3. INFORMATION ON CONTRACT DOCUMENTS IS GENERAL. INFORMATION AND FOR BID PURPOSES ONLY. CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR THE FINAL SYSTEM DESIGN AND LAYOUT OF ALL COMPONENTS, COORDINATION WITH ALL OTHER TRADES, AND SYSTEM CALCULATIONS REQUIRED FOR APPROVAL BY THE AUTHORITY HAVING JURISDICTION, ENGINEER, AND OWNER'S INSURER.
4. THE CONTRACTOR SHALL FOLLOW THE ENGINEER OF RECORD'S SYSTEM DESIGN AND LAYOUT OF ALL COMPONENTS EXCEPT WHERE MODIFICATION TO THE DESIGN IS NECESSARY. MODIFICATIONS SHALL BE REFLECTED IN THE CONTRACTOR'S SHOP DRAWINGS AND CALCULATIONS.
5. DEVIATIONS FROM ENGINEER'S DESIGN WILL NOT BE CONSIDERED UNLESS A FORMALLY SUBMITTED RFIS RECEIVED AND APPROVED.
6. THE CONTRACTOR SHALL PROVIDE ALL EQUIPMENT AND LABOR REQUIRED FOR A COMPLETE AND OPERATIONAL SYSTEM AS INDICATED IN THE DRAWINGS AND SPECIFICATIONS.
7. WHERE EXISTING SYSTEMS ARE PRESENT, CONTRACTOR SHALL MODIFY, RELOCATE AND/OR PROVIDE ADDITIONAL EQUIPMENT AS REQUIRED FOR SCOPE OF WORK AS REQUIRED FOR A COMPLETE AND OPERATIONAL SYSTEM. COORDINATE WITH WALLS, CEILINGS, LIGHTS, DIFFUSERS, STRUCTURE, OBSTRUCTIONS, ETC. IN AREAS AFFECTED BY SCOPE OF WORK, NEW EQUIPMENT SHALL BE COMPATIBLE WITH EXISTING SYSTEMS. CONTRACTOR SHALL REMOVE ALL ABANDONED EQUIPMENT. COORDINATE SYSTEM MODIFICATIONS TO MINIMIZE SYSTEM IMPAIRMENT, AND PROVIDE FIRE WATCH AND/OR INTERIM FIRE PROTECTION MEASURES WHERE REQUIRED BY THE AUTHORITY HAVING JURISDICTION, INSURANCE CARRIER OR OWNER.
8. PROVIDE ADDITIONAL MATERIALS AND LABOR REQUIRED DUE TO LACK OF COORDINATION OR TO MEET AUTHORITY HAVING JURISDICTION AND INSURANCE CARRIER REQUIREMENTS AT NO ADDITIONAL COST TO THE OWNER.
9. FORWARD COMPLETED CERTIFICATE OF COMPLETION AND CONTRACTOR MATERIAL TEST CERTIFICATES TO THE OWNER.
10. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.

FIRE ALARM GENERAL DEMOLITION NOTES:

1. COORDINATE ALL DEMOLITION WITH WHAT IS SHOWN ON ARCHITECTURAL PLANS. NOTIFY ARCHITECT OF ANY DISCREPANCIES.
2. COORDINATE NEW WORK AND DEMOLITION WITH OTHER DISCIPLINES AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION.
3. PRIOR TO SUBMITTING BID, VISIT THE JOB SITE AND BECOME FULLY ACQUAINTED WITH THE EXISTING CONDITIONS OF THE PROJECT. REVIEW GENERAL NOTES, SPECIFICATIONS AND OTHER DRAWINGS FOR ADDITIONAL REQUIREMENTS THAT MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY ARCHITECT, ENGINEER OR OWNER, AS DEFINED IN BID DOCUMENTS, OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID. ADDITIONAL COMPENSATION WILL NOT BE PAID FOR LACK OF SUCH DETERMINATION, FAMILIARIZATION, AND/OR ALLOWANCE.
4. EXISTING CONDITIONS WERE TAKEN FROM ORIGINAL DRAWINGS AND SITE VISITS AND MAY NOT REFLECT EXACT "AS-BUILT" CONDITIONS. FIELD VERIFY EXISTING CONDITIONS PRIOR TO SUBMITTING FINAL BIDS. COORDINATE NEW WORK AND DEMOLITION WITH OTHER DISCIPLINES AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION.
5. OWNER RETAINS RIGHTS OF SALVAGE FOR EQUIPMENT AND FIXTURES TO BE REMOVED. COORDINATE WITH THE OWNER THE EQUIPMENT AND FIXTURES TO BE SALVAGED AND THE LOCATION FOR STORAGE. AVOID DAMAGE TO EQUIPMENT DURING DEMOLITION WORK AND DURING TRANSPORT TO OWNER'S DESIGNATED STORAGE LOCATION. PROPERLY DISPOSE OF MATERIALS THAT ARE REMOVED AND ARE NOT REQUESTED TO BE SALVAGED BY THE OWNER.
6. EQUIPMENT TO BE REMOVED SHALL BE KEPT FOR REINSTALLATION DURING THE CONSTRUCTION PHASE WHEN POSSIBLE AND/OR INDICATED ON THE DRAWINGS. AVOID DAMAGING EXISTING SURFACES AND EQUIPMENT TO REMAIN FOR NEW INSTALLATION. REPAIR ANY DAMAGE CAUSED DURING WORK AT NO EXTRA COST TO THE OWNER.
7. SEAL PENETRATIONS THROUGH FLOORS, WALLS, CEILINGS AND ROOFS WHERE COMPONENTS ARE REMOVED AND WHERE THE EXISTING PENETRATION IS NOT USED FOR THE NEW INSTALLATION. REPAIR DAMAGED SURFACES TO MATCH ADJACENT AREAS OR AS INDICATED ON THE ARCHITECTURAL DRAWINGS.
8. PERFORM ALL WORK ACCORDING TO THE PHASING SCHEDULE FOR THIS PROJECT. PROVIDE ALL TEMPORARY DESIGN AND/OR CONFIGURATIONS THAT MEET APPLICABLE CODE REQUIREMENTS AS NECESSARY TO CONFORM TO THE REQUIRED CONSTRUCTION PHASING OF THE PROJECT.
9. ONLY THE PORTIONS OF THE BUILDING AFFECTED BY THE SCOPE OF THE PROJECT HAVE BEEN SHOWN. INFORMATION SHOWN AS EXISTING TO REMAIN IS NOT BEING MODIFIED AS A PART OF THIS PROJECT.
10. ALL WORK SHALL BE PERFORMED SO AS TO NOT INTERRUPT SERVICE. THE CONTRACTOR SHALL PROPERLY NOTIFY THE BUILDING OWNER, LANDLORD, THE LEASER AND ADJACENT TENANTS AS APPLICABLE A MINIMUM OF 48 HOURS IN ADVANCE BEFORE PROCEEDING WITH THIS WORK.
11. REMOVE ALL UNUSED AND DEMOLISHED EQUIPMENT AND ASSOCIATED MATERIALS FROM SITE. ABANDONING UNUSED PORTIONS WILL NOT BE ACCEPTABLE.
12. SYSTEM(S) NOT ASSOCIATED WITH THE DEMOLITION SHALL BE LEFT IN SERVICE AS APPLICABLE.
13. INSPECT EXISTING EQUIPMENT TO REMAIN TO VERIFY THAT EQUIPMENT IS OPERATING PROPERLY. NOTIFY OWNER OF DAMAGED AND/OR MALFUNCTIONING COMPONENTS.
14. ALL SYSTEMS TO BE LEFT IN SERVICE PRIOR TO THE END OF EACH WORKDAY.

FIRE PROTECTION SYMBOLS

THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS OR ABBREVIATIONS ARE USED. V2.02

ABBREVIATIONS		FIRE ALARM	
AF	ABOVE FINISHED FLOOR	FA	FIRE ALARM CONTROL PANEL/UNIT
AFG	ABOVE FINISHED GRADE	FAAP	RECESSED FIRE ALARM CONTROL PANEL/UNIT
CD	CANDELA	FAAP	FIRE ALARM ANNUNCIATOR PANEL
DI	DUCTILE IRON	FAAP	RECESSED FIRE ALARM ANNUNCIATOR PANEL
ESFR	EARLY SUPPRESSION	AMP	AMPLIFIER PANEL
ETR	FAST RESPONSE	RPS	REMOTE POWER SUPPLY
FHC	EXISTING TO REMAIN	RT	REMOTE TEST STATION WITH INDICATING LIGHT
FP	FIRE PROTECTION	RT	REMOTE INDICATING LIGHT
GC	FIRE HOSE CABINET	PS	PRESSURE SWITCH LOW/HIGH
GPM	GALLONS PER MINUTE	FS	WATERFLOW ALARM SWITCH
JB/J-BOX	JUNCTION BOX	VT	CONTROL VALVE TAMPER SWITCH
MAX	MAXIMUM	DN	MAGNETIC DOOR HOLD OPEN DEVICE
MIN	MINIMUM	CM	CONTROL MODULE
N/A	NOT APPLICABLE	MM	MONITOR MODULE
WP	WEATHERPROOF	K	FIRE DEPARTMENT KEY BOX
		F	PULL STATION
		F	FIREFIGHTER'S PHONE JACK
		⬇	HEAT DETECTOR (E INDICATES ELEVATOR RECALL)
		①	SMOKE DETECTOR (E INDICATES ELEVATOR RECALL)
		①	SINGLE STATION SMOKE DETECTOR
		①	PROJECTED BEAM SMOKE DETECTOR
		①	DUCT MOUNTED SMOKE DETECTOR (SD=SUPPLY/RD=RETURN)
		①	CARBON MONOXIDE DETECTOR
		①	AREA OF REFUGE 2-WAY COMMUNICATION SYSTEM
		①	WALL MOUNTED AUDIBLE NOTIFICATION APPLIANCE #W INDICATES WATTAGE (VOICE EVACUATION SYSTEMS ONLY)
		①	WALL MOUNTED VISIBLE NOTIFICATION APPLIANCE ## INDICATES CANDELA
		①	WALL MOUNTED AUDIBLE/VISIBLE NOTIFICATION APPLIANCE ## INDICATES CANDELA #W INDICATES WATTAGE (VOICE EVACUATION SYSTEMS ONLY)
		①	CEILING MOUNTED AUDIBLE NOTIFICATION APPLIANCE #W INDICATES WATTAGE (VOICE EVACUATION SYSTEMS ONLY)
		①	CEILING MOUNTED VISIBLE NOTIFICATION APPLIANCE ## INDICATES CANDELA
		①	CEILING MOUNTED AUDIBLE/VISIBLE NOTIFICATION APPLIANCE ## INDICATES CANDELA #W INDICATES WATTAGE (VOICE EVACUATION SYSTEMS ONLY)
		①	END OF LINE RESISTOR
		①	ABORT SWITCH
		①	BELL

STANDARD MOUNTING HEIGHTS

AUDIBLE APPLIANCE (TOP OF APPLIANCE)	90"
FIRE ALARM ANNUNCIATOR PANEL (TOP OF DISPLAY)	60"
FIRE ALARM BELL (EXTERIOR) (CENTERLINE)	120"
FIRE ALARM CONTROL PANEL/UNIT (TOP OF DISPLAY)	60"
PULL STATION (TOP OF DEVICE)	48"
VISIBL APPLIANCE (CENTERLINE)	84"

INSTALL DEVICES AT THE MOUNTING HEIGHTS SHOWN ABOVE UNO IN THE CONSTRUCTION DOCUMENTS. MOUNTING HEIGHTS LISTED ABOVE, OR ELSEWHERE IN THE CONSTRUCTION DOCUMENTS, ARE AFF OR AFG. UNO, ALL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH CURRENT ADA AND LOCAL REQUIREMENTS.


CALL OUTS

ENLARGED PLAN CALLOUT	
NOT IN SCOPE	

LINETYPE LEGEND

THROUGHOUT THE DRAWINGS DIFFERENT LINETYPES ARE USED IN COMBINATION WITH THE SYMBOLS TO INDICATE THE STATUS OF ITEMS AS EXISTING, TO BE DEMOLISHED, TO BE INCLUDED AS PART OF NEW WORK AND/OR ITEMS WHICH ARE ANTICIPATED TO BE PROVIDED IN THE FUTURE. THE STATUS OF ITEMS USING THESE LINETYPES ARE RELATIVE TO THE VIEW IN WHICH THEY APPEAR. PHASING SHOWN IN DRAWINGS IS NOT INTENDED TO FULLY DESCRIBE ALL NECESSARY CONSTRUCTION PHASING, WHICH IS DETERMINED BY THE CONTRACTOR AS PART OF THEIR RESPONSIBILITIES. ANY SUCH PHASES DESCRIBED IN THE CONSTRUCTION DOCUMENTS ARE GENERAL AND ONLY INTENDED TO INDICATE A BROAD ORDER FOR THE SAKE OF DESCRIBING THE PROJECT. THE FOLLOWING LINETYPES MAY BE USED ON ANY DEVICE, EQUIPMENT, NOTE, LINE, SHAPE, ETC.

EXISTING	NEW
DEMOLISH	FUTURE



③ FIRE ALARM RISER DIAGRAM - ADDRESSABLE SYSTEM (VOICE) NTS



CHRISTOPHER J. CULP  
LICENSE # PE-201937646  
09/08/2022

FIRE ALARM GENERAL NOTES AND LEGEND  
FA000



**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect: Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer: Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/T/Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com



8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM  
2150005255  
MO. CORPORATE NO. E-558D  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

**Revisions**

NUMBER	DESCRIPTION	DATE
--------	-------------	------




CHRISTOPHER J. CULP  
LICENSE # PE-2013037646  
09/08/2022

**FIRE ALARM PLAN**  
**FA101**

**FIRE ALARM PLAN NOTES:**

- F1 PROVIDE REMOTE POWER SUPPLY TO POWER VISIBLE NOTIFICATION APPLIANCES.  
F3 PROVIDE DUCT MOUNTED SMOKE DETECTOR FOR FAN POWERED MECHANICAL AIR HANDLING EQUIPMENT SHUTDOWN. INSTALL DETECTOR PER MANUFACTURER'S RECOMMENDATIONS. REFER TO MECHANICAL SHEETS FOR EQUIPMENT AND DUCTWORK LAYOUT AND DETAILS.  
F5 PROVIDE LOW VOLTAGE WIRING FROM DUCT DETECTOR TO REMOTE TEST STATION. MOUNT REMOTE TEST STATION IN CEILING.  
F6 PROVIDE A CARBON MONOXIDE DETECTOR IN ROOMS CONTAINING FIRST DIFFUSER FROM GAS POWERED AIR HANDLING UNITS. CARBON MONOXIDE DETECTOR SHALL EMIT A LOCAL ALARM TONE UPON DETECTION OF CARBON MONOXIDE.  
F7 PROVIDE NEW FIRE ALARM VOICE AMPLIFIER PANEL.

**FIRE ALARM PLAN - LSN**  
3/16" = 1'-0"



**FIRE ALARM PLAN - LSW**  
3/16" = 1'-0"





## TELECOMMUNICATIONS SYMBOLS

THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS OR ABBREVIATIONS ARE USED.

### STANDARD MOUNTING HEIGHTS

TELECOM BACKBOARD (BOTTOM OF BACKBOARD)	4"
LADDER RACK IN TELECOM ROOMS (BOTTOM OF DEVICE)	90"
CABLE TRAY / CONDUIT AFC (BOTTOM OF PATHWAY)	3"(MIN)
LIGHT FIXTURE IN TELECOM ROOMS (BOTTOM OF DEVICE)	108"(MIN)
TELEPHONE WALL OUTLET (CENTERLINE)	48"
DATA WALL OUTLET	SAME AS ADJACENT DEVICE; UNO
TELEVISION OUTLET	REFER TO ARCH DRAWINGS
TMGB/TGB (CENTERLINE)	84"
WALL CLOCK (CENTERLINE)	84"
INTERCOM (CENTERLINE)	48"

USE THE DEFAULT MOUNTING HEIGHTS SHOWN ABOVE UNO IN THE CONSTRUCTION DOCUMENTS. MOUNTING HEIGHTS LISTED ARE ABOVE FINISHED FLOOR (AFF) OR ABOVE FINISHED GRADE (AFG) TO BOTTOM OF OUTLET BOX. ALL DEVICES SHALL BE INSTALLED IN COMPLIANCE WITH CURRENT ADA AND LOCAL REQUIREMENTS.

### ABBREVIATIONS

A AMPERES	LAN LOCAL AREA NETWORK
ADA AMERICANS WITH DISABILITIES ACT	LCC LIMITED COMBUSTIBLE CABLE
AFC ABOVE FINISHED CEILING	LEC LOCAL EXCHANGE CARRIER
AFF ABOVE FINISHED FLOOR	LED LIGHT-EMITTING DIODE
AFG ABOVE FINISHED GRADE	LF LINEAR FEET
AHJ AUTHORITY HAVING JURISDICTION	MAN METROPOLITAN AREA NETWORK
ANISI AMERICAN NATIONAL STANDARDS INSTITUTE	MATV MASTER ANTENNA TELEVISION
AP ACCESS POINT	MC MAIN CROSS-CONNECT
AV AUDIO-VIDEO	MD MAIN DISTRIBUTION FRAME
AWG AMERICAN WIRE GAUGE	MFR MANUFACTURER
BAS BUILDING AUTOMATION SYSTEM	MH MAINTENANCE HOLE
BBC BACKBONE BONDING	MM MULTIMODE
BD BUILDING DISTRIBUTOR	MPE MAIN POINT OF ENTRANCE
BDF BUILDING DISTRIBUTION FRAME	MPO MAIN POINT OF PRESENCE
BFC BELOW FINISHED CEILING	MTD MOUNTED
C CONDUIT	N/A NOT APPLICABLE
CAT CATEGORY	NEC NATIONAL ELECTRICAL CODE
CATV COMMUNITY ANTENNA TELEVISION	NFPA NATIONAL FIRE PROTECTION ASSOCIATION
CCTV CLOSED CIRCUIT TELEVISION	NIC NOT IN CONTRACT
CD CAMPUS DISTRIBUTOR	nm NANOMETER
CMP COMMUNICATIONS PLENUM JACKET	NRTL NATIONAL RECOGNIZED TESTING LAB
CMR COMMUNICATIONS RISER JACKET	OC OCCUPATIONAL SAFETY AND HEALTH
das DISTRIBUTED ANTENNA SYSTEM	OSP OUTSIDE PLANT
dB DEIBELS	PBB PRIMARY BONDING BUSBAR
DEMO DEMOLITION	PBX PRIVATE BRANCH EXCHANGE
(E) EXISTING	PDE POWER OVER ETHERNET
EC ELECTRICAL CONTRACTOR	PON PASSIVE OPTICAL NETWORK
ECIA ELECTRONIC COMPONENTS INDUSTRY ASSOCIATION	POTS PLAIN OLD TELEPHONE SERVICE
EMI ELECTROMAGNETIC INTERFERENCE	PSSTN PUBLIC SWITCHED TELEPHONE NETWORK
EMS ENERGY MANAGEMENT SYSTEM	QTY QUANTITY
EMT ELECTRICAL METALLIC TUBING	RCDD REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
ER EQUIPMENT ROOM	RMC RIGID METAL CONDUIT
ETR EXISTING TO REMAIN	RU RACK UNIT
FAAP FIRE ALARM ANNUNCIATOR PANEL	SBB SECONDARY BONDING BUSBAR
FACP FIRE ALARM CONTROL PANEL	SCS STRUCTURED CABLING SYSTEM
FD FLOOR DISTRIBUTOR	SF SQUARE FEET
FMC FLEXIBLE METAL CONDUIT	SM SINGLEMODE
FS FIRE STOP SYSTEM	SPCS SPECIFICATIONS
FLR FLOOR	TBB TELECOMMUNICATIONS BONDING BACKBONE
FUTP SCREEN TWISTED PAIR (SHIELDED)	TBD TO BE DETERMINED
GC GENERAL CONTRACTOR	TIA TELECOMMUNICATIONS INDUSTRY ASSOCIATION
GYP GYPSUM BOARD	TR TELECOMMUNICATIONS ROOM
HC HORIZONTAL CROSS-CONNECT	TYP TYPICAL
HCM HORIZONTAL CABLE MANAGER	UNO UNLESS NOTED OTHERWISE
HH HAND HOLE	UL UNDERWRITER LABORATORIES, INC.
HZ HERTZ	UPS UNINTERRUPTIBLE POWER SUPPLY
IMC INTERMEDIATE METAL CONDUIT	U/UTP UNSHIELDED TWISTED PAIR V (VOLTS)
IP INTERNET PROTOCOL	VCM VERTICAL CABLE MANAGER
ISP INTERNET SERVICE PROVIDER	W WIRE
ISP INSIDE PLANT CABLE	WAN WIDE AREA NETWORK
JB JUNCTION BOX	WAO WORK AREA OUTLET
J-BOX JUNCTION BOX	WAP WIRELESS ACCESS POINT
	WP WEATHER PROOF
	WR WEATHER RESISTANT
	WT WATERTIGHT
	XP EXPLOSION-PROOF

### ANNOTATION

①	TECHNOLOGY PLAN CALLOUT
1	EQUIPMENT DESIGNATION (OWNER FURNISHED, CONTRACTOR INSTALLED)
●	CONNECTION POINT OF NEW WORK TO EXISTING
① T1	DETAIL REFERENCE UPPER NUMBER INDICATES DETAIL NUMBER, LOWER NUMBER INDICATES SHEET NUMBER
① T1	SECTION CUT DESIGNATION
⊗	DEDICATED EQUIPMENT ACCESS TILE
⊞	ACCESS PANEL

### LINE/TYPE LEGEND

THROUGHOUT THE DRAWINGS DIFFERENT LINE-TYPES ARE USED IN COMBINATION WITH THE SYMBOLS TO INDICATE THE STATUS OF ITEMS AS EXISTING, TO BE DEMOLISHED, TO BE INCLUDED AS PART OF THE NEW WORK AND/OR ITEMS WHICH ARE ANTICIPATED TO BE PROVIDED IN THE FUTURE. THE STATUS OF ITEMS USING THESE LINE/TYPES ARE RELATIVE TO THE VIEW IN WHICH THEY APPEAR. PHASING SHOWN IN DRAWINGS IS NOT INTENDED TO FULLY DESCRIBE ALL NECESSARY CONSTRUCTION PHASING, WHICH IS DETERMINED BY THE CONTRACTOR AS PART OF THEIR RESPONSIBILITIES. ANY SUCH PHASES DESCRIBED IN THE CONSTRUCTION DOCUMENTS ARE GENERAL AND ONLY INTENDED TO INDICATE A BROAD ORDER FOR THE SAKE OF DESCRIBING THE PROJECT. THE FOLLOWING LINE/TYPES MAY BE USED ON ANY DEVICE, EQUIPMENT, NOTE, LINE, SHAPE, ETC.

EXISTING	—————	NEW	—————
DEMOLISH	- - - - -	FUTURE	- - - - -

### CABLE TYPES

A	CATEGORY 6 CABLE
B	PAGING SPEAKER CABLE
C	HDMI CABLE

### PATHWAYS

W×H	WIRE MESH CABLE TRAY (W"=WIDTH, "H"=HEIGHT)
—	VERTICAL CABLE TRAY
(#) D"	UNDERGROUND CONDUIT ("H"=QUANTITY, "D"=CONDUIT DIAMETER)
(#) D"	CONDUIT ("H"=QUANTITY, "D"=CONDUIT DIAMETER)
(#) D"	CABLE SUPPORTS OR J-HOOKS
(#) D"	CONDUIT SLEEVE ("H"=QUANTITY, "D"=CONDUIT DIAMETER)
FS	UL FIRESTOP SYSTEM ASSEMBLY
PB L"XW"XH"	PULL BOX (L"=LENGTH, W"=WIDTH, "H"=HEIGHT)
SC	SPLICE

### RISER DIAGRAMS

—	FIBER OPTIC CROSS CONNECT
⊗	COPPER UTP CROSS CONNECT
P	110-TYPE PROTECTOR BLOCK
[PATCH PANEL]	PATCH PANEL
[SBB]	SECONDARY BONDING BUSBAR (SBB)
[PBB]	PRIMARY BONDING BUSBAR (PBB)
— — — —	TELECOMMUNICATIONS BACKBONE CABLING (REFER TO RISER DIAGRAM FOR MORE INFORMATION)

### TELECOMMUNICATIONS ROOM

[LADDER RACK]	LADDER RACK
[PBB]	PRIMARY BONDING BUSBAR (PBB) - WALL ELEVATION VIEW
[SBB]	SECONDARY BONDING BUSBAR (SBB) - WALL ELEVATION VIEW
[PBB/SBB - PLAN VIEW]	PBB/SBB - PLAN VIEW
—	TELECOM BACKBOARD
[TWO-POST EQUIPMENT RACK]	TWO-POST EQUIPMENT RACK
[FOUR-POST EQUIPMENT RACK]	FOUR-POST EQUIPMENT RACK
[EQUIPMENT CABINET (REFER TO PLAN NOTES ON ENLARGED PLANS FOR MORE INFORMATION)]	EQUIPMENT CABINET (REFER TO PLAN NOTES ON ENLARGED PLANS FOR MORE INFORMATION)



### TELECOMMUNICATIONS OUTLETS

SYMBOL	DESCRIPTION	CABLE(S)			DETAIL
		A	B	C	
▽ 2D	DATA WALL OUTLET	2	0	0	7/TN400-A/B
▽ 4D	DATA WALL OUTLET	4	0	0	7/TN400-A/B
▽ 4D	DATA WALL OUTLET	4	0	0	7/TN400-A/B
◇ 2D	DATA CEILING OUTLET	2	0	0	8/TN400-A/B
▽ W.2D	TELEPHONE, VoIP WALL OUTLET	2	0	0	7/TN400-A/B

### TELECOMMUNICATIONS END-POINT DEVICES

DEVICE SCHEDULE					
SYMBOL	DESCRIPTION	CABLE(S)			DETAIL
		A	B	C	
(C) S	CLOCK, ANALOG SINGLE SIDED, WALL MOUNT	0	0	0	N/A
(S) RC	PAGING SPEAKER, RECESSED CAN CEILING MOUNT	0	1	0	5/TN400-A/B
(P)	PAGING SPEAKER, PENDANT CEILING MOUNT	0	1	0	5/TN400-A/B

### AUDIO-VIDEO IP END-POINT DEVICES

REFER TO TA-SERIES DRAWINGS FOR AV DEVICES					
SYMBOL	DESCRIPTION	CABLE(S)			DETAIL
		A	B	C	
	TELEVISION WALL OUTLET	1	0	2	9/TN400-A/B
	HDMI INTERFACE PLATE	2	0	1	8/TN400-A/B

### TELECOMMUNICATIONS RESPONSIBILITY MATRIX

Description	Furnish		Install		Comments
	Construction Team	Owner	Construction Team	Owner	
<b>General Communications</b>					
Grounding and Bonding	X		X		
Hangers and Supports	X		X		
Conduits and Backboxes	X		X		
Cable Trays	X		X		
Underground pathways for utility entrances and floor boxes	X		X		
Firestops, Conduit Sleeves, and Sleeve Seals	X		X		
<b>Structured Cabling</b>					
Telecom Room Cabinets, Racks, Frames, and Enclosures	X		X		
Telecom Room Buildout (ex. backboard and ladder rack)	X		X		
Telecom Room Uninterruptible Power Supply (UPS)		X		X	
Telecom Room Power Strips		X		X	
Optical Fiber Backbone Cable and Connectivity	X	X	X	X	
Copper Backbone Cable and Connectivity	X		X		
Copper Horizontal Cable and Connectivity	X		X		
<b>Data Communications</b>					
Router / Firewall		X		X	
Core Switch / Edge Switch		X		X	
Wireless Access Points		X		X	
Servers / Storage and Backup		X		X	
Laptops / Desktops / Copiers / Printers / Scanners		X		X	
Software		X		X	
<b>Voice Communications</b>					
VoIP Gateway / Analog handsets		X		X	
VoIP handset wall mount kit		X		X	
VoIP handsets		X		X	
VoIP Network licensing		X		X	
<b>Audio-Video Communications</b>					
Conduits and Backboxes for AV systems	X		X		
HDMI Classroom Cabling and Connectivity	X		X		
Refer to AV drawings for AV Scope					
<b>Distributed &amp; Monitoring Communications</b>					
K12 Classroom Analog Paging	X		X		
Wireless Clock Systems	X		X		
<b>Electronic Safety and Security</b>					
Conduits and Backboxes for Security systems	X		X		
Refer to Security drawings for Security Scope					

### GENERAL NEW WORK NOTES

- READ THE SPECIFICATIONS AND REVIEW DRAWINGS OF ALL DIVISIONS OF WORK. COORDINATE THIS WORK WITH ALL OTHER DIVISIONS OF WORK AND ALL SUBCONTRACTORS.
- ALL WORK SHALL CONFORM TO THE APPLICABLE SPECIFICATIONS (DIVISION 26, DIVISION 27, DIVISION 28, ETC.) AND THE CUSTOMER PRE-ESTABLISHED STRUCTURED CABLING STANDARDS. SHOULD DIFFERENCES EXIST IN THE SPECIFICATIONS RELATING TO TECHNOLOGY AND THE CLIENT'S PRE-ESTABLISHED STANDARDS THE CONTRACTOR SHALL CONTACT THE LOW VOLTAGE ENGINEER FOR CLARIFICATION THROUGH THE RFI PROCESS.
- FULLY COORDINATE ALL CABLE TRAY, FIRE STOP CONDUITS / SLEEVES, AND CONDUIT ROUTING WITH STRUCTURAL ELEMENTS. COORDINATE CABLE TRAY AND CONDUIT INSTALLATIONS WITH ARCHITECT, STRUCTURAL ENGINEER, STRUCTURAL CONTRACTOR, AND GENERAL CONTRACTOR PRIOR TO INSTALLATION. ROUTING IN CONCRETE SLAB OR UNDER SLAB (WHERE CONDUITS WOULD BE ON GRADE) REQUIRES THE USE OF WET LOCATION RATED CABLES.
- ALL TELECOMMUNICATIONS CONTINUOUS PATHWAYS SHALL BE BONDED TO THE TELECOMMUNICATIONS BONDING BACKBONE. FOR CONDUITS, INSULATION BUSHINGS SHALL BE USED AT THE END OF THE CONDUIT THE FARTHEST AWAY FROM THE SERVING TR. A BONDING BUSHING SHALL BE USED AT THE END CLOSEST TO THE SERVING TR. CONTRACTOR TO REFER TO THE ANSI-STD-J 607 STANDARD FOR ADDITIONAL INFORMATION AS TO THE INSTALLATION OF THE TELECOMMUNICATIONS BONDING BACKBONE.
- ALL FIRE RATED WALL / FLOOR ASSEMBLIES PENETRATED FOR TELECOMMUNICATIONS CABLING PATHWAYS SHALL BE FIRE STOPPED WITH THE APPROVED FIRE STOP SYSTEMS (F/S). ALL FIRESTOP SYSTEMS SHALL BE INSTALLED AS DIRECTED BY THE MANUFACTURER AND AS SPECIFIED IN DIVISION 07 07 54 00 - "FIRESTOPPING". FIRE STOP ASSEMBLY LOCATIONS ARE TO BE COORDINATED WITH CABLE TRAY PATHWAY TO TELECOMMUNICATIONS ROOM.
- BACK BOXES AND CONDUIT LOCATIONS IN PRECAST CONCRETE WALLS SHALL BE COORDINATED WITH ARCHITECT, STRUCTURAL ENGINEER, AND GC PRIOR TO ORDERING THE PRECAST WALLS.
- ROUTING OF CABLES SHALL BE CONCEALED. CABLES SHALL BE ROUTED IN CONDUIT IN EXPOSED AREAS. MINIMIZE AMOUNT OF EXPOSED CONDUIT BY EMBEDDING CONDUIT IN SLAB WHEN POSSIBLE. EMBEDDED CONDUITS AND PENETRATIONS OF STRUCTURE SHALL FOLLOW DETAILS IN STRUCTURAL DRAWINGS. WHEN CONDUITS CAN ONLY BE INSTALLED EXPOSED, NOTIFY ARCHITECT PRIOR TO START OF INSTALLATION OF CONDUITS. CABLES SHALL BE ROUTED IN CONDUIT WHEN ABOVE HARD CEILINGS. CONDUITS FOR ELEVATOR PHONES AND FIRE ALARM CONTROL PANEL SHALL BE CONTINUOUS (HOMERUN) FROM THE TELECOMMUNICATIONS ROOM TO THE APPLICABLE BOX / CABINET. CONTRACTOR SHALL SIZE AND PROVIDE CONDUITS TO MEET TIA-569.
- TELECOMMUNICATIONS ROOMS SHALL BE DEDICATED FOR INFORMATION TECHNOLOGY USE (I.E. NO SHARED SPACE WITH A JANITOR, FIRE ALARM SYSTEM, ETC.) NO SERVICES SHALL PASS THROUGH THE SPACE UNLESS DEDICATED TO THE SPACE (NO PLUMBING, MECHANICAL, ELECTRICAL, FIRE, ETC.)

### CALL OUTS

ENLARGED PLAN CALLOUT	
NOT IN SCOPE	

### Revisions

NUMBER	DESCRIPTION	DATE
--------	-------------	------



LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com

**HENDERSON**  
ENGINEERS  
8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM

2150005255  
MO. CORPORATE NO. E-6880  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/16/2022



09/15/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-201907648

LSW - TECHNOLOGY  
PLAN - LEVEL 1

TN101-A

○ TECHNOLOGY PLAN NOTES:

T16 PROVIDE DATA FOR ACCESS CONTROL PANEL.  
T18 DATA SHOWN FOR SECURITY CAMERA. REFER TO TY  
DRAWINGS FOR EXACT LOCATION PRIOR TO INSTALLATION.

① TECHNOLOGY LEVEL 1 PLAN - LSW  
3/16" = 1'-0"



**LSR7 Robotics, GiC &  
Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

0121-0100

civil engineer:  
**Kaw Valley Engineering**  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveng.com

structural engineer:  
**Bob D. Campbell & Company, Inc.**  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/PT/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com



8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM

Issue Date: September 9, 2022


Revisions		
NUMBER	DESCRIPTION	DATE
2	Addendum 02	09/23/2022




09/23/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

**LSW - TECHNOLOGY  
RCP - LEVEL 1**

**TN201-A**



① TECHNOLOGY LEVEL 1 RCP - LSW  
3/16" = 1'-0"





**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100

owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio


civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvang.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Belview  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/IT/Codes:  
Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com


**TECHNOLOGY PLAN NOTES:**

- T6 PROVIDE 19" WIDE TWO-POST EQUIPMENT RACK. REFER TO SECTION 271100 FOR FURTHER REQUIREMENTS.
- T7 PROVIDE 6" VERTICAL WIRE MANAGER. REFER TO SECTION 271100 FOR FURTHER REQUIREMENTS.
- T8 PROVIDE 12" WIDE LADDER RACK. REFER TO SECTION 271100 FOR FURTHER REQUIREMENTS.
- T9 PROVIDE TELECOMMUNICATIONS GROUNDING BUS BAR. SEE DETAILS SHEET AND SECTIONS 270500 FOR FURTHER REQUIREMENTS.
- T10 PROVIDE 3/4" FIRE-RATED TELECOMMUNICATIONS PLYWOOD BACKBOARD DOUBLE COATED IN UL 723 CLASSIFIED FIRE RETARDANT LOW GLOSS WHITE PAINT. PLYWOOD SHALL BE PAINTED PRIOR TO INSTALLATION.
- T11 (2) 4" CONDUIT INCOMING SERVICE CONDUITS. REFER TO ELECTRICAL SITE PLANS FOR EXACT ROUTING AND FURTHER INFORMATION.
- T12 ACCESS CONTROL PANEL. REFER TO SECURITY DRAWINGS FOR FURTHER REQUIREMENTS.
- T15 PROVIDE 12" WIDE VERTICAL LADDER RACK. REFER TO SECTION 271100 FOR FURTHER REQUIREMENTS.




① LSW TELECOM ROOM #R108 - ENLARGED PLAN  
1/2" = 1'-0"


② LSW TELECOM ROOM #R108 - ENLARGED PATHWAY  
1/2" = 1'-0"




③ ACCESS POINT CONNECTOR ASSEMBLY  
NTS




④ COMMUNICATIONS OUTLET MOUNTING  
NTS






⑤ SPEAKER INSTALLATION  
NTS




PAGING SPEAKER FOR HARD CEILING




PAGING SPEAKER FOR EXPOSED CEILING




⑥ CEILING COMM OUTLET 2D  
NTS




⑦ SINGLE GANG COMM OUTLET (2D)  
NTS



⑧ SINGLE GANG COMM OUTLET FOR DISPLAY (2D)  
NTS



⑨ SINGLE GANG COMM OUTLET FOR DISPLAY (2D)  
NTS




⑩ RISER DIAGRAM - BACKBONE CABLES  
NTS

**HENDERSON**  
ENGINEERS  
8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM  
2150005255  
MO. CORPORATE NO. E-8580  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

NUMBER	DESCRIPTION	DATE
2	Addendum 02	09/23/2022



09/23/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

**LSW - TECHNOLOGY  
ENLARGED PLANS AND  
DETAILS  
TN400-A**







LSR7 Robotics, GiC &  
Phys Education

LSN: 901 NE Douglas St., Lee's Summit MO  
64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO  
64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100


owner:  
Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086

architect:  
Multistudio  
4205 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi-studio

civil engineer:  
Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kvang.com

structural engineer:  
Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com

MEP/ET/Code:  
Henderson Engineers  
8345 Lenexa Drive, Suite  
300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com



2150005255  
MO. CORPORATE NO. E-6580  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

Revisions		
NUMBER	DESCRIPTION	DATE
1	Addendum 01	09/16/2022




09/15/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

LSW - SECURITY PLAN -  
LEVEL 1

TY101-A

◇ SECURITY PLAN NOTES:  
TY1 PROPOSED ACCESS CONTROL LOCATION. OWNER'S  
VENDOR SHALL COORDINATE FINAL LOCATION.  
TY3 ADA ACTUATOR. REFER TO DIVISION 08 DOOR HARDWARE.  
ENSURE ADA ACTUATOR WILL ONLY OPERATE WHEN THE  
DOOR IS UNLOCKED OR WITHIN 10 SECONDS OF A VALID  
CARD READ.  
TY4 CENTER BOX AT ~9'-6" VERTICALLY ON THE STRUCTURAL  
BEAM AND ROUTE HARD CONDUIT INTO NEAREST  
ACCESSIBLE CEILING. ENSURE ALL PATHWAY IS  
WEATHERTIGHT.

① SECURITY LEVEL 1 PLAN - LSW  
3/16" = 1'-0"










**LSR7 Robotics, GiC & Phys Education**

LSN: 901 NE Douglas St., Lee's Summit MO 64086  
LSW: 2600 SW Ward Rd, Lee's Summit MO 64082  
LSHS: 400 SE Blue Pkwy, Lee's Summit MO 64063

0121-0100


owner: Lee's Summit R-7 School  
301 NE Tudor Road  
Lee's Summit, MO 64086  
architect: Multistudio  
4209 Pennsylvania  
Kansas City, MO 64111  
816.931.6655  
multi.studio  
civil engineer: Kaw Valley Engineering  
14700 West 114th Terrace  
Lenexa, KS 66215  
913.485.0318  
kveneg.com  
structural engineer: Bob D. Campbell & Company, Inc.  
4338 Bellevue  
Kansas City, MO 64111  
816.531.4144  
www.bdc-engrs.com  
MEP/IT/Code: Henderson Engineers  
8345 Lenexa Drive, Suite 300  
Lenexa, KS 66214  
816.742.5000  
www.hendersonengineers.com



**HENDERSON**  
ENGINEERS  
8345 LENEXA DRIVE, SUITE 300  
LENEXA, KS 66214  
TEL 913.742.5000 FAX 913.742.5001  
WWW.HENDERSONENGINEERS.COM  
2150005255  
MO. CORPORATE NO. E-8580  
EXPIRES 12/31/2022

Issue Date: September 9, 2022

NUMBER	DESCRIPTION	DATE
--------	-------------	------



09/09/2022  
DOUGLAS M. EVERHART  
LICENSE # PE-2019007648

**SECURITY DETAILS**  
**TY500**

A

B

E

G

H

J

K

M

N

P