



MiTek USA, Inc.
16023 Swingley Ridge Rd
Chesterfield, MO 63017
314-434-1200

Re: 3008841
C&H/159 COBEY CREEK/MO

The truss drawing(s) referenced below have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Builders FirstSource (Valley Center).

Pages or sheets covered by this seal: I55211893 thru I55211895

My license renewal date for the state of Missouri is December 31, 2023.

Missouri COA: Engineering 001193



November 14, 2022

Sevier, Scott ,Engineer

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.


Job	Truss	Truss Type	Qty	Ply	C&H/159 COBEY CREEK/MO	I55211893
3008841	A2A	Roof Special	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.430 s Jan 6 2022 MiTek Industries, Inc. Thu Nov 10 12:47:52 2022 Page 1
ID:xKFGJ7evN?7xhJE66FFHnCzvA57-ulGsUMIZ9gUuTssI0mG3P18F25P9uiqi1dSHmwyKaYb

0-10-8	4-3-8	9-1-0	11-6-8	13-6-0	19-1-13	20-1-9	27-0-0	27-10-8
0-10-8	4-3-8	4-9-8	2-5-8	1-11-8	5-7-13	0-11-12	6-10-7	0-10-8

Scale = 1:49.1

REPAIR: PLATES LOOSE AT JOINT 8



ATTACH 1/2" PLYWOOD OR OSB GUSSET (15/32" RATED SHEATHING 32/16 EXP 1)
TO EACH FACE OF TRUSS WITH (0.131" X 2.5" MIN.) NAILS PER THE FOLLOWING NAIL SCHEDULE:
2 X 3'S - 2 ROWS, 2 X 4'S - 3 ROWS, 2 X 6'S AND LARGER - 4 ROWS: SPACED @ 4" O.C.
NAILS TO BE DRIVEN FROM BOTH FACES. STAGGER SPACING FROM FRONT TO BACK FACE
FOR A NET 2" O.C. SPACING IN EACH COVERED TRUSS MEMBER. USE 2" MEMBER END DISTANCE.

	4-3-8	9-1-0	11-6-8	13-6-0	19-1-13	27-0-0	
	4-3-8	4-9-8	2-5-8	1-11-8	5-7-13	7-10-3	
Plate Offsets (X,Y)--	[2:0-0-0,0-0-13], [9:0-0-0,0-0-9], [11:0-3-8,0-2-0], [14:0-5-12,0-3-0], [16:0-7-12,0-3-8], [18:0-3-8,0-2-0]						
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	PLATES
TCLL 25.0	Plate Grip DOL	1.15	TC 0.57	Vert(LL)	-0.23 15-16	>999	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.90	Vert(CT)	-0.41 15-16	>788	GRIP
BCLL 0.0	Rep Stress Incr	YES	WB 0.81	Horz(CT)	0.23 9	n/a	197/144
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS				Weight: 122 lb
							FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SP No.3 , Right: 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.
JOINTS 1 Brace at Jt(s): 14

REACTIONS. (size) 2=0-5-8, 9=0-3-8
Max Horz 2=114(LC 12)
Max Uplift 2=169(LC 12), 9=169(LC 13)
Max Grav 2=1276(LC 1), 9=1276(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2180/286, 3-5=-3962/492, 5-6=-2158/300, 6-8=-2128/292, 8-9=-2044/285
BOT CHORD 2-18=-288/1881, 5-16=-142/1287, 15-16=-409/3511, 14-15=-402/3470, 9-11=-159/1722
WEBS 5-14=-1828/345, 6-14=-149/1522, 8-11=-578/118, 11-14=-167/1825, 3-18=-981/201,
16-18=-321/2061, 3-16=-120/1601

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 13-6-0, Exterior(2R) 13-6-0 to 16-6-0, Interior(1) 16-6-0 to 27-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 169 lb uplift at joint 2 and 169 lb uplift at joint 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



November 14, 2022

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	C&H/159 COBEY CREEK/MO	I55211894
3008841	A4	Roof Special	4	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Jan 6 2022 MiTek Industries, Inc. Thu Nov 10 12:47:54 2022 Page 1

ID:xKFGJ7evN?77xhJE66FFHnCzvA57-qgOdv2mphlIc90g7BJXUSDa4v6lLhj?VxxOroyKaYZ

Job Reference (optional)


0-10-8 6-10-7 7-11-15 13-6-0 15-9-0 20-2-12 23-4-5 24-8-8 27-0-0 27-10-8
0-10-8 6-10-7 1-1-8 5-6-1 2-3-0 4-5-12 3-1-9 1-4-3 2-3-8 0-10-8

REPAIR: PLATES DAMAGED AT JOINTS 7,9,10,12

6.00 12

4x6 =

Scale = 1:51.2



ATTACH 1/2" PLYWOOD OR OSB GUSSET (15/32" RATED SHEATHING 32/16 EXP 1) TO EACH FACE OF TRUSS WITH (0.131" X 2.5" MIN.) NAILS PER THE FOLLOWING NAIL SCHEDULE:
2 X 3'S - 2 ROWS, 2 X 4'S - 3 ROWS, 2 X 6'S AND LARGER - 4 ROWS: SPACED @ 4" O.C.
NAILS TO BE DRIVEN FROM BOTH FACES. STAGGER SPACING FROM FRONT TO BACK FACE FOR A NET 2" O.C. SPACING IN EACH COVERED TRUSS MEMBER. USE 2" MEMBER END DISTANCE.



ATTACH < 2 LAYERS > 3/4" PLYWOOD OR OSB GUSSET (23/32" RATED SHEATHING 48/24 EXP 1) TO ONE FACE OF TRUSS WITH (0.131" X 3.0") NAILS PER THE FOLLOWING NAIL SCHEDULE:
2 X 3'S - 2 ROWS, 2 X 4'S - 3 ROWS, 2 X 6'S AND LARGER - 4 ROWS: SPACED @ 2" O.C.
USE 2" MEMBER END DISTANCE. GLUE PLYWOOD LAYERS TOGETHER PRIOR TO ATTACHING TO TRUSS.

7-11-15 13-6-0 15-9-0 20-2-12 24-8-8 27-0-0
7-11-15 5-6-1 2-3-0 4-5-12 4-5-12 2-3-8

Plate Offsets (X,Y)-- [2:0-3-8,Edge], [6:0-3-0,Edge], [7:0-3-7,0-0-1], [8:0-9-3,0-2-0], [8:0-0-12,0-9-11], [12:0-2-8,0-3-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.53	Vert(LL)	-0.19 10-21	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.89	Vert(CT)	-0.36 10-11	>907	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.40	Horz(CT)	0.20 8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS					Weight: 135 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2 "Except"
6-8: 2x6 SP 2400F 2.0E
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x6 SP 2400F 2.0E
LBR SCAB 6-8 2x6 SP 2400F 2.0E one side
WEDGE
Left: 2x4 SPF No.2 , Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-12

REACTIONS.

(size) 2=0-5-8, 8=0-3-8
Max Horz 2=120(LC 16)
Max Uplift 2=169(LC 12), 8=152(LC 13)
Max Grav 2=1276(LC 1), 8=1212(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2025/287, 3-5=-1634/277, 5-6=-1687/277, 6-7=-2714/374, 7-8=-485/91
BOT CHORD 2-15=-234/1719, 11-12=-229/2467, 10-11=-272/2551, 7-10=-274/2540
WEBS 5-12=-110/1018, 12-15=-199/1615, 3-12=-483/189, 6-10=0/268, 6-12=-1233/287

NOTES-

- Attached 7-9-8 scab 6 to 8, front face(s) 2x6 SP 2400F 2.0E with 2 row(s) of 10d (0.131"x3") nails spaced 9" o.c. except : starting at 0-0-8 from end at joint 6, nail 2 row(s) at 7" o.c. for 2-0-0; starting at 3-2-3 from end at joint 6, nail 2 row(s) at 4" o.c. for 4-4-5.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 13-6-0, Exterior(2R) 13-6-0 to 16-6-0, Interior(1) 16-6-0 to 26-11-11 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 169 lb uplift at joint 2 and 152 lb uplift at joint 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



November 14, 2022






16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	C&H/159 COBEY CREEK/MO	I55211895
3008841	A5	Roof Special	5	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Jan 6 2022 MiTek Industries, Inc. Thu Nov 10 12:47:55 2022 Page 1
ID:xKFGJ7evN?7xhJE66FFHnCzvA57-lty?6NnRSbtTKJashuqm0gmebJTL4468kbgxNFyKaYY




 APPLY 2 X 4 X 4' SPF NO.2 SCAB(S) TO EACH FACE OF TRUSS CENTERED ON SPLICE. ATTACH WITH (0.131" X 3") NAILS PER THE FOLLOWING NAIL SCHEDULE: 2 x 3'S - 1 ROW, 2 x 4'S - 2 ROWS, 2 x 6'S AND LARGER - 3 ROWS: SPACED @ 4" O.C. STAGGER NAIL SPACING FROM FRONT FACE AND BACK FACE FOR A NET 2" O.C SPACING IN THE TRUSS. USE 2" MEMBER END DISTANCE.

		3-2-10		5-2-8				13-0-8				19-8-1				26-6-8			
		3-2-10		1-11-14				7-10-0				6-7-9				6-10-7			
Plate Offsets (X,Y)-- [7:0-0-0,0-0-13]																			
LOADING (psf)		SPACING- 2-0-0				CSI.				DEFL. in (loc) l/defl L/d				PLATES		GRIP			
TCLL	25.0	Plate Grip DOL 1.15				TC 0.99				Vert(LL) -0.16 12 >999 240				MT20		197/144			
TCDL	10.0	Lumber DOL 1.15				BC 0.80				Vert(CT) -0.33 10-12 >960 180									
BCLL	0.0	Rep Stress Incr YES				WB 0.64				Horz(CT) -0.08 14 n/a n/a									
BCDL	10.0	Code IRC2018/TPI2014				Matrix-AS								Weight: 115 lb		FT = 20%			

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Right: 2x4 SP No.3

BRACING-
 TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-2.
 BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 14=Mechanical, 7=0-3-8
 Max Horz 7=-140(LC 13)
 Max Uplift 14=-149(LC 12), 7=-167(LC 13)
 Max Grav 14=1187(LC 1), 7=1250(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-2681/376, 3-4=-2788/517, 4-6=-1436/267, 6-7=-2048/287
 BOT CHORD 13-14=-426/2912, 3-13=-511/247, 10-12=-11/317, 9-10=-278/1741, 7-9=-278/1741
 WEBS 2-14=-2889/424, 10-13=-127/865, 4-13=-367/1525, 4-10=-30/445, 6-10=-673/216, 2-13=-530/84

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-2-10, Interior(1) 3-2-10 to 13-0-8, Exterior(2R) 13-0-8 to 16-0-8, Interior(1) 16-0-8 to 27-5-0 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 149 lb uplift at joint 14 and 167 lb uplift at joint 7.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



November 14,2022

Job 3008841	Truss A5-2	Truss Type Roof Special	Qty 5	Ply 1	C&H/159 COBEY CREEK/MO	155211895
----------------	---------------	----------------------------	----------	----------	------------------------	-----------

Builders First Source, Valley Center, KS 67147


8:430 s Jan 6 2022 MiTek Industries, Inc. Mon Nov 14 08:39:58 2022 Page 1
ID:xKFGJ7evN?7xhJE66FFHnCzvA57-KdJe3Y9kIFA4F7Cjp?i3GCps4ml7Y11gM3rrhXyJjp?

3-2-10 3-2-10	5-2-8 1-11-14	13-0-8 7-10-0	19-8-1 6-7-9	26-6-8 6-10-7	27-5-0 0-10-8
------------------	------------------	------------------	-----------------	------------------	------------------

REPAIR: REPLACE TOP HALF OF MEMBER 6-10

5x8 =

Scale = 1:47.0



ATTACH 1/2" PLYWOOD OR OSB GUSSET (15/32" RATED SHEATHING 32/16 EXP 1) TO EACH FACE OF TRUSS WITH (0.131" X 2.5" MIN.) NAILS PER THE FOLLOWING NAIL SCHEDULE: 2 X 3'S - 2 ROWS, 2 X 4'S - 3 ROWS, 2 X 6'S AND LARGER - 4 ROWS: SPACED @ 4" O.C. NAILS TO BE DRIVEN FROM BOTH FACES. STAGGER SPACING FROM FRONT TO BACK FACE FOR A NET 2" O.C. SPACING IN EACH COVERED TRUSS MEMBER. USE 2" MEMBER END DISTANCE.



APPLY 2 X 4 X 4' SPF NO.2 SCAB(S) TO EACH FACE OF TRUSS CENTERED ON SPLICE. ATTACH WITH (0.131" X 3") NAILS PER THE FOLLOWING NAIL SCHEDULE: 2 X 3'S - 1 ROW, 2 X 4'S - 2 ROWS, 2 X 6'S AND LARGER - 3 ROWS: SPACED @ 4" O.C. STAGGER NAIL SPACING FROM FRONT FACE AND BACK FACE FOR A NET 2" O.C. SPACING IN THE TRUSS. USE 2" MEMBER END DISTANCE.

3-2-10 3-2-10	5-2-8 1-11-14	13-0-8 7-10-0	19-8-1 6-7-9	26-6-8 6-10-7
------------------	------------------	------------------	-----------------	------------------

Plate Offsets (X,Y)-- [7:0-0-0,0-0-13]

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.99	Vert(LL) -0.16 12 >999 240	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.80	Vert(CT) -0.33 10-12 >960 180		
BCLL 0.0	Rep Stress Incr YES	WB 0.64	Horz(CT) -0.08 14 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-AS			
				Weight: 115 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-2.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 14=Mechanical, 7=0-3-8
Max Horz 7=-140(LC 13)
Max Uplift 14=-149(LC 12), 7=-167(LC 13)
Max Grav 14=1187(LC 1), 7=1250(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2681/376, 3-4=-2788/517, 4-6=-1436/267, 6-7=-2048/287
BOT CHORD 13-14=-426/2912, 3-13=-511/247, 10-12=-11/317, 9-10=-278/1741, 7-9=-278/1741
WEBS 2-14=-2889/424, 10-13=-127/865, 4-13=-367/1525, 4-10=-30/445, 6-10=-673/216, 2-13=-530/84

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-2-10, Interior(1) 3-2-10 to 13-0-8, Exterior(2R) 13-0-8 to 16-0-8, Interior(1) 16-0-8 to 27-5-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 149 lb uplift at joint 14 and 167 lb uplift at joint 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




November 14, 2022



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Builders First Source, Valley Center, KS 67147

8.430 s Jan 6 2022 MiTek Industries, Inc. Mon Nov 14 08:40:12 2022 Page 1
ID: xKEG I7eyN27xb IE66FEHbC7vA57-w I9x2l IWSYx5xGHR0xvM90EYBYQg4l IkaEE2ajv IJon



LUMBER- TOP CHORD 2x4 SPF No.2 BOT CHORD 2x4 SPF No.2 WEBS 2x4 SPF No.2 WEDGE Right: 2x4 SP No.3	BRACING- TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-2. BOT CHORD Rigid ceiling directly applied.
---	---

REACTIONS. (size) 14=Mechanical, 7=0-3-8
 Max Horz 7=-140(LC 13)
 Max Uplift 14=-149(LC 12), 7=-167(LC 13)
 Max Grav 14=1187(LC 1), 7=1250(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-2681/376, 3-4=-2788/517, 4-6=-1436/267, 6-7=-2048/287
BOT CHORD	13-14=-426/2912, 3-13=-511/247, 10-12=-11/317, 9-10=-278/1741, 7-9=-278/1741
WEBS	2-14=-2889/424, 10-13=-127/865, 4-13=-367/1525, 4-10=-30/445, 6-10=-673/216, 2-13=-530/84

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCdL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-2-10, Interior(1) 3-2-10 to 13-0-8, Exterior(2R) 13-0-8 to 16-0-8, Interior(1) 16-0-8 to 27-5-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 149 lb uplift at joint 14 and 167 lb uplift at joint 7.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



November 14.2022





WARNING – Velly design parameters are listed below and included with the key reference to AISC M14-15 16f, 17f, 18f, 19f, 20f, 21f, 22f, 23f, 24f, 25f, 26f, 27f, 28f, 29f, 30f, 31f, 32f, 33f, 34f, 35f, 36f, 37f, 38f, 39f, 40f, 41f, 42f, 43f, 44f, 45f, 46f, 47f, 48f, 49f, 50f, 51f, 52f, 53f, 54f, 55f, 56f, 57f, 58f, 59f, 60f, 61f, 62f, 63f, 64f, 65f, 66f, 67f, 68f, 69f, 70f, 71f, 72f, 73f, 74f, 75f, 76f, 77f, 78f, 79f, 80f, 81f, 82f, 83f, 84f, 85f, 86f, 87f, 88f, 89f, 90f, 91f, 92f, 93f, 94f, 95f, 96f, 97f, 98f, 99f, 100f, 101f, 102f, 103f, 104f, 105f, 106f, 107f, 108f, 109f, 110f, 111f, 112f, 113f, 114f, 115f, 116f, 117f, 118f, 119f, 120f, 121f, 122f, 123f, 124f, 125f, 126f, 127f, 128f, 129f, 130f, 131f, 132f, 133f, 134f, 135f, 136f, 137f, 138f, 139f, 140f, 141f, 142f, 143f, 144f, 145f, 146f, 147f, 148f, 149f, 150f, 151f, 152f, 153f, 154f, 155f, 156f, 157f, 158f, 159f, 160f, 161f, 162f, 163f, 164f, 165f, 166f, 167f, 168f, 169f, 170f, 171f, 172f, 173f, 174f, 175f, 176f, 177f, 178f, 179f, 180f, 181f, 182f, 183f, 184f, 185f, 186f, 187f, 188f, 189f, 190f, 191f, 192f, 193f, 194f, 195f, 196f, 197f, 198f, 199f, 200f, 201f, 202f, 203f, 204f, 205f, 206f, 207f, 208f, 209f, 210f, 211f, 212f, 213f, 214f, 215f, 216f, 217f, 218f, 219f, 220f, 221f, 222f, 223f, 224f, 225f, 226f, 227f, 228f, 229f, 230f, 231f, 232f, 233f, 234f, 235f, 236f, 237f, 238f, 239f, 240f, 241f, 242f, 243f, 244f, 245f, 246f, 247f, 248f, 249f, 250f, 251f, 252f, 253f, 254f, 255f, 256f, 257f, 258f, 259f, 260f, 261f, 262f, 263f, 264f, 265f, 266f, 267f, 268f, 269f, 270f, 271f, 272f, 273f, 274f, 275f, 276f, 277f, 278f, 279f, 280f, 281f, 282f, 283f, 284f, 285f, 286f, 287f, 288f, 289f, 290f, 291f, 292f, 293f, 294f, 295f, 296f, 297f, 298f, 299f, 300f, 301f, 302f, 303f, 304f, 305f, 306f, 307f, 308f, 309f, 310f, 311f, 312f, 313f, 314f, 315f, 316f, 317f, 318f, 319f, 320f, 321f, 322f, 323f, 324f, 325f, 326f, 327f, 328f, 329f, 330f, 331f, 332f, 333f, 334f, 335f, 336f, 337f, 338f, 339f, 340f, 341f, 342f, 343f, 344f, 345f, 346f, 347f, 348f, 349f, 350f, 351f, 352f, 353f, 354f, 355f, 356f, 357f, 358f, 359f, 360f, 361f, 362f, 363f, 364f, 365f, 366f, 367f, 368f, 369f, 370f, 371f, 372f, 373f, 374f, 375f, 376f, 377f, 378f, 379f, 380f, 381f, 382f, 383f, 384f, 385f, 386f, 387f, 388f, 389f, 390f, 391f, 392f, 393f, 394f, 395f, 396f, 397f, 398f, 399f, 400f, 401f, 402f, 403f, 404f, 405f, 406f, 407f, 408f, 409f, 410f, 411f, 412f, 413f, 414f, 415f, 416f, 417f, 418f, 419f, 420f, 421f, 422f, 423f, 424f, 425f, 426f, 427f, 428f, 429f, 430f, 431f, 432f, 433f, 434f, 435f, 436f, 437f, 438f, 439f, 440f, 441f, 442f, 443f, 444f, 445f, 446f, 447f, 448f, 449f, 450f, 451f, 452f, 453f, 454f, 455f, 456f, 457f, 458f, 459f, 460f, 461f, 462f, 463f, 464f, 465f, 466f, 467f, 468f, 469f, 470f, 471f, 472f, 473f, 474f, 475f, 476f, 477f, 478f, 479f, 480f, 481f, 482f, 483f, 484f, 485f, 486f, 487f, 488f, 489f, 490f, 491f, 492f, 493f, 494f, 495f, 496f, 497f, 498f, 499f, 500f, 501f, 502f, 503f, 504f, 505f, 506f, 507f, 508f, 509f, 510f, 511f, 512f, 513f, 514f, 515f, 516f, 517f, 518f, 519f, 520f, 521f, 522f, 523f, 524f, 525f, 526f, 527f, 528f, 529f, 530f, 531f, 532f, 533f, 534f, 535f, 536f, 537f, 538f, 539f, 540f, 541f, 542f, 543f, 544f, 545f, 546f, 547f, 548f, 549f, 550f, 551f, 552f, 553f, 554f, 555f, 556f, 557f, 558f, 559f, 560f, 561f, 562f, 563f, 564f, 565f, 566f, 567f, 568f, 569f, 570f, 571f, 572f, 573f, 574f, 575f, 576f, 577f, 578f, 579f, 580f, 581f, 582f, 583f, 584f, 585f, 586f, 587f, 588f, 589f, 590f, 591f, 592f, 593f, 594f, 595f, 596f, 597f, 598f, 599f, 600f, 601f, 602f, 603f, 604f, 605f, 606f, 607f, 608f, 609f, 610f, 611f, 612f, 613f, 614f, 615f, 616f, 617f, 618f, 619f, 620f, 621f, 622f, 623f, 624f, 625f, 626f, 627f, 628f, 629f, 630f, 631f, 632f, 633f, 634f, 635f, 636f, 637f, 638f, 639f, 640f, 641f, 642f, 643f, 644f, 645f, 646f, 647f, 648f, 649f, 650f, 651f, 652f, 653f, 654f, 655f, 656f, 657f, 658f, 659f, 660f, 661f, 662f, 663f, 664f, 665f, 666f, 667f, 668f, 669f, 670f, 671f, 672f, 673f, 674f, 675f, 676f, 677f, 678f, 679f, 680f, 681f, 682f, 683f, 684f, 685f, 686f, 687f, 688f, 689f, 690f, 691f, 692f, 693f, 694f, 695f, 696f, 697f, 698f, 699f, 700f, 701f, 702f, 703f, 704f, 705f, 706f, 707f,



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.


For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

PLATE SIZE


4 X 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION




BEARING



Industry Standards:
ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:
ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved



MITek Engineering Reference Sheet: MII-7473 rev. 5/19/2020

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor1 bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.