

copyright:

The following documents are the sole property of davidson architecture & engineering, llc for the specific purpose of construction of said building. These documents are considered confidential and subject to davidson architecture & engineering llc's copyright protection. Neither receipt nor possession transfers any rights to reproduce these documents or any part thereof. Any re-use of these documents without the express written permission of davidson architecture & engineering, llc is strictly prohibited and shall confer no liability to davidson architecture & engineering, llc.

disclaimer:

These documents are accurate to the best of davidson architecture & engineering, llc's professional knowledge. In the event a discrepancy in the documents is encountered, it is the responsibility of that party to notify davidson architecture & engineering in a timely manner, for corrections and/or explanation of the documents.

project description:

New pre-engineered metal building for indoor batting cages with support office, retail, and party room.

submittal dates:

sitework:

building envelope:

occupancy:

estimated duration:

fall 2022

fall 2022

spring 2023

9 months

schedule indications are estimated and shall be the responsibility of the contractor.

const. schedule

PDP & Rezoning submittal:

planning approval:

permit submittal:

permit approval:

approved January 2022

pending approval

May 2022

approved

project synopsis:

governing municipality: Lee's Summit, Missouri  
governing code:  
2018 International Building Code  
2018 International Plumbing Code  
2018 International Mechanical Code  
2018 International Fuel Gas Code  
2018 International Residential Code  
2018 International Fire Code  
2017 National Electrical Code  
ICC/ANSI A117.1-2009, Accessible and Usable Buildings and Facilities  
Lee's Summit Municipal Code

zoning: PI

construction: IIB, pemb

stories: one + mezzanine

building height: 27'-0" max.

fire suppression: yes

bldg footprint: 19,800 s.f.

occupancy group: A-3 (indoor sports) with B+M ( office mercantile accessory)

occupant load: 213  
first floor accessory spaces: 44  
mezzanine: 73  
batting cages: 96

\*reference code plan and code review

sheet index:

A0.0 cover sheet  
A0.1 code review, code plan, details

Civil  
C1.0 civil cover sheet  
C1.1 civil notes  
C1.2 site plan  
C1.3 utility plan  
C2.1 grading plan  
C2.2 phase I EC  
C2.3 phase II EC  
C2.4 spot elevation plan  
C3.1 existing drainage map  
C3.2 proposed drainage map  
C3.3 storm calculations  
C4.1 civil details  
C4.2 civil details  
C4.3 civil details  
C4.4 civil details

Landscaping  
L1.1 landscape plan  
L1.2 landscape details

Architectural  
A1.1 architectural site plan  
A2.1 first floor plan  
A2.3 first floor reflected ceiling plan  
A2.4 enlarged bathroom plans  
A3.1 exterior elevations  
A4.1 wall sections  
A4.2 wall sections and details  
A5.1 door schedule and details  
A5.2 first floor finish plan  
A5.3 mezzanine finish plan  
A5.4 millwork details

Structural  
S100 structural specifications  
S110 special inspections  
S200 structural foundation plan  
S500 typical foundation details  
S501 typical foundation details

Mechanical & Plumbing  
MP0.0 mp specifications  
P1.0 overall plumbing plan  
P1.1 enlarged plumbing plan  
P2.0 plumbing riser diagram  
M1.0 mechanical floor plan  
M1.1 not used  
M2.0 mechanical schedules

Electrical  
E0 electrical specifications  
E1 electrical lighting plan  
E2 electrical power plan  
E3 enlarged power plans  
E4 panel schedule and riser diagram  
E5 site lighting plan

owner:

WHD Management LLC  
PO Box 1059  
Lee's Summit, MO 64063  
P: 816.246.3987

architect:

Christopher L. Hafner, AIA, LEED AP  
Davidson Architecture & Engineering  
4301 Indian Creek Parkway  
Overland Park, Kansas 66207  
p: 913.451.9390 f: 913.451.9391

civil engineer:

Paul A. Miller, PE  
Davidson Architecture & Engineering  
4301 Indian Creek Parkway  
Overland Park, Kansas 66207  
p: 913.451.9390 f: 913.451.9391

structural engineer:


Bryce D. Crady  
Apex Engineers, Inc.  
1625 Locust St.  
Kansas City, MO 64108  
p: 816.421.3222

mp engineer:


Maxwell T. Apple  
BC Engineers  
5720 Reeder Shawnee, KS 66203  
p: 913.262.1772

electrical engineer:

Darin T. Seidel  
BC Engineers  
5720 Reeder Shawnee, KS 66203  
p: 913.262.1772



scale: 1/4" = 1'-0"



Contractor Note: Basis of design listed above, substitutions allowed per tenant/ownership approval

governing municipality: Lee's Summit, Missouri  
governing code:

- 2018 International Building Code
- 2018 International Plumbing Code
- 2018 International Mechanical Code
- 2018 International Fuel Gas Code
- 2018 International Residential Code
- 2018 International Fire Code
- 2017 National Electrical Code


ICC/ANSI A117.1-2009, Accessible and Usable Buildings and Facilities  
Lee's Summit Municipal Code

construction: 1 VB pemb  
stories: one  
building height: 27'-0" max.  
fire suppression: yes  
total bldg. area: 19,421 (first=19,421 s.f.)  
allowable area A-3 22,500 s.f. per floor with frontage increase = 54,000 s.f. with frontage increase  
occupancy group: A (indoor sports) with B, M (office mercantile accessory)





occupancy group: A (indoor sports) with B, M ( office mercantile accessory

occupant load: room	sq. ft.	load factor	occupants
first floor accessory spaces:			
shop	1,112	60	18.5
office	205	150	1.4
storage	49	300	0.2
parent lounge	363	15	24.2
jan. clos.	40	300	0.1

batting areas:	
batting cages: (2 per cage, 15 cages total)	30
batting cage seating: (per seat)	66

Total: restroom calcs: building occ.: A					
	water closets		lavatories		drinking fountain
	factor male female		factor male factor female		factor
required:	1/75 1.4 2.7		1/200 0.5 1/150 0.7		1/500 0.1
provided:	2+ 3		2 2		1 hi, 1 low
	urinal				

- Minimum Corridor Width = 44"
- Max. Dead end = 20'
- Exit access travel distance shall not exceed 300 feet for business occupancies
- Common path of egress shall not exceed 100 feet.



note: If alcove depth (x) is greater than 24", then alcove width (y) must be a min. of 36"



Notes :



Drinking fountains shall be located completely within alcoves or positioned so as not to encroach into pedestrian ways.

1. If located in an alcove, the alcove is not less than 32" wide x 18" deep.
2. Minimum depth of the fountain is 18".
3. Clear and unobstructed knee space a minimum of 27" high by 8" deep under the fountain (measured from front edge).
4. Toe clearance a minimum of 9" high by 17" deep.
5. Lever or push bar type control is located 6" maximum from front edge.
6. Bubbler outlet is located 6" maximum from front edge and 36" maximum height from the floor. \*\* (on an accessible drinking fountain with a round or oval bowl, the spout must be positioned so as the flow of water is within 3" of the front edge of the fountain).
7. Stream from bubbler is a minimum of 4" high and substantially parallel to front edge.

NOTE :

Where only one drinking fountain area is provided on a floor there shall be a drinking fountain which is accessible to individuals who use wheelchairs and one accessible to those who have difficulty bending or stooping. This can be accommodated by the use of "hi-lo" fountains, or by such other means as would achieve the required accessibility for each group on each floor.

scale: 1/2" = 1'-0"



a new development for  
**D-BAT - Town Centre Lot 1**  
540 NE Town Centre Drive  
Lee's Summit, Missouri

date  
05.19.2022

drawn by

Drawn by  
DAE

checked by:

checked by  
DAF

DAE

revisions

06/20/2022

06.20.2022

10.13.2022

sheet number

# A0.1


drawing type  
FDP & Permit

© 2004 Blackwell Publishing Ltd, *Journal of Internal Medicine* 255: 101–108

project number

20231





a new development for  
**D-BAT - Town Centre Lot 1**  
540 NE Town Centre Drive  
Lee's Summit, Missouri

date 05.23.2022  
drawn by DAE  
checked by DAE  
revisions

sheet number

**A1.1**

drawing type FDP & Permit  
project number 20231

## project synopsis

Municipality:	Lee's Summit, Missouri
Applicable Building Codes & Ordinances:	2018 International Building Code (IBC) 2018 International Plumbing Code (IPC) 2018 International Mechanical Code (IMC) 2018 International Fuel Gas Code (IFGC) 2018 International Fire Code (IFC) 2017 National Electrical Code (NEC) ICC/ANSI A117.1-2009, Accessible and Usable Buildings and Facilities Lee's Summit Unified Development Ordinance (UDO)
Project Address:	540 NE Town Centre Drive Lee's Summit, Missouri 64064
Property Owner:	WHD Management LLC PO Box 1059 Lee's Summit, MO 64063
Zoning:	PI - Planned Industrial
Proposed Land Use:	Limited Indoor Recreation
Building Setbacks:	Street 20 ft Side Yard 10 ft Rear Yard 20 ft
Landscaping Setbacks:	Street Frontage 20 ft
Height Requirements:	N/A
Number of Dwelling Units:	N/A

Special Conditions Met:  
A commercial indoor and/or outdoor recreation facility or area shall be allowed provided the front entrance is 300 feet or greater distance from any residential district or use.

Adjacent Zoning (within 185'): CP-2, RP-4  
Adjacent Land Use (within 185'): Commercial, Undeveloped, Residential, Government

Building Occupancy: A-3, Limited Indoor Recreation - Batting Cages  
Pad Site A: 83,267 sq. ft. 1.91 ac.

Site Area  
Pad Site A 20,130 sq. ft.

Building Area  
Pad Site A 20,130 sq. ft.

Floor Area Ratio - Maximim 1.0				
Pad Site A	20,130	/	83,267	0.24

Pervious/Impervious Areas

Pad Site A	24,656 sq. ft.	30%	58,611 sq. ft.	70%
------------	----------------	-----	----------------	-----

Parking

Pad Site A: Indoor Batting -		
Required: 4 per 1,000 sq. ft. of office space	20	
batting cages: determined by director	-	
total:	65	



Standard Parking Space Size: 9'-0"x19'-0"  
\*Parking Space Length can reduce by 2'-0" at curbed landscaping and 6' deep sidewalks.

## general notes

- All construction shall conform to the standards and specifications of Lee's Summit, Missouri.
- The general contractor shall contact all utility companies prior to the start of construction and verify the location and depth of any utilities that may be encountered during construction.
- The contractor shall field verify exist. surface & subsurface ground conditions prior to start of construction.
- Slopes shall maintain a maximum 3:1 slope.
- The contractor shall be responsible for obtaining all required permits, paying all fees, and otherwise complying with all applicable regulations governing the project.
- Place silt fence per civil for erosion control.
- Provide a temporary gravel access drive to prevent mud from being deposited onto the adjacent road.
- Prior to installing any structure on a public storm sewer, the contractor shall submit shop drawings for the structure(s). Installation shall not occur until drawings have been approved by public works.
- Prior to installing, constructing, or performing any work on the public storm sewer line (including connecting private drainage to the storm system) contact the city for inspection of the work. Contact must be made at least 48 hours prior to the start of work.
- Connections to the public storm sewer between structures will not be permitted.
- All exterior utility services shall be painted to match the primary building color.
- Signage shall comply with Lee's Summit Signage Ordinance.
- The property owner's association shall have ownership and maintenance responsibilities for the common area tract.
- Reference electrical plans for ground mounted equipment.

## plan notes

- Furnish and install 5'-0" wide concrete sidewalk with broom finish per city of Lee's Summit standards to connect to existing sidewalk.
- Furnish and install 5'-0" wide concrete sidewalk with broom finish per city of Lee's Summit standards. Sidewalk shall be in the r.o.w. offset by 1'-0" from the property line.
- Furnish and install new curb cut per city of Lee's Summit standards. Align with access across the street.
- Furnish and install new curb cut per city of Lee's Summit standards.
- Furnish and install 4" wide white parking space striping.
- Furnish and install 6'-0" wide concrete sidewalk with broom finish per city of Lee's Summit standards.
- Furnish and install handicap parking spaces with striped access aisle per UDO requirements.
- Furnish and install handicap parking space bollard sign per UDO requirements.
- Furnish and install door stoop with turn down edge doveled into building foundations; coordinate with civil drawings.
- Furnish and install strip of clean rock at perimeter of building for drainage and maintenance if required by the geotechnical report.
- Location of block retaining wall; reference civil drawings.
- Furnish and install UDO compliant building mounted area light.
- Furnish and install UDO compliant pole mounted area light; maximum top of pole height to be 18'-0".
- Furnish and install ground mounted monument sign to meet ordinance requirements. Provide electrical to sign as required.
- Furnish and install wall mounted sign to meet ordinance requirements. Provide electrical as required.
- Property line.
- Building setback line.
- Furnish and install concrete pad for ground mounted RTU; provide landscape screening as required around the equipment.
- Furnish and install equipment pad.



2 bollard parking sign  
scale: 1/2" = 1'-0"

1 Site Plan  
scale: 1" = 30'-0"





general notes

- Double keyed locks are not permitted on any required or marked exit.
- Exit/emergency lighting are subject to an on site inspection.
- Provide min. 3 1/2" batt insulation between conditioned & unconditioned spaces
- Exit doors shall be operable from the inside without the use of a key or any special knowledge or effort
- Provide electrical outlets @ 15" a.f.f. to the lowest outlet per a.d.a.
- Egress illumination will be provided at an intensity of not less than 1 foot candle at floor level.
- Construction materials exposed within plenums shall be noncombustible or shall have flame spread rating of not more than 25 and a smoke development rating of not more than 50.
- All electrical outlets within 6' of any sink or water source to be GFCI protected.
- Mezzanine floor height is 12'-0" above first floor.
- Paint liner panels in batting cage areas PT-4 (green) up to 12'-0" a.f.f.
- Reference DBAT standards for painting patterns.

construction notes #

1. Merchandise display by others.
2. Verify point of sale location with owner. Coordinate stub up if required.
3. Furnish and install built-in bar height counter.
4. Furnish and install seamless interior windows.
5. Furnish and install Recessed knob box in stone. Verify final location with fire marshal.
6. Cage by others.
7. Provide access to overhead doors.
8. Benches by others.
9. Furniture by others.
10. Provide data and power at wall mounted TV location.
11. Netting by others.
12. Premanufactured awning above by PEMB manufacturer.
13. Decorative wall sconce.
14. Reference site and landscaping plans for perimeter rock.
15. Furnish and install millwork per details.
16. Furnish and install bracket mounted fire extinguisher, min. 5lb ABC.
17. Furnish and install semi-recessed ADA fire extinguisher cabinet (white) with min. 5lb ABC fire extinguisher.
18. Furnish and install metal guardrail at mezzanine viewing area; verify attachment to structure with structural engineer; railing must have supports/attachments a maximum of 5'-0" apart, and railing must meet loading requirements per the 2018 IBC. Railing selection must be a minimum of 42" above finish floor of the mezzanine - open space between railing parts must not allow a sphere of 4" or greater to pass through.
19. Furnish and install door stoops; reference structural.
20. Furnish and install prefabricated concrete pads for condensing units per mechanical drawings.
21. Provide concrete pad for ground mounted RTU as required, consult with structural.
22. Furnish and install ADA bathroom partitions.
23. Furnish and install lintel above door to support stone.

symbol legend:

- |           |                   |   |                 |
|-----------|-------------------|---|-----------------|
| ##        | door tag          | # | elevation       |
| ##        | construction note | # | wall section    |
| [P#]      | partition type    | # | enlarged detail |
| room name | room tag          |   |                 |


partition legend

- Insulated Interior Partition:  
3-5/8" metal studs @ 16" o.c. to 6" above ceiling or to underside of decking with 5/8" gypsum board on both sides and 3-1/2" sound attenuation batt insulation. Stud gauge per supplier.
- Interior Partition:  
3-5/8" metal studs @ 16" o.c. to 6" above ceiling or to underside of decking with 5/8" gypsum board on both sides. Stud gauge per supplier.
- \*Utilize DensArmor Plus on plumbing walls

partition notes

- utilize 6" or 8" studs for plumbing walls
- walls with no ceiling shall extend up to underside of decking unless otherwise noted (reference reflected ceiling plan).
- walls with a lowered suspended ceiling should extend 6" above the ceiling height (reference reflected ceiling plan).
- interior wall height note: Utilize 3 5/8" metal studs @ 16" o.c. to an unbraced height of 13'-8", at heights up to 26'-0", utilize 6" 20 ga. studs @ 16" o.c. - adjust stud size as required for allowable L/240 deflection. Verify stud gauge with supplier.
- expansion joint note: Expansion joints shall be installed at a max. of 30'-0". Joints shall also be located to anticipate building movement, structural elements and substrate transition per elevations and wall sections.
- wet wall note: Utilize DensArmor Plus in all plumbing wet walls, walls receiving ceramic tile, and all walls adjacent to plumbing walls or where anticipated to be in contact with moisture.
- substrate: provide tile backerboard at any wall tile locations.
- blocking: Provide in wall blocking for all wall mounted items, including, but not limited to toilet accessories, plumbing fixtures, and hardware.
- maximum length of an unbraced wall shall be 8'-0".


4301 Indian Creek Parkway  
Overland Park, KS 66207  
phone: 913.451.9390  
fax: 913.451.9391  
www.davidsonae.com



a new development for  
**D-BAT - Town Centre Lot 1**  
540 NE Town Centre Drive  
Lee's Summit, Missouri

date 05.19.2022  
drawn by DAE  
checked by DAE  
revisions  
10.13.2022 2

sheet number  
**A2.1**  
drawing type  
FDP & Permit  
project number  
20231







reflected ceiling notes #

- Paint exposed structure off-white in areas open to the public.
- Furnish and install 2x4 suspended ceiling with lighting per reflected ceiling plan.
- Exposed structure finish to remain as-is.
- Reference room finish schedule for ceiling heights
- all materials above suspended ceilings must be fire retardant

reflected ceiling legend




2x4 lay-in LED light fixture with direct/indirect lens for finished areas



2x4 LED utility light fixture for unfinished areas



CLG - 1: 2' x 4' x 3/4", with 15/16" Exposed Tee Grid System, color white



a new development for

D-BAT - Town Centre Lot 1

540 NE Town Centre Drive  
Lee's Summit, Missouri

date 05.19.2022  
drawn by DAE  
checked by DAE  
revisions 10.13.2022 2


sheet number

A2.3

drawing type  
FDP & Permit

project number  
20231





a new development for  
**D-BAT - Town Centre Lot 1**  
540 NE Town Centre Drive  
Lee's Summit, Missouri



date 05.19.2022  
drawn by DAE  
checked by DAE  
revisions  
10.13.2022 2

sheet number

**A2.4**

drawing type  
FDP & Permit

project number  
20231



**1** Enlarged Restroom Plan  
scale: 3/8" = 1'-0"





a new development for  
**D-BAT - Town Centre Lot 1**  
540 NE Town Centre Drive  
Lee's Summit, Missouri


date 05.19.2022  
drawn by DAE  
checked by DAE  
revisions

sheet number


**A4.1**

drawing type  
FDP & Permit


project number  
20231




**1** Wall Section  
scale: 1/2" = 1'-0"



**2** Wall Section  
scale: 1/2" = 1'-0"




**3** Wall Section  
scale: 1/2" = 1'-0"




**4** Wall Section  
scale: 1/2" = 1'-0"







**5** | Clerestory Sill  
scale: 1-1/2" = 1'-0"




**4** | Window Sill @ Shop  
scale: 1-1/2" = 1'-0"




**2** | Window Head @ metal panel  
scale: 1-1/2" = 1'-0"




**9** | Ovhd Door  
scale: 1-1/2" = 1'-0"




**8** | metal panel @ base  
scale: 1-1/2" = 1'-0"




**7** | Stone Cap  
scale: 1-1/2" = 1'-0"




**6** | Gutter  
scale: 1-1/2" = 1'-0"




**12** | Door @ Liner Panel  
scale: 1-1/2" = 1'-0"



**11** | Awning  
scale: 1-1/2" = 1'-0"



**15** | Wall Section  
scale: 1/2" = 1'-0"




**14** | Wall Section  
scale: 1/2" = 1'-0"



## door schedule


door schedule													
door #	doors						frames					fire rating	remarks
	type	mat.	finish	size			type	material	finish	details			
				width	height	thick				jamb	sill		
01	E	alum.	black	3'-0" pr.	7'-0"	1 3/4"	F4	alum.	black	J-2	t-1	-	verify color matches window frames
02	A	wd.	paint	3'-0"	7'-0"	1 3/4"	F3	h.m.	paint	J-4	-	-	
03	B	wd.	paint	3'-0" pr	7'-0"	1 3/4"	F2	h.m.	paint	J-4	-	-	
04	A	wd.	paint	3'-0"	7'-0"	1 3/4"	F3	h.m.	paint	J-4	-	-	
05	A	wd.	paint	3'-0"	7'-0"	1 3/4"	F3	h.m.	paint	J-4	-	-	
06	A	wd.	paint	3'-0"	7'-0"	1 3/4"	F3	h.m.	paint	J-4	-	-	
07	A	wd.	paint	3'-0"	7'-0"	1 3/4"	F3	h.m.	paint	J-4	-	-	
08	A	wd.	paint	3'-0"	7'-0"	1 3/4"	F3	h.m.	paint	J-4	-	-	
09	C	galv. h.m.	paint	3'-0"	7'-0"	1 3/4"	F1	galv. h.m.	paint	J-3	t-2	-	
10a	C	galv. h.m.	paint	3'-0"	7'-0"	1 3/4"	F1	galv. h.m.	paint	J-1	t-2	-	
10b	C	galv. h.m.	paint	3'-0"	7'-0"	1 3/4"	F1	galv. h.m.	paint	J-1	t-2	-	
10c	C	galv. h.m.	paint	pair 3'-0"	7'-0"	1 3/4"	F1	galv. h.m.	paint	J-4	-	-	
11a	D	ovhd	prefin.	3'-0"	7'-0"	1 3/4"	-	-	-	-	t-3	-	paint door to match blue siding, verify size with PEMB dwgs
11b	D	ovhd	prefin.	3'-0"	7'-0"	1 3/4"	-	-	-	-	t-3	-	paint door to match blue siding, verify size with PEMB dwgs
12	C	galv. h.m.	paint	3'-0"	7'-0"	1 3/4"	F1	galv. h.m.	paint	J-1	t-2	-	



window jamb details by window manufacturer; provide prefinished flashing, caulk as required; provide galv. steel lintel at window heads in stone

## 2 | window type

scale: 1/4" = 1'-0"



## 1 | door frame types


scale: 1/4" = 1'-0"

## door and hardware notes


- All hardware shall be clear anodized aluminum or close match with the exception of the exterior entry storefront door, which should match the window frames.
- Coordinate security hardware and electrical that may be required with tenant.
- All hinges at exterior doors shall have non-removable pins.
- Doors with closers shall have ball bearing hinges
- Threshold shall coordinate with adjacent floor finish at either site
- Hardware shall be heavy-duty, commercial grade, level 1 with lever handle
- Finish hardware shall meet article III of ADA
- Keying shall be coordinated with owner prior to order of hardware
- All storefronts shall be caulked around entire perimeter and at the inside corners
- All exterior doors shall include a rain guard
- All glazing shall comply with section 2406 of the 2018 IBC
- All glazing interior or exterior per Section 2406 of the 2018 IBC, including glass mirrors shall be constructed with safety glazing
- Category II glazing is required in storefront doors per section 2406 of the 2018 IBC
- Category A glazing shall be utilized in glazed panels greater than 9 sq. ft. per section 2406 of the 2018 IBC.
- Each pane of safety glazing installed in hazardous locations shall be identified by a manufacturer's designation specifying who applied the designation, the manufacturer or installer and the safety glazing standard with which is complies, as well as the information specified in '2403.1' Section 2403.1. The designation shall be acid etched, sand blasted, ceramic fired, laser etched, embossed or aof a type that once applied, cannot be removed without being destroyed. Tempered spandrel glass is permitted to be identified by the manufacturer with a removable paper designation.
- Panic hardware shall be provided per section 1008.1.10 of the 2018 IBC.

## hardware list


- exterior storefront door: 01 \*match hardware color to door color)
  - rain drip
  - ADA offset door pull
  - panic hardware with closer (compatible with storefront)
  - entry door lockset
  - none removeable hinges
  - door sweep
  - weather gasketing
  - wall stop
- exterior hollow metal door: 10a, 10b, 12
  - rain drip
  - ADA exterior lever handle
  - panic hardware with closer
  - lockset
  - non removeable hinges
  - door sweep
  - weather gasketing
  - floor stop (locate away from floor traffic to avoid tripping hazard)
- interior double door: 03 10c
  - push bar with closer
  - ADA door pulls
  - vertical
  - silencers
  - non removeable hinges
  - wall stop
- sprinkler room: 09
  - rain drip
  - ADA exterior lever handle
  - closer
  - nonremovable hinges
  - door sweep
  - weather gasketing
- office door: 04
  - door stop
  - ADA lever handles with privacy lockset
  - hinges
  - silencers
  - wall stop
- party room/lounge: 06, 21
  - closer
  - ADA lever handles with storeroom lockset
  - hinges
  - silencers
  - wall stop
- multi-stall bathroom: 05, 08
  - closer
  - ADA door pull
  - no-hands door pull
  - push plate
  - kick plate
  - hinges
  - silencers
  - wall stop
- single user bathroom: 22, 23
  - closer
  - ADA lever handles with privacy lockset
  - hinges
  - silencers
  - wall stop
- storage/closet: 02, 07, 21a, 24
  - ADA lever handles with storeroom lockset
  - hinges
  - silencers
  - wall stop
- stair: 20
  - panic hardware with closer
  - ADA door pull
  - silencers
  - kick plates
  - hinges
  - wall stop




j-1



j-2




j-3




j-4

## 4 | Jamb Types


scale: 1'-1/2" = 1'-0"



t-1



t-2



t-3

## 5 | Threshold Types

scale: 1'-1/2" = 1'-0"

a new development for

D-BAT - Town Centre Lot 1

540 NE Town Centre Drive

Lee's Summit, Missouri

date  
05.19.2022  
drawn by  
DAE  
checked by  
DAE  
revisions

sheet number

**A5.1**

drawing type  
FDP & Permit

project number  
20231

a new development for  
**D-BAT - Town Centre Lot 1**  
540 NE Town Centre Drive  
Lee's Summit, Missouri


date 05.19.2022  
drawn by DAE  
checked by DAE  
revisions  
06.20.2022 1  
10.13.2022 2

sheet number

**A5.2**

drawing type  
FDP & Permit

project number  
20231



**1** Finish Floor Plan  
scale: 1/8" = 1'-0" north



## room finish schedule


room no.	room name	floor				base		wall				ceiling		remarks			
		CPT-1	CPT-2	VCT-1	VCT-2	TURF	sc	b1	none	nw	sw	ne	se	act 1	open	dig. htl.	
01	Pro-Shop	●						●		wall finishes per plan 1/A5.2				●		14'-0"	2
02	Storage	●						●		wall finishes per plan 1/A5.2				●	open	-	
03	Hallway			●				●		wall finishes per plan 1/A5.2				●		9'-0"	-
04	Office	●						●		wall finishes per plan 1/A5.2				●		8'-0"	-
05	Restroom			●				●		wall finishes per plan 1/A5.2				●		8'-0"	-
06	Parent Lounge		●					●		wall finishes per plan 1/A5.2				●		12'-0"	2
07	Janitor's Closet			●				●		wall finishes per plan 1/A5.2				●		8'-0"	-
08	Restroom			●				●		wall finishes per plan 1/A5.2				●		8'-0"	-
09	Sprinkler Room						●	●		wall finishes per plan 1/A5.2				●	open	-	
10	Walkway				●			●		wall finishes per plan 1/A5.2				●	open	-	
10c	Storage Closet			●				●		wall finishes per plan 1/A5.2				●	open	-	
11	Batting Cages				●			●		wall finishes per plan 1/A5.2				●	open	-	
12	Cage Access				●			●		wall finishes per plan 1/A5.2				●	open	-	
13	Batting Cages				●			●		wall finishes per plan 1/A5.2				●	open	-	
14	Batting Cages				●			●		wall finishes per plan 1/A5.2				●	open	-	

## finish legend

CPT-1	carpet tile, Philadelphia Commercial, style: Counterpart (54816), size: 24" x 24", color: Copilot (16400)
CPT-2	carpet tile, Philadelphia Commercial, style: Counterpart (54816), size: 24" x 24", color: Correlate (16505)
VCT-1	vinyl composite tile, Armstrong Flooring, style: Standard Excelon Imperial Texture VCT, size: 12" x 12", color: Gentian Blue (51946)
VCT-2	vinyl composite tile, Armstrong Flooring, style: Standard Excelon Imperial Texture VCT, size: 12" x 12", color: Pomegranate Red (51814) pricing alternate: basis of design Restek epoxy floor, colored flakes with red as primary color - submit sample for tenant approval
TURF	D-BAT Turf
SC	sealed concrete - ashford sealer
B-1	vinyl base, manufacturer: TBD, standard cove, size: 4", color: gray
PT-1	wall paint, manufacturer: TBD, finish: eggshell, color: D-Bat Gold (1 coat primer, 2 coats paint - to cover)
PT-2	wall paint, manufacturer: TBD, finish: eggshell, color: D-Bat Red (1 coat primer, 2 coats paint - to cover)
PT-3	wall paint, manufacturer: TBD, finish: eggshell, color: D-Bat White (1 coat primer, 2 coats paint - to cover)
PT-4	wall paint, manufacturer: TBD, finish: eggshell, color: D-Bat Green (1 coat primer, 2 coats paint - to cover) - from base to 12'-0" a.f.f.
PT-5	epoxy paint, manufacturer: TBD, color: D-Bat White (1 coat primer, 2 coats paint - to cover)
primer	primer, sherwin williams, PrepRite High Build latex primer/surfacer, B28V601
PL-1	plastic laminate, wilsonart, color: indigo (D379)
PL-2	plastic laminate, wilsonart, color: dove grey (D92)
ACT-1	acoustical ceiling tile, armstrong, 2x2, prelude xl 1/8" exposed tee grid, dune #1774, angled tegular (revealed), fine texture, white
LP-1	liner panel, Chief Buildings, steel liner panel, color: Emerald Green (EG)
door	door finish, manufacturer: TBD, color: manufacturer's standard white


## finish notes:

- All interior glazing to be clear. Temper all interior glass.
- Interior aluminum storefront shall have clear anodized aluminum finish
- Each material specified for application on the entire project shall be from the same dye lot.
- All surfaces shall be cleaned and conditioned to receive new finish as required by finish product manufacturer. Surfaces shall be smooth, free from depressions, protrusions, pits, slumps, streaks, flashing, and variation in texture. Installer/subcontractor shall notify general contractor prior to installation if conditions are not satisfactory.
- All wall mounted mechanical slots or grilles to be painted to match the wall on which they occur. Do not paint prefinished wall mullion end caps.
- Contractor shall be responsible for leveling of floor slabs to receive specified finishes.
- All patterned flooring to be centered in both directions and generated from center of room outward toward partitions, unless otherwise noted.
- All floor finish changes to occur under centerline of door in closed position.
- Combustible interior finish products shall be provided per the requirement of the international building code section 803.4.
- Carpet seams shall occur at junctions of partitions, thresholds or change of direction in corridors. No strip patch allowed smaller than 4'-0".
- Finishes shall be bid as specified or as approved equal only.
- Utilize dens-armour plus in all plumbing wet walls, walls anticipated to be in contact with moisture, or walls receiving ceramic tile.
- All interior ceramic corners & tops shall receive schluter trim.
- Refer to finish legend for level of gypsum board finish as defined by the gypsum association.
- LVT to sealed concrete shall occur with rubber transition to match base color.




6 ADA sink  
scale: 1/2" = 1'-0"

5 Sink Base Cabinet  
scale: 1" = 1'-0"



4 Base Cabinet  
scale: 1" = 1'-0"



3 Parents' Lounge Elevation  
scale: 1/4" = 1'-0"

a new development for

D-BAT - Town Centre Lot 1

540 NE Town Centre Drive

Lee's Summit, Missouri

date  
05.19.2022  
drawn by  
DAE  
checked by  
DAE  
revisions

06.20.2022 1  
10.13.2022 2

sheet number

A5.3

drawing type  
FDP & Permit

project number  
20231



## MECHANICAL SPECIFICATIONS

1. GENERAL PROVISIONS:
- A. PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, NECESSARY FOR THE COMPLETE INSTALLATION OF THE PLUMBING AND MECHANICAL SYSTEMS OUTLINED.
- B. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE APPLICABLE AUTHORITIES.
- C. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION OVER THE SITE.
- D. ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.
- E. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, PIPE, DUCT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNDAMAGED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERINGS SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.
- F. PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS AS NECESSARY. PATCHES SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.
- G. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
2. OPERATION AND MAINTENANCE MANUALS:
- A. DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, Piping DIAGRAMS, CATALOGS, CUTS, LUBRICATION AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.
- B. ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATION AND MAINTENANCE MANUALS.
- C. ALL LITERATURE LISTED ABOVE AND ALL PAPERS LISTING WARRANTIES, ETC. SHALL BE BOUND IN A 3-RING BINDER AND LABELED WITH THE PROJECT NAME, ADDRESS, ARCHITECT, ENGINEER, CONTRACTORS, ETC.
3. MANUFACTURERS:
- A. MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSIDERED AS LIMITING COMPETITION. STRUCTURES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO ARCHITECTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN, UNLESS NOTED OTHERWISE.
4. MOTORS:
- A. PROVIDE THERMAL OVERLOAD PROTECTION FOR EACH MOTOR PROVIDED BY THIS WORK.
5. TESTING, BALANCING, AND CLEANING:
- A. ALL PIPING SHALL BE TESTED FOR LEAKS BEFORE BEING CONCEALED IN WALL CONSTRUCTION OR COVERED WITH INSULATION.
- B. SEWER AND VENT PIPING SHALL BE HYDROSTATICALLY TESTED WITH NO LESS THAN 10 FEET OF HEAD FOR A PERIOD OF NOT LESS THAN 15 MINUTES, PER THE LOCAL PLUMBING CODE, WITH NO LEAKS.
- C. FIRE PROTECTION PIPING SHALL BE TESTED IN ACCORDANCE WITH THE REQUIREMENTS OF NFPA.
- D. DOMESTIC WATER PIPING SHALL BE HYDROSTATICALLY TESTED AT A PRESSURE OF NOT LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE, BUT NOT LESS THAN 60 PSI, FOR A PERIOD OF NOT LESS THAN 2 HOURS, WITH NO LEAKS.
- E. NATURAL GAS PIPING SHALL BE PNEUMATICALLY TESTED AT A PRESSURE OF NOT LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE, BUT NOT LESS THAN 90 PSI, FOR A PERIOD OF NOT LESS THAN 2 HOURS, WITH NO LEAKS.
- F. DUCTWORK AND PIPING SHALL BE BALANCED BY QUALIFIED INDEPENDENT BALANCING PERSONNEL, WHO HAVE PREVIOUS EXPERIENCE WITH BALANCING PROCEDURES AND ARE CERTIFIED BY THE ASSOCIATED AIR BALANCE ASSOCIATION (AIA) OR NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB).
- 1) BALANCING SHALL INCLUDE THE BALANCING OF THE EQUIPMENT AND AIR DISTRIBUTION SYSTEMS TO PROVIDE DESIGN QUANTITIES INDICATED AND VERIFICATION OF PERFORMANCE OF ALL EQUIPMENT AND AUTOMATIC CONTROLS.
- 2) WITH IN 30 DAYS OF THE COMPLETION OF THE TESTING AND BALANCING WORK, SUBMIT THE TEST AND BALANCING REPORT BEARING THE SIGNATURE OF THE TEST AND BALANCING ENGINEER. THE REPORTS SHALL BE CERTIFIED PROOF THAT THE SYSTEMS HAVE BEEN TESTED, ADJUSTED, AND BALANCED IN ACCORDANCE WITH THE REFERENCED STANDARDS, ARE AN ACCURATE REPRESENTATION OF HOW THE SYSTEMS HAVE BEEN INSTALLED AND ARE OPERATING. REPORTS SHALL BE BOUND IN A VINYL BINDER AND THE BINDER LABELED OR MAY BE AN ELECTRONIC PDF SUBMITTAL.
6. BEFORE DOMESTIC WATER PIPING IS PLACED IN SERVICE, ALL DOMESTIC WATER DISTRIBUTION SYSTEMS, INCLUDING THOSE FOR COLD WATER AND HOT WATER SYSTEMS, SHALL BE FLUSHED, STERILIZED AND CHLORINATED IN ACCORDANCE WITH HEALTH DEPARTMENT REGULATIONS. THE SYSTEMS SHALL BE THOROUGHLY FLUSHED OF ALL DIRT AND FOREIGN MATTER, THEN FILLED WITH WATER TREATED WITH 50 PPM OF CHLORINE. DURING THE FILLING PROCESS, VALVES AND FAUCETS SHALL BE OPENED SEVERAL TIMES TO ALLOW AIR TO BE PURGED FROM THE SYSTEM. THE TREATED WATER SHALL BE LEFT IN THE SYSTEM FOR 24 HOURS AFTER WHICH TIME THE SYSTEM SHALL BE FLUSHED. IF THE RESIDUAL CHLORINE IS NOT LESS THAN 10 PPM, THE FLUSHING SHALL BE REPEATED. AFTER STERILIZATION, SAMPLES OF WATER IN THE SYSTEM SHALL BE APPROVED BY THE BOARD OF HEALTH.
7. PLUMBING:
- A. PROVIDE AN APPROVED WATER HAMMER ARRESTOR FOR EACH PLUMBING FIXTURE SUPPLY AS REQUIRED BY FIXTURE MANUFACTURER.
- B. ALL EXPOSED WASTE PIPE SHALL BE CHROME PLATED BRASS PIPE, NO FERROUS PIPE.
- C. PROVIDE CLEANOUTS AT EACH CHANGE OF DIRECTION AND AT 100 FOOT INTERVALS IN STRAIGHT RUNS.
- D. PROVIDE ACCESS PANELS FOR ALL CONCEALED VALVES AND TRAPS.
- E. CLEANOUTS:
- 1) VINYL TILE FLOOR, JR. SMITH #4140, OR EQUAL.
- 2) QUARRY TILE FLOOR, JR. SMITH #4200, OR EQUAL.
- 3) CARPETED FLOOR, JR. SMITH #4020-Y, OR EQUAL.
- 4) FINISHED FLOOR, JR. SMITH #4020, OR EQUAL.
- 5) WALL, JR. SMITH #4472, OR EQUAL. 24" ABOVE THE FLOOR.
- 6) GRADE, JR. SMITH #4256, OR EQUAL, WITH HEAVY DUTY CAST IRON BODY AND COVER.
- F. PROVIDE ELECTRIC UNIONS WITH APPROPRIATE END CONNECTIONS TO MATCH THE PIPE SYSTEM IN WHICH INSTALLED (SCREWED, SOLDERED, OR FLANGED). PROVIDE FOR ELECTRICAL UNIONS ON ALL PIPING CONNECTIONS TO HOT WATER HEATERS AND EXPANSION TANKS.
8. WATER HEATERS:
- 1) EVERY WATER HEATER SHALL HAVE AN APPROVED MEANS INSTALLED ON THE COLD WATER SUPPLY LINE ABOVE THE EQUIPMENT TO PREVENT SIPHONING OF A STORAGE WATER HEATER OR TANK.
- 2) BOTTOM FED WATER HEATERS AND TANKS CONNECT TO WATER HEATERS SHALL HAVE A VACUUM RELIEF VALVE INSTALLED, ANSI 121.22.
- 3) STORAGE HEATERS OPERATING ABOVE ATMOSPHERIC PRESSURE SHALL HAVE AN APPROVED PRESSURE RELIEF VALVE AND/OR TEMPERATURE RELIEF VALVE.
9. ALL SEWER PIPING LOCATED INSIDE THE BUILDING SHALL BE INSTALLED WITH THE FOLLOWING SLOPES:
- 1) INSTALL 2-1/2" AND SMALLER PIPE AT 1/4" PER FOOT FALL.
- 2) INSTALL 3" AND LARGER PIPE AT 1/8" PER FOOT FALL.
- ALL SEWER PIPING LOCATED EXTERIOR TO THE BUILDINGS SHALL BE INSTALLED WITH THE FOLLOWING SLOPES:
- 1) INSTALL 4" AND SMALLER PIPE AT A MINIMUM OF 2% SLOPE.
- 2) INSTALL 6" AND LARGER PIPE AT A MINIMUM OF 1% SLOPE.
10. PIPING:
- A. DOMESTIC COLD, AND HOT WATER (ABOVEGROUND).
- 1) TYPE L HARD DRAWN COPPER TUBING, ASTM B-88.
- a) WROUGHT COPPER, ASTM B15 ALLOY C12200, ANSI B16.22, MS6 SP-104.
- b) MECHANICAL PRESS COPPER FITTINGS FOR USE IN PLUMBING OR MECHANICAL APPLICATIONS, ASME B16.22, ASME B16.51, OR ASME B16.10. MECHANICAL PRESS COPPER FITTINGS SHALL CONFORM TO APMO PS-11T OR ASME B16.51.
- 2) PEK, HIGH-DENSITY CROSS-LINKED POLYETHYLENE TUBING SHALL BE MANUFACTURED TO THE REQUIREMENTS OF ASTM F-816 AND MEET THE STANDARD GRADE HYDROSTATIC PRESSURE RATINGS FROM PLASTIC PIPE INSTITUTE IN ACCORDANCE WITH TR-4020.
- (MUST BE INSTALLED PER THE MANUFACTURERS REQUIREMENTS FOR FLENUM USE)
- a) PEK-A AND PEK-B MEETING ANSI/NFPA 61 AND ANSI/NFPA 32 STANDARDS FOR POTABLE WATER SAFETY AND LEAD-FREE STANDARD AND MUST BE MARKED WITH "PNS-6", "NSF-61-6" OR OTHER NSF-APPROVED MARKING, ASTM F-2023 FOR USE WITH CHLORINATED WATER.
- (MUST BE INSTALLED PER THE MANUFACTURERS REQUIREMENTS FOR FLENUM USE)
- b) PEK MECHANICAL CRIMP END EXPANSION FITTINGS SHALL BE MANUFACTURED WITH MANUFACTURERS INSTRUCTIONS. PIPE SIZES GIVEN ON THE DRAWINGS ARE NOMINAL COPPER PIPE SIZE. INCREASE PEK PIPING SIZE TO EQUAL OR EXCEED COPPER PIPE INSIDE DIAMETER FOR SUPPLY MAINS. (MUST BE INSTALLED PER THE MANUFACTURERS REQUIREMENTS FOR FLENUM USE)
- 3) VALVES:
- a) TO BE INSTALLED ON THE FIXTURE SUPPLY TO EACH PLUMBING FIXTURE.
- b) TO BE INSTALLED ON THE WATER SUPPLY SIDE TO EACH APPLIANCE OR MECHANICAL EQUIPMENT.
- c) TYPES:
1. GATE VALVE, JOMAR T/S-3010 OR EQUAL, LEAD-FREE NSF 61, ANSI B1.01.1.
2. GLOBE VALVE, JOMAR T/S-3010 OR EQUAL, LEAD-FREE NSF 61, ANSI B1.01.1.
3. BALL VALVE, JOMAR J1000XP OR EQUAL, COMPACT LEAD FREE BRASS BALL VALVE, UL642, CSA 5971-12, 1-1/2" FM, CALIFORNIA CODE, ABS/NSF 61, AWWA 95X APPROVED.
4. BALL VALVE, JOMAR T-1000, EQUAL, UL642, FM, CSA, NSF 61-5, MSS SP-110.
- B. DOMESTIC WATER SERVICE, 1-1/2"
- 1) TYPE K SOFT DRAWN COPPER TUBING, ASTM B-88.
- a) Cast Copper Alloy Fittings for Flared Copper Tube, ASME/ANSI B16.26.
- 2) HOPE, PIGMENTED BLUE THROUGHOUT, OT9 SIZES 1-1/2" AWWA C901 4710 DR11 PC200 IPS SIZES 2"-3", AWWA C901 4710 DR11 PC200 MATERIAL AND INSTALLATION MUST CONFORM TO WATER DEPARTMENT REQUIREMENTS.
- C. WATER (FIRE) SERVICE, 3" OR LARGER.
- 1) DUCTILE IRON PIPE & FITTINGS, AWWA C151, CLASS 50, CEMENT LINING, SEALCOATED, AWWA C900, MUST BE USED IN ACCORDANCE WITH NFPA 24.
- 2) HOPE IPS SIZES PIGMENTED BLUE THROUGHOUT, 3" AWWA C901 4710 DR11 PC200 4" AND LARGER, AWWA C906 3406/4710 DR19.5 PC160
- a) FITTINGS MUST BE USED IN THE ENDS OF THE HOPE, APPROVED TRACE NIRE MUST BE USED.
- b) 12 AND COPPERHEAD REINFORCED TRACE NIRE (BLUE IN COLOR)
- b) MATERIAL AND INSTALLATION MUST CONFORM TO WATER DEPARTMENT REQUIREMENTS.
- 3) POLYVINYL CHLORIDE (PVC) PIPE, AWWA C900, CLASS 200, WITH BELL END AND ELASTOMERIC GASKET, WITH PLAN END FOR CAST-IRON OR DUCTILE-IRON FITTINGS, OR PVC ELASTOMERIC GASKET FITTINGS.
- a) PVC COUPLINGS AND FITTINGS, AWWA C900, WITH ASTM F 471 ELASTOMERIC SEAL GASKETS, ASTM F 471, ELASTOMERIC SEAL.
- b) DUCTILE-IRON AND CAST-IRON FITTINGS: AWWA C110, DUCTILE-IRON OR CAST-IRON, 250-PSI PRESSURE RATING, OR AWWA C150, DUCTILE-IRON COMPACT FITTINGS, 350-PSI PRESSURE RATING, OR DIMENSION TO MATCH PIPE OUTSIDE DIAMETER, AWWA C104, CEMENT MORTAR LINING, GASKETS PER AWWA C111, RUBBER.
- 4) THRUST BLOCKS IN ACCORDANCE WITH NFPA 24.
- D. LEAD CONTENT OF WATER SUPPLY PIPE AND FITTINGS:
- 1) PIPE AND PIPE FITTINGS, INCLUDING VALVES AND FAUCETS, UTILIZED IN THE WATER SUPPLY SYSTEM SHALL NOT HAVE MORE THAN 0% LEAD CONTENT.
- 2) PIPE, PIPE FITTINGS, JOINTS, VALVES, FAUCETS, AND FIXTURE FITTINGS UTILIZED TO SUPPLY WATER FOR DRINKING OR COOKING PURPOSES SHALL CONFORM WITH NSF 372 AND SHALL HAVE A WEIGHTED AVERAGE LEAD CONTENT OF 0.25% OR LESS.

## MECHANICAL SPECIFICATIONS (CONTINUED)

- E. SANITARY SEWER, AND VENTS (UNDERGROUND, INTERIOR TO THE BUILDING).
- 1) ABS PIPE AND FITTINGS: ABS PIPE AND FITTINGS SHALL CONFORM WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS." FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKINGS WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SERVICE" FOR PLASTIC SEWER PIPING. SOLID-WALL ABS PIPE, ASTM D 2661, SCHEDULE 40. ABS SOCKET FITTINGS: ASTM D 2661, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS. SOLVENT CEMENT: ASTM D 2235.
- 2) PVC PIPE AND FITTINGS: PVC PIPE AND FITTINGS SHALL CONFORM WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS." FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKINGS WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SERVICE" FOR PLASTIC SEWER PIPING. SOLID-WALL PVC PIPE, ASTM D 2665, DRAIN, WASTE, AND VENT, PVC SOCKET FITTINGS: ASTM D 2665, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS AND TO FIT SCHEDULE 40 PIPE. ADHESIVE PRIMER: ASTM F 656, SOLVENT CEMENT: ASTM D 2664.
- 3) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 888 AND CSPI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO CSPI STANDARD 310 AND BE CERTIFIED BY NSF6 INTERNATIONAL. HUB AND SPIGOT CAST IRON PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 74.
- 4) SANITARY SEWER, AND VENTS (ABOVE GROUND, INTERIOR TO THE BUILDING).
- 1) ABS PIPE AND FITTINGS: ABS PIPE AND FITTINGS SHALL CONFORM WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS." FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKINGS WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SERVICE" FOR PLASTIC SEWER PIPING. SOLID-WALL ABS PIPE, ASTM D 2661, SCHEDULE 40. CELLULAR-CORE ABS PIPE: ASTM F 620, SCHEDULE 40 ABS SOCKET FITTINGS: ASTM D 2661, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS. SOLVENT CEMENT: ASTM D 2235. (NOT FOR USE IN A RETURN AIR FLENUM)
- 2) PVC PIPE AND FITTINGS: PVC PIPE AND FITTINGS SHALL CONFORM WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS." FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKINGS WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SERVICE" FOR PLASTIC SEWER PIPING. SOLID-WALL PVC PIPE, ASTM D 2665, DRAIN, WASTE, AND VENT, PVC SOCKET FITTINGS: ASTM D 2665, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS AND TO FIT SCHEDULE 40 PIPE. ADHESIVE PRIMER: ASTM F 656, SOLVENT CEMENT: ASTM D 2664. (NOT FOR USE IN A RETURN AIR FLENUM)
- 3) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 888 AND CSPI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO CSPI STANDARD 310 AND BE CERTIFIED BY NSF6 INTERNATIONAL. HUB AND SPIGOT CAST IRON PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 74.
6. SANITARY SEWER, AND VENTS (UNDERGROUND, EXTERIOR TO THE BUILDING).
- 1) ABS PIPE AND FITTINGS: ABS PIPE AND FITTINGS SHALL CONFORM WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS." FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKINGS WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SERVICE" FOR PLASTIC SEWER PIPING. SOLID-WALL ABS PIPE, ASTM D 2661, SCHEDULE 40. ABS SOCKET FITTINGS: ASTM D 2661, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS. SOLVENT CEMENT: ASTM D 2235.
- 2) PVC PIPE AND FITTINGS: PVC PIPE AND FITTINGS SHALL CONFORM WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS." FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKINGS WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SERVICE" FOR PLASTIC SEWER PIPING. SOLID-WALL PVC PIPE, ASTM D 2665, DRAIN, WASTE, AND VENT, PVC SOCKET FITTINGS: ASTM D 2665, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS AND TO FIT SCHEDULE 40 PIPE. ADHESIVE PRIMER: ASTM F 656, SOLVENT CEMENT: ASTM D 2664. (NOT FOR USE IN A RETURN AIR FLENUM)
- 3) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 888 AND CSPI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO CSPI STANDARD 310 AND BE CERTIFIED BY NSF6 INTERNATIONAL. HUB AND SPIGOT CAST IRON PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 74.
7. CONDENSATE DRAINS & INDIRECT WASTE (ABOVEGROUND).
- 1) CONDENSATE DRAINS: 1/2" DIA. PVC PIPE, SCHEDULE 40, SOLVENT JOINT (CONDENSATE).
- 2) DWV, WROUGHT COPPER, ANSI B-16.22 (WATER HEATER IP).
1. REFRIGERANT.
- 1) ASTM B 280, TYPE ACR, HARD-DRAWN STRAIGHT LENGTHS, AND SOFT-ANNEALED COILS, SEAMLESS COPPER TUBING.
- 2) REFRIGERANT COILS: 1/2" DIA. COPPER, ANSI B16.22, STREAMLINED PATTERN, FITTINGS: BRAZED JOINTS, AMS A 5.9, CLASSIFICATION BAg-1 (SILVER).
- 3) TUBING SHALL BE FACTORY CLEANED, READY FOR INSTALLATION, AND HAVE ENDS CAPPED TO PROTECT CLEANLINESS OF PIPE INTERIORS PRIOR TO SHIPPING.
- 4) SIZE AND INSTALLATION OF PIPE SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- 1) NATURAL GAS.
- a) BLACK STEEL PIPE, SCHEDULE 40, ASTM A53.
- b) PIPE 3" AND SMALLER: 150 LB. MALLEABLE IRON, THREADED FITTINGS.
- c) PIPE 4" AND SMALLER: VESGA MSA9865 60 FOR WATER AND GAS, CSA L64, T58A/ASME B31 FOR USE WITH ASTM A53 SCHEDULE 40 BLACK IRON PIPE.
- d) PIPE 2-1/2" AND LARGER, WELDED.
- e) FLUG VALVE: ROCKWELL NORDSTROM FIGURE NO. 142 OR 143.
- f) BALL VALVE: JOMAR T-1000E, APPROVALS: UL642, FM, CSA, NSF 61-5, MSS SP-110
- 2) GAS PIPING PANS:
- a) ALL BLACK STEEL GAS PIPING LOCATED EXTERIOR TO THE BUILDING SHALL BE PRIMED AND PAINTED TO EITHER MATCH ADJACENT EXTERIOR WHERE LOCATED OR NEAR EXTERIOR WALL AND PAINTED SATIN YELLOW WHERE LOCATED ON THE ROOF.
- K. ALL PIPE HANGERS AND SUPPORTS SHALL BE STANDARD PRODUCTS OF GRINNELL, FEE AND MASON, OR ELCEN. HANGER SPACING SHALL BE IN ACCORDANCE WITH MSS SP-64.
- L. SLEEVES
- 1) PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK. ALL SLEEVES SHALL BE OF SUFFICIENT SIZE TO PERMIT PIPE MOVEMENT DUE TO EXPANSION AND CONTRACTION AND TO ACCOMMODATE PIPE INSULATION.
- 2) INTERIOR PARTITIONS: 16 GAUGE GALVANIZED STEEL, PACK BETWEEN PIPE AND SLEEVE WITH FIRE SAFING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.
- 3) ROOF: PROSECT OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WATERPROOF SEAL. COORDINATE WATER AND FLASH AS REQUIRED TO MATCH THE PASSAGE OF WATER INTO OR OUT OF THE ROOF.
- 4) PROTECTION AGAINST CONTACT: METALLIC PIPING, EXCEPT FOR CAST IRON, DUCTILE IRON AND GALVANIZED STEEL SHALL NOT BE PLACED IN DIRECT CONTACT WITH STEEL FRAMING MEMBERS, CONCRETE, OR GINDER WALLS AND FLOORS OR OTHER MASONRY. METALLIC PIPING SHALL NOT BE PLACED IN DIRECT CONTACT WITH CORROSIVE SOIL. SHEATHING USED TO PREVENT DIRECT CONTACT SHALL HAVE A THICKNESS OF GREATER THAN 0.009" AND THE SHEATHING SHALL BE MADE OF PLASTIC, ANY PIPE THAT PASSES THROUGH A FOUNDATION WALL OR FOOTING SHALL BE PROVIDED WITH A RELIEVING ARCH, OR A PIPE SLEEVE SHALL BE BUILT INTO THE FOUNDATION WALL. THE SLEEVE SHALL BE TWO TIMES GREATER THAN THE PIPE PASSING THROUGH THE WALL OR FOOTING.
- 5) PLUMBING VENTS: FLASH ROOF VENT INTO ROOFING SYSTEM AS REQUIRED BY THE ROOFING CONTRACTOR TO MAINTAIN EXISTING ROOF WARRANTY. ALL PLUMBING VENT TERMINALS SHALL TERMINATE A MINIMUM OF 12" ABOVE ROOF OR EQUAL TO HEIGHT OF PARAPET, WHICHEVER IS GREATER.
- M. PROVIDE CHROME PLATED ESCUTCHEONS ON ALL PIPE ENTERING FINISHED AREAS.
- B. WATER HEATERS
- A. COMMERCIAL, LIGHT-DUTY, STORAGE, ELECTRIC, DOMESTIC-WATER HEATERS:
1. STANDARD: UL 174
2. STORAGE-TANK CONSTRUCTION: STEEL, VERTICAL ARRANGEMENT.
- a. PRESSURE RATINGS: 150 PSIG.
- b. INTERIOR FINISH: COMPLY WITH NSF 61 AND NSF 372 BARRIER MATERIALS FOR POTABLE-WATER TANK LININGS, INCLUDING EXTENDING FINISH INTO TAPINGS.
3. FACTORY-INSTALLED, STORAGE-TANK APPURTENANCES:
- a. ANODE ROD: REPLACEABLE MAGNESIUM.
- b. DIP TUBE: REQUIRED UNLESS COLD-WATER INLET IS NEAR BOTTOM OF TANK.
- c. DRAIN VALVE: CORROSION-RESISTANT METAL WITH HOSE-END CONNECTION.
- d. INSULATION: COMPLY WITH ASHRAE 90.1.
- e. JACKSET AFTER THE INLET VALVE FINISH OR HIGH-IMPACT COMPOSITE MATERIAL.
- f. HEAT-TRAP FITTINGS: INLET TYPE IN COLD-WATER PIPE INLET AND OUTLET TYPE IN HOT-WATER OUTLET.
- g. HEATING ELEMENTS: ELECTRIC, SCREW-IN IMMERSION TYPE.
- h. TEMPERATURE CONTROL: ADJUSTABLE THERMOSTAT.
- i. SAFETY CONTROL: HIGH-TEMPERATURE-LIMIT CUTOFF OR BY SYSTEM.
- j. RELIEF VALVE: ASME RATED AND STAMPED FOR COMBINATION TEMPERATURE-AND-PRESSURE RELIEF VALVES, INCLUDING RELIEF CAPACITY AT LEAST AS GREAT AS HEAT INPUT, AND INCLUDE PRESSURE SETTING LESS THAN WORKING-PRESSURE RATINGS OF DOMESTIC-WATER HEATER. SELECT RELIEF VALVE WITH SENSING ELEMENT THAT EXTENDS INTO STORAGE TANK.
- B. DOMESTIC-WATER EXPANSION TANKS:
1. DESCRIPTION: STEEL, PRESSURE-RATED TANK CONSTRUCTED WITH WELDED JOINTS AND FACTORY-INSTALLED BUTYL-RUBBER DIALPHRAM, INCLUDE AIR PRECHARGE TO MINIMUM SYSTEM-OPERATING PRESSURE AT TANK.
2. CONSTRUCTION:
- a. TAPPINGS: FACTORY-FABRICATED STEEL, WELDED TO TANK BEFORE TESTING AND LABELING. INCLUDE ASME B1.01 PIPE THREAD.
- b. INTERIOR FINISH: COMPLY WITH NSF 61 AND NSF 372 BARRIER MATERIALS FOR POTABLE-WATER TANK LININGS, INCLUDING EXTENDING FINISH INTO AND THROUGH TANK FITTINGS AND OUTLETS.
- c. AIR-CHARGING VALVE: FACTORY INSTALLED.
3. CAPACITY AND CHARACTERISTICS:
- a. WORKING-PRESSURE RATINGS: 150 PSIG.
4. FIRE PROTECTION (NET PIPE SPRINKLER SYSTEM).
- A. PROVIDE A "NET-PIPE" SPRINKLER SYSTEM WITH AUTOMATIC SPRINKLERS AND CONNECTED TO A SUFFICIENT WATER SUPPLY.
- B. THE SYSTEM DESIGN SHALL BE BASED ON LIGHT HAZARD CLASSIFICATION, NFPA 13.
- C. THE NET PIPE SPRINKLER SYSTEM SHALL CONFORM TO ALL REQUIREMENTS OF THE OWNER'S INSURANCE CARRIER AND LOCAL FIRE DEPARTMENT. THE SYSTEM SHALL BE DESIGNED TO PROTECT THE BUILDING FROM FIRE.
- D. THE NET PIPE SPRINKLER SYSTEM SHALL BE HYDRAULICALLY DESIGNED, BASED ON A WATER FLOW DATA OBTAINED FROM THE LOCAL WATER OR FIRE DEPARTMENT.
- E. PIPE AND TUBING MATERIALS:
- 1) STEEL PIPE, SMALLER THAN 2".
- a) ASTM A 53/A 53M STANDARD, SCHEDULE 40, SEAMLESS, BLACK STEEL PIPE.
- b) ASTM A 192/A 192M OR ASTM A 789M, OR ASME B36.10M, WALL THICKNESS GREATER THAN OR EQUAL TO SCHEDULE 40, OR NOTED OTHERWISE.
- c) ASTM A 135 OR ASTM A 193/A 193M, THEATREABLE, WALL THICKNESS GREATER THAN SCHEDULE 30 AND GREATER THAN SCHEDULE 10, BLACK STEEL PIPE.
- d) ASTM A 192 OR ASTM A 193/A 193M SCHEDULE 5, BLACK STEEL PIPE.
- 2) STEEL PIPE, 2" AND LARGER: ASTM A 789, SCHEDULE 10, SEAMLESS, BLACK STEEL.

## MECHANICAL SPECIFICATIONS (CONTINUED)

- F. FITTINGS:
- 1) CAST-IRON THREADED FITTINGS: ANSI B16.4, CLASS 125, STANDARD PATTERN, FOR THREADED JOINTS. THREADS SHALL CONFORM TO ANSI B1.20.1.
- 2) MALLEABLE-IRON THREADED FITTINGS: ANSI B16.3, CLASS 150, STANDARD PATTERN, FOR THREADED JOINTS. THREADS SHALL CONFORM TO ANSI B1.20.1.
- 3) STEEL FITTINGS: ASTM A 234, SEAMLESS OR WELDED, FOR WELDED JOINTS.
- 4) GROVED MECHANICAL FITTINGS: ASTM A 336, GRADE 68-45-12 DUCTILE IRON; ASTM A 414, GRADE 68-45-12 MALLEABLE IRON; OR ASTM A 414, TYPE 1, E, OR 3, GRADE 68-45-12 DUCTILE IRON. FITTINGS WITH GROOVES OR SHOULDERS DESIGNED TO ACCEPT GROVED END COUPLINGS, IN ACCORDANCE WITH ITS LISTED FITTINGS.
- 5) HANGERS AND SUPPORTS:
- 1) HANGERS, ANCHORS, AND SUPPORTS FOR FIRE PROTECTION PIPING AND EQUIPMENT SHALL BE IN ACCORDANCE WITH NFPA 13. HANGERS, ANCHORS, SUPPORTS, AND COMPONENTS SHALL BE LISTED BY UL AND ANY OTHER AGENSIES REQUIRED BY THE LOCAL FIRE AUTHORITIES AND THE OWNER'S INSURANCE CARRIER.
- 2) AUTOMATIC SPRINKLERS:
- 1) SPRINKLER HEADS: TYPE AS INDICATED OR REQUIRED BY THE APPLICATION, UNLESS OTHERWISE REQUIRED, PROVIDE QUICK RESPONSE WITH NOMINAL 1/2 INCH DISCHARGE ORIFICE, FOR "LIGHT HAZARD" TEMPERATURE RANGE.
- 2) SPRINKLER HEADS SHALL BE OF THE FOLLOWING CONSTRUCTION, CONFIGURATIONS, AND FINISH FOR THE AREAS INDICATED:
- a) FINISHED AREAS: SEMI-RECESSED PENDANT, CHROME PLATED, CHROME ESCUTCHEON CUP.
- b) UNFINISHED AREAS: UPRIGHT, ROUGH BRASS.
- 3) FURNISH THREE EXPOS, ONE FOR EACH OF THE HEADS OF EACH TYPE IN THE PROJECT, AND PROVIDE A SPRINKLER HEAD CABINET AND ANY SPECIAL WRENCHES TO REMOVE OR INSTALL SPRINKLER HEADS.
- 4) FURNISH QUICKSTOP TAPON SPRINKLER TOOL, QUICKSTOP TAPON SHALL STOP 1/2" AND 3/4" HEADS. THE TOOL SHALL HAVE A FUSIBLE LINK TO RELEASE THE TOOL IF HEATED AND SHALL BE 100% WATER TIGHT UP TO 350 PSI.
- I. ALARM DEVICES:
- 1) WATER FLOW INDICATORS: VANE TYPE WATERFLOW DETECTOR, RATED TO 250 PSIG, DESIGNED FOR HORIZONTAL OR VERTICAL INSTALLATION, HAVE 2-SPOT CIRCUIT SWITCHES TO PROVIDE ISOLATED ALARM AND AUXILIARY CONTACTS, 1 AMPERE 125 VOLTS AC AND 0.25 AMPERE 24 VOLTS DC, COMPLETE WITH ADJUSTABLE RETARD ELEMENT TO PREVENT FALSE SIGNALS, AND TAMPER-PROOF COVER WHICH SENDS A SIGNAL WHEN COVER IS REMOVED.
- 2) SUPERVISORY SWITCHES: SPST, NORMALLY CLOSED CONTACTS, DESIGNED TO SIGNAL WHEN VALVE IS OTHER THAN FULL OPEN POSITION.
10. INSULATION AND DUCT LININGS:
- A. ALL INSULATIONS AND ACCESSORIES SHALL HAVE A FIRE HAZARD CLASSIFICATION WITH A FLAME SPREAD RATING OF NOT OVER 25, A SMOKE DEVELOPED RATING OF NOT OVER 80, AND A SMOKE DEVELOPED RATING OF NOT OVER 80, IN ACCORDANCE WITH NFPA.
- B. PIPE INSULATION - ABOVE GRADE:
- 1) THE PIPING INSULATION USED SHALL HAVE A THERMAL CONDUCTIVITY OF 0.21 BTU PER IN/H-SQ-FT OR LESS.
- 2) FIBERGLASS INSULATION WITH FACTORY APPLIED VAPOR BARRIER, ASU JACKET, FACTORY APPLIED PRESSURE SEALING AND INSULATION LAP JOINT NO STAPLES, ZESTON PRESOLVED PVC FITTING COVERS. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- 3) FLEXIBLE CLOSED CELL ELASTOMERIC THERMAL INSULATION, UNSUL OR PRESUL WITH PRESSURE SENSITIVE ADHESIVE SYSTEM FOR CLOSURE AND VAPOR SEALING, EQUAL TO ARMSTRONGS AP ARMALEX OR ARMALEX 2000.
- 4) FOR NON GRULATING SYSTEMS, THE FIRST 8 FEET OF INLET AND OUTLET PIPING BETWEEN THE TANK AND THE HEAT TRAP (INCLUDING THE HEAT TRAP) MUST BE INSULATED.
- 5) FOR CIRCULATING SYSTEMS, ALL HOT WATER PIPING IN THE CIRCULATION LOOP MUST BE INSULATED AS SPECIFIED BELOW.
- a) INSULATION SCHEDULE:
- 1) DOMESTIC COLD WATER 1/2"
- 2) DOMESTIC HOT WATER 1" FOR PIPING UP TO 1-1/4", 1-1/2" FOR PIPING 1-1/2" AND LARGER
- 3) CONDENSATE DRAINS INSIDE BUILDING 1/2"
- 4) REFRIGERANT SUCTON 3/4" FOR PIPING UP TO 1-1/4", 1" FOR PIPING 1-1/2" AND LARGER
- C. EQUIPMENT INSULATION
- 1) FLEXIBLE FIBERGLASS GLASS FIBER INSULATION, ASTM C 593, TYPE 1, CLASS B-4, SEMI-RIGID BOARD, WITH FACTORY LAMINATED KRAFT ALUMINUM FOIL (ALL SERVICE JACKET), VAPOR BARRIER, OPEN/COVERING PIPE AND TANK INSULATION.
- D. DUCTWORK: ACOUSTICAL INSULATION.
- 1) DUCT LINING: 2 LB/CF, THICKNESS AS SCHEDULED, AIR STREAM SIDE COATED, INSTALL PER SMACNA STANDARDS.
- a) DUCT LINING SCHEDULE:
- (1) RECTANGULAR SUPPLY DUCT 1/2": THROUGHOUT THE FIRST 10 FEET OF DUCT.
- (2) RETURN AIR DUCT 1/2": THROUGHOUT THE FIRST 10 FEET OF DUCT.
- (3) SOUND BOOT 1"
- (4) VANE-UP AIR DUCT 2"
- (5) OUTDOOR AIR 2"
- E. DUCTWORK: THERMAL INSULATION.
- 1) DUCT COVERING: 3/4 LB/CF, FIBERGLASS BLANKET WITH FACTORY APPLIED VAPOR BARRIER AND FACING, THICKNESS AS SCHEDULED, INSTALLATION IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
- a) DUCT COVERING SCHEDULE, MINIMUM R-6
- (1) ROUND SUPPLY DUCT 2"
- (2) RECTANGULAR SUPPLY DUCT 2"
- (3) RETURN AIR DUCT 2"
- (4) VANE-UP AIR DUCT 2"
- (5) OUTDOOR AIR 2"
- 2) DUCT LINING: 2 LB/CF, THICKNESS AS SCHEDULED, AIR STREAM SIDE COATED, INSTALL PER SMACNA STANDARDS.
- a) DUCT LINING SCHEDULE:
- (1) RECTANGULAR SUPPLY DUCT 1/2"
- (2) ROUND SUPPLY DUCT 1/2"
- (3) RETURN AIR DUCT 1"
- 3) EXPOSED SPIRAL DUCT.
- a) DOUBLE WALL SPIRAL - DOUBLE WALL INSULATED SPIRAL DUCT AND FITTINGS WITH PERFORATED 1/4" INCH WITH A K VALUE OF 0.21.
- b) SPIRAL DUCT LINING: JOHNS MANVILLE SPIRACUSTIC PLUS ROUND DUCT LINER SYSTEM, VSD, 50, AND LD SIZES, 5/8" AND UP, MEETS ASTM E 84 25-50 FLAME AND SMOKE, ASHRAE 62, MEAT257-50-M, SMACNA TAPING STANDARDS, MINIMUM THICKNESS DOUBLE WALL DUCT LINER STANDARD, 1" THICKNESS, AIR STREAM SIDE COATED, INSTALL PER SMACNA STANDARDS.
- 4) DUCT COVERING (EXTERIOR SUPPLY AND RETURN)
- a) EXTERIOR INSULATION: JOHN MANVILLE XSPCT ISOFOAM AFF BOARD, 1-1/2" THICK R-4.3, UNIFORM CLOSED-CELL POLYISOCYANURATE WITH A FOIL PAPER WITH FACTORY APPLIED VAPOR BARRIER, MANUFACTURER'S REQUIREMENTS, COVER ISOFOAM BOARD INSULATION WITH POLYGUARD ALUMASIAUR, COMPOSITE MEMBRANE MULTIPLY EMBOSSED UV-RESISTANT ALUMINUM FOIL-POLYMER LAMINATE, ALL WEATHER FLEXIBLE WEATHER-PROOFING JACKET, MINIMUM R-6 RATINGS, MINIMUM R-12 CLIMATE ZONES 5-8.
11. DUCTWORK:
- A. ALL DUCTWORK, UNLESS OTHERWISE INDICATED, SHALL BE FABRICATED FROM GALVANIZED SHEET STEEL, COMPLYING WITH ASTM A 521, LOCKFORMING QUALITY, WITH 60 ZINC COATING IN ACCORDANCE WITH ASTM A 525, AND MILL PHOSPHATIZED FOR EXPOSED LOCATIONS.
- B. WHERE DUCTWORK IS INDICATED TO BE EXPOSED TO VIEW IN OCCUPIED SPACES, PROVIDE MATERIALS WHICH ARE FREE OF DISCOLORATIONS INCLUDING FITTINGS, SEAM WELDS, AND JOINTS. MATERIALS IN STAINS AND DISCOLORATIONS, AND OTHER IMPERFECTIONS, INCLUDING THOSE WHICH WOULD IMPAIR PAINTING.
- C. DUCTWORK: METAL GAUGES, REINFORCEMENTS, ETC. SHALL BE CONSTRUCTED IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS", LATEST EDITION FOR 2 INCH WATER GAUGE STATIC PRESSURE.
- 1) RECTANGULAR DUCT:
- a) ELBOWS, UNLESS INDICATED OTHERWISE SHALL BE CONSTRUCTED WITH CENTERLINE RADIUS OF NOT LESS THAN 15 DUCT WIDTH OR SQUARE ELBOW WITH DOUBLE WALL STREAM-LINE VANES.
- b) RETURN AIR ACOUSTICAL ELBOWS AND SOUND BOOTS SHALL BE A SQUARE ELBOW WITH NO TURNING VANES.
- c) SLOPES FOR TRANSITIONS OR OTHER CHANGES IN DIMENSIONS SHALL BE MINIMUM 1 TO 3.
- 2) ROUND AND OVAL SPIRAL SEAM DUCT:
- a) PROVIDE RADIAL TYPE FITTINGS, FABRICATED OF MULTIPLE SECTIONS WITH MAXIMUM 15 DEGREE CHANGE OF DIRECTION PER SECTION, UNLESS SPECIFICALLY DETAILED OTHERWISE, USE 45 DEGREE LATERALS FOR BRANCH TAKEOFF CONNECTIONS. WHERE 40 DEGREE BRANCHES ARE INDICATED PROVIDE 45 DEGREE BRANCHES.
- b) SLOPES FOR TRANSITIONS OR OTHER CHANGES IN DIMENSIONS SHALL BE MINIMUM 1 TO 3.
- c) AS AN OPTION, PROVIDE FACTORY-FABRICATED DUCT AND FITTINGS, IN LIEU OF SHOP-FABRICATED DUCT AND FITTINGS.
- (1) ELBOWS: ONE PIECE CONSTRUCTION FOR 40 DEGREES AND 45 DEGREE ELBOW 14" AND SMALLER. PROVIDE MULTIPLE GORE CONSTRUCTION FOR LARGER DIAMETER WITH STANDING SEAM CIRCUMFERENTIAL JOINT.
- (2) DIVIDED FLOW FITTINGS: 40 DEGREE TEES, CONSTRUCTED WITH SADDLE TAP SPOT WELDED AND BONDED TO DUCT FITTING BODY.
- d) ROUND LONGITUDINAL SEAM DUCT: USE FOR RIGID METAL DUCT ON LEAVING SIDE OF DUCT IN CONCEALED LOCATIONS FOR EXTENSION TO FLEX FOR DIFFUSERS, UNLESS OTHERWISE INDICATED.
- D. DUCT SIZES SHOWN ON THE DRAWINGS ARE SHEETMETAL SIZES, ALLOWANCE FOR DUCT LINER HAS BEEN MADE WHERE APPLICABLE.
- E. INSTALLATION OF METAL DUCTWORK:
- 1) GENERAL: ASSEMBLE AND INSTALL DUCTWORK IN ACCORDANCE WITH RECOGNIZED INDUSTRY PRACTICES WHICH WILL ACHIEVE AIR-TIGHT SYSTEMS (MAXIMUM 5% LEAKAGE), WITH NO COLLECTIONABLE NOISE, AND CAPABLE OF PERFORMING INDICATED SERVICE. INSTALL EACH RUN WITH MINIMUM NUMBER OF JOINTS. ALIGN DUCTWORK ACCURATELY WITH THE INTERNAL SURFACES SMOOTH. SUPPORT DUCTS RIGIDLY WITH SUITABLE STRAPS, BRACES, HANGERS AND ANCHORS IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS" LATEST EDITION. DUCT HANGERS SHALL BE OF THE TYPE WHICH HOLD DUCTS TRUE TO SHAPE AND TO PREVENT BUCKLING. SUPPORT VERTICAL DUCTS AT EVERY FLOOR.
- 2) AUXILIARY STEEL: PROVIDE AUXILIARY STEEL AS REQUIRED TO ADEQUATELY SUPPORT DUCTWORK.
- 3) ROUTING: LOCATE DUCTWORK RUNS, EXCEPT AS OTHERWISE INDICATED, VERTICALLY AND HORIZONTALLY AND AVOID DIAGONAL RUNS WHEREVER POSSIBLE. LOCATE RUNS AS INDICATED BY DIMENSIONS, DETAILS, AND NOTATIONS OR, IF NOT NOTED OTHERWISE, INDICATED BY THE SHORTEST ROUTE WHICH DOES NOT OBSTRUCT USABLE SPACE OR BLOCK ACCESS FOR SERVICING BUILDING AND ITS EQUIPMENT. PROVIDE OVERHEAD CONSTRUCTION OF OVERHEAD CONSTRUCTION COLUMNS, AND OTHER STRUCTURAL AND PERMANENT ENCLOSURE ELEMENTS OF BUILDINGS, WHEREVER POSSIBLE IN FINISHED AND OCCUPIED SPACES, CONCEAL DUCTWORK FROM VIEW BY LOCATING IN MECHANICAL SHUTTER, CONCEAL DUCTWORK OR ABOVE SUSPENDED CEILING, OR LOCATING IN CONCEALED HORIZONTAL RUNS IN SOLID PARTITIONS, EXCEPT AS SPECIFICALLY SHOWN. COORDINATE LAYOUT WITH SUSPENDED CEILING AND LIGHTING LAYOUTS AND SIMILAR FINISHED WORK.

## MECHANICAL SPECIFICATIONS (CONTINUED)

- 4) DO NOT ROUTE DUCTWORK THROUGH ELECTRICAL EQUIPMENT SPACES AND ENCLOSURES, UNLESS INDICATED OTHERWISE.
- 5) PENETRATIONS:
- a) WHERE DUCTS PASS THROUGH FIRE-RATED FLOORS, WALLS, OR PARTITIONS, PROVIDE FIRESTOPPING BETWEEN DUCT AND PENETRATED AREA. PROVIDE ACCESS DOORS AS REQUIRED.
- 6) COORDINATION: COORDINATE DUCT INSTALLATIONS WITH INSTALLATION OF ACCESSORIES, DAMPERS, COIL FRAMES, EQUIPMENT, CONTROLS, AND OTHER ASSOCIATED WORK OF THE DUCTWORK SYSTEM.
- 7) INSTALLATION: INSTALL METAL DUCTWORK IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS", LATEST EDITION.
- F. EQUIPMENT CONNECTIONS:
- 1) CONNECT METAL DUCTWORK TO EQUIPMENT AS INDICATED. PROVIDE FLEXIBLE CONNECTION FOR EACH DUCTWORK CONNECTION TO EQUIPMENT MOUNTED ON VIBRATION ISOLATORS AND/OR EQUIPMENT CONTAINING ROTARY MOTION. PROVIDE ACCESS DOORS AS REQUIRED.
- 2) CONDITIONED SPACES (PLENUM) CLASS C CLASS B CLASS B CLASS B RETURN SUPPLY 1/2" P.C. CLASS B CLASS B CLASS B CLASS B RETURN SUPPLY 1/2" P.C. EXHAUST
12. FLEXIBLE DUCT:
- A. ATCO 1056 (R-6), OR EQUAL.
- B. FACTORY APPLIED INSULATION AND VAPOR BARRIER, 1-1/2" THICK.
- C. MAXIMUM LENGTH OF 5'-0".
13. FLUES AND ACCESSORIES:
- A. FLUE FOR GAS FIRED CONDENSING WATER HEATER OR FURNACE SHALL BE AS RECOMMENDED BY THE GAS APPLIANCE MANUFACTURER. FLUES SHALL BE SCHEDULE 40, PVC OR CPVC PIPE PER THE MANUFACTURER'S INSTALLATION REQUIREMENTS.
- B. PROVIDE MANUFACTURER'S STANDARD ACCESSORY ITEMS INCLUDING BIRD PROOF TOP, STORM COLLAR, ROOF THIMBLE, ETC. AS REQUIRED FOR A COMPLETE INSTALLATION. ROOF THIMBLES THROUGH THE BUILDING ROOF SHALL BE SUITABLE FOR USE WITH THE ROOF PROVIDED.
14. EXHAUST FANS:
- A. CENTRIFUGAL CEILING EXHAUSTERS SHALL BE ELECTRICALLY POWERED CENTRIFUGAL TYPE FAN SUITABLE FOR MOUNTING IN THE CEILING WITH A PERFORATED OFF-WHITE METAL GRILLE WITH A THUMBSCREW ATTACHMENT FOR EASY ACCESS TO FAN HOUSING. UNIT SHALL CONSIST OF A GALVANIZED STEEL HOUSING LINED WITH ACOUSTICAL INSULATION AND SHALL INCLUDE AN INTEGRAL BACKDRIFT DAMPER ON FAN DISCHARGE. MOTOR SHALL BE A PERMANENT SPLIT-CAPACITOR TYPE MOTOR, PERMANENTLY LUBRICATED, WITH THERMAL OVERLOAD PROTECTION. PROVIDE DISCONNECT SWITCH OR OTHER MEANS OF DISCONNECT AT MOTOR IN FAN HOUSING.
15. ROOFTOP UNITS:
- A. UNIT SHALL BE FACTORY-ASSEMBLED AND TESTED, DESIGNED FOR ROOF INSTALLATION, AND SHALL CONSIST OF SCROLL TYPE COMPRESSORS, CONDENSERS, EVAPORATOR COILS, THERMAL EXPANSION VALVE, CONDENSATE DRAIN PAN, CONDENSER AND EVAPORATOR FANS, CONDENSER PANS TO BE SECURING, REFRIGERATION CONTROLS, GAS FIRED HEAT EXCHANGER OR ELECTRIC HEATING SECTION, FILTERS, AND DAMPERS. CAPACITIES AND ELECTRICAL CHARACTERISTICS SHALL BE AS SCHEDULED ON THE DRAWINGS.
- B. COMPRESSORS: UNIT SHALL INCLUDE VIBRATION ISOLATORS AND CRANKCASE HEATER. REFRIGERANT CIRCUIT SHALL INCLUDE A FILTER DRYER, SIGHT GLASS, COMPRESSOR SERVICE VALVES, AND LIQUID LINE SERVICE VALVES.
- C. SAFETY CONTROLS SHALL INCLUDE:
- a) LOW PRESSURE CUTOFF, MANUAL RESET.
- b) HIGH PRESSURE CUTOFF, MANUAL RESET.
- c) COMPRESSOR MOTOR OVERLOAD PROTECTION, MANUAL RESET.
- d) ANTI-RECYCLING THING DEVICE.
- e) ADJUSTABLE THERMAL LOCKOUT.
- f) OIL PRESSURE SWITCH.
- D. REFRIGERANT COIL: ALUMINUM PINS BONDED TO SEAMLESS COPPER TUBE BY MEANS OF MECHANICAL EXPANSION, AN EQUALIZING THERMAL DISTRIBUTOR SHALL ENSURE EACH COIL CIRCULATES THE SAME AMOUNT OF REFRIGERANT.
- E. ECONOMIZER SHALL CONSIST OF RETURN AIR DAMPER, OUTDO



12/22/2022



a new development for  
**Town Centre Lot 1**  
520 NE Town Centre Drive  
Lee's Summit, Missouri 64064

date 05.19.22  
drawn by MA/FS  
checked by EK/DS  
revisions  
12.20.22 REV 1

sheet number

**P1.0**

drawing type  
permit

project number  
20231

**PLUMBING GENERAL NOTES:**


1. INSTALL ALL PIPE, ETC. AS HIGH AS POSSIBLE.
2. COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
3. REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATIONS AND MOUNTING HEIGHTS OF FIXTURES.
4. REFER TO ARCHITECTURAL & STRUCTURAL DRAWINGS FOR REQUIREMENTS FOR SUPPORTING PIPING, EQUIPMENT, ETC. FROM THE STRUCTURE. PROVIDE ADDITIONAL STEEL AS REQUIRED TO PROPERLY SUPPORT SYSTEMS FROM THE STRUCTURE.
5. PROVIDE 1" SCHEDULE 40 PVC CONDENSATE DRAIN PIPE FOR ROOFTOP UNIT LAID ROUTED TO GRASSY AREA. PROVIDE WATER TRAP AND CLEAN OUTS AS DETAILED. SECURE PVC PIPE TO DRAIN WITH NYLON STRAP.
6. NO PIPING SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
7. CONTRACTOR TO TEST WATER PRESSURE ON SITE AND PROVIDE PRESSURE REDUCING VALVE ON WATER SERVICE IF PRESSURE IS OVER 80 PSI.
8. ALL WATER SERVICE INSTALLATIONS INCLUDING BACKFLOW DEVICES ARE SUBJECT TO FIELD VERIFICATION AND APPROVAL BY THE WATER DEPARTMENT INSPECTOR.

**PLUMBING SYMBOLS**

	SOIL AND WASTE PIPING BELOW FLOOR/GRADE
	SOIL AND WASTE PIPING ABOVE FLOOR/GRADE
	SANITARY VENT PIPING ABOVE GRADE
	SANITARY VENT PIPING BELOW GRADE
	DOMESTIC COLD WATER PIPING
	DOMESTIC HOT WATER PIPING
	GAS PIPING
	EQUIPMENT DRAIN LINE
	FIRE LINE
	PIPING TURNING DOWN
	PIPING TURNING UP
	TEE TOP CONNECTION
	UNION
	BACKFLOW PREVENTER
	FLOOR DRAIN
	FLOOR CLEAN OUT
	WALL CLEAN OUT
	GRADE CLEAN OUT
	VALVE
	BALANCING VALVE
	SOLENOID VALVE
	PRESSURE REGULATOR
	CHECK VALVE
	CONNECT TO EXISTING
	I.E. INVERT ELEVATION OF PIPE
	MATCH MARKS ON PLUMBING RISER DIAGRAM

**PLUMBING PLAN NOTES:**

1. INSTALL WALL HYDRANT 18" ABOVE GRADE / FINISHED FLOOR.
2. CONNECT GAS TO EQUIPMENT AS REQUIRED AND AS DETAILED.
3. ALL APPLIANCE CONNECTIONS SHALL BE MADE WITH UL LISTED FLEXIBLE APPLIANCE CONNECTOR. FLEX CONNECTORS SHALL BE PROVIDED BY TENANT. CONTRACTOR SHALL PROVIDE SAFETY LOCK AND CHAIN AT ALL GAS APPLIANCES ON WHEELS. PROVIDE PIPING REDUCERS AND INCREASERS AS REQUIRED TO MATE HARD PIPING WITH FLEX CONNECTORS.
4. COORDINATE WITH GAS COMPANY FOR INSTALLATION OF A METER WITH CAPACITY FOR 694 CFH @ 7" W.C. ROUTE PIPING UP INSIDE THE EXTERIOR WALL AND UP TO 18'-0" ABOVE FINISHED FLOOR. ALL CONCEALED JOINTS ARE TO BE WELDED OR USE FITTINGS APPROVED FOR CONCEALED USE. VERIFY ALL EQUIPMENT GAS CAPACITIES AND OPERATING PRESSURES PRIOR TO INSTALLATION OF ANY PIPING.
5. ROUTE PIPING ON INTERIOR SIDE OF INSULATION FOR FREEZE PROTECTION.
6. ROUTE GAS PIPE DOWN TO 18" AFF AND PENETRATE EXTERIOR WALL. ROUTE GAS PIPE ABOVE GRADE AND OVER TO RTU AS REQUIRED.
7. COORDINATE WITH G.C. TO SEAL PENETRATION WEATHER TIGHT.
8. SEE ENLARGED PLUMBING PLAN ON SHEET P1.1 FOR CONTINUATION OF PIPING AND PIPING IN THIS AREA.
9. SEE CIVIL PLAN FOR CONTINUATION OF 4" SANITARY SEWER. MAINTAIN MIN 30" COVER.
10. CONNECT CONDENSATE TO RTU AS REQUIRED AND AS DETAILED.



**OVERALL PLUMBING FLOOR PLAN**  
SCALE: 1/8" = 1'-0"  
F.F.E. = 1008.50'

BC PROJECT #: 22323  
MISSOURI PE COA #2009003629  
This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Present to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of details and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.

**BC ENGINEERS INCORPORATED**

5720 Reeder Shawnee, Ks. 66203 (913)262-1772

12/22/2022



a new development for  
**Town Centre Lot 1**  
520 NE Town Centre Drive  
Lee's Summit, Missouri 64064

date 05.19.22  
drawn by MA/FS  
checked by EK/DS  
revisions 12.20.22 REV 1

sheet number


**P1.1**

drawing type  
permit

project number  
20231

**PLUMBING PLAN NOTES:**

- 1 REFER TO SHEET P1.0 FOR CONTINUATION OF PIPING.
- 2 4" WASTE PIPE DOWN TO FLOOR BELOW. REFER TO ENLARGED FIRST FLOOR PLUMBING PLAN FOR CONTINUATION OF PIPING. PROVIDE CLEANOUT AT BASE OF RISER.
- 3 REFER TO ENLARGED FIRST FLOOR PLUMBING PLAN FOR CONTINUATION OF PIPING.
- 4 1/2" CW UP FROM FLOOR BELOW. REFER TO ENLARGED FIRST FLOOR PLUMBING PLAN FOR CONTINUATION OF PIPING.
- 5 1/2" HW UP FROM FLOOR BELOW. REFER TO ENLARGED FIRST FLOOR PLUMBING PLAN FOR CONTINUATION OF PIPING.
- 6 NOT USED.
- 7 LOCATION OF 3" VTR. VERIFY 10' CLEARANCE FROM ALL OUTDOOR AIR INTAKES. SEAL PENETRATION WEATHERTIGHT.
- 8 4" WASTE PIPE DOWN FROM FLOOR ABOVE. REFER TO ENLARGED 2ND FLOOR PLUMBING PLAN FOR CONTINUATION OF PIPING. PROVIDE CLEANOUT AT BASE OF RISER.
- 9 NOT USED.
- 10 NOT USED.
- 11 NOT USED.
- 12 NOT USED.
- 13 SEE CIVIL PLAN FOR CONTINUATION OF 1-1/2" DOMESTIC C.W. MAINTAIN MIN 48" COVER.
- 14 ROUTE PIPING ON INTERIOR SIDE OF INSULATION FOR FREEZE PROTECTION.
- 15 PROVIDE 1-1/2" RPZ BACKFLOW PREVENTER AND INSTALL 24" A.F.F. 4 6" FROM WALL. ROUTE DRAIN FROM RPZ BFP TO FLOOR DRAIN WITH AN AIR GAP.
- 16 PROVIDE ICE MAKER BOX WITH VALVE FOR CONNECTION TO REFRIGERATOR BY OTHERS.
- 17 6" FIRE LINE, SEE CIVIL PLANS FOR CONTINUATION. MAINTAIN A MINIMUM 48" BURY FOR FREEZE PROTECTION.
- 18 ROUTE 6" FIRE LINE THRU FOUNDATION UP THRU FLOOR 24" AFF AND CAP FOR FUTURE EXTENSION BY SPRINKLER CONTRACTOR.



**ENLARGED PLUMBING 1ST FLOOR PLAN**  
SCALE: 1/4" = 1'-0"

BC PROJECT #: 22323  
MISSOURI PE COA #2009003629  
This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Payment to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of details and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.

**BC ENGINEERS  
INCORPORATED**

5720 Reeder Shawnee, Ks. 66203 (913)262-1772



12/22/2022



a new development for  
**Town Centre Lot 1**  
520 NE Town Centre Drive  
Lee's Summit, Missouri 64064

date  
05.19.22  
drawn by  
MA/FS  
checked by  
EK/DS  
revisions  
12.20.22 REV 1

sheet number

**P2.0**

drawing type  
permit

project number  
20231

PLUMBING FIXTURE BRANCH PIPING SCHEDULE				
FIXTURE	WASTE	VENT	GA	HA
WATER CLOSET (TANK TYPE)	4"	2"	1/2"	--
URINAL	2"	1-1/2"	3/4"	--
LAVATORY	1-1/4"	1-1/4"	1/2"	1/2"
SINK	1-1/2"	1-1/2"	1/2"	1/2"
FLOOR DRAIN	2"	2"	--	--
MOP BASIN	2"	2"	1/2"	1/2"
ELECTRIC WATER COOLER (BI-LEVEL)	1-1/2"	1-1/2"	1/2"	--

NOTE: INDIVIDUAL VENTS FOR FIXTURES ON PLANS AND RISER DIAGRAM HAVE BEEN INCREASED WHERE HORIZONTAL VENT LENGTH IS IN EXCESS OF THE MAXIMUM DISTANCE INDICATED BY THE CODE.

PIPE HANGER SCHEDULE		
PIPE MATERIAL	MAXIMUM HANGER SPACING	HANGER ROD DIAMETER
ABS (All sizes)	4'	3/8"
PVC (All Sizes)	4'	3/8"
CPVC, 1 inch and smaller	3'	1/2"
CPVC, 1-1/4 inches and larger	4'	1/2"
Cast Iron (All Sizes)	5'	5/8"
Cast Iron (All Sizes) with 10 foot length of pipe	10'	5/8"
Copper Tube, 1-1/4 inches and smaller	6'	1/2"
Copper Tube, 1-1/2 inches and larger	10'	1/2"
Steel, 3 inches and smaller	12'	1/2"
Steel, 4 inches and larger	12'	5/8"
Pex, 1" and below without support channel	32"	3/8"
Pex, 1-1/4" and above without support channel	48"	3/8"
Pex 3/4" and below with support channel	6'	3/8"
Pex 1" and above with support channel	8'	3/8"

PLUMBING FIXTURE SCHEDULE:

**HWC** HANDICAP WATER CLOSET: TOTO, #CST144EL(R)/N, "DRAKE CLOSE COUPLED TOILET", 1.28 GALLON FLUSH, 16-1/2" HIGH ELONGATED BOWL, FLOOR MOUNTED, FLOOR OUTLET, TANK TYPE, VITREOUS CHINA, SIPHON-JET ACTION, #SC934 OPEN FRONT SEAT WITH CHECK HINGE AND LESS COVER, CHROME PLATED ANGLE STOP AND RISER, HANDLE ON WIDE SIDE OF FIXTURE.

**WC** WATER CLOSET: TOTO, #CST144E(R)/G/N, "DRAKE CLOSE COUPLED TOILET", 1.28 GALLON FLUSH, ELONGATED BOWL, FLOOR MOUNTED, FLOOR OUTLET, TANK TYPE, VITREOUS CHINA, SIPHON-JET ACTION, #SC934 OPEN FRONT SEAT WITH CHECK HINGE AND LESS COVER, CHROME PLATED ANGLE STOP AND RISER.

**L1** NOT USED.

**L2** HANDICAP LAVATORY, COUNTERTOP: TOTO, #LT501, VITREOUS CHINA, 20" X 11" OVAL BASIN, DELTA #501 FAUCET WITH SINGLE METAL LEVER HANDLE, OFFSET GRID DRAIN WITH 1-1/4" TAILPIECE, CHROME PLATED P-TRAP(MOUNTED PARALLEL WITH WALL), CHROME PLATED ANGLE STOPS AND RISERS, INSULATE EXPOSED DRAIN, WATER SUPPLIES, AND VALVES WITH PROWRAP SEAMLESS MOLDED CLOSED CELL VINYL INSULATION.

**UI** URINAL, WALL HUNG: TOTO, #UT44T.O1, VITREOUS CHINA, WASH OUT, WALL HUNG URINAL WITH 3/4" TOP SPID, #TMU11NC-12 FLUSH VALVE, FLOOR MOUNTED FIXTURE SUPPORT, SET RIM HEIGHT PER ARCHITECTURAL DRAWINGS.

**S1** NOT USED.

**MB** MOP BASIN: FIAT, #MSB-2424, MOLDED STONE MOP BASIN, 2" DRAIN, 24" X 24" BASIN, VINYL BUMPER GUARD, STERN WILLIAMS #T-10-VB FAUCET, SPRING CHECKS, VACUUM BREAKER, INTEGRAL STOPS, WALL BRACE & PAIL HOOK, WALL BRACKET WITH 30" HOSE.

**ENC** ELECTRIC WATER COOLER: OASIS, #P68ACSL, BARRIER FREE TWO-STATION WATER COOLER, 8.0 GPH, 50 DEGREES F WATER WITH 90 DEGREES F AIR TEMPERATURE, 120 VOLT, COLOR TO BE SELECTED BY ARCHITECT AFTER AWARD OF CONTRACT, FRONT AND SIDE ANTIMICROBIAL PUSH PADS, ANTIMICROBIAL FLEX BUBBLERS, CHROME PLATED CAST BRASS P-TRAP WITH CLEANOUT, CHROME PLATED LOOSE KEY ANGLE STOP, FLOOR MOUNTED CARRIER AND GANE APRON.

**FD** FLOOR DRAIN: SIOUX CHIEF, #842, PVC FLOOR DRAIN WITH ADJUSTABLE TOP AND CAST BRASS STRAINER.

**WH** HOT WATER HEATER: AO SMITH #DEL-40, 40 GALLON STORAGE, 208 VOLT, SINGLE PHASE, (2) 4500 WATT ELEMENT, NON-SIMULTANEOUS, ASME TEMPERATURE AND PRESSURE RELIEF VALVE. SET TEMPERATURE TO 120°F.

**ET** HOT WATER EXPANSION TANK: AMTROL, #ST-8, 3.2 GALLON EXPANSION TANK WITH DIAPHRAGM.

**MV** NOT USED.


**MV1** MIXING VALVE: MATTS, #LFMMV THERMOSTATIC CONTROLLED MIXING VALVE, LEAD FREE BRONZE BODY, LOCKED TEMPERATURE ADJUSTMENT CAP (VANDAL RESISTANT), SOLID MAX HYDRAULIC PRINCIPLE THERMOSTAT, INTEGRAL FILTER WASHERS AND CHECK VALVES ON HOT AND COLD INLETS, SET TO 110°F ASSE #101T, #1064, #1070

**RPZ** REDUCED ZONE PRESSURE BACKFLOW PREVENTOR: MATTS #LF004, LEAD FREE BRONZE BODY CONSTRUCTION, TWO, IN-LINE INDEPENDENT CHECK VALVES, REPLACEABLE CHECK SEATS WITH AN INTERMEDIATE RELIEF VALVE, AND BALL VALVE TEST COCKS.


**IB** NOT USED.

**FCO/NGO** VINYL TILE FLOOR: JR SMITH #4140, OR EQUAL.  
QUARRY TILE FLOOR: JR SMITH #4200, OR EQUAL.  
CARPETED FLOOR: JR SMITH #4020-Y, OR EQUAL.  
UNFINISHED FLOOR: JR SMITH #4020, OR EQUAL.  
WALL: JR SMITH #44T2, OR EQUAL, 24" ABOVE THE FLOOR.



**FPWH** FREEZEPROOF WALL HYDRANT: JR SMITH #5609, 3/4" SIZE, NICKEL-BRONZE FACE, KEY OPERATED, INTEGRAL VACUUM BREAKER.



**GAS CONNECTION DETAIL**  
SCALE: NONE



**CONDENSATE DRAIN DETAIL**  
SCALE: NONE



**PLUMBING RISER DIAGRAMS**  
SCALE: NONE

BC PROJECT #: 22323  
MISSOURI PE COA #2009003629  
This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Payment to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of details and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.

**BC ENGINEERS INCORPORATED**

5720 Reeder Shawnee, Ks. 66203 (913)262-1772



12/22/2022



**MECHANICAL GENERAL NOTES:**


- COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
- THIS CONTRACTOR SHALL PERFORM ALL WORK INDICATED AND/OR AS REQUIRED FOR THE PROPER INSTALLATION AND OPERATION OF THE MECHANICAL SYSTEMS.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATIONS OF DIFFUSERS.
- INSTALL ALL DUCT, PIPE, ETC. AS HIGH AS POSSIBLE.
- DUCT SIZES SHOWN ARE ACTUAL SHEET METAL SIZES AND INCLUDE AN ALLOWANCE FOR DUCT LINER WHERE APPLICABLE.
- PROVIDE FLEXIBLE CONNECTION BETWEEN DUCTWORK AND ROOFTOP UNITS, EXHAUST FANS, AND OTHER MOTORIZED EQUIPMENT.
- NO DUCT SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
- ALL MATERIALS WITHIN FLENUMS SHALL BE NONCOMBUSTIBLE OR SHALL HAVE A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE-DEVELOPED INDEX OF NOT MORE THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM E 84.
- ALL MECHANICAL SYSTEMS SHALL BE BALANCED BY A CERTIFIED BALANCING CONTRACTOR. REFER TO SPECIFICATIONS FOR DETAILS.

**MECHANICAL SYMBOLS**

	NEW SUPPLY DIFFUSER
	NEW RETURN AIR GRILLE
	EXHAUST GRILLE/FAN
	REMOTE TEMPERATURE SENSOR
	THERMOSTAT, MOUNTED AT 48" AFF
	DUCT-MOUNTED SMOKE DETECTOR
	NEW DUCTWORK
	SIZE OF RECTANGULAR DUCT
	SIZE OF ROUND DUCT
	FLEXIBLE DUCTWORK
	FLEXIBLE CONNECTION TO FAN
	FLOOR PLAN NOTE DESIGNATION
	S.A. SUPPLY AIR
	R.A. RETURN AIR
	EXH. EXHAUST AIR
	TRANSITION IN DUCT SIZE
	ELBOW WITH TURNING VANES
	MANUAL VOLUME DAMPER
	MANUAL VOLUME DAMPER
	SUPPLY AIR DUCT UP/DOWN
	RETURN AIR DUCT UP/DOWN
	EXHAUST AIR DUCT UP/DOWN
	CHANGE IN ELEVATION UP (UP) DOWN (DN) IN DIRECTION OF FLOW
	RTU-1 SCHEDULED MECHANICAL EQUIPMENT

**MECHANICAL PLAN NOTES:**

- PROVIDE GROUND MOUNTED RTU WHERE SHOWN ON PLAN. INSTALLATION OF EQUIPMENT SHALL COMPLY WITH EQUIPMENT MANUFACTURER'S INSTALLATION AND CLEARANCE REQUIREMENTS TO ALLOW FOR INSPECTION, SERVICE, REPAIR OR REPLACEMENT. FRESH AIR INTAKE OF DOAS UNIT SHALL BE LOCATED A MINIMUM OF 10 FOOT FROM VENT THRU ROOF, FLUES AND EXHAUST FANS.
- COORDINATE PENETRATION FOR HVAC EQUIPMENT WITH METAL BUILDING MANUFACTURER. COORDINATE FINAL ELEVATION OF EQUIPMENT WITH WALL GIRTS AND WALL SUPPORTS. SEE ARCH ELEVATION FOR DETAILS. COORDINATE WITH SC TO SEAL WALL PENETRATION WEATHER TIGHT.
- ALL EXTERIOR DUCT SHALL BE PROVIDED WITH R-8 INSULATION. SEAL EXTERIOR DUCT PENETRATION WEATHER TIGHT.
- PROVIDE WALL VENT GAP WITH BACKDRAFT DAMPER FOR EXHAUST FAN. SEAL PENETRATIONS WEATHER TIGHT.
- SUPPORT EXHAUST FAN FROM STRUCTURE AS REQUIRED BY THE MANUFACTURER.
- ROUTE DUCTWORK UP TO AS HIGH AS POSSIBLE.
- PROVIDE T-DAY PROGRAMMABLE AUTO/HEAT/COOL THERMOSTAT AT 48" AFF.
- TURN UP RETURN DUCT TO 4" OF CEILING. INSTALL BIRDSCREEN OVER R.A. OPENING AS REQUIRED.
- INSTALL BOTTOM OF DUCT AT 12'-6" AFF.
- INSTALL EXPOSED SPIRAL DUCTWORK IN OPEN CEILING AREA. DUCT SIZES SHOWN ARE OUTER DIAMETER OF DUCTWORK AND INCLUDES AN ALLOWANCE FOR DUCT LINER WHERE APPLICABLE. COORDINATE INSTALLATION OF DUCTWORK WITH LIGHTING LAYOUT.
- PROVIDE CONCEALED SUPPLY DUCTWORK ABOVE CEILING. ROUTE DUCTWORK UP HIGH AND SUPPORT FROM THE STRUCTURE. ALL DUCTWORK SHALL BE INSTALLED IN ACCORDANCE WITH SHACMA STANDARDS. COORDINATE ROUTING OF DUCTWORK WITH LIGHT HOUSINGS, ELECTRICAL CONDUIT, PIPING ETC. TO AVOID CONFLICT. DUCTWORK INSULATION SHALL BE AT LEAST 3" FROM LIGHT HOUSINGS. PROVIDE TRANSITION AS REQUIRED TO INSTALL DUCTWORK BETWEEN JOISTS.
- LOCATION OF DUCT MOUNTED SMOKE DETECTOR. PROVIDE REMOTE ENUNCIATOR AUDIO/VISUAL. VERIFY LOCATION WITH FIRE MARSHALL PRIOR TO INSTALLATION. REFER TO SPECIFICATION SHEET MPO.0 FOR ADDITIONAL INFORMATION.
- PROVIDE TRANSFER GRILLE ON BOTH SIDES AT 8'-0" AFF.
- UNDERCUT DOOR TO ALLOW FOR TRANSFER AIR PATH.



**MECHANICAL FLOOR PLAN**  
SCALE: 1/8" = 1'-0"

BC PROJECT #: 22323  
MISSOURI PE COA #2009003629  
This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Payment to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of details and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Designer/Engineer is strictly prohibited. © 2022 BC Engineers, Inc.

**BC ENGINEERS INCORPORATED**

5720 Reeder Shawnee, Ks. 66203 (913)262-1772

a new development for

**Town Centre Lot 1**

520 NE Town Centre Drive

Lee's Summit, Missouri 64064

date 05.19.22  
drawn by MA/FS  
checked by EK/DS  
revisions  
12.20.22 REV 1

sheet number


**M1.0**

drawing type permit

project number 20231



12/22/2022



*[Handwritten Signature]*

a new development for

Town Centre Lot 1

520 NE Town Centre Drive  
Lee's Summit, Missouri 64064

date  
05.19.22

drawn by  
MA/FS

checked by  
EK/DS

revisions  
12.20.22    REV 1



BC PROJECT #: 22323  
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.



5720 Reeder Shawnee, Ks. 66203 (913)262-1772

sheet number

M1.1

drawing type  
permit

project number  
20231

NOT USED



12/22/2022







EXHAUST FAN SCHEDULE										
MARK	MFG	MODEL	CFM	EXTERNAL STATIC P. IN. WG.	RPM	ELECTRICAL		FAN TYPE	CONTROLS	NOTES
						VOLT/Ø/HZ	PWR			
EF-1	COOK	GC-182	225	0.25	1,400	120/1/60	167 W	CEILING EXH.	SWITCH	1
EF-2	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓

NOTES: 1. PROVIDE CEILING GRILLE, INTEGRAL BACK DRAFT DAMPER, VARI-SPEED CONTROLLER (NEAR FAN AND ABOVE CEILING), AND WALL CAP.

ROOFTOP UNIT SCHEDULE																											
MARK	MFGR.	MODEL NO.	NOM. TONS	EVAP. CFM	EXT. STATIC P. IN. WG. (NOTE 2)	COOLING				HOT GAS REHEAT	HEATING (GAS)			ELECTRICAL				UNIT CONTROLS	BLOWER DRIVE TYPE	ECONOMIZER + BAROMETRIC RELIEF		MINIMUM OUTDOOR AIR (CFM) *	SEER /EER	TOTAL WEIGHT (LBS)	NOTES		
						COOLING STAGES	TOTAL BTUH	SENS. BTUH	AMB.		EVAP. EAT DB/MB	BTUH INPUT	BTUH OUTPUT	HEATING STAGES	VOLT/Ø/HZ	BLOWER MOTOR	POWER EXHAUST			MGA (AMPS)	MOCF (AMPS)					TYPE	CONTROLLER
RTU-1	CARRIER	48TCED16A2A5	15	6,000	0.5	2	184,780	137,040	105	80/67	N	240,000	195,000	2	208/3/60	6.1 HP	N	71	80	DIGITAL	CAV	STANDARD	SENSIBLE	450	- / 11.2	1760	1,2,3,4,5,6
RTU-2		48TCED12A2A5	10	4,000	0.5	2	124,100	96,200	105	80/67	N	224,000	184,000	2	208/3/60	4.7 HP	N	49	60	DIGITAL	CAV	STANDARD	SENSIBLE	450	- / 11	1149	1,2,3,4,5,6
RTU-3		48FCMO8A2A5	7.5	3,000	0.5	2	90,000	66,020	105	80/67	N	180,000	148,000	2	208/3/60	3 HP	N	39	50	DIGITAL	CAV	STANDARD	SENSIBLE	425	- / 11.2	914	1,2,3,4,5,6

- NOTES:
- PROVIDE HINGED ACCESS DOORS, SCROLL COMPRESSORS WITH CRANKCASE HEATER, HIGH PRESSURE SWITCHES, FREEZE/STAT, HAIL GUARDS. STANDARD COOLING DOWN TO 30°F. OUTDOOR AIR DAMPER TO FULLY CLOSE W/ FAN SHUTDOWN FOR ALL UNITS.
  - EXTERNAL STATIC PRESSURE LISTED REPRESENTS STATIC PRESSURE REQUIRED FOR DUCTWORK AND DIFFUSERS OUTSIDE THE HVAC UNIT COMPLETELY INDEPENDENT OF ANY PRESSURE DROP THROUGH THE HVAC EQUIPMENT INCLUDING BUT NOT LIMITED TO FILTERS, COILS AND ECONOMIZERS. THE FAN AND MOTOR SHALL BE SIZED APPROPRIATELY TO MEET THIS DEFINITION OF EXTERNAL STATIC PRESSURE.
  - PROVIDE COMMERCIAL, 7-DAY PROGRAMMABLE HEAT/COOL/AUTO CHANGEOVER TOUCHSCREEN THERMOSTAT WITH OPTIMUM START CONTROLS. OUTDOOR AIR DAMPER IS TO CLOSE DURING UNOCCUPIED HOURS.
  - PROVIDE NEW 2" MERV 8 FILTERS UPON COMPLETION OF CONSTRUCTION.
  - PROVIDE 14" PRE-FABRICATED GROUND MOUNTED CURB.
  - MECHANICAL CONTRACTOR SHALL COORDINATE ALL UNIT MOCF'S OF ACTUAL INSTALLED EQUIPMENT WITH ELECTRICAL CONTRACTOR.
  - OCCUPANCY FOR BATTING CAGES IS 30 PEOPLE. 30\*30 = 900 CFM MINIMUM REQUIRED FOR BATTING CAGE AREA.

DIFFUSER SCHEDULE									
MARK	MFG	MODEL	BORDER TYPE	NECK SIZE	FACE SIZE	FINISH	DAMPER	ACCESSORIES	NOTES
SD-1	TITUS	TMS	3	8"Ø	24"x24"	WHITE	-	-	-
SD-2		↓		↓	↓		OB DAMPER	TRM KIT	-
SD-3		↓		6"Ø	12"x12"		-	-	-
SD-4		↓		↓	↓		OB DAMPER	TRM KIT	-
RG-1		PAR		18"x18"	24"x24"		-	-	-
RG-2		↓		12"Ø	24"x24"		-	-	-
SR-1		300FS		12"x10"	-	↓	OB DAMPER	-	-
SR-2		5300FS		20"x4"	-	ANODIZED	FULL LENGTH VOLUME DAMPER	-	-
TG-1		350RL		-	14"x14"	WHITE	-	-	-



OUTDOOR AIR CALCULATIONS									
UNIT	Area (sqft)	OCCUPANCY CLASSIFICATION	Occupant Density #/1000 sqft	People outdoor airflow rate in breathing zone, (Rp) cfm/person	Area outdoor airflow rate in breathing zone, (Ra) cfm/sqft	Exhaust airflow rate cfm/sqft	Breathing zone outdoor airflow (Vbz)	Zone air distribution effectiveness (Ez)	Zone outdoor airflow (cfm)
RTU-3	1230	Sales	15	7.5	0.12		286	0.8	357
	1015	Conference rooms	50	5	0.06		315	0.8	393
	336	Conference/meeting	50	5	0.06		104	0.8	130
	188	Office spaces	5	5	0.06		16	0.8	20
	320	Corridors	0	0	0.06		19	0.8	24
							Total		925

a new development for  
**Town Centre Lot 1**  
520 NE Town Centre Drive  
Lee's Summit, Missouri 64064

date 05.19.22  
drawn by MA/FS  
checked by EK/DS  
revisions 12.20.22 REV 1

BC PROJECT #: 22323  
MISSOURI PE COA #2009003629  
This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Payment to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.

**BC ENGINEERS INCORPORATED**

5720 Reeder Shawnee, Ks. 66203 (913)262-1772

sheet number

**M2.0**

drawing type permit

project number 20231



ELECTRICAL SPECIFICATIONS

1. GENERAL PROVISIONS:
- A. PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, NECESSARY FOR THE COMPLETE INSTALLATION OF THE ELECTRICAL SYSTEMS OUTLINED.
- B. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE AUTHORITIES.
- C. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST APPROVED EDITION OF THE NATIONAL ELECTRIC CODE (NEC), AND ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION OVER THE SITE.
- D. ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.
- E. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, CONDUIT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNDAMAGED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERINGS SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.
- F. PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS AS NECESSARY. PATCH AROUND ALL OPENINGS SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.
- G. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
- H. CONTRACTOR SHALL PROVIDE ACCESS PANELS WHERE NECESSARY FOR CONCEALED ELECTRICAL COMPONENTS.
2. OPERATION AND MAINTENANCE MANUALS:
- A. DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, WIRING DIAGRAMS, CATALOG CUTS, LUBRICATION AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.
- B. ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATION AND MAINTENANCE MANUALS.
- C. ALL LITERATURE LISTED ABOVE AND ALL PAPERS LISTING WARRANTIES, ETC. SHALL BE COLLATED AND LABELED WITH THE PROJECT NAME, ADDRESS, ARCHITECT, ENGINEER, CONTRACTORS, ETC. CONTRACTORS, ETC. DOCUMENTS SHALL BE COMPILED AND BOUND IN DIGITAL FILE OR 3 RING BINDER.
3. MANUFACTURERS:
- A. MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSIDERED AS LIMITING COMPETITION. ARTICLES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO STRUCTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN, UNLESS NOTED OTHERWISE.
4. TESTING, AND BALANCING:
- A. ALL CIRCUITS SHALL BE TESTED FOR CONTINUITY, SHORTS, AND GROUNDS BEFORE CONNECTING TO THE PROPER PHASE AS DESIGNED TO BALANCE THE LOADSING PHASES.
- B. POWER AND LIGHTING PANELS SHALL BE PROPERLY PHASED TO DISTRIBUTE THE LOAD AND SHALL BE CONNECTED AND ADJUSTED TO OPERATE AS SPECIFIED.
- C. ALL MOTORS AND SIMILAR EQUIPMENT SHALL BE CHECKED FOR PROPER PHASE ROTATION AND OPERATION.
5. RACEWAYS:
- A. CONDUIT INSIDE THE BUILDING SHALL BE METALLIC TUBING (EMT), BEARING THE UL LABEL, WITH COMPRESSION TYPE FITTINGS OR SCREEN SET FITTINGS.
- B. CONDUIT EXPOSED TO THE WEATHER, INSTALLED UNDERGROUND, IN CONCRETE, OR USED FOR SERVICE ENTRANCE SHALL BE STANDARD RIGID CONDUIT (GALVANIZED) WITH THREADED FITTINGS.
- C. UNDERGROUND CONDUIT MAY BE POLYVINYL CHLORIDE WITH A DEFLECTION TEMPERATURE, UNDER LOAD AT 264 PSI, OF 78 DEGREES C, AND A TENSILE STRENGTH OF 5,200 PSI. JOINTS SHALL BE FLUSH JOINTS, FUSED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE EQUAL TO CARLON POWER AND COMMUNICATIONS DUCT TYPE DB (DIRECT BURIAL). CONDUIT AND FITTINGS SHALL BE PROVIDED BY THE SAME MANUFACTURER.
- D. FLEXIBLE METAL CONDUIT SHALL ONLY BE USED FOR CONNECTIONS TO MOTORS, TRANSFORMERS, AND LIGHT FIXTURES. MAXIMUM LENGTH SHALL BE 6'-0".
6. CONDUCTORS:
- A. WIRES SHALL BE CONTINUOUS WITHOUT SPLICES OR TAPS IN CONDUIT RUNS. ALL SPLICES SHALL BE MADE IN JUNCTION, PULL, OR OUTLET BOXES. ALL WIRES SHALL BE INSTALLED IN CONDUIT, RISERSAYS, OR OTHER PROTECTIVE COVERS SANCTIONED BY CODES.
- B. CONDUCTORS FOR LIGHTING AND POWER SHALL BE COPPER, MINIMUM NO. 12 AWG, 600 VOLT.
- C. NO. 10 GAUGE AND SMALLER CONDUCTORS SHALL BE TYPE THIN (NET LOCATIONS) OR THIN (DRY LOCATIONS), SOLID CONDUCTOR, UNLESS OTHERWISE INDICATED.
- D. NO. 3 GAUGE AND LARGER CONDUCTORS SHALL BE TYPE THIN (NET LOCATIONS) OR THIN (DRY LOCATIONS), STRANDED, UNLESS OTHERWISE INDICATED.
- E. SERVICE ENTRANCE AND PANEL FEEDER CONDUCTORS, NO. 3 GAUGE AND LARGER SHALL BE TYPE XHHW-2 (NET LOCATIONS) OR THIN (DRY LOCATIONS), STRANDED COPPER, UNLESS OTHERWISE INDICATED.
- F. ALUMINUM SERVICE WIRE MAY BE USED FOR SERVICE ENTRANCE CONDUCTORS AND/OR PANEL FEEDERS ONLY. ALL OTHER WIRING SHALL BE COPPER CONDUCTORS AS HEREBEFORE SPECIFIED.
- G. ALUMINUM CONDUCTORS SHALL BE TYPE XHHW-2, ALCAN, "STABLOK" TYPE ALLOY CONDUCTORS UTILIZING AA-8030" ALUMINUM ALLOY. CONDUCTORS SHALL BE UL LISTED.
- H. ALL ALUMINUM CONDUCTORS SHALL BE TERMINATED IN CONNECTIONS OR LUGS WHICH ARE DUAL RATED (AL2G OR AL3G) AND ARE LISTED BY UL FOR USE WITH ALUMINUM OR COPPER CONDUCTORS AND SHALL BE SIZED TO ACCEPT ALUMINUM CONDUCTORS OF THE AMPACITY SPECIFIED.
7. MC CABLE:
- A. MC CABLE SHALL CONSIST OF INTERLOCK ARMORED CABLE MADE OF THREE OR FOUR TYPE THIN SOLID (16 AWG AND LARGER MAY BE STRANDED) COPPER CONDUCTORS RATED 407C FOR DRY LOCATIONS, WITH NYLON OR EQUIVALENT UL LISTED JACKET, PER UL STANDARD 03 THE THREE CONDUCTORS SHALL BE TWISTED TOGETHER WITH THE COPPER GROUNDING CONDUCTOR, SUITABLE FILLERS, AND WRAPPED IN BINDER TAPE. THE ASSEMBLY SHALL BE ARMORED WITH SPIRALLY WRAPPED INTERLOCKED ARMOR OF ALUMINUM OR GALVANIZED STEEL.
- B. CABLES SHALL BE TESTED IN ACCORDANCE WITH UL STANDARD 1564 FOR TYPE MC CABLE AND RATED AT 600 VOLTS, 90 DEGS. C FOR DRY LOCATIONS AND 75 DEGS. C FOR NET LOCATIONS.
8. WIRING DEVICES:
- A. WALL SWITCHES SHALL BE SPECIFICATION GRADE, QUIET TYPE, FLUSH TOS&LSE SWITCH, RATED FOR 20 AMPS, WITH THERMOPLASTIC COVER PLATES.
- 1) SINGLE POLE: HUBBELL #S1221-X, OR EQUAL.
- 2) THREE WAY: HUBBELL #S1225-X, OR EQUAL.
- 3) AS SPECIFIED ON PLANS.
- B. RECEPTACLES SHALL BE SPECIFICATION GRADE, DUPLEX, GROUNDING, TYPE LUGS WHICH ARE DUAL RATED FOR 20 AMPS, WITH THERMOPLASTIC COVER PLATES, HUBBELL #CR5952-X, OR EQUAL.
- C. GROUND FAULT INTERRUPTER RECEPTACLES (GFI) SHALL BE HUBBELL #SF20-XL. DEVICE COVER PLATES SHALL BE AS HEREBEFORE SPECIFIED.
- D. ISOLATED GROUND RECEPTACLES (IG) SHALL BE HUBBELL #CR5552IG, ORANGE COLOR. DEVICE COVER PLATES SHALL BE AS HEREBEFORE SPECIFIED.
- E. RECEPTACLES OUTSIDE BUILDINGS AND WHERE NOTED AS WEATHERPROOF, SHALL BE LISTED WEATHER-RESISTANT HUBBELL #SFTR20-X OR EQUAL AND SHALL BE INSTALLED IN A WEATHERPROOF ENCLOSURE WHICH SHALL BE INTERMATIC INV1010AND OR INV1010AND DECAT-METAL WEATHERPROOF RECEPTACLE COVER. COVER SHALL BE WEATHER PROOF RATED WHILE IN USE.
- F. VERIFY DEVICES AND DEVICE COVER PLATES COLOR AND STYLE WITH ARCHITECT.
9. BOXES:
- A. HOT DIPPED GALVANIZED STEEL BOXES. PROVIDE TYPE TO SUIT CONDITIONS FOR INSTALLATION.
- B. ALL BOXES SHALL BE FLUSH MOUNTED, UNLESS INDICATED OTHERWISE.

ELECTRICAL SPECIFICATIONS (CONTINUED)

10. PANELBOARDS:
- A. FURNISH AND INSTALL CIRCUIT BREAKER PANELBOARDS AS SHOWN ON THE DRAWINGS. PANELBOARDS SHALL BE LISTED AND SHALL BE FULLY RATED FOR THE VOLTAGE AND CURRENT CAPACITY INDICATED ON THE PANEL SCHEDULE. PANELBOARDS SHALL BE EQUAL TO SQUARE D TYPE NG OR NF WITH BOLT IN TYPE BREAKERS. PANELBOARD LUGS SHALL BE RATED AT 75'C.
- 1) CIRCUIT BREAKER INTERRUPTING CAPACITIES SHALL MEET OR EXCEED THE AVAILABLE RMS SYMMETRICAL FAULT CURRENTS INDICATED AND AS REQUIRED TO MEET OR EXCEED THE AVAILABLE FAULT CURRENT FROM LOCAL UTILITY.
- B. CIRCUIT BREAKERS SHALL MEET APPLICABLE PORTIONS OF UL STANDARD 484 AND NEMA AB-1. CIRCUIT BREAKERS SHALL BE BOLT-ON, GROUP MOUNTED, AMBIENT MAGNETIC, WITH COMMON TRIP, UL RATED TO CARRY 50% OF NAMEPLATE RATING CONTINUOUSLY IN FREE AIR AT 40'C. CIRCUIT BREAKERS SHALL BE TRIP INDICATING AND FULLY INTERCHANGEABLE WITHOUT DISTURBING ADJACENT UNITS. WIRE TERMINALS SHALL BE RATED 75 DEGREES C. THE OPERATING MECHANISM SHALL BE TRIP-FREE SO THAT CONTACTS CANNOT BE HELD CLOSED AGAINST ANY ABNORMAL OVERCURRENT OR SHORT CIRCUIT CONDITION.
- a) BREAKERS SHALL MEET APPLICABLE NEMA AND/OR UL SPECIFICATIONS.
- C. PANELBOARD BOXES SHALL BE GALVANIZED SHEET STEEL WITH AMPLIFIED WIRING GUTTER SPACE IN ACCORDANCE WITH NEC. FRONTS SHALL BE OF SHEET STEEL, PAINTED LIGHT GREY OVER A SUITABLE RUST INHIBITOR PRIMER. PANELBOARDS SHALL BE EQUIPPED WITH ONE PIECE DOOR, CYLINDER TUMBLER TYPE LOCK, DIRECTORY CARD-HOLDER AND QUARTER-TURN ADJUSTABLE TRIM CLAMPS.
- D. PANELBOARD INTERIORS SHALL CONSIST OF REINFORCED GALVANIZED SHEET STEEL FRAMES WITH ALUMINUM BUS BARS AND CIRCUIT BREAKERS, PROPERLY SUPPORTED TO PREVENT VIBRATIONS AND BREAKAGE IN HANDLING. BUS BARS SHALL BE SEQUENCE PHASED. PANELBOARD SHALL HAVE A FULL SIZED SOLID ALUMINUM NEUTRAL AND GROUND BUS.
- E. BUS BAR BRACING SHALL BE UL LISTED AS INDICATED ON DRAWINGS. ADDITIONAL BRACING SHALL BE PROVIDED AS REQUIRED TO MEET OR EXCEED INDICATED AVAILABLE FAULT CURRENTS.
- F. DIRECTORY CARDS SHALL BE COMPLETELY FILLED IN BY TYPEWRITER, LISTING CIRCUIT NUMBERS AND LOAD SERVED, INCLUDING EXISTING CIRCUITS. CIRCUIT BREAKERS SHALL BE IDENTIFIED BY CIRCUIT NUMBER LABELS AS HEREBEFORE SPECIFIED.
11. DISCONNECTS:
- A. DISCONNECTS SHALL BE EXTERNALLY OPERATED, QUICK-MAKE, QUICK-BREAK, SAFETY, WITH PROVISIONS FOR PAD LOCKING. FUSED AND NON-FUSED DISCONNECT SWITCHES SHALL BE PROVIDED AS INDICATED.
- B. INDOOR SWITCHES SHALL BE NEMA 1 AND OUTDOOR SWITCHES SHALL BE NEMA 3B, UNLESS INDICATED OTHERWISE.
12. FUSES:
- A. FUSES PROTECTING CIRCUIT BREAKER PANELS SHALL BE CURRENT LIMITING UL CLASS RK-1 FUSES WITH 200,000 AMPERES RMS SYM INTERRUPTING CAPACITY. FUSING ELEMENTS SHALL BE SILVER FOR RATINGS ABOVE 60 AMPERES.
- B. ALL OTHER FUSES SHALL BE UL CLASS RK-5, DUAL-ELEMENT WITH A MINIMUM TIME-DELAY OF 10 SECONDS AT 800% RATING. FUSES SHALL HAVE CURRENT-LIMITING SHORT-CIRCUIT LINKS AND 200,000 AMPERES RMS SYM INTERRUPTING CAPACITY. FUSING ELEMENTS SHALL BE COPPER.
13. LIGHT FIXTURES:
- A. WHERE LIGHT FIXTURES ARE MOUNTED IN A LAY-IN CEILING, PROVIDE A MINIMUM OF 2 SUPPORT WIRES ATTACHED DIRECTLY BETWEEN EACH LIGHT FIXTURE AND THE BUILDING STRUCTURE. SUPPORT WIRES SHALL BE A MINIMUM OF 12 GAUGE GALVANIZED STEEL WIRE, SOFT ANNEALED.
- B. FIXTURES ARE REQUIRED AT ALL LIGHTING OUTLETS SHOWN ON THE DRAWINGS. APPROVED LIGHTING FIXTURE WIRE IS REQUIRED IN ALL FIXTURES AND FIXTURE RACEWAYS. WEATHERPROOF WIRING IS REQUIRED FOR EXTERIOR FIXTURES. ALL PARTS OF FIXTURES AND WIRING SHALL BE IN ACCORDANCE WITH NEC REQUIREMENTS.
- C. ALL FIXTURES SHALL CARRY UL AND ETL LABELS.
14. SLEEVES:
- A. PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK.
- B. INTERIOR PARTITIONS: 16 GAUGE GALVANIZED STEEL, PACK BETWEEN CONDUIT AND SLEEVE WITH FIRE SAFING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.
- C. ROOF: PROSET OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WEATHERPROOF SEAL. COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF WARRANTY.
15. GROUNDING:
- A. GROUND ALL ELECTRICAL APPARATUS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE (NEC) 250, AND ANY LOCAL REQUIREMENTS. INSURE CONTINUOUS BOND WHERE FLEXIBLE CONDUIT IS USED. PROVIDE BONDING JUMPER INSIDE ALL FLEXIBLE CONDUIT.
- B. BOND METAL PIPING SYSTEMS IN COMPLIANCE WITH NEC 250.4(A)(4).
16. REMODELING WORK:
- A. DEMOLITION, DISCONNECT, DEMOLISH AND REMOVE ABANDONED ELECTRICAL MATERIALS AND EQUIPMENT INDICATED TO BE REMOVED AND NOT INDICATED TO BE SALVAGED OR REMAIN.
- B. EQUIPMENT TO BE SALVAGED:
- 1) DISCONNECT AND REMOVE EXISTING ELECTRICAL EQUIPMENT INDICATED TO BE REMOVED AND SALVAGED. DELIVER EQUIPMENT TO THE LOCATION DESIGNATED BY THE OWNER FOR STORAGE.
- 2) ALL MATERIALS AND EQUIPMENT DESIGNATED TO BE REUSED OR RELOCATED SHALL BE CAREFULLY REMOVED, AND STORED UNTIL NEEDED FOR REMODELING WORK. ALL ITEMS SHALL BE RESTORED TO LIKE NEW CONDITION WITH RUST OR CORROSION REMOVED, SURFACE PAINT TOUCHED UP OR REPAINTED AS REQUIRED TO MATCH NEW CONSTRUCTION, AND THOROUGHLY CLEANED AND INSPECTED. ANY ITEMS WHICH BECOME DAMAGED BEYOND REPAIR AS A RESULT OF CONSTRUCTION OR DEMOLITION ACTIVITY SHALL BE REPLACED WITH NEW MATERIAL EQUIVALENT IN EVERY RESPECT.
- C. DISPOSAL AND CLEANUP: REMOVE FROM THE SITE AND LEGALLY DISPOSE OF DEMOLISHED MATERIALS AND EQUIPMENT NOT INDICATED TO BE SALVAGED.
- D. PROTECT ADJACENT MATERIALS INDICATED TO REMAIN. INSTALL AND MAINTAIN DUST AND NOISE BARRIERS TO KEEP DIRT, DUST, AND NOISE FROM BEING TRANSMITTED TO ADJACENT AREAS. REMOVE PROTECTION AND BARRIERS AFTER REMODELING OPERATIONS ARE COMPLETE.
- E. PROVIDE ALL ALTERATIONS AND REWORK INDICATED AND/OR REQUIRED FOR THE PROPER INSTALLATION AND OPERATION OF ALL EXISTING ELECTRICAL SYSTEMS, INTEGRATING THE NEW AND EXISTING AREAS. LOCATE, IDENTIFY, AND PROTECT ELECTRICAL SERVICES PASSING THROUGH REMODELING AREA AND SERVING OTHER AREAS OUTSIDE THE REMODELING LIMITS. MAINTAIN SERVICES TO AREAS OUTSIDE REMODELING LIMITS. WHEN SERVICES MUST BE INTERRUPTED, INSTALL TEMPORARY SERVICES FOR AFFECTED AREAS.
- 1) ABANDONED CONDUIT SHALL HAVE WIRE REMOVED AND SHALL BE CAPPED. ABANDONED OUTLETS IN WALLS OR PARTITIONS SHALL HAVE DEVICES AND WIRE REMOVED, AND SHALL BE COVERED.
- 2) WHERE EXISTING CONDUITS TERMINATE AT AN EXISTING OUTLET IN A WALL, CEILING, OR FLOOR TO BE REMOVED, DISCONNECT AND REMOVE DEVICE AND WIRE FROM CONDUIT. CONDUIT SHALL BE CUT BACK AND CAPPED (BELOW THE FLOOR OR ABOVE THE CEILING) SO NOT TO CREATE AN OBSTRUCTION. PATCH FLOOR TO MATCH EXISTING.
- 3) WHERE EXISTING CIRCUITS EXTEND BEYOND THE OUTLET IN THE EXISTING WALL, CEILING, OR FLOOR TO BE REMOVED, FURNISH AND INSTALL NEW CONDUIT AND WIRE TO EITHER REROUTE THE CIRCUIT OR FEED THE REMAINING OUTLET(S) FROM ANOTHER ELECTRICAL SOURCE, BUT IN SUCH A MANNER AS NOT TO REVISE THE CIRCUIT. ALL REROUTED CONDUIT SHALL BE APPROVED BY THE ARCHITECT.
- 4) WHERE EXISTING OUTLETS IN A WALL, CEILING, OR FLOOR TO BE REMOVED ARE ESSENTIAL TO MAINTAIN OPERATION OF OTHER REMAINING OUTLETS, RELOCATE THE OUTLET TO A NEW CONVENIENT LOCATION. EXISTING WIRING DEVICES SHALL NOT BE REUSED, UNLESS OTHERWISE INDICATED.
- 5) WHERE LIGHTING FIXTURES ARE INDICATED TO BE DEMOLISHED, REMOVE ALL WIRE AND MODIFY THE EXISTING CONDUIT (IF APPLICABLE) FOR THE NEW LIGHTING. ALL UNUSED CONDUIT SHALL BE REMOVED.
- 6) WHERE A TELEPHONE CIRCUIT EXTENDS BEYOND AN OUTLET IN AN EXISTING WALL, CEILING, OR FLOOR TO BE REMOVED, PROVIDE NECESSARY EMPTY CONDUIT AND NOTIFY THE OWNER WHO WILL REQUEST THE OWNER TO ARRANGE WITH THE TELEPHONE COMPANY FOR NEW WIRING TO OUTLETS THAT REMAIN.
- 7) WHERE EXISTING CONDUIT AND WIRE RUNS ARE LOCATED IN OR ATTACHED TO AN EXISTING WALL, CEILING OR FLOOR TO BE REMOVED, THEY SHALL BE REROUTED IN EITHER NEW OR EXISTING CONSTRUCTION TO MAINTAIN CONTINUITY OF CIRCUITS UNLESS OTHERWISE INDICATED.
- 8) CONDUIT SHALL BE CONCEALED WITHIN THE EXISTING BUILDING CONSTRUCTION WHEREVER POSSIBLE, EXCEPT WHERE OTHERWISE INDICATED.
- 9) EXISTING WIRE SHALL BE DISCONNECTED AND REMOVED WHEREVER EXISTING CIRCUITS ARE ABANDONED.
17. BOXES IN FIRE RATED ASSEMBLIES:
- A. OUTLET BOXES THAT DO NOT EXCEED 16 SQUARE INCHES AND INSTALLED IN FIRE RATED WALLS SHALL NOT BE INSTALLED CLOSER THAN 24" HORIZONTAL INCHES TO OTHER OUTLET BOXES.
- B. IF BOXES MUST BE INSTALLED WITHIN 24" OF EACH OTHER THAN BOTH OUTLET BOXES SHALL BE PROTECTED WITH LISTED PUTTY PADS, 3M FIRE BARRIER MOLDABLE PUTTY + OR EQUAL.
18. FIRE ALARM SYSTEM:
- A. ELECTRICAL CONTRACTOR SHALL PROVIDE DESIGN BUILD ENGINEERED SHOP DRAWINGS OF FIRE ALARM SYSTEM TO BE INSTALLED. PROVIDE DEVICES, CONDUIT, WIRES, CABLE, PROGRAMMING AND TESTING AS DIRECTED BY EQUIPMENT MANUFACTURER AND LOCAL FIRE DEPARTMENT FOR A CODE COMPLIANT FIRE ALARM/DETECTION SYSTEM. MATERIALS, EQUIPMENT, AND WORKMANSHIP SHALL MEET PREVAILING CODES. THE SYSTEM SHALL BE COMPLETE AND OPERABLE. SUBMIT ONE LINE DIAGRAM OF SYSTEM WITH SIZES AND BATTERIES. EQUIPMENT TO BE NEW AND SHALL BE STAMPED, SIGNED, CALIBRATION AND TESTED BY FACTORY CERTIFIED TECHNICIAN. FIRE ALARM DEVICES ARE SHOWN FOR INTENT ONLY FOR PERMITTING PROCESS. CONTRACTOR IS RESPONSIBLE FOR INCLUDING IN BID/DESIGN ALL NECESSARY DEVICES (ANNUNCIATOR(S)), NOTIFICATION APPLIANCES, INITIATING DEVICES, AND ADDITIONAL COMPONENTS).

ELECTRICAL SYMBOLS LIST

CIRCUITING & NOTES

+48"	SPECIAL MOUNTING HEIGHT FOR ASSOCIATED DEVICE (CENTERLINE OF DEVICE)
GFI	GROUND FAULT CIRCUIT INTERRUPTER DEVICE
WP	WEATHERPROOF ENCLOSURE ON DEVICE
WR	WEATHERPROOF RESISTANT DEVICE
IG	ISOLATED GROUND DEVICE
EM	EMERGENCY BATTERY BACKUP
TR	TAMPER RESISTANT OUTLET
USB	COOPER #TR1756-X OR EQUAL DUPLEX RECEPTACLE WITH DUAL USB CHARGING PORTS. PROVIDE 2-1/8" DEEP BACK BOX.
(TIE)	PARTIAL HOMERUN. REFER TO PLANS FOR ADDITIONAL DEVICES CONNECTED TO THIS CIRCUIT.
X	ELECTRICAL FLOOR PLAN NOTE WITH DESIGNATION
2 LP	CONDUIT CONCEALED WHERE POSSIBLE OR AS NOTED, ARROWS INDICATE HOME RUN TO PANEL. CIRCUIT NUMBERS INDICATED
⚡	#12 WIRE IN CONDUIT, UNLESS NOTED OTHERWISE ON DRAWINGS OR SPECIFICATION
⚡	GROUNDING CONDUCTOR, #12 WIRE UNLESS NOTED OTHERWISE ON DRAWINGS OR SPECIFICATION
⚡	CONDUIT ROUTED UNDER FLOOR/GRADE

LIGHTING

⚡	EMERGENCY TWIN HEAD LIGHT FIXTURE
⚡	EXIT LIGHT WITH DIRECTIONAL ARROWS INDICATED
⚡	STRIP FIXTURE WITH TYPE DESIGNATION
A •	RECESSED OR SURFACE MOUNTED FIXTURE WITH TYPE DESIGNATION
A NL	NIGHT LIGHT, CONNECT TO UNSWITCHED CIRCUIT
A □	CEILING OR RECESSED FIXTURE WITH TYPE DESIGNATION
A □	WALL MOUNTED FIXTURE WITH TYPE DESIGNATION

POWER DEVICES

⚡	DUPLEX RECEPTACLE, BOTTOM OF BOX AT 16" AFF, UNLESS NOTED OTHERWISE
⚡	FOURPLEX RECEPTACLE, BOTTOM OF BOX AT 16" AFF, UNLESS NOTED OTHERWISE
⚡⚡	TVSS SURGE SUPPRESSION RECEPTACLE
⚡	HEAVY DUTY OUTLET - NEMA CONFIGURATION SIZE PER EQUIPMENT MANUFACTURER'S RECOMMENDATION
⚡	PANEL BOARD, TOP OF BOX 6'-0" AFF
⚡	JUNCTION BOX
⚡	NON-FUSED DISCONNECT SWITCH
⚡	FUSED DISCONNECT SWITCH
⚡	MOTOR WITH DESIGNATION
⚡	FLOOR BOX

CONTROLS

S	SINGLE POLE WALL SWITCH, TOP OF BOX AT 48" AFF
S3	THREE-WAY WALL SWITCH, TOP OF BOX AT 48" AFF
SD	DIMMER SWITCH, TOP OF BOX AT 48" AFF
SM	MANUAL MOTOR STARTER WITH OVERLOADS

OCCUPANCY SENSORS

1. DUAL TECHNOLOGY/ULTRASONIC CEILING SENSORS SHALL BE MOUNTED 6' FROM SUPPLY/EXHAUST AIR DIFFUSERS.
2. LOW VOLTAGE CEILING SENSORS SHALL BE PROVIDED WITH 6' SLACK CONDUCTOR COILED AT SENSOR.


S2	WALL MOUNTED DUAL-TECHNOLOGY OCCUPANCY SENSOR, MATT STOPPER #DW-100, TOP OF BOX AT 48" AFF
SD	DUAL TECHNOLOGY CEILING MOUNT OCCUPANCY SENSORS, MATTSTOPPER DT-300
SD	OCCUPANCY SENSOR POWER PACK, MATTSTOPPER BZ-150 OR EQUAL, PROVIDE LOW VOLTAGE WIRING TO OCCUPANCY SENSORS AND MOMENTARY SWITCHES
SMD	MOMENTARY SWITCH, TOP OF BOX AT 48" AFF

COMMUNICATIONS

▼	DATA/TELEPHONE OUTLET WITH MINIMUM 3/4" CONDUIT STUBBED UP TO ABOVE ACCESSIBLE CEILING, BOTTOM OF BOX AT 16", UNLESS NOTED OTHERWISE. PROVIDE WITH FULL STRING
TV	FLAT SCREEN TELEVISION - PROVIDE AND INSTALL ONE (1) HUBBELL #RR1510X RECESSED TAMPER-RESISTANT DUPLEX RECEPTACLE WITH COVERPLATE AND ONE(1) HUBBELL #HBL260 TWO GANG LARGE CAPACITY WALL BOX (UP TO 2" KNOCKOUT) IV/ MUD RING AND COVERPLATE FOR DATA. PROVIDE 2"C WITH FULL STRING TO ABOVE ACCESSIBLE CEILING FOR DATA CABLES. MOUNT BOX AT 7'-6" AFF UNLESS NOTED OTHERWISE (VERIFY)

ELECTRICAL GENERAL NOTES:


1. COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
2. WHERE CONDUIT IS SHOWN UNDER FLOOR, VERIFY IF FLOOR IS STRUCTURAL SLAB OR SLAB ON GRADE. IF STRUCTURAL SLAB, CORE DRILL PENETRATION, AND ROUTE CONDUIT IN SPACE BELOW. IF SLAB ON GRADE, SAW CUT EXISTING FLOOR SLAB AS REQUIRED FOR INSTALLATION OF UNDER FLOOR CONDUIT. NO STRUCTURAL ELEMENTS SHALL BE CORE DRILLED OR SAW CUT, WHEN SAW CUTTING, PATCH FLOOR TO MATCH EXISTING SURFACE AS REQUIRED.
3. IT IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY TO PROPERLY BALANCE ALL BRANCH CIRCUITS BETWEEN THE PHASES OF THE SYSTEM REGARDLESS OF CIRCUITING INDICATED.
4. ALL EXPOSED RACEWAYS SHALL BE EMT CONDUIT, MC CABLE IS NOT PERMITTED IN EXPOSED AREAS.
5. ELECTRICAL CONTRACTOR TO COORDINATE MANUFACTURER ELECTRICAL REQUIREMENTS FOR HVAC EQUIPMENT BEING FURNISHED WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN. EQUIPMENT DISCONNECTS TO BE PROVIDED BY ELECTRICAL CONTRACTOR UNLESS NOTED OTHERWISE IN MECHANICAL SCHEDULES.
6. ALL MATERIALS EXPOSED WITHIN PLENUMS SHALL BE NONCOMBUSTIBLE OR SHALL HAVE A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE-DEVELOPED INDEX OF NOT MORE THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM E 84.
7. EACH BRANCH CIRCUIT SHALL HAVE A DEDICATED NEUTRAL PER NEC 210.4.
8. FIRE ALARM SYSTEM IS SHOWN FOR SCHEMATIC PURPOSES. THE FIRE ALARM CONTRACTOR IS RESPONSIBLE FOR PROVIDING DESIGN AND SHOP DRAWINGS SUBMITTAL TO FIRE MARSHAL FOR APPROVAL AS REQUIRED BY THE FIRE MARSHAL. IT IS THE CONTRACTORS RESPONSIBILITY TO PROVIDE ADDITIONAL DEVICES, POWER SUPPLIES, ETC FOR COMPLIANCE WITH CODE.
9. ALL BRANCH CIRCUITS SHALL BE SIZED TO ALLOW FOR A MAXIMUM OF 3% VOLTAGE DROP. ALL FEEDERS SHALL BE SIZED TO ALLOW FOR A MAXIMUM OF 2% VOLTAGE DROP. ELECTRICAL CONTRACTOR SHALL VERIFY WIRING INDICATED IS SUFFICIENT AND INCREASE CONDUCTOR SIZE AS REQUIRED BASED OFF ACTUAL INSTALLED LENGTH OF CONDUCTORS.
10. PROVIDE LOW VOLTAGE WIRING BETWEEN ALL 0-10V DIMMING DRIVERS CONTROLLED BY 0-10V DIMMERS PER MANUFACTURER'S INSTRUCTIONS WHETHER INDICATED ON PLANS OR NOT.
11. COORDINATE VENDING AND TV LOCATIONS WITH OWNER.



BC PROJECT #: 22323  
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Design Engineer and is intended for use on the project only. Payment to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of signs and elements appearing herein, constitute the original, copyrighted work of the Design Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.






LIGHTING PLAN NOTES:

- 1 ROUTE CIRCUIT THROUGH CONTACTOR A FOR CONTROL OF BATTING CAGE LIGHTS. SEE DETAIL, THIS SHEET.
- 2 ROUTE CIRCUIT THROUGH CONTACTOR B FOR CONTROL OF BATTING CAGE LIGHTS. SEE DETAIL, THIS SHEET.
- 3 ROUTE CIRCUIT THROUGH CONTACTOR C FOR CONTROL OF BATTING CAGE LIGHTS. SEE DETAIL, THIS SHEET.
- 4 ROUTE CIRCUIT THROUGH CONTACTOR D FOR CONTROL OF BATTING CAGE LIGHTS. SEE DETAIL, THIS SHEET.
- 5 ROUTE CIRCUIT THROUGH CONTACTOR F FOR CONTROL OF BATTING CAGE LIGHTS. SEE DETAIL, THIS SHEET.
- 6 ROUTE CIRCUIT THROUGH CONTACTOR G FOR CONTROL OF BATTING CAGE LIGHTS. SEE DETAIL, THIS SHEET.
- 7 VERIFY BATTING CAGE SWITCHBANK LOCATION WITH OWNER PRIOR TO ROUGH-IN.
- 8 JUNCTION BOX WITH DISCONNECTING MEANS PER NEC FOR CONNECTION TO BUILDING MOUNTED SIGNAGE. VERIFY EXACT LOCATION AND CONNECT TO SIGN PER MANUFACTURER'S INSTRUCTIONS. ROUTE CIRCUIT THRU TIMECLOCK, SEE DETAIL, THIS SHEET.
- 9 ROUTE THRU EXTERIOR LIGHTING CONTROLS. SEE DETAIL, THIS SHEET.




ELECTRICAL LIGHTING PLAN

SCALE: 1/8" = 1'-0"



LIGHTING CONTROL DIAGRAM  
SCALE: NONE



EXTERIOR LIGHTING CONTROL DIAGRAM  
SCALE: NONE

BC PROJECT #: 22323  
MISSOURI PE COA #2009003629  
This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Payment to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of signs and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.

BC ENGINEERS  
INCORPORATED

5720 Reeder Shawnee, Ks. 66203 (913)262-1772

a new development for

Town Centre Lot 1

520 NE Town Centre Drive

Lee's Summit, Missouri 64064

date 05.19.22  
drawn by MA/FS  
checked by EK/DS  
revisions  
12.20.22 REV 1

sheet number

E1  
LIGHTING PLAN

drawing type  
permit

project number  
20231




1/4/2023



POWER PLAN NOTES:

1. PROVIDE QUAD RECEPTACLE AND DATA TO EACH PITCHING MACHINE. EACH MACHINE REQUIRES (2) ETHERNET CABLES AND (1) MULTI CABLE WIRE, SUPPLIED BY PITCHING MACHINE COMPANY, IN CONDUIT FROM THE PITCHING MACHINE TO THE CARD OPERATED BOX KIOSK. VERIFY ALL ELECTRICAL SPECIFICATIONS WITH PITCHING MACHINE COMPANY PRIOR TO ROUGH-IN.
2. VERIFY LOCATION OF CARD OPERATED BOX KIOSK WITH OWNER PRIOR TO ROUGH-IN.
3. VERIFY EXACT LOCATION OF ELECTRICAL DEVICES IN MOUNTED IN CASEWORK.
4. VERIFY LOCATION OF 2'X4'X3/4" FIRE RETARDANT FLYWOOD TELEPHONE BACKBOARD WITH GROUND BAR AND #6 CU BOND TO BUILDING ELECTRODE SYSTEM. PROVIDE 4" C TO PROPERTY LINE FOR BUILDING TELEPHONE AND INTERNET SERVICE. TERMINATE AS DIRECTED BY SERVICE PROVIDER. VERIFY ROUTING AND DISTANCE.
5. PENDANT MOUNT FIRE ALARM DEVICE.



**ELECTRICAL POWER PLAN**  
SCALE: 1/8" = 1'-0"  
NORTH

a new development for  
**Town Centre Lot 1**  
520 NE Town Centre Drive  
Lee's Summit, Missouri 64064

date 05.19.22  
drawn by MA/FS  
checked by EK/DS  
revisions 12.20.22 REV 1

BC PROJECT #: 22323  
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on the project only. Payment to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.

**BC ENGINEERS INCORPORATED**

5720 Reeder Shawnee, Ks. 66203 (913)262-1772

sheet number

**E2**  
POWER PLAN

drawing type  
permit


project number  
20231



LIGHT FIXTURE SCHEDULE					
MARK NO.	MANUFACTURER & CATALOG NUMBER	VOLTS WATTS	LIGHT SOURCE	DESCRIPTION	EQUIVALENT MANUFACTURERS
A	LUX DYNAMICS IK10 SERIES E 3 D A 850 4 U10 CP B 33Y X 6YM	120 229	LED 36,000LUM 5000K	3 LIGHT BAR 2 CHANNEL LED 36,000 LUMEN, 5,000 KELVIN, 2-POINT Y CABLE MOUNT, VERIFY FINISH COLOR, MOUNT BOTTOM OF FIXTURE AT 22' AFF. ORDER CABLE TO LENGTH REQUIRED	WILLIAMS COLUMBIA OR EQUAL
B	LUX DYNAMICS IK10 SERIES E 1 S A 850 4 U10 CP B 33Y X 6YM	120 78	LED 11,000LUM 5000K	1 LIGHT BAR 1 CHANNEL LED 11,000 LUMEN, 5,000 KELVIN, 2-POINT Y CABLE MOUNT, VERIFY FINISH COLOR, MOUNT BOTTOM OF FIXTURE AT 22' AFF. ORDER CABLE TO LENGTH REQUIRED	WILLIAMS COLUMBIA OR EQUAL
BE	LUX DYNAMICS IK10 SERIES E 1 S A 850 4 U10 CP B E15 33Y X 6YM	120 78	LED 11,000LUM 5000K	1 LIGHT BAR 1 CHANNEL LED 11,000 LUMEN, 5,000 KELVIN, 2-POINT Y CABLE MOUNT WITH EMERGENCY DRIVER, 2,561 LUMEN. VERIFY FINISH COLOR, MOUNT BOTTOM OF FIXTURE AT 22' AFF. ORDER CABLE TO LENGTH REQUIRED	WILLIAMS COLUMBIA OR EQUAL
C	LITHONIA EPANL 2X4 4000LM 80CRI 50K EZT MVOLT	120 38	LED 4000LUM 5000K	LED FLAT PANEL, 4000 LUMEN, 5000 KELVIN, VERIFY MOUNTING REQUIREMENTS AND HEIGHTS	WILLIAMS COLUMBIA OR EQUAL
C1	LITHONIA EPANL 2X4 3000LM 80CRI 50K EZT MVOLT	120 29	LED 3000LUM 5000K	LED FLAT PANEL, 3000 LUMEN, 5000 KELVIN, VERIFY MOUNTING REQUIREMENTS AND HEIGHTS	WILLIAMS COLUMBIA OR EQUAL
DE	LITHONIA GLX L48 4000LM SEF RDL 120 EZ1 40K 80CRI FS1050 WH	120 28	LED 4000LUM 4000K	4' LED STRIP FIXTURE WITH ROUND LENS, 4000 LUMEN, 4000 KELVIN, WALL MOUNTED	WILLIAMS COLUMBIA OR EQUAL
W	EXTERIOR SCONCE, VERIFY FINISH WITH OWNER	120	LED LUM K	LED SCONCE	
W1	CREE LIGHTING XSPN-B-NM-4ME-AL-40K-UNV	120 31	LED 4270LUM 4000K	WALL MOUNTED LED BUILDING LIGHT WITH TYPE IV MEDIUM THROW OPTIC. VERIFY FINISH COLOR WITH ARCHITECT	
SA	CREE LIGHTING OSQ-M-B-9L-40K7-4M-UNV-NM MOUNT-SQG-ML-B-DA SHIELD-OSQ-BLSMT POLE-SSS-4-11-12-CN-B5-1D-C	120 130	LED 7075LUM 4000K	POLE MOUNTED WITH HOUSE SIDE SHIELD LED AREA LIGHT WITH TYPE IV MEDIUM THROW OPTIC. MOUNT ON 12'X4" SQUARE STEEL POLE WITH 3' CONCRETE BASE. VERIFY FINISH COLOR WITH ARCHITECT	
SB	CREE LIGHTING OSQ-M-B-9L-40K7-5Q-UNV-NM MOUNT-SQG-ML-B-DA POLE-SSS-4-11-12-CN-B5-2D1B-C	120 120	LED 10250LUM 4000K	POLE MOUNTED LED 180 DEGREE AREA LIGHT WITH TYPE V SQUARE OPTIC. MOUNT ON 12'X4" SQUARE STEEL POLE WITH 3' CONCRETE BASE. VERIFY FINISH COLOR WITH ARCHITECT	
EL	DUAL-LITE EV2	120 1	INCL	EMERGENCY LIGHT WITH TWIN ADJUSTABLE 1 WATT LED HEADS AND BATTERY, MOUNT AT T-6", TO CLEAR OBSTACLES. (PROVIDES 1 FC AVG. ON 2T CENTER FIXTURE SPACING)	SURE-LITES LITHONIA OR EQUAL
EL1	DUAL-LITE EVE-U-R-N-VR53	120 1	INCL	EXIT LIGHT WITH LED LAMPS, RED LETTERS ON WHITE BACKGROUND, UNIVERSAL MOUNT, BATTERY BACKUP, WITH VANDAL RESISTANT SHIELD	SURE-LITES LITHONIA OR EQUAL
EL2	DUAL-LITE EVC-U-R-N-VR53	120 3	INCL	COMBINATION EMERGENCY/EXIT LIGHT WITH LED LAMPS, RED LETTERS ON WHITE BACKGROUND, TWIN LED EMERGENCY LIGHT HEADS, UNIVERSAL MOUNT, BATTERY BACKUP, WITH VANDAL RESISTANT SHIELD	SURE-LITES LITHONIA OR EQUAL
EL3	DUAL-LITE EVC-U-R-M-D4-VR53 WITH EVO-D-X	120 5	INCL	COMBINATION EMERGENCY/EXIT LIGHT WITH LED LAMPS, RED LETTERS ON WHITE BACKGROUND, TWIN 6W EMERGENCY LIGHT HEADS, UNIVERSAL MOUNT, HIGH CAPACITY BATTERY BACKUP, VANDAL RESISTANT SHIELD AND REMOTE TWIN HEAD OUTDOOR RATED FIXTURE	SURE-LITES LITHONIA OR EQUAL
EX	LITHONIA AITFOEL-XX-UVOLT-LTP-SDRT-WT-CN	120 12	LED INCL 4000K	ARCHITECTURAL EXTERIOR LED EMERGENCY LIGHT WITH COLD WEATHER BATTERY, COORDINATE FINISH TO MATCH BUILDING	SURE-LITES LITHONIA OR EQUAL
NOTES:					






**date**  
 05.19.22  
**drawn by**  
 MA/FS  
**checked by**  
 EK/DS  
**revisions**   
 12.20.22 REV 1

**BC PROJECT #:** 22323  
**MISSOURI** **PE COA #**2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2022 BC Engineers, Inc.

5720 Reeder Shawnee, Ks. 66203 (913)262-1772



COORDINATE ALL ELECTRICAL  
SERVICE WORK WITH LOCAL UTILITY  
COMPANY.