

20300 W 207TH St
Spring Hill, KS
66083

P

Since 1923

PREMIER

BUILDING SUPPLY OF KANSAS CITY

Phone: 913.686.1812

www.premierbuildingsupply.com

Customer

Clover & Hive

Job Name:

Twin Cobalt

Address:

Osage Lot 53

Salesperson:

Kyle Clifford

Designer:

Dereck Cooper

TRUSS PLACEMENT DIAGRAM

Job #:

P230110

Date:

3/16/2023

Scale:

NTS

ROOF

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/28/2023 4:27:54

1 - H2.5T REQUIRED AT ALL BEARING LOCATIONS (u.n.o.)
ALL TRUSS TO TRUSS CONNECTIONS = "NAILED" (u.n.o.)
1 - H2.5T NECESARIO EN TODO LOS PUNTOS DE APOYO (u.n.o.)
TODAS LAS CONEXIONES DE TRUSS A TRUSS = "CLAVADAS " (u.n.o.)

ROOF PITCH FRONT TO BACK: 5/12
SOFFIT DESIGNED FOR 12" OH
HEEL HEIGHT: 12"

ROOF PITCH LEFT TO RIGHT: 8/12
SOFFIT DESIGNED FOR 12" OH
HEEL HEIGHT: 12"

ALL CEILINGS ARE FLAT UNLESS OTHERWISE NOTED

TYPICAL WALL HEIGHT 8' 1 1/8" 2X4 PER PLAN
PLATE HEIGHT 9' 1 1/8" 2X4 (HATCHED) PER PLAN

SEE PLACEMENT PLAN FOR ADDITIONAL INFORMATION

Truss Connector Total List		
Manuf	Product	Qty
SIMPSON	HUS26	16
SIMPSON	THJU26	4
SIMPSON	HGUS26-2	2
SIMPSON	SDW15600	300

Hatch Legend	
	= 9-1-2 PLATE HEIGHT
	= RAKED WALL

◀ - EL EXTREMO IZQUIERDO DE LOS TRUSSES (VEA LOS PERFILES)
TODAS LAS DIMENSIONES PARA LAS TRUSSES SON DE FUERA DE LA MADERA (u.n.o.)
ESTABLECER LOS TRUSSES NIVELADAS CON LA ESTRUCTURA (u.n.o.)
◀ - LEFT END OF TRUSS (SEE TRUSS PROFILES)
ALL ROOF TRUSS DIMENSIONS ARE FROM OUTSIDE EDGE OF STUD (u.n.o.)
SET ROOF TRUSSES FLUSH WITH FRAMING (u.n.o.)

WARNING: Trusses must be handled with care to prevent damage and injury.
This truss placement diagram is to be used only as an installation aid; it is not a structural diagram. These trusses are designed as individual building components to be incorporated into the building design at the the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing.
Professional advice should be sought regarding handling, installation, temporary and permanent bracing before erecting trusses. Temporary and permanent bracing is required during installation of trusses to prevent possible collapse.
For general guidance regarding bracing, consult "BCSI-06" available jointly from WTCA & TPI.
Premier Building Supply must be notified of any issues requiring a back charge prior to any work being done. Premier Building Supply reserves the right to use it's service staff in lieu of being back charged.

EVERSTEAD
SHOP DRAWINGS/SUBMITTAL REVIEW

SUBMITTAL WAS REVIEWED FOR DESIGN CONFORMITY AND GENERAL CONFORMANCE TO CONTRACT DOCUMENTS ONLY. THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING AND CORRELATING DIMENSIONS AT JOBSITE FOR TOLERANCE, CLEARANCE, QUANTITIES, FABRICATION, COORDINATION OF HIS OR HER WORK WITH OTHER TRADES, AND FULL COMPLIANCE WITH CONTRACT DOCUMENTS.

STATUS:
APPROVED
03/20/2023
REVIEWED BY:
BH
ENGINEER, EVERSTEAD