



## **FIRE DEPARTMENT**

**Prevention Division  
(816)969-1300**

### **PLANS REVIEW CONDITIONS**

Permit No:	PRCOM20225393	Date:	March 31, 2023
Project Title:	FIRE STATION #5	Applicant:	
Location:			
	801 SW M 150 HWY, LEES SUMMIT, MO 64082		AEGIS FIRE PROTECTION LLC
Type of Work:			11936 W 119TH ST #262
Occupancy Group:	MIX		OVERLAND PARK, KS 66213
Description:	NEW FIRE STATION		
Construction Type:	Type IIB (Unprotected)	Primary:	(913) 825-0343
Map Page:			

**Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.**

#### **Sprinkler Plan Review**

**Reviewed By: Jim Eden**

**Released for Construction**

1. 2018 IFC 901.2- Construction documents. The fire code official shall have the authority to require construction documents and calculations for all fire protection systems and to require permits be issued for the installation, rehabilitation or modification of any fire protection system. Construction documents for fire protection systems shall be submitted for review and approval prior to system installation.

Stamped plans received March 22, 2023.

2. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

Call (816) 969-1300 to schedule hydrostatic and flow tests.

**The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.**