

TABLE OF CONTENTS

PAGE NO.

UL ASSEMBLIES

UL ASSEMBLY L528	1-25
UL ASSEMBLY L569	1-13
UL ASSEMBLY N743.....	1-4
UL ASSEMBLY P556	1-9
UL ASSEMBLY P571	1-3
UL ASSEMBLY U301.....	1-7
UL ASSEMBLY U305.....	1-19
UL ASSEMBLY U309.....	1-12
UL ASSEMBLY U341.....	1-11
UL ASSEMBLY U351.....	1-4
UL ASSEMBLY U356.....	1-10
UL ASSEMBLY X528.....	1-4

DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS

NOT APPLICABLE

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 010005 – CONTRACT DOCUMENTS	010005-1 - 010005-1
SECTION 010010 – GENERAL CONDITIONS	010010-1 - 010010-1
SECTION 010020 – SUPPLEMENTRY GENERAL CCONDITIONS.....	010020-1 - 010020-3
SECTION 012500 – SUBSTITUTION PROCEDURES	012500-1 - 012500-4
SECTION 012600 – CONTRACT MODIFICATION PROCEDURES.....	012600-1 - 012600-3
SECTION 012900 – PAYMENT PROCEDURES	012900-1 - 012900-5
SECTION 013100 – PROJECT MANAGEMENT AND COORDINATION.....	013100-1 - 013100-9
SECTION 013200 – CONSTRUCTION PROGRESS DOCUMENTATION.....	013200-1 - 013200-5
SECTION 013300 – SUBMITTAL PROCEDURES.....	013300-1 - 013300-8
SECTION 014000 – QUALITY REQUIREMENTS	014000-1 - 040000-9
SECTION 014200 – REFERENCES	014200-1 - 014200-8
SECTION 014339 – MOCKUPS	014339-1 - 014339-4
SECTION 016000 – PRODUCT REQUIREMENTS	016000-1 - 016000-6
SECTION 017300 – EXECUTION.....	017300-1 - 017300-10
SECTION 017700 – CLOSEOUT PROCEDURES.....	017700-1 - 017700-5
SECTION 017823 – OPERATION AND MAINTENANCE DATA	017823-1 - 017823-7
SECTION 017839 – PROJECT RECORD DOCUMENTS.....	017839-1 - 017839-4

DIVISION 02 – EXISTING CONDITIONS

NOT APPLICABLE

DIVISION 03 - CONCRETE

SECTION 033000 – CAST-IN-PLACE CONCRETE	033000-1 - 033000-10
SECTION 033010 – UNDER-SLAB VAPOR BARRIER	033010-1 - 033010-3
SECTION 033816 – POST-TENSIONED CONCRETE	033816-1 - 033816-11
SECTION 035413 – GYPSUM CEMENT UNDERLAYMENT	035413-1 - 035413-3

DIVISION 04 - MASONRY

SECTION 042113 – BRICK MASONRY	042113-1 - 042113-9
SECTION 042200 – CONCRETE UNIT MASONRY	042200-1 - 042200-6
SECTION 047200 – CAST STONE	047200-1 - 047200-6

DIVISION 05 - METALS

SECTION 051200 – STRUCTURAL STEEL	051200-1 - 051200-8
SECTION 055000 – METAL FABRICATIONS.....	055000-1 - 055000-3
SECTION 055133 – ALTERNATING TREAD STEEL STAIRS	055133-1 - 055133-5
SECTION 055213 – PIPE AND TUBE RAILINGS.....	055230-1 - 055230-4
SECTION 057300 – DECORATIVE METAL RAILINGS.....	057300-1 - 057300-4
SECTION 057313 – GLAZED DECORATIVE METAL RAILINGS.....	057313-1 - 057313-4

DIVISION 06 – WOOD, PLASTICS AND COMPOSITES

SECTION 061000 – ROUGH CARPENTRY.....	061000-1 - 061000-3
SECTION 061753 – SHOP-FABRICATED WOOD TRUSSES.....	061753-1 - 061753-4
SECTION 062000 – FINISH CARPENTRY AND MILLWORK	062000-1 - 062000-3
SECTION 066400 – PLASTIC PANELING	066400-1 - 066400-2

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

SECTION 071326 – SHEET MEMBRANE WATERPROOFING	071326-1 - 071326-2
SECTION 071416 – COLD FLUID-APPLIED WATERPROOFING	071416-1 - 071416-3
SECTION 072100 – BUILDING INSULATION	072100-1 - 072100-2
SECTION 072500 – WEATHER BARRIER.....	072500-1 - 072500-4
SECTION 073113 – ASPHALT SHINGLES	073113-1 - 073113-3
SECTION 074243 – COMPOSITE WALL PANELS	074243-1 - 074243-7
SECTION 074642 – FIBER CEMENT LAP SIDING	074642-1 - 074642-5
SECTION 075423 – THERMOPLASTIC-POLYOLEFIN (TPO) ROOFING	075423-1 - 075423-7
SECTION 076200 – SHEET METAL AND FLASHING	076200-1 - 076200-4
SECTION 077200 – ROOF ACCESSORIES	077200-1 - 077200-3
SECTION 078446 – FIRE RESISTIVE JOINT SEALANTS.....	078446-1 - 078446-4
SECTION 079200 – JOINT SEALANTS.....	079200-1 - 079200-4
SECTION 079219 – ACOUSTICAL JOINT SEALANTS.....	079219-1 - 079219-2

DIVISION 08 - OPENINGS

SECTION 081113 – HOLLOW METAL DOORS AND FRAMES	081113-1 - 081113-5
SECTION 082000 – PEDESTRIAN DOORS.....	082000-1 - 082000-2
SECTION 083113 – ACCESS DOORS AND FRAMES	083113-1 - 083113-2
SECTION 083613 – GARAGE DOORS	083613-1 - 083613-1
SECTION 084133 – ALUMINUM ENTRANCES AND STOREFRONTS	084133-1 - 084133-6
SECTION 084226 – ALL-GLASS ENTRANCES	084226-1 - 084226-4
SECTION 085313 – VINYL WINDOWS	085313-1 - 085313-3
SECTION 087100 – DOOR HARDWARE	087100-1 - 087100-14
SECTION 088300 – MIRRORS	088300-1 - 088300-4

DIVISION 09 - FINISHES

SECTION 092900 – GYPSUM BOARD	092900-1 - 092900-5
-------------------------------------	---------------------

SECTION 093013 – CERAMIC TILING.....	093013-1 - 093013-6
	<u>PAGE NO.</u>

SECTION 096500 – VINYL PLANK FLOORING.....	096500-1 - 096500-2
SECTION 096513 – RESILIENT BASE AND ACCESSORIES.....	096513-1 - 096513-3
SECTION 096519 – RESILIENT TILE FLOORING.....	096519-1 - 096519-3
SECTION 096723 – RESINOUS FLOORING.....	096723-1 - 096723-4
SECTION 096816 – CARPETING.....	096816-1 - 096816-3
SECTION 099113 – EXTERIOR PAINTING.....	099113-1 - 099113-7
SECTION 099123 – INTERIOR PAINTING.....	099123-1 - 099123-6
SECTION 099646 – INTUMESCENT PAINTING.....	099646-1 - 099646-3

DIVISION 10 - SPECIALTIES

SECTION 101400 – SIGNAGE.....	101400-1 - 101400-2
SECTION 102800 – TOILET, BATH, AND CUSTODIAL ACCESSORIES.....	102800-1 - 102800-2
SECTION 102819 – SHOWER DOORS.....	102819-1 - 102819-2
SECTION 103100 – MANUFACTURED FIREPLACES.....	103100-1 - 103100-1
SECTION 104413 – FIRE EXTINGUISHER CABINETS.....	104413-1 - 104413-3
SECTION 104416 – FIRE EXTINGUISHERS.....	104416-1 - 104416-2
SECTION 105500 – POSTAL SPECIALTIES.....	105500-1 - 105500-1
SECTION 105700 – WIRE SHELVING.....	105700-1 - 105700-2

DIVISION 11 - EQUIPMENT

SECTION 113100 – APPLIANCES AND EQUIPMENT.....	113100-1 - 113100-3
--	---------------------

DIVISION 12 - FURNISHINGS

SECTION 122113 – DOOR AND WINDOW BLINDS.....	122113-1 - 122113-3
SECTION 123530 – CABINETS.....	123530-1 - 123530-3
SECTION 123661 – QUARTZ AGGLOMERATE COUNTERTOPS.....	123661-1 - 123661-2
SECTION 129300 – BICYCLE RACKS.....	129300-1 - 129300-2

DIVISION 13 - SPECIAL CONSTRUCTION

SECTION 132416 – SAUNAS.....	132416-1 - 132416-4
------------------------------	---------------------

DIVISION 14 - CONVEYING EQUIPMENT

SECTION 142100 – ELECTRIC TRACTION ELEVATORS.....	142400-1 - 142400-9
---	---------------------

DIVISION 21 – FIRE SUPPRESSION

SECTION 211300 - FIRE SUPPRESSION SYSTEMS.....	211300-1 - 211300-6
--	---------------------

DIVISION 22 – PLUMBING

SECTION 220500 - COMMON WORK RESULTS FOR PLUMBING.....	220500-1 - 220500-12
SECTION 220700 - PIPING AND EQUIPMENT INSULATION.....	220700-1 - 220700-3
SECTION 221100 - PLUMBING PIPING, EQUIP., AND ACCESSORIES.....	221100-1 - 221100-7
SECTION 224000 - PLUMBING FIXTURES.....	224000-1 - 224000-1

DIVISION 23 – HEATING, VENTILATING AND AIR CONDITIONING

SECTION 230500 - COMMON WORK RESULTS FOR MECH. SYSTEM	230500-1 - 230500-10
SECTION 230593 - TESTING & BALANCING	230593-1 - 230593-2
SECTION 230700 - HVAC INSULATION.....	230700-1 - 230700-4
SECTION 233100 - DUCTWORK	233100-1 - 233100-3
SECTION 233400 - FANS	233400-1 - 233400-1
SECTION 233700 - AIR INLETS AND OUTLETS.....	233700-1 - 233700-1
SECTION 237000 - SPLIT SYSTEMS.....	237000-1 - 237000-2

DIVISION 26 – ELECTRICAL

SECTION 260500 – COMMON WORK RESULTS FOR ELECTRICAL.....	260500-1 - 260500-10
SECTION 260519 – CONDUCTORS AND CABLES	260519-1 - 260519-2
SECTION 260526 – GROUNDING.....	260526-1 - 260526-2
SECTION 260533 – RACEWAYS AND BOXES.....	260533-1 - 260533-5
SECTION 262400 – PANELBOARDS AND SWITCHBOARDS.....	262400-1 - 262400-3
SECTION 262726 – SWITCHES, RECEPTACLES AND COVER PLATES.....	262726-1 - 262726-3
SECTION 262813 – OVERCURRENT PROTECTIVE DEVICES	262813-1 - 262813-1
SECTION 262816 – METER CENTER AND DISCONNECT SWITCHES.....	262816-1 - 262816-1
SECTION 265100 – LIGHTING	265100-1 - 265100-2

DIVISION 27 – COMMUNICATIONS

SECTION 271000 – TELECOMMUNICATIONS.....	271000-1 - 271000-12
--	----------------------

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

SECTION 282000 – ELECTRONIC SURVEILLANCE.....	282000-1 - 282000-13
SECTION 283100 – FIRE ALARM SYSTEMS	283100-1 - 283100-8
SECTION 284000 – ACCESS CONTROL SYSTEM.....	284000-1 - 284000-24
SECTION 284500 – ACCESS CONTROL SYSTEM.....	284500-1 - 284500-9

DIVISION 31 – EARTHWORK

SECTION 312113 – RADON MITIGATION	312113-1 - 312113-3
SECTION 313116 – TERMITE CONTROL	313116-1 - 313116-3

DIVISION 32 – EXTERIOR IMPROVEMENTS

SECTION 321813 – SYNTHETIC GRASS SURFACING	321813-1 - 321813-2
SECTION 323113 – CHAIN LINK FENCES AND GATES	323113-1 - 323113-4
SECTION 323119 – DECORATIVE METAL FENCES AND GATES	323119-1 - 323119-3

DIVISION 33 – UTILITIES

SECTION 334600 – SUBDRAINAGE.....	334600-1 - 334600-3
-----------------------------------	---------------------

END OF TABLE OF CONTENTS

SECTION 074243 - COMPOSITE WALL PANELS

PART 1 - GENERAL

1.1 SECTION INCLUDES

- A. Exterior, panelized fiber cement cladding system and accessories to complete a drained and back-ventilated rainscreen.

1.2 RELATED SECTIONS

- A. Section 061000 – Rough Carpentry
- B. Section 072100 – Building Insulation
- C. Section 072500 – Weather Barriers
- D. Section 076000 – Sheet Metal and Flashing
- E. Section 079200 – Joint Sealants

1.3 REFERENCES

- A. American Architectural Manufacturers Association (AAMA):
 - 1. AAMA 509-14 – Voluntary Test and Classification Method of Drained and Back Ventilated Rain Screen Wall Cladding Systems
- B. ASTM International (ASTM):
 - 1. ASTM C 518 – Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus.
 - 2. ASTM C 1185 - Standard Test Methods for Sampling and Testing Non-Asbestos Fiber Cement.
 - 3. ASTM C 1186 – Standard Specification for Flat Fiber-Cement Sheets
 - 4. ASTM E-84 – Standard Test for Surface Burning Characteristics of Building Materials.
 - 5. ASTM E 119 – Standard Test Methods for Fire Tests of Building Construction and Materials.
 - 6. ASTM E 228 – Standard Test Method for Linear Thermal Expansion of Solid Materials with a Vitreous Silica Dilatometer.
 - 7. ASTM E 330 – Standard Test Method for Structural Performance of Exterior Windows, Curtain Walls, and Doors by Uniform Static Air Pressure Difference.
 - 8. ASTM E 331 – Standard Test Method for Water Penetration of Exterior Windows, Curtain Walls, and Doors by Uniform Static Air Pressure Difference.
- C. National Fire Protection Association (NFPA):
 - 1. NFPA 285 – Fire Test Method for Exterior Wall Assemblies Containing Combustible Material.
 - 2. NFPA 268 – Ignition Resistance of Exterior Wall Assemblies.

1.4 SUBMITTALS

- A. Product Data: Submit manufacturer's product description, storage and handling requirements, and installation instructions.
- B. Product Test Reports and Code Compliance: Documents demonstrating product compliance with local building code, such as test reports or Evaluation Reports from qualified, independent testing agencies.
- C. Manufacturer's Details: Submit drawings, including plans, sections, showing installation details that demonstrate product dimensions, edge/termination conditions/treatments, compression and control joints, corners, openings, and penetrations.
- D. Samples: Submit samples of each product type proposed for use.

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications:
 - 1. All fiber cement panels specified in this section must be supplied by a manufacturer with a minimum of 10 years of experience in fabricating and supplying fiber cement cladding systems.
 - a. Products covered under this section are to be manufactured in an ISO 9001 certified facility.
 - 2. Provide technical and design support as needed regarding installation requirements and warranty compliance provisions.
- B. Installer Qualifications: All products listed in this section are to be installed by a single installer trained by the manufacturer or representative.
- C. Mock-Up Wall: Provide a mock-up wall as an evaluation tool for product and installation workmanship.
- D. Pre-Installation Meetings: Prior to beginning installation, conduct conference to verify and discuss substrate conditions, manufacturer's installation instructions and warranty requirements, and project requirements.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Panels must be stored flat and kept dry before installation. A waterproof cover over panels and accessories should be used at all times prior to installation. Do not stack pallets more than two high. Refer to the information included on each pallet.
- B. If panels are exposed to water or water vapor prior to installation, allow them to completely dry before installing. Failure to do so may result in panel shrinkage at ship lap joints, and such action may void warranty.
- C. Panels MUST be carried on edge. Do not carry or lift panels flat. Improper handling may cause cracking or panel damage.
- D. Direct contact between the panels and the ground should be avoided at all times. It is necessary to keep panels clean during the installation process.

1.7 WARRANTY

- A. Provide manufacturer's 15-year warranty against manufactured defects in fiber cement panels. Additional 5-year extension available when refinished in year 14-15.
- B. Provide manufacturer's 15-year warranty against manufactured defects in panel finish.
- C. Warranty provides for the original purchaser. See warranty for detailed information on terms, conditions and limitations.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturer: Nichiha Corporation, 18-19 Nishiki 2-chome Naka-ku, Nagoya, Aichi 460-8610, Japan.
- B. Acceptable Manufacturer's Representative: Nichiha USA, Inc., 6465 E. Johns Crossing, Suite 250, Johns Creek, GA 30097. Toll free: 1.866.424.4421, Office: 770.805.9466, Fax: 770.805.9467, www.nichiha.com.

1. Basis of Design Product: Nichiha VintageWood.

- a. Profile Colors: Spruce, subject to Owner approval.
- b. Profiles: Wood plank texture with three, 3/8" grooves running lengthwise, spaced 5-5/8" apart.
- c. Accessory/Component Options:
 - 1) Manufactured Corners with 3-1/2" returns for each profile color.
 - 2) Aluminum trim options: Corner Key, Open Outside Corner, H-Mold, J-Mold, Compression Joint, Inside Corner
 - 1. Finish: Bark, Cedar, Clear Anodized, or Primed.
 - 3) Essential Flashing System: Starter, Overhang.
 - a) Finish: Matte black, subject to Owner approval.
- d. Dimensions:
 - 1) AWP-1818: 455mm (17-7/8") (h) x 1,818 mm (71-9/16") (l).
 - 2) AWP-3030: 455mm (17-7/8") (h) x 3,030 mm (119-5/16") (l).
- e. Panel Thickness: 16 mm (5/8").
- f. Weight: AWP-1818: 35.27 lbs. per panel, AWP-3030: 57.32 lbs. per panel.
- g. Coverage: 8.88 sq. ft. per panel (1818), 14.81 sq. ft. per panel (3030).
- h. Factory sealed on six [6] sides.

- C. Requests for substitutions will be considered in accordance with the provisions of Section 016000.

2.2 MATERIALS

- A. Fiber cement panels manufactured from a pressed, stamped, and autoclaved mix of Portland cement, fly ash, silica, recycled rejects, and wood fiber bundles.
- B. Panel surface pre-finished and machine applied.
- C. Panels profiled along 3030mm edges so that the long joints between the installed panels are ship-lapped.
- D. Factory-applied sealant gasket added to top panel edge; all 3030mm edge joints contain a factory sealant.

2.3 PERFORMANCE REQUIREMENTS

- A. Fiber Cement Cladding – Must comply with ASTM C-1186, Type A, Grade II requirements:
 - 1. Wet Flexural Strength: Result: 1418 psi, Lower Limit: 1015 psi.
 - 2. Water Tightness: No water droplets observed on any specimen.
 - 3. Freeze-thaw: No damage or defects observed.
 - 4. Warm Water: No evidence of cracking, delamination, swelling, or other defects observed.
 - 5. Heat-Rain: No crazing, cracking, or other deleterious effects, surface or joint changes observed in any specimen.
- B. Mean Coefficient of Linear Thermal Expansion (ASTM E-228): Max 1.0×10^{-5} in./in. F.
- C. Surface Burning (CAN-ULC S102/ASTM E-84): Flame Spread: 0, Smoke Developed: 0.
- D. Wind Load (ASTM E-330): Contact manufacturer for ultimate test pressure data corresponding to framing type, dimensions, fastener type, and attachment clips. Project engineer(s) must determine Zone 4 and 5 design pressures based on project specifics.
 - 1. Minimum lateral deflection: $L/120$.
- E. Water Penetration (ASTM E-331): No water leakage observed into wall cavity.
- F. Steady-State Heat Flux and Thermal Transmission Properties Test (ASTM C-518): 16mm thick panel thermal resistance R Value of 0.47.
- G. Fire Resistant (ASTM E-119): The wall assembly must successfully endure 60-minute fire exposure without developing excessive unexposed surface temperature or allowing flaming on the unexposed side of the assembly.
- H. Ignition Resistance (NFPA 268): No sustained flaming of panels, assembly when subjected to a minimum radiant heat flux of $12.5 \text{ kW/m}^2 \pm 5\%$ in the presence of a pilot ignition source for a 20-minute period.
- I. Drained and Back Ventilated Rainscreen (AAMA 509-14): System classifications: W1, V1.

2.4 INSTALLATION COMPONENTS

- A. Ultimate Clip System:
 - 1. Starter Track:

- a. Horizontal Panel Installations - FA 700 – 3,030mm (l) galvalume coated steel.
 - b. Vertical Panel Installations (AWP-3030 only) – FA 710T – 3,030mm (l) galvalume coated steel.
- 2. Panel Clips: JEL 778 “Ultimate Clip II” (10mm rainscreen for 16mm AWP) – Zinc-Aluminum-Magnesium alloy coated steel.
 - a. Joint Tab Attachments (included) – used at all AWP-1818 panel to panel vertical joints, NOT used with AWP-3030 installations.
- 3. Corner Clips: JE 777C (10mm rainscreen for 5/8” AWP Manufactured Corners) -- Zinc-Aluminum-Magnesium alloy coated steel.
- 4. Single Flange Sealant Backer – FHK 1015 R (10mm) – 6.5’ (l) fluorine coated galvalume.
- 5. Double Flange Sealant Backer – FH 1015 R (10mm) – 10’ (l) fluorine coated galvalume.
- 6. Corrugated Spacer – FS 1005 (5mm), FS 1010 (10mm) – 4’ (l).
- B. Aluminum Trim: Paint primed trim as specified in finish schedule.
- C. Essential Flashing System:
 - 1. Starter – main segments (3,030mm), inside corners, outside corners
 - 2. Overhang – main segments (3,030mm), inside corners, outside corners, joint clips
- D. Fasteners: Corrosion resistant fasteners, such as hot-dipped galvanized screws appropriate to local building codes and practices must be used. Use Stainless Steel fasteners in high humidity and high-moisture regions. The panel manufacturer is not liable for corrosion resistance of fasteners. Do not use aluminum fasteners, staples or fasteners that are not rated or designed for intended use. See manufacturer’s instructions for appropriate fasteners for construction method used.
- E. Flashing: Flash all areas specified in manufacturer’s instructions. Do not use raw aluminum flashing. Flashing must be galvanized, anodized, or PVC coated.
- F. Sealant: Sealant shall comply with ASTM C920, Class 35.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verification of Conditions:
 - 1. Fiber cement panels can be installed over braced wood, steel studs and sheathing including plywood, OSB, plastic foam (1” or less) or fiberboard sheathing. Fiber cement panels can also be installed over Structural Insulated Panels (SIP’s), Concrete Masonry Units (CMU’s) and Concrete Block Structures (CBS’s) with furring strips, and Pre-Engineered Metal Construction. Insulated Concrete Forms (ICFs) require added measures. Consult with Nichiha Technical Services.
 - 2. Allowable stud spacing: 16” o.c. maximum.
 - 3. A weather resistive barrier is required when installing fiber cement panels. Use an approved weather resistive barrier (WRB) as defined by the 2012 IBC. Refer to local building codes.

4. Appropriate metal flashing should be used to prevent moisture penetration around all doors, windows, wall bottoms, material transitions and penetrations. Refer to local building codes for best practices.
 - B. Examine site to ensure substrate conditions are within alignment tolerances for proper installation.
 - C. Do not begin installation until unacceptable conditions have been corrected.
 - D. Do not install panels or components that appear to be damaged or defective. Do not install wet panels.
- 3.2 TOLERANCE
- A. Wall surface plane must be plumb and level within +/- ¼ inch in 20 feet in any direction.
 1. One layer of Nichiha 5mm (~3/16") Spacer may be used as shim.
- 3.3 INSTALLATION
- A. General: Install products in accordance with the latest installation guidelines of the manufacturer and all applicable building codes and other laws, rules, regulations and ordinances. Review all manufacturer installation, maintenance instructions, and other applicable documents before installation.
 1. Consult with your local dealer or Nichiha Technical Department before installing any Nichiha fiber cement product on a building higher than 45 feet or three stories or for conditions not matching prescribed standard installation guide requirements and methods.
 - a. Technical Design Review (TDR) process is available to evaluate project feasibility.
 2. Vertical Control/Expansion Joints are required with AWP-1818, for walls wider than 30 feet, within 2-12 feet of outside corners finished with metal trim *and* approximately every 30 feet thereafter.
 - a. Vertical Control/Expansion Joints are required at each AWP-3030 vertical joint, or H-Mold trim may be used instead.
 3. Horizontal/Compression Joints are required for multi-story installations of AWP. Locate joints at floor lines. Joints are flashed minimum ½" breaks. Do not caulk. Refer to installation guide(s).
 - a. Wood framed buildings of three or more floors require a compression joint at each floor.
 - b. Steel framed buildings (including reinforced concrete core with LGMF exterior walls) of more than three floors (or 45 feet) require a compression joint every 25 feet at a floor line.
 - B. Panel Cutting
 1. Always cut fiber cement panels outside or in a well-ventilated area. Do not cut the products in an enclosed area.

2. Always wear safety glasses and NIOSH/OSHA approved respirator whenever cutting, drilling, sawing, sanding or abrading the products. Refer to manufacturer SDS for more information.
3. Use a dust-reducing circular saw with a diamond-tipped or carbide-tipped blade.
 - a. Recommended circular saw: Makita 7-1/4" Circular Saw with Dust Collector (#5057KB).
 - b. Recommended blade: Tenryu Board-Pro Plus PCD Blade (#BP-18505).
 - c. Shears (electric or pneumatic) or jig saw can be used for complicated cuttings, such as service openings, curves, radii and scrollwork.
4. Silica Dust Warning: Fiber cement products may contain some amounts of crystalline silica, a naturally occurring, potentially hazardous mineral when airborne in dust form. Consult product SDS or visit <https://www.osha.gov/dsg/topics/silicacrystalline/>.
5. Immediately clean dust from cut panels as it may bind to the finish.

3.4 CLEANING AND MAINTENANCE

- A. Review manufacturer guidelines for detailed care instructions.

END OF SECTION 074243