


FILEPATH: C:\Users\ross\OneDrive - Scherdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_jrsZHKC2.rvt
DATE: 5/23/2023 4:19:16 PM
DRAWN BY: Author



MATERIAL LEGEND

PLAN OR SECTION		RIGID INSULATION
ACOUSTIC TILE (SECTION)		SAND, GRAVEL, PLASTER, DRYWALL, CUT STONE, GROUT
BATT INSULATION		TILE (LARGE SCALE)
BRICK		WOOD BLOCKING
CARPET		WOOD MEMBER (CONTINUOUS)
CONCRETE		WOOD STUDS, PARALAM, FINISHED
CONCRETE MASONRY UNITS		
CONCRETE, PLASTER CUT STONE, STUCCO		
EARTH COMPACTED/DISTURBED		
METAL		
METAL STUDS		
PLYWOOD (LARGE SIZE)		

CORE & SHELL BUILDING STREETS OF WEST PRYOR LOT 5 LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

GRAPHIC SYMBOLS

ELEVATION TAG	B3	BEARING ELEVATION MARK	EL - FLOOR
WALL SECTION TAG	B3	MATCHLINE	A-101 / 1
DETAIL CALLOUT	A2	DESCRIPTIVE ARROW	NEW EXISTING
PARTITION TYPE TAG	P2	CENTERLINE MARK	
WINDOW TAG	11	SPOT ELEVATION	
DOOR TAG	101B	DEMOLITION MARK	
ROOM TAG	101	GENERAL NOTE MARK	
		NEW CONSTRUCTION MARK	
		REVISION MARK	
		EQUIPMENT TAG	

CODE SUMMARY

PROJECT SCOPE:

CORE & SHELL DOCUMENTS. DRAWINGS FOR TENANT IMPROVEMENT WILL BE ISSUED A SEPARATE PERMIT AND PROVIDED BY OTHERS.

JURISDICTIONAL BUILDING CODES:

INTERNATIONAL BUILDING CODE	2018
INTERNATIONAL MECHANICAL CODE	2018
NATIONAL ELECTRICAL CODE	2017
INTERNATIONAL PLUMBING CODE	2018
INTERNATIONAL FIRE CODE	2018
INTERNATIONAL FUEL GAS CODE	2018

CONSTRUCTION INFORMATION:

BUILDING TYPE:	NEW CONSTRUCTION
OCCUPANCY TYPES:	M (MERCANTILE)
CONSTRUCTION TYPE:	V-B (NON-SPRINKLERED)
ALLOWABLE HEIGHT:	40 FT
ACTUAL HEIGHT:	26 FT
ALLOWABLE STORIES:	1
ACTUAL STORIES:	1
GROSS BUILDING AREA:	5,800 SF

ALLOWABLE FLOOR AREA:

ALLOWABLE FLOOR AREA (M):	9,000 SF
*FRONTAGE INCREASE N/A DUE TO ACTUAL AREA LESS THAN ALLOWABLE FLOOR AREA	

GROSS BUILDING AREA:

TENANT A & C:	4,821 SF
TENANT B:	890 SF
TOTAL GROSS AREA:	5,711 SF

OCCUPANT LOAD CALCS:

TENANT B (M): IBC TABLE 1004.5	890 SF
TOTAL NET SF	80 GROSS
MERCANTILE	15 OCC

EXITS REQUIRED:

TENANT A (M): IBC TABLE 1006.2.1	1 EXIT
EXITS REQUIRED	2 EXITS
EXITS PROVIDED	

TENANT B (M): IBC TABLE 1006.2.1	1 EXIT
EXITS REQUIRED	1 EXITS
EXITS PROVIDED	

TENANT C (M): IBC TABLE 1006.2.1	1 EXIT
EXITS REQUIRED	2 EXITS
EXITS PROVIDED	

STRUCTURAL FIRE PROTECTION (IBC TABLE 601)

PRIMARY STRUCTURAL FRAME	(I) HOUR
EXTERIOR BEARING WALLS	(I) HOUR
INTERIOR BEARING WALLS	(I) HOUR
EXTERIOR NON-BEARING WALLS & PARTITIONS	N/A
INTERIOR NON-BEARING WALLS & PARTITIONS	(I) HOUR
STRUCTURAL FRAME	(I) HOUR
FLOOR CONSTRUCTION	(I) HOUR
ROOF CONSTRUCTION	(I) HOUR

STRUCTURAL FIRE PROTECTION (IBC TABLE 601)

1. AUTOMATIC SPRINKLER SYSTEM (NO)
2. EXIT LIGHTING PROVIDED

DESIGN TEAM

ARCHITECTURAL DESIGN

SCHWERDT DESIGN GROUP
2231 SW WANAMAKER RD SUITE 303
TOPEKA, KANSAS 66614

CONTACT: MICHAEL HAMPTON & ROSS SIEGLE
PHONE: 785-273-7540
FAX: 785-273-7579
E-MAIL: MKH@SDGARCH.COM
RJS@SDGARCH.COM

MECHANICAL & ELECTRICAL DESIGN

PKMR ENGINEERS
13300 WEST 98TH STREET
LENEKA, KANSAS, 66215

CONTACT: BRYAN LEINWETTER
PHONE: 913-492-2400
E-MAIL: BRYAN.LEINWETTER@PKMRENG.COM

STRUCTURAL DESIGN

CERTUS STRUCTURAL ENGINEERS
900 S KANSAS AVENUE SUITE 400
TOPEKA, KANSAS, 66612

CONTACT: AARON SCOTT
PHONE: 785-291-0400
E-MAIL: AARON.SCOTT@CERTUSSE.COM

CIVIL DESIGN

SM ENGINEERING
919 W STEWART ROAD
COLUMBIA, MISSOURI 65203

CONTACT: SAM MALINOWSKI, PE
PHONE: 785-341-8747
E-MAIL: SMCIVILENGR@GMAIL.COM

SHEET INDEX

GENERAL

G-001 COVER SHEET

CIVIL

- C-1 SITE IMPROVEMENT PLAN
- C-2 TOPOGRAPHIC SURVEY
- C-3 DEMOLITION SHEET
- C-4 SITE PLAN
- C-5 UTILITY
- C-6 GRADING
- C-7 ADA RAMPS
- C-8 EROSION CONTROL
- C-9 EROSION DETAILS
- C-10 DETAILS
- C-11 DETAILS
- C-12 DETAILS
- C-13 LANDSCAPE

ARCHITECTURAL

- A-100 SITE PLAN
- A-101 FIRST FLOOR PLAN
- A-102 ROOF PLAN
- A-201 EXTERIOR ELEVATIONS
- A-301 WALL SECTIONS
- A-302 WALL SECTIONS
- A-303 WALL SECTIONS
- A-304 WALL SECTIONS
- A-401 ENLARGED RESTROOM PLAN
- A-501 BUILDING DETAILS
- A-502 BUILDING DETAILS
- A-601 DOOR / FRAME SCHEDULE & DETAILS

STRUCTURAL

- S-001 GENERAL NOTES
- S-101 FOUNDATION PLAN
- S-102 WALL FRAMING PLAN
- S-103 ROOF FRAMING PLAN
- S-201 FRAMING ISOMETRIC
- S-301 CONCRETE DETAILS & SECTIONS
- S-601 FRAMING DETAILS & SECTIONS
- S-602 FRAMING DETAILS & SECTIONS
- S-603 FRAMING DETAILS & SECTIONS

MEP

- ME-101 MEP SPECIFICATIONS
- ME-201 PHOTOMETRIC PLAN
- ME-202 SITE MEP PLAN

MECHANICAL

- M-101 PLUMBING FLOOR PLAN
- M-201 HVAC FLOOR PLAN

ELECTRICAL

- E-101 POWER FLOOR PLAN
- E-201 LIGHTING FLOOR PLAN

CODE PLAN LEGEND


2-HR SEPARATION	•••••
EXIT	▲
NOTE:	2-HR SEPARATION WALL WILL BE CONSTRUCTED AS A FIRE BARRIER, UL #423, EXTENDING FROM FOUNDATION TO UNDERSIDE OF ROOF SHEATHING.

EGRESS LOAD TAGS

DOOR / OPENING	1200 / 24"
OCCUPANT LOAD / EGRESS WIDTH REQ'D	34"

CODE PLAN ROOM TAG

ROOM	ROOM NAME
100	OCCUPANCY LOAD
1000 SF	ROOM AREA (SQUARE FEET)



A3 CODE PLAN
SCALE: 1/16" = 1'-0"



SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING STREETS OF WEST PRYOR LOT 5 LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES
PROGRESS PRINT ONLY

SHEET TITLE
COVER SHEET

PROJECT NUMBER
230117

SHEET NUMBER
G-001

STREETS OF WEST PRYOR

Electric Service
Every
Nathan Michael
913-347-4310
Nathan.michael@evergy.com

Gas Service
Spire
Katie Darnell
816-969-2247
Katie.darnell@spireenergy.com

Water/Sanitary Sewer
Water Utilities Department
1200 SE Hamblen Road
Lee's Summit, Mo 64081
Jeff Thorn
816-969-1900
jeff.thorn@cityofls.net

Communication Service
AT&T Carrie Cilke
816-703-4386
cc3527@att.com

Time Warner Cable
Steve Baxter
913-643-1928
steve.baxter@charter.com

Comcast
Ryan Alkire
816-795-2218
ryan.alkire@cable.comcast.com

Google Fiber
Becky Davis
913-725-8745
rebeccadavis@google.com



THE UNDERGROUND UTILITIES SHOWN HEREON ARE FROM FIELD SURVEY INFORMATION OF ONE-CALL LOCATED UTILITIES, FIELD SURVEY INFORMATION OF ABOVE GROUND OBSERVABLE EVIDENCE, AND/OR THE SCALING AND PLOTTING OF EXISTING UTILITY MAPS AND DRAWINGS AVAILABLE TO THE SURVEYOR AT THE TIME OF SURVEY. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. FURTHERMORE, THE SURVEYOR DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES BY EXCAVATION UNLESS OTHERWISE NOTED ON THIS SURVEY.

IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICE, THE CONTRACTOR WILL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.

THE DESIGNS REPRESENTED IN THESE PLANS ARE IN ACCORDANCE WITH ESTABLISHED PRACTICES OF CIVIL ENGINEERING FOR THE DESIGN FUNCTIONS AND USES INTENDED BY THE OWNER AT THIS TIME. HOWEVER, NEITHER SM ENGINEERING NOR ITS PERSONNEL CAN OR DO WARRANTY THESE DESIGNS OR PLANS AS CONSTRUCTED, EXCEPT IN THE SPECIFIC CASES WHERE SM ENGINEERING PERSONNEL INSPECT AND CONTROL THE PHYSICAL CONSTRUCTION ON A CONTEMPORARY BASIS AT THE SITE.

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH PROPOSED IMPROVEMENTS SHOWN ON THE PLANS. THE CONTRACTOR SHALL EXPOSE EXISTING UTILITIES AT LOCATIONS OF POSSIBLE CONFLICTS PRIOR TO ANY CONSTRUCTION.



LOCATION MAP

LEGAL DESCRIPTION:
LOT 5 STREET OF WEST PRYOR
LEE'S SUMMIT, MO, JACKSON COUNTY MISSOURI

BENCHMARKS:
#1 CHISELED "SQUARE" ON TOP OF CURB POINT OF INTERSECTION OF WEST PARK PARKING LOT AT EAST DRIVE ENTRANCE
ELEVATION 985.05

#2 CHISELED "SQUARE" ON NORTHWEST CORNER AREA INLET, 25' EAST OF CURB LINE AND ON-LINE WITH SOUTH CURB OF LOWENSTEIN DRIVE AT 90° BEND IN ROAD
ELEVATION 971.06

FLOODPLAIN NOTE:
SUBJECT PROPERTY IS SHOWN TO BE LOCATED IN "OTHER AREAS ZONE X" ON THE FLOOD INSURANCE RATE MAP FOR JACKSON COUNTY, MISSOURI AND INCORPORATED AREAS. COMMUNITY PANEL NO. 29095C0416G, REVISED JANUARY 20, 2017. "OTHER AREAS ZONE X" IS DEFINED AS "AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN". LOCATION DETERMINED BY A SCALED GRAPHICAL PLOT OF THE FLOOD INSURANCE RATE MAP.

NOTE:
THERE ARE NO GAS/OIL WELLS ON SITE
PER ALTA SURVEY

INDEX OF SHEETS

- C-1 COVER SHEET
- C-2 EXISTING CONDITIONS
- C-3 DEMOLITION PLAN
- C-4 SITE PLAN
- C-5 UTILITY PLAN
- C-6 GRADING PLAN
- C-7 ADA RAMPS
- C-8 EROSION CONTROL
- C-9 EROSION CONTROL DETAILS
- C-10 DETAILS
- C-11 DETAILS
- C-12 DETAILS
- C-13 LANDSCAPE PLAN

DEVELOPER

SWP III, LLC
C/O DRAKE DEVELOPMENT, LLC
7200 W 132nd ST, SUITE 150
OVERLAND PARK, KS 66213
913-662-2630

ENGINEER

SM ENGINEERING
SAM MALINOWSKY
5507 HIGH MEADOW CIRCLE
MANHATTAN KANSAS, 66503
SMCIVILENGR@GMAIL.COM
785.341.9747

SURVEYOR

ENGINEERING SOLUTIONS, LLC
50 SE 30TH STREET
LEE'S SUMMIT, MO 64082
P:(816) 623-9888



SAMUEL D. MALINOWSKY
PROFESSIONAL ENGINEER

SM Engineering
SME
5507 High Meadow Circle
Manhattan Kansas, 66503
smcivilengr@gmail.com
785.341.9747



Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineer is prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions and dimensions is required.

Revisions

STREETS OF W. PRYOR
LOT 5
LEES SUMMIT, MO

shee
C1.0
Civil
Site Improvement PL
permit
3 MAY 2023

Topographic Survey
Streets of West Pryor Lots 4 & 5
Section 35, Township 48, Range 32
Lee's Summit, Jackson County, Missouri



LEGEND

These standard symbols will be found in the drawing.

- Set 1/2" Rebar & Cap
- ⊙ Found Survey Monument (As Noted)

PROPERTY DESCRIPTION

All of Lots 4 and 5 of Streets of West Pryor Lots 1 thru 14, Tracts "A", "B", "C", & "D"

SURVEYOR'S GENERAL NOTES:

- This survey is based upon the following information provided by the client or researched by this surveyor.
(A) Final Plat of Streets of West Pryor Lots 1 thru 14, Tracts "A", "B", "C", & "D", Recorded as Document No. 2019E0032538-2.
- This survey meets or exceeds the accuracy standards of a (SUBURBAN) Property Boundary Survey as defined by the Missouri Standards for Property Boundary Surveys.
- No Title report was furnished by the client.
- Bearings shown hereon are based upon bearings described in the Final Plat of Streets of West Pryor Lots 1 thru 14, Tracts "A", "B", "C", & "D", Recorded as Document No. 2019E0032538-2.
- This company assumes no responsibility in the location of existing utilities within the subject premises. This is an above-ground survey. The underground utilities, if shown, are based on information provided by the various utility companies and these locations should be considered approximate. There may be additional underground utilities not shown on this drawing.
- Subsurface and environmental conditions were not surveyed or examined or considered as a part of this survey. No evidence or statement is made concerning the existence or underground or overhead conditions, containers or facilities that may affect the use or development of this property. No attempt has been made to obtain or show data concerning existence, size, depth, conditions, capacity or location of any utility existing on the site, whether private, municipal or public owned.
- This property is located outside the 100 year flood plain, zone "X" as shown on the Firm panel 29095C0416G, dated January 20, 2017.

SURVEYOR'S CERTIFICATION:

I HEREBY CERTIFY THAT I HAVE MADE A SURVEY OF THE PREMISES DESCRIBED HEREIN WHICH MEETS OR EXCEEDS THE CURRENT "MISSOURI MINIMUM STANDARDS FOR PROPERTY BOUNDARY SURVEYS" AS JOINTLY ESTABLISHED BY THE MISSOURI BOARD FOR ARCHITECTS, PROFESSIONAL ENGINEERS, PROFESSIONAL LAND SURVEYORS, AND LANDSCAPE ARCHITECTS AND THE MISSOURI DEPARTMENT OF NATURAL RESOURCES, DIVISION OF GEOLOGICAL SURVEY AND RESOURCE ASSESSMENT AND THAT THE RESULTS OF SAID SURVEY ARE REPRESENTED ON THIS PLAT TO THE BEST OF MY PROFESSIONAL KNOWLEDGE AND BELIEF.

MATTHEW J. SCHLICHT, MOPLS 2012000102
ENGINEERING SOLUTIONS, LLC., MO CORP LS 2005008319-D

REVISIONS


DATE	

Topographic Survey
Streets of West Pryor Lots 4 & 5
Section 35, Township 48, Range 32
Lee's Summit, Jackson County, Missouri

Topographic Survey

SHEET	SECTION	TOWNSHIP	RANGE	COUNTY	JOB NO.
1 OF 1	35	48	32	JACKSON	SWP Lot 4

PROFESSIONAL SEAL



SM Engineering
SM E
5507 High Meadow Circle
Manhattan Kansas, 66503
smcivilengr@gmail.com
785.341.9747


Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineer is prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.

6

Revisions

STREETS OF W. PRYOR
LOT 5
LEES SUMMITT, MO.

sheet
C3.0
Civil
DEMOLITION PLAN
permit
3 MAY 2023



SITE DATA

TOTAL SITE	0.753ac (32,820sf)
TOTAL BUILDING	6,000sf
TOTAL PERVIOUS AREA	26,820sf
TOTAL PARKING	41 (6.83 STALLS / 1000sf)

CONSTRUCTION NOTES:

- COORDINATE START-UP AND ALL CONSTRUCTION ACTIVITIES WITH OWNER.
- CONSTRUCTION METHODS AND MATERIALS NOT SPECIFIED IN THESE PLANS ARE TO MEET OR EXCEED THE STANDARD SPECIFICATIONS.
- ALL CONSTRUCTION WORK AND UTILITY WORK OUTSIDE OF PROPERTY BOUNDARIES SHALL BE PERFORMED IN COOPERATION WITH AND IN ACCORDANCE WITH REGULATIONS OF THE AUTHORITIES CONCERNED.
- PUBLIC CONVENIENCE AND SAFETY: THE CONTRACTOR SHALL CONDUCT THE WORK IN A MANNER THAT WILL INSURE, AS FAR AS PRACTICABLE, THE LEAST OBSTRUCTION TO TRAFFIC, AND SHALL PROVIDE FOR TI-1E CONVENIENCE AND SAFETY OF THE GENERAL PUBLIC AND RESIDENTS ALONG AND ADJACENT TO STREETS IN THE CONSTRUCTION AREA.
- ALL DIMENSIONS SHOWN ARE TO THE BACK OF CURB UNLESS OTHERWISE NOTED.
- ACCESSIBLE STALLS SHOWN WITH A "VAN" SHALL BE 16'-0" MIN. AND SHALL HAVE A SIGN DESIGNATING "VAN-ACCESSIBLE". SEE DETAIL102.


NOTE:

- CONTRACTOR SHALL REFER TO ARCHITECTURAL PLANS FOR EXACT LOCATIONS AND DIMENSIONS OF ENTRANCE. SLOPED PAVING, EXIT PORCHES AND RAMPS, PRECISE BUILDING DIMENSIONS AND EXACT BUILDING UTILITY ENTRANCE LOCATIONS.
- THESE PLANS HAVE NOT BEEN VERIFIED WITH FINAL ARCHITECTURAL CONTRACT DRAWINGS. CONTRACTOR SHALL VERIFY AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES. CONTRACTOR IS FULLY RESPONSIBLE FOR REVIEW AND COORDINATION OF ALL DRAWINGS AND CONTRACTOR DOCUMENTS.
- ALL DIMENSIONS ARE PERPENDICULAR TO PROPERTY LINE.
- ACTUAL SIGN LOCATIONS TO BE COORDINATED WITH CONSTRUCTION MANAGER.

- SEE DETAIL SHEET FOR THE FOLLOWING DETAILS:
- PK1 96" ACCESSIBLE & VAN ACCESSIBLE SPACE STRIPING
 - PK2 ACCESSIBLE SIGN (MOUNTED TO BUILDING)
 - CG1 CURB AND GUTTER
 - C1 STRAIGHT BACK CURB
 - PV1 REGULAR DUTY PAVEMENT
 - PV2 HEAVY DUTY ASPHALT PAVEMENT
 - PV3 HEAVY DUTY CONCRETE PAVEMENT
 - CW1 CURB WALK AT BUILDING
 - CW2 SIDEWALK
 - ADA-1 HANDICAP RAMP SEE GEN-3A DETAIL
 - LP LIGHT POLE BASE

NOTES:


- 8A DOOR (SEE ARCH. PLANS)
- 12K YELLOW PARKING LOT STRIPING (SHERWIN-WILLIAMS TM 2160 LEAD FREE OR APPROVED EQUAL)
- 12N 4" YELLOW STRIPES 3'-0" O.C
- 11 PAINT CURB RED "NO PARKING FIRE LANE"




Revisions

6

STREETS OF W. PRYOR
LOT 5
LEES SUMMITT, MO.





UTILITY NOTES:

1. ALL UTILITY AND STORM SEWER TRENCHES CONSTRUCTED UNDER AREAS THAT RECEIVE PAVING SHALL BE BACKFILLED TO 18 INCHES ABOVE THE TOP OF THE PIPE WITH SELECT GRANULAR MATERIAL PLACED ON EIGHT-INCH LIFTS, AND COMPACTED TO 95% MODIFIED PROCTOR DENSITY.
2. CONTRACTOR SHALL NOT OPEN, TURN OFF, INTERFERE WITH, OR ATTACH ANY PIPE OR HOSE TO OR TAP ANY WATER MAIN BELONGING TO THE CITY UNLESS DULY AUTHORIZED TO DO SO BY THE CITY. ANY ADVERSE CONSEQUENCE OF ANY SCHEDULED OR UNSCHEDULED DISRUPTIONS OF SERVICE TO THE PUBLIC ARE TO BE THE LIABILITY OF THE CONTRACTOR. SM ENGINEERING AND OWNER ARE TO BE HELD HARMLESS.
3. ALL WATER AND SANITARY SEWER SYSTEMS THAT ARE TO BE PUBLIC LINES SHALL BE CONSTRUCTED IN ACCORDANCE WITH SPECIFICATIONS PREVIOUSLY APPROVED BY THE CITY OF LEE'S SUMMIT AND THE STATE OF MISSOURI AND SHALL BE INSPECTED BY THE CITY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ASSURE THAT THIS INSPECTION OCCURS.
4. LOCATIONS SHOWN FOR PROPOSED WATER LINES ARE APPROXIMATE. VARIATIONS MAY BE MADE, WITH APPROVAL OF THE ENGINEER, TO AVOID CONFLICTS.
5. CONTRACTOR TO INSTALL TRACING TAPE ALONG ALL NON-METALLIC WATER MAINS AND SERVICE LINES PER SPECIFICATIONS.
6. CONTRACTOR SHALL EXPOSE EXISTING UTILITIES AT LOCATIONS OF POSSIBLE CONFLICT AND POINTS OF CONNECTION PRIOR TO ANY CONSTRUCTION OF NEW UTILITIES.
7. WATER LINES SHALL HAVE A MINIMUM COVER OF 42 INCHES. ALL VALVES ON MAINS AND FIRE HYDRANT LEADS SHALL BE WITH VALVE BOX ASSEMBLIES. THE SIZE OF VALVE BOX ASSEMBLY TO BE INSTALLED IS DETERMINED BY THE TYPE AND SIZE OF VALVE. VALVE BOX CAPS SHALL HAVE THE WORD "WATER".
8. A MINIMUM HORIZONTAL DISTANCE OF 10 FEET SHALL BE MAINTAINED BETWEEN PARALLEL WATER AND SANITARY SEWER LINES. WHEN IT IS NECESSARY FOR ANY WATER LINE TO CROSS A SANITARY SEWER LINE, THE SEWER LINE SHALL BE CONSTRUCTED OF DUCTILE IRON PIPE AT LEAST 10 FEET EITHER SIDE OF THE WATER LINE UNLESS THE WATER LINE IS AT LEAST 2 FEET CLEAR DISTANCE ABOVE THE SANITARY SEWER LINE.
9. INSTALL 2" TYPE "K" COPPER FROM THE MAIN AT LEAST 10' BEYOND THE METER AND EITHER TYPE "K" OR POLYETHYLENE PLASTIC TUBING (PE 3608) FROM METER TO STOP AND WASTE VALVE INSIDE BUILDING.
10. CONTRACTOR RESPONSIBLE FOR PROVIDING CASEMENT FOR ELECTRICAL SERVICE PER EVERGY
11. CONTRACTOR TO REMOVE EXISTING STUB AS REQUIRED TO CLEAR BUILDING CONSTRUCTION

DETAILS

MS1	TRENCH AND BEDDING DETAILS
DCO	DOUBLE CLEANOUT
WAT-11	WATER SERVICE CONNECTION
CO	CLEANOUT


NOTES

- 17A POINT OF CONNECTION - GAS SERVICE
- 17B GAS SERVICE (BY GAS COMPANY)
- 17C GAS METER
- 18A POINT OF CONNECTION - TELEPHONE SERVICE - COORDINATE WITH TELEPHONE COMPANY
- 18B UNDERGROUND TELEPHONE SERVICE PER LOCAL TELEPHONE COMPANY
- 18C 2-2" CONDUIT INSTALLED BY CONTRACTOR - TELEPHONE SERVICE
- 19A POINT OF CONNECTION - ELECTRICAL SERVICE
- 19B ELECTRICAL SERVICE (SEE NOTE 10)
- 19C 4" CONDUIT INSTALLED BY CONTRACTOR - ELECTRIC SERVICE
- 19D TRANSFORMER - PER EVERGY DETAIL 700-103
- 19E 2-3" CONDUITS FOR FUTURE ELECTRICAL SERVICE FOR FUTURE SERVICE
- 20A POINT OF CONNECTION - WATER SERVICE
- 20B 2" SERVICE LINE
- 20C 4-1" METERS
- 59 4" SANITARY SEWER SERVICE LINE SDR-26 PVC CONNECTION SHALL BE A CUT-IN WYE

UTILITY STATEMENT:


THE UNDERGROUND UTILITIES SHOWN HEREON ARE FROM FIELD SURVEY INFORMATION OF ONE-CALL LOCATED UTILITIES, FIELD SURVEY INFORMATION OF ABOVE GROUND OBSERVABLE EVIDENCE, AND/OR THE SCALING AND PLOTTING OF EXISTING UTILITY MAPS AND DRAWINGS AVAILABLE TO THE SURVEYOR AT THE TIME OF SURVEY. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. FURTHERMORE, THE SURVEYOR DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES BY EXCAVATION UNLESS OTHERWISE NOTED ON THIS SURVEY.

Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineer is prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.




Revisions

STREETS OF W. PRYOR
LOT 5
LEE'S SUMMIT, MO.




Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineer is prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.





Revisions


STREETS OF W. PRYOR
LOT 5
LEES SUMMITT, MO.

sheet
C6.0
Civil
GRADING
permit
3 MAY 2023



- GRADING NOTES:**
1. EARTHWORK UNDER THE BUILDING SHALL COMPLY WITH THE PROJECT ARCHITECTURAL PLANS. OTHER FILL MATERIAL SHALL BE MADE IN LIFTS NOT TO EXCEED EIGHT INCHES DEPTH COMPACTED TO 95% STANDARD PROCTOR DENSITY. FILL MATERIAL MAY INCLUDE ROCK FROM ON-SITE EXCAVATION IF CAREFULLY PLACED SO THAT LARGE STONES ARE WELL DISTRIBUTED AND VOIDS ARE COMPLETELY FILLED WITH SMALLER STONES, EARTH, SAND OR GRAVEL TO FURNISH A SOLID EMBANKMENT. NO ROCK LARGER THAN THREE INCHES IN ANY DIMENSION NOR ANY SHALE SHALL BE PLACED IN THE TOP 12 INCHES OF EMBANKMENT.
 2. AREAS THAT ARE TO BE CUT TO SUBGRADE LEVELS SHALL BE PROOF ROLLED WITH A MODERATELY HEAVY LOADED DUMP TRUCK OR SIMILAR APPROVED CONSTRUCTION EQUIPMENT TO DETECT UNSUITABLE SOIL CONDITIONS.
 3. IN ALL AREAS OF EXCAVATION, IF UNSUITABLE SOIL CONDITIONS ARE ENCOUNTERED. A QUALIFIED GEOTECHNICAL ENGINEER SHALL RECOMMEND TO THE OWNER THE METHODS OF UNDERCUTTING AND REPLACEMENT OF PROPERLY COMPACTED, APPROVED FILL MATERIAL. ALL PROOF ROLLING AND UNDERCUTTING SHOULD BE PERFORMED DURING A PERIOD OF DRY WEATHER.
 4. CONTRACTOR SHALL USE SILT FENCE OR OTHER MEANS OF CONTROLLING EROSION ALONG THE EDGE OF THE PROPERTY OR OTHER BOTTOM OF SLOPE LOCATIONS.
 5. CONTRACTOR IS TO REMOVE AND DISPOSE OF ALL DEBRIS, RUBBISH AND OTHER MATERIALS RESULTING FROM PREVIOUS AND CURRENT DEMOLITION OPERATIONS.
 6. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO AVOID PROPERTY DAMAGE TO ADJACENT PROPERTIES DURING THE CONSTRUCTION PHASES OF THIS PROJECT. THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR ANY DAMAGES TO THE ADJACENT PROPERTIES OCCURRING DURING THE CONSTRUCTION PHASES OF THIS PROJECT.
 7. IT IS NOT THE DUTY OF THE ENGINEER OR THE OWNER TO REVIEW THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES, IN, ON OR NEAR THE CONSTRUCTION SITE AT ANY TIME DURING CONSTRUCTION.
 8. PIPE LENGTHS ARE CENTER TO CENTER OF STRUCTURE OR TO END OF END SECTIONS.
 9. HANDICAP STALLS SHALL MEET ADA REQUIREMENTS AND SHALL NOT EXCEED 2% SLOPE IN ANY DIRECTION AT THE BUILDING ENTRY AND ACCESSIBLE PARKING STALLS. SLOPES EXCEEDING 2.0% WILL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
 10. CONTRACTOR TO ADJUST DEPTHS OF EXISTING SERVICE LINES AS NECESSARY
 11. ALL CONSTRUCTION TRAFFIC, TEMPORARY TRAFFIC CONTROL DEVICES AND PAVEMENT MARKINGS SHALL CONFORM TO REQUIREMENTS OF THE LATEST MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
 12. SITE BEING ROUGH GRADED TO 12.5" BELOW FINISHED GRADE
 13. CONTRACTOR TO PLACE 8" LOW PERMEABILITY LVC FOR BUILDING PAD








Revisions

STREETS OF W. PRYOR
LOT 5
LEE'S SUMMITT, MO.


sheet
C7.0
Civil
ADA RAMPS
permit
3 MAY 2023






NOTES:

1. Prior to Land Disturbance activities, the following shall occur:
 - a) Identify the limits of construction on the ground with easily recognizable indications such as construction staking, construction fencing and placement of physical barriers or other means acceptable to the City inspector and in conformance with the erosion and pollution control plan;
 - b) Construct a stabilized entrance/parking/staging area;
 - c) Install perimeter controls and protect any existing stormwater inlets;
 - d) Request an initial inspection of the installed Phase I pollution control measures designated on the approved erosion and pollution control plan. Land disturbance work shall not proceed until there is a passed inspection
2. The site shall comply with all requirements of the MoDNR general requirements
 - a) Immediate initiation of temporary stabilization BMPs on disturbed areas where construction activities have temporarily ceased on that portion of the project site if construction activities will not resume for a period exceeding 14 calendar days. Temporary stabilization may include establishment of vegetation, geotextiles, mulches or other techniques to reduce or eliminate erosion until either final stabilization can be achieved or until further construction activities take place to re-disturb the area. This stabilization must be completed within 14 calendar days;
 - b) Inspection of erosion and sediment control measures shall be performed to meet or exceed the minimum inspection frequency in the MoDNR General Permit. At a minimum, inspections shall be performed during all phases of construction at least once every 14 days and within 24 hours of each precipitation event.
 - c) An inspection log shall be maintained and shall be available for review by the regulatory authority;
 - d) The erosion and pollution control plan shall be routinely updated to show all modifications and amendments to the original plan. A copy of the erosion and pollution control plan shall be kept on site and made available for review by the regulatory authority.
3. Temporary seeding shall only be used for periods not to exceed 12 months. For final stabilization, temporary seeding shall only be used to establish vegetation outside the permanent seeding or sodding dates as specified in the Standard Specifications. Final stabilization requires a uniform perennial vegetative cover with a density of 70% over 100% of disturbed area.
4. Erosion and pollution control shall be provided for the duration of a project. All installed erosion and pollution control BMPs shall be maintained in a manner that preserves their effectiveness. If the City determines that the BMPs in place do not provide adequate erosion and pollution control at any time during the project, additional or alternate measures that provide effective control shall be required.
5. Concrete wash or rinse water from concrete mixing equipment. Tools and/or ready-mix trucks, etc. may not be discharged into or be allowed to run to any existing water body or portion of the storm water system. One or more locations for concrete washout will be designated on site, such that discharges during concrete washout will be contained in a small area where waste concrete can solidify in place. Proper signage will be installed to direct users to the concrete washout. Concrete washouts must be handled prior to pouring any concrete.
6. Silt fences and sediment control BMPs which are shown along the back of curb must be installed within two weeks of curb backfill and prior to placement of base asphalt. Exact locations of these erosion control methods may be field adjusted to minimize conflicts with utility construction. However, anticipated disturbance by utility construction shall not delay installation.
7. Required sediment basins and traps shall be installed as early as possible during mass grading. Sediment basins and traps shall be cleaned out when the sediment capacity has been reduced by 20% of its original design volume.
8. All manufactured BMPs such as erosion control blankets, TRMs, biodegradable logs, filter socks, synthetic sediment barriers and hydraulic erosion control shall be installed as directed by the manufacturer.
9. The above requirements are the responsibility of the permittee for the site. Responsibility may be transferred to another party by the permittee, but the permittee shall remain liable by the City of Lee's Summit if any of the above conditions are not met.




- Notes for Concrete Washout:**
1. Concrete washout areas shall be installed prior to any concrete placement on site.
 2. Concrete washout area shall include a flat subsurface pit sized relative to the amount of concrete to be placed on site. The slopes leading out of the subsurface pit shall be 2:1. The vehicle tracking pit shall be sloped towards the concrete washout area.
 3. Vehicle tracking control is required of the access point to all concrete washout areas.
 4. Signs shall be placed at the construction site entrance, washout area and elsewhere as necessary to clearly indicate the location(s) of the concrete washout area(s) to operators of concrete truck and pump rigs.
 5. A one-piece impervious liner may be required along the bottom and sides of the subsurface pit in sandy or gravelly soils.


- Maintenance for Concrete Washout:**
1. Concrete washout materials shall be removed once the materials have filled the washout to approximately 75% full.
 2. Concrete washout areas shall be enlarged as necessary to maintain capacity for washed concrete.
 3. Concrete washout water, washed pieces of concrete and all other debris in the subsurface pit shall be transported from the job site in a water-tight container and disposed of properly.
 4. Concrete washout areas shall remain in place until all concrete for the project is placed.
 5. When concrete washout areas are removed, excavations shall be filled with suitable compacted backfill and topsoil, any disturbed areas associated with the installation, maintenance, and/or removal of the concrete washout areas shall be stabilized.



CONCRETE WASHOUT

AMERICAN PUBLIC WORKS ASSOCIATION	
	KANSAS CITY METRO CHAPTER
CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT	STANDARD DRAWING NUMBER ESC-01 ADOPTED: 10/24/2016

Construction Entrance modified from 2015 Overland Park Standard Details for Erosion and Sediment Control; Concrete Washout modified from 2009 City of Great Bend Standard Drawings.



- (*) POSTS**
- MIN. LENGTH 4'
 - HARDWOOD 1 3/4" x 1 3/4"
 - NO.2 SOUTHERN PINE 2 3/4" x 2 3/4"
 - STEEL 1.33 LB/FT

- (**) - Geotextile Fabric** shall meet the requirements of AASHTO M288

SILT FENCE DETAILS




Figure A


SILT FENCE LAYOUT


Modified from 2015 Overland Park Standard Details for Erosion and Sediment Control.


- Notes:**
1. In order to contain water, the ends of the silt fence must be turned uphill (Figure A).
 2. Long perimeter runs of silt fence must be limited to 100'. Runs should be broken up into several smaller segments to minimize water concentrations (Figure A).
 3. Long slopes should be broken up with intermediate rows of silt fence to slow runoff velocities.
 4. Attach fabric to upstream side of post.
 5. Install posts a minimum of 2' into the ground.
 6. Trenching will only be allowed for small or difficult installation, where slicing machine cannot be reasonably used.

Maintenance:

1. Remove and dispose of sediment deposits when the deposit approaches 1/2 the height of silt fence.
2. Repair as necessary to maintain function and structure.




AMERICAN PUBLIC WORKS ASSOCIATION	
	KANSAS CITY METRO CHAPTER
SILT FENCE	STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016



- Notes:**
1. Early Stage Area Inlet Sediment Barrier to be installed immediately after inlet or junction box is constructed.
 2. Silt fence shall remain in place until excavated area is removed and Late Stage Area Inlet is being installed.
 3. Backfill excavated area ONLY after final grading of the site. Stabilization of the site is to immediately follow.
 4. Wire reinforced silt fence may be used in place of silt fence attached to wood frame.

- Maintenance:**
1. Remove deposited sediment from excavated storage areas when available storage has been reduced by 20%.
 2. Remove deposited sediment from filter socks or similar when any accumulation of sediment is visible.
 3. Repair or replace as necessary to maintain function and integrity of installation.


AMERICAN PUBLIC WORKS ASSOCIATION	
	KANSAS CITY METRO CHAPTER
AREA INLET AND JUNCTION BOX PROTECTION	STANDARD DRAWING NUMBER ESC-07 ADOPTED: 10/24/2016

Modified from 2015 Overland Park Standard Details for Erosion and Sediment Control.

Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineer is prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.

Revisions


STREETS OF W. PRYOR
 LOT 5
 LEES SUMMITT, MO.




Revisions

STREETS OF W. PRYOR
LOT 5
LEES SUMMITT, MO.



sheet
C10.0
Civil
DETAILS
permit
3 MAY 2023




C1 TRASH ENCLOSURE GATE ELEVATION
SCALE: 1/4" = 1'-0"



TRASH ENCLOSURE





A1 ENCLOSURE GATE HINGE DETAIL
SCALE: 1 1/2" = 1'-0"




A2 TRASH ENCLOSURE WALL SECTION
SCALE: 3/4" = 1'-0"

NOTES:
BRICK- YANKEE HILL DARK IRON SPOT
MORTAR- SPEC MIX SM770 (SUBMIT TO OWNER FOR APPROVAL)
STONE- GLEN GEARY GLENN RIDGE BLACK/GRANITE






REGULAR DUTY PAVING PV1




HEAVY DUTY CONCRETE PV3


1. FLEXIBLE PAVEMENT SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE MISSOURI DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS.
- ASPHALT SURFACE COURSE - APWA TYPE 3-01
ASPHALT BASE COURSE - APWA TYPE 2-01
AGGREGATE BASE MoDOT TYPE 5 OR EQUIVALENT
2. PORTLAND CEMENT CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS WITH 6% ENTRAINED AIR $\pm 2\%$ AND SHALL MEET OR EXCEED THE SPECIFICATIONS SET FORTH IN THE LATEST EDITION OF THE MISSOURI DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS.




TRAIL PAVING TP




HEAVY DUTY ASPHALT PAVING PV2



CONCRETE SIDEWALK CW2




90° ACCESSIBLE & VAN ACCESSIBLE SPACE STRIPING PK1




ACCESSIBLE PARKING SIGN PK2


FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_rjsZHKC2.rvt
DATE: 5/23/2023 4:19:09 PM
DRAWN BY: Author




A1 SITE PLAN
SCALE: 1" = 30'-0"




C1 TYP. TRASH ENCLOSURE PLAN
SCALE: 1/4" = 1'-0"




D3 TRASH ENCLOSURE CAP DETAIL
SCALE: 3" = 1'-0"



A3 ENCLOSURE GATE HINGE DETAIL
SCALE: 1 1/2" = 1'-0"



C4 TRASH ENCLOSURE GATE ELEVATION
SCALE: 1/4" = 1'-0"



A4 TRASH ENCLOSURE WALL SECTION
SCALE: 1/2" = 1'-0"

schwerdt design group
architecture | interiors | planning
2231 sw warrenpark rd suite 300
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579
500 north broadway suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115
MICHAEL K HAMPTON
ARCHITECT
#MCA-A200027042

SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876

**CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5**
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES
PROGRESS PRINT ONLY


SHEET TITLE
SITE PLAN

PROJECT NUMBER
230117

SHEET NUMBER
A-100

FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_rjsZHKC2.rvt
DATE: 5/23/2023 4:19:09 PM
DRAWN BY: Author

A1 FIRST FLOOR
SCALE: 1/8" = 1'-0"




KEYED PLAN NOTES

1. LANDLORD TO PROVIDE PADLOCK FOR ROOF ACCESS LADDER AND 5 KEYS TO PADLOCK

PARTITION TYPES

SCALE: 1" = 1'-0"



2 HOUR RATED U301
NOTE: ALL PENETRATIONS THRU DEMISING WALLS MUST BE FIRESTOPPED.

CORE & SHELL BUILDING STREETS OF WEST PRYOR LOT 5

LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES
PROGRESS PRINT ONLY

SHEET TITLE
FIRST FLOOR PLAN

PROJECT NUMBER
230117

SHEET NUMBER
A-101



schwerdt design group
architecture | interiors | planning
2231 sw vanwinkle rd suite 303
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579

500 north broadway suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115



MICHAEL K. HAMPTON
#MCH A-2008027042


SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876

FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_ljsZHKC2.rvt
DATE: 5/23/2023 4:19:10 PM
DRAWN BY: Author


12345

ROOF PLAN NOTES

1. TPO ROOF MEMBRANE
2. R-30 INSULATION



A1 ROOF PLAN
SCALE: 1/8" = 1'-0"
N



schwerdt design group
architecture | interiors | planning
2231 sw warrenmaker rd suite 303
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579

500 north broadway suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115



MICHAEL K. HAMPTON
#MCH-A2000027042

SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES
PROGRESS PRINT ONLY



SHEET TITLE
ROOF PLAN

PROJECT NUMBER
230117

SHEET NUMBER
A-102

12345

FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_jrsZHKC2.rvt
DATE: 5/23/2023 4:19:11 PM
DRAWN BY: Author



EXTERIOR MATERIALS

	SPLIT FACE STONE VENEER (ST-1) COLOR: (CHARCOAL) BANFF SPRINGS CLIFFSTONE STYLE / MORTAR: ENGINEERED STONE VENEER MANUFACTURER: ELDORADO STONE
	FACE BRICK (BK-1) COLOR: CHARCOAL W/ SM770 SABLE MORTAR STYLE: COAL CREEK MANUFACTURER: MUTUAL MATERIALS
	WOOD / FIBER CEMENT SIDING (WD-1) COLOR: (DARK BROWN) SONORAN W/ DADOS PROFILE STYLE: RESAWN TIMBER / SEALED FACE AND BACK 3/4" THICK X 7-3/8" WIDE X 8-1/8" RANDOM LENGTHS MANUFACTURER: ACCOYA WOOD SIDING
	PRE-FINISHED METAL (MTL-1) COLOR: TBD LANDLORD TO SELECT FINAL COLOR STYLE: FLUSH SEAM PANEL FOR ALUMINUM MANUFACTURER: STUCCO EMBOSSED BERRIDGE
	EIFS - MAIN (EF-1) COLOR: WHITE (SW ID TBD) STYLE: SANDBLAST TEXTURE MANUFACTURER: DRYVIT
	EIFS - ACCENT (EF-2) COLOR: SW 7018 DOVETAIL STYLE: SANDBLAST TEXTURE MANUFACTURER: DRYVIT

schwerdt design group
architecture | interiors | planning
2231 sw warrenpark rd. suite 300
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579

500 north broadway, suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115

Michael K. Hampton
ARCHITECT
MICHAEL K. HAMPTON
#MCH A-200002702

SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #FD0353876

CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081


SUBMISSION DATES
PROGRESS PRINT ONLY

SHEET TITLE
EXTERIOR ELEVATIONS


PROJECT NUMBER
230117

SHEET NUMBER
A-201


FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_jrsZHKC2.nt
DATE: 5/23/2023 4:19:12 PM
DRAWN BY: Author



A1 SECTION @ EAST WALL STOREFRONT
SCALE: 1/2" = 1'-0"



A2 SECTION @ EAST WALL WINDOW TENANT C
SCALE: 1/2" = 1'-0"



A4 SECTION @ EAST WALL WINDOW TENANT A
SCALE: 1/2" = 1'-0"



SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING STREETS OF WEST PRYOR LOT 5 LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081


SUBMISSION DATES
PROGRESS PRINT ONLY

SHEET TITLE
WALL SECTIONS



PROJECT NUMBER
230117

SHEET NUMBER
A-301



FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_rjsZHKC2.rvt
DATE: 5/23/2023 4:19:12 PM
DRAWN BY: Author





A1 SECTION @ EAST WALL PILASTER
SCALE: 1/2" = 1'-0"



A2 SECTION @ NORTH WALL PILASTER
SCALE: 1/2" = 1'-0"




A4 SECTION @ NORTH WALL
SCALE: 1/2" = 1'-0"



schwerdt design group

architecture | interiors | planning
2231 sw warrenmaker rd. suite 300
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579

500 north broadway, suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115



SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING STREETS OF WEST PRYOR LOT 5 LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081


SUBMISSION DATES
PROGRESS PRINT ONLY

SHEET TITLE
WALL SECTIONS


PROJECT NUMBER
230117

SHEET NUMBER
A-302


FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_jrsZHKC2.rvt
DATE: 5/23/2023 4:19:13 PM
DRAWN BY: Author




A1 SECTION @ SOUTH WALL PILASTER
SCALE: 1/2" = 1'-0"



A2 SECTION @ NORTH WALL W/ PARAPET
SCALE: 1/2" = 1'-0"



A4 SECTION @ WEST WALL
SCALE: 1/2" = 1'-0"



schwerdt design group

architecture | interiors | planning
2231 sw vanwinkle rd suite 303
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579

500 north broadway, suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115



MICHAEL K. HAMPTON
#MCA-0200027042

SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081



SUBMISSION DATES
PROGRESS PRINT ONLY

SHEET TITLE
WALL SECTIONS

PROJECT NUMBER
230117

SHEET NUMBER
A-303


FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_ljsZHKC2.rvt
DATE: 5/23/2023 4:19:13 PM
DRAWN BY: Author



schwerdt design group

architecture | interiors | planning
2231 sw warrenmaker rd suite 300
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579

500 north broadway, suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115



SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876


CORE & SHELL BUILDING STREETS OF WEST PRYOR LOT 5 LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES
PROGRESS PRINT ONLY


SHEET TITLE
WALL SECTIONS

PROJECT NUMBER
230117

SHEET NUMBER
A-304




RESTROOM / BATH ACCESSORIES



PLUMBING FIXTURES AND ACCESSORIES



ACCESSIBILITY STANDARDS

SCALE: 3/8" = 1'-0"





RR INT ELEV - WEST

SCALE: 1/2" = 1'-0"




RR INT ELEV - EAST

SCALE: 1/2" = 1'-0"



RR INT ELEV - NORTH

SCALE: 1/2" = 1'-0"




RESTROOM GENERAL NOTES

1. RESTROOM FIXTURES AND ACCESSORIES IN PLAN ARE PROVIDED BY LANDLORD.
REF. C71A-401 FOR TYPICAL ACCESSIBLE MOUNTING HEIGHTS & DETAILS.
LANDLORD TO PROVIDE WALL PAINT; TENANT TO PROVIDE ALL OTHER FINISHES.
4. WALLS WITHIN 2'-0" OF PLUMBING FIXTURES MUST HAVE A SMOOTH, HARD, AND NON-ABSORBANT WALL SURFACE THAT EXTENDS A MINIMUM OF 4" A.F.F IN ACCORDANCE WITH 1209.2.2, BY TENANT
5. ALL RESTROOM WALLS/FLOORS MUST HAVE A SMOOTH, HARD, AND NON-ABSORBANT SURFACE WALL BASE THAT EXTENDS A MINIMUM OF 4" A.F.F. IN ACCORDANCE WITH 1209.2.1, BY TENANT


FIXTURE & ACCESSORY LEGEND

<u>GB-1</u>	GRAB BARS
<u>SD-1</u>	SOAP DISPENSER
<u>PTD-1</u>	PAPER TOWEL DISPENSER
<u>TPD-1</u>	TOILET PAPER DISPENSER
<u>MIR-1</u>	VANITY MIRROR
<u>CH-1</u>	COAT HOOK



45 ENLARGED RR PLAN


SCALE: 1/2" = 1'-0"



schwerdt design group

architecture | interiors | planning
2231 sw wanamaker rd suite 300
topeka, kansas 66614-4275
phone: 785.273.7540
fax: 785.273.7579

500 north broadway
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115



MICHAEL K HAMPTON
#MO# A-2008027042

SCHWERDT DESIGN GROUP INC
NO CERTIFICATE OF AUTH. #F00353876

**CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081**

SUBMISSION DATES
PROGRESS PRINT ONLY


SHEET TITLE
ENLARGED RESTROOM
PLAN

PROJECT NUMBER
230117


SHEET NUMBER
A-401

FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_rjsZHKC2.rvt
DATE: 5/23/2023 4:19:16 PM
DRAWN BY: Author


C1 CANOPY DETAIL
SCALE: 1 1/2" = 1'-0"




C3 AWNING DETAIL
SCALE: 1 1/2" = 1'-0"




C4 PARAPET CAP AT EAST WALL PILASTER
SCALE: 1 1/2" = 1'-0"



A1 STONE WALL BASE DETAIL
SCALE: 1 1/2" = 1'-0"



A3 EAST WALL PILASTER BASE DETAIL
SCALE: 1 1/2" = 1'-0"



schwerdt design group
architecture | interiors | planning
2231 sw warrenaker rd suite 383
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579
500 north broadway suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115
MICHAEL K HAMPTON
#MCA-A2000027042

SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES
PROGRESS PRINT ONLY

SHEET TITLE
BUILDING DETAILS

PROJECT NUMBER
230117


SHEET NUMBER
A-502

FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell_rjsZHKC2.rvt
DATE: 5/23/2023 4:19:16 PM
DRAWN BY: Author


DOOR LEGEND
SG = SAFETY GLASS
ALUM = ALUMINUM
HM = HOLLOW METAL
PT = PAINT
T = TRANSPARENT FINISH
F = FACTORY FINISH

DOOR SCHEDULE


DOOR							FRAME									NOTES
DOOR #	SIZE		MATL	FINISH	GLAZ	EL	MATL	FINISH	GLAZ	EL	DETAIL		HARDWARE			
	W	HT									HEAD	JAMB				
A101	3'-0"	7'-0"	ALUM	F	T	2	ALUM	F	T	C	A2	B3	SET 01			
A102	3'-6"	7'-0"	HM	PT	----	1	HM	PT	---	A	A1	B1	SET 02			
B101	3'-0"	7'-0"	ALUM	F	T	2	ALUM	F	T	C	A2	B3	SET 01			
B102	3'-0"	7'-0"	HM	PT	---	1	HM	PT	---	A	A1	B1	SET 02			
C101	3'-0"	6'-10"	ALUM	F	---	2	ALUM	F	T	C	A2	B3	SET 01			
C102	3'-6"	7'-0"	HM	PT	---	1	HM	PT	---	A	A1	B1	SET 02			




C3 STOREFRONT TYP JAMB DETAIL
SCALE: 1 1/2" = 1'-0"




B2 STOREFRONT JAMB DETAIL @ BRAKE METAL
SCALE: 1 1/2" = 1'-0"




B3 HM JAMB DETAIL
SCALE: 1 1/2" = 1'-0"



D4 STOREFRONT HEAD DETAIL
SCALE: 1 1/2" = 1'-0"



C4 HM HEAD DETAIL
SCALE: 1 1/2" = 1'-0"



B4 DOOR ELEVATIONS
SCALE: 1/4" = 1'-0"

DOOR HARDWARE SCHEDULE - SET 01 STOREFRONT

QTY.	DESCRIPTION	MODEL	FINISH	MFG.
3 PR.	HINGES	BB1191 4 1/2" x 4 1/2" NRP	US10B	HAGER
1 EA.	EXIT DEVICE	1692	DC13	FALCON
1 EA.	EXIT DEVICE	1690	DC13	FALCON
2 EA.	66" LADDER PULL	66LPBS	US26/626	CRL
2 EA.	CLOSER	SC70-18	DC13	FALCON
2 EA.	STOP	100S	DC13	FALCON
1 EA.	THRESHOLD	350	DKB	NGP
2 EA.	DOOR SWEEP	200NA	DKB	NGP
1 EA.	PERIMETER SEAL	160S	DKB	NGP
1 EA.	ASTRAGAL	672	DKB	NGP

DOOR HARDWARE SCHEDULE - SET 02 SERVICE DOOR


QTY.	DESCRIPTION	MODEL	FINISH	MFG.
1 EA.	ROTON HINGE SURFACE MOUNT	70-210HD-84	ALUM	ROTON
1 EA.	EXIT DEVICE RIM SURFACE MOUNT	4501-48-26D	26D/626	HAGER
1 EA.	CLOSER 5100 HOLD OPEN STOP	5100-HDHOS-ALUM	ALUM	HAGER
1 EA.	ARMOR PLATE 20"x40" S.S.	190S-20X40-32D	32D	HAGER
1 EA.	WEATHER STRIPPING NEOPRENE	873S-N-4284-MILL	ML	HAGER
1 EA.	DOOR BOTTOM SWEEP NEOPRENE	750SN-42-CLR	CL	HAGER
1 EA.	NGP STEEL SECURITY ASTRAGAL 83"	1392SP-USP-83	PRIME COAT	NGP
1 EA.	HALF SADDLE THRESHOLD 5"x12"x42"	431S-42-MIL	MIL	HAGER
1 EA.	OVERHEAD RAIN DRIP GUARD	810S-46-MIL	AL	HAGER
1 EA.	WIDE ANGLE PEEP HOLE SET @ 45° AFF			

DOOR HARDWARE SCHEDULE - SET 03 STOREFRONT

QTY.	DESCRIPTION	MODEL	FINISH	MFG.
3 PR.	HINGES	BB1191 4 1/2" x 4 1/2" NRP	US10B	HAGER
1 EA.	EXIT DEVICE	1692	DC13	FALCON
1 EA.	66" LADDER PULL	66LPBS	US26/626	CRL
1 EA.	CLOSER	SC70-18	DC13	FALCON
1 EA.	STOP	100S	DC13	FALCON
1 EA.	THRESHOLD	350	DKB	NGP
1 EA.	DOOR SWEEP	200NA	DKB	NGP
1 EA.	PERIMETER SEAL	160S	DKB	NGP


B5 DOOR HARDWARE SCHEDULE
SCALE: NO SCALE

A1 FRAME ELEVATIONS
SCALE: 1/4" = 1'-0"



schwerdt design group
architecture | interiors | planning
2231 sw warrenpark rd
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579

500 north broadway
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115



SCHWERDT DESIGN GROUP INC.
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES
PROGRESS PRINT ONLY

SHEET TITLE
DOOR / FRAME SCHEDULE
& DETAILS

PROJECT NUMBER
230117

SHEET NUMBER
A-601

FILEPATH: C:\Users\John.Donalson\Documents\01190008.120 - Streets of West Pryor - Lot 5_ JohnDon7.rvt
DATE: 5/24/2023 7:32:27 AM
DRAWN BY: GSH

STRUCTURAL GENERAL NOTES

GENERAL NOTES:

ALL STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH THE OTHER PROJECT DRAWINGS AND SPECIFICATIONS. THE MATERIAL REQUIREMENTS IN THESE NOTES ARE TO BE CONSIDERED AS MINIMUM. SPECIFICATIONS SHALL GOVERN WHEN MORE STRINGENT.

VERIFY ALL DIMENSIONS SHOWN WITH ARCHITECTURAL DRAWINGS AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION. DISCREPANCIES SHALL BE RESOLVED BEFORE PROCEEDING WITH CONSTRUCTION. CONTRACTOR SHALL COORDINATE THE WORK OF ALL TRADES AND MAKE NECESSARY INVESTIGATIONS AND FIELD MEASUREMENTS. INFORM ENGINEER OF ALL DISCREPANCIES.

THE CONTRACTOR SHALL VERIFY THE SIZE AND LOCATIONS OF PENETRATIONS AND EMBEDDED ITEMS THROUGH THE STRUCTURE FOR ALL TRADES. PENETRATIONS SHALL BE SUBJECT TO APPROVAL BY THE ARCHITECT AND STRUCTURAL ENGINEER.

SEE MECHANICAL, ELECTRICAL, ARCHITECTURAL DRAWINGS FOR ANCHORS, PIPE SLEEVES, CONDUITS OR OTHER ITEMS TO BE EMBEDDED IN OR PASS THROUGH CONCRETE. IN GENERAL, EMBEDMENTS AND PENETRATIONS LESS THAN 12 INCHES IN DIAMETER ARE NOT SHOWN ON THE STRUCTURAL DRAWINGS.

SEE ARCHITECTURAL DRAWINGS FOR DOOR HEIGHTS AND WALL OPENING DIMENSIONS.

STRUCTURAL ELEMENTS ARE NON-SELF SUPPORTING AND REQUIRE INTERACTION WITH OTHER ELEMENTS FOR STABILITY. FRAMING AND WALLS SHALL BE TEMPORARILY BRACED BY THE CONTRACTOR UNTIL PERMANENT BRACING, FLOOR AND ROOF DECKS AND WALLS HAVE BEEN INSTALLED AND CONNECTIONS BETWEEN THESE ELEMENTS HAVE BEEN MADE.

SUPPORT OF ALL NON-STRUCTURAL ELEMENTS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. NON-STRUCTURAL ELEMENTS ARE THOSE THAT DO NOT CONTRIBUTE TO THE DIRECT LOAD PATH OF BOTH THE GRAVITY AND LATERAL FORCE RESISTING SYSTEMS. THESE ELEMENTS INCLUDE, BUT ARE NOT LIMITED TO PARTITIONS, FINISHES, MILLWORK, MECHANICAL EQUIPMENT, DUCTWORK, PIPING, LIGHT FIXTURES, ELECTRICAL CONDUIT, STORAGE RACKS, ETC. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT THESE ELEMENTS ARE ADEQUATELY CONNECTED TO THE STRUCTURE TO RESIST ALL APPLIED LOADS. NOTIFY THE STRUCTURAL ENGINEER OF RECORD IF UNUSUAL SUPPORT CONDITIONS EXIST.

WORK REQUIRING SPECIAL INSPECTIONS SHALL BE INSPECTED ACCORDING TO THE BUILDING CODE AND INCLUDES: CONCRETE, REINFORCING STEEL, STRUCTURAL WELDING, HIGH-STRENGTH BOLTING, AND MASONRY. RE: SPECIAL INSPECTION PROGRAM TABLE WHEN APPLICABLE.

DESIGN CRITERIA:

BUILDING CODE: 2018 INTERNATIONAL BUILDING CODE AS ADOPTED AND AMENDED BY THE CITY OF LEE'S SUMMIT, MISSOURI.

LIVE LOADS:
ROOF: 20 PSF

SNOW LOADS:
GROUND SNOW LOAD, Pg: 20 PSF
FLAT-ROOF SNOW LOAD, Pf: 20 PSF
SNOW EXPOSURE FACTOR, Ce: 1.0
SNOW LOAD IMPORTANCE FACTOR, Is: 1.0
THERMAL FACTOR, Ct: 1.0

WIND LOAD:
BASIC WIND SPEED: 115 MPH
EXPOSURE CATEGORY: C
WIND IMPORTANCE FACTOR, Iw: 1.0
BASIC INTERNAL PRESSURE COEFFICIENT, GCpi: ±0.18
BASIC COMPONENTS AND CLADDING PRESSURE (ADJUSTED TO COMPLY WITH BUILDING CODE):
±20 PSF @ INTERIOR ZONES
±25 PSF @ END ZONES

SEISMIC LOAD:
SEISMIC IMPORTANCE FACTOR, Ie: 1.0
SPECTRAL RESPONSE ACCELERATIONS:
Ss: 0.1274
S1: 0.0612
SPECTRAL RESPONSE COEFFICIENTS:
Sds: 0.102
Sd1: 0.069
SITE CLASS: C
SEISMIC DESIGN CATEGORY: B
BASIC SEISMIC-FORCE-RESISTING SYSTEM: LIGHT-FRAMED WALLS WITH WOOD STRUCTURAL PANELS & STEEL ORDINARY MOMENT FRAMES
DESIGN BASE SHEAR: Cs x W
SEISMIC RESPONSE COEFFICIENTS, Cs: 0.0157 & 0.0291
RESPONSE MODIFICATION FACTOR, R: 6.5 & 3.5
ANALYSIS PROCEDURE: EQUIVALENT LATERAL FORCE

FOUNDATION AND EARTHWORK NOTES:

REFER TO THE GEOTECHNICAL EXPLORATION AND FOUNDATION RECOMMENDATIONS: WEST PRYOR VILLAGE, LEE'S SUMMIT, MISSOURI / COOK, FLATT, & STROBEL ENGINEERS PA, KANSAS CITY, KANSAS (CFS NO 19-5125) / JUNE 15, 2018

THE FOUNDATION BEARING MATERIAL SHALL BE INSPECTED AND APPROVED BY A GEOTECHNICAL ENGINEER BEFORE FOUNDATIONS ARE CONSTRUCTED.

AT STEPPED FOOTINGS, THE LOWER FOOTING SHALL BE PLACED FIRST.

FOUNDATIONS HAVE BEEN DESIGNED FOR A NET ALLOWABLE SOIL BEARING PRESSURE OF 2,500 PSF FOR CONTINUOUS FOOTINGS AND 3,000 PSF FOR ISOLATED SPREAD FOOTINGS. FOUNDATIONS SHALL BEAR DIRECTLY ON A 24-INCH THICK, GEOGRID REINFORCED AGGREGATE PAD (GRAP) DESIGNED AND CONSTRUCTED AS OUTLINED IN THE GEOTECHNICAL REPORT, SECTION 7.2.

WALL FOUNDATION SHALL BEAR AT MINIMUM OF 3'-0" BELOW ADJACENT FINISH GRADE, UNLESS OTHERWISE NOTED.

UNUSUAL CONDITIONS OR CHANGES TO THE FOUNDATIONS AS REQUIRED BY FIELD CONDITIONS SHALL BE REFERRED TO THE ENGINEER FOR APPROVAL.

REFER TO GEOTECHNICAL REPORT FOR SUBGRADE PREP REQUIREMENTS FOR SLAB-ON-GRADE CONSTRUCTION. PREPARED SUBGRADES EXCAVATED TO INSTALL UTILITIES BELOW FLOOR SLABS SHALL BE BACKFILLED AND COMPACTED AS SPECIFIED BY THE GEOTECHNICAL ENGINEER.

REFER TO GEOTECHNICAL REPORT FOR COMPACTION REQUIREMENTS.

MAINTAIN ALL EXCAVATIONS FREE OF WATER.

CONCRETE NOTES:

CONCRETE SHALL HAVE THE FOLLOWING UNLESS OTHERWISE SPECIFIED (SELECT PROPORTIONS FOR CONCRETE IN ACCORDANCE WITH ACI 318):

	MAX WATER/CEMENT RATIO	MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS
INTERIOR SLAB ON GRADE	0.45	3,000 PSI
FOOTINGS	0.45	4,500 PSI
FOUNDATION WALLS	0.45	4,500 PSI
GRADE BEAMS	0.45	4,500 PSI
DRILLED PIERS	0.50	4,000 PSI
CONCRETE ON STEEL DECK	0.45	3,000 PSI

REINFORCING STEEL SHALL BE BILLET STEEL CONFORMING TO ASTM A615, GRADE 60.

WELDED WIRE FABRIC SHALL CONFORM TO ASTM A185.

CEMENT SHALL CONFORM TO ASTM C150, TYPE I OR II.

AGGREGATES SHALL CONFORM TO ASTM C33. COARSE AGGREGATE SHALL CONSIST OF 1" MAXIMUM AGGREGATE SIZE. COMBINED GRADATION SHALL HAVE A UNIFORM DISTRIBUTION AS FOLLOWS:
5-20% RETAINED ON 3/4", 1/2", 3/8", NO. 4, NO. 8, NO. 16, NO. 30 AND NO. 50 SIEVES; LESS THAN 5% PASSING NO. 50 SIEVE.

MATERIALS AND ADMIXTURES SHALL NOT CONTAIN CALCIUM CHLORIDE.

ALL EXTERIOR AND CONCRETE EXPOSED TO FREEZE/THAW CYCLES SHALL BE AIR-ENTRAINED 6%±) BY VOLUME. THIS INCLUDES BUT IS NOT LIMITED TO FOOTINGS, FOUNDATION WALLS AND GRADE BEAMS.

SLEEVES, OPENINGS, OR OTHER ATTACHMENTS NOT SHOWN ON DRAWINGS SHALL BE APPROVED BY THE ENGINEER PRIOR TO PLACING CONCRETE.

MINIMUM TENSION LAP SPlice LENGTHS AND TENSION DEVELOPMENT LENGTHS SHALL BE AS SCHEDULED, UNLESS NOTED OTHERWISE ON THE DRAWINGS. WELDED WIRE FABRIC SHALL LAP ONE (1) FULL SQUARE PLUS TWO (2) INCHES.

MAINTAIN CONCRETE COVER AS SCHEDULED.

REINFORCING STEEL FABRICATION AND INSTALLATION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CRSI MANUAL OF STANDARD PRACTICE.

ALL REINFORCING AND EMBEDDED ANCHOR BOLTS SHALL BE ACCURATELY PLACED AND TIED PRIOR TO POURING CONCRETE. "STABBING" OF DOWELS OR ANCHOR BOLTS IS NOT ALLOWED.

CONSTRUCTION JOINTS IN WALLS AND ELEVATED FORMED SLABS SHALL BE KEVED (1 1/2" DEEP BY 1/3 MEMBER AREA) AND REINFORCING SHALL CONTINUE THROUGH JOINT OR BE TENSION LAP SPLICED. CONSTRUCTION JOINTS SHALL BE LOCATED BY THE CONTRACTOR TO LEAST IMPAIR THE STRUCTURE. JOINT LOCATIONS SHALL BE APPROVED BY THE ENGINEER.

EMBEDDED CONDUIT SHALL NOT BE LARGER IN OUTSIDE DIMENSION THAN 1/3 THE OVERALL THICKNESS OF SLAB, WALL OR BEAM IN WHICH THEY ARE EMBEDDED. THEY SHALL NOT BE SPACED CLOSER THAN 3 DIAMETERS OR WIDTHS ON CENTER.

CONDUIT LOCATED WITH CONCRETE SECTIONS SHALL COMPLY WITH ACI 318 REQUIREMENTS.

INTERIOR FLOOR SLABS SHALL COMPLY WITH ACI 117, SHALL MEET THE REQUIREMENTS OF A TYPE 5, SINGLE COURSE, HARD STEEL-TROWELED FINISH AS DESCRIBED IN ACI 302, AND SHALL ACHIEVE AN OVERALL FF25/FL20 TOLERANCE.

ADHESIVE ANCHORS IN CONCRETE OR FULLY GROUTED MASONRY SHALL BE ITW RAMISET/REDHEAD EPCOM CERAMIC 6 SYSTEM, HILTI HY200, OR SIMPSON AT-XP. ADHESIVE ANCHORS FOR HOLLOW BLOCK AND OTHER MASONRY SHALL BE HILTI HY270 OR SIMPSON SET-XP.

STRUCTURAL STEEL ENCASED WITHIN CONCRETE SHALL COMPLY WITH AISC TOLERANCES.

MASONRY NOTES:

CONSTRUCT MASONRY IN ACCORDANCE WITH THE IBC. MASONRY REQUIRES LEVEL 1 QUALITY ASSURANCE (RE: SPECS). ALL MASONRY SHALL BE LAID IN RUNNING (COMMON) BOND USING THE LOW-LIFT METHOD OF GROUTING. REFER ARCHITECTURAL PLAN FOR ALL BLOCK COURSING.

MASONRY DESIGN IS BASED ON A MINIMUM COMPRESSIVE STRENGTH (F'm) OF ASSEMBLY OF 1,500 PSI.

MASONRY UNITS SHALL MEET THE REQUIREMENTS OF ASTM C-90, GRADE N, WITH A NET AREA COMPRESSIVE STRENGTH OF 1,900 PSI.

MORTAR SHALL BE PREPARED IN ACCORDANCE WITH ASTM C-270. PROVIDE TYPE M MORTAR AT ALL MASONRY BELOW GRADE AND TYPE S AT ALL OTHER MASONRY.

GROUT SHALL BE PREPARED IN ACCORDANCE WITH ASTM C-476, WITH A MINIMUM COMPRESSIVE STRENGTH OF 2,000 PSI AT 28 DAYS.

REINFORCING STEEL SHALL BE BILLET STEEL CONFORMING TO ASTM A615, GRADE 60.

LAP SPlice BAR REINFORCEMENT FOR MASONRY PER LAP SCHEDULE AND JOINT REINFORCEMENT A MINIMUM OF 6 INCHES.

CONCRETE MASONRY UNITS BELOW GRADE SHALL BE SOLID GROUTED.

CELLS WITH REINFORCING SHALL BE SOLID GROUTED AND VIBRATED.

STRUCTURAL STEEL NOTES:

STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING, UNLESS OTHERWISE NOTED:
WIDE FLANGE SHAPES (W, WT): ASTM A992 (Fy=50 KSI)
OTHER ROLLED SHAPES (M, S, HP, C, L): ASTM A36 (Fy=36 KSI)
STEEL PIPE: ASTM A53, GRADE B (Fy=35 KSI)
SQUARE AND RECTANGULAR TUBE: ASTM A500, GRADE B (Fy=46 KSI)
ANCHOR BOLTS: ASTM F1554, GRADE 36
HEADED ANCHOR STUDS: ASTM A108, GRADES 1010 TO 1020
PLATES AND BARS: ASTM A36 (Fy=36 KSI)

SHEAR CONNECTORS AND HEADED WELDED STUDS OF TYPE AND SIZE NOTED SHALL BE TYPE B.

STRUCTURAL STEEL SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH GOOD STANDARD PRACTICE AND IS THE RESPONSIBILITY OF THE CONTRACTOR.

PROPER FIT IN THE FIELD OF STRUCTURAL STEEL SHALL BE IN ACCORDANCE WITH GOOD STANDARD PRACTICE AND IS THE RESPONSIBILITY OF THE CONTRACTOR.

THE FABRICATOR SHALL BE RESPONSIBLE FOR THE DESIGN AND PERFORMANCE OF ALL CONNECTIONS NOT FULLY DESIGNED OR DETAILED ON THE CONTRACT DOCUMENTS.

ANCHOR BOLTS SHALL BE ASTM F1554, A36 UNO. ANCHOR BOLTS SHALL BE SET WITH TEMPLATES WITH THE APPROPRIATE BOLT PROJECTION, 4" MINIMUM UNO. PROVIDE DOUBLE NUTS AND DOUBLE WASHERS FOR STEEL COLUMN ANCHOR BOLTS TO ALLOW FOR ADJUSTMENT IN BASE PLATE ELEVATION.

NON-SHRINK GROUT UNDER BASE PLATES SHALL BE NON-METALLIC WITH A MINIMUM COMPRESSIVE STRENGTH OF 5,000 PSI AT 28 DAYS.

HIGH STRENGTH BOLTED CONNECTIONS SHALL CONFORM TO THE AISC SPECIFICATIONS FOR STRUCTURAL JOINTS USING A325 BOLTS. UNLESS OTHERWISE NOTED, HIGH STRENGTH BOLTS MAY BE TIGHTENED BY ANY METHOD THEREIN. REGARDLESS OF THE METHOD USED IN TIGHTENING, A HARDENED WASHER SHALL BE USED UNDER THE TURNED ELEMENT. UNLESS OTHERWISE NOTED, BOLTED CONNECTIONS SHALL BE MADE WITH 3/4"Ø, ASTM A325 HIGH STRENGTH BOLTS.

CONNECTIONS REQUIRING FULL PRETENSIONING ARE SLIP-CRITICAL, AND INCLUDE BOLTED COLUMN SPLICES AND CONNECTIONS SUBJECT TO DIRECT TENSION.

ALL WELDING SHALL BE DONE IN ACCORDANCE WITH THE LATEST EDITION OF THE STRUCTURAL WELDING CODE, AWS D1.1. UNLESS NOTED OTHERWISE, MINIMUM WELD SIZE SHALL BE PER AISC 360, BUT SHALL BE NO LESS THAN 3/16" FILLET.

FIELD WELDING SHALL NOT BE STARTED UNTIL JOINT ELEMENTS ARE BOLTED IN INTIMATE CONTACT AND/OR ADJUSTED TO DIMENSIONS INDICATED WITH ALLOWANCE FOR EXPECTED WELD SHRINKAGE. MAINTAIN PLUMBNESS AND TRUENESS OF THE STRUCTURE.

FIELD WELDS FOR STRUCTURAL STEEL SHALL BE MADE WITH LOW HYDROGEN ELECTRODES. WELD FILLER METAL SHALL HAVE A MINIMUM TENSILE STRENGTH OF 70 KSI.

WOOD NOTES:

GENERAL STRUCTURAL WOOD FRAMING SHALL MEET THE MINIMUM STRESS REQUIREMENTS FOR DOUGLAS-FIR #2 AND SHALL BEAR THE STAMP OF AN APPROVED TESTING AGENCY.

ROOF SHEATHING SHALL BE 5/8" (19/32" MIN) PLYWOOD WITH A SPAN RATING OF AT LEAST 32/16. PANELS SHALL BE NAILED WITH 10d NAILS AT 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. 1/8" GAP BETWEEN INDIVIDUAL SHEETS. PLYWOOD SHALL BE APA RATED C-D EXTERIOR AND SHALL BEAR THE STAMP OF AN APPROVED TESTING AGENCY.

ALL WOOD-TO-WOOD CONNECTIONS SHALL MEET THE MINIMUM NAILING REQUIREMENTS OF THE BUILDING CODE.

PROVIDE SIMPSON CONNECTION HARDWARE AS SHOWN ON THE DRAWINGS. SUBSTITUTIONS MUST BE APPROVED BY THE ARCHITECT AND STRUCTURAL ENGINEER PRIOR TO USE. INSTALL CONNECTION HARDWARE ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS.

WALL SHEATHING SHALL BE 1/2" OSB ON THE EXTERIOR FACE OF ALL EXTERIOR WALLS. PANELS SHALL BE NAILED WITH 10d GALVANIZED NAILS AT 4" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. ALL PANEL EDGES SHALL BE BLOCKED.

INSTALL ALL ROOF PLYWOOD SHEATHING WITH THE LONG DIMENSION OF THE PANEL PERPENDICULAR TO THE SUPPORTS WITH A MINIMUM OF TWO SPANS FOR EACH PANEL. STAGGER ALL END JOINTS. PROVIDE 1/8" SPACE AT PANEL JOINTS FOR EXPANSION PER APA.

PREFABRICATED WOOD TRUSS NOTES:

SPECIAL INSPECTIONS OF THE FABRICATION PROCESS OF PRE-FABRICATED WOOD STRUCTURAL ELEMENTS AND ASSEMBLIES SHALL BE IN ACCORDANCE WITH THE IBC.

TRUSSES SHALL BE CONFIGURED TO FOLLOW FINAL ROOF LINES, UNLESS NOTED OTHERWISE.

TRUSSES SHALL BE DESIGNED FOR ALL LOAD COMBINATIONS REQUIRED BY THE BUILDING CODE. IN NO CASE SHALL THE DEAD LOAD BE LESS THAN 15 PSF ON THE TOP CHORD AND 10 PSF ON THE BOTTOM CHORD.

TRUSS MANUFACTURER SHALL SUPPLY ALL TRUSS CONNECTIONS USING PREFABRICATED STEEL CONNECTORS AS REQUIRED.

CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL TEMPORARY AND PERMANENT BRACING IN ADDITION TO ANY BRACING INDICATED ON THE PLANS.

ALL TEMPORARY AND PERMANENT BRACING FOR INDIVIDUAL TRUSS MEMBERS SHALL BE DESIGNED BY AND STAMPED BY A PROFESSIONAL ENGINEER PROVIDED BY CONTRACTOR AND/OR TRUSS MANUFACTURER. APPLIED ROOF SHEATHING AND OTHER ROOFING MATERIALS SHALL NOT BE ASSUMED TO PROVIDE SUFFICIENT BRACING FOR TRUSS CHORDS.

SHOP FABRICATED WOOD TRUSSES SHALL MEET DESIGN SPECIFICATIONS FOR METAL PLATE CONNECTED WOOD TRUSSES BY THE TRUSS PLATE INSTITUTE. PROVIDE PERMANENT AND TEMPORARY BRACING ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

COORDINATE ALL TRUSS DETAILS WITH ARCHITECTURAL PLANS.

SPLICE & DEVELOPMENT LENGTHS FOR REINFORCEMENT
(UNLESS NOTED OTHERWISE ON THE DRAWINGS)

BAR SIZE	LENGTH OF LAPPED SPLICES FOR REINFORCEMENT (INCHES)		LENGTH OF END ANCHORAGE FOR DEVELOPMENT OF REINFORCEMENT (INCHES)			HOOK LENGTH	BAR SIZE
	TOP BARS*	OTHERS	TOP BARS*	OTHERS	HOOKED BARS		
3	28	22	22	17	9	6	3
4	38	29	29	22	11	8	4
5	47	36	36	28	14	10	5
6	56	43	43	33	17	12	6
7	81	63	63	48	20	14	7
8	93	72	72	55	22	16	8
9	105	81	81	62	25	20	9
10	118	91	91	70	28	22	10
11	131	101	101	78	31	24	11
14	--	--	121	93	38	31	14
18	--	--	161	124	50	41	18

*TOP BARS ARE HORIZONTAL BARS SO PLACED THAT MORE THAN 12" OF CONCRETE IS CAST IN THE MEMBER BELOW THE BAR. HORIZONTAL BARS IN WALLS ARE TO BE CONSIDERED AS TOP BARS. VERTICAL BARS MAY BE CONSIDERED AS OTHER BARS.

UNLESS EITHER OF THE FOLLOWING TWO CASES EXIST FOR STRAIGHT BARS, THE DEVELOPMENT OR SPLICE LENGTH FOR STRAIGHT BARS IN THE ABOVE TABLE MUST BE MULTIPLIED BY 1.5:

I. THE CLEAR SPACING OF BARS BEING DEVELOPED OR SPLICED IS GREATER THAN OR EQUAL TO ONE BAR DIAMETER, THE CLEAR COVER IS GREATER THAN OR EQUAL TO ONE BAR DIAMETER, AND STIRRUPS OR TIES PROVIDED THROUGHOUT THE DEVELOPMENT OR SPLICE LENGTH MEET OR EXCEED THE CODE MINIMUM.

II.THE CLEAR SPACING OF BARS BEING DEVELOPED OR SPLICED IS GREATER THAN OR EQUAL TO TWO BAR DIAMETERS AND THE CLEAR COVER IS GREATER THAN OR EQUAL TO ONE BAR DIAMETER.

THE DEVELOPMENT LENGTH FOR HOOKED BARS, SIZE 11 AND SMALLER, PLACED WITH SIDE COVER GREATER THAN OR EQUAL TO 2 1/2" AND COVER ON THE BAR EXTENSION BEYOND THE HOOD (90° HOOK ONLY) GREATER THAN OR EQUAL TO 2", MAY BE MULTIPLIED BY 0.7.

VALUES IN THE ABOVE TABLE ARE NOT TO BE USED FOR EPOXY COATED REINFORCING AND/OR REINFORCING PLACED IN CONCRETE CONTAINING LIGHTWEIGHT AGGREGATE.

CONCRETE COVER FOR REINFORCEMENT
(UNLESS NOTED OTHERWISE ON THE DRAWINGS)

LOCATION	MINIMUM COVER
CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH	3"
CONCRETE EXPOSED TO EARTH OR WEATHER: #6 AND LARGER #5 AND SMALLER	2" 1 1/2"
CONCRETE NOT EXPOSED TO WEATHER OR IN CONTACT WITH THE GROUND: SLABS, WALLS, AND JOISTS: #14 AND LARGER #11 AND SMALLER BEAMS AND COLUMNS	1 1/2" 3/4" 1 1/2"

CERTUS
STRUCTURAL ENGINEERS
900 S. Kansas Avenue; Suite 400
Topeka, Kansas 66612
Phone: (785) 291-0400
Fax: (785) 291-0401
Proj #01190008.120
Certificate Of Authorization
E-1392
Revit 2023 Local

schwerdt design group
architecture | interiors | planning
2231 sw wanamaker rd suite 303
topeka, kansas 66614-4275
phone: 785.273.7540
fax: 785.273.7579
500 north broadway suite 200
oklahoma city, ok 73102
phone: 405.291.3105
fax: 405.291.3115

CORE & SHELL BUILDING FOR
STREETS OF WEST PRYOR LOT 5
LEE'S SUMMIT, MISSOURI


SUBMISSION DATES
2023-05-23

SHEET TITLE
GENERAL NOTES

PROJECT NUMBER
230117

SHEET NUMBER
S-001

FILEPATH: C:\Users\John.Donaldson\Documents\01190008.120 - Streets of West Pryor - Lot 5_JohnDon7.rvt
DATE: 5/24/2023 7:32:28 AM
DRAWN BY: Author



FOUNDATION PLAN

SCALE: 1/8" = 1'-0"

FLOOR CONSTRUCTION: 4" CONCRETE SLAB ON GRADE REINFORCE w/6X6 - W2.9XW2.9 WELDED WIRE FABRIC. LOCATE REINFORCING 1 1/2" BELOW TOP OF SLAB. PROVIDE 6" LAYER OF GRANULAR LEVELING COURSE (#57 STONE) BELOW SLAB. VAPOR BARRIER SHALL BE PLACED DIRECTLY OVER GRANULAR FILL AND UNDER SLAB. REFERENCE ARCHITECTURAL AND SPECIFICATIONS FOR FURTHER DETAILS.

THE BUILDING FLOOR SLAB SHALL BE WITHIN A FLATNESS TOLERANCE OF 1/4" PER 10'-0".

TOSL - TOP OF SLAB ELEVATION: 100-0 = SITE ELEVATION: 984.25, 99-4 = SITE ELEVATION 983.58

TOF - TOP OF FOOTING ELEVATION: 98-8 OR 99-4, RE: PLAN

SJ - SLAB JOINT
FS - FOOTING STEP
C-(#) - DENOTES COLUMN MARK, REFERENCE SCHEDULE
F-(#) - DENOTES FOOTING MARK, REFERENCE SCHEDULE
BP-(#) - DENOTES COLUMN BASE PLATE TYPE, REFERENCE DETAILS

COORDINATE ALL PENETRATIONS THROUGH THE SLAB AND ALL UNDER SLAB ITEMS WITH OTHER TRADES BEFORE CONSTRUCTION.

VERIFY ALL DIMENSIONS SHOWN WITH ARCHITECTURAL AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION. INFORM ENGINEER OF ALL DISCREPANCIES.

ISOLATED FOOTING

MARK	SIZE (LxWxD)	REINFORCING
F-1	3'-0x3'-0x3'-0	(4) #5 EW
F-2	5'-0x5'-0x1'-4	(6) #5 EW

COLUMN SCHEDULE

MARK	SIZE
C-1	HSS4x4x1/4
C-2	HSS5x5x1/4
C-3	DBL HSS9x7x3/8
C-4	(7) 2X8

CERTUS
STRUCTURAL ENGINEERS
900 S. Kansas Avenue; Suite 400
Topeka, Kansas 66612
Phone: (785) 291-0400
Fax: (785) 291-0401
Proj #01190008.120
Certificate Of Authorization
E-1392
Revit 2023 Local

SUBMISSION DATES

2023-05-23

SHEET TITLE
FOUNDATION PLAN


PROJECT NUMBER
230117

SHEET NUMBER
S-101



CORE & SHELL BUILDING FOR
STREETS OF WEST PRYOR LOT 5
LEE'S SUMMIT, MISSOURI

FILEPATH: C:\Users\John.Donaldson\Documents\01190008.120 - Streets of West Pryor - Lot 5_JohnDon7.rvt
DATE: 5/24/2023 7:32:29 AM
DRAWN BY: Author



WALL FRAMING PLAN

SCALE: 1/8" = 1'-0"

WALL CONSTRUCTION: TYPICAL EXTERIOR WALL CONSTRUCTION SHALL BE 2x8 WOOD STUDS @ 16" MAXIMUM ON CENTER. MINIMUM (2) TRIMMER STUDS AND (2) KING STUDS SHALL BE PROVIDED AT ALL OPENINGS IN EXTERIOR, BEARING, AND SHEAR WALLS. TYPICAL INTERIOR SHEAR WALL CONSTRUCTION SHALL BE 2x6 WOOD STUDS @16 ON CENTER. REFERENCE HEADER SCHEDULE FOR CONDITIONS REQUIRING ADDITIONAL STUDS. DOUBLE TOP PLATE SHALL BE CONTINUOUS AND SHALL BE SPLICED PER TYPICAL DETAIL. SEE SHEAR WALL SCHEDULE FOR FURTHER INFORMATION ON CONSTRUCTION OF SHEAR WALLS.

VERIFY ALL DIMENSIONS SHOWN WITH ARCHITECTURAL AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION. INFORM ENGINEER OF ALL DISCREPANCIES.

NOTE: FACE OF STUD ALIGNS WITH THE CONCRETE SLAB EDGE FOR ALL EXTERIOR WALLS. ALL PLAN DIMENSIONS TO EXTERIOR WALLS ARE TO FACE OF STUD/FACE OF CONCRETE SLAB. ALL DIMENSIONS TO INTERIOR WALLS ARE TO FACE OF STUD/STRUCTURAL WALL.


WOOD SHEARWALL (SW) SCHEDULE							
MARK	STUD SIZE & SPACING	SHEATHING MATERIAL	EDGE NAILING	FIELD NAILING	COMPRESSION CHORD (MIN)	HOLDDOWN	SILL PLATE ANCHOR BOLT AT FDN
SW-1	2x8@16	1/2" OSB ZIP SYSTEM PANELS BLOCKED ONE SIDE OF WALL	8d COMMON @4" OC	8d COMMON @12" OC	(3) 2x8 WD STUDS	HDU8-SD2.5 7/8"Ø AB	5/8"Ø AB AT 1'-4" OR 3/4"Ø AB AT 2'-0" OC
SW-2	2x8@16	1/2" OSB ZIP SYSTEM PANELS BLOCKED ONE SIDE OF WALL	8d COMMON @6" OC	8d COMMON @12" OC	(2) 2x8 WD STUDS	HDU4-SD2.5 5/8"Ø AB	5/8"Ø AB AT 2'-0" OR 3/4"Ø AB AT 2'-8" OC
SW-3	2x6@16	1/2" (MIN) GYPSUM BOARD BLOCKED BOTH SIDES OF WALL	5d COOLER @7" OC	5d COOLER @7" OC	(2) 2x6 WD STUDS	HDU4-SD2.5 5/8"Ø AB	5/8"Ø AB AT 2'-0" OR 3/4"Ø AB AT 2'-8" OC

CERTUS
STRUCTURAL ENGINEERS
900 S. Kansas Avenue; Suite 400
Topeka, Kansas 66612
Phone: (785) 291-0400
Fax: (785) 291-0401
Proj #01190008.120
Certificate Of Authorization
E-1392
Revit 2023 Local

schwerdt design group
architecture | interiors | planning
2231 sw wanamaker rd suite 303
topeka, kansas 66614-4275
phone: 785.273.7540
fax: 785.273.7579
500 north broadway suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115

CORE & SHELL BUILDING FOR
STREETS OF WEST PRYOR LOT 5
LEE'S SUMMIT, MISSOURI

SUBMISSION DATES
2023-05-23
SHEET TITLE
WALL FRAMING PLAN
PROJECT NUMBER
230117
SHEET NUMBER
S-102



SCALE: 1/8" = 1'-0"

DESIGN ALL TRUSSES FOR 15 PSF NET UPLIFT.

PROVIDE BRIDGING AS PRESCRIBED BY THE TRUSS MANUFACTURER REQUIREMENTS.

TOS - TOP OF STEEL ELEVATION: NOTED THUS (ELEV)

TOP OF PARAPET = 125-0 (MAX)

TRUSS BEARING ELEVATION = 114'-4"

TYPICAL HEADERS IN OPENINGS LESS THAN 4'-0" SHALL BE (4) 2X8 OR DEEPER, ALL HEADERS IN OPENINGS UP TO 6'-6" SHALL BE (4) 2X10 OR DEEPER, ALL HEADERS IN OPENINGS UP TO 8'-4" SHALL BE (4) 2X12. CONSTRUCT HEADERS PER "TYPICAL HEADER CONSTRUCTION" DETAIL." ALL HEADERS SHALL HAVE (1) TRIMMER MINIMUM AND (2) DEDICATED STUDS MINIMUM. PROVIDE (2) TRIMMERS AT OPENINGS LARGER THAN 7'-4".

LINTELS: LOOSE BRICK LINTELS FOR DOOR AND WINDOW OPENINGS UP TO 8'-4" SHALL BE L5X5X3/8 GALVANIZED (ASTM A36)

DESIGN ROOF TRUSSES TO SUPPORT RTU LOADS AT LOCATIONS SHOWN. NOTIFY ENGINEER IF WEIGHTS, SIZES, OR LOCATIONS VARY FROM THAT SHOWN.

VERIFY ALL DIMENSIONS SHOWN WITH ARCHITECTURAL DRAWINGS PRIOR TO CONSTRUCTION. INFORM ENGINEER OF ALL DISCREPANCIES.

**CORE & SHELL BUILDING FOR
STREETS OF WEST PRYOR LOT 5
LEE'S SUMMIT, MISSOURI**

SUBMISSION DATES
2023-05-23


SHEET TITLE
ROOF FRAMING PLAN

PROJECT NUMBER
230117

SHEET NUMBER
S-103

CERTUS 
STRUCTURAL ENGINEERS
900 S. Kansas Avenue; Suite 400
Topeka, Kansas 66612
Phone: (785) 291-0400
Fax: (785) 291-0401
Proj #01190008.120
Certificate Of Authorization
E-1392
Revit 2023 Local

FILEPATH: C:\Users\John.Donaldson\Documents\01190008.120 - Streets of West Pryor - Lot 5_JohnDon7.rvt
DATE: 5/24/2023 7:32:31 AM
DRAWN BY: Author



ISOMETRIC VIEWS ARE INTENDED TO SHOW
GENERAL FRAMING CONFIGURATIONS AND
ARE FOR REFERENCE ONLY. IN NO WAY SHALL
THESE VIEWS BE USED TO CONVEY THE FULL
EXTENT OF FRAMING MATERIALS REQUIRED.
QUANTITY OF MATERIALS SHALL BE BASED
UPON STRUCTURAL PLANS, DETAILS,
ARCHITECTURAL DRAWINGS, AND THE FULL
EXTENT OF CONSTRUCTION DOCUMENTS.

① STRUCTURAL STEEL ISOMETRIC VIEW FROM SE CORNER
SCALE: NONE


CERTUS
STRUCTURAL ENGINEERS
900 S. Kansas Avenue; Suite 400
Topeka, Kansas 66612
Phone: (785) 291-0400
Fax: (785) 291-0401
Proj #01190008.120
Certificate Of Authorization
E-1392
Revit 2023 Local




CORE & SHELL BUILDING FOR
STREETS OF WEST PRYOR LOT 5
LEE'S SUMMIT, MISSOURI

SUBMISSION DATES 2023-05-23
SHEET TITLE FRAMING ISOMETRIC
PROJECT NUMBER 230117
SHEET NUMBER S-201


FILEPATH: C:\Users\John.Donaldson\Documents\01190008.120 - Streets of West Pryor - Lot 5_JohnDon7.rvt
DATE: 5/24/2023 7:32:33 AM
DRAWN BY: Author



A SECTION
SCALE: NONE




E SECTION
SCALE: NONE




NOTE: ALL SLABS ON GRADE SHALL BE CONSTRUCTED WITH CONTROL JOINTS IN SQUARE OR RECTANGULAR PATTERNS WITH A LENGTH TO WIDTH RATION OF 1 1/2 OR LESS. CONTROL JOINTS SHALL BE SPACED NO FURTHER APART THAN 10'-0". AT THE CONTRACTORS OPTION, CONSTRUCTION JOINT MAY BE USED IN LIEU OF ANY CONTROL JOINT.


3 TYPICAL CONCRETE SLAB JOINT DETAIL
SCALE: NONE



B SECTION
SCALE: NONE




F SECTION
SCALE: NONE




BP-1


4 BASEPLATE DETAILS
SCALE: NONE




BP-2




BP-3




C SECTION
SCALE: NONE




1 TYPICAL ANCHOR BOLT DETAIL
SCALE: NONE




D SECTION
SCALE: NONE



2 TYPICAL COLUMN ISOLATION IN SLAB ON GRADE DETAIL
SCALE: NONE



6 TYPICAL FOOTING STEP DETAIL
SCALE: NONE



5 TYPICAL CORNER REINFORCEMENT DETAIL (ONE CURTAIN)
SCALE: NONE


CERTUS
STRUCTURAL ENGINEERS
900 S. Kansas Avenue; Suite 400
Topeka, Kansas 66612
Phone: (785) 291-0400
Fax: (785) 291-0401
Proj #01190008.120
Certificate Of Authorization
E-1392
Revit 2023 Local




**CORE & SHELL BUILDING FOR
STREETS OF WEST PRYOR LOT 5**
LEE'S SUMMIT, MISSOURI

SUBMISSION DATES 2023-05-23
SHEET TITLE CONCRETE DETAILS & SECTIONS I
PROJECT NUMBER 230117
SHEET NUMBER S-301


FILEPATH: C:\Users\John.Donaldson\Documents\01190008.120 - Streets of West Pryor - Lot 5_JohnDon7.rvt
DATE: 5/24/2023 7:32:34 AM
DRAWN BY: Author




1 TYPICAL HOLDOWN ASSEMBLY
CORNER (ALTERNATE)
SCALE: NONE




2 NON-LOAD BEARING WALL LATERAL
SUPPORT DETAIL
SCALE: NONE



3 TYPICAL HEADER CONSTRUCTION DETAIL
SCALE: NONE




4 TYPICAL BUILT-UP HEADER CONSTRUCTION
SCALE: NONE




- NOTES:
1. SPLICE REQUIRED OVER ALL SHEARWALLS AND ALL EXTERIOR AND BEARING WALLS.
 2. SPECIFIC SPLICE REQUIREMENTS DO NOT APPLY TO INTERIOR NON-SHEARWALLS OR TOP OF PARAPET WALLS UNLESS NOTED OTHERWISE.


5 TYPICAL TOP PLATE SPLICE DETAIL
SCALE: NONE




6 TYPICAL SHEARWALL CONSTRUCTION
SCALE: NONE




7 TYPICAL CANOPY CONNECTION BLOCKING DETAIL
SCALE: NONE




8 TYPICAL SHEAR BLOCKING
BETWEEN TRUSSES
SCALE: NONE



9 TYPICAL SHEARWALL TERMINATION
AT STEEL COLUMN DETAIL
SCALE: NONE



10 TYPICAL TUBE COLUMN TO BEAM CONNECTION
SCALE: NONE



11 TYPICAL STEEL CONNECTIONS DETAIL (SHEAR TABS)
SCALE: NONE

BOLT SCHEDULE		
CONNECTION BEAM SIZE	LENGTH (L)	(#) ROWS OF BOLTS
W8, W10	6"	2
W12, W14	9"	3
W16	1'-0"	4
W18	1'-3"	5
W21	1'-6"	6
W24, W27	1'-9"	7
W30, W33	2'-6"	10


NOTE: BOLTS SHALL BE 3/4"Ø A325 AT 3" CENTERS, UNLESS NOTED OTHERWISE

CERTUS
STRUCTURAL ENGINEERS
900 S. Kansas Avenue; Suite 400
Topeka, Kansas 66612
Phone: (785) 291-0400
Fax: (785) 291-0401
Proj #01190008.120
Certificate Of Authorization
E-1392
Revit 2023 Local




CORE & SHELL BUILDING FOR
STREETS OF WEST PRYOR LOT 5
LEE'S SUMMIT, MISSOURI


SUBMISSION DATES 2023-05-23
SHEET TITLE FRAMING DETAILS & SECTIONS I
PROJECT NUMBER 230117
SHEET NUMBER S-601




D SECTION
SCALE: NONE




E SECTION
SCALE: NONE




G SECTION
SCALE: NONE



A SECTION
SCALE: NONE



B SECTION
SCALE: NONE



C SECTION
SCALE: NONE



**CORE & SHELL BUILDING FOR
STREETS OF WEST PRYOR LOT 5
LEE'S SUMMIT, MISSOURI**


SUBMISSION DATES
2023-05-23

SHEET TITLE
FRAMING DETAILS & SECTIONS II


PROJECT NUMBER
230117

SHEET NUMBER
S-602


FILEPATH: C:\Users\John.Donaldson\Documents\01190008.120 - Streets of West Pryor - Lot 5_JohnDon7.rvt
DATE: 5/24/2023 7:32:35 AM
DRAWN BY: Author



B SECTION
SCALE: NONE



C SECTION
SCALE: NONE



D SECTION
SCALE: NONE

CERTUS
STRUCTURAL ENGINEERS
900 S. Kansas Avenue; Suite 400
Topeka, Kansas 66612
Phone: (785) 291-0400
Fax: (785) 291-0401
Proj #01190008.120
Certificate Of Authorization
E-1392
Revit 2023 Local



**CORE & SHELL BUILDING FOR
STREETS OF WEST PRYOR LOT 5**
LEE'S SUMMIT, MISSOURI

SUBMISSION DATES 2023-05-23
SHEET TITLE FRAMING DETAILS & SECTIONS III
PROJECT NUMBER 230117
SHEET NUMBER S-603

15000 - MECHANICAL SPECIFICATIONS

- SECTION 15000 - MECHANICAL REQUIREMENTS
1. GENERAL REQUIREMENTS
- A. ALL WORK SHALL BE IN ACCORDANCE W/ LATEST EDITION OF INTERNATIONAL BUILDING, MECHANICAL & PLUMBING CODES, CODES AS ADOPTED BY CITY, COUNTY, STATE & ALL OTHER APPLICABLE CODES.
- B. FURNISH & INSTALL ALL LABOR & MATERIALS REQUIRED FOR COMPLETE, FUNCTIONING, MECHANICAL & PLUMBING SYSTEMS W/ ALL ASSOCIATED EQUIPMENT & APPARATUS AS SHOWN ON PLANS. PROVIDE MEANS TO FURNISH & INSTALL.
- C. OBTAIN & PAY FOR ALL PERMITS REQUIRED FOR EXECUTION OF THIS WORK & SHALL MAKE ARRANGEMENTS FOR MODIFICATIONS TO WATER, GAS & SEWER CONNECTIONS TO BUILDING AS REQUIRED.
- D. VISIT SITE & OBSERVE CONDITIONS UNDER WHICH WORK WILL BE DONE. ANY DISCREPANCIES SHALL BE CALLED TO ARCHITECT'S ATTENTION. NO SUBSEQUENT ALLOWANCE WILL BE MADE IN CONTRACT FOR ANY ERROR OR NEGLIGENCE ON CONTRACTOR'S PART.
- E. FINAL ACCEPTANCE OF WORK SHALL BE SUBJECT TO CONDITION THAT ALL SYSTEMS, EQUIPMENT, APPARATUS & APPLIANCES OPERATE SATISFACTORILY AS DESIGNED & INTENDED. WORK SHALL INCLUDE REQUIRED ADJUSTMENT OF SYSTEMS & CONTROL EQUIPMENT INSTALLED UNDER THESE SPECIFICATIONS.
- F. WARRANT TO OWNER QUALITY OF MATERIAL, EQUIPMENT, WORKMANSHIP & OPERATION OF EQUIPMENT PROVIDED UNDER THESE SPECIFICATIONS FOR ONE YEAR FROM & AFTER COMPLETION OF BUILDING & ACCEPTANCE OF MECHANICAL SYSTEMS BY OWNER.
- G. ALL MATERIALS INSTALLED IN PLENUMS SHALL BE NONCOMBUSTIBLE OR HAVE FLAME/SMOKE INDEX OF NO MORE THAN 25/50 IN ACCORDANCE W/ ASTM E 84.
- H. ROOF PENETRATIONS - MADE BY AUTHORIZED ROOFING CONTRACTOR WHEN REQUIRED.
- SECTION 15100 - PLUMBING
1. PIPING
- A. WATER PIPING - ALL WATER PIPING SHALL BE 3/8"-5" TIN-ANTIMONY JOINED TYPE L COPPER, INSULATE W/ FIBERGLASS W/ ASJ & PVC COVERS. THICKNESS IN ACCORDANCE W/ ASHRAE 90.1.
- B. WASTE & VENT PIPING - C) BELL & SPIGOT OR HUBLESS C) W/ NEOPRENE GASKET FITTINGS W/ STAINLESS STEEL BANDS. SCHED 40 PVC W/ SOLVENT WELDS MAY BE USED WHERE ALLOWED BY LOCAL CODE. PVC NOT ALLOWED IN PLENUMS.
- C. ROOF/STORM DRAIN PIPING - C) BELL & SPIGOT OR HUBLESS C) W/ NEOPRENE GASKET FITTINGS W/ STAINLESS STEEL BANDS. SCHED 40 PVC W/ SOLVENT WELDS MAY BE USED WHERE ALLOWED BY LOCAL CODE. PVC NOT ALLOWED IN PLENUMS. INSULATE W/ MIN 1/2" FIBERGLASS PIPE WRAP W/ ASJ JACKET.
- D. GAS PIPING - PROVIDE SCHED 40 CONT. WELD CARBON STEEL W/ CORRESPONDING FITTINGS. PROVIDE THREADED FITTINGS. PROVIDE IRON BODY-BRASS PLUG GAS STOPS. PAINT ALL EXPOSED GAS PIPING ON THE EXTERIOR OF THE BUILDING INCLUDING ON THE ROOF.
2. VALVES
- A. BALL VALVES - 2" & UNDER - BRONZE FULL PORT W/ TEFLON SEATS, BRONZE BALL & INSULATED HANDLE.
- B. BALANCING VALVES - ARMSTRONG MODEL CBV 1 OR CBV II, 125 PSI-WP AT 250 DEGREES F, WATER CONNECTIONS W/ BUILT-IN CHECK VALVES SCREWED OR FLANGED ENDS. PROVIDE POLYURETHANE INSULATION COVER.
- C. CHECK VALVES - 2" 7" SMALLER SCREWED OR SOLDER BRONZE CHECK VALVE, 200 PSI-WOG/125 PSI-WSP, TEFLON OR BRONZE DISC & SEAT RING, 2-1/2" & LARGER FLANGED, ASTM 128 IRON BODY, BRONZE TRIMMED, 200 PSI-WOG/125 PSI-WSP.
- D. BUTTERFLY VALVES - 3" & LARGER LEVER ASTM A126 C) DRILLED & TAPPED FULL LUG BODY, 200 PSI-WOG, EXTENDED NECK, BRONZE DISC, STAINLESS STEEL STEM, FIELD-REPLACABLE EPDM SLEEVE & STEM SEALS.
- E. EQUIVALENT VALVE MANUFACTURERS: MILWAUKEE, STOCKHAM, POWELL, RED-WHITE, CRANE, APOLLO, MUELLER, MUESCO, WATTS, HAYS, ROCKWELL-NORDSTROM.
- FITURES - SEE SCHEDULES
- A. FITURES: AMERICAN STANDARD, KOHLER, CRANE, ZURN, TOTO
- B. STAINLESS STEEL FITURES: ELKAY, JUST, MOEN COMMERCIAL
- C. FITTINGS & SUPPORTS: JOSAM, SMITH, WADE, ZURN, OR JONESPEC.
- D. SEATS, CHURCH, OLSONITE, BENS OR BENE.
- E. DRINKING FOUNTAINS: HALSEY TAYLOR, ELKAY, OASIS, OR HAWS.
- F. TRIM BY DELTA, ELVER, KOHLER, AMERICAN STANDARD, CRANE, SLOAN.
- G. FLUSHVALVES: SLOAN, ZURN, TOTO
- H. DRAINS BY WADE, ZURN, WOODFORD, SMITH, JOSAM.
- I. ROOF DRAINS - CAST IRON ROOF DRAIN W/ FLANGE, C) MUSHROOM DOME, 2" DAM FOR OVERFLOW DRAINS
- J. WALL HYDRANTS JOSAM SERIES 71000 W/ CONNECTIONS FOR 3/4" PIPE & HOSE. NON-FREEZING W/ KEY, VACUUM BREAKER, LOCKING COVER. EQUIVALENT BY J.R. SMITH, WADE, WOODFORD OR ZURN.
- EQUIPMENT - SEE SCHEDULES

16000 - ELECTRICAL SPECIFICATIONS

- SECTION 16000 - ELECTRICAL REQUIREMENTS
- GENERAL REQUIREMENTS
- A. ALL WORK SHALL BE IN ACCORDANCE W/ LATEST EDITION OF INTERNATIONAL BUILDING CODE, NATIONAL ELECTRICAL CODE, NFPA CODES AS ADOPTED BY CITY, COUNTY, STATE & ALL OTHER APPLICABLE CODES.
- B. ALL MATERIALS & EQUIPMENT SHALL BE NEW & SHALL BEAR U.L. LABEL WHERE APPLICABLE. PROVIDE WATERPROOF EQUIPMENT ENCLOSURES WHERE REQUIRED.
- C. OBTAIN & PAY FOR ALL PERMITS REQUIRED FOR EXECUTION OF THIS WORK & SHALL MAKE ARRANGEMENTS FOR MODIFICATIONS TO ELECTRICAL CONNECTIONS TO BUILDING AS REQUIRED.
- D. CONTRACTOR SHALL PROVIDE ALL LABOR & MATERIALS REQUIRED TO HAVE COMPLETE FUNCTIONING ELECTRICAL LIGHTING & POWER SYSTEMS TOGETHER W/ ALL ASSOCIATED EQUIPMENT & APPARATUS AS SHOWN ON PLANS.
- E. WHERE AN ELECTRICAL DEVICE IS REQUIRED BY CODE BUT NOT SHOWN, IT SHALL BE PROVIDED AS THOUGH FULLY SHOWN & SPECIFIED.
- F. CONTRACTOR SHALL VISIT SITE & OBSERVE CONDITIONS UNDER WHICH WORK WILL BE DONE. ANY DISCREPANCIES SHALL BE CALLED TO ARCHITECT'S ATTENTION. NO SUBSEQUENT ALLOWANCE WILL BE MADE IN THIS CONNECTION FOR ANY ERROR OR NEGLIGENCE ON CONTRACTOR'S PART.
- G. FINAL ACCEPTANCE OF WORK SHALL BE SUBJECT TO CONDITION THAT ALL SYSTEMS, EQUIPMENT, APPARATUS & APPLIANCES OPERATE SATISFACTORILY AS DESIGNED & INTENDED. WORK SHALL INCLUDE REQUIRED ADJUSTMENT OF SYSTEMS & CONTROL EQUIPMENT INSTALLED UNDER THESE SPECIFICATIONS.
- H. WARRANT TO OWNER QUALITY OF MATERIALS, EQUIPMENT, WORKMANSHIP & OPERATION OF EQUIPMENT PROVIDED UNDER THESE SPECIFICATIONS FOR ONE YEAR FROM & AFTER COMPLETION OF BUILDING & ACCEPTANCE OF MECHANICAL SYSTEMS BY OWNER.
- I. ALL MATERIALS INSTALLED IN PLENUMS SHALL BE NONCOMBUSTIBLE OR HAVE FLAME/SMOKE INDEX OF NO MORE THAN 25/50 IN ACCORDANCE W/ ASTM E 84.
- SECTION 16100 - CONDUIT & CONDUCTORS
- A. FOLLOW CIRCUITING SHOWN ON PLANS. USE NO CONDUIT SMALLER THAN 1/2" & NO CONDUCTORS SMALLER THAN #12 GA UNLESS NOTED OTHERWISE.
- B. WIRE SHALL BE IN NON-FLEXIBLE METALLIC CONDUIT (EMT, IMC OR RMC) FOR ALL CIRCUITS AND FEEDERS GREATER THAN 30A, LIGHT SWITCH RISERS, KITCHEN CIRCUITS & HOME RUNS.
- C. MC CABLE ACCEPTABLE FOR BRANCH CONVENIENCE CIRCUITS AND LIGHTING CIRCUITS. DO NOT DASHY CHAIN LIGHT FIXTURES. PROVIDE MC LUMINARY CABLE WITH BUILT-IN TWISTED JACKETED PAIR FOR LIGHTING CIRCUITS FOR LIGHTING CONTROLS. PROVIDE HEALTH CARE RATED MC FOR MEDICAL TREATMENT AREAS WHEN NOT IN CONDUIT.
- D. CONDUIT INSTALLED BELOW GRADE SHALL BE SCHEDULE 80 PVC HEAVY WALL PLASTIC CONDUIT MEETING NEMA STANDARDS & UL LISTED FOR UNDERGROUND & EXPOSED USE. PROVIDE OIS RADIUS BENDS & RISERS AS CONDUITS RISE ABOVE GRADE OR ABOVE FLOOR SLAB.
- E. PROVIDE INTERLOCKING SPACERS FOR MULT RUNS OF UG CONDUITS IN SAME TRENCH.
- F. LIGHTING & RECEPTACLE CIRCUIT CONDUCTORS SHALL BE COPPER THIN/THIN 600 VOLT, 75 DEG C. COLOR CODED AS DESCRIBED UNDER APPLICABLE CODES. NO ROMEX, PLASTIC FLEX TUBING ETC PERMITTED. LIGHT FIXTURE WIRE INSULATION SHALL HAVE TAMP RATING NOT LESS THAN INDIVIDUAL FIXTURE MANUF RECOMMENDED RATING.
- G. CIRCUITS W/ NO. 8 OR LARGER CONDUCTORS, MOTOR CIRCUITS, POWER & FEEDER CIRCUITS & BUILDING SERVICE FEEDERS SHALL BE COPPER THIN/THIN 600 VOLT, 75 DEG C.
- H. ALL CONDUIT, JUNCTION BOXES, ETC. ABOVE CEILINGS SHALL BE SUPPORTED FROM STRUCTURE. PIPE SLEEVES, HANGERS & SUPPORTS SHALL BE FURNISHED & SET & CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER & PERMANENT LOCATIONS.
- SECTION 16200 - GROUNDING
- A. SUPPLEMENT GROUNDING NEUTRAL OF SECONDARY DISTRIBUTION SYSTEM W/ EQUIPMENT GROUNDING SYSTEM, INSTALLED SO THAT METALLIC STRUCTURES, ENCLOSURES, RACKWAYS, JUNCTION BOXES, OUTLET BOXES, CABINETS, MACHINE FRAMES, PORTABLE EQUIPMENT & OTHER CONDUCTIVE ITEMS OPERATE CONTINUOUSLY AT GROUND POTENTIAL & PROVIDE LOW IMPEDANCE PATH FOR GROUND FAULT CURRENTS.
- B. SYSTEM SHALL COMPLY W/ NATIONAL ELECTRICAL CODE, DRAWINGS & AS SPECIFIED.
- C. PROVIDE EQUIPMENT GROUND BUS IN BASE OF LOW VOLTAGE SWITCHGEAR BRAZED OR OTHERWISE ADEQUATELY CONNECTED BY AN APPROVED METHOD TO GROUND RODS.
- D. PROVIDE IN CONDUIT GREEN INSULATED COPPER GROUND CONDUCTOR TO MAIN METALLIC WATER SERVICE ENTRANCE & CONNECT BY MEANS OF ADEQUATE GROUND CLAMPS.
- E. EQUIPMENT GROUNDING CONDUCTORS FOR BRANCH CIRCUIT HOME RUNS SHOWN ON DRAWINGS SHALL INDICATE AN INDIVIDUAL & SEPARATE GROUND CONDUCTOR FOR THAT BRANCH CIRCUIT WHICH SHALL BE TERMINATED AT BRANCH CIRCUIT PANELBOARD, SWITCHBOARD, OR OTHER DISTRIBUTION EQUIPMENT.
- F. PROVIDE LOW VOLTAGE DISTRIBUTION SYSTEM W/ SEPARATE GREEN INSULATED EQUIPMENT GROUNDING CONDUCTOR FOR EACH SINGLE OR THREE-PHASE FEEDER.

- SINGLE PHASE 120 VOLT BRANCH CIRCUITS FOR LIGHTING & POWER SHALL CONSIST OF PHASE & NEUTRAL CONDUCTORS & GREEN GROUND CONDUCTOR INSTALLED IN COMMON CONDUIT WHICH SHALL SERVE AS GROUNDING CONDUCTOR.
- G. GROUNDING CONDUCTORS SHALL BE AS SHOWN ON PLANS OR IF NOT SPECIFICALLY SHOWN SHALL BE NO SMALLER THAN THAT REQUIRED BY NEC.
- SECTION 16300 - ELECTRICAL EQUIPMENT
- A. JUNCTION BOXES & OUTLET BOXES SHALL BE GALVANIZED KNOCKOUT TYPE. LIGHTING FIXTURE BOXES IN CEILINGS SHALL NOT BE LESS THAN 4" OCTAGONAL KNOCKOUT TYPE. OUTLETS SHALL BE INSTALLED IN LOCATIONS SHOWN ON DRAWINGS EXCEPT OUTLETS MAY BE MOVED 4 FEET IN EITHER DIRECTION IF SO DIRECTED, WITHOUT ADDITIONAL COST. BOXES SHALL BE FLUSH MOUNTED ON WALLS FOR CONCEALED WORK. GANGLABLE BOXES SHALL BE USED IN ALL CYPRBOARD SURFACES.
- PANELBOARDS
- A. BRANCH CIRCUIT 208/240V PANELS SHALL BE CAPACITY SHOWN W/ TIN PLATED COPPER BUSSING & BRACED FOR MINIMUM OF 22,000A AIC OR AS OTHERWISE NOTED OR REQUIRED (SERIES RATED ACCEPTABLE). BOLT ON CIRCUIT BREAKERS. 480V PANELS SAME EXCEPT 25,000A AIC MIN. MINIMUM 20" WIDE W/ GALV STEEL ENCLOSURE W/ HINGED DOOR & KEVED LOCK. COORD TRIM WITH MOUNTING LOCATION. PANELS TO BE RECESSED WHENEVER POSSIBLE.
- B. DISTRIBUTION PANELS SHALL BE CAPACITY SHOWN & SHALL BE SQUARE D I-LINE W/ TIN PLATED COPPER BUSSING. 480V MIN OR AS OTHERWISE NOTED/REQD. BOLT ON CIRCUIT BREAKERS (SERIES RATED ACCEPTABLE), GALV STEEL ENCLOSURE.
- C. EQUIVALENT BY SQUARE D, SIEMENS, CUTLER HAMMER, OR GE.
- SECTION 16350 - ELECTRICAL IDENTIFICATION
- A. MANUFACTURED LABELS FOR EACH PANELBOARD & TRANSFORMER. TYPEWRITTEN PANEL SCHEDULES MOUNTED IN PANELS.
- B. PRINTED TAPE STYLE LABEL FOR EACH RECEPTACLE INDICATING PANEL & CIRCUIT #.
- C. MANUFACTURED LABELS FOR ALL DISCONNECT SWITCHES INDICATING EQUIPMENT SERVED.
- D. BRANCH CIRCUITS - IDENTIFY EACH CIRCUIT W/ WIRE MARKERS WHEN ENCLOSURE LABEL AND WIRE COLORS DO NOT PROVIDE ENOUGH INFORMATION TO IDENTIFY EACH CIRCUIT WITHOUT TRACING. FEEDERS & BRANCH CIRCUIT HOME RUNS W/ WIRE MARKER W/ PANEL & CKT #. BOX COVERS ABOVE LAY-IN CEILINGS NEATLY MARKED W/ INDELEBLE MARKER.
- SECTION 16400 - WIRING DEVICES
- A. CONVENIENCE OUTLETS - SPEC GRADE 20 AMP DUPLEX W/ GROUND & SS WALL PLATES. OTHER OUTLETS SHALL BE VERIFIED W/ EQUIPMENT SUPPLIERS FOR PROPER NEMA CONFIGURATIONS. PROVIDE GFC RATED DEVICES WHERE INDICATED AND AS REQD PER CODE.
- B. PROVIDE GFC RATED DEVICES WHERE INDICATED AND ANYWHERE REQUIRED PER THE NEC.
- C. PROVIDE AFCI PROTECTION ON ALL CIRCUITS REQUIRED PER THE NEC.
- D. PROVIDE TAMPER RESISTANT RECEPTACLES ON ALL RECEPTACLES IN PUBLIC AREAS, AREAS ACCESSIBLE TO CHILDREN, AND WHERE OTHERWISE REQUIRED TO BE TAMPER RESISTANT PER THE NEC.
- E. LIGHT SWITCHES - SPEC GRADE 20 AMP TOGGLE SWITCHES W/ SS WALL PLATES.
- F. WALL MOTION SWITCHES - SPEC GRADE, PIR, OVERMOLD.
- G. CEILING MOTION SWITCHES - SPEC GRADE, DUAL TECHNOLOGY, MODEL AS REQD BY ROOM CONFIGURATION, ALL NECESSARY POWER PACKS AND RELAYS.
- H. WALL MOTION SWITCHES (BATHROOM) - DUAL RELAY, SPEC GRADE, PIR, 2ND RELAY FOR OPERATION OF EXHAUST FAN DELAY.
- I. COLOR OF DEVICES AS DIRECTED BY ARCHITECT.
- J. EQUIVALENT DEVICES BY LEVITON, BRYANT, HUBBELL, WATTSOPPER, LITHONIA, SENSOR SWITCH.
- EXECUTION
- A. ALL OUTLETS, SHALL BE MOUNTED W/ BOTTOM AT 18" AFF & SWITCHES W/ BOTTOM AT 44" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE ON PLANS. REFER TO ARCH FOR OTHER REQUIRED ELEVATIONS AND CABINTRY COORDINATION.
- SECTION 16500 - LED LUMINAIRES
- LUMINAIRES
- A. PROVIDE LIGHTING FIXTURES W/ ALL ACCESSORIES REQD FOR HANGING. COORD MOUNTING OF LIGHTING FIXTURES W/ ARCHITECT & G/C. ADDITIONAL FIXTURE SUPPORTS SHALL BE PROVIDED BY E/C. SUPPORTS SHALL COMPLY W/ LATEST EDITION OF NEC. PROVIDE LIGHTING FIXTURE SECURITY CLIPS AS REQUIRED. CONSULT ARCH PLANS FOR CEILING TYPES & PROVIDE SURFACE & RECESSED LIGHTING FIXTURES W/ APPROPRIATE MOUNTING COMPONENTS & ACCESSORIES.
- B. REFER TO LIGHTING FIXTURE SCHEDULE PLANS FOR FIXTURE TYPES.
- C. EQUIVALENT LUMINAIRES BY CREC, COOPER, HUBBELL, INFINITY, LITHONIA, WILLIAMS, COLUMBIA, EXTRONICS, LITELARM, EXIDE, MULE, DUALITE.

ELECTRICAL SYMBOL LEGEND

SOME SYMBOLS AND ABBREVIATIONS ON THIS LEGEND MAY NOT BE USED

CIRCUITING

INDICATES 2 PHASE, 1 N, & 1 GRD CONDUCTOR

HOME RUN: INDICATES SHARED CIRCUIT

HOME RUN: INDICATES #10 CONDUCTORS ENTIRELY

UTILITIES

UNDERGROUND ELECTRICAL

OVERHEAD ELECTRICAL

TELECOMMUNICATIONS CONDUIT

UNDERGROUND TELECOMMUNICATIONS CONDUIT

LIGHTING

SURFACE/RECESSED LIGHT FIXTURE

WALL-MOUNTED LIGHT FIXTURE

POLE-MOUNTED LIGHT FIXTURE

TIMECLOCK - REFER TO PLANS / DETAILS

EQUIPMENT

DISCONNECT SWITCH. RE: PLANS FOR INFORMATION.

MAGNETIC MOTOR STARTER

COMBINATION DISCONNECT SWITCH / MOTOR STARTER

TOGGLE-TYPE DISCONNECT. FURNISH WITH THERMAL MOTOR PROTECTION WHERE SERVING FANS/PUMPS.

SURFACE PANELBOARD

RECESSED PANELBOARD

DISTRIBUTION PANELBOARD

SWITCHBOARD. FEEDER/MAIN CIRCUIT BREAKER SECTION AND DISTRIBUTION SECTION.

GENERAL SYMBOLS

INDICATES CONNECT TO EXISTING

INDICATES ELEVATION

POWER DEVICES

DUPLEX RECEPTACLE

LINE THRU DEVICE INDICATES ABOVE COUNTER

SPECIAL DUPLEX RECEPTACLE (GFCI, ISOLATED GROUND, ETC.)

QUADPLEX RECEPTACLE

SIMPLEX RECEPTACLE W/NEMA CONFIG AS NOTED

MULTI-POLE RECEPTACLE W/NEMA CONFIG AS NOTED

CEILING MOUNTED RECEPTACLE

RECEPTACLE/DEVICE MOUNTED IN "TOMBSTONE"

POKE-THRU WITH POWER

POKE-THRU WITH TELECOMMUNICATIONS

POKE-THRU W/POWER AND TELECOM

SINGLE GANG FLOOR BOX (2, 3, 4 GANG SIMILAR)

DIVIDED POWER POLE

CLOCK RECEPTACLE

PLUG MOLD / WIRE MOLD AS SPECIFIED

JUNCTION BOX

THERMOSTAT - ELECTRIC

PUSH BUTTON

MOTOR

FIRE ALARM

DUCT SMOKE DETECTOR

MECHANICAL AND PLUMBING SYMBOL LEGEND

SOME SYMBOLS AND ABBREVIATIONS ON THIS LEGEND MAY NOT BE USED

SHEET METAL

HIGH EFFICIENCY ROUND DUCT TAKEOFF (WITH & WITHOUT MANUAL DAMPER)

SPIN-IN ROUND DUCT TAKEOFF (WITH & WITHOUT MANUAL DAMPER)

CONICAL BELLMOUTH ROUND TAKEOFF

ROUND DUCT RUNOUT WITH FLEX DUCT

DUCTWORK ELBOW (WITH & WITHOUT TURNING VANES)

RETURN GRILLE OR EXHAUST REGISTER

SUPPLY AIR FLOW INDICATOR

RETURN AND EXHAUST AIR FLOW INDICATOR

THERMOSTAT

TEMPERATURE SENSOR

HUMIDISTAT

CONTROL WIRING

GENERAL SYMBOLS

INDICATES CONNECT TO EXISTING

INDICATES ELEVATION

PLUMBING FIXTURES/EQUIPMENT

HOSE BIBB

WALL HYDRANT

CLEAN OUT

REDUCED PRESSURE BACKFLOW PREVENTER

DOUBLE CHECK BACKFLOW PREVENTER

PLUMBING FIXTURE AND CALLOUT

FD: FLOOR DRAIN, AD: AREA DRAIN, FS: FLOOR SINK

RD: ROOF DRAIN

ORD: OVERFLOW ROOF DRAIN

MECHANICAL PIPING

REFRIGERANT LIQUID

REFRIGERANT SUCTION

DRAIN (CONDENSATE)

COMPRESSED AIR

REFRIGERANT VENT

RUPTURE DISK

PLUMBING PIPING

DOMESTIC COLD WATER

DOMESTIC HOT WATER

RECIRCULATING DOMESTIC HOT WATER

WASTE ABOVE GRADE OR FLOOR

WASTE BELOW GRADE OR FLOOR

STORM ABOVE GRADE OR FLOOR

STORM BELOW GRADE OR FLOOR

STORM OVERFLOW ABOVE GRADE OR FLOOR

STORM OVERFLOW BELOW GRADE OR FLOOR

PLUMBING VENT

WATER SERVICE

GAS (NATURAL)

PIPING SYMBOLS

SHUTOFF VALVE

SHUTOFF VALVE IN RISER

BALANCING VALVE

PLUG VALVE

AUTO FLOW CONTROL VALVE

PIPING ELBOW UP

PIPING ELBOW DOWN

PIPING TEE

PIPING ELBOW

PIPING TEE UP

PIPING TEE DOWN

INCREASER / REDUCER

UNION

CAP

PIPE FLEX

STRAINER

CHECK VALVE

INLINE STRAINER

TEST PLUG

PIPING SPECIALTIES

LOW

PRESSURE REDUCING VALVE

ABBREVIATIONS

A/E	ARCHITECT / ENGINEER	EW	ENTERING WATER TEMPERATURE	PSI	POUNDS PER SQUARE INCH
AF	ABOVE FINISHED FLOOR	EX	EXISTING ITEM	PVC	POLYVINYLCHLORIDE
AG	ABOVE GRADE	FFA	FROM FLOOR ABOVE	RA	RETURN AIR
AH	AUTHORITY HAVING JURISDICTION	FTB	FROM FLOOR BELOW	RE/REF	REFER / REFERENCE
ARCH	ARCHITECT	FFCO	FINISHED FLOOR CLEAN OUT	RF	RELIEF FAN
BFP	BACKFLOW PREVENTER	FGO	FLUSH GRADE CLEAN OUT	RL	RELOCATED ITEM
BG	BELOW GRADE	FL	FLOOR LINE	RPZ	REDUCED PRESSURE ZONE
BLDG	BUILDING	FLR	FLOOR	RR	RESTROOM
BMS	BUILDING MANAGEMENT SYSTEM	FTM	FEET PER MINUTE	SA	SUPPLY AIR
C	CONDUIT	FWCO	FLUSH WALL CLEAN OUT	SPD	SURGE PROTECTIVE DEVICE
CD	CANDELA	G	GROUND / GANG	TA	TRANSFER AIR
CD	COLD DECK	G/C	GENERAL CONTRACTOR	TFA	TO FLOOR ABOVE
CLG	COOLING	GFCI	GROUND FAULT CIRCUIT INTERRUPTER	TFB	TO FLOOR BELOW
CM	COORDINATE MOUNTING HEIGHT	GPM	GALLONS PER MINUTE	TP	TAMPERPROOF
CO	CLEAN OUT	HD	HOT DECK	TYP	TYPICAL
CTE	CONNECT TO EXISTING	HTG	HEATING	UNO	UNLESS NOTED OTHERWISE
DCVA	DOUBLE CHECK VALVE ASSEMBLY	IG	ISOLATED GROUND	VTR	VENT THROUGH ROOF
DCW	DOMESTIC COLD WATER	JB	JUNCTION BOX	WP	WEATHERPROOF
DDC	DIRECT DIGITAL CONTROLS	LED	LIGHT EMITTING DIODE		
DF	DRINKING FOUNTAIN	LWT	LEAVING WATER TEMPERATURE		
DHW	DOMESTIC HOT WATER	M/C	MECHANICAL CONTRACTOR		
DHW	DOMESTIC HOT WATER RETURN	MCB	MAIN CIRCUIT BREAKER		
DA	DAMETER	MECH	MECHANICAL		
DN	DOWN	MH	MANHOLE		
E/C	ELECTRICAL CONTRACTOR	MLO	MAIN LUGS ONLY		
EA	EXHAUST AIR	NFA	NET FREE AREA		
ELEV	ELEVATION	OA	OUTSIDE AIR		
EM	EMERGENCY FIXTURE/DEVICE	ORD	OVERFLOW ROOF DRAIN		
		P/C	PLUMBING CONTRACTOR		

schwerdt design group

architecture|interiors|planning

2231 sw wanamaker dr. suite 303
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.5779

500 north broadway suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115

STATE OF MISSOURI

BRYAN LEINWETTER - Engineer
NUMBER
PE-2020020297

05/23/23

Bryan Leinwetter - Engineer
MCM PE-2020020297

CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, MISSOURI

SUBMISSION DATES
MAY 23, 2023

SHEET TITLE
MECHANICAL AND ELECTRICAL SPECIFICATIONS

PROJECT NUMBER
230117

SHEET NUMBER
ME-101

FIRE SEALING NOTES

- COORDINATE CONSTRUCTION OF OPENINGS AND PENETRATING ITEMS TO ENSURE THAT THROUGH-PENETRATION FIRESTOP SYSTEMS ARE INSTALLED ACCORDING TO SPECIFIED AND APPLICABLE UL REQUIREMENTS.
- COORDINATE SIZING OF SLEEVES, OPENINGS, CORE-DRILLED HOLES, OR CUT OPENINGS TO ACCOMMODATE THROUGH-PENETRATION FIRESTOP SYSTEMS.
- DO NOT COVER UP THROUGH-PENETRATION FIRESTOP SYSTEM INSTALLATIONS UNTIL EXAMINED BY INSPECTOR, IF REQUIRED BY AUTHORITIES HAVING JURISDICTION.
- COMPATIBILITY: PROVIDE THROUGH-PENETRATION FIRESTOP SYSTEMS THAT ARE COMPATIBLE WITH ONE ANOTHER, WITH THE SUBSTRATES FORMING OPENINGS, AND WITH THE ITEMS, IF ANY, PENETRATING THROUGH-PENETRATION FIRESTOP SYSTEMS, UNDER CONDITIONS OF SERVICE AND APPLICATION, AS DEMONSTRATED BY THROUGH-PENETRATION FIRESTOP SYSTEM MANUFACTURER BASED ON TESTING AND FIELD EXPERIENCE.
- PROVIDE COMPONENTS FOR EACH THROUGH-PENETRATION FIRESTOP SYSTEM THAT ARE NEEDED TO INSTALL FILL MATERIALS, USE ONLY COMPONENTS SPECIFIED BY THROUGH-PENETRATION FIRESTOP SYSTEM MANUFACTURER AND APPROVED BY QUALIFIED TESTING AND INSPECTING AGENCY FOR FIRESTOP SYSTEMS INDICATED.
- PROVIDE SLEEVES THROUGH ALL FIRE-RATED WALLS AND FILL VOIDS SURROUNDING SLEEVES AND INTERIOR TO SLEEVES AROUND PIPING WITH FIRE STOP PUTTY WITH U.L. LISTED 3 HOUR RATING INSTALLED AS PER MANUFACTURERS RECOMMENDATIONS.
- FIRE SEAL ALL PIPING, CONDUIT, CABLE, ETC PENETRATIONS ROUTED THROUGH FIRE RATED WALLS.
- PROVIDE FIRE RATED ENCLOSURES OR WRAPS ON LIGHT FIXTURES AND OTHER ITEMS PENETRATING FIRE RATED CEILINGS, FLOOR/CEILING/ CEILING/ROOF ASSEMBLIES TO MAINTAIN UL LISTING FOR CONSTRUCTION.

GENERAL ELECTRICAL NOTES

- COMPLETE INSTALLATION SHALL BE IN ACCORDANCE WITH THE LATEST ADOPTED VERSION OF THE NATIONAL ELECTRICAL CODE, LOCAL AND STATE CODES, AND REQUIREMENTS OF THE A/E.
- COORDINATE LOCATIONS OF RECEPTACLES, SWITCHES, ETC. WITH ARCHITECTURAL CASEWORK AND ELEVATIONS.
- REFER TO MOUNTING HEIGHTS DETAIL FOR MOUNTING HEIGHTS OF ALL DEVICES NOT INDICATED OTHERWISE.
- PROVIDE ALL EMPTY CONDUITS WITH PULL STRINGS AND BUSHED ENDS.
- CONTRACTOR SHALL CONCEAL ALL CONDUIT, FITTINGS, AND DEVICES FROM VIEW WHERE REASONABLY POSSIBLE.

GENERAL NOTES

- SOME ROOM NAMES MAY NOT BE SHOWN FOR PURPOSE OF CLARIFYING PLAN. REFER TO ARCHITECTURAL PLANS FOR REFERENCE TO ROOM NAMES NOT SHOWN.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN AND KEEP AT THE JOB SITE AN UP TO DATE SET OF "RECORD DRAWINGS" SHOWING ALL CHANGES FROM THE ORIGINAL PLANS. THE CONTRACTOR SHALL DELIVER THE "RECORD DRAWINGS" TO THE ENGINEER AT THE CONCLUSION OF THE PROJECT ELECTRONICALLY.
- THESE DRAWINGS ARE DIAGRAMMATIC. THE CONTRACTOR SHALL VERIFY ALL CONDITIONS (NEW AND EXISTING), DIMENSIONS, AND CLEARANCES PRIOR TO THE COMMENCEMENT OF WORK AND SHALL INCLUDE ALL COSTS, EQUIPMENT, MATERIAL, ACCESSORIES, ETC. REQUIRED FOR A FULLY COMPLETE, FUNCTIONAL AND CODE COMPLIANT INSTALLATION.
- FINAL LOCATIONS OF ALL DEVICES, LIGHT FIXTURES, EQUIPMENT ETC. SHALL BE INDICATED ON THE ARCHITECTURAL DRAWINGS. ALL DIMENSIONAL INFORMATION SHALL BE OBTAINED FROM ARCHITECTURAL PLANS. NO DIMENSIONAL INFORMATION SHALL BE OBTAINED FROM MEP DRAWINGS.
- THE CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS, APPROVALS, LICENSES, ETC. AS NEEDED FOR THE COMPLETE INSTALLATION AND PROJECT. THE CONTRACTOR SHALL COORDINATE WITH THE OWNER FOR ALL FEES AND DATA NEEDED FOR THIS.

GEN. MECHANICAL NOTES


- COMPLETE INSTALLATION SHALL BE IN ACCORDANCE WITH THE LATEST ADOPTED VERSION OF THE INTERNATIONAL MECHANICAL CODE, LOCAL AND STATE CODES, AND REQUIREMENTS OF THE A/E.
- ANY POWER FOR CONTROL SYSTEMS TO BE PROVIDED BY E/C IS INDICATED ON ELECTRICAL PLANS. ANY ADDITIONAL LINE VOLTAGE OR LOW VOLTAGE POWER REQUIRED BY THE M/C OR SUBCONTRACTORS TO HAVE A FULLY FUNCTIONING SYSTEM SHALL BE PROVIDED BY THE M/C CONTRACTOR OR SUBS.
- ALL EQUIPMENT SHALL BE ADEQUATELY AND PROPERLY SUPPORTED AND FASTENED FROM STRUCTURE.
- ALL EQUIPMENT AND ACCESSORIES INSTALLED IN CONCEALED SPACES REQUIRING ACCESS SHALL BE PROVIDED WITH ACCESS DOORS MEETING ANY FIRE REQUIREMENTS OF THE WALL/CEILING THEY ARE INSTALLED.
- EACH AIR HANDLING UNIT OVER 2000CFM SHALL BE PROVIDED WITH A SMOKE DETECTOR TO SHUT DOWN THE UNIT PER IMC 606 AS REQUIRED BY A/E. COORDINATE WITH OTHER TRADES.
- START UP AND ADJUST ALL EQUIPMENT AND VERIFY ALL MECHANICAL SYSTEMS IN OPERATE IN ACCORDANCE WITH THEIR INTENDED PURPOSES. SUBMIT BALANCE AND START UP REPORTS TO THE A/E. REFER TO SPECIFICATIONS FOR ANY ADDITIONAL REQUIREMENTS.

GENERAL PLUMBING NOTES

- COMPLETE INSTALLATION SHALL BE IN ACCORDANCE WITH THE LATEST ADOPTED VERSION OF THE INTERNATIONAL PLUMBING CODE, LOCAL AND STATE CODES, AND REQUIREMENTS OF THE A/E.
- NO PIPING SHALL BE INSTALLED WHERE IT WILL SUBJECT TO FREEZING TEMPERATURES. PIPING IN EXTERIOR WALLS SHALL BE INSTALLED ON THE WARM SIDE OF BUILDING INSULATION, INSULATED AND THE CHASE SHALL BE VENTILATED WITH GRILLES ALLOWING INDOOR AMBIENT CONDITIONS TO CIRCULATE THROUGH THE CHASE.
- PROVIDE CLEANOUTS IN THE FOLLOWING LOCATIONS:
 - IN ALL HORIZONTAL DRAINS (WITHIN THE BUILDING) NOT MORE THAN 100 FEET APART.
 - IN BUILDING SEWERS LOCATED NO MORE THAN 100 FEET APART MEASURED FROM THE UPSTREAM ENTRANCE OF THE CLEANOUT.
 - EACH CHANGE OF DIRECTION OF THE BUILDING DRAIN OR HORIZONTAL WASTE OR SOIL LINES GREATER THAN 45 DEGREES WHERE MORE THAN ONE CHANGE OF DIRECTION OCCURS IN A RUN OF PIPING, ONLY ONE CLEANOUT SHALL BE REQUIRED FOR EACH 40 FEET OF DEVELOPED LENGTH OF THE DRAINED PIPING.
 - AT THE BASE OF EACH WASTE OR SOIL STACK.
 - NEAR THE JUNCTION OF THE BUILDING DRAIN AND BUILDING SEWER.

COORDINATION NOTES

- COORDINATE REQUIREMENTS FOR INSTALLATION OF SYSTEMS AND EQUIPMENT WITH ALL OTHER TRADES.
- THE CONTRACTOR SHALL COORDINATE THE ROUTING AND PATH OF ALL SYSTEMS, CONDUITS, PIPES, DUCTS, ETC. WITH THE POSITION AND LAYOUT OF THE STRUCTURE. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING NECESSARY OFFSETS, TURNS, RISERS AND DROPS FOR SYSTEMS AND COMPONENTS AS NEEDED TO INSTALL THE MEP SYSTEMS TO CLEAR STRUCTURE, CEILINGS, ETC. AND OTHER SYSTEMS IN POTENTIAL CONFLICT WITH ROUTING.
- COORDINATE WORK WITH OTHER TRADES TO INSTALL SYSTEMS ABOVE CEILING HEIGHTS INDICATED ON ARCHITECTURAL PLANS.
- CHECK SPACE REQUIREMENTS WITH OTHER TRADES AND STRUCTURE/CONSTRUCTION TO INSURE THAT ALL MATERIALS AND EQUIPMENT CAN BE INSTALLED IN THE SPACE ALLOTTED INCLUDING FINISHED SUSPENDED CEILINGS AND OTHER SPACES, CHASES, ETC. WITHIN THE BUILDING. MAKE MODIFICATIONS THERETO AS REQUIRED AND APPROVED.
- TRANSMIT TO OTHER TRADES ALL INFORMATION REQUIRED FOR WORK TO BE PROVIDED UNDER THEIR RESPECTIVE SECTIONS IN AMPLE TIME FOR INSTALLATION.
- WHEREVER WORK INTERCONNECTS WITH WORK OF OTHER TRADES, COORDINATE WITH THOSE TRADES TO INSURE THAT ALL SUBCONTRACTORS HAVE THE INFORMATION NECESSARY SO THAT THEY MAY PROPERLY INSTALL ALL CONNECTIONS AND EQUIPMENT. IDENTIFY ALL ITEMS OF WORK THAT REQUIRE ACCESS SO THAT THE CEILING TRADE WILL KNOW WHERE TO INSTALL ACCESS DOORS AND PANELS.
- COORDINATE, PROJECT AND SCHEDULE WORK WITH OTHER TRADES IN ACCORDANCE WITH THE CONSTRUCTION SEQUENCE.
- DRAWINGS SHOW THE GENERAL RUNS OF CONDUITS, PIPING AND DUCTWORK AND APPROXIMATE LOCATION OF OUTLETS. ANY SIGNIFICANT CHANGES IN LOCATION OF ITEMS NECESSARY IN ORDER TO MEET FIELD CONDITIONS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE ARCHITECT/ENGINEER AND RECEIVE HIS APPROVAL BEFORE SUCH ALTERATIONS ARE MADE. ALL SUCH MODIFICATIONS SHALL BE MADE WITHOUT ADDITIONAL COST TO THE OWNER.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION AND REPAIR OF SURFACES, AREAS AND PROPERTY THAT MAY BE DAMAGED AS A RESULT OF CONSTRUCTION ACTIVITIES.
- ADJUST LOCATION OF PIPING, DUCTWORK, ETC. TO PREVENT INTERFERENCES, BOTH ANTICIPATED AND ENCOUNTERED. DETERMINE THE EXACT ROUTE AND LOCATION OF EACH ITEM PRIOR TO FABRICATION. MAKE OFFSETS, TRANSITIONS AND CHANGES IN DIRECTION IN SYSTEMS AS REQUIRED TO MAINTAIN ADEQUATE CLEARANCES AND HEADROOM.
- WHEREVER THE WORK IS OF SUFFICIENT COMPLEXITY, PREPARE ADDITIONAL COORDINATION DRAWINGS AND ORANGE ON-SITE MEETINGS WITH ALL RELATED SUBCONTRACTORS TO COORDINATE THE WORK BETWEEN TRADES. DRAWINGS SHALL CLEARLY SHOW THE WORK AND ITS RELATION TO THE WORK OF OTHER TRADES, AND BE SUBMITTED FOR REVIEW PRIOR TO COMMENCING SHOP FABRICATION OR ERECTION IN THE FIELD.
- COORDINATE WITH LOCAL UTILITY PROVIDERS FOR THEIR REQUIREMENTS FOR SERVICE CONNECTIONS AND PROVIDE ALL NECESSARY PAYMENTS, MATERIALS, LABOR AND TESTING TO ACCOMPLISH THE WORK.



TYPICAL LIGHT POLE BASE DETAIL


SCALE: NONE

LIGHT FIXTURE SCHEDULE

PLAN MARK	MANUFACTURER	MODEL NUMBER	MOUNTING	FINISH	LAMP CODE	LAMP QUANTITY	NOTES
AA	MCGRAW-EDISON	GALN-SAZC-740-U-T4FT-20180 DEG	20' POLE	BRONZE	216 LED PER HEAD	2	1,2,3,5
BB	MCGRAW-EDISON	GALN-SAZC-740-U-T4FT	20' POLE	BRONZE	216 LED PER HEAD	1	1,2,3,5
A	LITHONIA	WPX1-LED-P2-30K-MVOLT-E14WC-DDBXD	WALL/SURFACE	BRONZE	24W LED	-	1,2
B	GREEN CREATIVE	12NCDRL6DM/930/EXT	RECESSED	BLACK	12W LED	-	1,2,3,6
B1	GREEN CREATIVE	12NCDRL6DM/930/EXT-EM	RECESSED	BLACK	12W LED	-	1,2,3,4,6

NOTES LEGEND

- PROVIDE WET LOCATION RATED FIXTURE
- PROVIDE COLD LOCATION RATED DRIVER
- PROVIDE SQUARE STRAIGHT STEEL POLE RATED FOR 100 MPH WIND GUSTS, PRIMED AND PAINTED TO MATCH FIXTURE
- PROVIDE EMERGENCY BATTERY
- PROVIDE ALL ACCESSORIES FOR A COMPLETE INSTALLATION.
- PROVIDE WEATHER PROOF JUNCTION BOX FOR DRIVERS AND ELECTRICAL CONNECTIONS ABOVE SOFFIT.



SITE PLAN - LIGHTING

pkmr
ENGINEERS

PEARSON KENT MCKINLEY A&M ENGINEERS LLC
2849 SW WANAMAKER DR., TOPEKA, KANSAS 66614
785.273.2447 WWW.PKMR.ENG.COM



schwerdt design group
architecture|interiors|planning

2231 sw wanamaker rd suite 303
topeka, kansas 66614-4275
phone: 785.273.7540
fax: 785.273.7579

500 north broadway suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115



Bryan Leinwetter - Engineer
MCM PE-2020020297

CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, MISSOURI

SUBMISSION DATES


MAY 23, 2023

SHEET TITLE
SITE PHOTOMETRIC
PLAN AND GENERAL
NOTES

PROJECT NUMBER
230117

SHEET NUMBER
ME-201

FILE PATH:
DATE:
DRAWN BY:




pkmr
ENGINEERS
PEARSON KENT MCKINLEY RAMP ENGINEERS, LLC
2849 SW WANAMAKER DR., TOPEKA, KANSAS 66614
785.273.2447 WWW.PKMRENG.COM


23.205

SUBMISSION DATES
MAY 23, 2023
SHEET TITLE
SITE MEP PLAN
PROJECT NUMBER
230117
SHEET NUMBER
ME-202

CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, MISSOURI



schwerdt design group
architecture|interiors|planning
2231 sw wanamaker rd
topeka, kansas 66614-4276 suite 303
phone: 785.273.7540
fax: 785.273.7579
500 north broadway
oklahoma city, ok 73102 suite 200
phone: 405.231.3105
fax: 405.231.3115



NOT TO SCALE



Diagram illustrating the installation of a 60° wye branch cast iron soil pipe. The diagram shows a cross-section of the pipe assembly embedded in concrete. The main pipe is labeled "6\" CAST IRON PIPE". The branch pipe is labeled "60° WYE BRANCH CAST IRON SOIL PIPE". The concrete surrounding the pipe is labeled "POURED 8\"x16\" CONCRETE". The top of the concrete is labeled "GRADE". The bottom of the concrete is labeled "1\" CHAMFER". The top of the pipe is labeled "IRON FERRULE WITH METAL COUNTER SUNK SCREW PLUG". The bottom of the pipe is labeled "30° BEND". The top of the pipe is labeled "GROUTED PLUG WHEN CLEANOUT OCCURS AT END OF LINE".

NOT TO SCALE



PIPING MATERIAL & INSULATION SCHEDULE								
PIPING SYSTEM	SIZE	TYPE/SCHED	MATERIAL	ACCEPTABLE FITTINGS	FIELD TEST PRESSURE/TIME	ALLOWABLE IN PLENUMS	INSULATION	
							TYPE	THICKNESS
DOMESTIC COLD WATER	1/2"-2-1/2"	L	COPPER	SOLDER, PRO-PRESS	130 PSI - 1/2HR	YES	FIBERGLASS W/ ASJ	1/2"
DOMESTIC HOT WATER & HW RETURN	1/2"-2-1/2"	L	COPPER	SOLDER, PRO-PRESS	130 PSI - 1/2HR	YES	FIBERGLASS W/ ASJ	1"
NATURAL GAS - ABOVE GRADE	2-1/2 & Up	SCH. 40	STEEL - SEAMED	WELDED	75 PSI - 1HR	YES	----	----
NATURAL GAS - ABOVE GRADE	1/2"-2"	SCH. 40	STEEL - SEAMLESS	THREADED IRON	75 PSI - 1HR	YES	----	----
SOIL & WASTE BELOW GRADE	2"-8"	SCH. 40	PVC	SOLVENT JOINED	10 FT - 1/2HR	NO	----	----
DOM. WATER SERVICE BELOW GRADE	4"-8"	AWWA C151	DUCTILE IRON	AWWA C111, MECH JOINTS	130 PSI - 1/2HR	YES	----	----
DOM. WATER SERVICE BELOW GRADE	1"-3"	K	COPPER	CONTINUOUS TUBING, BRAZED	130 PSI - 1/2HR	YES	----	----
DOM. WATER SERVICE BELOW GRADE	1"-3"	DR 9	HDPE	CONTINUOUS TUBING, FUSED	130 PSI - 1/2HR	NO	----	----



NOTES

- ALL PIPING AND MATERIALS IN PLENUMS MUST MEET ASTM E84 FLAME/SMOKE RATING OF 25/50.
- ALL INSULATION THICKNESSES SHALL MEET ASHRAE 90.1 - 2007 REQUIREMENTS AT A MINIMUM.
- REFER TO SPECIFICATIONS FOR MORE DETAILED INFORMATION.

PLUMBING FIXTURE SCHEDULE								
PLAN MARK	FIXTURE MODEL	FIXTURE DESCRIPTION	FITTINGS MODEL	FITTINGS DESCRIPTION	PIPE SIZES			
					WASTE	VENT	DCW	DHW
P-1	TOTO DRAKE CS1744SL	ADA COMPLIANT WATER CLOSET: FLUSH TANK; WHITE ELONGATED BOWL, 1.6 GALLON SIPHON JET FLUSHING SYSTEM, 2-1/8" TRAP DIAMETER, WITH POLISHED CHROME FLUSH HANDLE MOUNTED ON WIDE SIDE OF RESTROOM STALL, WITH HANDLE STOP VALVE AND METAL FLEXIBLE WATER RISER	TOTO SCS34	SEAT: WHITE, SOLID PLASTIC, OPEN FRONT, ELONGATED	4"	2"	1/2"	---
P-2	AMERICAN STANDARD 0355.012	LAVATORY: WHITE WALL HUNG LAVATORY 20"x18" WITH 4" BACK FAUCET HOLES ON 4" CENTERS, WITH CONCEALED ARM CARRIER. PROVIDE HANDLE STOP VALVES AND FLEXIBLE METAL WATER RISERS.	AMERICAN STANDARD 2175.504	FAUCET: 4" CENTERSET, CHROME FINISH WITH 4" METAL LEVER HANDLE, 1/2" CONNECTIONS, 1.5 GPM MAX FLOWRATE. CHROME PLATED BRASS GRID DRAIN, TAILPIECE, AND P-TRAP. INSULATE THE TAILPIECE, P-TRAP, AND WATER RISERS	2"	2"	1/2"	1/2"



NOT TO SCALE



**CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, MISSOURI**


SUBMISSION DATES
MAY 23, 2023

SHEET TITLE
PLUMBING FLOOR
PLAN


PROJECT NUMBER
230117

SHEET NUMBER
M-101


FILE PATH:
DATE:
DRAWN BY:



ROOF PIPE CURB PENETRATION
NOT TO SCALE



ROOFTOP UNIT CURB DETAIL
NOT TO SCALE



FLOOR PLAN - HVAC
SCALE: 1/8" = 1'-0"

ROOF TOP UNIT SCHEDULE - THREE PHASE ELECTRIC WITH GAS HEAT

PLAN MARK	MANUFACTURER	MODEL NUMBER	SIZE	REFRIGERANT	MINIMUM EFFICIENCY	AIRFLOW	COMPRESSORS	COOLING CAPACITY	CFM	EXTERNAL STATIC	OA CFM	HEATING CAPACITY	ELECTRICAL	WEIGHT	FILTER	NOTES
RTU-1	TRANE	YSC 048 E3	4 TON	R-410A	14 SEER	DOWN	(1) SCROLL	49,000 BTUH	1,600	0.7"	160	80 MBH	208 V., 3 PH, 35 AMP	800 LBS	MERV 13	1,2,3,4
RTU-2	TRANE	YSC 048 E3	4 TON	R-410A	14 SEER	DOWN	(1) SCROLL	49,000 BTUH	1,600	0.7"	160	80 MBH	208 V., 3 PH, 35 AMP	800 LBS	MERV 13	1,2,3,4
RTU-3	TRANE	YSC 048 E3	4 TON	R-410A	14 SEER	DOWN	(1) SCROLL	49,000 BTUH	1,600	0.7"	160	80 MBH	208 V., 3 PH, 35 AMP	800 LBS	MERV 13	1,2,3,4
RTU-4	TRANE	YSC 060 E3	5 TON	R-410A	14 SEER	DOWN	(1) SCROLL	60,100 BTUH	2,000	1.0"	200	80 MBH	208 V., 3 PH, 40 AMP	800 LBS	MERV 13	1,2,3,4
RTU-5	TRANE	YSC 072 E3	6 TON	R-410A	14.6 IEER	DOWN	(1) SCROLL	75,000 BTUH	2,400	1.1"	240	120 MBH	208 V., 3 PH, 50 AMP	1000 LBS	MERV 13	1,2,3,4

NOTES LEGEND

- PROVIDE ROOF CURB, DISCONNECT SWITCH, HAIL GUARDS, AND ECONOMIZER
- PROVIDE WALL MOUNTED 7-DAY PROGRAMMABLE THERMOSTAT
- PROVIDE INTERNAL VIBRATION ISOLATION FOR THE RTU FAN AND COMPRESSORS

EXHAUST FAN SCHEDULE

PLAN MARK	MANUFACTURER	MODEL NUMBER	MOUNTING	SERVICE	CFM	STATIC PRESSURE	ELECTRICAL	DRIVE	DISCONNECT	DAMPER	NOTES
EF-1	GREENHECK	SP-B90	CEILING	EXHAUST	75	1/4"	50 WATTS, 120V, 1 PHASE	DIRECT	YES	BACKDRAFT	1

NOTES:

- PROVIDE 12" ROOF CURB WITH CURB CAP MODEL RCC-7 WITH INTEGRAL BIRDSCREEN.



schwerdt design group
architecture|interiors|planning
2231 sw wanamaker rd
topeka, kansas 66614-4276 suite 303
phone: 785.273.7540
fax: 785.273.7579
500 north broadway
oklahoma city, ok 73102 suite 200
phone: 405.231.3105
fax: 405.231.3115



CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, MISSOURI

SUBMISSION DATES
MAY 23, 2023

SHEET TITLE
HVAC FLOOR PLAN

PROJECT NUMBER
230117

SHEET NUMBER
M-201

PANELBOARD SCHEDULE

PANEL DESIGNATION P1	MAIN BUS AMPS: 200		VOLTAGE: 120/208V				MOUNTING: RECESSED		
	MAIN BREAKER: 200		PHASE/WIRE: 3PH/4W				LOCATION: SEE PLANS		
	PANEL TYPE: N000		MINIMUM AIC: 22K						
CIRCUIT DESCRIPTION			CKT. P	BKR. AMP	CKT. NO.	CKT. NO.	BKR. AMP	P	CIRCUIT DESCRIPTION
SPARE			1	20	1	2	35	3	RTU-1
SPARE			1	20	3	4	-	-	
SPARE			1	20	5	6	-	-	
SPARE			1	20	7	8	35	3	RTU-2
SPARE			1	20	9	10	-	-	
SPARE			1	20	11	12	-	-	
SPARE			1	20	13	14	20	1	ROOF RECEPTACLES
SPARE			1	20	15	16	20	1	SPARE
SPARE			1	20	17	18	20	1	SPARE
SPARE			1	20	19	20	20	1	SPARE
SPARE			1	20	21	22	20	1	SPARE
SPARE			1	20	23	24	20	1	SPARE
SPARE			1	20	25	26	20	1	SPARE
SPARE			1	20	27	28	20	1	SPARE
SPARE			1	20	29	30	20	1	SPARE
SPARE			1	20	31	32	20	1	SPARE
SPARE			1	20	33	34	20	1	SPARE
SPARE			1	20	35	36	20	1	SPARE
SPARE			1	20	37	38	20	1	SPARE
SPARE			1	20	39	40	20	1	SPARE
SPARE			1	20	41	42	20	1	SPARE

PANELBOARD SCHEDULE

PANEL DESIGNATION P3		MAIN BUS AMPS: 200 MAIN BREAKER: 200 PANEL TYPE: NQ00			VOLTAGE: 120/208V PHASE/WIRE: 3PH/4W			MOUNTING: RECESSED LOCATION: SEE PLANS MINIMUM AIC: 22K			
CIRCUIT	DESCRIPTION	CKT.	BKR.	CKT. NO.	CKT. NO.	CKT.	BKR.	AMP	P	CIRCUIT	DESCRIPTION
		P	AMP			P	AMP				
SPARE		1	20	1	2	40	3			RTU-4	
SPARE		1	20	3	4	-	-			-	
SPARE		1	20	5	6	-	-			-	
SPARE		1	20	7	8	50	3			RTU-5	
SPARE		1	20	9	10	-	-			-	
SPARE		1	20	11	12	-	-			-	
SPARE		1	20	13	14	20	1			ROOF RECEPTACLES	
SPARE		1	20	15	16	20	1			SPARE	
SPARE		1	20	17	18	20	1			SPARE	
SPARE		1	20	19	20	20	1			SPARE	
SPARE		1	20	21	22	20	1			SPARE	
SPARE		1	20	23	24	20	1			SPARE	
SPARE		1	20	25	26	20	1			SPARE	
SPARE		1	20	27	28	20	1			SPARE	
SPARE		1	20	29	30	20	1			SPARE	
SPARE		1	20	31	32	20	1			SPARE	
SPARE		1	20	33	34	20	1			SPARE	
SPARE		1	20	35	36	20	1			SPARE	
SPARE		1	20	37	38	20	1			SPARE	
SPARE		1	20	39	40	20	1			SPARE	
SPARE		1	20	41	42	20	1			SPARE	

PANELBOARD SCHEDULE

PANEL DESIGNATION	MAIN BUS AMPS: 200		VOLTAGE: 120/208V			MOUNTING: RECESSED	
P2	MAIN BREAKER: 200		PHASE/WIRE: 3PH/4W			LOCATION: SEE PLANS	
	PANEL TYPE: NQ00					MINIMUM AIC: 22K	
CIRCUIT DESCRIPTION	CKT. BKR.		CKT. NO.	CKT. NO.	CKT. BKR.		CIRCUIT DESCRIPTION
	P	AMP			AMP	P	
EXHAUST FAN-1	1	15	1	2	35	3	RTU-3
WATER HEATER-1	1	30	3	4	-	-	
SPARE	1	20	5	6	-	-	
SPARE	1	20	7	8	20	1	ROOF RECEPTACLE
SPARE	1	20	9	10	20	1	SPARE
SPARE	1	20	11	12	20	1	SPARE
SPARE	1	20	13	14	20	1	SPARE
SPARE	1	20	15	16	20	1	SPARE
SPARE	1	20	17	18	20	1	SPARE
SPARE	1	20	19	20	20	1	SPARE
SPARE	1	20	21	22	20	1	SPARE
SPARE	1	20	23	24	20	1	SPARE
SPARE	1	20	25	26	20	1	SPARE
SPARE	1	20	27	28	20	1	SPARE
SPARE	1	20	29	30	20	1	SPARE
SPARE	1	20	31	32	20	1	SPARE
SPARE	1	20	33	34	20	1	SPARE
SPARE	1	20	35	36	20	1	SPARE
SPARE	1	20	37	38	20	1	SPARE
SPARE	1	20	39	40	20	1	SPARE
SPARE	1	20	41	42	20	1	SPARE



PANELBOARD SCHEDULE

PANEL DESIGNATION		MAIN BUS AMPS: 100		VOLTAGE: 120/208V		MOUNTING: SURFACE	
HP		MAIN BREAKER: 100A		PHASE/WIRE: 3PH/4W		LOCATION: EXTERIOR	
		PANEL TYPE: NEMA 3R				MINIMUM AIC: 22K	
CIRCUIT DESCRIPTION		CKT. NO.	BKR. AMP	CKT. NO.	BKR. AMP	CIRCUIT DESCRIPTION	
IRRIGATION CONTROLLER		1	20	1	2	20	SITE LTG: PARKING LOT
SPARE		1	20	3	4	-	-
SPARE		1	20	5	6	20	SITE LTG: WALL MOUNTED
SPARE		1	20	7	8	-	-
SPARE		1	20	9	10	20	SITE LTG: CANOPIES
SPARE		1	20	11	12	20	SPARE
SPARE		1	20	13	14	20	SPARE
SPARE		1	20	15	16	20	SPARE
SPARE		1	20	17	18	20	SPARE
SPARE		1	20	19	20	20	SPARE
SPACE				21	22		SPACE
SPACE				23	24		SPACE
SPACE				25	26		SPACE
SPACE				27	28		SPACE
SPACE				29	30		SPACE

NOTES:
NEMA 3R RATED PANEL WITH LOCKABLE COVER

ELECTRICAL RISER KEYED NOTES


- 200 AMP, 3 PH, NEMA 3R DISCONNECT SWITCH FUSED AT 200 AMP
- #1 AND (1) #8 GRD. IN 1-1/2" C.
- 1 SET OF (4) #3/0 AND (1) #6 GRD. IN 2-1/2" C.




ELECTRICAL TRANSFORMER PAD DETAIL
NO SCALE 75-500 KVA

NOTES:


- THE PAD LOCATION SHALL BE APPROVED BY EVERY
- TRANSFORMER SHALL BE INSTALLED NEAR THE CUSTOMER'S SERVICE ENTRANCE.
- IF THE TRANSFORMER PAD IS INSTALLED IN AN AREA SUBJECT TO VEHICULAR TRAFFIC, THE INSTALLATION SHALL BE PROTECTED WITH A PIPE-RAIL GUARD.
- FOR PROPER CLEARANCE AROUND THE TRANSFORMER, REFER TO EVERY STANDARDS.
- CONTRACTOR SHALL EXTEND FORMS DOWN TO AT LEAST 3" BELOW AVERAGE GROUND LINE.
- THE CONCRETE SHALL BE A MINIMUM OF 3,000 LB. MIX.
- THE TOP OF THE TRANSFORMER PAD SHALL RECEIVE A SMOOTH TROWEL FINISH. THE CORNERS AND EDGES SHALL BE ROUNDED OR BEVELLED.
- THE CONDUIT OPENING SHALL BE FREE AND CLEAR OF CONCRETE.
- THE TOPS OF THE CONDUITS SHALL BE FLUSH WITH THE TOP OF THE CONCRETE PAD.
- NUMBER OF CONDUITS NECESSARY IS DEPENDENT ON THE MAXIMUM NUMBER OF SERVICE CONDUITS ALLOWED IN THE LOW-VOLTAGE COMPARTMENT OF THE TRANSFORMER. INSTALL 1" METERING CONDUIT FROM PAD TO METER ENCLOSURE WHEN TRANSFORMER RATED METERING IS SET ON ADJACENT BUILDING OR STAND AND METERING TRANSFORMERS ARE IN THE PADMOUNT TRANSFORMER.
- PILLARS ARE FORMED BY AUGERING AN 8" DIAMETER HOLE TO A DEPTH OF UNDISTURBED EARTH. A SEPARATOR, SUCH AS TAP PAPER, SHOULD BE PLACED BETWEEN THE PILLAR AND THE PAD SO THAT THE PAD CAN BE LEVELLED AT A LATER TIME IF NECESSARY.
- EVERY RESERVES THE RIGHT NOT TO ACCEPT THE CONDITION OF THE CONCRETE PAD IF IT FAILS TO MEET THE REQUIREMENTS STATED IN THEIR STANDARD.
- THE 6" ABOVE GRADE CAN BE REDUCED TO 4" ABOVE FINISHED PAVEMENT.
- CONDUIT OPENING DIMENSIONS PERTAIN TO HOWARD (2012 AND NEWER) TRANSFORMERS. CHECK WITH EVERY LOCAL SERVICE CENTER TO BE SURE THAT THE OPENING IS THE CORRECT SIZE FOR THE TRANSFORMER DESIGNATED FOR THE JOB.
- VERIFY PAD REGULATIONS WITH EVERY




FLOOR PLAN - POWER
SCALE: 1/8" = 1'-0"




DUCT SMOKE DETECTOR DIAGRAM
NOT TO SCALE



GROUNDING ELECTRODE SYSTEM
N.T.S



schwerdt design group
architecture|interiors|planning
2231 sw warrensburg rd
topeka, kansas 66614-4276 suite 303
phone: 785.273.7540
fax: 785.273.7579
500 north broadway
oklahoma city, ok 73102 suite 200
phone: 405.231.3105
fax: 405.231.3115



Bryan Leinwetter - Engineer
MOW PE-2020020297



CORE & SHELL BUILDING
STREETS OF WEST PRYOR LOT 5
LEES SUMMIT, MISSOURI

SUBMISSION DATES
MAY 23, 2023

SHEET TITLE
POWER FLOOR PLAN


PROJECT NUMBER
230117

SHEET NUMBER
E-101





schwerdt design group
architecture|interiors|planning
2231 sw wanamaker rd suite 303
topeka, kansas 66614-4276
phone: 785.273.7540
fax: 785.273.7579
500 north broadway suite 200
oklahoma city, ok 73102
phone: 405.231.3105
fax: 405.231.3115



Bryan Leinwetter - Engineer
MOW PE-2020020297

CORE & SHELL BUILDING

STREETS OF WEST PRYOR LOT 5

LEES SUMMIT, MISSOURI

SUBMISSION DATES
MAY 23, 2023
SHEET TITLE
LIGHTING FLOOR PLAN
PROJECT NUMBER
230117
SHEET NUMBER
E-201