






FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell\_rjsZHKC2.rvt  
DATE: 5/23/2023 4:19:09 PM  
DRAWN BY: Author





**C1** TYP. TRASH ENCLOSURE PLAN  
SCALE: 1/4" = 1'-0"




**A1** SITE PLAN  
SCALE: 1" = 30'-0"




**D3** TRASH ENCLOSURE CAP DETAIL  
SCALE: 3" = 1'-0"




**A3** ENCLOSURE GATE HINDGE DETAIL  
SCALE: 1 1/2" = 1'-0"




**C4** TRASH ENCLOSURE GATE ELEVATION  
SCALE: 1/4" = 1'-0"



**A4** TRASH ENCLOSURE WALL SECTION  
SCALE: 1/2" = 1'-0"



**schwerdt design group**  
architecture | interiors | planning  
2231 sw warrenpark rd suite 300  
topeka, kansas 66614-4276  
phone: 785.273.7540  
fax: 785.273.7579



SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #F00353876

**CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5**  
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES  
PROGRESS PRINT ONLY


SHEET TITLE  
SITE PLAN

PROJECT NUMBER  
**230117**

SHEET NUMBER  
**A-100**



FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell\_jfsZHKC2.rvt  
DATE: 6/13/2023 12:50:51 PM  
DRAWN BY: Author




A1 FIRST FLOOR  
SCALE: 1/8" = 1'-0"

#### KEYED PLAN NOTES

- LANDLORD TO PROVIDE PADLOCK FOR ROOF ACCESS  
LADDER AND 5 KEYS TO PADLOCK

#### PARTITION TYPES

2 HR WALL ASSEMBLY PER UL DESIGN NO. U301



- Nailheads — Exposed or covered with joint compound.
- Joints — Exposed joints covered with joint compound and paper tape. Joint compound and paper tape may be omitted when square edge boards are used. As an alternate, nom 3/32 in. thick gypsum veneer plaster may be applied to the entire surface of Classified veneer baseboard with the joints reinforced with paper tape.
- Nails — 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam, 1/4 in. diam heads, and 8d cement coated nails 2-3/8 in. long, 0.113 in. shank diam, 9/32 in. diam heads.
- Gypsum Board\* — 5/8 in. thick, two layers applied either horizontally or vertically. Inner layer attached to studs with the 1-7/8 in. nails spaced 6 in. O.C. Outer layer attached to studs over inner layer with the 2-3/8 in. long nails spaced 8 in. O.C. Vertical joints located over studs. All joints in face layers staggered with joints in base layers. Joints of each base layer offset with joints of base layer on opposite side. When used in widths other than 48 in., gypsum board to be installed horizontally.
- NOT USED
- NOT USED
- NOT USED
- NOT USED
- Batts and Blankets — Min. 3 in. thick glass fiber batts bearing the UL Classification Marking as to Surface Burning and/or Fire Resistance, friction-fitted to fill the stud cavities. See Batts and Blankets (BKNV or BZJZ) Categories for names of Classified companies.
- NOT USED
- NOT USED


NOTE: ALL PENETRATIONS THRU DEMISING WALLS MUST BE FIRESTOPPED.

NON-RATED GYPSUM BOARD PARTITION  
1. 5/8" Gypsum board on each side of 3 1/2" wood studs @ 16" O.C.  
2. Water resist gyp on restroom side.

NON-RATED PARTITION  
1. 5/8" Gypsum board on one side only of 3 1/2" wood studs @ 16" O.C.  
2. Water resist gyp on restroom side.


PLUMBING CHASE PARTITION  
1. 5/8" Gypsum board on one side only of 3 1/2" wood studs @ 16" O.C.  
2. Water resist gyp on restroom side.

PLUMBING CHASE PARTITION



**schwerdt design group**  
architecture | interiors | planning  
2231 sw warrenmaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579

500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



SCHWERDT DESIGN GROUP INC.  
MO CERTIFICATE OF AUTH. #F00353876

**CORE & SHELL BUILDING**  
**STREETS OF WEST PRYOR LOT 5**  
2070 NW LOWENSTEIN DR, LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081


SUBMISSION DATES  
PROGRESS PRINT ONLY  
1 ADD-1 06-02-2023

SHEET TITLE  
FIRST FLOOR PLAN

PROJECT NUMBER  
**230117**

SHEET NUMBER  
**A-101**

FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell\_jrsZHKC2.rvt  
DATE: 5/23/2023 4:19:10 PM  
DRAWN BY: Author



ROOF PLAN NOTES


1. TPO ROOF MEMBRANE
2. R-30 INSULATION



**schwerdt design group**  
architecture | interiors | planning

2231 sw warrenmaker rd suite 303  
topeka, kansas 66614-4276  
phone: 785.273.7540  
fax: 785.273.7579

500 north broadway, suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



MICHAEL K. HAMPTON  
#MCH A-2008027042

SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #F00353876

**CORE & SHELL BUILDING**  
**STREETS OF WEST PRYOR LOT 5**  
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES  
PROGRESS PRINT ONLY

SHEET TITLE  
ROOF PLAN

PROJECT NUMBER  
**230117**

SHEET NUMBER  
**A-102**





architecture | interiors | planning  
2231 sw vanamaker rd suite 300  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579

500 north broadway, suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115

STATE OF MISSOURI  
MICHAEL K HAMPTON  
ARCHITECT  
#MCH A-200020702

SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #FD0353876

CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5  
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081


SUBMISSION DATES  
PROGRESS PRINT ONLY

SHEET TITLE  
EXTERIOR ELEVATIONS


PROJECT NUMBER  
230117

SHEET NUMBER  
A-201


| EXTERIOR MATERIALS   |   |
|--|---|
|  | <b>SPLIT FACE STONE VENEER (ST-1)</b><br>COLOR: (CHARCOAL) BANFF SPRINGS CLIFFSTONE<br>STYLE / MORTAR: ENGINEERED STONE VENEER<br>MANUFACTURER: ELDORADO STONE  |
|  | <b>FACE BRICK (BK-1)</b><br>COLOR: CHARCOAL W/ SM770 SABLE MORTAR<br>STYLE: COAL CREEK<br>MANUFACTURER: MUTUAL MATERIALS  |
|  | <b>WOOD / FIBER CEMENT SIDING (WD-1)</b><br>COLOR: (DARK BROWN) SONORAN W/ DADOS PROFILE<br>STYLE: RESAWN TIMBER / SEALED FACE AND BACK<br>3/4" THICK X 7-3/8" WIDE X 8-1/8" RANDOM LENGTHS<br>MANUFACTURER: ACCOYA WOOD SIDING |
|  | <b>PRE-FINISHED METAL (MTL-1)</b><br>COLOR: TBD LANDLORD TO SELECT FINAL COLOR<br>STYLE: FLUSH SEAM PANEL<br>FOR ALUMINUM<br>MANUFACTURER: STUCCO EMBOSSED BERRIDGE   |
|  | <b>EIFS - MAIN (EF-1)</b><br>COLOR: WHITE (SW ID TBD)<br>STYLE: SANDBLAST TEXTURE<br>MANUFACTURER: DRYVIT   |
|  | <b>EIFS - ACCENT (EF-2)</b><br>COLOR: SW 7018 DOVETAIL<br>STYLE: SANDBLAST TEXTURE<br>MANUFACTURER: DRYVIT  |
| * COLOR MATCH ALL METAL FOR ALUMINUM STOREFRONTS, FLASHINGS / COPINGS, CANOPIES, PANELS, DOWNSPOUTS & SCUPPERS |   |
| * LANDLORD TO HAVE FINAL DETERMINATION OVER MATERIAL COLOR AND SELECTION                                       |   |




C1 EAST ELEVATION  
SCALE: 1/8" = 1'-0"



C4 NORTH ELEVATION  
SCALE: 1/8" = 1'-0"



A1 WEST ELEVATION  
SCALE: 1/8" = 1'-0"



A4 SOUTH ELEVATION  
SCALE: 1/8" = 1'-0"





architecture | interiors | planning  
2231 sw warrenaker rd suite 300  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579



SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #00353876

CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5  
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081


SUBMISSION DATES  
PROGRESS PRINT ONLY

SHEET TITLE  
WALL SECTIONS



PROJECT NUMBER  
230117

SHEET NUMBER  
A-301



FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell\_jrsZHKC2.rvt  
DATE: 5/23/2023 4:19:12 PM  
DRAWN BY: Author




A1 SECTION @ EAST WALL STOREFRONT  
SCALE: 1/2" = 1'-0"



A2 SECTION @ EAST WALL WINDOW TENANT C  
SCALE: 1/2" = 1'-0"



A4 SECTION @ EAST WALL WINDOW TENANT A  
SCALE: 1/2" = 1'-0"







architecture | interiors | planning  
2231 sw warrenaker rd suite 300  
topeka, kansas 66614-4276  
phone: 785.273.7540  
fax: 785.273.7579



SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5  
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081


SUBMISSION DATES  
PROGRESS PRINT ONLY

SHEET TITLE  
WALL SECTIONS


PROJECT NUMBER  
230117

SHEET NUMBER  
A-302


FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell\_rjsZHKC2.rvt  
DATE: 5/23/2023 4:19:12 PM  
DRAWN BY: Author



A1 SECTION @ EAST WALL PILASTER  
SCALE: 1/2" = 1'-0"






A2 SECTION @ NORTH WALL PILASTER  
SCALE: 1/2" = 1'-0"



A4 SECTION @ NORTH WALL  
SCALE: 1/2" = 1'-0"



FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell\_ljszHKC2.rvt  
DATE: 5/23/2023 4:19:13 PM  
DRAWN BY: Author



SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #F00353876

# CORE & SHELL BUILDING STREETS OF WEST PRYOR LOT 5 LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES  
PROGRESS PRINT ONLY


SHEET TITLE  
WALL SECTIONS

PROJECT NUMBER  
230117


SHEET NUMBER  
A-303



FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell\_ljsZHKC2.rvt  
DATE: 5/23/2023 4:19:13 PM  
DRAWN BY: Author



**A2 SECTION @ NORTH WALL W/ WINDOW**  
SCALE: 1/2" = 1'-0"



**A4 SECTION @ EAST WALL W/ STANDING SEAM AWNING**  
SCALE: 1/2" = 1'-0"

**schwerdt design group**  
architecture | interiors | planning  
2231 sw warrenpark rd suite 300  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579  
500 north broadway, suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115  
MICHAEL K HAMPTON  
#MCH-A200020202

SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #F00353876

**CORE & SHELL BUILDING**  
**STREETS OF WEST PRYOR LOT 5**  
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES  
PROGRESS PRINT ONLY

SHEET TITLE  
WALL SECTIONS

PROJECT NUMBER  
**230117**

SHEET NUMBER  
**A-304**



FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell\_rjsZHKC2.rvt  
DATE: 5/23/2023 4:19:14 PM  
DRAWN BY: Author



**schwerdt design group**  
architecture | interiors | planning  
2231 sw warrenmaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579

500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



MICHAEL K. HAMPTON  
#MOA-A2000027042

SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #F00353876


CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5  
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES  
PROGRESS PRINT ONLY


SHEET TITLE  
ENLARGED RESTROOM  
PLAN

PROJECT NUMBER  
230117


SHEET NUMBER  
A-401




RESTROOM / BATH ACCESSORIES




A1 ACCESSIBILITY STANDARDS  
SCALE: 3/8" = 1'-0"



B3 RR INT ELEV - EAST  
SCALE: 1/2" = 1'-0"




D5 RR INT ELEV - WEST  
SCALE: 1/2" = 1'-0"



B5 RR INT ELEV - NORTH  
SCALE: 1/2" = 1'-0"

- RESTROOM GENERAL NOTES
1. RESTROOM FIXTURES AND ACCESSORIES IN PLAN ARE PROVIDED BY LANDLORD.
  2. REF. C1/A-401 FOR TYPICAL ACCESSIBLE MOUNTING HEIGHTS & DETAILS.
  3. LANDLORD TO PROVIDE WALL PAINT; TENANT TO PROVIDE ALL OTHER FINISHES.
  4. WALLS WITHIN 2'-0" OF PLUMBING FIXTURES MUST HAVE A SMOOTH, HARD, AND NON-ABSORBANT WALL SURFACE THAT EXTENDS A MINIMUM OF 4'-0" A.F.F. IN ACCORDANCE WITH 1209.2.2, BY TENANT.
  5. ALL RESTROOM WALLS/FLOORS MUST HAVE A SMOOTH, HARD, AND NON-ABSORBANT SURFACE WALL BASE THAT EXTENDS A MINIMUM OF 4" A.F.F. IN ACCORDANCE WITH 1209.2.1, BY TENANT.
- FIXTURE & ACCESSORY LEGEND
- GB-1 GRAB BARS
  - SD-1 SOAP DISPENSER
  - PTD-1 PAPER TOWEL DISPENSER
  - TPD-1 TOILET PAPER DISPENSER
  - MIR-1 VANITY MIRROR
  - CH-1 COAT HOOK



A5 ENLARGED RR PLAN  
SCALE: 1/2" = 1'-0"





schwerdt design group  
architecture | interiors | planning  
2231 sw vanwinkle rd suite 300  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579



MICHAEL K. HAMPTON  
#MCH-A-2008027042

SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5  
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081

SUBMISSION DATES  
PROGRESS PRINT ONLY



SHEET TITLE  
BUILDING DETAILS

PROJECT NUMBER  
230117


SHEET NUMBER  
A-501

GENERAL FLASHING REQUIREMENTS


- A. PROPERLY WEEP FLASHING POINTS AND NORMAL DRAINAGE POINTS WITH WEEPS @ 1'-4" O.C. MAX.SPACING. WEEP POINTS ARE TO BE LOCATED DIRECTLY ON TOP OF FLASHING.
- B. WHERE FLASHING IS LOCATED TERMINATE AND/OR SEPARATES MATERIALS, DO NO SEAL (U.N.O.) -REFER TO DIAGRAM "C" WHERE IT IS DETERMINED BY THE MATERIAL MANUFACTURER OR OTHERWISE THAT SEALING IS REQUIRED (TO PREVENT WATER PENETRATION BEYOND FLASHING DUE TO WIND DRIVEN RAIN), THEN SEALANT MUST BE WEEPED IN ACCORDANCE WITH NOTE "A" ABOVE.
- C. UNLESS NOTED OTHERWISE, TURN FLASHING UP A MIN. OF 4" BEHIND APPROPRIATE MATERIALS.
- D. FLASHING CONDITIONS, WHETHER DETAILED OR NOT, ARE TO BE IN ACCORDANCE WITH S.M.A.C.M.A. SPECIFICATIONS. WHERE ATYPICAL CONDITIONS OCCUR THAT ARE NOT DETAILED, FLASHING IS TO BE INSTALLED AS CLOSELY AS POSSIBLE TO THE S.M.A.C.M.A. DETAIL THAT IS MOST CLOSELY APPROXIMATES THE ACTUAL CONDITION.
- E. UNLESS NOTED OTHERWISE, AT FLASHING HIGH POINTS SEAL WATER TIGHT TO BACK-UP SUBSTRATE.




C1 PARAPET CAP AT WALL  
SCALE: 1 1/2" = 1'-0"




C3 PARAPET CAP AT PILASTER  
SCALE: 1 1/2" = 1'-0"




B1 PARAPET CAP  
SCALE: 3" = 1'-0"




B2 PILASTER PLAN DETAIL  
SCALE: 3/4" = 1'-0"




B3 EIFS / BRICK SECTION  
SCALE: 1 1/2" = 1'-0"





B4 DETAIL AT ENTRANCE SOFFIT  
SCALE: 1 1/2" = 1'-0"




A1 PILASTER WALL PLAN DETAIL  
SCALE: 3/4" = 1'-0"



A2 ROOF ACCESS LADDER  
SCALE: 1/2" = 1'-0"



CJ-1




CJ-2

A4 EIFS REVEAL DETAILS  
SCALE: 3" = 1'-0"





architecture | interiors | planning  
2231 sw warrenpark rd suite 300  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579  
500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



MICHAEL K. HAMPTON  
#MCA-A2000027042  
NO CERTIFICATE OF AUTH. #F00353876

PARAPET CONSTRUCTION  
• BRAKE METAL COLUMN WRAP  
• LIQUID-APPLIED WEATHER BARRIER  
• 1/2" ZIP SYSTEM SHEATHING, W/OUT TAPE  
• PRE-FABRICATED WOOD TRUSS W/  
INTEGRAL PARAPET DESIGN  
• 1/2" ZIP SYSTEM SHEATHING, W/OUT TAPE  
• LIQUID-APPLIED WEATHER BARRIER  
• TPO ROOF MEMBRANE, WRAP UP  
AND OVER TOP OF PARAPET

SCHWERDT DESIGN GROUP INC.  
NO CERTIFICATE OF AUTH. #F00353876

CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5  
LEES SUMMIT, JACKSON COUNTY, MISSOURI 64081


SUBMISSION DATES  
PROGRESS PRINT ONLY

SHEET TITLE  
BUILDING DETAILS


PROJECT NUMBER  
230117

SHEET NUMBER  
A-502


FILEPATH: C:\Users\ross\OneDrive - Schwerdt Design Group\Documents\230117 SOWP Lot 5 Core - Shell\_rjsZHKC2.rvt  
DATE: 5/23/2023 4:19:16 PM  
DRAWN BY: Author




C1 CANOPY DETAIL  
SCALE: 1 1/2" = 1'-0"




C3 AWNING DETAIL  
SCALE: 1 1/2" = 1'-0"




C4 PARAPET CAP AT EAST WALL PILASTER  
SCALE: 1 1/2" = 1'-0"



A1 STONE WALL BASE DETAIL  
SCALE: 1 1/2" = 1'-0"



B3 STOREFRONT WALL BASE DETAIL  
SCALE: 1 1/2" = 1'-0"



A3 EAST WALL PILASTER BASE DETAIL  
SCALE: 1 1/2" = 1'-0"







FILEPATH: C:\Users\John.Donalson\Documents\01190008.120 - Streets of West Pryor - Lot 5\_ JohnDon7.rvt  
DATE: 5/24/2023 7:32:27 AM  
DRAWN BY: GSH

STRUCTURAL GENERAL NOTES

GENERAL NOTES:

ALL STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH THE OTHER PROJECT DRAWINGS AND SPECIFICATIONS. THE MATERIAL REQUIREMENTS IN THESE NOTES ARE TO BE CONSIDERED AS MINIMUM. SPECIFICATIONS SHALL GOVERN WHEN MORE STRINGENT.

VERIFY ALL DIMENSIONS SHOWN WITH ARCHITECTURAL DRAWINGS AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION. DISCREPANCIES SHALL BE RESOLVED BEFORE PROCEEDING WITH CONSTRUCTION. CONTRACTOR SHALL COORDINATE THE WORK OF ALL TRADES AND MAKE NECESSARY INVESTIGATIONS AND FIELD MEASUREMENTS. INFORM ENGINEER OF ALL DISCREPANCIES.

THE CONTRACTOR SHALL VERIFY THE SIZE AND LOCATIONS OF PENETRATIONS AND EMBEDDED ITEMS THROUGH THE STRUCTURE FOR ALL TRADES. PENETRATIONS SHALL BE SUBJECT TO APPROVAL BY THE ARCHITECT AND STRUCTURAL ENGINEER.

SEE MECHANICAL, ELECTRICAL, ARCHITECTURAL DRAWINGS FOR ANCHORS, PIPE SLEEVES, CONDUITS OR OTHER ITEMS TO BE EMBEDDED IN OR PASS THROUGH CONCRETE. IN GENERAL, EMBEDMENTS AND PENETRATIONS LESS THAN 12 INCHES IN DIAMETER ARE NOT SHOWN ON THE STRUCTURAL DRAWINGS.

SEE ARCHITECTURAL DRAWINGS FOR DOOR HEIGHTS AND WALL OPENING DIMENSIONS.

STRUCTURAL ELEMENTS ARE NON-SELF SUPPORTING AND REQUIRE INTERACTION WITH OTHER ELEMENTS FOR STABILITY. FRAMING AND WALLS SHALL BE TEMPORARILY BRACED BY THE CONTRACTOR UNTIL PERMANENT BRACING, FLOOR AND ROOF DECKS AND WALLS HAVE BEEN INSTALLED AND CONNECTIONS BETWEEN THESE ELEMENTS HAVE BEEN MADE.

SUPPORT OF ALL NON-STRUCTURAL ELEMENTS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. NON-STRUCTURAL ELEMENTS ARE THOSE THAT DO NOT CONTRIBUTE TO THE DIRECT LOAD PATH OF BOTH THE GRAVITY AND LATERAL FORCE RESISTING SYSTEMS. THESE ELEMENTS INCLUDE, BUT ARE NOT LIMITED TO PARTITIONS, FINISHES, MILLWORK, MECHANICAL EQUIPMENT, DUCTWORK, PIPING, LIGHT FIXTURES, ELECTRICAL CONDUIT, STORAGE RACKS, ETC. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT THESE ELEMENTS ARE ADEQUATELY CONNECTED TO THE STRUCTURE TO RESIST ALL APPLIED LOADS. NOTIFY THE STRUCTURAL ENGINEER OF RECORD IF UNUSUAL SUPPORT CONDITIONS EXIST.

WORK REQUIRING SPECIAL INSPECTIONS SHALL BE INSPECTED ACCORDING TO THE BUILDING CODE AND INCLUDES: CONCRETE, REINFORCING STEEL, STRUCTURAL WELDING, HIGH-STRENGTH BOLTING, AND MASONRY. RE: SPECIAL INSPECTION PROGRAM TABLE WHEN APPLICABLE.

DESIGN CRITERIA:

BUILDING CODE: 2018 INTERNATIONAL BUILDING CODE AS ADOPTED AND AMENDED BY THE CITY OF LEE'S SUMMIT, MISSOURI.

LIVE LOADS:  
ROOF: 20 PSF

SNOW LOADS:  
GROUND SNOW LOAD, Pg: 20 PSF  
FLAT-ROOF SNOW LOAD, Pf: 20 PSF  
SNOW EXPOSURE FACTOR, Ce: 1.0  
SNOW LOAD IMPORTANCE FACTOR, Is: 1.0  
THERMAL FACTOR, Ct: 1.0

WIND LOAD:  
BASIC WIND SPEED: 115 MPH  
EXPOSURE CATEGORY: C  
WIND IMPORTANCE FACTOR, Iw: 1.0  
BASIC INTERNAL PRESSURE COEFFICIENT, GCpi: ±0.18  
BASIC COMPONENTS AND CLADDING PRESSURE (ADJUSTED TO COMPLY WITH BUILDING CODE):  
±20 PSF @ INTERIOR ZONES  
±25 PSF @ END ZONES

SEISMIC LOAD:  
SEISMIC IMPORTANCE FACTOR, Ie: 1.0  
SPECTRAL RESPONSE ACCELERATIONS:  
Ss: 0.1274  
S1: 0.0612  
SPECTRAL RESPONSE COEFFICIENTS:  
Sds: 0.102  
Sd1: 0.069  
SITE CLASS: C  
SEISMIC DESIGN CATEGORY: B  
BASIC SEISMIC-FORCE-RESISTING SYSTEM: LIGHT-FRAMED WALLS WITH WOOD STRUCTURAL PANELS & STEEL ORDINARY MOMENT FRAMES  
DESIGN BASE SHEAR: Cs x W  
SEISMIC RESPONSE COEFFICIENTS, Cs: 0.0157 & 0.0291  
RESPONSE MODIFICATION FACTOR, R: 6.5 & 3.5  
ANALYSIS PROCEDURE: EQUIVALENT LATERAL FORCE

FOUNDATION AND EARTHWORK NOTES:

REFER TO THE GEOTECHNICAL EXPLORATION AND FOUNDATION RECOMMENDATIONS: WEST PRYOR VILLAGE, LEE'S SUMMIT, MISSOURI / COOK, FLATT, & STROBEL ENGINEERS PA, KANSAS CITY, KANSAS (CFS NO 19-5125) / JUNE 15, 2018

THE FOUNDATION BEARING MATERIAL SHALL BE INSPECTED AND APPROVED BY A GEOTECHNICAL ENGINEER BEFORE FOUNDATIONS ARE CONSTRUCTED.

AT STEPPED FOOTINGS, THE LOWER FOOTING SHALL BE PLACED FIRST.

FOUNDATIONS HAVE BEEN DESIGNED FOR A NET ALLOWABLE SOIL BEARING PRESSURE OF 2,500 PSF FOR CONTINUOUS FOOTINGS AND 3,000 PSF FOR ISOLATED SPREAD FOOTINGS. FOUNDATIONS SHALL BEAR DIRECTLY ON A 24-INCH THICK, GEOGRID REINFORCED AGGREGATE PAD (GRAP) DESIGNED AND CONSTRUCTED AS OUTLINED IN THE GEOTECHNICAL REPORT, SECTION 7.2.

WALL FOUNDATION SHALL BEAR AT MINIMUM OF 3'-0" BELOW ADJACENT FINISH GRADE, UNLESS OTHERWISE NOTED.

UNUSUAL CONDITIONS OR CHANGES TO THE FOUNDATIONS AS REQUIRED BY FIELD CONDITIONS SHALL BE REFERRED TO THE ENGINEER FOR APPROVAL.

REFER TO GEOTECHNICAL REPORT FOR SUBGRADE PREP REQUIREMENTS FOR SLAB-ON-GRADE CONSTRUCTION. PREPARED SUBGRADES EXCAVATED TO INSTALL UTILITIES BELOW FLOOR SLABS SHALL BE BACKFILLED AND COMPACTED AS SPECIFIED BY THE GEOTECHNICAL ENGINEER.

REFER TO GEOTECHNICAL REPORT FOR COMPACTION REQUIREMENTS.

MAINTAIN ALL EXCAVATIONS FREE OF WATER.

CONCRETE NOTES:

CONCRETE SHALL HAVE THE FOLLOWING UNLESS OTHERWISE SPECIFIED (SELECT PROPORTIONS FOR CONCRETE IN ACCORDANCE WITH ACI 318):

|                        | MAX WATER/CEMENT RATIO | MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS |
|------------------------|------------------------|---|
| INTERIOR SLAB ON GRADE | 0.45                   | 3,000 PSI                               |
| FOOTINGS               | 0.45                   | 4,500 PSI                               |
| FOUNDATION WALLS       | 0.45                   | 4,500 PSI                               |
| GRADE BEAMS            | 0.45                   | 4,500 PSI                               |
| DRILLED PIERS          | 0.50                   | 4,000 PSI                               |
| CONCRETE ON STEEL DECK | 0.45                   | 3,000 PSI                               |

REINFORCING STEEL SHALL BE BILLET STEEL CONFORMING TO ASTM A615, GRADE 60.

WELDED WIRE FABRIC SHALL CONFORM TO ASTM A185.

CEMENT SHALL CONFORM TO ASTM C150, TYPE I OR II.

AGGREGATES SHALL CONFORM TO ASTM C33. COARSE AGGREGATE SHALL CONSIST OF 1" MAXIMUM AGGREGATE SIZE. COMBINED GRADATION SHALL HAVE A UNIFORM DISTRIBUTION AS FOLLOWS:  
5-20% RETAINED ON 3/4", 1/2", 3/8", NO. 4, NO. 8, NO. 16, NO. 30 AND NO. 50 SIEVES; LESS THAN 5% PASSING NO. 50 SIEVE.

MATERIALS AND ADMIXTURES SHALL NOT CONTAIN CALCIUM CHLORIDE.

ALL EXTERIOR AND CONCRETE EXPOSED TO FREEZE/THAW CYCLES SHALL BE AIR-ENTRAINED 6%±) BY VOLUME. THIS INCLUDES BUT IS NOT LIMITED TO FOOTINGS, FOUNDATION WALLS AND GRADE BEAMS.

SLEEVES, OPENINGS, OR OTHER ATTACHMENTS NOT SHOWN ON DRAWINGS SHALL BE APPROVED BY THE ENGINEER PRIOR TO PLACING CONCRETE.

MINIMUM TENSION LAP SPLICE LENGTHS AND TENSION DEVELOPMENT LENGTHS SHALL BE AS SCHEDULED, UNLESS NOTED OTHERWISE ON THE DRAWINGS. WELDED WIRE FABRIC SHALL LAP ONE (1) FULL SQUARE PLUS TWO (2) INCHES.

MAINTAIN CONCRETE COVER AS SCHEDULED.

REINFORCING STEEL FABRICATION AND INSTALLATION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CRSI MANUAL OF STANDARD PRACTICE.

ALL REINFORCING AND EMBEDDED ANCHOR BOLTS SHALL BE ACCURATELY PLACED AND TIED PRIOR TO POURING CONCRETE. "STABBING" OF DOWELS OR ANCHOR BOLTS IS NOT ALLOWED.

CONSTRUCTION JOINTS IN WALLS AND ELEVATED FORMED SLABS SHALL BE KEVED (1 1/2" DEEP BY 1/3 MEMBER AREA) AND REINFORCING SHALL CONTINUE THROUGH JOINT OR BE TENSION LAP SPLICED. CONSTRUCTION JOINTS SHALL BE LOCATED BY THE CONTRACTOR TO LEAST IMPAIR THE STRUCTURE. JOINT LOCATIONS SHALL BE APPROVED BY THE ENGINEER.

EMBEDDED CONDUIT SHALL NOT BE LARGER IN OUTSIDE DIMENSION THAN 1/3 THE OVERALL THICKNESS OF SLAB, WALL OR BEAM IN WHICH THEY ARE EMBEDDED. THEY SHALL NOT BE SPACED CLOSER THAN 3 DIAMETERS OR WIDTHS ON CENTER.

CONDUIT LOCATED WITH CONCRETE SECTIONS SHALL COMPLY WITH ACI 318 REQUIREMENTS.

INTERIOR FLOOR SLABS SHALL COMPLY WITH ACI 117, SHALL MEET THE REQUIREMENTS OF A TYPE 5, SINGLE COURSE, HARD STEEL-TROWELED FINISH AS DESCRIBED IN ACI 302, AND SHALL ACHIEVE AN OVERALL FF25/FL20 TOLERANCE.

ADHESIVE ANCHORS IN CONCRETE OR FULLY GROUTED MASONRY SHALL BE ITW RAMISET/REDHEAD EPCOM CERAMIC 6 SYSTEM, HILTI HY200, OR SIMPSON AT-XP. ADHESIVE ANCHORS FOR HOLLOW BLOCK AND OTHER MASONRY SHALL BE HILTI HY270 OR SIMPSON SET-XP.

STRUCTURAL STEEL ENCASED WITHIN CONCRETE SHALL COMPLY WITH AISC TOLERANCES.

MASONRY NOTES:

CONSTRUCT MASONRY IN ACCORDANCE WITH THE IBC. MASONRY REQUIRES LEVEL 1 QUALITY ASSURANCE (RE: SPECS). ALL MASONRY SHALL BE LAID IN RUNNING (COMMON) BOND USING THE LOW-LIFT METHOD OF GROUTING. REFER ARCHITECTURAL PLAN FOR ALL BLOCK COURSING.

MASONRY DESIGN IS BASED ON A MINIMUM COMPRESSIVE STRENGTH (F'm) OF ASSEMBLY OF 1,500 PSI.

MASONRY UNITS SHALL MEET THE REQUIREMENTS OF ASTM C-90, GRADE N, WITH A NET AREA COMPRESSIVE STRENGTH OF 1,900 PSI.

MORTAR SHALL BE PREPARED IN ACCORDANCE WITH ASTM C-270. PROVIDE TYPE M MORTAR AT ALL MASONRY BELOW GRADE AND TYPE S AT ALL OTHER MASONRY.

GROUT SHALL BE PREPARED IN ACCORDANCE WITH ASTM C-476, WITH A MINIMUM COMPRESSIVE STRENGTH OF 2,000 PSI AT 28 DAYS.

REINFORCING STEEL SHALL BE BILLET STEEL CONFORMING TO ASTM A615, GRADE 60.

LAP SPLICE BAR REINFORCEMENT FOR MASONRY PER LAP SCHEDULE AND JOINT REINFORCEMENT A MINIMUM OF 6 INCHES.

CONCRETE MASONRY UNITS BELOW GRADE SHALL BE SOLID GROUTED.

CELLS WITH REINFORCING SHALL BE SOLID GROUTED AND VIBRATED.

STRUCTURAL STEEL NOTES:

STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING, UNLESS OTHERWISE NOTED:  
WIDE FLANGE SHAPES (W, WT): ASTM A992 (Fy=50 KSI)  
OTHER ROLLED SHAPES (M, S, HP, C, L): ASTM A36 (Fy=36 KSI)  
STEEL PIPE: ASTM A53, GRADE B (Fy=35 KSI)  
SQUARE AND RECTANGULAR TUBE: ASTM A500, GRADE B (Fy=46 KSI)  
ANCHOR BOLTS: ASTM F1554, GRADE 36  
HEADED ANCHOR STUDS: ASTM A108, GRADES 1010 TO 1020  
PLATES AND BARS: ASTM A36 (Fy=36 KSI)

SHEAR CONNECTORS AND HEADED WELDED STUDS OF TYPE AND SIZE NOTED SHALL BE TYPE B.

STRUCTURAL STEEL SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH GOOD STANDARD PRACTICE AND IS THE RESPONSIBILITY OF THE CONTRACTOR.

PROPER FIT IN THE FIELD OF STRUCTURAL STEEL SHALL BE IN ACCORDANCE WITH GOOD STANDARD PRACTICE AND IS THE RESPONSIBILITY OF THE CONTRACTOR.

THE FABRICATOR SHALL BE RESPONSIBLE FOR THE DESIGN AND PERFORMANCE OF ALL CONNECTIONS NOT FULLY DESIGNED OR DETAILED ON THE CONTRACT DOCUMENTS.

ANCHOR BOLTS SHALL BE ASTM F1554, A36 UNO. ANCHOR BOLTS SHALL BE SET WITH TEMPLATES WITH THE APPROPRIATE BOLT PROJECTION, 4" MINIMUM UNO. PROVIDE DOUBLE NUTS AND DOUBLE WASHERS FOR STEEL COLUMN ANCHOR BOLTS TO ALLOW FOR ADJUSTMENT IN BASE PLATE ELEVATION.

NON-SHRINK GROUT UNDER BASE PLATES SHALL BE NON-METALLIC WITH A MINIMUM COMPRESSIVE STRENGTH OF 5,000 PSI AT 28 DAYS.

HIGH STRENGTH BOLTED CONNECTIONS SHALL CONFORM TO THE AISC SPECIFICATIONS FOR STRUCTURAL JOINTS USING A325 BOLTS. UNLESS OTHERWISE NOTED, HIGH STRENGTH BOLTS MAY BE TIGHTENED BY ANY METHOD THEREIN. REGARDLESS OF THE METHOD USED IN TIGHTENING, A HARDENED WASHER SHALL BE USED UNDER THE TURNED ELEMENT. UNLESS OTHERWISE NOTED, BOLTED CONNECTIONS SHALL BE MADE WITH 3/4"Ø, ASTM A325 HIGH STRENGTH BOLTS.

CONNECTIONS REQUIRING FULL PRETENSIONING ARE SLIP-CRITICAL, AND INCLUDE BOLTED COLUMN SPLICES AND CONNECTIONS SUBJECT TO DIRECT TENSION.

ALL WELDING SHALL BE DONE IN ACCORDANCE WITH THE LATEST EDITION OF THE STRUCTURAL WELDING CODE, AWS D1.1. UNLESS NOTED OTHERWISE, MINIMUM WELD SIZE SHALL BE PER AISC 360, BUT SHALL BE NO LESS THAN 3/16" FILLET.

FIELD WELDING SHALL NOT BE STARTED UNTIL JOINT ELEMENTS ARE BOLTED IN INTIMATE CONTACT AND/OR ADJUSTED TO DIMENSIONS INDICATED WITH ALLOWANCE FOR EXPECTED WELD SHRINKAGE. MAINTAIN PLUMBNESS AND TRUENESS OF THE STRUCTURE.

FIELD WELDS FOR STRUCTURAL STEEL SHALL BE MADE WITH LOW HYDROGEN ELECTRODES. WELD FILLER METAL SHALL HAVE A MINIMUM TENSILE STRENGTH OF 70 KSI.

WOOD NOTES:

GENERAL STRUCTURAL WOOD FRAMING SHALL MEET THE MINIMUM STRESS REQUIREMENTS FOR DOUGLAS-FIR #2 AND SHALL BEAR THE STAMP OF AN APPROVED TESTING AGENCY.

ROOF SHEATHING SHALL BE 5/8" (19/32" MIN) PLYWOOD WITH A SPAN RATING OF AT LEAST 32/16. PANELS SHALL BE NAILED WITH 10d NAILS AT 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. 1/8" GAP BETWEEN INDIVIDUAL SHEETS. PLYWOOD SHALL BE APA RATED C-D EXTERIOR AND SHALL BEAR THE STAMP OF AN APPROVED TESTING AGENCY.

ALL WOOD-TO-WOOD CONNECTIONS SHALL MEET THE MINIMUM NAILING REQUIREMENTS OF THE BUILDING CODE.

PROVIDE SIMPSON CONNECTION HARDWARE AS SHOWN ON THE DRAWINGS. SUBSTITUTIONS MUST BE APPROVED BY THE ARCHITECT AND STRUCTURAL ENGINEER PRIOR TO USE. INSTALL CONNECTION HARDWARE ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS.

WALL SHEATHING SHALL BE 1/2" OSB ON THE EXTERIOR FACE OF ALL EXTERIOR WALLS. PANELS SHALL BE NAILED WITH 10d GALVANIZED NAILS AT 4" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE SUPPORTS. ALL PANEL EDGES SHALL BE BLOCKED.

INSTALL ALL ROOF PLYWOOD SHEATHING WITH THE LONG DIMENSION OF THE PANEL PERPENDICULAR TO THE SUPPORTS WITH A MINIMUM OF TWO SPANS FOR EACH PANEL. STAGGER ALL END JOINTS. PROVIDE 1/8" SPACE AT PANEL JOINTS FOR EXPANSION PER APA.

PREFABRICATED WOOD TRUSS NOTES:

SPECIAL INSPECTIONS OF THE FABRICATION PROCESS OF PRE-FABRICATED WOOD STRUCTURAL ELEMENTS AND ASSEMBLIES SHALL BE IN ACCORDANCE WITH THE IBC.

TRUSSES SHALL BE CONFIGURED TO FOLLOW FINAL ROOF LINES, UNLESS NOTED OTHERWISE.

TRUSSES SHALL BE DESIGNED FOR ALL LOAD COMBINATIONS REQUIRED BY THE BUILDING CODE. IN NO CASE SHALL THE DEAD LOAD BE LESS THAN 15 PSF ON THE TOP CHORD AND 10 PSF ON THE BOTTOM CHORD.

TRUSS MANUFACTURER SHALL SUPPLY ALL TRUSS CONNECTIONS USING PREFABRICATED STEEL CONNECTORS AS REQUIRED.

CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL TEMPORARY AND PERMANENT BRACING IN ADDITION TO ANY BRACING INDICATED ON THE PLANS.

ALL TEMPORARY AND PERMANENT BRACING FOR INDIVIDUAL TRUSS MEMBERS SHALL BE DESIGNED BY AND STAMPED BY A PROFESSIONAL ENGINEER PROVIDED BY CONTRACTOR AND/OR TRUSS MANUFACTURER. APPLIED ROOF SHEATHING AND OTHER ROOFING MATERIALS SHALL NOT BE ASSUMED TO PROVIDE SUFFICIENT BRACING FOR TRUSS CHORDS.

SHOP FABRICATED WOOD TRUSSES SHALL MEET DESIGN SPECIFICATIONS FOR METAL PLATE CONNECTED WOOD TRUSSES BY THE TRUSS PLATE INSTITUTE. PROVIDE PERMANENT AND TEMPORARY BRACING ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

COORDINATE ALL TRUSS DETAILS WITH ARCHITECTURAL PLANS.

SPLICE & DEVELOPMENT LENGTHS FOR REINFORCEMENT  
(UNLESS NOTED OTHERWISE ON THE DRAWINGS)

| BAR SIZE | LENGTH OF LAPPED SPLICES FOR REINFORCEMENT (INCHES) |        | LENGTH OF END ANCHORAGE FOR DEVELOPMENT OF REINFORCEMENT (INCHES) |        |             | HOOK LENGTH | BAR SIZE |
|----------|---|--------|---|--------|-------------|-------------|----------|
|          | TOP BARS*   | OTHERS | TOP BARS*   | OTHERS | HOOKED BARS |             |          |
| 3        | 28  | 22     | 22  | 17     | 9           | 6           | 3        |
| 4        | 38  | 29     | 29  | 22     | 11          | 8           | 4        |
| 5        | 47  | 36     | 36  | 28     | 14          | 10          | 5        |
| 6        | 56  | 43     | 43  | 33     | 17          | 12          | 6        |
| 7        | 81  | 63     | 63  | 48     | 20          | 14          | 7        |
| 8        | 93  | 72     | 72  | 55     | 22          | 16          | 8        |
| 9        | 105   | 81     | 81  | 62     | 25          | 20          | 9        |
| 10       | 118   | 91     | 91  | 70     | 28          | 22          | 10       |
| 11       | 131   | 101    | 101   | 78     | 31          | 24          | 11       |
| 14       | --  | --     | 121   | 93     | 38          | 31          | 14       |
| 18       | --  | --     | 161   | 124    | 50          | 41          | 18       |

\*TOP BARS ARE HORIZONTAL BARS SO PLACED THAT MORE THAN 12" OF CONCRETE IS CAST IN THE MEMBER BELOW THE BAR. HORIZONTAL BARS IN WALLS ARE TO BE CONSIDERED AS TOP BARS. VERTICAL BARS MAY BE CONSIDERED AS OTHER BARS.

UNLESS EITHER OF THE FOLLOWING TWO CASES EXIST FOR STRAIGHT BARS, THE DEVELOPMENT OR SPLICE LENGTH FOR STRAIGHT BARS IN THE ABOVE TABLE MUST BE MULTIPLIED BY 1.5:

I. THE CLEAR SPACING OF BARS BEING DEVELOPED OR SPLICED IS GREATER THAN OR EQUAL TO ONE BAR DIAMETER, THE CLEAR COVER IS GREATER THAN OR EQUAL TO ONE BAR DIAMETER, AND STIRRUPS OR TIES PROVIDED THROUGHOUT THE DEVELOPMENT OR SPLICE LENGTH MEET OR EXCEED THE CODE MINIMUM.

II. THE CLEAR SPACING OF BARS BEING DEVELOPED OR SPLICED IS GREATER THAN OR EQUAL TO TWO BAR DIAMETERS AND THE CLEAR COVER IS GREATER THAN OR EQUAL TO ONE BAR DIAMETER.

THE DEVELOPMENT LENGTH FOR HOOKED BARS, SIZE 11 AND SMALLER, PLACED WITH SIDE COVER GREATER THAN OR EQUAL TO 2 1/2" AND COVER ON THE BAR EXTENSION BEYOND THE HOOD (90° HOOK ONLY) GREATER THAN OR EQUAL TO 2", MAY BE MULTIPLIED BY 0.7.

VALUES IN THE ABOVE TABLE ARE NOT TO BE USED FOR EPOXY COATED REINFORCING AND/OR REINFORCING PLACED IN CONCRETE CONTAINING LIGHTWEIGHT AGGREGATE.

CONCRETE COVER FOR REINFORCEMENT  
(UNLESS NOTED OTHERWISE ON THE DRAWINGS)

| LOCATION  | MINIMUM COVER            |
|---|--------------------------|
| CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH  | 3"                       |
| CONCRETE EXPOSED TO EARTH OR WEATHER:<br>#6 AND LARGER<br>#5 AND SMALLER  | 2"<br>1 1/2"             |
| CONCRETE NOT EXPOSED TO WEATHER OR IN CONTACT WITH THE GROUND:<br>SLABS, WALLS, AND JOISTS:<br>#14 AND LARGER<br>#11 AND SMALLER<br>BEAMS AND COLUMNS | 1 1/2"<br>3/4"<br>1 1/2" |

**CERTUS**

STRUCTURAL ENGINEERS

900 S. Kansas Avenue; Suite 400  
Topeka, Kansas 66612  
Phone: (785) 291-0400  
Fax: (785) 291-0401  
Proj #01190008.120  
Certificate Of Authorization  
E-1392  
Revit 2023 Local

SUBMISSION DATES  
2023-05-23

SHEET TITLE  
GENERAL NOTES

PROJECT NUMBER  
230117

SHEET NUMBER  
S-001

CORE & SHELL BUILDING FOR  
STREETS OF WEST PRYOR LOT 5  
LEE'S SUMMIT, MISSOURI

SUBMISSION DATES  
2023-05-23

SHEET TITLE  
GENERAL NOTES

PROJECT NUMBER  
230117

SHEET NUMBER  
S-001

**schwerdt design group**


architecture | interiors | planning

2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579

500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115







## FOUNDATION PLAN

SCALE: 1/8" = 1'-0"

**FLOOR CONSTRUCTION:** 4" CONCRETE SLAB ON GRADE REINFORCE w/6X6 - W2.9XW2.9 WELDED WIRE FABRIC. LOCATE REINFORCING 1 1/2" BELOW TOP OF SLAB. PROVIDE 6" LAYER OF GRANULAR LEVELING COURSE (#57 STONE) BELOW SLAB. VAPOR BARRIER SHALL BE PLACED DIRECTLY OVER GRANULAR FILL AND UNDER SLAB. REFERENCE ARCHITECTURAL AND SPECIFICATIONS FOR FURTHER DETAILS.

THE BUILDING FLOOR SLAB SHALL BE WITHIN A FLATNESS TOLERANCE OF 1/4" PER 10'-0".

TOSL - TOP OF SLAB ELEVATION: 100-0 = SITE ELEVATION: 984.25, 99-4 = SITE ELEVATION 983.58

TOF - TOP OF FOOTING ELEVATION: 98-8 OR 99-4, RE: PLAN

SJ - SLAB JOINT

FS - FOOTING STEP

C-(#) - DENOTES COLUMN MARK, REFERENCE SCHEDULE

BB (#) - DENOTES COLUMN BASE PLATE TYPE REFERENCE

BP-(#) - DENOTES COLUMN BASE PLATE TYPE, REFERENCE DETAILS

COORDINATE ALL PENETRATIONS THROUGH THE SLAB AND ALL UNDER SLAB ITEMS WITH OTHER TRADES BEFORE CONSTRUCTION.

VERIFY ALL DIMENSIONS SHOWN WITH ARCHITECTURAL AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION. INFORM ENGINEER OF ALL DISCREPANCIES.

| ISOLATED FOOTING |              |             |
|------------------|--------------|-------------|
| MARK             | SIZE (LxWxD) | REINFORCING |
| F-1              | 3-0x3-0x3-0  | (4) #5 EW   |
| F-2              | 5-0x5-0x1-4  | (6) #5 EW   |

| COLUMN SCHEDULE |                |
|-----------------|----------------|
| MARK            | SIZE           |
| C-1             | HSS4x4x1/4     |
| C-2             | HSS5X5X1/4     |
| C-3             | DBL HSS9X7X3/8 |
| C-4             | (7) 2X8        |

**CERTUS**   
STRUCTURAL ENGINEERS

900 S. Kansas Avenue; Suite 400  
Topeka, Kansas 66612  
Phone: (785) 291-0400  
Fax: (785) 291-0401  
Proj #01190008.120  
Certificate Of Authorization  
E-1392  
Revit 2023 Local



**CORE & SHELL BUILDING FOR  
STREETS OF WEST PRYOR LOT 5  
LEE'S SUMMIT, MISSOURI**

|                  |
|------------------|
| SUBMISSION DATES |
| 2023-05-23       |


SHEET TITLE  
FOUNDATION PLAN

PROJECT NUMBER  
**230117**

SHEET NUMBER  
**S-101**



FILEPATH: C:\Users\John.Donaldson\Documents\01190008.120 - Streets of West Pryor - Lot 5\_ JohnDon7.rvt  
DATE: 5/24/2023 7:32:29 AM  
DRAWN BY: Author



WALL FRAMING PLAN

SCALE: 1/8" = 1'-0"

WALL CONSTRUCTION: TYPICAL EXTERIOR WALL CONSTRUCTION SHALL BE 2x8 WOOD STUDS @ 16" MAXIMUM ON CENTER. MINIMUM (2) TRIMMER STUDS AND (2) KING STUDS SHALL BE PROVIDED AT ALL OPENINGS IN EXTERIOR, BEARING, AND SHEAR WALLS. TYPICAL INTERIOR SHEAR WALL CONSTRUCTION SHALL BE 2x6 WOOD STUDS @16 ON CENTER. REFERENCE HEADER SCHEDULE FOR CONDITIONS REQUIRING ADDITIONAL STUDS. DOUBLE TOP PLATE SHALL BE CONTINUOUS AND SHALL BE SPLICED PER TYPICAL DETAIL. SEE SHEAR WALL SCHEDULE FOR FURTHER INFORMATION ON CONSTRUCTION OF SHEAR WALLS.

VERIFY ALL DIMENSIONS SHOWN WITH ARCHITECTURAL AND EXISTING CONDITIONS PRIOR TO CONSTRUCTION. INFORM ENGINEER OF ALL DISCREPANCIES.

NOTE: FACE OF STUD ALIGNS WITH THE CONCRETE SLAB EDGE FOR ALL EXTERIOR WALLS. ALL PLAN DIMENSIONS TO EXTERIOR WALLS ARE TO FACE OF STUD/FACE OF CONCRETE SLAB. ALL DIMENSIONS TO INTERIOR WALLS ARE TO FACE OF STUD/STRUCTURAL WALL.

| WOOD SHEARWALL (SW) SCHEDULE |                     |  |                  |                   |                         |                        |  |
|------------------------------|---------------------|--|------------------|-------------------|-------------------------|------------------------|--|
| MARK                         | STUD SIZE & SPACING | SHEATHING MATERIAL                                     | EDGE NAILING     | FIELD NAILING     | COMPRESSION CHORD (MIN) | HOLDDOWN               | SILL PLATE ANCHOR BOLT AT FDN                |
| SW-1                         | 2x8@16              | 1/2" OSB ZIP SYSTEM PANELS<br>BLOCKED ONE SIDE OF WALL | 8d COMMON @4" OC | 8d COMMON @12" OC | (3) 2x8 WD STUDS        | HDU8-SD2.5<br>7/8"Ø AB | 5/8"Ø AB AT 1'-4" OR<br>3/4"Ø AB AT 2'-0" OC |
| SW-2                         | 2x8@16              | 1/2" OSB ZIP SYSTEM PANELS<br>BLOCKED ONE SIDE OF WALL | 8d COMMON @6" OC | 8d COMMON @12" OC | (2) 2x8 WD STUDS        | HDU4-SD2.5<br>5/8"Ø AB | 5/8"Ø AB AT 2'-0" OR<br>3/4"Ø AB AT 2'-8" OC |
| SW-3                         | 2x6@16              | 1/2" (MIN) GYPSUM BOARD<br>BLOCKED BOTH SIDES OF WALL  | 5d COOLER @7" OC | 5d COOLER @7" OC  | (2) 2x6 WD STUDS        | HDU4-SD2.5<br>5/8"Ø AB | 5/8"Ø AB AT 2'-0" OR<br>3/4"Ø AB AT 2'-8" OC |


**CERTUS**  
STRUCTURAL ENGINEERS  
900 S. Kansas Avenue; Suite 400  
Topeka, Kansas 66612  
Phone: (785) 291-0400  
Fax: (785) 291-0401  
Proj #01190008.120  
Certificate Of Authorization  
E-1392  
Revit 2023 Local

**schwerdt design group**  
architecture | interiors | planning  
2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579  
500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115

CORE & SHELL BUILDING FOR  
STREETS OF WEST PRYOR LOT 5  
LEE'S SUMMIT, MISSOURI

|                   |
|-------------------|
| SUBMISSION DATES  |
| 2023-05-23        |
| SHEET TITLE       |
| WALL FRAMING PLAN |
| PROJECT NUMBER    |
| 230117            |
| SHEET NUMBER      |
| S-102             |





**NOTE: FACE OF STUD ALIGNS WITH THE CONCRETE SLAB EDGE FOR ALL EXTERIOR WALLS. ALL PLAN DIMENSIONS TO EXTERIOR WALLS ARE TO FACE OF STUD/FACE OF CONCRETE SLAB. ALL DIMENSIONS TO INTERIOR WALLS ARE TO FACE OF STUD/STRUCTURAL WALL.**

## ROOF FRAMING PLAN

SCALE: 1/8" = 1'-0"

ROOF CONSTRUCTION: WOOD SHEATHING (19/32" MIN) OVER PREFAB WOOD ROOF TRUSSES @ 2'-0" OC MAX. SHEATHING SHALL BE CONTINUOUS UNDER AREAS OF OVERBUILD. REFERENCE GENERAL NOTES FOR SHEATHING SPECIFICATIONS AND ATTACHMENT.

DESIGN ALL TRUSSES FOR 15 PSF NET UPLIFT.

PROVIDE BRIDGING AS PRESCRIBED BY THE TRUSS MANUFACTURER REQUIREMENTS.

TOS - TOP OF STEEL ELEVATION: NOTED THUS (ELEV)

TOP OF PARAPET = 125-0 (MAX)

TRUSS BEARING ELEVATION = 114'-4"

TYPICAL HEADERS IN OPENINGS LESS THAN 4'-0" SHALL BE (4) 2X8 OR DEEPER, ALL HEADERS IN OPENINGS UP TO 6'-6" SHALL BE (4) 2X10 OR DEEPER, ALL HEADERS IN OPENINGS UP TO 8'-4" SHALL BE (4) 2x12. CONSTRUCT HEADERS PER "TYPICAL HEADER CONSTRUCTION" DETAIL." ALL HEADERS SHALL HAVE (1) TRIMMER MINIMUM AND (2) DEDICATED STUDS MINIMUM. PROVIDE (2) TRIMMERS AT OPENINGS LARGER THAN 7'-4".

LINTELS: LOOSE BRICK LINTELS FOR DOOR AND WINDOW OPENINGS UP TO 8'-4" SHALL BE L5X5X3/8 GALVANIZED (ASTM A36)

DESIGN ROOF TRUSSES TO SUPPORT RTU LOADS AT LOCATIONS SHOWN. NOTIFY ENGINEER IF WEIGHTS, SIZES, OR LOCATIONS VARY FROM THAT SHOWN.

VERIFY ALL DIMENSIONS SHOWN WITH ARCHITECTURAL DRAWINGS PRIOR TO CONSTRUCTION. INFORM ENGINEER OF ALL DISCREPANCIES.


FILE PATH: C:\Users\John.Donaldson\Documents\01190008.120 - Streets of West Pryor - Lot 5\_JohnDon7.rvt  
DATE: 5/24/2023 7:32:30 AM  
DRAWN BY: Author



schwerdt design group

architecture | interiors | planning  
2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579

500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



**CORE & SHELL BUILDING FOR  
STREETS OF WEST PRYOR LOT 5  
LEE'S SUMMIT, MISSOURI**

SUBMISSION DATES  
2023-05-23

SHEET TITLE  
ROOF FRAMING PLA

PROJECT NUMBER  
**230117**

SHEET NUMBER  
**S-103**

**CERTUS**   
STRUCTURAL ENGINEER

900 S. Kansas Avenue; Suite 400

Topeka, Kansas 66612

Phone: (785) 291-040

**Fax: (785) 291-0401**

Proj #:01190008.120

**Certificate Of Aut**


Certificate Of Aut  
E-1392

Revit 2023 Local





**schwerdt design group**  
architecture | interiors | planning  
2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: (785) 273-7540  
fax: (785) 273-7579  
500 north broadway suite 200  
oklahoma city, ok 73102  
phone: (405) 231-3105  
fax: (405) 231-3115



**CORE & SHELL BUILDING FOR  
STREETS OF WEST PRYOR LOT 5**  
LEE'S SUMMIT, MISSOURI


| SUBMISSION DATES |
|------------------|
| 2023-05-23       |

| SHEET TITLE       |
|-------------------|
| FRAMING ISOMETRIC |

| PROJECT NUMBER |
|----------------|
| <b>230117</b>  |

| SHEET NUMBER |
|--------------|
| <b>S-201</b> |

ISOMETRIC VIEWS ARE INTENDED TO SHOW  
GENERAL FRAMING CONFIGURATIONS AND  
ARE FOR REFERENCE ONLY. IN NO WAY SHALL  
THESE VIEWS BE USED TO CONVEY THE FULL  
EXTENT OF FRAMING MATERIALS REQUIRED.  
QUANTITY OF MATERIALS SHALL BE BASED  
UPON STRUCTURAL PLANS, DETAILS,  
ARCHITECTURAL DRAWINGS, AND THE FULL  
EXTENT OF CONSTRUCTION DOCUMENTS.




① STRUCTURAL STEEL ISOMETRIC VIEW FROM SE CORNER  
SCALE: NONE

**CERTUS**  
STRUCTURAL ENGINEERS  
900 S. Kansas Avenue; Suite 400  
Topeka, Kansas 66612  
Phone: (785) 291-0400  
Fax: (785) 291-0401  
Proj #:01190008.120  
Certificate Of Authorization  
E-1392  
Revit 2023 Local





2231 sw wanamaker rd, suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579  
500 north broadway, suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115




CORE & SHELL BUILDING FOR  
STREETS OF WEST PRYOR LOT 5  
LEE'S SUMMIT, MISSOURI

SUBMISSION DATES  
2023-05-23

SHEET TITLE  
CONCRETE DETAILS &  
SECTIONS I

PROJECT NUMBER  
230117

SHEET NUMBER  
S-301




**CERTUS**  
STRUCTURAL ENGINEERS  
900 S. Kansas Avenue; Suite 400  
Topeka, Kansas 66612  
Phone: (785) 291-0400  
Fax: (785) 291-0401  
Proj #01190008.120  
Certificate Of Authorization  
E-1392  
Revit 2023 Local





architecture | interiors | planning  
2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579  
500 north broadway, suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



CORE & SHELL BUILDING FOR  
STREETS OF WEST PRYOR LOT 5  
LEE'S SUMMIT, MISSOURI


SUBMISSION DATES  
2023-05-23

SHEET TITLE  
FRAMING DETAILS &  
SECTIONS I

PROJECT NUMBER  
230117


SHEET NUMBER  
S-601

**CERTUS**  
STRUCTURAL ENGINEERS  
900 S. Kansas Avenue; Suite 400  
Topeka, Kansas 66612  
Phone: (785) 291-0400  
Fax: (785) 291-0401  
Proj #01190008.120  
Certificate Of Authorization  
E-1392  
Revit 2023 Local




- NOTES:
1. SPLICE REQUIRED OVER ALL SHEARWALLS AND ALL EXTERIOR AND BEARING WALLS.
  2. SPECIFIC SPLICE REQUIREMENTS DO NOT APPLY TO INTERIOR NON-SHEARWALLS OR TOP OF PARAPET WALLS UNLESS NOTED OTHERWISE.


5 TYPICAL TOP PLATE SPLICE DETAIL  
SCALE: NONE




4 TYPICAL BUILT-UP HEADER CONSTRUCTION  
SCALE: NONE




3 TYPICAL HEADER CONSTRUCTION DETAIL  
SCALE: NONE




2 NON-LOAD BEARING WALL LATERAL SUPPORT DETAIL  
SCALE: NONE




1 TYPICAL HOLDOWN ASSEMBLY CORNER (ALTERNATE)  
SCALE: NONE




6 TYPICAL SHEARWALL CONSTRUCTION  
SCALE: NONE




7 TYPICAL CANOPY CONNECTION BLOCKING DETAIL  
SCALE: NONE




8 TYPICAL SHEAR BLOCKING BETWEEN TRUSSES  
SCALE: NONE



9 TYPICAL SHEARWALL TERMINATION AT STEEL COLUMN DETAIL  
SCALE: NONE



10 TYPICAL TUBE COLUMN TO BEAM CONNECTION  
SCALE: NONE




11 TYPICAL STEEL CONNECTIONS DETAIL (SHEAR TABS)  
SCALE: NONE

| BOLT SCHEDULE   |            |                   |
|---|------------|-------------------|
| CONNECTION BEAM SIZE  | LENGTH (L) | (#) ROWS OF BOLTS |
| W8, W10   | 6"         | 2                 |
| W12, W14  | 9"         | 3                 |
| W16   | 1'-0"      | 4                 |
| W18   | 1'-3"      | 5                 |
| W21   | 1'-6"      | 6                 |
| W24, W27  | 1'-9"      | 7                 |
| W30, W33  | 2'-6"      | 10                |
| NOTE: BOLTS SHALL BE 3/4"Ø A325 AT 3" CENTERS, UNLESS NOTED OTHERWISE |            |                   |





architecture | interiors | planning  
2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579  
500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



CORE & SHELL BUILDING FOR  
STREETS OF WEST PRYOR LOT 5  
LEE'S SUMMIT, MISSOURI


| SUBMISSION DATES |
|------------------|
| 2023-05-23       |

| SHEET TITLE                   |
|-------------------------------|
| FRAMING DETAILS & SECTIONS II |


| PROJECT NUMBER |
|----------------|
| 230117         |

| SHEET NUMBER |
|--------------|
| S-602        |


**CERTUS**  
STRUCTURAL ENGINEERS  
900 S. Kansas Avenue; Suite 400  
Topeka, Kansas 66612  
Phone: (785) 291-0400  
Fax: (785) 291-0401  
Proj #01190008.120  
Certificate Of Authorization  
E-1392  
Revit 2023 Local




**A** SECTION  
SCALE: NONE




**B** SECTION  
SCALE: NONE




**C** SECTION  
SCALE: NONE




**D** SECTION  
SCALE: NONE



**E** SECTION  
SCALE: NONE



**F** SECTION  
SCALE: NONE



**G** SECTION  
SCALE: NONE





architecture | interiors | planning  
2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579  
500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



CORE & SHELL BUILDING FOR  
STREETS OF WEST PRYOR LOT 5  
LEE'S SUMMIT, MISSOURI


| SUBMISSION DATES |
|------------------|
| 2023-05-23       |

| SHEET TITLE                    |
|--------------------------------|
| FRAMING DETAILS & SECTIONS III |


| PROJECT NUMBER |
|----------------|
| 230117         |

| SHEET NUMBER |
|--------------|
| S-603        |


**CERTUS**  
STRUCTURAL ENGINEERS  
900 S. Kansas Avenue; Suite 400  
Topeka, Kansas 66612  
Phone: (785) 291-0400  
Fax: (785) 291-0401  
Proj #01190008.120  
Certificate Of Authorization  
E-1392  
Revit 2023 Local



**B** SECTION  
SCALE: NONE



**C** SECTION  
SCALE: NONE



**D** SECTION  
SCALE: NONE



15000 - MECHANICAL SPECIFICATIONS

SECTION 15000 - MECHANICAL REQUIREMENTS

1. GENERAL REQUIREMENTS
- A. ALL WORK SHALL BE IN ACCORDANCE W/ LATEST EDITION OF INTERNATIONAL BUILDING MECHANICAL & PLUMBING CODES, CODES AS ADOPTED BY CITY, COUNTY, STATE & ALL OTHER APPLICABLE CODES.
- B. FURNISH & INSTALL ALL LABOR & MATERIALS REQUIRED FOR COMPLETE, FUNCTIONING, MECHANICAL & PLUMBING SYSTEMS W/ ALL ASSOCIATED EQUIPMENT & APPARATUS AS SHOWN ON PLANS. "PROVIDE" MEANS TO FURNISH & INSTALL.
- C. OBTAIN & PAY FOR ALL PERMITS REQUIRED FOR EXECUTION OF THIS WORK & SHALL MAKE ARRANGEMENTS FOR MODIFICATIONS TO WATER, GAS & SEWER CONNECTIONS TO EXISTING SITES AS REQUIRED.
- D. VISIT SITE & OBSERVE CONDITIONS UNDER WHICH WORK WILL BE DONE. ANY DISCREPANCIES SHALL BE CALLED TO ARCHITECT'S ATTENTION. NO SUBSEQUENT ALLOWANCE WILL BE MADE IN CONTRACT FOR ANY ERROR OR NEGLIGENCE ON CONTRACTOR'S PART.
- E. FINAL ACCEPTANCE OF WORK SHALL BE SUBJECT TO CONDITION THAT ALL SYSTEMS, EQUIPMENT, APPARATUS & APPLIANCES OPERATE SATISFACTORILY AS DESIGNED & INTENDED. WORK SHALL INCLUDE REQUIRED ADJUSTMENT OF SYSTEMS & CONTROL EQUIPMENT INSTALLED UNDER THESE SPECIFICATIONS.
- F. WARRANTY TO OWNER QUALITY OF MATERIAL, EQUIPMENT, WORKMANSHIP & OPERATION OF EQUIPMENT PROVIDED UNDER THESE SPECIFICATIONS FOR ONE YEAR FROM & AFTER COMPLETION OF BUILDING & ACCEPTANCE OF MECHANICAL SYSTEMS BY OWNER. ALL MATERIALS INSTALLED IN PLUMBING SHALL BE NONCOMBUSTIBLE OR HAVE FLAME/SMOKE INDEX OF NO MORE THAN 25/50 IN ACCORDANCE W/ ASTM E 84.
- G. ROOF PENETRATIONS - MADE BY AUTHORIZED ROOFING CONTRACTOR WHEN REQUIRED.

SECTION 15100 - PLUMBING

1. PIPING
- A. WATER PIPING - ALL WATER PIPING SHALL BE 95-5 TIN-ANTIMONY JOINED TYPE L COPPER, INSULATE W/ FIBERGLASS W/ ASJ & PVC COVERS. THICKNESS IN WASTE W/ ASHRAE 90.1.
- B. WASTE & VENT PIPING - C) BELL & SPIGOT OR HUBLESS C) W/ NEOPRENE GASKET FITTINGS W/ STAINLESS STEEL BANDS. SCHED 40 PVC W/ SOLVENT WELDS MAY BE USED WHERE ALLOWED BY LOCAL CODE. PVC NOT ALLOWED IN PLUMBING.
- C. ROOF/STORM DRAIN PIPING - C) BELL & SPIGOT OR HUBLESS C) W/ NEOPRENE GASKET FITTINGS W/ STAINLESS STEEL BANDS. SCHED 40 PVC W/ SOLVENT WELDS MAY BE USED WHERE ALLOWED BY LOCAL CODE. PVC NOT ALLOWED IN PLUMBING. INSULATE W/ MIN 1/2" FIBERGLASS PIPE WRAP W/ ASJ JACKET.
- D. GAS PIPING - PROVIDE SCHED 40 CONT. WELD CARBON STEEL W/ CORRESPONDING FITTINGS. PROVIDE THREADED FITTINGS. PROVIDE IRON BODY-BRASS PLUG GAS STOPS. PAINT ALL EXPOSED GAS PIPING ON THE EXTERIOR OF THE BUILDING INCLUDING ON THE ROOF.
2. VALVES
- A. BALL VALVES - 2" & UNDER - BRONZE FULL PORT W/ TEFLON SEATS, BRONZE BALL & INSULATED HANDLE.
- B. BALANCING VALVES - ARMSTRONG MODEL CBV 1 OR CBV II, 125 PSI-WP AT 250 DEGREES F., WATER CONNECTIONS W/ BUILT-IN CHECK VALVES SOLDERED OR FLANGED ENDS. PROVIDE POLYURETHANE INSULATION COVER.
- C. CHECK VALVES - 2" 7" SMALLER SOLDERED OR SOLDER BRONZE CHECK VALVE, 200 PSI-WOG/125 PSI-WSP, TEFLON OR BRONZE DISC & SEAT. RING, 2-1/2" & LARGER FLANGED, ASTM 126 IRON BODY, BRONZE TRIMMED, 200 PSI-WOG/125 PSI-WSP.
- D. BUTTERFLY VALVES - 3" & LARGER LEVER ASTM A126 C) DRILLED & TAPPED FULL LUG BODY, 200 PSI-WOG, EXTENDED NECK, BRONZE DISC, STAINLESS STEEL STEM, FIELD-REPLACEABLE EPDM SLEEVE & STEM SEALS.
- E. EQUIVALENT VALVE MANUFACTURERS: MILWAUKEE, STOCKHAM, POWELL, RED-WHITE, CRANE, APOLLO, MUELLER, MUESCO, WATTS, HAYS, ROCKWELL-NORSTROM.

- FIXTURES - SEE SCHEDULES
- A. FIXTURES: AMERICAN STANDARD, KOHLER, CRANE, ZURN, TOTO
- B. STAINLESS STEEL FIXTURES: ELKAY, JUST, MOEN COMMERCIAL
- C. FITTINGS & SUPPORTS: JOSAM, SMITH, WADE, ZURN, OR JONESPEC.
- D. SEATS: CHURCH, OLSONITE, BEMIS OR BENKE.
- E. DRINKING FOUNTAINS: HALSEY TAYLOR, ELKAY, GASS, OR HANS.
- F. TRIM BY DELTA, ELJER, KOHLER, AMERICAN STANDARD, CRANE, SLOAN.
- G. FLUSHVALVES: SLOAN, ZURN, TOTO
- H. DRAINS BY WADE, ZURN, WOODFORD, SMITH, JOSAM.
- I. ROOF DRAINS - CAST IRON ROOF DRAIN W/ FLANGE, C) MUSHROOM DOME. 2" DAM FOR OVERFLOW DRAINS
- J. WALL HYDRANTS JOSAM SERIES 71000 W/ CONNECTIONS FOR 3/4" PIPE & HOSE. NON-FREEZING W/ KEY, VACUUM BREAKER, LOCKING COVER. EQUIVALENT BY J.R. SMITH, WADE, WOODFORD OR ZURN.

EQUIPMENT - SEE SCHEDULES

- A. WATER HEATER - STATE, RHEEM, NATIONAL, A.O. SMITH. PORCELAINIZED GLASSLINED TANK. COLD WATER INLET DROP TUBE. MAGNESIUM ANODE RODS. ULL SEAL, 160 PSI. FACTORY TEMPERATURE & PRESSURE RELIEF VALVE. N.S.F. CONSTRUCTION. 3 YR WARRANTY.
- B. SUBMERSIBLE SUMP PUMPS - SIMPLEX/DUPLEX SUBMERSIBLE PUMP SYSTEM AS SCHED/SHOWN. PUMP CASING ONE PIECE CAST IRON W/ SUPPORT LEGS, C) SUCTON STRAINER. VERTICAL MOTOR, NEMA-B, NOT LESS THAN HP SCHED & 1750 RPM. AUTO-RESET THERMAL/OVERLOAD PROTECTION.
- C. RECIRCULATION PUMPS - HORIZONTAL, OIL-LUBRICATED, ALL BRONZE. NON-OVERLOADING MOTOR.
- EXECUTION
- A. PROVIDE UNIONS OR FLANGED JOINTS IN EACH PIPE LINE PRECEDING CONNECTIONS TO EQUIPMENT TO ALLOW REMOVAL FOR REPAIR OR REPLACEMENT. PROVIDE ALL SOLDERED & CONTROL VALVES W/ UNIONS ADJACENT TO EACH CONNECTION. PROVIDE SOLDERED END VALVES W/ UNION ADJACENT TO VALVE UNLESS VALVE CAN BE OTHERWISE EASILY REMOVED FROM LINE.
- B. AFTER PIPING IS IN PLACE TEST LINES TO ENSURE NO LEAKS.
- C. ALL PIPING & EQUIPMENT SHALL BE SUPPORTED PROPERLY FROM STRUCTURE.
- D. ESCUTCHEONS - PROVIDE NICKEL-BRASS OR CHROME PLATED ON ALL EXPOSED PIPES WHEN PASSING THRU WALL OR CEILING OF FINISHED ROOMS.
- E. VERIFY FLOOR MATERIALS USED FROM ARCHITECTURAL PLANS & PROVIDE PROPER CLEANOUT TOPS, WHERE THEY OCCUR IN CARPET, QUARRY TILE, VINYL TILE OR CERAMIC TILE.
- F. PROVIDE WATER HAMMER ARRESTORS FOR ALL PLUMBING BANKS W/ FIXTURES UTILIZING FLUSH VALVES IN ANY CAPACITY. LOCATE ARRESTER BETWEEN LAST TWO FIXTURES SERVED ON BRANCH LINE.

SECTION 15300 - HVAC GENERAL

- A. PROVIDE COMPLETE HVAC SYSTEM AS SHOWN ON DRAWINGS INCLUDING ALL NECESSARY EQUIPMENT, DUCTWORK, GRILLES, & FILTERS. PROVIDE OPERATING & MAINTENANCE INSTRUCTIONS ON ALL EQUIPMENT.
- B. ALL HVAC WORK SHALL BE DONE IN STRICT ACCORDANCE W/ ALL REQUIREMENTS OF LOCAL BUILDING CODE, ASHRAE, NEC, NFPA, & ALL OTHER APPLICABLE CODES HAVING JURISDICTION.
- DUCTWORK
- A. HVAC DUCTWORK SHALL BE GALV SHEET METAL OF GAUGES & JOINT TYPES SPECIFIED IN SMACNA MANUAL. PROVIDE TURNING VANES IN ELBOWS.
- B. VOLUME DAMPERS SHALL BE MANUAL LOCKING BLADE TYPE.
- C. ALL DUCTWORK MUST BE SUPPORTED PROPERLY FROM STRUCTURE.
- D. WRAP ALL SUPPLY & OUTSIDE AIR HVAC DUCTWORK W/ CERTAINTED 1-1/2" THICK INSULATION W/ VAPOR BARRIER IN CONCEALED LOCATIONS. ALSO LINE FIRST 10' OF SUPPLY DUCTWORK FOR SOUND ATTENUATION ( IN ADDITION TO WRAP) LINE ALL RETURN AIR DUCTS & TRANSFER BOOTS W/ 1/2" LINER.

EQUIPMENT

- A. ROOFTOP UNITS AS SCHEDULED. EQUIVALENTS BY TRANE, CARRIER, YORK, LENNOX, A/CAN, DAKIN, MIN 14" ROOF CURB. PROVIDE SLOPED CURB AS REQUIRED FOR LEVEL UNIT INSTALLATION. ECONOMIZER W/ BAROMETRIC RELIEF, FIXED DRY BULB CONTROL. 2" MERV 7 FILTERS. LOUVERED HAIL GUARDS. 30 DEG LOW AMBIENT.
- B. EXHAUST FANS - EQUIVALENT BY COOK, PENN, A/CME, GREENHECK, JENNAIRE, TWIN CITY. PROVIDE W/ SPEED CONTROLS FOR ALL FANS LESS THAN 1/3HP TO BE FURNISHED TO E/C FOR MOUNTING AT FAN. PROVIDE W/ 14" MIN. CURB.
- C. PROVIDE PROGRAMMABLE THERMOSTATS W/ STAGES OF HEATING AND COOLING AS REQUIRED BY STAGES OF HEATING AND COOLING ON SPECIFIED EQUIPMENT. SEVEN (7) DAY PROGRAMMING CAPABILITY W/ 2 OCC/UNOCC PERIODS/DAY. AUTO HEAT/COOL CHANGE OVER. LOCKING SETPOINTS TO PREVENT TAMPERING. PROVIDE W/ ALL INTERFACES TO OTHER EQUIPMENT AS REQUIRED. THERMOSTATS BY HONEYWELL, JOHNSON CONTROLS, WHITE-ROGERS, TRANE, CARRIER, A/CAN, LENNOX, DAKIN, OR APPROVED EQUAL.

EXECUTION

- B. COORDINATE W/ E/C TO PROVIDE ALL WIRING BETWEEN EQUIPMENT, DAMPERS, THERMOSTATS & ALL OTHER REQUIRED CONTROLS & DEVICES. PROVIDE ANY REQUIRED INTERFACES TO FIRE ALARM OR SIMILAR SYSTEMS.
- C. PROVIDE GROUND-MOUNTED UNITS ON 4", REINFORCED CONCRETE BASE, 4" LARGER THAN UNIT ON EACH SIDE.
- D. ROOF-MOUNTED UNITS ON EQUIPMENT SUPPORTS OR CURBS. ANCHOR UNITS TO SUPPORTS
- E. PROVIDE FACTORY-AUTHORIZED SERVICE START UP ON EQUIPMENT. TRAIN OWNER'S MAINTENANCE PERSONNEL ON STARTUP, SHUTDOWN, TROUBLESHOOTING, SERVICING, PREVENTIVE MAINTENANCE.

16000 - ELECTRICAL SPECIFICATIONS

SECTION 16000 - ELECTRICAL REQUIREMENTS

GENERAL REQUIREMENTS

- A. ALL WORK SHALL BE IN ACCORDANCE W/ LATEST EDITION OF INTERNATIONAL BUILDING CODE, NATIONAL ELECTRICAL CODE, NFPA, CODES AS ADOPTED BY CITY, COUNTY, STATE & ALL OTHER APPLICABLE CODES.
- B. ALL MATERIALS & EQUIPMENT SHALL BE NEW & SHALL BEAR U.L. LABEL WHERE APPLICABLE. PROVIDE WATERPROOF EQUIPMENT ENCLOSURES WHERE REQUIRED.
- C. OBTAIN & PAY FOR ALL PERMITS REQUIRED FOR EXECUTION OF THIS WORK & SHALL MAKE ARRANGEMENTS FOR MODIFICATIONS TO ELECTRICAL CONNECTIONS TO BUILDING AS REQUIRED.
- D. CONTRACTOR SHALL PROVIDE ALL LABOR & MATERIALS REQUIRED TO HAVE COMPLETE FUNCTIONING ELECTRICAL LIGHTING & POWER SYSTEMS TOGETHER W/ ALL ASSOCIATED EQUIPMENT & APPARATUS AS SHOWN ON PLANS.
- E. WHERE AN ELECTRICAL DEVICE IS REQUIRED BY CODE BUT NOT SHOWN, IT SHALL BE PROVIDED AS THOUGH FULLY SHOWN & SPECIFIED.
- F. CONTRACTOR SHALL VISIT SITE & OBSERVE CONDITIONS UNDER WHICH WORK WILL BE DONE. ANY DISCREPANCIES SHALL BE CALLED TO ARCHITECT'S ATTENTION. NO SUBSEQUENT ALLOWANCE WILL BE MADE IN THIS CONNECTION FOR ANY ERROR OR NEGLIGENCE ON CONTRACTOR'S PART.
- G. FINAL ACCEPTANCE OF WORK SHALL BE SUBJECT TO CONDITION THAT ALL SYSTEMS, EQUIPMENT, APPARATUS & APPLIANCES OPERATE SATISFACTORILY AS DESIGNED & INTENDED. WORK SHALL INCLUDE REQUIRED ADJUSTMENT OF SYSTEMS & CONTROL EQUIPMENT INSTALLED UNDER THESE SPECIFICATIONS.
- H. WARRANTY TO OWNER QUALITY OF MATERIALS, EQUIPMENT, WORKMANSHIP & OPERATION OF EQUIPMENT PROVIDED UNDER THESE SPECIFICATIONS FOR ONE YEAR FROM & AFTER COMPLETION OF BUILDING & ACCEPTANCE OF MECHANICAL SYSTEMS BY OWNER.
- I. ALL MATERIALS INSTALLED IN PLUMBING SHALL BE NONCOMBUSTIBLE OR HAVE FLAME/SMOKE INDEX OF NO MORE THAN 25/50 IN ACCORDANCE W/ ASTM E 84.

SECTION 16100 - CONDUIT & CONDUCTORS

- A. FOLLOW CIRCUITING SHOWN ON PLANS. USE NO CONDUIT SMALLER THAN 1/2" & NO CONDUCTORS SMALLER THAN #12 GA. UNLESS NOTED OTHERWISE.
- B. WIRE SHALL BE IN NON-FLEXIBLE METALLIC CONDUIT (EMT, IMC OR RMC) FOR ALL CIRCUITS AND FEEDERS GREATER THAN 30A, LIGHT SWITCH RISERS, KITCHEN CIRCUITS & HOME RUNS.
- C. MC CABLE ACCEPTABLE FOR BRANCH COMMENCEMENT CIRCUITS AND LIGHTING CIRCUITS. DO NOT DASHY CHAIN LIGHT FIXTURES. PROVIDE MC LUMINARY CABLE WITH BUILT-IN TWISTED JACKETED PAIR FOR LIGHTING CIRCUITS FOR LIGHTING CONTROLS. PROVIDE HEALTH CARE RATED MC FOR MEDICAL TREATMENT AREAS WHEN NOT IN CONDUIT.
- D. CONDUIT INSTALLED BELOW GRADE SHALL BE SCHEDULE 80 PVC HEAVY WALL PLASTIC CONDUIT MEETING NEMA STANDARDS & UL LISTED FOR UNDERGROUND & EXPOSED USE. PROVIDE GRS RADIUS BENDS & RISERS AS CONDUITS RISE ABOVE GRADE OR ABOVE FLOOR SLAB.
- E. PROVIDE INTERLOCKING SPACERS FOR MULT RUNS OF UG CONDUITS IN SAME TRENCH.
- F. LIGHTING & RECEPTACLE CIRCUIT CONDUCTORS SHALL BE COPPER THWN/THHN 600 VOLT, 75 DEG C, COLOR CODED AS DESCRIBED UNDER APPLICABLE CODES. NO ROMEX, PLASTIC FLEX TUBING ETC PERMITTED. LIGHT FIXTURE WIRE INSULATION SHALL HAVE TEMP RATING NOT LESS THAN INDIVIDUAL FIXTURE MANUF RECOMMENDED RATING.
- G. CIRCUITS W/ NO. 8 OR LARGER CONDUCTORS, MOTOR CIRCUITS, POWER & FEEDER CIRCUITS & BUILDING SERVICE FEEDERS SHALL BE COPPER THWN/THHN 600 VOLT, 75 DEG C.
- H. ALL CONDUIT, JUNCTION BOXES, ETC. ABOVE CEILINGS SHALL BE SUPPORTED FROM STRUCTURE. PIPE SLEEVES, HANGERS & SUPPORTS SHALL BE FURNISHED & SET & CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER & PERMANENT LOCATIONS.

SECTION 16200 - GROUNDING

- A. SUPPLEMENT GROUNDING NEUTRAL OF SECONDARY DISTRIBUTION SYSTEM W/ EQUIPMENT GROUNDING SYSTEM, INSTALLED SO THAT METALLIC STRUCTURES, ENCLOSURES, RACKWAYS, JUNCTION BOXES, OUTLET BOXES, CABINETS, MACHINE FRAMES, PORTABLE EQUIPMENT & OTHER CONDUCTIVE ITEMS OPERATE CONTINUOUSLY AT GROUND POTENTIAL & PROVIDE LOW IMPEDANCE PATH FOR GROUND FAULT CURRENTS.
- B. SYSTEM SHALL COMPLY W/ NATIONAL ELECTRICAL CODE, DRAWINGS & AS SPECIFIED.
- C. PROVIDE EQUIPMENT GROUND BUS IN BASE OF LOW VOLTAGE SWITCHGEAR BRAZED OR OTHERWISE ADEQUATELY CONNECTED BY AN APPROVED METHOD TO GROUND RODS.
- D. PROVIDE IN CONDUIT GREEN INSULATED COPPER GROUND CONDUCTOR TO MAIN METALLIC WATER SERVICE ENTRANCE & CONNECT BY MEANS OF ADEQUATE GROUND CLAMPS.
- E. EQUIPMENT GROUNDING CONDUCTORS FOR BRANCH CIRCUIT HOME RUNS SHOWN ON DRAWINGS SHALL INDICATE AN INDIVIDUAL & SEPARATE GROUND CONDUCTOR FOR THAT BRANCH CIRCUIT WHICH SHALL BE TERMINATED AT BRANCH CIRCUIT PANELBOARD, SWITCHBOARD, OR OTHER DISTRIBUTION EQUIPMENT.
- F. PROVIDE LOW VOLTAGE DISTRIBUTION SYSTEM W/ SEPARATE GREEN INSULATED EQUIPMENT GROUNDING CONDUCTOR FOR EACH SINGLE OR THREE-PHASE FEEDER.

SINGLE PHASE 120 VOLT BRANCH CIRCUITS FOR LIGHTING & POWER SHALL CONSIST OF 2 PHASE & NEUTRAL CONDUCTORS & GREEN GROUND CONDUCTOR INSTALLED IN CONDUIT WHICH SHALL SERVE AS GROUNDING CONDUCTOR.

G. GROUNDING CONDUCTORS SHALL BE AS SHOWN ON PLANS OR IF NOT SPECIFICALLY SHOWN SHALL BE NO SMALLER THAN THAT REQUIRED BY NEC.

SECTION 16300 - ELECTRICAL EQUIPMENT

- A. JUNCTION BOXES & OUTLET BOXES SHALL BE GALVANIZED KNOCKOUT TYPE. LIGHTING FIXTURE BOXES IN CEILINGS SHALL NOT BE LESS THAN 4" OCTAGONAL KNOCKOUT TYPE. OUTLETS SHALL BE INSTALLED IN LOCATIONS SHOWN ON DRAWINGS EXCEPT OUTLETS MAY BE MOVED 4 FEET IN EITHER DIRECTION IF SO DIRECTED, WITHOUT ADDITIONAL COST. BOXES SHALL BE FLUSH MOUNTED ON WALLS FOR CONCEALED WORK. GANGABLE BOXES SHALL BE USED IN ALL GYPSBOARD SURFACES.

PANELBOARDS

- A. BRANCH CIRCUIT 208/240V PANELS SHALL BE CAPACITY SHOWN W/ TIN PLATED COPPER BUSSING & BRACED FOR MINIMUM OF 22,000A AIC OR ANY OTHERS NOTED OR REQUIRED (SERIES RATED ACCEPTABLE). BOLT ON CIRCUIT BREAKERS. 480V PANELS SAME, EXCEPT 25,000A AIC MIN. MINIMUM 20" WIDE W/ GALV STEEL ENCLOSURE W/ HINGED DOOR & KEYS LOCK. COORD TRIM WITH MOUNTING LOCATION. PANELS TO BE RECESSED WHENEVER POSSIBLE.
- B. DISTRIBUTION PANELS SHALL BE CAPACITY SHOWN & SHALL BE SQUARE D I-LINE W/ TIN PLATED COPPER BUSSING. 65K AIC MIN OR AS OTHERWISE NOTED/REQ'D. BOLT ON CIRCUIT BREAKERS (SERIES RATED ACCEPTABLE). GALV STEEL ENCLOSURE.
- C. EQUIVALENT BY SQUARE D, SIEMENS, CUTLER HAMMER, OR GE.

SECTION 16350 - ELECTRICAL IDENTIFICATION

- A. MANUFACTURED LABELS FOR EACH PANELBOARD & TRANSFORMER. TYPEWRITTEN PANEL SCHEDULES MOUNTED IN PANELS
- B. PRINTED TAPE STYLE LABEL FOR EACH RECEPTACLE INDICATING PANEL & CIRCUIT #.
- C. MANUFACTURED LABELS FOR ALL DISCONNECT SWITCHES INDICATING EQUIPMENT SERVED.
- D. BRANCH CIRCUITS - IDENTIFY EACH CIRCUIT W/ WIRE MARKERS WHEN ENCLOSURE LABEL AND WIRE COLORS DO NOT PROVIDE ENOUGH INFORMATION TO IDENTIFY EACH CIRCUIT WITHOUT TRACING. FEEDERS & BRANCH CIRCUIT HOME RUNS W/ WIRE MARKER W/ PANEL & CKT #. BOX COVERS ABOVE LAY-IN CEILINGS NEATLY MARKED W/ INDELEBIL MARKER.

SECTION 16400 - WIRING DEVICES

- A. CONVENIENCE OUTLETS - SPEC GRADE 20 AMP DUPLEX W/ GROUND & SS WALL PLATES. OTHER OUTLETS SHALL BE VERIFIED W/ EQUIPMENT SUPPLIERS FOR PROPER NEMA CONFIGURATIONS. PROVIDE GFC RATED DEVICES WHERE INDICATED AND AS REQ'D PER CODE.
- B. PROVIDE GFC RATED DEVICES WHERE INDICATED AND ANYWHERE REQUIRED PER THE NEC.
- C. PROVIDE AFCI PROTECTION ON ALL CIRCUITS REQUIRED PER THE NEC.
- D. PROVIDE TAMPER RESISTANT RECEPTACLES ON ALL RECEPTACLES IN PUBLIC AREAS, AREAS ACCESSIBLE TO CHILDREN, AND WHERE OTHERWISE REQUIRED TO BE TAMPER RESISTANT PER THE NEC.
- E. LIGHT SWITCHES - SPEC GRADE 20 AMP TOGGLE SWITCHES W/ SS WALL PLATES.
- F. WALL MOTION SWITCHES - SPEC GRADE, PIR, OVERRIDE.
- G. CEILING MOTION SWITCHES - SPEC GRADE, LIDAL TECHNOLOGY, MODEL AS REQ'D BY ROOM CONFIGURATION, ALL NECESSARY POWER PACKS AND RELAYS.
- H. WALL MOTION SWITCHES (BATHROOM) - DUAL RELAY, SPEC GRADE, PIR, 2ND RELAY FOR OPERATION OF EXHAUST FAN DELAY.
- I. COLOR OF DEVICES AS DIRECTED BY ARCHITECT.
- J. EQUIVALENT DEVICES BY LEVITON, BRYANT, HUBBELL, WATTS/OPPER, LITHONIA, SENSOR SWITCH.

EXECUTION

- A. ALL OUTLETS, SHALL BE MOUNTED W/ BOTTOM AT 18" AFF & SWITCHES W/ BOTTOM AT 44" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE ON PLANS. REFER TO ARCH FOR OTHER REQUIRED ELEVATIONS AND CABINETRY COORDINATION.

SECTION 16500 - LED LUMINAIRES

- A. PROVIDE LIGHTING FIXTURES W/ ALL ACCESSORIES REQ'D FOR HANGING. COORD MOUNTING OF LIGHTING FIXTURES W/ ARCHITECT & E/C. ADDITIONAL FIXTURE SUPPORTS SHALL BE PROVIDED BY E/C. SUPPORTS SHALL COMPLY W/ LATEST EDITION OF NEC. PROVIDE LIGHTING FIXTURE SCHEDULING PLANS AS REQUIRED.
- B. REFER TO LIGHTING FIXTURE SCHEDULE PLANS FOR FIXTURE TYPES.
- C. EQUIVALENT LUMINAIRES BY CRE, COOPER, HUBBELL, INFINITY, LITHONIA, WILLIAMS, COLUMBIA, EXTRONICS, LITEALARM, EXIDE, MULE, DUALITE.

ABBREVIATIONS

|      |                               |      |                                  |                          |                         |
|------|-------------------------------|------|----------------------------------|--------------------------|-------------------------|
| A/E  | ARCHITECT / ENGINEER          | ENT  | ENTERING WATER TEMPERATURE       | PSI                      | POUNDS PER SQUARE INCH  |
| AFF  | ABOVE FINISHED FLOOR          | EX   | EXISTING ITEM                    | PVC                      | POLYVINYLCHLORIDE       |
| AFG  | ABOVE FINISHED GRADE          | FFA  | FROM FLOOR ABOVE                 | RA                       | RETURN AIR              |
| AG   | ABOVE GRADE                   | FFB  | FROM FLOOR BELOW                 | RE/REF REFER / REFERENCE |                         |
| AHJ  | AUTHORITY HAVING JURISDICTION | FFCO | FINISHED FLOOR CLEAN OUT         | RF                       | RELIEF FAN              |
| ARCH | ARCHITECT                     | FL   | FLOOR LINE                       | RL                       | RELOCATED ITEM          |
| BFP  | BACKFLOW PREVENTER            | FL   | FLOOR                            | RPZ                      | REDUCED PRESSURE ZONE   |
| BG   | BELOW GRADE                   | FPM  | FEET PER MINUTE                  | RR                       | RESTROOM                |
| BLDG | BUILDING                      | FWCO | FLUSH WALL CLEAN OUT             | SA                       | SUPPLY AIR              |
| BMS  | BUILDING MANAGEMENT SYSTEM    | G    | GROUND / GANG                    | SPD                      | SURGE PROTECTIVE DEVICE |
| C    | CONDUIT                       | G/C  | GENERAL CONTRACTOR               | TA                       | TRANSFER AIR            |
| CD   | CANDELA                       | GFCI | GROUND FAULT CIRCUIT INTERRUPTER | TFA                      | TO FLOOR ABOVE          |
| CD   | COLD DECK                     | GPM  | GALLONS PER MINUTE               | TFB                      | TO FLOOR BELOW          |
| CLG  | COOLING                       | HD   | HOT DECK                         | TP                       | TAMPERPROOF             |
| CM   | COORDINATE MOUNTING HEIGHT    | HTG  | HEATING                          | TYP                      | TYPICAL                 |
| CO   | CLEAN OUT                     | IG   | ISOLATED GROUND                  | UNO                      | UNLESS NOTED OTHERWISE  |
| CTE  | CONNECT TO EXISTING           | JB   | JUNCTION BOX                     | VTR                      | VENT THROUGH ROOF       |
| DCVA | DOUBLE CHECK VALVE ASSEMBLY   | LED  | LIGHT EMITTING DIODE             | WP                       | WEATHERPROOF            |
| DCW  | DOMESTIC COLD WATER           | LWT  | LEAVING WATER TEMPERATURE        |                          |                         |
| DDC  | DIRECT DIGITAL CONTROLS       | M/C  | MECHANICAL CONTRACTOR            |                          |                         |
| DF   | DRINKING FOUNTAIN             | MCB  | MAIN CIRCUIT BREAKER             |                          |                         |
| DHW  | DOMESTIC HOT WATER            | MCH  | MECHANICAL                       |                          |                         |
| DHWR | DOMESTIC HOT WATER RETURN     | MH   | MANHOLE                          |                          |                         |
| DM   | DIAMETER                      | MLD  | MAIN LUGS ONLY                   |                          |                         |
| DN   | DOWN                          | NFA  | NET FREE AREA                    |                          |                         |
| E/C  | ELECTRICAL CONTRACTOR         | OA   | OUTSIDE AIR                      |                          |                         |
| EA   | EXHAUST AIR                   | ORD  | OVERFLOW ROOF DRAIN              |                          |                         |
| ELEV | ELEVATION                     | P/C  | PLUMBING CONTRACTOR              |                          |                         |
| EM   | EMERGENCY FIXTURE/DEVICE      |      |                                  |                          |                         |

ELECTRICAL SYMBOL LEGEND

SOME SYMBOLS AND ABBREVIATIONS ON THIS LEGEND MAY NOT BE USED

|                        |   |                      |  |  |
|------------------------|---|----------------------|--|--|
| <b>CIRCUITING</b>      |   | <b>POWER DEVICES</b> |  | DUPLEX RECEPTACLE.                                     |
|                        | INDICATES 2 PHASE, 1 N, & 1 GND CONDUCTOR   |                      |  | LINE THRU DEVICE INDICATES ABOVE COUNTER               |
|                        | HOME RUN: INDICATES SHARED CIRCUIT  |                      |  | SPECIAL DUPLEX RECEPTACLE (GFI, ISOLATED GROUND, ETC.) |
|                        | HOME RUN: INDICATES #10 CONDUCTORS ENTIRELY   |                      |  | QUADPLEX RECEPTACLE                                    |
| <b>UTILITIES</b>       |   |                      |  | RECEPTACLE/DEVICE MOUNTED IN "TOMBSTONE"               |
| --- UGE ---            | UNDERGROUND ELECTRICAL  |                      |  | POKE-THRU WITH POWER                                   |
| --- OHE ---            | OVERHEAD ELECTRICAL   |                      |  | POKE-THRU WITH TELECOMMUNICATIONS                      |
| --- TELE ---           | TELECOMMUNICATIONS CONDUIT  |                      |  | POKE-THRU W/POWER AND TELECOM                          |
| --- UGT ---            | UNDERGROUND TELECOMMUNICATIONS CONDUIT  |                      |  | SINGLE GANG FLOOR BOX (2, 3, 4 GANG SIMILAR)           |
| <b>LIGHTING</b>        |   |                      |  | CEILING MOUNTED RECEPTACLE                             |
|                        | SURFACE/RECESSED LIGHT FIXTURE  |                      |  | RECEPTACLE/DEVICE MOUNTED IN "TOMBSTONE"               |
|                        | WALL-MOUNTED LIGHT FIXTURE  |                      |  | POKE-THRU WITH POWER                                   |
|                        | POLE-MOUNTED LIGHT FIXTURE  |                      |  | POKE-THRU WITH TELECOMMUNICATIONS                      |
|                        | TIMECLOCK - REFER TO PLANS / DETAILS  |                      |  | POKE-THRU W/POWER AND TELECOM                          |
| <b>EQUIPMENT</b>       |   |                      |  | SINGLE GANG FLOOR BOX (2, 3, 4 GANG SIMILAR)           |
|                        | DISCONNECT SWITCH. RE: PLANS FOR INFORMATION.   |                      |  | CEILING MOUNTED RECEPTACLE                             |
|                        | MAGNETIC MOTOR STARTER  |                      |  | RECEPTACLE/DEVICE MOUNTED IN "TOMBSTONE"               |
|                        | COMBINATION DISCONNECT SWITCH / MOTOR STARTER   |                      |  | POKE-THRU WITH POWER                                   |
|                        | TOGGLE-TYPE DISCONNECT. FURNISH WITH THERMAL MOTOR PROTECTION WHERE SERVING FANS/PUMPS. |                      |  | POKE-THRU WITH TELECOMMUNICATIONS                      |
|                        | SURFACE PANELBOARD  |                      |  | POKE-THRU W/POWER AND TELECOM                          |
|                        | RECESSED PANELBOARD   |                      |  | SINGLE GANG FLOOR BOX (2, 3, 4 GANG SIMILAR)           |
|                        | DISTRIBUTION PANELBOARD   |                      |  | CEILING MOUNTED RECEPTACLE                             |
|                        | SWITCHBOARD. FEEDER/MAIN CIRCUIT BREAKER SECTION AND DISTRIBUTION SECTION.              |                      |  | RECEPTACLE/DEVICE MOUNTED IN "TOMBSTONE"               |
| <b>GENERAL SYMBOLS</b> |   |                      |  | POKE-THRU WITH POWER                                   |
|                        | INDICATES CONNECT TO EXISTING   |                      |  | POKE-THRU WITH TELECOMMUNICATIONS                      |
|                        | INDICATES ELEVATION   |                      |  | POKE-THRU W/POWER AND TELECOM                          |

MECHANICAL AND PLUMBING SYMBOL LEGEND

SOME SYMBOLS AND ABBREVIATIONS ON THIS LEGEND MAY NOT BE USED

## SHEET METAL

HIGH EFFICIENCY ROUND DUCT TAKEOFF  
(WITH & WITHOUT MANUAL DAMPER)

SPIN-IN ROUND DUCT TAKEOFF  
(WITH & WITHOUT MANUAL DAMPER)

CONICAL BELLMOUTH ROUND TAKEOFF

ROUND DUCT RUNOUT WITH FLEX DUCT

DUCTWORK ELBOW (WITH & WITHOUT TURNING VANES)

RETURN GRILLE OR EXHAUST REGISTER

SUPPLY AIR FLOW INDICATOR

RETURN AND EXHAUST AIR FLOW INDICATOR

THERMOSTAT

TEMPERATURE SENSOR

HUMIDISTAT

CONTROL WIRING

## GENERAL SYMBOLS

INDICATES CONNECT TO EXISTING

INDICATES ELEVATION

## PLUMBING FIXTURES/EQUIPMENT

HOSE BIBB

WALL HYDRANT

CLEAN OUT

REDUCED PRESSURE BACKFLOW PREVENTER

DOUBLE CHECK BACKFLOW PREVENTER

PLUMBING FIXTURE AND CALLOUT

FD: FLOOR DRAIN, AD: AREA DRAIN,  
FS: FLOOR SINK

RD: ROOF DRAIN

ORD: OVERFLOW ROOF DRAIN

## MECHANICAL PIPING

— RL —

REFRIGERANT LIQUID

— RS —

REFRIGERANT SUCTION

— D —

DRAIN (CONDENSATE)

— CA —

COMPRESSED AIR

— RV —

REFRIGERANT VENT

— RD —

RUPTURE DISK

## PLUMBING PIPING

— · —

DOMESTIC COLD WATER

— ··· —

DOMESTIC HOT WATER

— ····· —

RECIRCULATING DOMESTIC HOT WATER

— SAN —

WASTE ABOVE GRADE OR FLOOR

— SAN —

WASTE BELOW GRADE OR FLOOR

— ST —

STORM ABOVE GRADE OR FLOOR

— ST —

STORM BELOW GRADE OR FLOOR

— ST/O —

STORM OVERFLOW ABOVE GRADE OR FLOOR

— ST/O —

STORM OVERFLOW BELOW GRADE OR FLOOR

— V —

PLUMBING VENT

— W —

WATER SERVICE

— G —

GAS (NATURAL)

## PIPING SYMBOLS

SHUTOFF VALVE

SHUTOFF VALVE IN RISER

BALANCING VALVE

PLUG VALVE

AUTO FLOW CONTROL VALVE

PIPING ELBOW UP

PIPING ELBOW DOWN

PIPING TEE

PIPING ELBOW

PIPING TEE UP

PIPING TEE DOWN

INCREASE / REDUCER

UNION

CAP

PIPE FLEX

STRAINER

CHECK VALVE

INLINE STRAINER

TEST PLUG

## PIPING SPECIALTIES

PRESSURE REDUCING VALVE









**schwerdt design group**  
architecture|interiors|planning  
2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579  
500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



Bryan Leinwetter - Engineer  
MO# PE-2020020297


**CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5**  
LEES SUMMIT, MISSOURI

SUBMISSION DATES  
MAY 23, 2023  
JUNE 12, 2023-REV 1

SHEET TITLE  
SITE MEP PLAN

PROJECT NUMBER  
**230117**

SHEET NUMBER  
**ME-202**







2231 sw wanamaker rd  
topeka, kansas 66614-4275 suite 303  
phone: 785.273.7540  
fax: 785.273.7579

500 north broadway  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



Bryan Leinweitter - Engineer  
MO# PE-2020020297

CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5  
LEES SUMMIT, MISSOURI

SUBMISSION DATES  
MAY 23, 2023  
JUNE 12, 2023-REV 1

SHEET TITLE  
PLUMBING FLOOR  
PLAN

PROJECT NUMBER  
230117

SHEET NUMBER  
M-101




2949 SW WANAMAKER DR., TOPEKA, KANSAS 66614  
785.273.2447  
WWW.PKMRENG.COM

### FLOOR DRAIN SCHEDULE

| PLAN MARK | MANUFACTURER | MODEL NUMBER | SERVICE     | TOPIGRATE SIZE | WASTE SIZE | REMARKS |
|-----------|--------------|--------------|-------------|----------------|------------|---------|
| FD-1      | WADE         | 1100         | FLOOR DRAIN | 6"Ø            | 3"         | 1       |

REMARKS:  
1. PROVIDE WITH NICKEL BRONZE TOP AND TRAP SEAL.




### FLUSH GRADE CLEANOUT DETAIL

NOT TO SCALE


#### NOTES:

1. BACKFLOW PREVENTER MANUFACTURER AND INSTALLATION SHALL BE AS APPROVED BY LOCAL AND STATE AUTHORITIES AND IN ACCORDANCE TO LISTING OF DEVICE.
2. ALL PIPING TO BE RIGIDLY SUPPORTED AND INSTALLED IN SUCH A MANNER AS TO BE DRAINABLE.



### WATER SERVICE REDUCED PRESSURE BACKFLOW PREVENTER DETAIL

NOT TO SCALE



### GAS SERVICE DETAIL

NOT TO SCALE

### WATER HEATER SCHEDULE

| PLAN MARK      | MANUFACTURER   | MODEL NUMBER | GALLONS       | CAPACITY | ELECTRICAL       | NOTES |
|----------------|----------------|--------------|---------------|----------|------------------|-------|
| WATER HEATER-1 | STIEBEL ELTRON | DHC 3-1      | INSTANTANEOUS | 3.0 KW   | 120V, 1PH, 30AMP |       |


### PIPING MATERIAL & INSULATION SCHEDULE

| PIPING SYSTEM                  | SIZE        | TYPE/SCHED | MATERIAL        | ACCEPTABLE FITTINGS       | FIELD TEST PRESSURE/TIME | ALLOWABLE IN PLENUMS | INSULATION        |           |
|--------------------------------|-------------|------------|-----------------|---------------------------|--------------------------|----------------------|-------------------|-----------|
|                                |             |            |                 |                           |                          |                      | TYPE              | THICKNESS |
| DOMESTIC COLD WATER            | 1/2"-2-1/2" | L          | COPPER          | SOLDER, PRO-PRESS         | 130 PSI - 1/2HR          | YES                  | FIBERGLASS W/ ASJ | 1/2"      |
| DOMESTIC HOT WATER & HW RETURN | 1/2"-2-1/2" | L          | COPPER          | SOLDER, PRO-PRESS         | 130 PSI - 1/2HR          | YES                  | FIBERGLASS W/ ASJ | 1"        |
| NATURAL GAS - ABOVE GRADE      | 2-1/2" & Up | SCH. 40    | STEEL- SEAMED   | WELDED                    | 75 PSI - 1HR             | YES                  | ----              | ----      |
| NATURAL GAS - ABOVE GRADE      | 1/2"-2"     | SCH. 40    | STEEL- SEAMLESS | THREADED IRON             | 75 PSI - 1HR             | YES                  | ----              | ----      |
| SOIL & WASTE BELOW GRADE       | 2"-8"       | SCH. 40    | PVC             | SOLVENT JOINED            | 10 FT - 1/2HR            | NO                   | ----              | ----      |
| DOM. WATER SERVICE BELOW GRADE | 4"-8"       | AWWA C151  | DUCTILE IRON    | AWWA C111, MECH JOINTS    | 130 PSI - 1/2HR          | YES                  | ----              | ----      |
| DOM. WATER SERVICE BELOW GRADE | 1"-3"       | K          | COPPER          | CONTINUOUS TUBING, BRAZED | 130 PSI - 1/2HR          | YES                  | ----              | ----      |
| DOM. WATER SERVICE BELOW GRADE | 1"-3"       | DR 9       | HDPE            | CONTINUOUS TUBING, FUSED  | 130 PSI - 1/2HR          | NO                   | ----              | ----      |

- NOTES
1. ALL PIPING AND MATERIALS IN PLENUMS MUST MEET ASTM E84 FLAME/SMOKE RATING OF 25/50.
  2. ALL INSULATION THICKNESSES SHALL MEET ASHRAE 90.1 - 2007 REQUIREMENTS AT A MINIMUM.
  3. REFER TO SPECIFICATIONS FOR MORE DETAILED INFORMATION.


### PLUMBING FIXTURE SCHEDULE

| PLAN MARK | FIXTURE MODEL              | FIXTURE DESCRIPTION  | FITTINGS MODEL             | FITTINGS DESCRIPTION  | PIPE SIZES |      |      |      |
|-----------|----------------------------|--|----------------------------|---|------------|------|------|------|
|           |                            |  |                            |   | WASTE      | VENT | DCW  | DHW  |
| P-1       | TOTO DRAKE CST744SL        | ADA COMPLIANT WATER CLOSET: FLUSH TANK, WHITE ELONGATED BOWL, 1.6 GALLON SIPHON JET FLUSHING SYSTEM, 2-1/8" TRAP DIAMETER, WITH POLISHED CHROME FLUSH HANDLE MOUNTED ON WIDE SIDE OF RESTROOM STALL, WITH HANDLE STOP VALVE AND METAL FLEXIBLE WATER RISER | TOTO SC534                 | SEAT: WHITE, SOLID PLASTIC, OPEN FRONT, ELONGATED   | 4"         | 2"   | 1/2" | ---  |
| P-2       | AMERICAN STANDARD 0355.012 | LAVATORY: WHITE WALL HUNG LAVATORY 20"x18" WITH 4" BACK FAUCET HOLES ON 4" CENTERS, WITH CONCEALED ARM CARRIER. PROVIDE HANDLE STOP VALVES AND FLEXIBLE METAL WATER RISERS.  | AMERICAN STANDARD 2175.504 | FAUCET: 4" CENTERSET, CHROME FINISH WITH 4" METAL LEVER HANDLE, 1/2" CONNECTIONS, 1.5 GPM MAX FLOWRATE. CHROME PLATED BRASS GRID DRAIN, TAILPIECE, AND P-TRAP. INSULATE THE TAILPIECE, P-TRAP, AND WATER RISERS | 2"         | 2"   | 1/2" | 1/2" |



### ROOF SUPPORT FOR GAS LINE

NOT TO SCALE



### TYPICAL GAS CONNECTION

NOT TO SCALE



### FLOOR PLAN - PLUMBING

SCALE: 1/8" = 1'-0"





**schwerdt design group**  
architecture|interiors|planning

2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579

500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



Bryan Leinwetter - Engineer  
MO# PE-2020020297



**CORE & SHELL BUILDING**  
**STREETS OF WEST PRYOR LOT 5**  
LEES SUMMIT, MISSOURI

SUBMISSION DATES  
MAY 23, 2023  
JUNE 12, 2023-REV 1

SHEET TITLE  
HVAC FLOOR PLAN

PROJECT NUMBER  
**230117**

SHEET NUMBER  
**M-201**



**FLOOR PLAN - HVAC**  
SCALE: 1/8" = 1'-0"

#### ROOF TOP UNIT SCHEDULE - THREE PHASE ELECTRIC WITH GAS HEAT

| PLAN MARK | MANUFACTURER | MODEL NUMBER | SIZE  | REFRIGERANT | MINIMUM EFFICIENCY | AIRFLOW | COMPRESSORS | COOLING CAPACITY | CFM   | EXTERNAL STATIC | OA CFM | HEATING CAPACITY | ELECTRICAL          | WEIGHT   | FILTER  | NOTES   |
|-----------|--------------|--------------|-------|-------------|--------------------|---------|-------------|------------------|-------|-----------------|--------|------------------|---------------------|----------|---------|---------|
| RTU-1     | TRANE        | YSC 048 E3   | 4 TON | R-410A      | 14 SEER            | DOWN    | (1) SCROLL  | 49,000 BTUH      | 1,600 | 0.7"            | 160    | 80 MBH           | 208 V, 3 PH, 35 AMP | 800 LBS  | MERV 13 | 1,2,3,4 |
| RTU-2     | TRANE        | YSC 048 E3   | 4 TON | R-410A      | 14 SEER            | DOWN    | (1) SCROLL  | 49,000 BTUH      | 1,600 | 0.7"            | 160    | 80 MBH           | 208 V, 3 PH, 35 AMP | 800 LBS  | MERV 13 | 1,2,3,4 |
| RTU-3     | TRANE        | YSC 048 E3   | 4 TON | R-410A      | 14 SEER            | DOWN    | (1) SCROLL  | 49,000 BTUH      | 1,600 | 0.7"            | 160    | 80 MBH           | 208 V, 3 PH, 35 AMP | 800 LBS  | MERV 13 | 1,2,3,4 |
| RTU-4     | TRANE        | YSC 060 E3   | 5 TON | R-410A      | 14 SEER            | DOWN    | (1) SCROLL  | 60,100 BTUH      | 2,000 | 1.0"            | 200    | 80 MBH           | 208 V, 3 PH, 40 AMP | 800 LBS  | MERV 13 | 1,2,3,4 |
| RTU-5     | TRANE        | YSC 072 E3   | 6 TON | R-410A      | 14.6 IEER          | DOWN    | (1) SCROLL  | 75,000 BTUH      | 2,400 | 1.1"            | 240    | 120 MBH          | 208 V, 3 PH, 50 AMP | 1000 LBS | MERV 13 | 1,2,3,4 |

#### NOTES LEGEND

1. PROVIDE ROOF CURB, DISCONNECT SWITCH, HAIL GUARDS, AND ECONOMIZER
2. PROVIDE WALL MOUNTED 7-DAY PROGRAMMABLE THERMOSTAT
3. PROVIDE INTERNAL VIBRATION ISOLATION FOR THE RTU FAN AND COMPRESSORS

#### EXHAUST FAN SCHEDULE

| PLAN MARK | MANUFACTURER | MODEL NUMBER | MOUNTING | SERVICE | CFM | STATIC PRESSURE | ELECTRICAL              | DRIVE  | DISCONNECT | DAMPER    | NOTES |
|-----------|--------------|--------------|----------|---------|-----|-----------------|-------------------------|--------|------------|-----------|-------|
| EF-1      | GREENHECK    | SP-B90       | CEILING  | EXHAUST | 75  | 1/4"            | 50 WATTS, 120V, 1 PHASE | DIRECT | YES        | BACKDRAFT | 1     |

#### NOTES:

1. PROVIDE 12" ROOF CURB WITH CURB CAP MODEL RCC-7 WITH INTEGRAL BIRDSCREEN.



PEARSON KENT MCKINLEY RAAF ENGINEERS LLC  
2949 SW WANAMAKER DR. TOPEKA, KANSAS 66614  
785.273.2447 WWW.PKMRENG.COM

23.05









**schwerdt design group**

architecture|interiors|planning

2231 sw wanamaker rd suite 303  
topeka, kansas 66614-4275  
phone: 785.273.7540  
fax: 785.273.7579

500 north broadway suite 200  
oklahoma city, ok 73102  
phone: 405.231.3105  
fax: 405.231.3115



Bryan Leinwetter - Engineer  
MO# PE-2020020297



**CORE & SHELL BUILDING  
STREETS OF WEST PRYOR LOT 5  
LEES SUMMIT, MISSOURI**

SUBMISSION DATES  
MAY 23, 2023  
JUNE 12, 2023-REV 1

SHEET TITLE  
LIGHTING FLOOR PLAN

PROJECT NUMBER  
**230117**

SHEET NUMBER  
**E-201**



**FLOOR PLAN - LIGHTING**

SCALE: 1/8" = 1'-0"



PEARSON KENT MCKINLEY RAAF ENGINEERS LLC  
2949 SW WANAMAKER DR., TOPEKA, KANSAS 66614  
785.273.2447  
WWW.PKMRENG.COM

231205