


REMOTE LOT CHARGING STATIONS NOTES

- 1 NEW 277/480V 3Ø PAD MOUNT TRANSFORMER. CONCRETE PAD PER EVERGY'S SPECIFICATIONS. TRANSFORMER PROVIDED BY EVERGY.
- 2 600 AMP 277/480V 3Ø CT METERING CABINET NEMA 3R AND CT METER PER EVERGY'S STANDARDS.
- 3 600 AMP 277/480V 3Ø 4-WIRE 65K AIG PANEL BOARD NEMA 3R WITH BREAKERS. (2) 400 AMP 3-POLE BREAKERS (EUSE), (1) 300 AMP 3-POLE BREAKER (225 KVA TRANSFORMER)
- GALVANIZED METAL UNISTRUT RACK FOR MOUNTING SERVICE EQUIPMENT. PER EVERGY'S STANDARDS.
- 240KW STANDALONE EV CHARGING STATION. MOUNTED ON CONCRETE PAD. LEVEL 3.

600A 277/480V MAIN BRKR REMOTE LOT RISER DIAGRAM NOTES CT 3Ø 4 WIRE EV CAB NEMA 3R 240 KW DESCRIPTION NEW 277/ 480 VOLT 3Ø PAD MOUNT TRANSFORMER PROVIDED BY EVERGY 600 AMP 277/480V 3Ø CT METERING CABINET NEMA 3R & CT METER PER EVERGY'S STANDARDS 65K AIC L3 600 AMP 277/480V 3Ø 4-WIRE 65K AIG SWITCH BOARD WITH 600 AMP MAIN BREAKER NEMA 3R WITH GFCI. DISTRIBUTION SECTION NEMA 3R FURNISH WITH BREAKERS 8' X 5/8" GROUND ROD (1) 400 AMP 3-POLE BREAKERS (EUSE) 240KW DCFC STANDALONE EV CHARGING STATION MOUNT ON CONCRETE PAD 600 AMP SERVICE FEEDERS (2) SETS OF (4) 500 MCM ALUMINUM IN 3" CONDUIT 400 AMP 480 VOLT FEEDERS (2) SETS OF (4) 4/0 AWG (CU), (1) #3 AWG (CU) IN 2 1/2" CONDUIT CT METER GROUNDING ELECTRODE 2' 5'0" CROUND ROD WITH 2/0 AWG (CU) 8' 5/8" GROUND ROD WITH 2/0 AWG (CU) SERVICE GROUND ELECTRODES (2) 8' X 5/8" GROUND RODS WITH 3/0 AWG (CU) 6' APART 8' X 5/8" **GROUND ROD GROUND ROD**





Date

TEAGUE

ELECTRIC

12425 W 92ND STREET LENEXA, KS 66215 PHONE: (913) 529-4600 FAX: (913) 529-4611

4/6/2023


1" = 40'

THIS PRINT IS THE PROPERTY OF TEAGUE ELECTRIC CONSTRUCTION, INC., PREPARED FOR AND SUBMITTED TO: BOB SIGHT FORD.

THIS MAY NOT BE REPRODUCED OR DISTRIBUTED TO ANY 3RD PARTY WITHOUT THE CONSENT OF TEAGUE ELECTRIC CONSTRUCTION, INC.

1





SITE PLAN CHARGING STATIONS NOTES

- NEW 750KVA 277/480V 3Ø PAD MOUNT TRANSFORMER. CONCRETE PAD PER EVERGY'S SPECIFICATIONS. TRANSFORMER PROVIDED BY EVERGY.
- 1200 AMP 277/480V 3Ø CT METERING CABINET NEMA 3R AND CT METER PER EVERGY'S STANDARDS.
- 1200 AMP 277/480V 3Ø 4-WIRE 65K AIG PANEL BOARD NEMA 3R WITH BREAKERS.
 (2) 400 AMP 3-POLE BREAKERS (EUSE), (1) 300 AMP 3-POLE BREAKER (225 KVA TRANSFORMER)
- 225 KVA TRANSFORMER 480 VOLT 3Ø TO 120/208 VOLT 3Ø. NEMA 3R WITH RAIN SHEILD.
- 600 AMP 120/208V 3Ø 4- WIRE PANEL BOARD NEMA 3R WITH 600AMP MAIN BREAKER. FURNISH (5) 100 AMP 2-POLE BREAKERS (EUSE).
- 19.2KW SINGLE PHASE 208V STANDALONE EV CHARGING STATION. MOUNTED ON CONCRETE PAD. LEVEL 2.
- FUTURE 240KW DCFC STANDALAONE EV CHARGING STATION. LEVEL 3.


RISER DIAGRAM NOTES

8' X 5/8"

8' X 5/8"

GROUND ROD

	RISER DIAGRAM NOTES
	DESCRIPTION
1	NEW 750 KVA 480 VOLT 3Ø PAD MOUNT TRANSFORMER PROVIDED BY EVERGY
2	1200 AMP 277/480V 3Ø CT METERING CABINET NEMA 3R & CT METER PER EVERGY'S STANDARDS
3	1200 AMP 277/480V 3Ø 4-WIRE 65K AIG SWITCH BOARD WITH 1200 AMP MAIN BREAKER NEMA 3R WITH GFCI. DISTRIBUTION SECTION NEMA 3R FURNISH WITH BREAKERS (2) 400 AMP 3-POLE BREAKERS (EUSE) (1) 300A 3-POLE BREAKER (225 KVA TRANSFORMER)
4	225KVA TRANSFORMER 480 VOLT 3Ø -120/208V 3Ø NEMA 3R WITH RAIN SHEILD
(5)	600A 120/208V 3Ø 4-WIRE PANEL BOARD, NEMA 3R WITH 600AMP MAIN BREAKER AND FURNISHED BREAKERS (5) 125 AMP 2-POLE BREAKERS FURNISHED (EUSE)
6	19.2 KW SINGLE PHASE 208 VOLT EV CHARGING STATION LEVEL 2
7	1200 AMP SERVICE FEEDERS (4) SETS OF (4) 500MCM ALUMINUM IN 3" CONDUIT
8	300 AMP 480V FEEDER (2) SETS OF (3) 2/0 AWG (CU), (1) #3 AWG (CU) IN 2" CONDUIT.
9	600 AMP 480V FEEDER (2) SETS OF (4) 350 MCM AWG (CU), (1) #1 (CU) IN 3" CONDUIT.
10	CT-METER GROUNDING ELECTRODE 8' X 5/8" GROUND ROD WITH #6 AWG (CU)
(11)	SERVICE GROUND ELECTRODE 8' X 5/8" GROUND ROD WITH 3/0 AWG (CU)
(12)	100AMP 208 VOLT SINGLE PHASE FEEDER (1) SET OF (3) 1/0 AWG (CU), (1) #6 AWG (CU) IN 1 1/2" CONDUIT
(13)	TRANSFORMER GROUNDING ELECTRODE 8' X 5/8" GROUND ROD WITH #2 AWG (CU)



THIS PRINT IS THE PROPERTY OF TEAGUE ELECTRIC CONSTRUCTION, INC., PREPARED FOR AND SUBMITTED TO: BOB SIGHT FORD. THIS MAY NOT BE REPRODUCED OR DISTRIBUTED TO ANY 3RD PARTY WITHOUT THE CONSENT OF TEAGUE ELECTRIC CONSTRUCTION, INC.



RELEASED FOR CONSTRUCTION
As Noted on Plans Review velopment Services Departme Lee's Summit, Missouri 06/22/2023

TEAGUE ELECTRIC

12425 W 92ND STREET LENEXA, KS 66215 PHONE: (913) 529-4600 FAX: (913) 529-4611

Revision/Issue

Date

D1769BS 4/6/2023 1" = 40'

