

CS	COVER SHEET
<u>CIVIL</u>	
1.	COVER SHEET
2.	DEMOLITION PLAN
3.	SITE DIMENSION PLAN
4A.	GRADING PLAN
4B.	STORM SEWER LINE 1, 2 AND 3 – PLAN AND PROFILE
5.	EROSION CONTROL PLAN
6.	PRELIMINARY DEVELOPMENT DRAINAGE AREA MAP
7.	POST DEVELOPMENT DRAINAGE AREA MAP
8.	UTILITY PLAN
9.	LANDSCAPE PLAN
10.	SITE DETAIL SHEET
11.	SITE DETAIL SHEET
12.	SITE DETAIL SHEET
13.	SITE DETAIL SHEET

A1	FLOOR PLANS
A2	EXTERIOR ELEVATIONS AND DETAILS
A3	ROOF PLAN AND DETAILS
A4	BUILDING SECTIONS
A5	BUILDING SECTIONS
A6	BUILDING DETAILS
A7	SPECIFICATIONS
A8	SPECIFICATIONS

\$100	GENERAL NOTES
\$110	TABLES
\$120	SCHEDULES
\$130	LOAD DIAGRAMS
\$200	FOUNDATION PLAN
\$202	SHEAR WALL PLAN
\$210	FRAMING PLAN
\$500	TYPICAL FOUNDATION DETAILS
\$501	FOUNDATION DETAILS
\$510	TYPICAL STEEL DETAILS
\$511	MOMENT FRAME ELEVATION AND DETAILS
\$520	TYPICAL WOOD DETAILS
\$521	TYPICAL WOOD DETAILS
\$522	FRAMING DETAILS
\$523	FRAMING DETAILS
\$530	TYPICAL SHEAR DETAILS

MP1	MECHANICAL AND PLUMBING SPECIFICATIONS, SYMBOLS, SCHEDULES AND DETAILS.
M1	MECHANICAL PLAN
P1	PLUMBING PLAN
E1	ELECTRICAL SPECIFICATIONS AND SYMBOLS
E2	ELECTRICAL LIGHTING PLAN
E3	ELECTRICAL POWER PLAN
E4	ELECTRICAL SITE LIGHTING AND DETAILS
E5	ELECTRICAL SCHEDULES AND SINGLE LINE DIAGRAM



LOT 1B, LEES SUMMIT, MISSOURI 64086



**PROJECT LOCATION**

Map showing the project location in Lees Summit, Missouri. The location is marked with a black star at the intersection of NE Douglas St and NE Chipman Rd. The map includes major roads such as NW Colbern Rd, NE Colbern Rd, NE Chipman Rd, NE Orchard St, NE Douglas St, NE 4th St, NE 3rd St, NE 2nd St, NE 1st St, NE 5th St, NE 6th St, NE 7th St, NE 8th St, NE 9th St, NE 10th St, NE 11th St, NE 12th St, NE 13th St, NE 14th St, NE 15th St, NE 16th St, NE 17th St, NE 18th St, NE 19th St, NE 20th St, NE 21st St, NE 22nd St, NE 23rd St, NE 24th St, NE 25th St, NE 26th St, NE 27th St, NE 28th St, NE 29th St, NE 30th St, NE 31st St, NE 32nd St, NE 33rd St, NE 34th St, NE 35th St, NE 36th St, NE 37th St, NE 38th St, NE 39th St, NE 40th St, NE 41st St, NE 42nd St, NE 43rd St, NE 44th St, NE 45th St, NE 46th St, NE 47th St, NE 48th St, NE 49th St, NE 50th St, NE 51st St, NE 52nd St, NE 53rd St, NE 54th St, NE 55th St, NE 56th St, NE 57th St, NE 58th St, NE 59th St, NE 60th St, NE 61st St, NE 62nd St, NE 63rd St, NE 64th St, NE 65th St, NE 66th St, NE 67th St, NE 68th St, NE 69th St, NE 70th St, NE 71st St, NE 72nd St, NE 73rd St, NE 74th St, NE 75th St, NE 76th St, NE 77th St, NE 78th St, NE 79th St, NE 80th St, NE 81st St, NE 82nd St, NE 83rd St, NE 84th St, NE 85th St, NE 86th St, NE 87th St, NE 88th St, NE 89th St, NE 90th St, NE 91st St, NE 92nd St, NE 93rd St, NE 94th St, NE 95th St, NE 96th St, NE 97th St, NE 98th St, NE 99th St, NE 100th St. A purple line highlights a route starting from the northwest, passing through the project location, and heading southeast. A north arrow is in the bottom left corner.

- 1) **Project Information:**
  - 1.A) Name: Douglas Corner
  - 1.B) Legal Description: Lot 1B, Lees Summit, Missouri 64086
- 2) **Building Information:**
  - 2.A) Gross Floor Area: 7,820 sqft
  - 2.B) Number of stories: 1 story
  - 2.C) Height: 24'-0"

- 3) **Codes:** (As amended by the City of Lees Summit, Missouri)
  - 3.A) 2018 International Building Code
  - 3.B) 2018 International Plumbing Code
  - 3.C) 2018 International Mechanical Code
  - 3.D) 2018 International Fuel Gas Code
  - 3.E) 2018 International Residential Code
  - 3.F) 2018 International Fire Code
  - 3.G) 2017 National Electrical Code
  - 3.H) ICC/ANSI A117.1-2009, Accessible and Usable Buildings and Facilities
- 4) **Use / Occupancy Classification:** (Chapter 3)
  - 4.A) Restaurant / A-3 Assembly
  - 4.B) Office / B – Business
  - 4.C) Retail / M – Mercantile
- 5) **Nonseparated Occupancies** [508.3]:
  - 5.A) Allowable building area, height and number of stories [508.3.2]: They shall be based on the most restrictive allowances for the occupancy groups under consideration. A-3 Assembly Group is the most restrictive
  - 5.B) Separation [508.3.3]: No separation is required between nonseparated occupancies
- 6) **Fire Protection Systems:** (Chapter 9)
  - 6.A) An automatic sprinkler system will be provided throughout in accordance with NFPA 13.
  - 6.B) Sprinkler system supervision and alarms [903.4]: All valves controlling the water supply for automatic sprinkler systems, pumps, tanks, water levels and temperatures, critical air pressures and water flow switches on all sprinkler systems shall be electrically supervised by a listed fire alarm control unit.
  - 6.C) A manual fire alarm system that activates the occupant notification system in accordance with Section 907.5 shall be installed in Group A occupancies where the occupant load due to the assembly occupancy is 300 or more, or where the Group A occupant load is more than 100 persons above or below the lowest level of exit discharge. Group A occupancies not separated from one another in accordance with Section 707.3 shall be considered as a single occupancy for the purposes of applying this section. It is not anticipated that tenant finish projects will exceed these conditions. A manual fire alarm system will not be provided.
  - 6.D) Group B [907.2.2]: A manual fire alarm system is required when: 1. The combined Group B occupant load of all floors is 500 or more persons. 2. The group M occupant load is more than 100 persons above or below the lowest level of exit discharge, or 3. The fire area contains an ambulatory care facility. It is not anticipated that tenant finish projects will exceed these conditions. A manual fire alarm system will not be provided.
  - 6.E) Group M [907.2.7]: A manual fire alarm system is required when: 1. The combined Group M occupant load of all floors is 500 or more persons, and 2. The group M occupant load is more than 100 persons above or below the lowest level of exit discharge. It is not anticipated that tenant finish projects will exceed these conditions. A manual fire alarm system will not be provided.
- 7) **Type of Construction:** (Chapter 6)
  - 7.A) Type VB
- 8) **Allowable Building Heights and Areas:** (IBC Chapter 5)
  - 8.A) Allowable Building Height in feet above grade Plane (Table 504.3): A, S = 60ft
  - 8.B) Allowable Number of Stories Above Grade Plane (Table 504.4): A-3, S = 2 stories
  - 8.C) Allowable Area Factor (Table 504.2): A-3, S1 = 24,000 sqft
- 9) **Fire-Resistance Rating Requirements for Building Elements:** (Table 601)
  - 9.A) Structural Frame: 0 hours
  - 9.B) Bearing Walls Exterior: 0 hours but not less than per Table 602
  - 9.C) Bearing Walls Interior: 0 hours
  - 9.D) Nonbearing Walls and Partitions Exterior: per Table 602
  - 9.E) Nonbearing Walls and Partitions Interior: 0 hours
  - 9.F) Floor Construction and associated secondary members: 0 hours
  - 9.G) Roof Construction and associated secondary members: 0 hours
- 10) **Fire-Resistance Rating Requirements for Exterior Walls Based on Fire Separation Distance (FSD):** (Table 602)
  - 10.A) FSD = 0' and greater for group A = 0 hour
- 11) **Exterior Wall Openings:** Maximum Area of Exterior Wall Openings Based on Fire Separation Distance (FSD) and Degree of Opening Protection (Table 705.8): FSD = 20' and greater = No limit
- 12) **Means of Egress:** (IBC Chapter 10)
  - 12.A) Occupant load (Table 1004.1.2): To be analyzed under each separate tenant finish package.  
Assumed occupant load for shell based on occupancy group M - Mercantile =  
 $7,820 \text{ sqft} / 30 = 260.67 = 261$  occupants
- 13) **Plumbing Requirements:** (Table 290.2.1)
  - 13.A) To be analyzed under each separate tenant finish package.

DOUGLAS  
| CORNER |

LOT 1B, LEE330MILL, MISSOURI 64080

instrument of service by the architect, or under his supervision and is intended for use on this project only. Pursuant to the provisions of the Copyright Protection Act of 1909, all drawings, specifications, ideas of design, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the designer/architect. Any reproduction, use, or disclosure of the material contained herein without the written consent of the architect is strictly prohibited.

© COPYRIGHT 2023 GUY  
GRONBERG ARCHITECTS, P.C.


[illegible]

CS









DEMOLITION PROPOSED FEATURES	
---	LIMITS OF DEMOLITION
XXXX	ALL TREES, STRUCTURES, AND UTILITIES WITHIN THE HATCHED AREAS ARE TO BE REMOVED. ANYTHING LOCATED OUTSIDE THE HATCHED AREAS ARE TO REMAIN UNLESS OTHERWISE SPECIFIED.
XXXX	FULL DEPTH PAVEMENT REMOVAL

DEMO NOTES	
XXX	Items listed by the following symbols are shown on this sheet.
DMO	EXISTING TO BE REMOVED
ERM	EXISTING TO REMAIN
REL	EXISTING TO BE RELOCATED

DEMOLITION GENERAL NOTES:	
CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVAL OF THE EXISTING STRUCTURES, RELATED UTILITIES, PAVING, UNDERGROUND STORAGE TANKS AND ANY OTHER EXISTING IMPROVEMENTS AS NOTED. SEE THE OWNER'S/DEVELOPER'S SITE WORK SPECIFICATIONS. CONTRACTOR IS TO REMOVE AND DISPOSE OF ALL DEBRIS, RUBBISH AND OTHER MATERIALS RESULTING FROM PREVIOUS AND CURRENT DEMOLITION OPERATIONS. DISPOSAL WILL BE IN ACCORDANCE WITH ALL LOCAL, STATE AND/OR FEDERAL REGULATIONS GOVERNING SUCH OPERATIONS.	
THE GENERAL CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO AVOID PROPERTY DAMAGE TO ADJACENT PROPERTIES DURING THE CONSTRUCTION PHASES OF THIS PROJECT. THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR ANY DAMAGES TO THE ADJACENT PROPERTIES OCCURRING DURING THE CONSTRUCTION PHASES OF THIS PROJECT.	
THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS, WHETHER SHOWN OR NOT SHOWN AT NO ADDITIONAL COST TO THE OWNER.	
CONTRACTOR SHALL INSPECT AND TEST AS NECESSARY FOR ASBESTOS MATERIALS. REMOVAL OF ASBESTOS MATERIAL WILL MEET ALL LOCAL GOVERNING REQUIREMENTS.	

DEMOLITION PLAN	
DOUGLAS CORNER BUILDING	
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI	
X-REF NO. 181018	
DRAWING NO. 23-033FDP	
DATE MAY 10, 2023	
JOB NO. 23-033	
2	13




CONSULT inc engineers planners	
1533 Locust Street, Kansas City, Missouri 64108	
CORPORATE LICENSE NO. E20100572 (NO.) / E-1738 (KS.) / LS 2019005467	
August 15, 2023	
R. KEVIN STERRETT, NO E-26440	

STATE OF MISSOURI	
RICHARD KEVIN STERRETT	
JULY 2024	
REGISTERED PROFESSIONAL ENGINEER	

NO. BY DATE	
1	BY DATE
2	BY DATE
3	BY DATE
4	BY DATE
5	BY DATE
6	BY DATE
7	BY DATE
8	BY DATE
9	BY DATE
10	BY DATE
11	BY DATE
12	BY DATE
13	BY DATE
14	BY DATE
15	BY DATE
16	BY DATE
17	BY DATE
18	BY DATE
19	BY DATE
20	BY DATE
21	BY DATE
22	BY DATE
23	BY DATE
24	BY DATE
25	BY DATE
26	BY DATE
27	BY DATE
28	BY DATE
29	BY DATE
30	BY DATE
31	BY DATE
32	BY DATE
33	BY DATE
34	BY DATE
35	BY DATE
36	BY DATE
37	BY DATE
38	BY DATE
39	BY DATE
40	BY DATE
41	BY DATE
42	BY DATE
43	BY DATE
44	BY DATE
45	BY DATE
46	BY DATE
47	BY DATE
48	BY DATE
49	BY DATE
50	BY DATE
51	BY DATE
52	BY DATE
53	BY DATE
54	BY DATE
55	BY DATE
56	BY DATE
57	BY DATE
58	BY DATE
59	BY DATE
60	BY DATE
61	BY DATE
62	BY DATE
63	BY DATE
64	BY DATE
65	BY DATE
66	BY DATE
67	BY DATE
68	BY DATE
69	BY DATE
70	BY DATE
71	BY DATE
72	BY DATE
73	BY DATE
74	BY DATE
75	BY DATE
76	BY DATE
77	BY DATE
78	BY DATE
79	BY DATE
80	BY DATE
81	BY DATE
82	BY DATE
83	BY DATE
84	BY DATE
85	BY DATE
86	BY DATE
87	BY DATE
88	BY DATE
89	BY DATE
90	BY DATE
91	BY DATE
92	BY DATE
93	BY DATE
94	BY DATE
95	BY DATE
96	BY DATE
97	BY DATE
98	BY DATE
99	BY DATE
100	BY DATE

IF THIS IS NOT A BLUE INK SEAL AND THE SIGNATURE IN BLUE INK, THE PLAN IS A COPY AND MAY CONTAIN UNAUTHORIZED ALTERATIONS. THE CERTIFICATION CONTAINED ON THIS DOCUMENT SHALL NOT APPLY TO ANY COPIES.





DETAIL OF ADA PARKING STALLS  
1"=10'



- NOTES:**
1. All construction and materials to conform to the city and the specifications and details per the Kansas City Metro Chapter APWA. It is advisable that the contractor become familiar with this document in the event that there is a discrepancy between this and the approved plan and the Manual. Advise the design engineer of any discrepancy prior to bidding or working on this project.
  2. Silt fence shall be installed at the perimeter of all disturbed areas within the site during construction for erosion control.
  3. Contractor shall contact the Development Engineering Inspections 48 hours prior to commencement of work at (816) 969-1800.
  4. Contractor to locate and relocate any existing utilities that may conflict with construction as necessary.
  5. All curb shall be CC-1 or integral with the sidewalk.
  6. A handicap parking sign, 5' above finish grade, shall be placed at the head of the designated parking space.
  7. There shall be two way traffic movement.
  8. Perimeter parking area dimensions shown are to the back of curb.
  9. All mechanical equipment shall be screened to 100% opacity and match building material (See Architectural Submittal). (Height of screen shall equal the height of mechanical equipment that is being screened).
  10. See architectural submittal for all building dimensions, monument signs and lighting details.
  11. This lot is not in a flood plane per FIRM Panel 417 of 625, Map No. 2809500417G, dated Jan. 20, 2017.
  12. ADA accessible ramp to have detectable surface on public handicap ramps only. Detectable surfaces do not need to be installed on the ramps at commercial drives. See KCAPWA web site for details.
  13. Building coordinates are pointed to or measured at the outside face of building foundation corners. Contractor shall confirm building dimensions with structural drawings.
  14. Other coordinates are pointed to or measured from the back of curb, back of wall or property corner location.
  15. Contractor shall coordinate building entrances, egresses, walkways and door locations with architectural and structural drawings.
  16. See architectural/structural/mechanical/electrical drawings for miscellaneous site equipment and pads.
  17. Curb to be installed at proposed drives by saw cutting a clean straight edge of existing asphalt and forming curb to edge of gutter existing elevation.

**SITE INFORMATION:**  
Property Description: Lot 1C, Douglas Corners  
Site Address: 150 NE Tudor Road  
Zoning: CP-2 Planned Community Commercial  
Lot Area: 75,508 SF (1.73 AC)  
Building Area (GFA): 7,792 SF Retail  
FAR: .10 to 1  
Impervious Coverage: 34,710 SF, 46%  
Parking Space Required:  
Retail: 5 space/1000 SF = 39 spaces  
Parking Spaces Provided: 44 spaces  
ADA Spaces Required/Provided: 2/2  
Standard Space Size: 9'x19',  
Planned Use: Retail Shops  
Anticipated Completion: Spring / Summer 2024  
Watershed - West Tributary to Prairie Lee Lake (East Fork of Little Blue River)

**TOTAL PARKING FOR DOUGLAS CORNERS:**

Square Footage	Use	Parking required
3258 SF	Retail	5 sp/1000 SF=27
4785 SF	Service	5 sp/1000 SF=24
1533 SF	Retail	5 sp/1000 SF=7
1256 SF	Retail	5 sp/1000 SF=10
1998 SF	Office	4 sp/1000 SF=8
1932 SF	Office	4 sp/1000 SF=9
3800 SF	Office	4 sp/1000 SF=14
2027 SF	Office	
3489 SF	Office	
REQUIRED:		126 Parking spaces
PROVIDED:		142 Parking spaces
TOTAL PROVIDED:		188 Parking spaces

- Legend:**
- Heavy Duty PCC Pavement
  - 6" Concrete Pavement over 4" McDOT Type 5 compacted aggregate base course
  - Sidewalk
- All level landings to have a minimum of 18" of level pavement beyond the pull/latch side of all ADA doorways designated with "LEVEL LANDING"



CONSULT INC

engineers planners

1533 Locust Street, Kansas City, Missouri 64108

CORPORATE LICENSE NO. E20100573 (MO.) / E-1736 (KS.) / LS 201905467

STATE OF MISSOURI

RICHARD KEVIN STERRETT

REGISTERED PROFESSIONAL ENGINEER

August 15, 2023

REVISION

DATE

NO.

BY

DATE

X-REF NO.

181098

DRAWING NO.

23-033FDP

DATE

MAY 10, 2023

JOB NO.

23-033

3


SHEET OF 13

SITE DIMENSION PLAN


DOUGLAS CORNER BUILDING

LEE'S SUMMIT - JACKSON COUNTY - MISSOURI





Know what's below.  
Call before you dig.



GRADING AND DRAINAGE NOTES:

Information pertaining to under ground utilities was obtained from available records and field locations when possible, but the contractor must determine the exact location and elevation of all existing utilities by digging test pits by hand at all utility crossings in advance of machine trenching. If clearances are less than specified on these plans or 24", which ever is less, contact the Engineer and the Owner/ Developer prior to proceeding with construction. All structures located within Right Of Way or otherwise noted on the these plans shall be constructed per City standards. If structure(s) are not prototypical or construction cannot be achieved contractor shall submit shop drawing to HG Consult, for review and approval. Contractor shall be responsible for relocation or removal of existing underground utilities shown or not shown at no additional cost to the owner. Contractor shall coordinate with utility companies on adjusting existing utility line as required by cut and fill at no additional cost to the owner. Contractor shall be held responsible for the design and implementation of sheeting, shoring, bracing and special excavation measures required to meet OSHA, Federal, State and Local regulations pursuant to the installation of the work indicated on these drawings. All disturbed areas and slopes shall be graded smooth and (4") of top soil applied. The area shall be seeded and watered until hardy grass growth has been established. Storm drain pipe bedding shall be installed per APWA, section 2102. See Erosion Control Plan for rip rap pad sizes. Elevations are called out to top of curb, top of pavement, or top of structure, unless otherwise noted. Parking lot grading shall be performed to route storm water as directed to the storm collection system. All curb shall be CG-1. Clear and grub areas to be filled, remove trees, vegetation, roots, or other debris, and other materials that would affect the stability of the fill. Ensure that fill material is free of brush, rubbish, rocks, logs, stumps, building debris, and other materials inappropriate for constructing stable fill. Do not incorporate frozen material or soft, muck, or highly compressible materials into fill slopes. Permanently stabilize all graded areas after final grading is completed on each area of the grading plan, apply temporary stabilization measures on all graded areas when work is to be interrupted or delayed (see Erosion Control Plan(s)). Contractor shall match top of proposed drainage structures with proposed grades. If a discrepancy occurs between proposed grades and proposed structure tops, the grading shall govern. If the discrepancy is more than 4 inches the contractor shall contact the Engineer of Record. All utilities, including storm sewer, shown within public easements or right of ways shall be constructed to the governing agency's specifications. All other utilities shall be constructed to the client's or the governing agency's specifications, whichever is more stringent, if there is a question as to which specifications should apply the contractor shall contact the Engineer of Record. All existing structures, unless otherwise noted to remain, all fencing, trees, & etc., within construction area shall be removed & disposed of off site, unless otherwise noted. any burning on site shall be subject to local ordinances and/or the owner/developers standards and specifications. All drainage structures shall be pre-cast. All drainage structures and storm sewer pipes shall meet heavy duty traffic (H20) loading and be installed accordingly. Contractor shall notify all utility companies having underground utilities on site or in right-of-way prior to excavation. Contractor shall contact utility locating company (STATE ONE CALL system) and locate all utilities prior to grading start. Site grading shall not proceed until Erosion Control measures have been installed. After permits have been obtained and Erosion Control measures installed, the contractor shall grade building pad & aprons to 0" to - 1/2" of subgrade.

TC Top of Curb  
FG Finish Grade  
G Gutter Elevation  
HP High Point  
LP Low Point  
FFE Finish Floor Elevation

KEY

PROPOSED

Tip out curb and gutter  
1' Finish Grade Contours  
5' Finish Grade Contours  
Finish Grade slope

EXISTING

Contractor to verify all invert elevations for existing sewer connections. Contact civil engineer if conflict arises.

PROJECT BENCHMARK:

#1 Iron bar at north west corner of property.  
N 1006947.3760  
E 2823375.6230  
TOP ELEV. 1021.42

#2 Top of curb at corner of parking lot in Schlotsky's parking.  
N 1006628.2690  
E 2823585.0320  
TOP ELEV. 1019.80

GRADING PLAN

DOUGLAS CORNER BUILDING  
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI



August 15, 2023

hgconsult  
Inc  
engineers  
planners  
1533 Locust Street, Kansas City, Missouri 64108  
CORPORATE LICENSE NO. E201000573 (NO.) / E-1736 (KS.) / LS 2019005467


X-REF NO.  
181008  
DRAWING NO.  
23-033PDP  
DATE  
MAY 10, 2023  
JOB NO.  
23-033

4A SHEET OF 13









The Contractor shall inspect, repair and add stone to the stone construction entrance when it becomes saturated with mud to insure it functions as it was intended.

When necessary, the Contractor shall install a temporary sand trap and sump pump to collect and remove all erosion and sediment control devices shall be inspected, cleaned regularly in accordance with the Storm Water Pollution Prevention Plan.

Temporary sediment control measures (silt fence, construction entrance, etc.) shall be maintained until all contributing areas are graded and stabilized.

Dust control on site shall be minimized by spraying water on dry areas of the site. The use of oils and other petroleum based or toxic liquids for dust suppression is strictly prohibited.

When necessary, the Contractor shall establish a network of temporary erosion control measures which wash areas of construction traffic exit points and vehicle operation shall be inspected and trapped before wash water is allowed to be discharged offsite. Rise-off will be required at all exits from the site.

Riprap eroded areas immediately, reseed as necessary to maintain good vegetative cover, mow vegetative cover to maintain a maximum height of six inches, and remove trash.

The Contractor shall install and maintain all erosion control measures and devices as required by the permit and the approved construction methods and devices as required by the permit.

Inspect and repair the collection system (i.e. catch basins, pipes, swales, rip rap, etc.) after significant rainfall to maintain proper functioning.

All existing structures, fences, trees, etc., within the construction area shall be removed or relocated off site in accordance with local ordinances. Any burning on site shall be subject to local ordinances.

All wash water (concrete truck, vehicle cleaning, equipment cleaning, etc.) shall be contained until it is a permanent contact between these materials and storm water that is discharged from the site.

All materials spilled, dropped, washed, or tracked from vehicles onto roadways or into storm drains shall be removed immediately.

When necessary, the Contractor shall install erosion control devices/fences and dispose of per local codes once the site has been stabilized. Contractor shall report to the grading plan for final grades.

And distribute activities shall not commence until approval to do so has been received by governing authorities.

No land clearing or grading shall begin until all erosion control measures have been installed.

All exposed areas shall be seeded as specified within 14 days of final grading.

Should construction stop for longer than 14 days, the site shall be seeded as specified.

After every significant runoff producing rainfall event of 1/2" or greater or at least once a week.

A. Impact the detention basin system for sediment accumulation, erosion, trash accumulation, vegetated cover, and general condition.

B. Check and clear the storm drainage system (pipes, swales, etc.) after every significant rainfall event.

This plan shall not be considered all inclusive as the governing Contractor shall take all necessary precautions to prevent soil sediment from leaving the site.

Additional Contractor and/or local government (City of Lincoln) rules that apply.

Additional erosion and sediment control measures will be installed if deemed necessary by an site inspection.

If necessary, the storm drainage system should be interrupted by overhead or nightfall, the pipe ends shall be covered with fabric.

General Contractor shall be responsible to take whatever means necessary to establish permanent soil stabilization.

Additional erosion and sediment control methods and devices may be required as directed by the City or MOJNR.

[illegible]

August 15, 2023

**g** Consult  
Inc engineers  
planners  
1523 Locust Street Kansas City, Missouri 64108

CORPORATE LICENSE No. E201000573 (MO.) / E-1736 (KS.) / LS 2019005467

## EROSION CONTROL PLAN

DOUGLAS CORNER BUILDING  
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI

X-REF NO.

DRAWING NO.  
3-033PDP

DATE  
MAY 10, 2023

JOB NO.  
23-033

5

SHEET OF 13

### MAJOR CONSTRUCTION ACTIVITIES:

1. Pull all necessary city permits.
2. Construct temporary construction entrance at location shown on this sheet.
3. Install perimeter silt fences in the locations shown on this sheet.
4. Locate and disconnect all existing utilities.
5. Begin clearing and grubbing operations. Clearing and grubbing shall be done only in areas where the earthwork will be performed and only in areas where building is planned to commence within 14 days after clearing and grubbing.
6. Commence site grading.
7. Disturbed areas of the site where construction activity has ceased for more than 14 days shall be temporarily seeded and watered.
8. Relocate existing utilities.
9. Install remaining areas of temporary measures and structures.
10. Prepare temporary parking and storage area.
11. Grade remainder of site.
12. Start construction of building pad and structures.
13. Install utilities, storm sewers, curbs and gutters.
14. Finalize pavement sub grade preparation.
15. Install base material as required for pavement.
16. Pave site.
17. Remove inlet protection around inlets and manholes no more than 48 hours prior to placing stabilized base course.
18. Remove temporary construction exits only prior to pavement construction in these areas (these areas are to be paved last).
19. Disturbed areas of the site where construction activity has ceased for more than 14 days shall be temporarily seeded and watered.
20. Carry out final grading, seeding and planting. Fine grade and install permanent seeding areas.
21. Submit notice of termination for permit termination.
22. Remove all temporary erosion and sediment control devices (only if site is stabilized and notice of termination has been filed).

PROPOSED



KEY

*Proposed Silt Fence (ESC-03)*

Inlet (ESC-06) and outlet protection (ESC-14)

*Tip out curb and gutter*

1' Finish Grade Contours

' *Finish Grade Contours*

**Temporary Construction Entrance (ESC-01)**

*D50 Rip Rap*

EXISTING

Contractor to verify all invert elevations for existing sewer connections. Contact civil engineer if conflict arises.

## PROJECT BENCHMARK:


- #1 Iron bar at north west corner of property.  
N 1006947.3760  
E 2823375.6230  
TOP ELEV. 1021.42
- #2 Top of curb at corner of parking lot in Schlotsky's parking.  
N: 1006628.2690  
E: 2823585.0320  
TOP ELEV. 1019.80



Contractor to verify all invert elevations for existing sewer connections. Contact civil engineer if conflict arises.

[illegible]





- STORM SEWER NOTES:**
- All construction shall be in accordance with the latest edition of the City of Lee's Summit "DESIGN AND CONSTRUCTION MANUAL".
  - All pipe to be HDPE with smooth interior with a minimum "n" value of 0.011
  - Contractor shall verify the exact location and depth of all existing utilities prior to construction.
  - Elevations are called out to top of curb, top of pavement, or top of structure, unless otherwise noted.
  - See Storm Water Report for pipe sizing.
  - Parking lot grading shall be performed to route storm water as directed to the storm collection system.

**Detention Pond Details:**

Elevation (feet)	Surf.Area (sq-ft)	Cum.Store (cubic-feet)
1014.10	52	0
1015	5,623	2,553
1016	10,269	10,499
1017	17,998	24,633
1018	20,048	43,657

Detention release was sized by Bentley PondPACK V8i and is sized to release the 100-year storm event over the proposed rip rap lined channel.

\*Areas shown are impervious areas to drainage structures.


Contractor to verify all invert elevations for existing sewer connections. Contact civil engineer if conflict arises.

**PROJECT BENCHMARK:**

- #1** Iron bar at north west corner of property.  
N: 1006947.3760  
E: 2823375.6230  
TOP ELEV. 1021.42
- #2** Top of curb at corner of parking lot in Schlotsky's parking.  
N: 1006628.2690  
E: 2823585.0320  
TOP ELEV. 1019.80



Know what's below.  
Call before you dig.



PROPOSED	KEY	EXISTING
—979—	Grades	—960—
➔	100 Year Overflow	
- - - - -	Drainage Area	

Contractor to verify all invert elevations for existing sewer connections. Contact civil engineer if conflict arises.

STATE OF MISSOURI  
REGISTERED PROFESSIONAL ENGINEER  
RICHARD KEVIN STERRETT  
No. 0000000000  
EXPIRATION DATE 12/31/2024

August 15, 2023


**Consult Inc**  
engineers planners  
1533 Locust Street, Kansas City, Missouri 64108  
CORPORATE LICENSE NO. E20100573 (MO.) / E-1736 (KS.) / LS 201905467

POST DEVELOPMENT  
DRAINAGE AREA MAP


DOUGLAS CORNER BUILDING  
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI

X-REF NO.  
181098  
DRAWING NO.  
23-033PDP  
DATE  
MAY 10, 2023  
JOB NO.  
23-033  
SHEET  
OF 13










Interior Landscape

Area	SF
A	195 SF
B	138 SF
C	356 SF
D	183 SF
E	121 SF
F	427 SF
TOTAL	1392 SF



NOTES:

- Open areas not covered with other landscaping materials shall be covered with sod.
- All trees/shrubs are shown graphically, not numerically.
- A 3 foot tall berm may be substituted for screening shrubs.
- Trees shall be located a minimum distance of 5 feet from the sanitary and water lines as measured from the outside of the mature tree trunk to the outside of the pipe.
- The trees and shrubs shown are for graphical purposes and does not represent the actual count required per the worksheet.
- Evergreen shrubs used to screen mechanical equipment shall be equal height as the mechanical units at the time of planting.
- Detention pond and slopes into pond to use TBM with seed and all other disturbed ground to be sodded.

Worksheet for Tree and Shrub Requirements:

A - Size of development site	= 75,508 SF
B - Length of street frontage of development site	= 0 LF
C - Trees required on street frontage = 1/30 LF	= 0 Trees
D - Trees provided	= 0 Trees
E - Parking lot area	= 14,178 SF
F - Green space required in parking lot (E x 5%)	= 709 SF
G - Green space provided	= 1,392 SF
H - Shrubs required along frontage = 1/20 LF	= 0 Shrubs
Shrubs required along frontage (Parking lot screen) 270 LF at 12/40 LF	= 81 Shrubs
I - Shrubs Provided	= 81 Shrubs
Shrubs Provided (Parking lot screen)	= 81 Shrubs
Shrubs Provided (Total frontage)	= 0 Shrubs
J - Quantity of additional trees required	= 13 Trees
1 tree per 5000 SF of open area (63,040/5,000)	= 15 Trees
K - Additional Trees Provided	= 25 Shrubs
L - Quantity of additional shrubs required	= 25 Shrubs
2 shrubs per 5000 SF of open area (63,040/5,000)	= 25 Shrubs
M - Additional Shrubs Provided	= 25 Shrubs

LANDSCAPE SCHEDULE:

SPECIES	CALIPER/HEIGHT	QUANTITY
"October Glory" Maple	3" caliper measured 6" from the ground	12
Acer Rubrum		
Eastern White Pine (or equal) 8' (at time of planting)		1
Pinus Strobus		
Evergreen Shrub (or equal)	24" Minimum height at time of planting	76

LANDSCAPE PLAN

DOUGLAS CORNER BUILDING  
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI



August 15, 2023



DATE

REVISION

NO.

BY

CK/APP

IF THIS IS NOT A BLUE INK SEAL AND THE SIGNATURE IN BLUE INK, THE PLAN IS A COPY AND MAY CONTAIN UNAUTHORIZED ALTERATIONS. THE CERTIFICATION CONTAINED ON THIS DOCUMENT SHALL NOT APPLY TO ANY COPIES.

R. KEVIN STERRETT, MO E-26440

X-REF NO.

DRAWING NO.

DATE

JOB NO.

SHEET OF

9

13







REQUIRED CONCRETE BEARING AREA (SQUARE FEET - SF)									
NOM. DIA. (INCHES)	TEE, PLUG	BEND	BEND	BEND	BEND	11.25			
6	4.7	6.7	4.0	4.0	4.0	4.0			
8	8.4	11.8	6.4	4.0	4.0	4.0			
10	13.1	18.5	10.0	5.1	4.0	4.0			
12	18.8	26.2	14.4	7.4	4.0	4.0			
14	25.7	36.3	19.6	10.0	5.0	5.0			
16	33.5	47.4	25.6	13.1	6.6	6.6			
18	42.4	REST. JT.	32.5	16.5	8.3	8.3			
20	REST. JT.	REST. JT.	40.1	20.4	10.3	10.3			
24	REST. JT.	REST. JT.	REST. JT.	29.4	14.8	14.8			

NOTES:  
1. ALL BENDS WITHOUT RESTRAINED JOINTS SHALL HAVE CONCRETE THRUST BLOCKS INSTALLED FOR RESTRAINT.  
2. MEGA LUGS MAY BE USED ONLY IN CONJUNCTION WITH CONCRETE THRUST BLOCKING.  
3. BEARING AREA MUST BE AGAINST UNDISTURBED SOIL.  
4. DO NOT COVER JOINTS OR BOLTS (WHERE APPLICABLE) WITH CONCRETE.

REQUIRED CONCRETE VOLUME (CUBIC FEET - CF)									
NOM. DIA. (INCHES)	TEE, PLUG	BEND	BEND	BEND	BEND	11.25			
6	50.5	71.4	38.6	19.7	9.9	9.9			
8	89.8	126.9	68.7	35.0	17.6	17.6			
10	140.2	198.3	107.3	54.7	27.5	27.5			
12	202.0	REST. JT.	154.6	78.8	39.6	39.6			
14	REST. JT.	REST. JT.	210.4	107.3	53.9	53.9			
16	REST. JT.	REST. JT.	REST. JT.	140.1	70.4	70.4			
18	REST. JT.	REST. JT.	REST. JT.	177.3	89.1	89.1			
20	REST. JT.	REST. JT.	REST. JT.	REST. JT.	110.0	110.0			
24	REST. JT.	REST. JT.	REST. JT.	REST. JT.	158.4	158.4			

NOTES:  
1. ALL BENDS WITHOUT RESTRAINED JOINTS SHALL HAVE CONCRETE THRUST BLOCKS INSTALLED FOR RESTRAINT.  
2. MEGA LUGS MAY BE USED ONLY IN CONJUNCTION WITH CONCRETE THRUST BLOCKING.  
3. BEARING MUST BE AGAINST UNDISTURBED SOIL.  
4. DO NOT COVER JOINTS OR BOLTS (WHERE APPLICABLE) WITH CONCRETE.

SIDEWALK/SHARED-USE PATH DETAIL									
GEN-2									

GENERAL NOTES:  
1. SUBGRADE MUST BE OF STABLE, COMPACTED EARTH AND SHALL BE OVERLAYED WITH 4" COMPACTED DENSE GRADED AGGREGATE BASE.  
2. 1.5% CROSS SLOPE MUST BE MAINTAINED THROUGH DRIVEWAYS.  
3. KCMRB 4K CONCRETE MIX SHALL BE REQUIRED FOR ALL SIDEWALKS AND SHARED-USE PATHS OR AS APPROVED BY THE CITY INSPECTOR.  
4. ALL SIDEWALKS SHALL MEET CURRENT PUBLIC RIGHT OF WAY ACCESSIBILITY GUIDELINES (PROWAG).  
5. AN EXPANSION JOINT SHALL BE PLACED AT A MAXIMUM OF 150 FT. CONSTRUCTION JOINTS SHALL BE PLACED THE SAME WIDTH OF SIDEWALK, BUT NO GREATER THAN 10 FT.  
6. SHARED-USE PATH WIDTH SHALL BE 10 FT. WIDE.  
7. SIDEWALK FINISHING (NO PICTURE FRAMING) AS DIRECTED BY CITY INSPECTOR.  
8. WHITE CURING COMPOUND MUST BE APPLIED UNIFORMLY TO THE CONCRETE SURFACE IMMEDIATELY AFTER FINAL FINISHING.

SERVICE CONNECTION/METER WELL									
LEE'S SUMMIT MISSOURI									

NOTES:  
1. METER INSTALLATION SHALL NOT BE LOCATED IN AREAS SUBJECT TO VEHICULAR TRAFFIC OR IN CONCRETE PAVEMENT WITHOUT CITY APPROVAL.  
2. IF METER IS TO BE LOCATED OTHER THAN IN FRONT OF PROPERTY LINE, CITY APPROVAL SHALL BE OBTAINED.  
3. CITY TO FURNISH ITEMS A-K.  
4. NO OTHER EQUIPMENT SHALL BE INSTALLED IN THIS PIT.  
5. 42" MINIMUM BURY DEPTH FOR ALL SERVICE LINES.  
6. EXCAVATION FOR TAP TO EXPOSE 4 LINEAR FEET OF MAIN.  
7. NO SPLICES ALLOWED BETWEEN METER AND MAIN.  
8. SERVICE CONNECTION TAP AT APPROXIMATELY 45 DEGREES.  
9. LID AND RISER RING SHALL BE SET SO THAT GROUND WATER WILL DRAIN AWAY FROM THE WELL.  
10. CONTACT WATER UTILITIES, 816-969-1900, FOR REQUIREMENTS OF A METER LARGER THAN 2"

HORIZONTAL THRUST BLOCKS									
LEE'S SUMMIT MISSOURI									

VERTICAL THRUST BLOCKS									
LEE'S SUMMIT MISSOURI									

SIDEWALK/SHARED-USE PATH DETAIL									
GEN-2									

SERVICE CONNECTION/METER WELL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									

AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STEEL FRAME INLET									
LEE'S SUMMIT MISSOURI									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

SILT FENCE									
AMERICAN PUBLIC WORKS ASSOCIATION									





AMERICAN PUBLIC WORKS ASSOCIATION									
KANSAS CITY METRO CHAPTER									
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016									

SITE DETAIL SHEET									
DOUGLAS CORNER BUILDING									
LEE'S SUMMIT - JACKSON COUNTY - MISSOURI									

STANDARD DETAILS									
CITY OF LEE'S SUMMIT, MO									

CURB INLET DETAIL									
LEE'S SUMMIT MISSOURI									





**CONSULT INC**  
engineers planners

**18**

**1533 Locust Street, Kansas City, Missouri 64108**  
CORPORATE LICENSE NO. E201000573 (MO.) / E-1736 (KS.) / LS 2019050467

**STATE OF MISSOURI**  
**REGISTERED PROFESSIONAL ENGINEER**  
**Richard W. Sterrett, P.E.**  
No. 18109B

**NO. BY**  
**REVISION**  
**DATE**



**SITE DETAIL SHEET**

**DOUGLAS CORNER BUILDING**  
**LEE'S SUMMIT - JACKSON COUNTY - MISSOURI**

**12** **13**  
SHEET OF


**X-REF NO.**  
18109B  
**DRAWING NO.**  
23-033PDP  
**DATE**  
MAY 10, 2023  
**JOB NO.**  
23-033  
**12** **13**  
SHEET OF









13 SHEET OF 13






A1





## 8 TRASH ENCLOSURE ELEVATIONS

STG-1	CEMENTITIOUS STUCCO SYSTEM (COLOR = OFF WHITE)
STG-2	CEMENTITIOUS STUCCO SYSTEM WITH PROJECTED FOAM SHAPE (COLOR = OFF WHITE)
CJ	STUCCO CONTROL JOINT.
MTL-1	BREAK METAL FLASHINGS, SCUPPER HEADS AND DOWNSPOUTS (COLOR = DARK BRONZE)
MTL-2	FLUSH CONCEALED FASTENER METAL WALL PANEL - PAK-GLD 12"X 1" D/F FLUSH PANELS (COLOR = DARK BRONZE)
MTL-3	ARCHITECTURAL METAL PANEL - ELEVATE (FORMERLY FIRESTONE) DELTA CFF-12 (50%), CFF-12B(25%), AND CFF-12T(25%) INSTALLED IN A RANDOM MANNER TO PROVIDED VAREGATED SPACING. (COLOR = SLATE GRAY)
AVN-1	BREAK METAL FACED CANOPY PER DETAIL 13/A6 (COLOR = DARK BRONZE)
GLZ-1	ALUMINUM STOREFRONT AND ENTRY SYSTEM (COLOR = BLACK ANODIZED) WITH DOUBLE PANE INSULATED GLASS (COLOR = GRAY TINT)
GLZ-2	WOOD CASEMENT WINDOW WITH EXTERIOR ALUMINUM CLADDING AND 1" GRILLS. (COLOR = BLACK) WITH DOUBLE PANE INSULATED GLASS (COLOR = GRAY TINT)
HMD-1	HOLLOW METAL DOOR AND FRAME. PAINT (COLOR = DARK BRONZE TO MATCH MTL-1)
IND-1	COMPOSITE WOOD PANEL SYSTEM. NINETEENTH-CENTURY EUROPEAN STYLE SIDING UH53 BELGIAN BOARD (COLOR = PERUVIAN TEAK)
SGN-1	WALL SIGN. TO BE SUBMITTED UNDER SEPARATE SIGN PERMIT



DOUGLAS

LOT 1B, LEE3 SUMMIT, MISSOURI 64080

under this service by the architect, or  
under this supervision and is intended for  
use on this project only. Pursuant to  
Architectural Records Copyright Protection Act  
of 1990, all drawings, specifications, ideas  
and designs, including the overall form,  
arrangement and composition of spaces and  
elements appearing herein, constitute  
the original, copyrighted work of the  
Designer/Architect. Any reproduction, use,  
or disclosure of information contained herein  
without prior written consent of the Architect  
is strictly prohibited.

**© COPYRIGHT 2023 GUY  
GRONBERG ARCHITECTS P.C.**

REV#	DATE	DESCRIPTION
01	6-12-23	CITY COMMENTS
02	6-26-23	TRASH ENCLOSURE

DATE: 08-11-2023

PROJECT# 23012

## A2















- 1) 4" CONCRETE SLAB ON VAPOR BARRIER ON 4" GRANULAR LEVELING COURSE - REFER STRUCT. DRAWINGS
- 2) CONCRETE TRENCH FOOTING - REFER STRUCT. DRAWINGS
- 3) 2" RIGID PERIMETER INSULATION
- 4) PRE-ENGINEERED WOOD ROOF TRUSSES AT 24' O.C. TOP CHORD TO SLOPE AT 1/2" PER FOOT. - REFER TO STRUCT. DRAWINGS
- 5) INSTALL 6 1/2" FSK BATT INSULATION BETWEEN JOISTS.
- 6) 2X6 LOAD BEARING WALL - REFER TO STRUCT. DRAWINGS. PROVIDE BATT INSULATION PER SPECIFICATIONS.
- 7) NOT USED
- 8) SINGLE PLY ROOF MEMBRANE PER SPECIFICATION OVER 3/4" DENS DECK BOARD OVER TWO LAYERS OF 2 1/2" RIGID INSULATION WITH JOINTS STAGGERED OVER PLYWOOD ROOF DECKING PER STRUCTURAL DRAWINGS
- 9) SINGLE PLY ROOF MEMBRANE PER SPECIFICATION OVER TAPERED CRICKETS OVER PLYWOOD ROOF DECKING PER STRUCTURAL DRAWINGS.
- 10) 2X6 WOOD JOISTS AT 24" O.C. - REFER TO STRUCTURAL DRAWINGS.
- 11) AT CONTRACTOR OPTION PROVIDE GYPSUM BOARD OVER FRAMING - REFER TO SPEC. FOR TYPE AND THICKNESS OF GYPSUM BOARD
- 12) TYPICAL AT BACKSIDE OF PARAPETS INSTALL SINGLE-PLY ROOFING MEMBRANE WITH BONDING ADHESIVE ON VERTICAL FACE OVER 1/2" DENS DECK
- 13) CONCEALED FASTENER METAL WALL PANEL SYSTEM - MTL-3 WITH END CLOSURES, FLASHING, HANGER CLIPS ECT. PER MFG. STANDARDS. INSTALL OVER WEATHER BARRIER OVER EXTERIOR SHEATHING PER SPECIFICATION.
- 14) CONCEALED FASTENER METAL WALL PANEL SYSTEM - MTL-2 WITH END CLOSURES, FLASHING, HANGER CLIPS ECT. PER MFG. STANDARDS. INSTALL OVER WEATHER BARRIER OVER EXTERIOR SHEATHING PER SPECIFICATION.
- 15) GEMENTINOUS STUCCO SYSTEM - STG-1 INSTALL OVER WEATHER BARRIER OVER EXTERIOR SHEATHING PER SPECIFICATION.
- 16) COMPOSITE WOOD PANEL SIDING SYSTEM - WD-1 WITH TRIMS AND FASTENERS PER MFG. STANDARDS. INSTALL OVER WEATHER BARRIER OVER EXTERIOR SHEATHING PER SPECIFICATION.
- 17) ALUMINUM STOREFRONT AND ENTRY SYSTEM (COLOR = BLACK ANODIZED) WITH DOUBLE PANE INSULATED GLASS (COLOR = GRAY TINT)
- 18) HOLLOW METAL DOOR AND FRAME. PAINT
- 19) INSTALL DIRECT APPLIED EXTERIOR FINISH SYSTEM OVER EXTERIOR GYPSUM BOARD







instrument of service by the architect, or under his supervision and is intended for use on this project only. Invariant to the Architecture Institute. Copy right Protection Act. All drawings, specifications, details and other documents are the property of the architect and shall remain his property. No arrangement or composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Architect. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Architect is strictly prohibited.

© COPYRIGHT 2023 GUY  
GRONBERG ARCHITECTS, P.C.

	DATE	DESCRIPTION						
<b>DATE:</b> 08-11-2023								
<b>PROJECT#</b> 23012								

## A6



## GENERAL REQUIREMENTS 01000

- ## PRODUCTS

- ### SPECIAL CONDITIONS

- ## DIVISION 2 - SITE WORK

## SITE WORK / GENERAL

- LANDSCAPING, SEEDING, SOD

- ## PAYEMENTS

1. All pavements shall be as indicated on the Civil drawings and in the civil General Notes. All pavements shall be installed per recommendations of The Geotechnical Report prepared for this site.
2. Sidewalk areas shall be minimum 4" thick concrete, reinforced with 6 x 6 M1.4X1.4 mesh over 4" rock. Walks adjacent to building shall be tied to building footings with #4 bars 18" o.c.

## CONCRETE WORK

- #### DIVISION 4 - MASONRY

## STRUCTURAL STEEL AND MISCELLANEOUS STEEL

- ## DIVISION 6 - WOODS AND PLASTIC

## CARPENTRY

1. Material used in this work shall meet the criteria outlined in the structural General Notes.
2. Each piece of framing lumber shall be identified by the grademark of an approved inspection agency or association.
3. All wood sills and sleepers in contact with masonry or concrete, and wood the bottom of which is 24" or less from the finished floor slab shall be CCA treated. Between the concrete foundation and sill plate provide STYROFOAM brand sill seal foam gasket, a flexible polyethylene gasketing strip, in 5.5" x 50" rolls
4. All rough carpentry items shall be installed in accordance with IBC and/or FHA requirements whichever is most restrictive.
5. 1/2" sheathing to be min 3/8" thick 24/16 span-rated APA rated exterior plywood.

## WEATHER BARRIER


- ## SINGLE PLY ROOFING

- ## THERMAL INSULATION

1. Where insulating materials listed below will not be covered with gypsum board substitute specified insulation w/ product of same thickness and R-value and similar facing, but such shall have a flame spread rating of 25 or less and a smoke developed rating of 50 or less when tested in accordance with ASTM E84 unless more stringent requirements are listed for a specific product.
2. Insulation Schedule
  - 2.1. First floor exterior walls: 6 1/4" - R19 batts of fiberglass with foil skim kraft (FSK) vapor barrier - CertainTeed CertaPRO Thermal Foil Faced Batts. At contractors option 6 1/4" - R19 kraft faced insulation may be used ONLY if it is covered by minimum of one layer of gypsum board.
  - 2.2. Between roof trussed above bearings plate: 6 1/4" - R19 batts of fiberglass with foil skim kraft (FSK) vapor barrier - CertainTeed CertaPRO Thermal Foil Faced Batts.
  - 2.3. See single ply roofing membrane specification for insulation at low sloped roofs (1/4" per ft.) Gaps and voids around door and window areas: Minimal expanding foam insulation shall be Dow Chemical Great Stuff. It is to be tack free in 20 minutes and with full cure in 5 hours at room temperature and 50% relative humidity. It is to be paintable and stainable.
  - 2.4. Interior non-loadbearing walls: Unfaced Fiberglass Batts - CertainTeed CertaPRO AcoustaTherm Batts

## SHEET METAL COMPONENTS

1. Prefinished Sheet: Aluminum-Zinc Alloy-Coated Steel Sheet ASTM A 792/A 792M, Class A250 coating designation, Grade 40 (Class AZM150 coating designation, Grade 75); structural quality and pre-painted by the coil-coating process to comply with ASTM A 755/A 755M. Apply the following coil coating: High-Performance Organic Finish - Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
2. Schedule:
  - 2.1. MTL-1 Prefinished Cap, Fascia, and Miscellaneous Flashing: Form from 24ga Prefinished Sheet (unless noted otherwise) as detailed on the drawings.
  - 2.2. MTL-2 Flush concealed fastener metal wall panel - Pac-Clad 12"x 1"dp flush panels. Form from 24ga Prefinished Sheet. To be formed on precision roll-forming equipment that includes levelers.
  - 2.3. MTL-3 Concealed fastener architectural metal panel - Elevate (formerly Firestone) Delta CFF-12 (50%), CFF-12B (25%), and CFF-12T (25%) installed in a random manner to provide variegated spacing. Form from 22ga Prefinished Sheet. Provide metal end closures. Install with CFF-UNA 25 hanger clips
3. Anchor work in place with noncorrosive fasteners, adhesives, setting compounds, tapes and other materials and devices as recommended by manufacturer of each material or system. Provide for thermal expansion and building movements. Comply with recommendations of "Architectural Sheet Metal Manual" by SMACNA
1. Schedule (Reference typical details on sheet A10)
4. ~~See schedule for joint treatments. Use noncorrosive fasteners.~~
  - 51 - Joints abutting stone joints: Sonoborn, Sonolastic NP2, color to match stone.
  - 52 - See aluminum storefront specification section.
  - 53 - Joints abutting stone: Sonoborn, Sonolastic NP2, color to coordinate with stone.
  - 54 - Joints abutting Stucco: Sonoborn, Sonolastic 150 VLM, color to match stucco.
  - C1 - Interior joints in wet areas: GE Silcones, Sanitary SC5100 Silicone Sealant
  - C2 - Interior storefront to druggall and hollow metal to druggall: Pecora, AC-20 iSilcone
2. Joints and spaces to be caulked shall be clean, dry and free of dust, loose mortar or other foreign materials. After joints have been filled, they shall be neatly tooled to eliminate air pockets or voids and to provide a smooth, neat appearing surface. Compressible Filler is required for back-up of all joints and shall be polyethylene Foam Rod, Pecora Foam No. 88, or approved equal.





## EXTERIOR ALUMINUM FRAMES, DOORS, AND WINDOWS

1. Aluminum storefront and Windows to be EfcO Corporation Series 403T 2"x4½" thermal storefront framing. Provide thermal sills and applied muntins as indicated on the drawings.
2. Aluminum doors to be EfcO Corporation Series D500 Wide Stile 1½" thick Standard aluminum swing entrance doors. Bottom Rail of door to be minimum of 10" high and provide matching intermediate rail at exit device hardware mounting height.
3. Minimum thickness of aluminum shall be 1/8". Slots shall receive thickness of glazing indicated on drawings.
4. Provide aluminum-framed systems, including anchorage, capable of withstanding without failure, load criteria outlined in the Structural General Notes.
5. Comply with manufacturer's instructions and recommendations for installation. Set units plumb and level, accurately aligned and securely anchored.
6. Head, sill, and intermediate mullion break metal flashings shall be formed from .032" aluminum sheet finished to match aluminum finish. Sealant (52) shall be Sonneborn, Sonolastic NP2, with color to match aluminum finish. Sealants of storefronts/windows and associated flashings shall be done by aluminum storefront subcontractor or under his control.

## STEEL FRAMES AND DOORS 08110

3. Drywall interior frames shall be manufactured from cold-rolled 16 gauge steel conforming to ASTM A366 or A620 & A568. Frames shall be knock-doubt, double return back bend (to prevent cutting into wall) Flush hairline miter at the corner of the head and jamb, and the corner reinforced with a concealed clip. Each jamb is to have one compression anchor to securely hold the frame between the studs and maintain proper alignment.
2. Welded exterior frames are to be fabricated of either cold-rolled steel conforming to ASTM A366 or A620 & A568 at interior locations or hot-dipped galvanized steel conforming to ASTM A924 and A653 at exterior locations both of 16 gauge material. Fabricate frames with mitered or coped and continuously welded corners and seamless face joints. Provide welded frames with temporary spreader bars.
3. All Frames and Doors are to be thoroughly degreased and cleaned of all imperfections and provided with one coat of oven-cured neutral color primer paint. Primer coat shall conform with ANSI A250.10. The primer coat is to be a preparatory base for necessary finish painting.
4. Frame Hardware Provisions: Frames are to be mortised, reinforced and drilled and tapped for all mortise finish hardware. Frames are to be reinforced only for surface mounted hardware, with drilling and tapping to be done in the field by the installation contractor. Steel plates and mortising boxes are to be welded to all hinge and lock reinforcement. Frames are drilled, Hinge Jamb's are to be mortised for hinges with 7 gauge steel hinge reinforcement welded in place and headed and tapped for fasteners in accordance with ANSI A156.7. The strike jamb is to be prepared for 4-7/8" universal strike in accordance with ANSI A 115.142. Additional hardware reinforcement (e.g. closer/holder as indicated by hardware schedule) is to be 12 gauge minimum steel welded in place. Three door mutes are to be provided per strike jamb and two for double swing heads.
5. Where fire rated openings are scheduled, provide fire rated frames and doors for the assembly with ratings as scheduled or noted. Frames and Doors shall have factory applied underwriter Laboratories, Inc. metal label permanently affixed, identifying fire rating classification and time. Where required to achieve rating, due to size of openings, gauge of fire rated doors and frames shall be increased.
6. Exterior Steel doors are to be full-Flush style with face sheets of 16ga hot-dipped galvanized steel conforming to ASTM A924 and A653. They are to have mechanically interlocked, hemmed, hairline seams on vertical edges and have no visible seams on faces (S.D.I. Design I). Face sheets are to be totally supported by a foamed-in-place polyurethane core. The core is to fill the entire door cavity and be chemically bonded to all interior surfaces. Density of foam to exceed 1.5pcf and it have a minimum crush strength of 3600 psf. The top and bottom door edges are to be closed with 16 gauge steel channels welded in place.
7. Door Hardware Provisions: Hinge preparations are handed. Hinge edges are to be mortised for hinges with 7 gauge steel hinge reinforcement welded inside the door edge and drilled and tapped for fasteners in accordance with ANSI A156.7. The lock edge is to have a standard bore (1-1/8") and be prepared for locks in accordance with hardware schedule. Additional hardware reinforcement (e.g. closer/pulls as indicated by hardware schedule) is to be 12 gauge steel channel.

## GLASS AND GLAZING

1. "1" insulated tinted, low-E glass: Each pane shall be 1/4" thick plate or float glass. Units shall be dual-sealed silicone units. All units to have low-E coating per manufacturers standard. Where indicated also provide light bronze tint per manufacturers standard.
2. Clear tempered safety glass shall be prime glass type, which has been treated to strengthen glass in bending to not less than 4.5 times annealed strength.
3. Except as otherwise indicated, comply with glass manufacturer's instructions, glazing materials manufacturer's instructions, and "Glazing Manual" by F&M and other technical publications of recognized authorities in the industry. Install each piece to achieve watertight and airtight performance, and to minimize breakage.
4. Provide glazing sealants, compounds, tapes and gaskets as indicated and required, making specific product selections in compliance with manufacturer's recommendations. Coordinate materials for compatibility, and do not use solvent-release materials for glazing laminate glass, sealant-edged insulated glass, or glazing plastics.

## FINISH HARDWARE 08710

1. Provide finish hardware for all doors in project. See Door Hardware Schedule on drawings for specific information. The Contractor shall verify all keying requirements with owner prior to installation. Finish to be 26D (confirm w/ owner.) Hardware mounting heights by the door and hardware institute "Recommended Locations for Builders Hardware". Comply with all ADA requirements for hardware.

## CEMENTITIOUS STUCCO SYSTEMS

1. Cementitious Stucco System is to be Sto Powerwall as manufactured by Sto Corp., 3800 Camp Creek Parkway, Building 1400, Suite 120, Atlanta, GA 30331. Install products below per manufactures written installation instructions and specification "Sto guide Specification S504 StoPowerwall with Metal Plaster Base on Concrete, Concrete Masonry (CMU), and Frame Wall Construction"
2. Lath shall be minimum paper backed 2.5 lb./yd2 (1.4 kg/m2) self furred galvanized steel diamond mesh metal lath in compliance with ASTM C 847.
3. Mechanical Fasteners: Non-corroding fasteners in compliance with AISI S200 2007 and ASTM C 1519, minimum 11 gauge, 7/16 inch diameter head galvanized roofing nails with minimum ¾ inch (19mm) penetration into studs or minimum #5 U shape w/ water head fully threaded corrosion resistant screws with minimum ¾ inch (19 mm) penetration into studs.
4. Provide Drip screed, casing bead, corner lath, expansion and control joint accessories. All accessories shall meet the requirements of ASTM C 1063 and its referenced documents. Accessories shall be either PVC plastic (ASTM D 1754, cell classification 13244C), Zinc (ASTM B 64), or galvanized metal (ASTM A 653 with G60 coating.) All accessories shall have perforated or expanded flanges and shall be designed with grounds for the specified thickness of stucco.
5. Stucco shall be 105 StoPowerwall Scratch & Brown portland cement-based stucco concentrate in compliance with ASTM C 926 factory proportioned, fiber reinforced portland cement based stucco for trowel or pump application, field mixed with graded sand (ASTM C 847) and potable water.
6. Application of Scratch Coat Stucco: Apply scratch coat in accordance with PCA Plaster (Stucco) Manual. Apply scratch coat to nominal thickness of 1/2 inch over metal lath surfaces. If weather is hot or surface is dry, dampen previous coat before applying mortar and thin stone veneer. If scratch coat is done in advance, use notch trowel to create texture for better bond. Smooth surface is not acceptable for bond.
7. Application of Brown Coat Stucco: Apply Brown coat as soon as the first coat is firm enough to receive the second coat without damage. Alternatively, moist cure the first coat up to 48 hours and dampen the scratched surface with water immediately before applying the second coat. Apply the second coat with sufficient pressure to ensure intimate contact with the first coat and as needed to bring the stucco to a uniform thickness that matches the grounds of the accessories. Use a rod or straight edge to bring the surface to a true, even plane. Fill depressions in wall with stucco. Final combined thickness of scratch and brown coats shall be uniform throughout the plane area and shall be 3/4 inch.
8. Finish coat shall be Sto Powerflex with texture as selected by owner.

GYPSUM DRYWALL

1. Materials shall meet the following standards:
  - 1.1. Gypsum Wallboard - ASTM C36
  - 1.2. Nails - ASTM C380
  - 1.3. Metal Accessories - ASA A97.1
  - 1.4. Water Resistant Gypsum Backing Board - ASTM C1278 (paragraph 6.1)
2. Use gypsum board fasteners that are recommended by gypsum board manufacturer except as otherwise indicated. Furnish and install all trim accessories, adhesives and joint treatments per manufacturer's recommendations. All exposed gypsum board to be finished to Level 4 unless noted otherwise.
3. Schedule: (basis of design)
  - 3.1. Interior side of exterior walls:  $\frac{1}{2}$ " Gold Bond XP Gypsum Board. Note: No gypsum board is required unless otherwise indicated. At owners option gypsum board may be installed. If installed Gypsum Board is to be installed from floor to underside of roof trusses.
  - 3.2. Interior partitions in mechanical equipment rooms:  $\frac{1}{2}$ " Gold Bond XP Gypsum Board.

## PAINT AND WOOD FINISHES

1. Paint shall be as manufactured by Sherwin Williams Paints or approved equal.
2. Surface Preparation for paint;
  - 2.1. General: Protect adjacent and underlying surfaces. Remove or mask electrical plates, hardware, light fixture trim, escutcheons, and fittings prior to preparing surfaces of finishing. Correct defects and clean surfaces capable of affecting work of this section. Seal marks that may bleed through surface finishes with compatible sealer.
  - 2.2. Galvanized Steel: Remove surface contamination and oils and wash with solvent.
  - 2.3. Uncoated Ferrous Metals: Remove grease, mill scale weld splatter, dirt and rust. Where heavy coatings of scale are evident, remove by hand or power tool wire brushing or sandblasting; wash with solvent. Apply treatment of phosphoric acid solution, ensuring weld joints, bolts and nuts are similarly cleaned. Spot Prime paint after repairs.
  - 2.4. Shop primed ferrous Metals: Sand and scrape to remove loose primer and rust. Feather edges to make patches inconspicuous. Clean with solvent. Prime bare steel surfaces.
  - 2.5. Other existing surfaces: Remove loose, flaking, powdery, and peeling paints. Light sand painted surfaces. Fill holes, cracks, depressions and other imperfections with compatible patching compound; sand flush with surface. Remove oil, grease, and wax by scraping; solvent wash and thoroughly rinse. Remove rust by wire brushing to expose base metal.
3. Paint and wood finishes schedule;
  - 3.1. Paint all new and existing interior gypsum board walls in wet areas (Mechanical Rooms):
    - 1 ct. PrepRite 200 Latex Primer and
    - 2 cts. Waterbased Catalyzed Epoxy
  - 3.2. Interior gypsum board ceilings and soffits (unless noted otherwise):
    - 1 ct. PrepRite 200 Latex Primer
    - 2 cts. ProMar 200 Int. Latex Flat.
  - 3.3. Interior and Exterior Ferrous metal (metal frames, exposed steel structure, misc. metal):
    - Touch up factory prime coat with compatible Metal Primer or
    - 1 ct. Sprayed All Surface Enamel oil Primer
    - 2 cts. Sprayed A-100 Exterior Latex Satin.

## FIRE EXTINGUISHER

1. Provide THREE Fire extinguishers. Fire extinguishers shall be Cosmic 5E (2A,10B,C) by J.L. Industries or approved equal. Cabinets to be Ambassador by J.L. Industries or approved equal, Not Fire-Rated, Tub - 10 1/2 x 24 x 5 1/2 inches. Trim Material - Steel, white epoxy primer finish, Trim Style Semi recessed 3" rolled edge. Door Style - Vertical Duo Panel with pull handle, Door Glazing - Clear Safety Glass, with Die Cut Letters - Vertical Red Reverse.



**G<sup>2</sup>**

DOUGLAS  
| CORNER |

This drawing has been provided as an instrument of service by the architect, or under his supervision and is intended for use on this project only. In accordance with the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, designs, and/or computer generated drawings, arrangements and compositions of various graphic elements appearing herein, constitute the original, copyrighted work of the Designer/Architect. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Architect is strictly prohibited.

© COPYRIGHT 2023 GUY  
GRONBERG ARCHITECTS P.C.

[illegible]

# A8



NOTES - STEEL

1. ALL STRUCTURAL STEEL TO BE FABRICATED AND ERECTED IN ACCORDANCE WITH THE GOVERNING EDITION OF THE AISC "CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES."
2. BOLTED CONNECTIONS: ALL BOLTED CONNECTIONS SHALL BE SNUG-TIGHT IN ACCORDANCE WITH THE "SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM F312S GRADE A325 OR A490 BOLTS" PUBLISHED BY THE RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS.
3. WELDED CONNECTIONS: ALL WELDING SHALL BE IN ACCORDANCE WITH THE "STRUCTURAL WELDING SOCIETY CODE" (AWS D1.1) PUBLISHED BY THE AMERICAN WELDING SOCIETY. ELECTRODES FOR WELDING SHALL COMPLY WITH THE REQUIREMENTS OF TABLE 3.1 OF AWS D1.1. ALL WELDING TO BE DONE BY QUALIFIED WELDERS CONFORMING TO THE AMERICAN WELDING SOCIETY STANDARDS.
4. SPLICING OF STEEL MEMBERS, UNLESS SHOWN ON THE DRAWINGS, IS PROHIBITED WITHOUT THE WRITTEN APPROVAL OF APEX ENGINEERS, INC.
5. CHANGES IN SIZE OR POSITION OF THE STRUCTURAL ELEMENTS, AND HOLES, SLOTS, CUTS, ETC. THROUGH ANY MEMBER, ARE NOT PERMITTED UNLESS THEY ARE DETAILED ON THE APPROVED SHOP DRAWINGS.
6. NO FINAL BOLTING OR WELDING SHALL BE MADE UNTIL AS MUCH OF THE STRUCTURE AS WILL BE STIFFENED THEREBY HAS BEEN PROPERLY ALIGNED.
7. FABRICATE ALL BEAMS WITH THE MILL CAMBER UP UNO.
8. ALL VISIBLE WELDED CONNECTIONS ON ARCHITECTURAL ELEMENTS TO BE GROUND SMOOTH TO NOT REDUCE THICKNESS OF WELD.
9. THE FABRICATOR SHALL BE RESPONSIBLE FOR THE DESIGN AND PERFORMANCE OF ALL CONNECTIONS NOT FULLY DESIGNED OR DETAILED IN THE CONTRACT DOCUMENTS. FABRICATOR TO PROVIDE ENGINEERD STAMPED SHOP DRAWINGS AND CALCULATIONS FOR ALL CONNECTIONS THAT DO NOT COMPLY WITH AISC STEEL CONSTRUCTION MANUAL CHAPTER 10 SIMPLE SHEAR CONNECTIONS.
10. STEEL MEMBERS ON THE EXT OF THE BUILDING OR EXPOSED TO SOIL MUST BE, AT A MIN, PROPERLY PRIMED WITH RUST INHIBITING PRIMER AND PAINTED. STEEL MEMBERS COMPLETELY ENCLOSED IN BUILDING ENVELOPE DO NOT REQUIRE PRIMER OR PAINT. UNO. REF ARCHITECTURAL DOCUMENTS FOR ADDITIONAL REQUIREMENTS OF EXPOSED STEEL.

NOTES - ROUGH CARPENTRY

1. CONTRACTOR IS RESPONSIBLE TO ADEQUATELY SHORE AND BRACE ALL FLOOR AND ROOF FRAMING AND WALLS DURING CONSTRUCTION.
2. NAILING SHALL BE PER FASTENING SCHEDULE OF THE INTERNATIONAL BUILDING CODE. FOR PREFABRICATED CONNECTORS USE ALL FASTENERS AS PRESCRIBED BY THE MANUFACTURER.
3. ALL POST AND JAMBS ARE TO BE BLOCKED SOLID WITH THE SAME NUMBER OF PIECES AS THE POST OR JAMB WITHIN THE FLOOR SPACE AND CONTINUOUS TO THE FOUNDATION LEVEL. BLOCKING IS TO ALIGN WITH POST OR JAMBS.
4. SPECIES AND GRADES SHOWN IN SCHEDULE ARE THE MINIMUM ACCEPTABLE. BETTER GRADES MAY BE SUBSTITUTED.
5. PRESSURE TREATED WOOD TO BE USED WHEN EXPOSED TO WEATHER OR IN CONTACT WITH CONCRETE OR MASONRY.
6. WOOD STRUCTURAL PANELS TO BE APA RATED AND EXPOSURE 1. PANELS TO BE MANUFACTURED PER US DEPARTMENT OF COMMERCE PRODUCT STANDARDS PS1 OR PS2.
7. ANY FASTENERS OR CONNECTORS TO AND THROUGH TREATED WOOD SHALL BE FASTENED WITH ASTM A153 CLASS D HOT DIP GALVANIZED OR STAINLESS STEEL FASTENERS.
8. WOOD FRAMING WILL HAVE SHRINKAGE. THE CONTRACTOR SHALL COORDINATE REQUIREMENTS TO ACCOMMODATE SHRINKAGE WITH OTHER TRADES.
9. BORED HOLES FOR HORZ PLUMBING PIPING SHALL BE PROVIDED WITH FLEXIBLE JOINTS TO PERMIT MOVEMENT.
10. RIGID ELECTRICAL CONDUIT INSTALLED VERTICALLY SHALL BE PROVIDED WITH FLEXIBLE JOINTS TO PERMIT MOVEMENT.
11. ALL DIMENSIONAL LUMBER SHALL BE GRADE STAMPED WITH MOISTURE CONTENT NOT TO EXCEED 19%.
12. INJOISTED STRUCTURAL LUMBER NOT PERMITTED WITHOUT THE PRIOR WRITTEN APPROVAL OF THE STRUCTURAL ENGINEER.
13. DIMENSIONAL LUMBER SIZES SHOWN ON PLANS ARE NOMINAL DIMENSIONS. DRESSED SIZES PUBLISHED IN THE LATEST EDITION OF AMERICAN SOUTHWEST LUMBER PS20 SHALL BE ACCEPTED AS MINIMUM NET SIZES CONFORMING TO SUCH NOMINAL SIZES.
14. WOOD HEADERS SHALL HAVE A FULL 3" LENGTH OF BEARING AT EACH END UNO.
15. ALL BEAMS AND JOISTS NOT BEARING ON SUPPORTING MEMBERS SHALL BE FRAMED WITH PREFABRICATED METAL JOIST HANGERS FOR REQUIRED CAPACITY. ALL PREFABRICATED METAL HARDWARE IS BY SIMPSON STRONG-TIE COMPANY OR APPROVED EQUIVALENT. CONNECTIONS IN CONTACT WITH PRESSURE TREATED WOOD SHALL HAVE G185 GALVANIZED COATING PER ASTM A653 AND HOT DIPPED GALVANIZED FASTENERS PER ASTM A153. ALTERNATE CORROSION RESISTANT CONNECTIONS IN ACCORDANCE WITH IBC WILL BE CONSIDERED. PRIOR WRITTEN APPROVAL BY THE STRUCTURAL EOR IS REQUIRED.
16. WALL, FLOOR, AND ROOF SHEATHING NAILS SHALL HAVE FULL HEADS. CLIPPED NAILS ARE NOT ALLOWED IN THESE APPLICATIONS.
17. NAIL TYPE USED IN WALL, FLOOR, AND ROOF WSP SHEATHING SHALL BE COMMON OR GALVANIZED BOX NAILS. SINKER NAILS, COOLER NAILS, ETC ARE NOT PERMITTED IN THESE APPLICATIONS.
18. ALL SIDE LOADED LVL BEAMS TO BE FASTENED TOGETHER PER MFR REQUIREMENTS.
19. ALL MULTI-PLY BEAMS TO BE SUPPORTED BY STUD PACK WITH (1) ADDITIONAL STUD THAN BEAM PLIES.

NOTES - PREFAB WOOD TRUSSES

1. TRUSSES TO BE DESIGNED AND ERECTED IN CONFORMANCE WITH TRUSS PLATE INSTITUTE SPECIFICATIONS AND RECOMMENDATIONS AND IN ACCORDANCE WITH LOCAL BUILDING CODES.
2. TRUSSES TO BE BRACED PER MFR RECOMMENDATIONS DURING ERECTION.
3. TRUSSES SHALL BE LATERALLY SUPPORTED AT ALL PANEL POINTS.
4. TRUSS MFR TO DESIGN AND PROVIDE ALL TRUSS CONNECTIONS.
5. TRUSS MFR IS TO SUBMIT LAYOUT PLANS AND CALCULATIONS FOR ALL TRUSSES. THE CALCULATIONS ARE TO BEAR A LICENSED PROFESSIONAL ENGINEERS SEAL IN THE STATE OF WHICH THE PROJECT IS LOCATED. CALCULATIONS ARE TO SHOW LOADINGS, SPACING, STRESSES, CONFIGURATION, CONNECTIONS, GRADE OF MATERIAL, CAMBER, AND DEFLECTIONS.
6. FLOOR AND ROOF TRUSSES NOTED AS A DRAG TRUSS (DT) SHALL BE DESIGNED TO TRANSFER OR CARRY AXIAL LOAD NOTED ON FRAMING PLANS ACTING ALONG TRUSS TOP CHORD AND SHALL BE RESISTED ALONG BOTTOM CHORD OVER LENGTH NOT GREATER THAN LENGTH OF SHEAR WALL NOTED ON PLANS (IF APPLICABLE). ALL PROVIDED LOADS ON PLANS ARE ULTIMATE LEVEL, (UNFACTORED) WIND LOAD, UNO ON PLAN).
7. TRUSSES SHALL NOT BE NOTCHED, DRILLED, CUT, OR ALTERED WITHOUT WRITTEN APPROVAL OF THE TRUSS MANUFACTURER'S ENGINEER. PROPOSED MODIFICATIONS SHALL BE REVIEWED BY THE STRUCTURAL EOR PRIOR TO MODIFICATION.
8. THE WOOD TRUSS MFR SHALL BE REGISTERED AND APPROVED PER IRC SECTION 1704.5.2 FOR FABRICATION WITHOUT SPECIAL INSPECTION.
9. FLAT ROOF TRUSSES SHALL BE DESIGNED FOR AN ADDITIONAL LOAD OF MIN (2) 20 LB POINT LOADS SPACED AT 5' APART ANYWHERE ALONG THE TOP CHORD FOR MECH. CONDENSORS. MECH CONDENSORS SHALL BE PLACED SUCH THAT THEY ARE SUPPORTED BY AT LEAST (2) ROOF TRUSSES.

NOTES - GENERAL

1. THESE DRAWINGS ARE INTENDED TO BE USED WITH ARCHITECTURAL AND MECHANICAL DRAWINGS. CONTRACTOR IS RESPONSIBLE FOR COORDINATING SUCH REQUIREMENTS INTO THEIR SHOP DRAWINGS AND WORK.
2. NO OPENING SHALL BE MADE IN ANY STRUCTURAL MEMBER WITHOUT THE WRITTEN APPROVAL OF THE ENGINEER.
3. NO CHANGE IN SIZE OR DIMENSION OF STRUCTURAL MEMBERS SHALL BE MADE WITHOUT THE WRITTEN APPROVAL OF THE ENGINEER.
4. THE CONTRACTOR IS RESPONSIBLE FOR LIMITING THE AMOUNT OF CONSTRUCTION LOAD IMPOSED UPON STRUCTURAL FRAMING. CONSTRUCTION LOADS SHALL NOT EXCEED THE DESIGN CAPACITY OF THE FRAMING AT THE TIME THE LOADS ARE IMPOSED.
5. THE STRUCTURE IS DESIGNED TO FUNCTION AS A UNIT UPON COMPLETION. THE CONTRACTOR IS RESPONSIBLE FOR FURNISHING ALL TEMPORARY BRACING AND/OR SUPPORT THAT MAY BE REQUIRED AS THE RESULT OF THE CONTRACTOR'S CONSTRUCTION METHODS AND/OR SEQUENCES.
6. FOUNDATION WALLS SHALL NOT BE BACKFILLED UNTIL LOWER AND UPPER SLABS ARE IN PLACE AND REACH FULL STRENGTH UNLESS ADEQUATE BRACING IS PROVIDED. USE ONLY HAND-OPERATED TOOLS FOR COMPACTION ADJACENT TO FOUNDATION WALLS AND FOOTINGS. FOOTINGS SHALL BE BACKFILLED EVENLY ON BOTH SIDES.
7. UNLESS OTHERWISE NOTED, FIREPROOFING METHODS AND MATERIALS FOR STRUCTURAL MEMBERS ARE NOT SHOWN ON STRUCTURAL DRAWINGS. REFERENCE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR FIRE RATING REQUIREMENTS, FIRE PROOFING METHODS AND MATERIALS.
8. DO NOT SCALE THESE DRAWINGS. USE DIMENSIONS SHOWN ON PLANS.
9. THE CONTRACTOR SHALL INFORM THE ARCHITECT/ENGINEER OF ANY DEVIATION FROM THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL NOT BE RELIEVED OF THE RESPONSIBILITY FOR SUCH DEVIATION BY THE ARCHITECT/ENGINEER'S APPROVAL OF SHOP DRAWINGS, PRODUCT DATA, ETC., UNLESS HE HAS SPECIFICALLY INFORMED THE ARCHITECT/ENGINEER OF SUCH DEVIATION AT THE TIME OF SUBMISSION, AND THE ARCHITECT/ENGINEER HAS GIVEN WRITTEN APPROVAL TO THE SPECIFIC DEVIATION.
10. ALL THINGS WHICH, IN THE OPINION OF THE CONTRACTOR, APPEAR TO BE DEFICIENCIES, OMISSIONS, CONTRADICTIONS, SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/ENGINEER. PLANS AND/OR SPECIFICATIONS WILL BE CORRECTED, OR WRITTEN INTERPRETATION OF THE ALLEGED DEFICIENCY, OMISSION, CONTRADICTION OR AMBIGUITY WILL BE MADE BY THE ARCHITECT/ENGINEER BEFORE THE AFFECTED WORK PROCEEDS.
11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL ERRORS OF DETAILING, FABRICATION AND INSTALLATION. THE CONTRACTOR SHALL MAKE ALL MEASUREMENTS IN THE FIELD NECESSARY TO VERIFY OR SUPPLEMENT DIMENSIONS SHOWN ON THE CONTRACT DRAWINGS AND HE SHALL VERIFY THAT ALL DIMENSIONS SHOWN ON THE SHOP DRAWINGS ARE COORDINATED WITH THE DIMENSIONS AND REQUIREMENTS OF THE CONTRACT DRAWINGS. REVIEW OF THE SHOP DRAWINGS DOES NOT RELIEVE THE CONTRACTOR OF RESPONSIBILITY FOR COMPLETING THE WORK SUCCESSFULLY IN ACCORDANCE WITH THE CONTRACT DRAWINGS AND SPECIFICATIONS.
12. SUBMIT PRINTS OR ELECTRONIC COPIES OF EACH SHOP DRAWINGS. REPRODUCIBLE COPIES OF CONTRACT DOCUMENTS SHALL NOT BE USED AS SHOP DRAWINGS. SHOP DRAWINGS SHALL BE REVIEWED BY CONTRACTOR PRIOR TO SUBMISSION. CONTRACTOR STAMP SHOP DRAWINGS ACCEPTING RESPONSIBILITY FOR COORDINATION OF DIMENSIONS SHOWN IN THE CONTRACT DOCUMENTS. QUANTITIES AND COORDINATION WITH OTHER TRADES, DRAWINGS NOT BEARING CONTRACTOR'S STAMP MAY BE REJECTED AT THE DISCRETION OF THE ARCHITECT OR STRUCTURAL ENGINEER.
13. REVIEW AND RETURN OF SHOP DRAWINGS SHALL BE BASED ON A MINIMUM OF TEN (10) WORKING DAYS IN THE STRUCTURAL ENGINEER'S OFFICE FROM RECEIPT OF SUBMISSION TO RETURN TO THE NEXT PARTY FOR THEIR ACTION. SHOP DRAWINGS SHOULD BE SUBMITTED INCREMENTALLY AS APPROPRIATE PACKAGES ARE PREPARED TO EQUALIZE THE WORKLOAD FOR REVIEW OF THE DRAWINGS. SUBMISSION OF A LARGE VOLUME OF SHOP DRAWINGS AT ONE TIME MAY RESULT IN REVIEW TIMES WHICH WILL EXCEED THOSE NOTED ABOVE. DEFINITION OF A "LARGE VOLUME" OF SHOP DRAWINGS IS SUBJECT TO INTERPRETATION.

NOTES - SHALLOW FOUNDATIONS

1. CONTRACTOR SHALL BE FULLY FAMILIAR WITH ALL ASPECTS OF THE SOILS REPORT BEFORE BEGINNING CONSTRUCTION.
2. CONTRACTOR SHALL USE THE SOILS REPORT FOR SPECIFICATIONS AND DETAILS FOR PLACEMENT OF PERIMETER DRAINS, UNDER-SLAB DRAINS, AND ANY OTHER SOILS RELATED ITEMS.
3. CONTRACTOR SHALL REFER TO THE SOILS REPORT FOR ALL SOIL CONDITIONING REQUIREMENTS PRIOR TO PLACING BUILDING FOUNDATIONS.
4. ALL FOOTING EXCAVATIONS TO BE APPROVED BY GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE.
5. ALL EXT AND PERIMETER FOOTINGS SHALL EXTEND BELOW FROST DEPTH, REF DESIGN INFORMATION FOR FROST DEPTH.

NOTES - CONCRETE

1. ALL CONCRETE CONSTRUCTION TO CONFORM TO ACI "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE", THE GOVERNING EDITION OF THE ACI 318, AND ACI "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS" ACI 301, UNO.
2. WATER REDUCING ADJ MIXTURES ARE ALLOWED IN CONCRETE MIX DESIGNS.
3. SYNTHETIC MICRO-FIBERS ARE NOT ALLOWED UNLESS SPECIFICALLY NOTED IN THESE DRAWINGS.
4. UNLESS OTHERWISE SHOWN IN THE ARCHITECTURAL DRAWINGS, PROVIDE 3/4" CHAMFERS AT THE EDGES THAT ARE EXPOSED TO VIEW IN THE FINISHED STRUCTURE.
5. REF ARCHITECTURAL DRAWINGS FOR DOOR AND WINDOW OPENINGS, DRIP SLOTS, REGLETS, MASONRY, ANCHORS, BRICK LEDGE ELEVATIONS AND FOR MISCELLANEOUS EMBEDDED PLATES, BOLTS, ANCHORS, ANGLES, ETC.
6. REF ARCHITECTURAL DRAWINGS FOR CONCRETE FINISHES. WHERE FINISH IS NOT SPECIFIED, CONFORM TO REQUIREMENTS OF ACI 301.
7. REF MECHANICAL, PLUMBING, AND ELECTRICAL DRAWINGS FOR DRAINS, SLEEVES, OUTLET BOXES, CONDUIT, ANCHORS, ETC.
8. CONTACT APEX ENGINEERS, INC. IF HOUSE KEEPING PADS OR INERTIA BASES ARE REQUIRED BEYOND WHAT IS SHOWN IN THE STRUCTURAL CONTRACT DOCUMENTS.
9. ALL REINFORCING STEEL TO BE DETAILED IN ACCORDANCE WITH ACI "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES."
10. REINFORCING SHALL BE CONTINUOUS WHEREVER POSSIBLE. SPLICES AND LAPS TO CONFORM TO ACI 318. REFER TO CONCRETE REBAR SCHEDULE.
11. DOWELS IN FOOTING, WALLS, AND DRILLED PIERS MUST BE IN POSITION BEFORE PLACING CONCRETE WHENEVER POSSIBLE.
12. REF TYP FOUNDATION DETAILS FOR INFORMATION ON REINFORCING REQUIREMENTS AT WALL AND SLAB OPENINGS.
13. REF TYP FOUNDATION DETAILS FOR INFORMATION ON REINFORCING REQUIREMENTS AT CORNER AND TEE INTERSECTIONS.
14. PROVIDE VERT CONTROL JOINTS ON ALL POURED CONCRETE WALLS AND BASEMENT WALLS, EXCEPT FOUNDATION STEM WALLS LOCATED IN THE GROUND. SPACE JOINTS AT 3 x WALL HEIGHT FOR WALLS LESS THAN 10'-0" AND WALL HEIGHT FOR TALLER WALLS. PROVIDE ADDITIONAL JOINT WITHIN 10'-0" OF CORNERS.
15. OPENINGS IN WALLS 1'-4" AND LESS ON A SIDE ARE GENERALLY NOT SHOWN ON THE STRUCTURAL DRAWINGS. REF ARCHITECTURAL AND MECHANICAL DRAWINGS FOR SUCH OPENINGS.

MATERIAL SPECIFICATIONS						
CONCRETE & REINFORCING STEEL SPECIFICATIONS						
MATERIAL			SPECIFICATION			
REINFORCING BARS			ASTM A615, GRADE 60			
WELDED REBAR			ASTM A706			
WELDED WIRE FABRIC			ASTM A1064			
STUD RAIL ASSEMBLIES			ASTM A1044			
PORTLAND CEMENT			ASTM C 150			
FLY ASH			ASTM C 618, 15% MAX			
CONCRETE AGGREGATES			ASTM C 33, 3/4" MAX AGGREGATE SIZE			
EPOXY - THREADED ROD ANCHORS			HILTI HIT-HY 200 V3 A OR SIMPSON SET 3G			
EPOXY - REINFORCING BARS			HILTI HIT-HY 200 V3 R OR SIMPSON SET 3G			
POWDER-ACTUATED FASTENERS			HILTI 0.157" DIA X-U OR SIMPSON 0.157" DIA PDPA			
REBAR CONDITIONS			MINIMUM CONCRETE COVER			
FORMED SURFACES EXPOSED TO GROUND OR WEATHER			2"			
UNFORMED SURFACE IN CONTACT WITH GROUND			3"			
WALLS AND SLABS NOT EXPOSED TO GROUND OR WEATHER			1"			
INTERIOR BEAMS AND COLUMNS (TO TIES OR STIRRUPS)			1 1/2"			
CONCRETE MIX DESIGNS						
CONCRETE USE	WEIGHT	28 DAY Fc	CEMENT TYPE	MAX W/C	SLUMP (H+1")	%AIR
FOOTINGS	NW	3500 psi	III	0.55	5"	6% MAX
INT. SLAB ON GRADE	NW	4000 psi	III	0.45	5"	3% MAX
CONCRETE SLAB SPECIFICATIONS						
FLATNESS CRITERIA			SPECIFICATION			
FLOOR FLATNESS, FF			SOV: 35   MLV: 25			
FLOOR LEVELNESS, FL			SOV: 24   MLV: 17			
STEEL MATERIAL SPECIFICATIONS			SPECIFICATION			
WIDE FLANGE SHAPES (W)			ASTM A992			
CHANNELS (C), ANGLES (L)			ASTM A36			
PLATES			ASTM A36			
HOLLOW STRUCTURAL SHAPES (HSS)			ASTM A500, GRADE C			
HEADER ANCHOR STUDS			AWS D1.1 TYPE B / ASTM A225			
HIGH STRENGTH BOLTS			ASTM F312S, GRADE A325			
ANCHOR BOLTS (HEX HEAD UNO)			ASTM F1554 (55 KSI) "S1"			
EPOXY ANCHOR RODS			ASTM A36			
POWDER-ACTUATED FASTENERS			HILTI 0.157" DIA X-U OR SIMPSON 0.157" DIA PDPA			
STEEL DECK, PLAIN STEEL			ASTM A1008, (33 KSI)			
STEEL DECK, GALVANIZED			ASTM A653, (33 KSI)			
NON-SHRINK GROUT, COLUMN BASES			5000 PSI (28 DAY STRENGTH)			
WOOD MATERIAL SPECIFICATIONS						
MATERIAL			SPECIFICATION			
JOISTS, RAFTER, HEADERS, BEAMS			No. 2 DFL			
TREATED LUMBER			No. 2 SP			
STUDS, BEARING WALL			REF PLAN / SCHEDULE			
SILL AND TOP PLATES			REF PLAN / SCHEDULE			
HEAVY TIMBERS			No. 1 DFL			
GLULAM BEAMS - SINGLE SPAN			DFIDF 24F-V4			
GLULAM BEAMS - MULTI SPAN			DFIDF 24F-V8			
GLULAM COLUMNS			DF COMB #2			
LAMINATED VENEER LUMBER, LVL			Fb = 2600 psi, E = 2.0 x 10 <sup>6</sup> psi			
LAMINATED STRAND LUMBER, LSL			Fb = 1700 psi, E = 1.3 x 10 <sup>6</sup> psi			
PARALLEL STRAND LUMBER, PSL			Fb = 2500 psi, E = 1.8 x 10 <sup>6</sup> psi			
BOLTS AND THREADED RODS			ASTM A307 (MIN.)			
POWDER-ACTUATED FASTENERS			SIMPSON 0.157" DIA POPAWL			
FRAMING NAIL SPECIFICATIONS						
COMMON NAIL			BOX NAIL			
SIZE	DIAMETER	LENGTH	DIAMETER	LENGTH		
6d	0.113"	2"	0.099"	2"		
8d	0.131"	2 1/2"	0.113"	2 1/2"		
10d	0.148"	3"	0.128"	3"		
16d	0.162"	3 1/2"	0.135"	3 1/2"		
20d	0.192"	4"	0.148"	4"		
40d	0.225"	5"	0.162"	5"		


NOTES - DEFERRED SUBMITTALS

1. THE ARCHITECT OR ENGINEER OF RECORD SHALL LIST THE DEFERRED SUBMITTALS ON THE PLANS FOR REVIEW BY THE BUILDING OFFICIAL.
2. DOCUMENTS FOR DEFERRED SUBMITTAL ITEMS SHALL BE SUBMITTED TO THE ARCHITECT OR ENGINEER OF RECORD WHO SHALL REVIEW THEM AND FORWARD THEM TO THE BUILDING OFFICIAL WITH A NOTATION INDICATING THAT THE DEFERRED SUBMITTAL DOCUMENTS HAVE BEEN REVIEWED AND FOUND TO BE IN THE GENERAL CONFORMANCE TO THE DESIGN OF THE BUILDING.
3. THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THE DEFERRED SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL.
4. DEFERRED SUBMITTALS ARE DEFINED AS THOSE PORTIONS OF THE DESIGN THAT ARE NOT SUBMITTED AT THE TIME OF THE APPLICATION AND THAT ARE TO BE SUBMITTED TO THE BUILDING OFFICIAL WITHIN A SPECIFIED PERIOD.
5. DEFERRAL OF ANY SUBMITTAL ITEMS SHALL HAVE THE PRIOR APPROVAL OF THE BUILDING OFFICIAL.
6. SUBMITTALS SHALL INCLUDE DETAILED DRAWINGS OF EACH MEMBER AND ITS CONNECTIONS ALONG WITH SUPPORTING CALCULATIONS PREPARED UNDER THE SUPERVISION, BEARING THE SEAL AND SIGNATURE, OF A LICENSED PROFESSIONAL ENGINEER IN THE PROJECT JURISDICTION.
7. CONTRACTOR SHALL SUBMIT STRUCTURAL DEFERRED SUBMITTAL FOR THE FOLLOWING:
- PREFABRICATED WOOD TRUSSES
  - GUARDRAILS AND HANDRAILS
  - STEEL FABRICATED STAIRS AND LADDERS

NOTES - SHOP DRAWING SUBMITTALS

1. SHOP DRAWINGS SHALL BE SUBMITTED FOR ALL STRUCTURAL ITEMS IN ADDITION TO THOSE REQUIRED BY ARCHITECTURAL SPECIFICATION. SHOP DRAWING REVIEW IS INTENDED FOR VERIFICATION OF DESIGN CONCEPT CONVEYANCE AND GENERAL CONFORMANCE TO CONTRACT DOCUMENTS ONLY.
2. CHANGES, SUBSTITUTIONS, OR DEVIATIONS FROM CONTRACT DOCUMENTS SHALL BE CLOUDED BY MFR/FABRICATOR. ANY OF THE AFOREMENTIONED WHICH ARE NOT CLOUDED OR FLAGGED BY SUBMITTING PARTIES SHALL NOT BE CONSIDERED APPROVED AFTER ENGINEER'S REVIEW, UNO.
3. SHOP DRAWINGS DO NOT REPLACE THE CONTRACT DOCUMENTS. ITEMS SHOWN INCORRECTLY OR OMITTED BY THE ENGINEER DURING REVIEW ARE NOT TO BE CONSIDERED CHANGES TO THE CONTRACT DOCUMENTS.
4. THE ADEQUACY OF ENGINEERING DESIGNS AND LAYOUT PERFORMED BY OTHERS REISTS WITH THE DESIGNING OR SUBMITTING AUTHORITY. DESIGNED SHOP DRAWINGS SHALL BE PREPARED UNDER THE SUPERVISION OF A LICENSED PROFESSIONAL ENGINEER.
5. SHOP DRAWINGS MUST BE ORIGINAL DOCUMENTS. REPRODUCTION OF ANY PORTION OF THE CONTRACT DOCUMENTS FOR USE IN SUBMITTALS IS NOT PERMITTED AND MAY RESULT IN REJECTION.
6. THE ENGINEER HAS THE RIGHT TO APPROVE OR DISAPPROVE ANY CHANGES TO CONTRACT DOCUMENTS AT ANY TIME BEFORE OR AFTER SHOP DRAWING REVIEW.
7. CONTRACTOR SHALL SUBMIT STRUCTURAL SHOP DRAWINGS FOR THE FOLLOWING:
- CONCRETE MIX DESIGN, MATERIALS, AND TEST REPORTS
  - CONCRETE REINFORCING STEEL, HARDWARE, AND FASTENERS
  - STRUCTURAL STEEL FRAMING
  - ROUGH CARPENTRY HARDWARE, AND FASTENERS
  - ENGINEERED WOOD FRAMING

PLAN LEGENDS



SYMBOLS & ABBREVIATIONS

DETAIL ON SHEET SHEET NUMBER		DETAILS, SECTIONS, AND ELEVATIONS	
T.O.W. = XXX' - XX"		FOUNDATION WALLS AND LEDGES (SIM)	
B.O.W. = XXX' - XX"		LEVELS, SPOT ELEVATIONS & PLAN ELEVATIONS	
T.O.X. XXX' - XX"		SHEET REVISIONS	
ABV	DEFINITION	ABV	DEFINITION
ARCH	ARCHITECT	LLV	LONG LEG VERTICAL
BO	BOTTOM OF	LONG	LONGITUDINAL
BOF	BOTTOM OF FOOTING	MECH	MECHANICAL
BOS	BOTTOM OF STEEL	MEP	MECH. ELECTRICAL, PLUMBING
BOT   B	BOTTOM	MFR	MANUFACTURER
BOW	BOTTOM OF WALL	NA	NOT APPLICABLE
BRG	BEARING	NS	NEAR SIDE
CTR   C	CENTER	NTS	NOT TO SCALE
CGS	CENTER OF GRAVITY STRAND	OC	ON CENTER
CIP	CAST-IN-PLACE	OPP	OPPOSITE
CJ	CONTRACTION/CONTROL JOINT	PAF	POWDER ACTUATED FASTENER
CL	CENTERLINE	PARL	PARALLEL
CLR	CLEAR	PERP	PERPENDICULAR
COL	COLUMN	PI	POST-INSTALLED
CONT	CONTINUOUS	PT	POST-TENSION
DI	DIAMETER	RAD	RADIUS
DT	DRAG TRUSS	REF	REFERENCE
EA	EACH	RTU	ROOF TOP UNIT
EL	ELEVATION	SIM	SIMILAR
EOD	EDGE OF DECK	SOG	SLAB ON GRADE
EOR	ENGINEER OF RECORD	STD	STANDARD
EOS	EDGE OF STEEL	TJ	TOP
EQ	EQUAL	T&B	TOP AND BOTTOM
EW	EACH WAY	TO	TOP OF
EX	EXISTING	TOC	TOP OF CONCRETE
EXT	EXTERIOR	TOD	TOP OF DECK
FS	FAR SIDE	TOF	TOP OF FOOTING
FRT	FIRE RETARDANT TREATED	TOL	TOP OF LEDGE
FV	FIELD VERIFY	TOM	TOP OF MASONRY
GA	GAUGE	TOS	TOP OF STEEL
GC	GENERAL CONTRACTOR	TOW	TOP OF WALL
GT	GIRDER TRUSS	TR	TREATED
HAS	HEADER ANCHOR STUD	TRANS	TRANSVERSE
HORZ	HORIZONTAL	TYP	TYPICAL
INT	INTERIOR	UNO	UNLESS NOTED OTHERWISE
ISO	ISOMETRIC	VERT	VERTICAL
LLH	LONG LEG HORIZONTAL	WP	WORK POINT

SHEET LIST - STRUCTURAL

SHEET NUMBER	SHEET NAME
S100	GENERAL NOTES AND SPECIFICATIONS
S110	SPECIAL INSPECTIONS
S120	SCHEDULES
S130	ROOF LOADING DIAGRAMS
S200	FOUNDATION PLAN
S202	FIRST FLOOR SHEAR WALL PLAN
S210	ROOF FRAMING PLAN
S500	TYPICAL FOUNDATION DETAILS
S501	FOUNDATION DETAILS
S510	TYPICAL STEEL DETAILS
S511	STEEL FRAMING DETAILS
S520	TYPICAL WOOD DETAILS
S521	TYPICAL WOOD DETAILS
S522	WOOD FRAMING DETAILS
S523	WOOD FRAM



INSPECTION TASKS PRIOR TO WELDING		QC	QA
1. WELDING PROCEDURE SPECIFICATIONS (WPSs) AVAILABLE	P	P	P
2. MANUFACTURER CERTIFICATIONS FOR WELDING CONSUMABLES AVAILABLE	P	P	P
3. MATERIAL IDENTIFICATION (TYPE/GRADE)	O	O	O
4. WELDER IDENTIFICATION SYSTEM	O	O	O
5. FIT-UP OF GROOVE WELDS (INCLUDING JOINT GEOMETRY)			
• JOINT PREPARATION			
• DIMENSIONS (ALIGNMENT, ROOT OPENING, ROOT FACE, BEVEL)	O	O	O
• CLEANLINESS (CONDITION OF STEEL SURFACES)			
• TACKING (TACK WELD QUALITY AND LOCATION)			
• BACKING TYPE AND FIT (IF APPLICABLE)			
6. CONFIGURATION AND FINISH OF ACCESS HOLES	O	O	O
7. FIT-UP OF FILLET WELDS			
• DIMENSIONS (ALIGNMENT, GAPS AT ROOT)	O	O	O
• CLEANLINESS (CONDITION OF STEEL SURFACES)			
• TACKING (TACK WELD QUALITY AND LOCATION)			
8. CHECK WELDING EQUIPMENT	O		-
THE FABRICATOR OR ERECTOR, AS APPLICABLE, SHALL MAINTAIN A SYSTEM BY WHICH A RECORD OF WHO HAS WELDED A JOINT OR MEMBER CAN BE IDENTIFIED. STAMPS, IF USED, SHALL BE THE LOW-STRESS TYPE			

AISC TABLE N5.4-2		
INSPECTION TASKS DURING WELDING	QC	QA
1. USE OF QUALIFIED WELDERS	O	O
2. CONTROL AND HANDLING OF WELDING CONSUMABLES		
• PACKAGING	O	O
• EXPOSURE CONTROL		
3. NO WELDING OVER CRACKED TACK WELDS	O	O
4. ENVIRONMENTAL CONDITIONS		
• WIND SPEED WITHIN LIMITS	O	O
• PRECIPITATION AND TEMPERATURE		
5. WPS FOLLOWED		
• SETTINGS ON WELDING EQUIPMENT		
• TRAVEL SPEED		
• SELECTED WELDING MATERIALS		
• SHIELDING GAS TYPE/FLOW RATE	O	O
• PREHEAT APPLIED		
• INTERPASS TEMPERATURE MAINTAINED (MIN./MAX.)		
• PROPER POSITION (F, V, H, OH)		
6. WELDING TECHNIQUES		
• INTERPASS AND FINAL CLEANING		
• EACH PASS WITHIN PROFILE LIMITATIONS	O	O
• EACH PASS MEETS QUALITY REQUIREMENTS		

INSPECTION TASKS AFTER WELDING		QC	QA
1. WELDS CLEANED		O	O
2. SIZE, LENGTH AND LOCATION OF WELDS		P	P
3. WELDS MEET VISUAL ACCEPTANCE CRITERIA			
• CRACK PROHIBITION			
• WELD/BASE-METAL FUSION			
• CRATER CROSS-SECTION			
• WELD PROFILES	P		P
• WELD SIZE			
• UNDERCUT			
• POROSITY			
4. ARC STRIKES		P	P
5. K-AREA <sup>1</sup>		P	P
6. BACKING REMOVED AND WELD TABS REMOVED (IF REQUIRED)		P	P
7. REPAIR ACTIVITIES		P	P
8. DOCUMENT ACCEPTANCE OR REJECTION OF WELDED JOINT OR MEMBER		P	P


<sup>1</sup> WHEN WELDING OF DOUBLER PLATES, CONTINUITY PLATES OR STRENGTHENERS HAS BEEN PERFORMED IN THE K-AREA, VISUALLY INSPECT THE WEB K-AREA FOR CRACKS WITHIN 3 IN. (75 MM) OF THE WELD

INSPECTION TASKS PRIOR TO BOLTING		QC	QA
1. MANUFACTURER'S CERTIFICATIONS AVAILABLE FOR FASTENER MATERIALS	O	P	
2. FASTENERS MARKED IN ACCORDANCE WITH ASTM REQUIREMENTS	O	O	
3. PROPER FASTENERS SELECTED FOR THE JOINT DETAIL (GRADE, TYPE, BOLT LENGTH IF THREADS ARE TO BE EXCLUDED FROM SHEAR PLANE)			O
4. PROPER BOLTING PROCEDURE SELECTED FOR JOINT DETAIL	O	O	
5. CONNECTING ELEMENTS, INCLUDING THE APPROPRIATE FAYING SURFACE CONDITION AND HOLE PREPARATION, IF SPECIFIED, MEET APPLICABLE REQUIREMENTS	O	O	
6. PRE-INSTALLATION VERIFICATION TESTING BY INSTALLATION PERSONNEL TO BE DOCUMENTED FOR FASTENER ASSEMBLIES AND METHODS USED	P		
7. PROPER STORAGE PROVIDED FOR BOLTS, NUTS, WASHERS AND OTHER FASTENER COMPONENTS	O	O	


AISC TABLE N5.6-2			
INSPECTION TASKS DURING BOLTING		QC	QA
1. FASTENER ASSEMBLIES, OF SUITABLE CONDITION, PLACED IN ALL HOLES AND WASHERS (IF REQUIRED) ARE POSITIONED AS REQUIRED		○	○
2. JOINT BROUGHT TO THE SNUG-TIGHT CONDITION PRIOR TO THE PRETENSIONING OPERATION		○	○
3. FASTENER COMPONENT NOT TURNED BY THE WRENCH PREVENTED FROM ROTATING		○	○
FASTENERS ARE PRETENSIONED IN ACCORDANCE WITH THE RCSC SPECIFICATION, PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID POINT TOWARD THE FREE EDGES		○	○

AISC TABLE N5.6-3		
INSPECTION TASKS AFTER BOLTING	QC	QA
1. DOCUMENT ACCEPTANCE OR REJECTION OF BOLTED CONNECTIONS	P	P

STATEMENT OF SPECIAL INSPECTION			
IBC CODE REFERENCE	CONSTRUCTION TYPE	FREQUENCY CONT. PER.	
1705.2	STEEL CONSTRUCTION		
1705.2.1	STRUCTURAL STEEL		
1. SPECIAL INSPECTION FOR STRUCTURAL STEEL SHALL BE IN ACCORDANCE WITH THE QUALITY ASSURANCE INSPECTION REQUIREMENTS OF AISC 360. (REFER TO AISC CHARTS ON THIS SHEET)			
1705.3	REINFORCED CONCRETE		
1. INSPECTION OF REINFORCING STEEL, INCLUDING PRESTRESSING TENDONS, AND ELEMENT.			X
2. INSPECTION OF REINFORCING STEEL WELDING:			
A. VERIFICATION OF WELDABILITY OF REINFORCING STEEL OTHER THAN ASTM A 706.			X
B. INSPECT SINGLE-PASS FILL WELDS, MAXIMUM 5/16"			X
C. INSPECT ALL OTHER WELDS		X	
3. INSPECTION OF ANCHORS CAST IN CONCRETE:			X
4. INSPECTION OF ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS.			
A. ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST TENSIONED LOADS.		X	
B. MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED IN 4 A			X
5. VERIFYING USE OF REQUIRED MIX DESIGN			X
6. PRIOR TO CONCRETE PLACEMENT, FABRICATE SAMPLES FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND DETERMINE THE TEMPERATURE OF THE CONCRETE.		X	
7. INSPECTION OF CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES.		X	
8. VERIFY MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND DURABLE.			X
9. INSPECTION OF PRESTRESSED CONCRETE:			
A. APPLICATION OF PRESTRESSING FORCES.		X	
B. GROUTING OF BONDED PRESTRESSING TENDONS IN THE SEISMIC-FORCE-RESISTING SYSTEM.		X	
10. ERECTION OF PRECAST CONCRETE MEMBERS.			X
11. VERIFICATION OF IN-SITU CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN POST-TENSIONED CONCRETE AND PRIOR TO REMOVAL OF SHORING.			X
12. INSPECT FORMWORK FOR SHAPE, LOCATION AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED.			X
SPECIAL INSPECTION AGENCY TO PERFORM TESTS AT SEVEN (7) DAYS AND AT TWENTY EIGHT (28) DAYS. A STRENGTH TEST SHALL BE THE AVERAGE OF THE STRENGTHS OF AT LEAST TWO (2) 6"X12" CYLINDERS OR AT LEAST THREE (3) 6"X6" CYLINDERS MADE FROM THE SAME SAMPLE OF CONCRETE. HOLD ONE ADDITIONAL CYLINDER IN RESERVE UNTIL PROJECT IS COMPLETED. TESTING LABORATORY IS TO FURNISH ARCHITECT/ENGINEER WITH TEST RESULTS PROMPTLY.			
FREQUENCY OF TESTING IS TO BE IN ACCORDANCE WITH ACI 318:			
A. AT LEAST ONCE EACH DAY A GIVEN CLASS IS PLACED			
B. AT LEAST ONCE FOR EACH 150 CUBIC YDS OF EACH CLASS PLACED			
C. AT LEAST ONCE FOR EACH 5000 SQFT OF SLAB WALL OR SURFACE AREA PLACED EACH DAY.			
1705.5	WOOD CONSTRUCTION		
1. HIGH-LOAD DIAPHRAGMS:			
A. THE WOOD STRUCTURAL PANEL SHEATHING TO ASCERTAIN WHETHER IT IS OF THE GRADE AND THICKNESS SHOWN ON THE APPROVED BUILDING PLANS.			X
B. NOMINAL SIZE OF FRAMING MEMBERS AT ADJOINING PANEL EDGES.			X
C. NAIL OR STAPLE DIAMETER AND LENGTH, THE NUMBER OF FASTENER LINES AND THAT THE SPACING BETWEEN FASTENERS IN EACH LINE AND AT EDGE MARGINS AGREES WITH THE APPROVED BUILDING PLANS.			X
2. SHEAR WALLS AND BEARING WALLS			
A. GRADE AND THICKNESS OF WOOD STRUCTURAL PANELS.			X
B. NOMINAL SIZE OF FRAMING MEMBERS AT ADJOINING PANEL EDGES.			X
C. NAIL OR STAPLE DIAMETER AND LENGTH, THE NUMBER OF FASTENER LINES AND THAT THE SPACING BETWEEN FASTENERS IN EACH LINE AND AT EDGE CONDITIONS.			X
D. VERIFY THE TYPE, CONNECTION, AND ANCHORAGE OF HOLD-DOWNS.			X
E. PROPRIETARY COMPONENTS INSTALLED PER MANUFACTURER SPECIFICATIONS.			X
F. VERIFY BLOCKING INSTALLATION AT PANEL EDGES.			X
G. GRADE AND NOMINAL SIZE OF CHORD STUDS.			X
3. DIAPHRAGMS AND FLOOR FRAMING			
A. VERIFY THE SIZE AND SPACING BETWEEN BOLTS, LAG SCREWS, AND FRAMING ANCHORS.			X
B. VERIFY CONNECTION OF DIAPHRAGMS TO SHEAR WALLS.			X
C. DIAPHRAGM BLOCKING PLACEMENT AND INSTALLATION.			X
D. DRAG TRUSS AND DRAG STRUT PLACEMENT AND CONNECTIONS.			X
E. SPLICE CONNECTIONS, SHEAR TRANSFER CLIPS, AND TRANSITION CONNECTIONS BETWEEN FLOOR.			X
F. PROPRIETARY COMPONENTS INSTALLED PER MANUFACTURER SPECIFICATIONS.			X
4. GENERAL WOOD FRAMING			
A. VERIFY THE SIZE AND SPACING BETWEEN BOLTS, LAG SCREWS, AND FRAMING ANCHORS.			X
B. NAIL OR STAPLE DIAMETER AND LENGTH, THE NUMBER OF FASTENER LINES AND SPACING FOR BUILT UP WOOD MEMBERS.			X
C. JAMB AND SILL FRAMING.			X
D. ATTACHMENT AT BEAM BEARING LOCATIONS.			X
E. PROPRIETARY COMPONENTS INSTALLED PER MANUFACTURER SPECIFICATIONS.			X
F. CUTTING, NOTCHING, OR DRILLING COMPLY WITH PLAN SPECIFICATIONS. VERIFY SIZE, LOCATION, AND SHAPE DO NOT EXCEED LIMITS IN FRAMING DETAILS AND WOOD SHRINKAGE DIAGRAM RECOMMENDATIONS.			X
1705.6	SOILS		
1. VERIFY MATERIALS BELOW SHALLOWN FOUNDATIONS ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY.			X
2. VERIFY EXCAVATIONS ARE EXCAVED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL.			X
3. PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS.			X
4. VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL MATERIALS.		X	
5. PRIOR TO PLACEMENT OF COMPACTED FILL, OBSERVE SUBGRADE AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY.			



**GUY GRONBERG  
ARCHITECTS, P.C.**  
113 SE 3rd St.  
Lee's Summit, MO 64063  
Phone 816.524.0878  
Fax 816.524.8578



1625 LOCUST ST.  
KANSAS CITY, MO 64108  
816.421.3222  
816.421.1050  
[www.apex-engineers.com](http://www.apex-engineers.com)

DOUGLAS  
CORNER

LOT 1B, LEES SUMMIT, MISSOURI 64086

This drawing has been provided as an instrument of service by the architect or under his supervision and is intended for use on this project only. Pursuant to the Architectural Rules Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Architect. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Architect is strictly prohibited.

**© COPYRIGHT 2018 GUY GRONBERG ARCHITECTS.**

[illegible]

# S110



SCHEDULE - SHEAR WALLS									
NOTES: 1. WSP = WOOD STRUCTURAL PANEL PLYWOOD OR OSB. 2. NAIL SIZES GIVEN ARE FOR COMMON NAILS OR GALVANIZED (HOT-DIPPED OR TUMBLE) BOX NAILS. SINKER NAILS, COOLER NAILS, ETC. SHALL NOT BE USED FOR WSP SHEAR WALLS. 3. SHEAR WALL NAILS SHALL HAVE FULL HEADS, CLIPPED NAILS ARE NOT ALLOWED. 4. ALL NAILS SHALL BE DRIVEN SUCH THAT THE HEAD IS FLUSH WITH FACE OF SHEATHING. DO NOT OVERDRIVE NAILS. 5. SLEEPLATE NAILS SHALL BE INSTALLED SUCH THAT THE NAILS FULLY ENGAGE THE RIM BOARD BELOW (IF APPLICABLE). REF TYP DETAILS. 6. PROVIDE INTERMEDIATE NAILING (FIELD) AT 12" OC, TYP. 7. PROVIDE (2) TOTAL RIMBOARDS OR A LAYER OF BLOCKING IN ADDITION TO THE RIMBOARD WHERE SOLE PLATE NAILING REQUIRES 2 ROWS OF FASTENERS PER SCHEDULE. 8. SILL ANCHORS MAY BE CAST-IN-PLACE J-BOLTS WITH 8" EMBED OR SIMPSON TITEN HD SCREW ANCHORS WITH 6" EMBED. REF SCHEDULE FOR BOLT DIA. BOTH BOLT TYPES REQUIRE 0.229"x3"x3" PLATE WASHER WITH EDGE OF PLATE LOCATED WITHIN 1/2" OF SHEAR WALL SHEATHING. 9. SHEAR WALL CLIPS TO BE A308LTP4, REF PLAN FOR NUMBER OF CLIPS PER SHEAR WALL. 48" OC MAX UNO. 10. AT WALLS DESIGNATED AS FORCE TRANSFER SHEAR WALLS, PROVIDE SIMPSON STRAP ABOVE AND BELOW ALL OPENINGS PER SHEAR WALL DETAIL. 11. END STUDS MUST CONTINUE DOWN TO FOUNDATION WALL UNLESS INTERRUPTED BY TRANSFER BEAM. 12. JACK STUDS FOR OPENINGS DO NOT COUNT TOWARDS THE REQUIRED NUMBER OF END STUDS IN A SHEAR WALL. 13. PROVIDE DOUBLE STUDS AND BLOCKING NAILED TOGETHER WITH (2) 16d NAILS AT 6" OC OR 3" NOMINAL STUDS AND BLOCKING AT THE FOLLOWING CONDITIONS: i. 2" OC EDGE NAIL SPACING ii. 10d NAILS AT 3" OC OR SMALLER EDGE NAIL SPACING iii. DOUBLE SIDED SHEAR WALL WHERE PANEL JOINTS ALIGN TO THE SAME STUD. 14. HOLDDOWNS AND STRAPS OCCUR AT THE BOT OF WALLS. HOLDDOWNS AND STRAPS BETWEEN FLOORS ARE CONTROLLED BY THE WALL ABOVE. 15. HOLDDOWN DEVICES SHALL BE INSTALLED PER MFR SPECIFICATIONS 16. REF SHEAR WALL DETAILS FOR ADDITIONAL INFORMATION AND REQUIREMENTS									
MARK	BLOCKED	SHEATHING		EDGE NAILS	SILL PLATE ATTACHMENT				
		TYPE	THICKNESS	PLACEMENT	SIZE	SPACING	NAILING	1/2" DIA ANCHOR BOLT	
S2-B	YES	WSP-SHEATHING	15/32"	ONE-SIDE	10d	4"	16d AT 4" OC	16"	
S3-B	YES	WSP-SHEATHING	15/32"	ONE-SIDE	10d	3"	16d AT 3" OC STAGGERED	12"	

SCHEDULE - HEADERS			
NOTES: 1. JAMB AND SILL STUDS TO MATCH TYPICAL WALL STUDS UNO.			
MARK	HEADER	COMMENTS	
H2-9.25	(2) 1½"x9½" LVL		
H2-10	(2) 2x10		
H2-11	(2) 1½"x11½" LVL		
H3-10	(3) 2x10		


SCHEDULE - BEAMS		
MARK	BEAM SIZE	COMMENTS
B1	C6X8.2	COORDINATE PLACEMENT WITH CANOPY ROD ATTACHMENT
B2	(1) 2x8+(1) 2x12	2x12 FORMING CANOPY CURB

SCHEDULE - JOISTS			
MARK	JOISTS	SPACING	COMMENTS
J1	2x8	16"	


SCHEDULE - TRUSSES			
MARK	TRUSSES	SPACING	COMMENTS
T1	ROOF TRUSS	24"	COORDINATE PLACEMENT WITH CANOPY ROD ATTACHMENT

SCHEDULE - ROOF SHEATHINGS				
MARK	SHEATHING TYPE	SUPPORT ATTACHMENT (EDGE / FIELD)	BLOCKED	
ROOF	5/8" (NOMINAL) APA RATED SHEATHING, EXPOSURE 1, 48/24 SPAN RATING	10d [6" OC / 12" OC]	No	

SCHEDULE - BASE PLATES					
NOTES: 1. PROVIDE 5/16" FILLET WELD AT COLUMN TO BASE PLATE CONNECTION. 2. CAST-IN PLACE ANCHORS TO BE HEX-HEAD ASTM F1554 (65 KSI) UNO. 3. POST INSTALLED EPOXY ANCHORS TO BE THREADED ROD INSTALLED IN EPOXY PER MATERIAL SPECIFICATIONS. UNO. 4. POST INSTALLED HILTI HUS-EZ ANCHORS TO BE INSTALLED PER MFR SPECIFICATIONS. 5. BASE PLATE WITH LESS THAN (4) ANCHORS REQUIRE COLUMNS BE DESIGNATED AS POSTS AND SHALL BE TEMPORARILY BRACED DURING ERECTION PER OSHA PART 1926, BY OTHERS. BRACING MAY BE REMOVED ONCE ATTACHMENTS TO MAIN STRUCTURE ARE COMPLETE. 6. MAX SIZES OF ANCHOR ROD HOLES IN BASE PLATES SHALL FOLLOW TABLE 14-2 OF THE AISC MANUAL. AN ADEQUATE WASHER SHOULD BE PROVIDED FOR EA ANCHOR ROD. 7. PLATE WASHERS MUST BE WELDED TO THE BASE PLATE AT SHEAR TRANSFER CONDITIONS (I.E. MOMENT FRAME AND BRACED FRAME COLUMNS). PROVIDE 1/4" FILLET WELD ALL AROUND. D = VARIES, COORDINATED WITH BEAM FLANGE WIDTH W = WIDTH OF BEAM FLANGE					
TYPE	PLATE SHAPE	PLATE THICKNESS	BOLT DIAMETER	ANCHOR BOLT EMBED	
				CAST-IN-PLACE (HEX-HEAD)	POST-INSTALLED / BOLT TYPE
BP-1	A	1"	3/4"	8	8"
BP-2	B	5/8"	1/2"	8	8"
BP-3	E	3/4"	7/8"	8	8"



SCHEDULE - CAP PLATES			
NOTES: 1. BOLT SIZE NOTE: FOR BEAMS WITH A FLANGE WIDTH LESS THAN 5", 5/8" BOLTS MAY BE USED FOR DETAILING TOLERANCES. 2. W = WIDTH OF BEAM FLANGE. 3. D = VARIES, COORDINATE WITH BEAM FLANGE WIDTH. 4. W = JOIST GIRDER SEAT WIDTH PLUS 1" FOR FILLET WELD CONNECTION. VERIFY SEAT WIDTH WITH JOIST SUPPLIER PRIOR TO FABRICATION. 5. VERIFY BOLT PLACEMENT WITH JOIST SUPPLIER.			
PLATE TYPE	SHAPE	PLATE THICKNESS	BOLT SIZE
A	1	1/4"	3/4"
B	2	1/4"	3/4"



SCHEDULE - CONTINUOUS FOOTINGS				
MARK	WIDTH	DEPTH	LONG BARS	TRANS BARS
CF16	1' - 4"	36"	(4) #5 BARS (2) AT T&B	#3 TIES AT 18" OC

SCHEDULE - PAD FOOTINGS				
MARK	LENGTH	WIDTH	DEPTH	REINFORCING
F42	3' - 6"	3' - 6"	36"	(10) #5 BARS EACH WAY (15) AT T&B
F54	4' - 6"	4' - 6"	12"	(6) #5 BARS EACH WAY
F54-F	4' - 6"	4' - 6"	36"	(12) #5 BARS EACH WAY (16) AT T&B

SCHEDULE - SLABS ON GRADE				
NOTES: 1. PROVIDE CONTROL JOINTS (1/4 SLAB THICKNESS) SPACED AT 30xSLAB THICKNESS OC BOTH WAYS, NOT SHOWN FOR CLARITY.				
MARK	SLAB THICKNESS	WEIGHT CLASS	SLAB REINFORCING	ADDITIONAL REQUIREMENTS
SG4	4"	NW	#3 AT 18" OC (C) EA WAY OR 6X6 W2.9XW2.9 WWF	15 MIL VAPOR BARRIER ON 4" OF 3/4" CLEAN, GRADED ROD

SCHEDULE - WOOD WALLS			
NOTES: 1. WALL SOLE PLATE ATTACHMENT, UNO: 1/2" DIA CAST-IN-PLACE ANCHORS WITH 7" EMBED AT 32" OC ATTACHMENT TO CONCRETE OR (2) ROWS OF 16d NAILS AT 16" OC STAGGERED WHEN FASTENING TO WOOD. 2. TYPICAL WALL SHEATHING, UNO: 15/32" APA RATED WSP, EXP. 1, 24/16 SPAN RATING. PANEL EDGES FASTENED WITH 8d NAILS AT 6" OC EDGE AND 12" OC IN THE FIELD. 3. REFERENCE SHEAR WALL SCHEDULE FOR ADDITIONAL NAILING REQUIREMENTS. ** = LATERAL CLIPS REQUIRED; PROVIDE SIMPSON A35 CLIP AT EACH STUD ABOVE HEADER, REFERENCE TYPICAL DETAILS FOR CLIP LOCATION.			
MARK	MATERIAL	WALL STUDS	BLOCKING
DFL6	DF-L No. 2	2x6 AT 16"	AT SHEATHING PANEL EDGES (4'-0" OC MAX)
DFL6-2	DF-L No. 2	2x6 AT 16"	AT SHEATHING PANEL EDGES (4'-0" OC MAX)

SCHEDULE - WOOD HANGERS			
NOTES: 1. ALL HANGERS ARE SIMPSON PRODUCTS UNO. 2. ALL EXTERIOR HANGERS TO BE ZMAX OR GALVANIZED. 3. INSTALL ALL HANGERS PER MANUFACTURERS RECOMMENDATIONS. 4. AT ROOF AND DECK LOCATIONS, USE FACEMOUNT HANGERS UNO. 5. USE SCHEDULE UNO ON PLAN. 6. WHERE FACE-MOUNT HANGER HEADER/FACE FASTENER LENGTH IS GREATER THAN THICKNESS OF SUPPORT MEMBER, FASTENER MUST BE SUBSTITUTED RESPECTIVELY: 0.148" x 3" TO 0.148" x 2 1/2", 0.162" x 3 1/2" TO 0.162" x 2 1/2" PER SIMPSON MANUFACTURER REQUIREMENTS. EOR SHOULD BE NOTIFIED IF OTHER CONDITIONS EXISTS			
BEAM	FACE MOUNT HANGER	TOP FLANGE HANGER	CONCEALED HANGER
2x12	LUS210	LB212AZ	N/A
2x4 Kickers	LUS4	LB24	N/A
(1) 2x8+(1) 2x12	LUS28	LB28	N/A
2x8	LUS28	LB28	N/A

SCHEDULE - WOOD FASTENING			
IBC TABLE 2304.10.1			
DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENER	SPACING AND LOCATION	
		EDGE	FIELD
WOOD STRUCTURAL PANELS (WSP), SUBFLOOR, ROOF AND INTERIOR WALL SHEATHING TO FRAMING AND PARTICLEBOARD WALL SHEATHING TO FRAMING*			
30. 3/8" - 1/2"	6d COMMON OR DEFORMED (2"x0.113") (SUBFLOOR AND WALL)	6"	12"
	8d COMMON OR DEFORMED (2-1/2"x0.131"x0.281" HEAD) (ROOF) OR RSRS-01 (2-3/8"x0.113") NAIL (ROOF)	6"	12"
	1-3/4" 16 GAGE STAPLE, 7/16" CROWN (SUBFLOOR AND WALL) 2-3/8"x0.113"x0.266" HEAD NAIL (ROOF) 1-3/4" 16 GAGE STAPLE, 7/16" CROWN (ROOF)	4" 3" 3"	8" 3" 3"
31. 19/32" - 3/4"	8d COMMON (2-1/2"x0.131"); OR 6d DEFORMED (2"x0.113") (SUBFLOOR AND WALL)	6"	12"
	8d COMMON OR DEFORMED (2-1/2"x0.131"x0.281" HEAD) (ROOF) OR RSRS-01 (2-3/8"x0.113") NAIL (ROOF)	6"	6"
	2-3/8"x0.113" NAIL OR 2" 16 GAGE STAPLE, 7/16" CROWN	4"	8"
32. 7/8" - 1-1/4"	10d COMMON (3"x0.148"); OR 8d DEFORMED (2-1/2"x0.131"x0.281" HEAD)	6"	12"
OTHER EXTERIOR WALL SHEATHING			
33. 1/2" FIBERBOARD SHEATHING	1-1/2"x0.120" GALVANIZED ROOFING NAIL (7/16" HEAD DIAMETER)	3"	6"
34. 25/32" FIBERBOARD SHEATHING	1-3/4"x0.120" GALVANIZED ROOFING NAIL (7/16" HEAD DIAMETER)	3"	6"
WOOD STRUCTURAL PANELS, COMBINATION SUBFLOOR UNDERLAYMENT TO FRAMING			
35. 3/4" AND LESS	8d COMMON (2-1/2"x0.131"); OR 6d DEFORMED (2"x0.113")	6"	12"
36. 7/8" - 1"	8d COMMON (2-1/2"x0.131"); OR 6d DEFORMED (2"x0.113")	6"	12"
37. 1-1/8" - 1-1/4"	10d COMMON (3"x0.148"); OR 8d DEFORMED (2-1/2"x0.131")	6"	12"
PANEL SIDING TO FRAMING			
38. 1/2" OR LESS	8d CORROSION-RESISTANT SIDING (1-7/8"x0.106"); OR 8d CORROSION-RESISTANT CASING (2"x0.099")	6"	12"
39. 5/8"	8d CORROSION-RESISTANT SIDING (2-3/8"x0.128"); OR 8d CORROSION-RESISTANT CASING (2-1/2"x0.113")	6"	12"
INTERIOR PANELING			
40. 1/4"	4d CASING (1-1/2"x0.080"); OR 4d FINISH (1-1/2"x0.072)	6"	12"
41. 3/8"	6d CASING (2"x0.099"); OR 6d FINISH (PANEL SUPPORTS AT 24 INCHES)	6"	12"

- NOTES:  
A. NAILS SPACED AT 6 INCHES AT INTERMEDIATE SUPPORTS WHERE SPANS ARE 48 INCHES OR MORE. FOR NAILING OF WOOD STRUCTURAL PANEL AND PARTICLEBOARD DIAPHRAGMS AND SHEAR WALLS, REFER TO IBC SECTION 2305. NAILS FOR WALL SHEATHING ARE PERMITTED TO BE COMMON, BOX OR CASING.  
B. SPACING SHALL BE 6 INCHES ON CENTER ON THE EDGES AND 12 INCHES ON CENTER AT INTERMEDIATE SUPPORTS FOR NONSTRUCTURAL APPLICATIONS. PANEL SUPPORTS AT 16 INCHES (20 INCHES IF STRENGTH AXIS IN THE LONG DIRECTION OF THE PANEL, UNLESS OTHERWISE MARKED).  
C. WHERE A RAFTER IS FASTENED TO AN ADJACENT PARALLEL CEILING JOIST IN ACCORDANCE WITH THIS SCHEDULE AND THE CEILING JOIST IS FASTENED TO THE TOP PLATE IN ACCORDANCE WITH THIS SCHEDULE, THE NUMBER OF TOENAILS IN THE RAFTER SHALL BE PERMITTED TO BE REDUCED BY ONE NAIL.  
D. RSRS-01 IS A ROOF SHEATHING RING SHANK NAIL MEETING THE SPECIFICATIONS IN ASTM F1667.  
E. TABULATED FASTENER REQUIREMENTS APPLY WHERE THE ULTIMATE DESIGN WIND SPEED IS LESS THAN 140 MPH. FOR WOOD STRUCTURAL PANEL ROOF SHEATHING ATTACHED TO GABLE-END ROOF FRAMING AND TO INTERMEDIATE SUPPORTS WITHIN 48 INCHES OF ROOF EDGES AND RIDGES, WALLS SHALL BE SPACED AT 4 INCHES ON CENTER WHERE THE ULTIMATE DESIGN WIND SPEED IS GREATER THAN 130 MPH IN EXPOSURE B OR GREATER THAN 110 MPH IN EXPOSURE C. SPACING EXCEEDING 6 INCHES ON CENTER AT INTERMEDIATE SUPPORTS SHALL BE PERMITTED WHERE THE FASTENING IS DESIGNED PER THE AISC NDS.  
F. FASTENING IS ONLY PERMITTED WHERE THE ULTIMATE DESIGN WIND SPEED IS LESS THAN OR EQUAL TO 110 MPH.  
G. NAILS AND STAPLES ARE CARBON STEEL MEETING THE SPECIFICATIONS OF ASTM F1667. CONNECTIONS USING NAILS AND STAPLES OF OTHER MATERIALS, SUCH AS STAINLESS STEEL, SHALL BE DESIGNED BY ACCEPTABLE ENGINEERING PRACTICE OR APPROVED UNDER SECTION 104.11.

SCHEDULE - HOLDDOWNS			
NOTES: 1. EMBEDMENT DEPTH IS FROM TOP OF FOOTING. INCREASE ANCHOR LENGTH AS REQUIRED FOR SLAB THICKNESS. 2. FOR HDU14 OR GREATER USE HEAVY HEX NUT. 3. HD19 REQUIRES DF END STUDS AND 10d EMBED PLATE. 4. GC TO VERIFY LOCATION OF ANCHOR BOLTS PRIOR TO FOUNDATION WALL REBAR INSPECTION. 5. ALL HOLDDOWNS ARE SIMPSON PRODUCTS UNO. 6. FOR POST-INSTALLED ANCHORS REF MATERIAL SPECIFICATIONS FOR EPOXY AND ANCHOR ROD REQUIREMENTS.			
MARK	HOLDDOWN	ANCHOR BOLT DIAMETER	MIN EMBEDMENT
HDU2	HDU2-SDS2.5	5/8"	5"
HDU5	HDU5-SDS2.5	5/8"	5"
HDU8	HDU8-SDS2.5	7/8"	7"
HDU11	HDU11-SDS2.5	1"	9"
HDU14	HDU14-SDS2.5	1"	11"
HD19	HD19 <sup>1</sup>	1 1/4"	HDEP #1

SCHEDULE - WOOD FASTENING		
IBC TABLE 2304.10.1		
DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENER	SPACING AND LOCATION
ROOF		
1. BLOCKING BETWEEN CEILING JOISTS, RAFTERS OR TRUSSES TO TOP PLATE OR OTHER FRAMING BELOW.	(3) 8d COMMON (2-1/2"x0.131"); OR (3) 10d BOX (3"x0.128")	EA END, TOENAIL
2. BLOCKING BETWEEN RAFTERS OR TRUSS NOT AT THE WALL TOP PLATE TO RAFTER OR TRUSS.	(2) 8d COMMON (2-1/2"x0.131")	EA END, TOENAIL
	(2) 16d COMMON (3-1/2"x0.162")	END NAIL
3. FLAT BLOCKING TO TRUSS AND WEB FILLER	16d COMMON (3-1/2"x0.162") AT 6" OC	FACE NAIL
2. CEILING JOIST TO TOP PLATE	(3) 8d COMMON (2-1/2"x0.131"); OR (3) 10d BOX (3"x0.128")	EA JOIST, TOENAIL
3. CEILING JOIST NOT ATTACHED TO PARALLEL RAFTER, LAPS OVER PARTITIONS (NO THRUST)	(3) 16d COMMON (3-1/2"x0.162"); OR (4) 10d BOX (3"x0.128")	FACE NAIL
4. CEILING JOIST ATTACHED TO PARALLEL RAFTER (HEEL JOINT)	PER IBC TABLE 2308.7.3.1	FACE NAIL
5. COLLAR TIE TO RAFTER	(3) 10d COMMON (3"x0.148"); OR (4) 10d BOX (3"x0.128")	FACE NAIL
6. RAFTER OR ROOF TRUSS TO TOP PLATE	(3) 10d COMMON (3"x0.148"); OR (3) 16d BOX (3-1/2"x0.135"); OR (4) 10d BOX (3"x0.128")	(2) TOENAILS ONE SIDE AND (1) TOENAIL OPP SIDE
7. ROOF RAFTERS TO RIDGE VALLEY OR HIP RAFTERS, OR ROOF RAFTER TO 2" RIDGE BEAM	(2) 16d COMMON (3-1/2"x0.162"); OR (3) 10d BOX (3"x0.128") (3) 10d COMMON (3"x0.148"); OR (4) 16d BOX (3-1/2"x0.135"); OR (4) 10d BOX (3"x0.128")	END NAIL  TOENAIL
WALL		
8. STUD TO STUD (NOT AT BRACED WALL PANELS)	16d COMMON (2-1/2"x0.162"); OR 10d BOX (3"x0.128")	24" OC, FACE NAIL 16" OC, FACE NAIL
9. STUD TO STUD AND ABUTTING STUDS AT INTERSECTION WALL CORNERS (AT BRACED WALL PANELS)	16d COMMON (3-1/2"x0.162")  16d BOX (3-1/2"x0.135")	16" OC, FACE NAIL  12" OC, FACE NAIL
10. BUILT-UP HEADER (2" TO 2" HEADER)	16d COMMON (3-1/2"x0.162")  16d BOX (3-1/2"x0.135")	16" OC EA EDGE, FACE NAIL  12" OC EA EDGE, FACE NAIL
11. CONTINUOUS HEADER TO STUD	(4) 8d COMMON (2-1/2"x0.131"); OR (4) 10d BOX (3"x0.128")	TOENAIL
12. TOP PLATE TO TOP PLATE	16d COMMON (3-1/2"x0.162")  10d BOX (3"x0.128")	16" OC FACE NAIL 12" OC FACE NAIL
13. TOP PLATE TO TOP PLATE, AT END JOINTS	(8) 16d COMMON (3-1/2"x0.162"); OR (12) 10d BOX (3"x0.128")	EA SIDE OF END JOINT, FACE NAIL, MIN 24" LAP SPUCE LENGTH EA SIDE OF END JOINT
14. BOTTOM PLATE TO JOIST, RIM JOIST, BAND JOIST OR BLOCKING (NOT AT BRACED WALL PANELS)	16d COMMON (3-1/2"x0.162")  16d BOX (3-1/2"x0.135")	16" OC FACE NAIL 12" OC FACE NAIL
15. BOTTOM PLATE TO JOIST, RIM JOIST, BAND JOIST OR BLOCKING AT BRACED WALL PANELS	(2) 16d COMMON (3-1/2"x0.162"); OR (3) 16d BOX (3-1/2"x0.135")	16" OC FACE NAIL
16. STUD TO TOP OR BOTTOM PLATE	(4) 8d COMMON (2-1/2"x0.131"); OR (4) 10d BOX (3"x0.128"); OR (2) 16d COMMON (3-1/2"x0.162"); OR (3) 10d BOX (3"x0.128")	TOENAIL  END NAIL
17. TOP PLATE, LAPS AT CORNERS AND INTERSECTIONS	(2) 16d COMMON (3-1/2"x0.162"); OR (3) 10d BOX (3"x0.128")	FACE NAIL
18. 1" BRACE TO EA STUD AND PLATE	(2) 8d COMMON (2-1/2"x0.131"); OR (2) 10d BOX (3"x0.128")	FACE NAIL
19. 1"x6" SHEATHING TO EA BEARING	(2) 8d COMMON (2-1/2"x0.131"); OR (2) 10d BOX (3"x0.128")	FACE NAIL
20. 1"x8" AND WIDER SHEATHING TO EA BEARING	(3) 8d COMMON (2-1/2"x0.131"); OR (3) 10d BOX (3"x0.128")	FACE NAIL
FLOOR		
21. JOIST TO SILL, TOP PLATE, OR GIRDER	(3) 8d COMMON (2-1/2"x0.131"); OR (3) 10d BOX (3"x0.128")	TOENAIL
22. RIM JOIST, BAND JOIST, OR BLOCKING TO TOP PLATE, SILL OR OTHER FRAMING BELOW	8d COMMON (2-1/2"x0.131"); OR 10d BOX (3"x0.128")	6" OC, TOENAIL
23. 1"x6" SUBFLOOR OR LESS TO EA JOIST	(2) 8d COMMON (2-1/2"x0.131"); OR (3) 10d BOX (3"x0.128")	FACE NAIL
24. 2" SUBFLOOR TO JOIST OR GIRDER	(2) 16d COMMON (3-1/2"x0.162")	FACE NAIL
25. 2" PLANKS (PLANK & BEAM-FLOOR & ROOF)	(2) 16d COMMON (3-1/2"x0.162")	EA BEARING, FACE NAIL
26. BUILT-UP GRIDDERS AND BEAM, 2" LUMBER LAYERS	20d COMMON (4"x0.192")  10d BOX (3"x0.128")	32" OC, FACE NAIL AT TOP AND BOTTOM STAGGERED ON OPPOSITE SIDES  24" OC FACE NAIL AT TOP AND BOTTOM STAGGERED ON OPPOSITE SIDES
	AND: (2) 20d COMMON (4"x0.192"); OR (3) 10d BOX (3"x0.128")	ENDS AND AT EA SPLICE, FACE NAIL
27. LEDGER STRIP SUPPORTING JOISTS OR RAFTERS	(3) 16d COMMON (3-1/2"x0.162"); OR (4) 10d BOX (3"x0.128")	EA JOIST OR RAFTER, FACE NAIL
28. JOIST TO BAND JOIST OR RIM JOIST	(3) 16d COMMON (3-1/2"x0.162"); OR (4) 10d BOX (3"x0.128")	END NAIL
29. BRIDGING OR BLOCKING TO JOIST, RAFTER, OR TRUSS	(2) 8d COMMON (2-1/2"x0.131"); OR (2) 10d BOX (3"x0.128")	EA END, TOENAIL

SCHEDULE - CONCRETE REBAR											
DEVELOPMENT LENGTHS - L <sub>de</sub>											
f' <sub>c</sub> = 3000 PSI						f' <sub>c</sub> = 4000 PSI					
BAR SIZE	STD. L <sub>de</sub>	CLASS B	BAR SIZE	STD. L <sub>de</sub>	CLASS B	BAR SIZE	STD. L <sub>de</sub>	CLASS B	BAR SIZE	STD. L <sub>de</sub>	CLASS B
TYP.	TYP.	TYP.	TYP.	TYP.	TYP.	TYP.	TYP.	TYP.	TYP.	TYP.	TYP.
#3	17"	22"	22"	28"	#3	15"	19"	19"	25"	25"	33"
#4	22"	29"	29"	38"	#4	19"	25"	25"	33"	33"	41"
#5	28"	36"	37"	47"	#5	24"	31"	31"	41"	41"	49"
#6	33"	43"	43"	56"	#6	29"	37"	37"	49"	49"	57"
#7	48"	63"	63"	82"	#7	42"	54"	54"	71"	71"	79"
#8	55"	72"	72"	94"	#8	48"	62"	62"	81"	81"	89"
#9	62"	81"	81"	106"	#9	54"	70"	70"	91"	91"	99"
STANDARD HOOKS & BAR BENDS											
BAR SIZE	L <sub>de</sub>	180° HOOK		90° HOOK		180° HOOK		90° HOOK		180° HOOK	







instrument of service by the architect, or under his supervision and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Architect. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Architect is strictly prohibited.

© COPYRIGHT 2018 GUY GRONBERG ARCHITECTS, P.C.

INLV#	DATE	DESCRIPTION
DATE: 08-11-2023		
PROJECT# 23012		

S130





1. CONTRACTOR TO VERIFY ALL FOUNDATION ELEVATIONS AND STEPS PER SITE CONDITIONS.
2. TOP OF SLAB ELEVATION SHOWN IN PLAN IS FOR REFERENCE ONLY.
3. REFERENCE ARCHITECTURAL DRAWINGS FOR WALL OPENING DIMENSIONS, EXTERIOR FINISHES AND ADDITIONAL NOTES.
4. REFERENCE GENERAL NOTES SHEET FOR ADDITIONAL FOUNDATION SPECIFICATIONS.
5. CONTRACTOR TO CONTACT APEX ENGINEERS, INC AT LEAST 48 HRS IN ADVANCE OF ANY CONCRETE POUR.

SCHEDULE - PAD FOOTINGS				
MARK	LENGTH	WIDTH	DEPTH	REINFORCING
F42	3' - 6"	3' - 6"	36"	(10) #5 BARS EACH WAY (5) AT T&B
F54	4' - 6"	4' - 6"	12"	(6) #5 BARS EACH WAY
F54-F	4' - 6"	4' - 6"	36"	(12) #5 BARS EACH WAY (6) AT T&B

MARK	WIDTH	DEPTH	LONG BARS	TRANS BARS
CF16	1' - 4"	36"	(4) #5 BARS [(2) AT T&B]	#3 TIES AT 18" OC





NOTES:  
1. PROVIDE CONTROL JOINTS (1/4 SLAB THICKNESS) SPACED AT 30xSLAB THICKNESS OC BOTH  
WAYS, NOT SHOWN FOR CLARITY.

MARK	SLAB THICKNESS	WEIGHT CLASS	SLAB REINFORCING	ADDITIONAL REQUIREMENTS
SG4	4"	NW	#3 AT 18" OC (C) EA WAY OR 6X6 W2.9XW2.9 WWF	15 MIL VAPOR BARRIER ON 4" OF 3/4" CLEAN, GRADED ROCK

NOTES:

1. PROVIDE 5/16" FLAT WELD AT CULUM TO BASE PLATE CONNECTION.
2. CAST-IN PLACE ANCHORS TO THE HEX-HEAD ASM F1554 (5 KSI) UNF.
3. POST INSTALLED EPOXY ANCHORS TO BE THREADED ROD INSTALLED IN EPOXY PER MATERIAL SPECIFICATIONS, UNF.
4. POST INSTALLED HILL-HUSZ ANCHORS TO BE INSTALLED PER MFR SPECIFICATIONS.
5. BASE PLATE WITH LESS THAN 4" ANCHORS REQUIRE COLUMNS BE DESIGNATED AS POSTS AND SHALL BE TEMPORARILY BRACED DURING PER GSMA PART 1626. BY OTHERS, BRACING MAY BE REMOVED ONCE ATTACHMENTS TO MAIN STRUCTURE ARE COMPLETE.
6. MAX SIZES OF ANCHOR-ROD HOLES IN BASE PLATES SHALL FOLLOW TABLE 14.2 OF THE AISC MANUAL. AN ADEQUATE WASHER SHOULD BE PROVIDED FOR EACH ANCHOR ROD.
7. BRACING SHALL BE PROVIDED TO ALL POSTS AND COLUMNS UNDER ALL SERVICE CONDITIONS (I.E. MOMENT FRAME AND BRACED FRAME COLUMNS). PROVIDE 1/4" FLAT WELD ALL AROUND.


D = VARIES, COORDINATED WITH BEAM FLANGE WIDTH bf = WIDTH OF BEAM FLANGE					
TYPE	PLATE SHAPE	PLATE THICKNESS	BOLT DIAMETER	ANCHOR BOLT EMBED	
				CAST-IN-PLACE (HEX-HEAD)	POST-INSTALLED / BOL TYPE
BP: 1	A	1"	3/4"	8	8"
BP: 2	B	5/8"	1/2"	8	8"
BP: 3	E	3/4"	7/8"	8	8"



REV#	DATE	DESCRIPTION
------	------	-------------

DATE: 08-11-2023
PROJECT# 23012





## PLAN NOTES - DIAPHRAGM

1. ROOF SHEATHING THICKNESS AND SPAN RATING MAY BE INCREASED FOR ROOFING MATERIAL REQUIREMENTS AND WARRANTIES. SHEATHING THICKNESS INCREASE SHALL BE APPROVED BY THE ARCHITECT.
2. CONTRACTOR SHALL PROVIDE ADDITIONAL SOLID BLOCKING AS REQUIRED FOR DIAPHRAGM NAILING REQUIREMENTS. SOLID BLOCKING SHALL BE OF MIN NOMINAL 2x4 IN SIZE AND SHALL BE MIN #3 GUT MATERIAL.
3. SOLID BLOCKING SHALL BE CUT TIGHT TO ADJACENT MEMBERS TO ENSURE ADEQUATE LOAD TRANSFER.
4. NAIL TYPES: IN FLOOR/ROOF SHEATHING SHALL BE COMMON OR GALVANIZED BOX NAIL, SINKER NAILS, CLOSER NAILS, ETC ARE NOT PERMITTED AT THESE APPLICATIONS.
5. NAILS USED FOR FLOOR/ROOF SHEATHING SHALL HAVE FULL HEADS. CLIPPED NAILS ARE NOT PERMITTED IN THESE APPLICATIONS.

### LEGEND - DIAPHRAGM

- - -	= DIAPHRAGM BOUNDARY NAILING: 10d NAILS AT 6" OC, CONTRACTOR SHALL ADD BLOCKING AS REQUIRED.
- - - -	= DIAPHRAGM BOUNDARY NAILING: 10d NAILS AT 4" OC, CONTRACTOR SHALL ADD BLOCKING AS REQUIRED.
- . - -	= DIAPHRAGM BOUNDARY NAILING: 10d NAILS AT 3" OC STAGGERED, CONTRACTOR SHALL ADD BLOCKING AS REQUIRED.
- . - . -	= DIAPHRAGM BOUNDARY NAILING: 10d NAILS AT 2" OC STAGGERED, CONTRACTOR SHALL ADD BLOCKING AS REQUIRED.
// // //	= BLOCKED DIAPHRAGM WITH PANEL EDGE FASTENING AT 6" OC EDGES, 12" OC FIELD.
[ ] [ ] [ ]	= SIMPSON LSTA12 STRAP, ATTACH WITH (10) 10d NAILS AT EACH TRUSS, ATTACH TO 2x6 CONT BLOCKING BETWEEN TRUSSES, INSTALL STRAP PER SIMPSON SPECIFICATIONS.
[ ] [ ] [ ]	= SIMPSON CS14 COL STRIP INSTALLED DIRECTLY OVER SHEATHING (ALT OF (2) CSHP18 COL STRAPS), INSTALL (2) PILES OF BLOCKING AS REQUIRED.

## SCHEDULE - HOLDDOWNS

- NOTES:
1. EMBEDMENT DEPTH IS FROM TOP OF FOOTING. INCREASE ANCHOR LENGTH AS REQUIRED FOR SLAB THICKNESS.
  2. FOR HDU14 OR GREATER USE HEAVY HEX NUT.
  3. HD19 REQUIRES DF END STUDS AND HD EMBED PLATE.
  4. GC TO VERIFY LOCATION OF ANCHOR BOLTS PRIOR TO FOUNDATION WALL REBAR INSPECTION.
  5. ALL HOLD-DOWNS ARE SIMPSON PRODUCTS UNO.
  6. FOR POST-INSTALLED ANCHORS REF MATERIAL SPECIFICATIONS FOR EPOXY AND ANCHOR ROD REQUIREMENTS.


MARK	HOLDDOWN	ANCHOR BOLT DIAMETER	MIN EMBEDMENT
HDU2	HDU2-SDS2.5	5/8"	5"
HDU5	HDU5-SDS2.5	5/8"	5"
HDU8	HDU8-SDS2.5	7/8"	7"
HDU11	HDU11-SDS2.5	1"	9"
HDU14	HDU14-SDS2.5	1 <sup>1/2</sup>	11"
HD19	HD19 <sup>3</sup>	1 1/4" <sup>2</sup>	HDEP #1

## SCHEDULE - SHEAR WALLS


- NOTES:
1. WSP = WOOD STRUCTURAL PANEL PLYWOOD OR OSB.
  2. NAIL SIZES GIVEN ARE FOR COMMON NAILS OR GALVANIZED (HOT-DIPPED OR TUMBLED) BOX NAILS. SINKER NAILS, COOLER NAILS, ETC. SHALL NOT BE USED FOR WSP SHEAR WALLS.
  3. SHEAR WALL NAILS SHALL NOT HAVE FULL HEADS. CURVED NAILS ARE NOT ALLOWED.
  4. ALL NAILS SHALL BE DRIVEN SUCH THAT THE HEAD IS FLUSH WITH FACE OF SHEATHING. DO NOT OVERDRIVE NAILS.
  5. SOLEPLATE NAILS SHALL BE INSTALLED SUCH THAT THE NAILS FULLY ENGAGE THE RIM BOARD BELOW (IF APPLICABLE). REF TYP DETAILS.
  6. PROVIDE INTERMEDIATE NAILING (FIELD) AT 12" OC, TYP.
  7. PROVIDE (2) TOTAL RIMBOARDS OR A LAYER OF BLOCKING IN ADDITION TO THE RIMBOARD WHERE SOLE PLATE NAILING REQUIRES 2 ROWS OF FASTENERS PER SCHEDULE.
  8. SILL ANCHORS MAY BE CAST-IN-PLACE J-BOLTS WITH 8" EMBED OR SIMPSON TITEN HD SCREW ANCHORS WITH 6" EMBED. REF SCHEDULE FOR BOLT DIA. BOTH BOLT TYPES REQUIRE 0.29"x3"x3" PLATE W/ASHER WITH EDGE OF PLATE LOCATED WITHIN 1/2" OF SHEAR WALL SHEATHING.
  9. SHEAR WALL REF PLAN FOR NUMBER OF CLIPS PER SHEAR WALL, 48" OC MAX. UNL.
  10. AT WALLS DESIGNATED AS FORCE TRANSFER SHEAR WALLS, PROVIDE SIMPSON STRAP ABOVE AND BELOW ALL OPENINGS PER SHEAR WALL DETAIL.
  11. END STUDS MUST CONTINUE DOWN TO FOUNDATION WALL UNLESS INTERRUPTED BY TRANSFER BEAM.
  12. JACK STUDS FOR OPENINGS DO NOT COUNT TOWARDS THE REQUIRED NUMBER OF END STUDS IN A SHEAR WALL.
  13. PROVIDE DOUBLE STUDS AND BLOCKING NAILED TOGETHER WITH (2) 16d NAILS AT 6" OC OR 3" NOMINAL STUDS AND BLOCKING AT THE FOLLOWING CONDITIONS:
    - i. 2" OC EDGE NAIL SPACING
    - ii. 10d NAILS AT 3' OC OR SMALLER EDGE NAIL SPACING
    - iii. DOUBLE SIDED SHEAR WALL WHERE PANEL JOINTS ALIGN TO THE SAME STUD.
  14. HOLD-DOWNS AND STRAPS OCCUR AT THE BOT OF WALLS. HOLD-DOWNS AND STRAPS BETWEEN FLOORS ARE CONTROLLED BY THE WALL ABOVE.
  15. HOLD-DOWN DEVICES SHALL BE INSTALLED PER MFR SPECIFICATIONS
  16. REF SHEAR WALL DETAILS FOR ADDITIONAL INFORMATION AND REQUIREMENTS

MARK	BLOCKED	SHEATHING		PLACEMENT	EDGE NAILS		SILL PLATE ATTACHMENT	
		TYPE	THICKNESS		SIZE	SPACING	NAILING	1/2" DIA ANCHOR BOLT SPACING
S2-B	YES	WSP-SHEATHING	15/32"	ONE-SIDE	10d	4"	16d AT 4" OC	16"
S3-B	YES	WSP-SHEATHING	15/32"	ONE-SIDE	10d	3"	16d AT 3" OC STAGGERED	12"

### FIRST FLOOR SHEAR WALL PLAN

$$1/8" = 1'-0"$$






PLAN NOTES - WOOD ROOF FRAMING

- REFERENCE "LOADING DIAGRAMS" SHEET FOR DESIGN LOADS.
- WOOD COLUMNS AND STUD PACKS TO BE CONTINUOUS DOWN TO FOUNDATION OR STEEL FRAMING. PROVIDE BLOCKING AS REQUIRED TO MAINTAIN CONTINUITY.
- REF PLANS FOR TOP OF STEEL BEAM ELEVATIONS.
- ROOF CONSTRUCTION: REFERENCE ARCHITECTURAL DRAWINGS FOR DIMENSIONS, ROOF MATERIAL, ROOF SLOPE, WATERPROOFING MEMBRANE, AND INSULATION.
- REFERENCE MECHANICAL DRAWINGS FOR ADDITIONAL RTU INFORMATION.
- CONTRACTOR SHALL COORDINATE SIZE AND LOCATION OF OPENINGS WITH MECHANICAL, ELECTRICAL, AND ARCHITECTURAL DRAWINGS.
- REFERENCE GENERAL NOTES AND SPECIFICATIONS FOR ABBREVIATIONS, SYMBOLS, AND ADDITIONAL SPECIFICATIONS.

SCHEDULE - WOOD WALLS

NOTES:  
1. WALL SOLE PLATE ATTACHMENT: UNO: 1/2" DIA CAST-IN-PLACE ANCHORS WITH 7" EMBED AT 32" OC ATTACHMENT TO CONCRETE OR (2) ROWS OF 16d NAILS AT 16" OC STAGGERED WHEN FASTENING TO WOOD.  
2. TYPICAL WALL SHEATHING: UNO: 15/32" APA RATED WSP, EXP: 1, 24/16 SPAN RATING, PANEL EDGES FASTENED WITH 8d NAILS AT 8" OC EDGE AND 12" OC IN THE FIELD.  
3. REFERENCE SHEAR WALL SCHEDULE FOR ADDITIONAL NAILING REQUIREMENTS.  
\*\* = LATERAL CLIPS REQUIRED; PROVIDE SIMPSON A35 CLIP AT EACH STUD ABOVE HEADER. REFERENCE TYPICAL DETAILS FOR CLIP LOCATION.

MARK	MATERIAL	WALL STUDS	BLOCKING
DFL6	DF-L No. 2	2x6 AT 16"	AT SHEATHING PANEL EDGES (4'-0" OC MAX)
DFL6-2	DF-L No. 2	2x6 AT 16"	AT SHEATHING PANEL EDGES (4'-0" OC MAX)

SCHEDULE - TRUSSES

MARK	TRUSSES	SPACING	COMMENTS
T1	ROOF TRUSS	24"	COORDINATE PLACEMENT WITH CANOPY ROD ATTACHMENT

SCHEDULE - JOISTS

MARK	JOISTS	SPACING	COMMENTS
J1	2x8	16"	

SCHEDULE - HEADERS

NOTES:  
1. JAMB AND SILL STUDS TO MATCH TYPICAL WALL STUDS UNO.

MARK	HEADER	COMMENTS
H2-9.25	(2) 1 1/2"x9/2" LVL	
H2-10	(2) 2x10	
H2-11	(2) 1 1/2"x11 1/2" LVL	
H3-10	(3) 2x10	

SCHEDULE - BEAMS

MARK	BEAM SIZE	COMMENTS
B1	C6X8.2	COORDINATE PLACEMENT WITH CANOPY ROD ATTACHMENT
B2	(1) 2x8-(1) 2x12	2x12 FORMING CANOPY CURB

SCHEDULE - CAP PLATES

NOTES:  
1. BOLT SIZE NOTE: FOR BEAMS WITH A FLANGE WIDTH LESS THAN 5", 5/8" BOLTS MAY BE USED FOR DETAILING TOLERANCES.  
2. Bf = WIDTH OF BEAM FLANGE.  
3. D = VARIES; COORDINATE WITH BEAM FLANGE WIDTH.  
4. W = JOIST GIRDER SEAT WIDTH PLUS 1" FOR FILLET WELD CONNECTION. VERIFY SEAT WIDTH WITH JOIST SUPPLIER PRIOR TO FABRICATION.  
5. VERIFY BOLT PLACEMENT WITH JOIST SUPPLIER.

PLATE TYPE	SHAPE	PLATE THICKNESS	BOLT SIZE
A	1	1/4"	3/4"
B	2	1/4"	3/4"

SHAPE - 1

SHAPE - 2


SEE NOTE 3

SCHEDULE - ROOF SHEATHINGS


MARK	SHEATHING TYPE	SUPPORT ATTACHMENT [EDGE / FIELD]	BLOCKED
ROOF	5/8" (NOMINAL) APA RATED SHEATHING, EXPOSURE 1, 48/24 SPAN RATING	10d [6" OC / 12" OC]	No

SCHEDULE - KEYNOTE LEGEND

KEYNOTE	COMMENT
1	BALLOON FRAMED WALL
2	SPF STUD GRADE OR BETTER 2x6 KICKERS AT EACH TRUSS PARAPET



GUY GRONBERG  
ARCHITECTS, P.C.  
118 SE 2nd St.  
Lee's Summit, MO 64063  
Phone 816.524.0819  
Fax 816.524.2519



DOUGLAS  
CORNER  
LOT 1B, LEE'S SUMMIT, MISSOURI 64086


This drawing has been provided as an informational document only. It is not to be used for construction. The user of this drawing assumes all responsibility for the accuracy and completeness of the information contained herein. The user of this drawing assumes all responsibility for the accuracy and completeness of the information contained herein. The user of this drawing assumes all responsibility for the accuracy and completeness of the information contained herein.

REV# DATE DESCRIPTION

DATE: 08-11-2023  
PROJECT# 23012

S210




















#### 4 | MOMENT FRAME END BEAM CONNECTION

<b>S511</b>	$3/4" = 1'-0"$
-------------	----------------




## 6 | MOMENT FRAME INTERMEDIATE BEAM CONNECTION

<b>S511</b>	3/4" = 1'-0"
-------------	--------------




### 3 | WIDE FLANGE BEAM SPLICE

<b>S511</b>	$3/4'' = 1'-0''$
-------------	------------------




## 2 | STEEL BEAM BEARING ON STEEL HSS COLUMN

<b>S511</b>	$3/4" = 1'-0"$
-------------	----------------




## 1 | STEEL BEAM CONTINUOUS ON STEEL HSS COLUMN

<b>S511</b>	$3/4" = 1'-0"$
-------------	----------------




## 5 | MOMENT FRAME ELEVATION

<b>S511</b>	1/4" = 1'-0"
-------------	--------------



**GUY GRUNBERG  
ARCHITECTS, P.C.**  
113 SE 3rd St.



DOUGLAS  
CORNER

LOT 1B, LEE'S SUMMIT, MISSOURI 04080

or instrument of service by the architect, or under his supervision and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Architect. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Architect is strictly prohibited.

**©COPYRIGHT 2018 GUY GRONBERG ARCHITECTS, P.C.**

[illegible]

S511






NOTE:  
1. SEE SECTION R602.6 AND FIGURES R602.6.1 AND R602.6.2

**2. VERTICAL HOLE SIZE (H):**

- LVL'S 1&2: D + 1/2"
- LVL 3: D + 1"
- LVL 4: D + 1 1/4"
- LVL 5: D + 1 1/2"

**3. TOP AND BOTTOM PLATE HOLES:** CUT OR NOTCH THAT IS 50% OR MORE OF WIDTH MUST BE REPAIRED USING 16 GA (MIN) METAL TIE THAT IS AT LEAST 1-1/2" WIDE IF WALL IS A SHEAR WALL IT MUST BE REPAIRED USING HARDY FRAME SADDLE (HFS).

WALL STUDS						PLATES
WALL SIZE	BORED HOLE SIZE			NOTCH		TOP & BOT
	LOAD BEARING OR EXT WALL	NON- LOAD BEARING		LOAD BEARING	NON-LOAD BEARING	
		40%	60%			
2x4	1 3/8"	60%	2 1/8"	7/8"	3 3/8"	1 3/4"
(2) 2x4	2 1/8"	2 1/8"	7/8"	3 3/8"	1 3/4"	1 3/4"
(2) 2x6	2 1/4"	3 15/16"	3 15/16"	1 3/8"	2 1/4"	2 3/4"
(2) 2x6	3 5/16"	3 15/16"	1 3/8"	2 1/4"	2 3/4"	2 3/4"
2x8	2 7/8"	4 3/8"	4 3/8"	1 13/16"	2 7/8"	3 5/8"
(2) 2x8	4 3/8"	4 3/8"	1 13/16"	2 7/8"	3 5/8"	3 5/8"



7	TYPICAL JAMB DETAIL	
S520	NOT TO SCALE	THIS DETAIL IS TYPICAL TO THE PROJECT AND MAY NOT BE CUT OR CALLED OUT ON PLANS




This drawing has been provided as an illustration of the type of service and the nature of the relationship between the architect and the client. It is not intended to constitute an offer of insurance or any other financial product. For more information, please contact your insurance broker or the architect.

[illegible]

# S520





THIS DETAIL IS TYPICAL TO THE PROJECT AND  
MAY NOT BE CUT OR CALLED OUT ON PLANS

MAY NOT BE CUT OR CALLED OUT ON TEARS

THIS DETAIL IS TYPICAL TO THE PROJECT AND  
MAY NOT BE CUT OR CALLED OUT ON PLANS



THIS DETAIL IS TYPICAL TO THE PROJECT AND  
MAY NOT BE CUT OR CALLED OUT ON PLANS


MAY NOT BE CUT OR CALLED OUT ON/ BY BARS

PANEL FIELD EDGE FASTENING, REF PLAN  
 SHEATHING, REF PLAN  
 ARROW INDICATES PANEL DIRECTION/ORIENTATION  
 PANEL EDGE FASTENING, REF PLAN  
 TRUSS SPACING, REF PLAN  
 PREMANUFACTURED TRUSS BY OTHERS, REF PLAN  
 BLOCKING AS REQUIRED, REF PLAN; HIGHLIGHTED GRAY FOR CLARITY


THIS DETAIL IS TYPICAL TO THE PROJECT AND  
MAY NOT BE CUT OR CALLED OUT ON PLANS









**7 ROOF KICKER BASE ATTACHMENT**  
**S522** 1 1/2" = 1'-0"




**6 TYPICAL CANOPY FRAMING**  
**S522** 3/4" = 1'-0"




**4 CANOPY TOP SUPPORT AT CORNER**  
**S522** 3/4" = 1'-0"




**3 TYP CANOPY SUPPORT AT BOTTOM**  
**S522** 3/4" = 1'-0"



**2 TYP CANOPY SUPPORT AT TOP**  
**S522** 3/4" = 1'-0"



**5 W ROOF TRUSS BEARING AT CANOPY**  
**S522** 3/4" = 1'-0"



**1 W EXTERIOR ROOF FRAMING AT CANOPY SUPPORT**  
**S522** 3/4" = 1'-0"



**GUY GRONBERG**  
**ARCHITECTS, P.C.**  
 118 SE 2nd St.  
 Lees Summit, MO 64063  
 Phone 816.524.0819  
 Fax 816.524.2519



**APEX**  
 ENGINEERS, INC.  
 1625 LOCUST ST.  
 KANSAS CITY, MO 64108  
 816.421.3222  
 816.421.1050  
 www.apex-engineers.com

**DOUGLAS**  
**CORNER**  
 LOT 1B, LEES SUMMIT, MISSOURI 64086












This drawing has been provided as an instrument of service to the architect or engineer for the project. It is not to be used for any other purpose without the written consent of the architect or engineer. The architect or engineer is not responsible for the accuracy or completeness of the information provided on this drawing. The architect or engineer is not responsible for the accuracy or completeness of the information provided on this drawing. The architect or engineer is not responsible for the accuracy or completeness of the information provided on this drawing.

REV#	DATE	DESCRIPTION


DATE: 08-11-2023  
 PROJECT# 23012

**S522**











ELECTRIC HEATER SCHEDULE									
MARK	LOCATION	MANUFACTURER	MODEL	WEIGHT	CFM	ELECTRICAL			NOTES
						VOLTS	PH	KW	
EUH-1	FIRE RISER ROOM	QUELLET	OHVU03008AM	40	300	208	3	3	A-E
NOTES:									
A.	MOUNT 8'-0" ABOVE FINISHED FLOOR WITHOUT OBSTRUCTING AIRFLOW.								
B.	PROVIDE NECESSARY MOUTING BRACKET AND ACCESSORIES FOR HORIZONTAL MOUNTING.								
C.	PROVIDE WALL MOUNTED THERMOSTAT.								
D.	PROVIDE FACTORY MOUNTED DISCONNECT SWITCH.								
E.	PROVIDE REPLY AND TRANSFORMER FOR CONNECTION TO 24V THERMOSTAT.								
F.	INSTALL RECESSED IN WALL. COORDINATE COLOR WITH ARCHITECT. PROVIDE TAMPERPROOF BUILT-IN THERMOSTAT.								

PLUMBING FIXTURE SCHEDULE	
FD	FLOOR DRAIN: SOUIX CHIEF 842-4PNR, FLOOR DRAIN, PVC BODY AND CLAMPING COLLAR, ADJUSTABLE 6-1/2" ROUND NICKEL BRONZE STRAINER. PROVIDE WITH PROSET SYSTEMS "TRAP GUARD" INSERT FOR ACTUAL FLOOR DRAIN MODEL AND SIZE PROVIDED.
RPZ1	WATTS #LF009, 1-1/2", REDUCED PRESSURE BACKFLOW PREVENTER, LEAD FREE BRONZE BODY CONSTRUCTION, TWO IN-LINE INDEPENDENT CHECK VALVES, REPLACEABLE CHECK SEATS WITH AN INTERMEDIATE RELIEF VALVE AND BALL VALVE TEST COCKS.
RPZ2	WATTS #LF009, 1", REDUCED PRESSURE BACKFLOW PREVENTER, LEAD FREE BRONZE BODY CONSTRUCTION, TWO IN-LINE INDEPENDENT CHECK VALVES, REPLACEABLE CHECK SEATS WITH AN INTERMEDIATE RELIEF VALVE AND BALL VALVE TEST COCKS.
HB	HOSE B/B, FREEZELESS, WOODFORD MODEL 65, ASSE 1019-B CERTIFIED WITH ASSE 1011 VACUUM BRAKER, LOOSE KEY OPERATOR, 3/4" MPT INLET.

FIXTURE BRANCH CONNECTION SCHEDULE				
FIXTURE	COLD WATER	HOT WATER	WASTE	VENT
FLOOR DRAIN	-	-	4"	2"
WALL HYDRANT	3/4"	-	-	-
NOTE:	PIPE SIZES SHOWN ARE MINIMUM.			

DUPLUX SEWAGE GRINDER PUMP SCHEDULE											
MARK	MANUFACTURER	MODEL	GPM	HEAD (FT. WC)	HP	ELECTRICAL (EACH PUMP)				WEIGHT (LBS)	NOTES
						VOLTS	PHASE	FULL LOAD AMPS	LOCKED ROTOR AMPS		
GP-1	LIBERTY	D3672LSG203	50	31	2	208	1	15	53	515	A-G
NOTES:											
A.	THIS IS A PREASSEMBLED DUPLUX GRINDER SYSTEM WITH TWO (2) IDENTICAL PUMPS. ELECTRICAL INFO ABOVE IS FOR ONE PUMP. ELECTRICAL SERVICE SHALL BE SIZED TO SUPPORT BOTH PUMPS RUNNING SIMULTANEOUSLY										
B.	PROVIDE FACTORY MOUNTED GUIDE RAIL SYSTEM WITH QUICK DISCONNECT.										
C.	PROVIDE THREE (3) FLOAT SWITCHES AND A HIGH WATER ALARM.										
D.	PROVIDE AE24HC NEMA 4X CONTROL PANEL. MOUNT ON WALL NEXT TO DUPLUX SYSTEM.										
E.	PUMPS SIT TOGETHER IN A 36" ID X 96" DEEP FIBERGLASS BASIN.										
F.	COORDINATE DISCHARGE HEIGHT WITH CIVIL PLANS PRIOR TO PURCHASE.										
G.	PROVIDE ONE (1) 42" OD X 3/8" THICK ROUND STEEL COVER.										

## MECHANICAL & PLUMBING SPECS

- GENERAL PROVISIONS:**
- A. PROVIDE ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY FOR THE COMPLETE INSTALLATION OF THE PLUMBING AND MECHANICAL SYSTEMS OUTLINED.
  - B. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATIONS OF COMPLIANCE OR APPROVAL AS REQUIRED BY AUTHORITIES.
  - C. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION OVER THE SITE.
  - D. ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.
  - E. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, PIPE, DUCT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNDAMAGED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERING SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.
  - F. THE CONTRACTOR SHALL CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS AS NECESSARY, PATCH AROUND ALL OPENINGS SHALL MATCH ADJACENT AREA, COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.
  - G. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECT FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
  - H. INSPECTION OF THE SITE. THIS CONTRACTOR SHALL THOROUGHLY ACQUAINT HIMSELF WITH THE MEP DRAWING SPECIFICATIONS, DETAIL AND THE SITE. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY SPECIAL OR UNUSUAL PROBLEMS, CONFLICTS, OR OBSTRUCTIONS THAT AFFECT HIS BID.
  - I. FOR THE PURPOSE OF CLEARNESS AND LEGIBILITY, THE MECHANICAL DRAWINGS ARE ESSENTIALLY DIAGRAMMATIC AND DO NOT SHOW ALL OFFSETS AND FITTINGS REQUIRED FOR INSTALLATION. DO NOT SCALE DRAWINGS. THE SIZE AND LOCATION OF EQUIPMENT IS SHOWN TO SCALE WHEREVER POSSIBLE. THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DATA AS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATION SECTIONS WHERE MECHANICAL WORK INTERFACES WITH OTHER TRADES.
  - J. IN THE EVENT OF ANY DISCREPANCY OR CONFLICT BETWEEN ITEMS INDICATED ON THE PLANS OR WITH CODE REQUIREMENTS, THE NOTE OR CODE WHICH PRESCRIBES AND ESTABLISHES THE MORE COMPLETE JOB OR HIGHER STANDARD SHALL PREVAIL.
  - K. INSTALL MATERIALS AND SYSTEMS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS AND APPROVED SUBMITTALS. INSTALL MATERIALS IN PROPER RELATION WITH ADJACENT CONSTRUCTION AND WITH UNIFORM APPEARANCE FOR EXPOSED WORK. COORDINATE WITH WORK OF OTHER SECTIONS. COMPLY WITH APPLICABLE REGULATIONS AND CODE REQUIREMENTS. PROVIDE PROPER CLEARANCES FOR SERVING.
  - L. INCLUDE ALL BASIC MATERIALS AND CONSTRUCTION METHODS INCLUDING PIPES, PIPE FITTINGS, AND SPECIALTIES AND SUPPORTING DEVICES, VALVES, PIPE AND VALVE IDENTIFICATION, PUMPS, VIBRATION ISOLATION, ETC.
  - M. FURNISH ADEQUATE ACCESS PANELS AND DOORS TO ALLOW FOR FUTURE PIPING ALTERATIONS, REPLACEMENT, AND MAINTENANCE OF PIPING. PROPERLY IDENTIFY ALL ACCESS PANELS AND DOORS.

2. OPERATION AND MAINTENANCE MANUALS:
- A. DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, WIRING DIAGRAMS, CATALOG CUTS, LUBRICATION AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.
  - B. ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATING AND MAINTENANCE MANUALS.

3. MANUFACTURERS:
- A. MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSIDERED AS IMPLYING COMPETITION. ARTICLES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO STRUCTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN.
- B. THE ELECTRICAL SYSTEM DESIGN IS BASED IN PART ON THE SPECIFIED EQUIPMENT. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE THE ELECTRICAL REQUIREMENTS OF THE EQUIPMENT FURNISHED, AND CHANGES TO THE ELECTRICAL SYSTEM DUE TO HVAC EQUIPMENT OTHER THAN THE SPECIFIED EQUIPMENT BEING FURNISHED SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.

4. MOTORS:  
A. PROVIDE THERMAL OVERLOAD PROTECTION FOR EACH MOTOR PROVIDED BY THIS WORK.

5. PLUMBING:
- A. PROVIDE CLEANOUTS AT EACH CHANGE IN DIRECTION AND AT 100 FOOT INTERVALS IN STRAIGHT RUNS
  - B. ALL SEWER PIPING LOCATED INSIDE THE BUILDING SHALL BE INSTALLED WITH THE FOLLOWING SLOPES.
    - 1. INSTALL 2-1/2" AND SMALLER PIPE AT 1/4" PER FOOT FALL.
    - 2. INSTALL 3" AND LARGER PIPE AT 1/8" PER FOOT FALL.

6. PIPING
- A. DOMESTIC COLD, HOT, AND HOT WATER RECIRCULATING (ABOVEGROUND).
1. TYPE L HARD DRAWN COPPER TUBING, ASTM B-88 WITH WROUGHT BRONZE SOLDERED FITTINGS.
  2. GATE VALVE: CRANE #428 OR EQUAL.
  3. BALL VALVE: CRANE #932 OR EQUAL.

- B. SANITARY SEWER AND VENTS (UNDERGROUND, INTERIOR TO BUILDING).
1. POLYVINYL CHLORIDE (PVC) DMV PIPE, SCHEDULE 40, SOLVENT JOINT.
  2. SEWER LINES SHALL BE LOCATED IN GENERAL AS SHOWN ON THE DRAWINGS. THE EXACT LOCATIONS SHALL BE DETERMINED BY THE CONTRACTOR IN SUCH A MANNER AS TO MAINTAIN PROPER CLEARANCES AND SUFFICIENT SLOPE TO ENSURE DRAINAGE.
- C. NATURAL GAS PIPING:
1. SCHEDULE 40 BLACK STEEL PIPING: 2" AND SMALLER WITH SCREWED JOINTS AND 150 LB. MALLEABLE IRON SCREWED FITTINGS, PIPE 2-1/2" AND LARGER SHALL USE STANDARD WEIGHT BLACK STEEL WELDING FITTINGS WITH WELDED JOINTS.
  2. GAS VALVES SHALL BE ROXWELL 142, PLUS G.V.E.
  3. SUPPORT PIPING AT INTERVALS NOT TO EXCEED THOSE LISTED IN TABLE 415.1 OF THE I.F.C.C.
  4. PROVIDE A.G.A. APPROVED SHUT OFF VALVES AND DIRT LEGS AT CONNECTIONS TO ALL EQUIPMENT.
- D. ALL PIPE HANGERS AND SUPPORTS SHALL BE STANDARD PRODUCTS OF GRINNELL, FEE AND MASON, OR ANVIL. HANGER SPACING SHALL BE IN ACCORDANCE WITH MSS-SP-69.

- 2. INSULATION:**
- A. ALL INSULATIONS AND ACCESSORIES SHALL HAVE A FIRE HAZARD CLASSIFICATION WITH A FLAME SPREAD RATING OF 0 OR 25, A FUEL CONTRIBUTION RATING OF NOT OVER 50, AND A SMOKE DEVELOPMENT RATING OF NOT OVER 50, IN ACCORDANCE WITH NFPA.**
- B. PIPE INSULATION (ABOVE GRADE):**
1. THE PIPE INSULATION USED SHALL HAVE A THERMAL CONDUCTIVITY OF 0.27 BTU PER IN/HR/50-FIT\* OR LESS.
2. FLEXIBLE CLOSED CELL ELASTOMERIC THERMAL INSULATION, UNSLIT OR PRESLIT WITH PRESSURE SENSITIVE ADHESIVE SYSTEM FOR CLOSURE AND VAPOR SEALING, EQUAL TO ARMSTRONG AIR-ARMAFLEX OR ARMAFLEX 2000.
- C. THICKNESS:**
- a. DOMESTIC COLD WATER: 1/2"

- 8. TESTING, BALANCING AND CLEANING:**
- A. ALL PIPING SHALL BE TESTED FOR LEAKS BEFORE BEING CONCEALED IN WALL CONSTRUCTION OR COVERED WITH INSULATION.
  - B. SEWER AND VENT PIPING SHALL BE HYDROSTATICALLY TESTED WITH NO LESS THAN 10 FEET OF HEAD FOR A PERIOD OF NO LESS THAN 15 MINUTES, PER THE LOCAL PLUMBING CODE, WITH NO LEAKS.
  - C. DOMESTIC WATER PIPING SHALL BE HYDROSTATICALLY TESTED AT A PRESSURE OF NO LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE, BUT NOT LESS THAN 60 PSI, FOR A PERIOD OF NOT LESS THAN 2 HOURS, WITH NO LEAKS.
  - D. NATURAL GAS SYSTEMS SHALL BE TESTED WITH COMPRESSED AIR AT A PRESSURE OF NOT LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE , BUT NOT LESS THAN 50 PSIG FOR A PERIOD OF 2 HOURS WITH NO LEAKS.



- 9. FLUES AND ACCESSORIES:**
- A. PROVIDE MANUFACTURERS STANDARD ACCESSORY ITEMS INCLUDING BIRD PROOF TOP, STORM COLLAR, ROOF THIMBLE, ETC. AS REQUIRED FOR A COMPLETE INSTALLATION. ROOF THIMBLES THROUGH THE BUILDING ROOF SHALL BE SUITABLE FOR USE WITH THE ROOF PROVIDED.
- B. FLUES FOR HEATERS SHALL BE DOUBLE WALL TYPE B EQUAL TO METALBESTOS. PROVIDE MANUFACTURER'S STANDARD FITTING AND ACCESSORIES (ROOF THIMBLE, STORM COLLAR, COUNTER FLASHING, ETC.) AS REQUIRED FOR A COMPLETE INSTALLATION.

10. ELECTRIC WALL HEATERS
- A. UNIT SHALL INCLUDE ELECTRIC HEATING ELEMENTS WITH SAFETY AND DISCONNECT DEVICES AS REQUIRED BY NEC, INCLUDING RELAYS, CONTROLLERS AND REQUIRED EQUIPMENT TO FORM A COMPLETE AND FUNCTIONAL HEATER.
  - B. ELEMENTS SHALL BE HEAVY DUTY ALUMINUM-FINNED, COPPER CLAD STEEL SHEATH. PROVIDE AUTOMATIC RESET THERMAL OVER-HEAT PROTECTION. THERMAL PROTECTOR SHALL BE UNEAR TYPE TO SENSE TEMPERATURES THE ENTIRE LENGTH OF HEATING ELEMENT.
  - C. FANS SHALL BE DIRECT DRIVE USING PERMANENT SPLIT CAPACITOR TYPE MOTORS WITH BUILT-IN AUTOMATIC RESET MOTOR OVERLOAD PROTECTION.

## M&P SYMBOLS

THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS, ETC, ARE NECESSARILY USED ON THE DRAWINGS.







## HVAC EQUIPMENT &amp; DUCTWORK



## HVAC EQUIPMENT & DUCTWORK


SYMBOL	DESCRIPTION
	SANITARY SEWER (ABOVE GRADE)
	SANITARY SEWER (BELOW GRADE)
	CONDENSATE DRAIN
	VENT PIPING
	G = GAS PIPING LESS THAN 2 PSI
	MPG = GAS PIPING 2 PSI
	COLD WATER PIPING
	HOT WATER PIPING
	RECIRCULATING HOT WATER
	COMPRESSED AIR
	PIPE ELBOW DOWN
	PIPE ELBOW UP
	CHECK VALVE/BACKFLOW PREVENTER
	GATE VALVE
	BALL VALVE
	PLUG VALVE
	FLOOR CLEANOUT (FCO)
	WALL CLEANOUT (WCO)
	FLOOR DRAIN
	FLOOR SINK
	HOSE BIB

## ANNOTATION


- |   |  |
|---|--|
|  | PLAN WORK NOTE   |
|  | MECHANICAL EQUIPMENT DESIGNATION (CONTRACTOR FURNISHED AND INSTALLED UNLESS NOTED OTHERWISE) |
|  | PLUMBING FIXTURE DESIGNATION   |
|  | CONNECTION POINT OF NEW WORK TO EXISTING   |
|  | DETAIL REFERENCE UPPER NUMBER INDICATED DETAIL NUMBER LOWER NUMBER INDICATES SHEET NUMBER    |
|  | DENOTES EXISTING ITEM  |



**GUY GRONBERG  
ARCHITECTS, P.C.**  
113 SE 3rd St.  
Lee's Summit, MO 64063  
Phone 816.524.0878  
Fax 816.524.0578



ORD. NO. 201205736 / KS COA NO. E-2818  
1925 CENTRAL STREET, SUITE 201  
KANSAS CITY, MO 64108  
phone: (816) 272-5289  
email: ksmothers@ksconline.com



DOUGLAS  
| CORNER |  
LOT 1B, LEES SUMMIT, MISSOURI 64086

This drawing has been provided as an instrument of service by the architect, or under his supervision and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the architect's copyrighted work of the drawing. Any reproduction, in whole or in part, without the architect's written consent, is strictly prohibited.

© COPYRIGHT 2018 GUY  
GRONBERG ARCHITECTS, P.C.

REV#	DATE	DESCRIPTION

PERMIT SET: 08-11-2023  
JSC PROJECT# 18-142

**MECHANICAL & PLUMBING  
SPECIFICATIONS, SYMBOLS,  
SCHEDULES AND DETAILS**

# MP1






MECHANICAL  
PLAN


M1






## SCALE : NO SCALE

4




SCALE : NO SCALE

3



## 2




1



- A. ROUTE PIPING AS HIGH AND AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE ROUTING WITH ALL EXISTING CONDITIONS, EQUIPMENT, STRUCTURAL ELEMENTS, DUCTWORK, ETC.
- B. COORDINATE PIPE ROUTING AWAY FROM ELECTRICAL PANELS. DO NOT ROUTE PIPING OVER ELECTRICAL PANELS.

1. 1-1/4" SANITARY FORCED MAIN TO UTILITY SERVICE. REFER TO CIVIL PLANS FOR CONTINUATION.
2. 1-1/2" DOMESTIC COLD WATER TO UTILITY SERVICE. CONTRACTOR SHALL WORK WITH THE WATER COMPANY AND BEAR ALL COSTS FOR THE INSTALLATION OF A NEW WATER MAIN ENTRANCE, INCLUDING TAP, METER, METER PIPE, FITTING, ETC. FOR A COMPLETE INSTALLATION.
3. 2" VENT FROM UNDERGROUND UP TO CEILING SPACE.
4. GAS PIPING TO UTILITY MAIN. TOTAL ESTIMATED GAS LOAD FOR BUILDING = 1,200 MBH. REFER TO CIVIL PLANS FOR CONTINUATION. CONTRACTOR TO COORDINATE WITH GAS UTILITY FOR INSTALLATION.
5. COORDINATE WITH GAS COMPANY FOR INSTALLATION OF (1) ONE INITIAL METER AND A METER BANK WITH CAPACITY FOR (6) TOTAL METERS. COORDINATE SPACE REQUIREMENTS WITH UTILITY. INITIAL GAS DEMAND IS 200CFH @ 7"W.C.
6. 4" VENT THRU ROOF. LOCATE MINIMUM 3'-0" FROM EDGE OF ROOF. COORDINATE PIPE PENETRATION WITH ROOFING CONTRACTOR SO NOT TO VOID ROOF WARRANTY. SEAL ROOF PENETRATION WEATHERTIGHT.
7. INSTALL 4" SANITARY SEWER SHUT-OFF AND CAP FOR FUTURE TENANT CONNECTION. EXTEND 4" PVC UP 6' ABOVE FINISHED FLOOR.
8. 1" GAS TO FURNACE. PROVIDE SHUT-OFF VALVE AND DIRT LEG PRIOR TO FINAL CONNECTION.
9. 1-1/2" VALVE AND 1-1/2" RPZ BACKFLOW PREVENTER APPROVED FOR DOMESTIC WATER SERVICE. INSTALL BACKFLOW PREVENTER 24" ABOVE FINISHED FLOOR (CENTERLINE ELEVATION) AS REQUIRED PER LOCAL A.H.J. PROVIDE MINIMUM 12" CLEARANCE FRONT AND BACK. PROVIDE DRAIN FROM BFP TO FLOOR DRAIN AND DISCHARGE WITH AIR GAP. PROVIDE PRESSURE REDUCING VALVE IF SERVICE PRESSURE AT DOMESTIC WATER ENTRY EXCEEDS 75 P.S.I. DOWNSTREAM OF REDUCED PRESSURE BACKFLOW PREVENTER. SEE INSTALLATION DETAIL.
10. 3/4" CW DOWN IN WALL TO FREEZE PROOF WALL HYDRANT. LOCATE SHUT OFF VALVE IN CEILING OF CLOSET.
11. PROVIDE 3/4" VALVED AND CAPPED COLD WATER LINE FOR FUTURE CONNECTION.
12. INSTALL 3" VENT PIPE IN CEILING ALONG BACK OF TENANT SPACE TO ALLOW FOR FUTURE TENANT CONNECTIONS.
13. 6" FIRE SERVICE TO MAIN. REFER TO CIVIL DRAWINGS FOR CONTINUATION. FIRE SPRINKLER CONTRACTOR TO CONFIRM SERVICE SIZE ONCE CALCULATIONS ARE PERFORMED.



DOUGLAS  
| CORNER |  
LOT 1B, LEES SUMMIT, MISSOURI 64086

under his supervision and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Architect. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Architect is strictly prohibited.

©COPYRIGHT 2018 GUY GRONBERG ARCHITECTS, P.C.


RMIT SET: 08-11-2023  
C PROJECT# 18-142

## JUMPING PLAN

P1










MO COA NO. 201205786 / KS COA NO. E-2818  
1925 CENTRAL STREET, SUITE 201  
KANSAS CITY, MO 64108  
phone: (816) 272-5289  
email: [smothers@csengineers.com](mailto:smothers@csengineers.com)



DOUGLAS  
| CORNER |  
LOT 1B, LEES SUMMIT, MISSOURI 64086

This drawing has been provided as an instrument of service by the architect, or under his supervision and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Architect. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Architect is strictly prohibited.

©COPYRIGHT 2018 GUY  
CONIBERIS ARCHITECTS, P.C.

REV#	DATE	DESCRIPTION

PERMIT SET: 08-11-2023


JSC PROJECT# 18-142

ELECTRICAL LIGHTING  
PLAN

# E2

- A. DRAWINGS ARE DIAGRAMMATIC AND SHALL NOT BE SCALED. REFER TO ARCHITECTURAL PLANS OR FIELD MEASUREMENTS FOR DIMENSIONS.
- B. ALL WORK SHALL COMPLY WITH THE LATEST ADOPTED EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AND ALL LOCAL BUILDING CODES AND AMENDMENTS.
- C. ALL ROOF AND WALL PENETRATIONS SHALL BE COORDINATED WITH THE GENERAL CONTRACTOR. PROVIDE ALL REQUIRED SLEEVES, FLASHINGS, CURBS, REINFORCED ANGLES, SUPPORTING FRAMES, ETC. UNLESS THEY ARE SPECIFICALLY CALLED OUT TO BE FURNISHED BY OTHERS.
- D. COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACE AVAILABLE, AND WITHOUT INTERFERENCES.
- E. THIS CONTRACTOR SHALL PERFORM ALL WORK INDICATED AND/OR AS REQUIRED FOR THE PROPER INSTALLATION AND OPERATION OF THE ELECTRICAL SYSTEMS.
- F. ALL WIRING SHALL BE IN APPROVED RACEWAY.
- G. WIRE SIZE SHALL BE MINIMUM #12 AWG, THWN SOLID COPPER UNLESS OTHERWISE NOTED. PROVIDE GROUND WIRE WHERE REQUIRED BY CODE. INCREASE WIRE SIZE TO COMPENSATE FOR VOLTAGE DROP WHERE TOTAL LENGTH OF ANY BRANCH EXCEEDS 100 FEET.
- H. MAXIMUM NUMBER OF UNGROUNDED WIRES IN ANY CONDUIT SHALL BE THREE. ADDITIONAL WIRES ARE ACCEPTABLE IF WIRE SIZE IS INCREASED TO ALLOW OPERATING PER CODE. PROVIDE ADDITIONAL WIRES FOR SWITCHING AS REQUIRED.
- I. REFER TO LIGHTING FIXTURE SCHEDULE FOR LIGHT FIXTURE TYPES AND REQUIREMENTS.
- J. LIGHT FIXTURES SHOWN WITH EM ARE EMERGENCY FIXTURES.
- K. CONNECT ALL EXIT SIGNS AND EMERGENCY LIGHTING UNITS TO THE INDICATED CIRCUIT WITH A SEPARATE AND UN-SWITCHED CONDUCTOR BYPASSING ALL CONTROLS AND CONTACTORS. REFER TO MANUFACTURER'S WRITTEN INSTRUCTIONS FOR PROPER INSTALLATION AND TESTING.

1. CIRCUIT VIA TIMECLOCK/PHOTOCELL.
2. (1) 3/4" -2 #8 & 1 #10 GND.



## LIGHTING PLAN - MAIN LEVEL

SCALE : 1/8" = 1'-0"


1







MO COA NO. 201206786 / KS COA NO. E2818  
 1925 CENTRAL STREET, SUITE 201  
 KANSAS CITY, MO 64108  
 phone: (816) 272-5289  
 email: jsmothers@isoengineers.com



DOUGLAS  
| CORNER |  
LOT 1B, LEES SUMMIT, MISSOURI 64086

This drawing has been provided as an instrument of service by the architect, or under his supervision and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Architect. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Architect is strictly prohibited.

©COPYRIGHT 2018 GUY  
CROWNEBC ARCHITECTS P.C.

REV#	DATE	DESCRIPTION

PERMIT SET: 08-11-2021


JSC PROJECT# 18-142

## ELECTRICAL POWER PLAN

### E3

- A. DRAWINGS ARE DIAGRAMMATIC AND SHALL NOT BE SCALED. REFER TO ARCHITECTURAL PLANS OR FIELD MEASUREMENTS FOR DIMENSIONS.
- B. ALL WORK SHALL COMPLY WITH THE LATEST ADOPTED EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70) AND ALL LOCAL BUILDING CODES AND AMENDMENTS.
- C. ALL ROOF AND WALL PENETRATIONS SHALL BE COORDINATED WITH THE GENERAL CONTRACTOR. PROVIDE ALL REQUIRED SLEEVES, FLASHINGS, CURBS, REINFORCED ANGLES, SUPPORTING FRAMES, ETC. UNLESS THEY ARE SPECIFICALLY CALLED OUT TO BE FURNISHED BY OTHERS.
- D. COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACE AVAILABLE, AND WITHOUT INTERFERENCES.
- E. THIS CONTRACTOR SHALL PERFORM ALL WORK INDICATED AND/OR AS REQUIRED FOR THE PROPER INSTALLATION AND OPERATION OF THE ELECTRICAL SYSTEMS.
- F. THE ELECTRICAL SYSTEM DESIGN IS BASED IN PART ON THE SPECIFIED HVAC EQUIPMENT. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE THE EXACT LOCATIONS AND ELECTRICAL REQUIREMENTS OF ALL HVAC EQUIPMENTS WHEN FURNISHED. ANY CHANGES TO THE ELECTRICAL SYSTEM DUE TO HVAC EQUIPMENT SUBSTITUTIONS SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.
- G. ALL POWER WIRING SHALL BE BY THE ELECTRICAL CONTRACTOR. ALL CONTROL WIRING SHALL BE ROUTED BY THE ELECTRICAL CONTRACTOR WITH FINAL CONTROL DEVICE (T-STATS) LANDINGS BY THE MECHANICAL CONTRACTOR.
- H. ALL WIRING SHALL BE IN APPROVED RACEWAY.
- I. WIRE SIZE SHALL BE MINIMUM #12 AWG. THINN SOLID COPPER UNLESS OTHERWISE NOTED. PROVIDE GROUND WIRE WHERE REQUIRED BY CODE. INCREASE WIRE SIZE TO COMPENSATE FOR VOLTAGE DROP WHERE TOTAL LENGTH OF ANY BRANCH EXCEEDS 100 FEET.
- J. MAXIMUM NUMBER OF UNGROUNDED WIRES IN ANY CONDUIT SHALL BE THREE. ADDITIONAL WIRES ARE ACCEPTABLE IF WIRE SIZE IS INCREASED TO ALLOW FOR DERATING PER CODE. PROVIDE ADDITIONAL WIRES FOR SWITCHING AS REQUIRED.
- K. FIRE ALARM, AUDIO/VIDEO AND SURVEILLANCE SYSTEMS BY OTHERS.
- L. ALL PORTIONS OF WORK SHALL BE DONE IN ACCORDANCE WITH APPLICABLE LOCAL, STATE, AND NATIONAL CODES, ORDINANCES, AND STANDARDS.
- M. VERIFY ALL EQUIPMENT LOCATIONS WITH OWNER PRIOR TO ROUGH-IN.

1. CONDUIT AND FEEDERS FROM UTILITY TRANSFORMER TO BUILDING ELECTRICAL SERVICE FOR 'MSI'. COORDINATE ROUTE OF TRENCHING WITH CIVIL DRAWINGS PRIOR TO BID. REFER TO SHEET E4 FOR ADDITIONAL INFORMATION.
2. PROVIDE 2"C TO PROPERTY LINE FOR BUILDING TELEPHONE SERVICES. TERMINATE AT LOCATION DIRECTED BY LOCAL SERVICE PROVIDER.
3. COORDINATE QUANTITY OF TAMPER/FLOW SWITCHES WITH FIRE PROTECTION CONTRACTOR.
4. (1) 3/4" -2 #8 & 1 #10 GND.
5. CIRCUIT VIA TIMECLOCK/PHOTOCELL.
6. PROVIDE JBOX FOR TENANT SIGNAGE. COORDINATE MOUNTING HEIGHT WITH ARCHITECTURAL ELEVATIONS.



## POWER PLAN - MAIN LEVEL

SCALE : 1/8" = 1'-0"

1





