

Project Information

Energy Code: 2018 IECC

Project Title: SWIG - Lees Summit Location: Lees Summit, Missouri

Climate Zone: 4a

Project Type: New Construction

Vertical Glazing / Wall Area: 2%

Construction Site: 400 NW Chipman Road Lees Summit, Missouri 64086 Owner/Agent: Star Development Missouri

SCOTT OLSON ARCHITECT 1916 Nw 79th Ter

Designer/Contractor:

Kansas City, Missouri 64151

8162252660 olsonagkc@aol.com

Additional Efficiency Package(s)

Credits: 1.0 Required 1.0 Proposed Enhanced Envelope Performance, 1.0 credit

Building Area Floor Area

1-Dining: Cafeteria/Fast Food : Nonresidential 650

Envelope Assemblies

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U- Factor _(a)
Floor: Unheated Slab-On-Grade Fully insulated (uniform R-value across perimeter + under entire slab), [Bldg. Use 1 - Dining: Cafeteria/Fast Food] (c) Roof: Insulation Entirely Above Deck, [Bldg. Use 1 - Dining:	112		8.0	0.400	0.540
Cafeteria/Fast Food]	650		30.0	0.032	0.032
NORTH North Walk-Up Ext. Wall: Wood-Framed, 16in. o.c., [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	208	19.0	6.0	0.046	0.064
Walk Up Window: Metal Frame with Thermal Break: Operable, Perf. Specs.: Product ID Kawneer, SHGC 0.22, PF 0.53, VT 0.30, [Bldg. Use 1 - Dining: Cafeteria/Fast Food] (b)	7			0.250	0.450
EAST East Drive-Up Ext. Wall: Wood-Framed, 16in. o.c., [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	520	19.0	6.0	0.046	0.064
Window: Metal Frame with Thermal Break: Fixed, Perf. Specs.: Product ID Kawneer, SHGC 0.22, PF 0.53, VT 0.30, [Bldg. Use 1 - Dining: Cafeteria/Fast Food] (b)	6			0.250	0.380
Window: Metal Frame with Thermal Break: Fixed, Perf. Specs.: Product ID Kawneer, SHGC 0.22, PF 0.53, VT 0.30, [Bldg. Use 1 - Dining: Cafeteria/Fast Food] (b)	6			0.250	0.380
Window: Metal Frame with Thermal Break: Operable, Perf. Specs.: Product ID Kawneer, SHGC 0.22, PF 0.53, VT 0.30, [Bldg. Use 1 - Dining: Cafeteria/Fast Food] (b)	6			0.250	0.450
SOUTH South Ext. Wall: Wood-Framed, 16in. o.c., [Bldg. Use 1 - Dining:	208	19.0	6.0	0.046	0.064

Project Title: SWIG - Lees Summit Report date: 08/18/23

Data filename: Page 1 of 9

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U- Factor _(a)
Cafeteria/Fast Food]					
Door: Insulated Metal, Non-Swinging, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	21			0.370	0.179
WEST					
West Ext. Wall: Wood-Framed, 16in. o.c., [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	520	19.0	6.0	0.046	0.064
Window: Metal Frame with Thermal Break: Fixed, Perf. Specs.: Product ID Kawneer, SHGC 0.22, PF 0.53, VT 0.30, [Bldg. Use 1 - Dining: Cafeteria/Fast Food] (b)	7			0.250	0.380

- (a) Budget U-factors are used for software baseline calculations ONLY, and are not code requirements.
- (b) Fenestration product performance must be certified in accordance with NFRC and requires supporting documentation.
- (c) Slab-On-Grade proposed and budget U-factors shown in table are F-factors.

Envelope PASSES: Design 7% better than code

Envelope Compliance Statement

Compliance Statement: The proposed envelope design represented in this document is consistent with the building plans,

designed to meet the 2018 IECC requirements in COM <i>check</i> Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.				
Name - Title	Signature	Date		

Project Title: SWIG - Lees Summit Report date: 08/18/23

Data filename: Page 2 of 9

COMcheck Software Version COMcheckWeb Inspection Checklist

Energy Code: 2018 IECC

Requirements: 96.0% were addressed directly in the COMcheck software

Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Plan Review	Complies?	Comments/Assumptions
C103.2 [PR1] ¹	Plans and/or specifications provide all information with which compliance can be determined for the building envelope and document where exceptions to the standard are claimed.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
C402.4.1 [PR10] ¹	The vertical fenestration area <= 30 percent of the gross above-grade wall area.	□Complies □Does Not □Not Observable □Not Applicable	
C402.4.1 [PR11] ¹	The skylight area <= 3 percent of the gross roof area.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
C402.4.2 [PR14] ¹	In enclosed spaces > 2,500 ft2 directly under a roof with ceiling heights >15 ft. and used as an office, lobby, atrium, concourse, corridor, storage, gymnasium/exercise center, convention center, automotive service, manufacturing, non-refrigerated warehouse, retail store, distribution/sorting area, transportation, or workshop, the following requirements apply: (a) the daylight zone under skylights is >= half the floor area; (b) the skylight area to daylight zone is >= 3 percent with a skylight VT >= 0.40; or a minimum skylight effective aperture >= 1 percent.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
C406 [PR9] ¹	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the additional energy efficiency package options.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

	1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)
--	---	----------------------	---	------------------------	---	---------------------

Project Title: Report date: 08/18/23 SWIG - Lees Summit Data filename: 3 of 9 Page

Section # & Req.ID	Footing / Foundation Inspection	Complies?	Comments/Assumptions
C303.2 [FO4] ²	Slab edge insulation installed per manufacturer's instructions.	\square Complies \square Does Not	Requirement will be met.
		□Not Observable □Not Applicable	
C303.2.1 [FO6] ¹	Exterior insulation protected against damage, sunlight, moisture, wind,	\square Complies \square Does Not	Requirement will be met.
	landscaping and equipment maintenance activities.	□Not Observable □Not Applicable	
C105 [FO3] ²	and R-value consistent with insulation	□Complies □Does Not	See the Envelope Assemblies table for values.
	specifications reported in plans and COMcheck reports.	□Not Observable □Not Applicable	
C402.2.4 [FO7] ²	Slab edge insulation depth/length. Slab insulation extending away from	□Complies □Does Not	Requirement will be met.
	building is covered by pavement or >= 10 inches of soil.	□Not Observable □Not Applicable	See the Envelope Assemblies table for values.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: SWIG - Lees Summit Report date: 08/18/23
Data filename: Page 4 of 9

Section # & Req.ID	Framing / Rough-In Inspection	Complies?	Comments/Assumptions
C303.1.3 [FR12] ²	Fenestration products rated in accordance with NFRC.	□Complies □Does Not	Exception: Default values are used.
		□Not Observable □Not Applicable	
C303.1.3 [FR13] ¹	Fenestration products are certified as to performance labels or certificates	\square Complies \square Does Not	Requirement will be met.
	provided.	□Not Observable □Not Applicable	
C402.4.3 [FR10] ¹	Vertical fenestration SHGC value.	□Complies □Does Not	See the Envelope Assemblies table for values.
		□Not Observable □Not Applicable	
C402.4.3.	Installed vertical fenestration U-factor and SHGC consistent with label	□Complies □Does Not	See the Envelope Assemblies table for values.
4 [FR8] ¹	specifications and as reported in plans and COMcheck reports.	□Not Observable □Not Applicable	
C402.5.1. 2.2	The building envelope contains a continuous air barrier that is sealed in	□Complies □Does Not	Requirement will be met.
[FR20] ¹	an approved manner and average assembly air leakage <= 0.04 cfm/ft2. Air barrier penetrations are sealed in an approved manner.	□Not Observable □Not Applicable	
C402.5.4	Factory-built fenestration and doors are labeled as meeting air leakage	□Complies □Does Not	Requirement will be met.
[FR18] ³	requirements.	□Not Observable □Not Applicable	
C402.5.7 [FR17] ³	Vestibules are installed on all building entrances. Doors have self-closing	□Complies □Does Not	Exception: Requirement does not apply.
	devices.	□Not Observable □Not Applicable	

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: SWIG - Lees Summit Report date: 08/18/23
Data filename: Page 5 of 9

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C402.5.5, C403.2.4. 3 [ME3] ³	Stair and elevator shaft vents have motorized dampers that automatically close. Refernece section C403.7.7 for operational details.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
C403.7.7 [ME58] ³	Outdoor air and exhaust systems have motorized dampers that automatically shut when not in use and meet maximum leakage rates. Check gravity dampers where allowed. Reference section language for operational details.		Exception: Requirement does not apply.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: SWIG - Lees Summit Report date: 08/18/23
Data filename: Page 6 of 9

Section # & Req.ID	Rough-In Electrical Inspection	Complies?	Comments/Assumptions
C405.6 [EL26] ²	Low-voltage dry-type distribution electric transformers meet the minimum efficiency requirements of Table C405.6.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	Exception: Requirement does not apply.
C405.7 [EL27] ²	Electric motors meet the minimum efficiency requirements of Tables C405.7(1) through C405.7(4). Efficiency verified through certification under an approved certification program or the equipment efficiency ratings shall be provided by motor manufacturer (where certification programs do not exist).	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
	Escalators and moving walks comply with ASME A17.1/CSA B44 and have automatic controls configured to reduce speed to the minimum permitted speed in accordance with ASME A17.1/CSA B44 or applicable local code when not conveying passengers.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
C405.9 [EL29] ²	Total voltage drop across the combination of feeders and branch circuits <= 5%.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: SWIG - Lees Summit Report date: 08/18/23
Data filename: Page 7 of 9

Section #	Insulation Inspection	Complies?	Comments/Assumptions
& Req.ID C303.1 [IN3] ¹	Roof insulation installed per manufacturer's instructions. Blown or poured loose-fill insulation is installed only where the roof slope is <=3 in 12.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	Requirement will be met.
C402.2.1 [IN20] ¹	e e e e e e e e e e e e e e e e e e e		Exception: Requirement does not apply.
C303.1 [IN10] ²	Building envelope insulation is labeled		Requirement will be met.
C303.2 [IN7] ¹	Above-grade wall insulation installed per manufacturer's instructions.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
C402.1.3 [IN19] ³	Non-swinging opaque doors have R-4.75 insulation.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	Requirement will be met.
C105 [IN6] ¹	Installed above-grade wall insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports.	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
C402.2.3 [IN8] ²		☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	See the Envelope Assemblies table for values.
C402.2.6 [IN18] ³	Radiant panels and associated components, designed for heat transfer from the panel surfaces to the occupants or indoor space are insulated with a minimum of R-3.5.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
C105 [IN2] ¹	Installed roof insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports. For some ceiling systems, verification may need to occur during Framing Inspection.	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
C402.5.1. 1 [IN1] ¹	•	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: SWIG - Lees Summit Report date: 08/18/23
Data filename: Page 8 of 9

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C402.5.6 [FI37] ¹	Weatherseals installed on all loading dock cargo door openings and provide direct contact along the top and sides of vehicles parked in the doorway.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	Exception: Requirement does not apply.
C402.5.8 [FI26] ³	Recessed luminaires in thermal envelope to limit infiltration and be IC rated and labeled. Seal between interior finish and luminaire housing.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	Exception: Requirement does not apply.
C408.1.1 [FI57] ¹	Building operations and maintenance documents will be provided to the owner. Documents will cover manufacturers' information, specifications, programming procedures and means of illustrating to owner how building, equipment and systems are intended to be installed, maintained, and operated.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: SWIG - Lees Summit Report date: 08/18/23
Data filename: Page 9 of 9