

Abby Jewell DDS


ORTHODONTICS

2070 NW LOWENSTEIN DR, Unit A, LEES SUMMIT, MO 64081

GENERAL NOTES

1. MAINTAIN ACCESS TO EXISTING WALKWAYS, CORRIDORS, AND OTHER ADJACENT OCCUPIED OR USED FACILITIES. DO NOT CLOSE OR OBSTRUCT WALKWAYS, CORRIDORS, OR OTHER OCCUPIED OR USED FACILITIES WITHOUT PERMISSION FROM TENANT.
2. DEFINITIONS:
 - 2.1. REMOVE AND DISCARD: DETACH ITEMS FROM EXISTING CONSTRUCTION AND LEGALLY DISPOSE OF THEM OFF-SITE.
 - 2.2. REMOVE AND SALVAGE: DETACH ITEMS FROM EXISTING CONSTRUCTION AND TURN OVER TO TENANT UNDAMAGED.
 - 2.3. RELOCATE: DETACH ITEMS FROM EXISTING CONSTRUCTION, MOVE ITEMS INTACT AND UNDAMAGED, AND REINSTALL THEM WHERE INDICATED.
 - 2.4. EXISTING TO REMAIN: EXISTING ITEMS OF CONSTRUCTION THAT ARE NOT TO BE REMOVED, BUT ARE TO REMAIN IN PLACE AND BE UNDAMAGED.
 - 2.5. REMOVE AND RECLAIM: DETACH ITEMS FROM EXISTING CONSTRUCTION. AT CONTRACTOR'S OPTION, ITEM MAY BE REUSED AS PART OF NEW WORK. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO INVENTORY ITEMS TO DETERMINE IF ITEMS WILL FUNCTION AND APPEAR LIKE THE NEW ITEMS SPECIFIED AND CALLED OUT ON THESE DOCUMENTS. IF ITEMS ARE REUSED, CONTRACTOR IS TO CLEAN, REPAIR, OR OTHERWISE BRING ITEMS TO LIKE NEW CONDITION. MODIFY REUSED ITEMS AS REQUIRED AND SUPPLEMENT WITH MATERIALS AND INCIDENTALS NECESSARY TO EXECUTE A COMPLETE WORKMANLIKE JOB. IF CONTRACTOR CHOOSES TO NOT REUSE ITEM, LEGALLY DISPOSE OF ITEM OFF-SITE AND REPLACE WITH NEW TO MATCH EXISTING.
 - 2.6. PROVIDE: THE MEANING OF THE WORD "PROVIDED" INCLUDES, BUT IS NOT LIMITED TO, FURNISHED, DELIVERED, INSTALLED, FINISHED, MADE FULLY OPERABLE AND COMPLETE. UNLESS SPECIFICALLY NOTED OTHERWISE, ALL WORK DESCRIBED IN THESE DOCUMENTS IS TO BE PROVIDED BY THE CONTRACTOR.
3. CONTRACTOR IS TO INCLUDE AS PART OF HIS SCOPE ALL CUTTING AND PATCHING REQUIRED THROUGH CAREFUL EVALUATION OF THE EXISTING SITE AND THE CONSTRUCTION DOCUMENTS. CONTRACTOR SHALL COORDINATE THE CUTTING AND PATCHING OF EXISTING CONSTRUCTION NECESSARY TO PERMIT INSTALLATION OR PERFORMANCE OF THE WORK INDICATED IN THESE CONSTRUCTION DOCUMENTS. SAW-CUT CONC. SLAB AS REQUIRED FOR UTILITIES, FOR EQUIPMENT AND SINKS. VERIFY ROUTE AND TRENCH DEPTH IN FIELD. PATCH BACK WITH MATCHING SLAB THICKNESS OVER SAME MATERIAL, COMPACT UNDERLYING MATERIALS TO MEET BEST PRACTICES. DOVEL NEW TO EXISTING WITH #4 REBAR AT 30" OC.
4. WHERE WALLS, CASEWORK, FINISHES, EQUIPMENT OR OTHER ITEMS AND CONSTRUCTIONS HAVE BEEN REMOVED EXPOSING UNDERLYING WALL AND/OR FLOOR SURFACES, SUCH SURFACES ARE TO BE PATCHED AND REPAIRED AS REQUIRED TO ACCEPT NEW FINISHES. ALL HOLES, DAMAGES, DEFECTS, ETC. IN EXISTING SURFACES ARE TO BE PATCHED TO MATCH EXISTING CONDITIONS.
5. EXISTING CONDITIONS SHOWN ON THESE DRAWINGS ARE BASED UPON BASE BUILDING OR OTHER CONSTRUCTION DOCUMENTS MADE AVAILABLE TO THE DESIGNER BY THE BUILDING MANAGEMENT. ALL AS-BUILT ARCHITECTURAL CONDITIONS HAVE NOT BEEN FIELD VERIFIED AND MAY VARY FROM THOSE SHOWN.
6. PRIOR TO BID: FIELD VERIFY ALL EXISTING CONSTRUCTION TO REMAIN AND INCLUDE COSTS FOR REPAIR AND RECONDITION OF ALL EXISTING CONSTRUCTION TO REMAIN SO THAT IT MEETS THE AESTHETIC AND FUNCTIONAL STANDARD OF QUALITY FOR NEW CONSTRUCTION. BLEND AND MATCH EXISTING CONSTRUCTION WITH NEW CONSTRUCTION. PRIOR TO BID, ADVISE TENANT OF ANY CONDITIONS WHICH CANNOT BE REPAIRED OR RECONDITIONED, BLENDED AND MATCHED. NOTE CONTRACT DOCUMENT REQUIREMENTS FOR EXISTING CONSTRUCTION AND INCLUDE COSTS FOR THIS WORK IN BID PROPOSAL.
7. THE GENERAL CONTRACTOR SHALL, IN THE BIDDING PROCESS, REQUIRE THAT MECHANICAL AND ELECTRICAL SUBCONTRACTORS MAKE A THOROUGH FIELD INSPECTION OF AS-BUILT CONDITIONS OF EXISTING SYSTEMS. AFTER SUCH FIELD VERIFICATION HAS BEEN COMPLETED, THE GENERAL CONTRACTOR AND SUBCONTRACTORS SHALL PROVIDE IN THEIR BIDS, ANY MODIFICATIONS TO THE EXISTING SYSTEMS WHICH MAY BE REQUIRED TO ACCOMMODATE THE PROPOSED REQUIREMENTS FOR THIS TENANT. IF A DETERMINATION OF SUCH MODIFICATIONS CANNOT BE MADE, THE GENERAL CONTRACTOR SHALL NOTIFY THE TENANT, AND AT THE DIRECTION OF THE TENANT, PROVIDE AN AGREED UPON ALLOWANCE TO COVER SUCH WORK.
8. COMMENCING WORK BY A CONTRACTOR OR SUBCONTRACTOR CONSTITUTES ACCEPTANCE OF THE UNDERLYING CONDITIONS AND SURFACES. PRIOR TO PROCEEDING WITH THE WORK, PREPARE EXISTING AND NEW UNDERLYING CONDITIONS AND SUBSTRATE TO COMPLY WITH THE CONTRACT DOCUMENTS, INDUSTRY STANDARDS AND MANUFACTURER'S RECOMMENDATION.
9. FIELD VERIFY ALL ROUGH OPENINGS AND WALL WIDTHS PRIOR TO ORDERING OR FABRICATION OF MATERIALS.
10. DIMENSIONS ARE NOMINAL AND TO THE FACE OF PARTITIONS.
11. CLEAN-UP OF RUBBISH AND DEBRIS RESULTING FROM DEMOLITION AND NEW WORK SHALL BE COLLECTED REGULARLY FROM PROJECT SITE AND LEGALLY DISPOSED.
12. ALL WEATHER EXPOSED SURFACES SHALL HAVE A WEATHER RESISTIVE BARRIER TO PROTECT THE INTERIOR WALL COVERING AND EXTERIOR OPENINGS SHALL BE FLASHED IN SUCH A MANNER AS TO MAKE THEM WEATHERPROOF.
13. BUILDING ADDRESS NUMBERS SHALL BE PROVIDED AND PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY. THESE NUMBERS SHALL CONTRAST WITH THEIR BACKGROUND. IN MULTI-TENANT COMMERCIAL BUILDING WHERE TENANTS HAVE MULTIPLE ENTRANCES LOCATED ON DIFFERENT SIDES OF THE BUILDING, EACH DOOR SHALL BE ADDRESSED. ADDRESS NUMBERS SHALL BE ARABIC NUMERALS OR ALPHABET LETTERS. NUMBERS SHALL BE A MINIMUM OF 4 INCHES (102 MM) HIGH WITH A MINIMUM STROKE WIDTH OF 0.5 INCH (12.7 MM).
14. CONTRACTORS ARE RESPONSIBLE FOR ALL MATERIALS AND QUANTITIES SHOWN IN THESE DRAWINGS GRAPHICALLY AS WELL AS THOSE CALLED FOR BY NOTE.
15. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS TO COMPLETE THE PROPOSED WORK AND SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS.
16. THE TENANT OR THE TENANT'S DESIGNATED REPRESENTATIVE WILL PROVIDE SERVICES IN CONNECTION WITH ADMINISTRATION OF THE CONTRACT.
17. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL LOCAL LAWS, ORDINANCES, RULES AND REGULATIONS OF THE GOVERNING AGENCIES HAVING JURISDICTION.
18. THE CONTRACTOR MUST TAKE ADEQUATE CARE TO PROTECT ALL AREAS OF THE BUILDING WHERE THE WORK OF THIS PROJECT IS LOCATED AS WELL AS THE AREAS ADJACENT TO THE AREA OF THE WORK OF THIS PROJECT SO AS TO PREVENT DAMAGE TO LIFE OR PROPERTY AS A RESULT OF THIS CONSTRUCTION PROJECT.
19. ONLY MATERIALS THAT ARE NEW, UNUSED, FREE FROM DEFECTS, AND THE BEST OF THEIR RESPECTIVE KINDS SHALL BE USED. THE BASIS OF QUALITY SHALL BE THE LATEST STANDARDS OF ASTM, ASA OR ASHRA.



BUILDING KEY PLAN



CODE NOTES


- A. ALL CONSTRUCTION FOR THIS PROJECT SHALL BE PERFORMED UNDER THE PROVISIONS OF FOLLOWING LIST OF CODES, AS AMENDED BY THE CITY OF LEES SUMMIT, MISSOURI:
- A.1. 2018 INTERNATIONAL BUILDING CODE
 - A.2. 2018 INTERNATIONAL PLUMBING CODE
 - A.3. 2018 INTERNATIONAL MECHANICAL CODE
 - A.4. 2018 INTERNATIONAL FUEL GAS CODE
 - A.5. 2018 INTERNATIONAL RESIDENTIAL CODE
 - A.6. 2018 INTERNATIONAL FIRE CODE
 - A.7. 2011 NATIONAL ELECTRICAL CODE
 - A.8. ICC/ANSI A117.1-2017, ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES
- B. USE, OCCUPANCY CLASSIFICATION, AND TYPE OF CONSTRUCTION:
- B.1. TENANT USE: PROFESSIONAL SERVICES - MEDICAL OFFICE
 - B.2. TENANT OCCUPANCY CLASSIFICATION: B - BUSINESS
 - B.3. BUILDING TYPE OF CONSTRUCTION: VB
- C. TENANT SQUARE FOOT CALCULATIONS:
- C.1. GROSS TENANT AREA = 2,563 SF
 - C.2. OCCUPIED AREA = INSIDE FACE OF WALLS = 2,317 SF
- D. FIRE PROTECTION SYSTEMS:
- D.1. AUTOMATIC SPRINKLER SYSTEMS: NONE PROVIDED.
 - D.2. FIRE ALARM AND DETECTION SYSTEMS: NONE PROVIDED.
- E. TENANT OCCUPANT LOAD (TABLE 1003.2.2.2):
- E.1. $2317\text{SF} \div 100\text{SF/F} = 23.17 \approx 24$ OCCUPANTS
- F. SPACES WITH ONE EXIT OR EXIT ACCESS DOORWAY (TABLE 1006.2.1): COMMON PATH OF EGRESS TRAVEL IN GROUP B OCCUPANCY WITHOUT SPRINKLER SYSTEM IN A SPACE WITH OCCUPANT LOAD OF ≤ 30 , THE LENGTH OF COMMON EGRESS TRAVEL SHALL NOT BE MORE THAN 100 FEET.
- G. DOOR SWING (SECTION 1010.1.2): EGRESS DOORS SHALL BE OF THE PIVOTED OR SIDE-HINGED SWING TYPE EXCEPT IN OTHER THAN GROUP H OCCUPANCIES MANUALLY OPERATED HORIZONTAL SLIDING DOORS ARE PERMITTED IN A MEANS OF EGRESS FROM SPACES WITH AN OCCUPANT LOAD OF 10 OR LESS.

AREA MAP



09/20/23

GUY GRONBERG
ARCHITECTS, P.C.
113 SE 24th St.
Lees Summit, MO 64063
Phone: 916.524.0970
Fax: 916.524.0570



Abby Jewell DDS
ORTHODONTICS
2070 NW LOWENSTEIN DR, Unit A, LEES SUMMIT, MO 64081

This drawing has been provided as a guide only. It is not intended to be used as a contract document. The user of this drawing is responsible for obtaining all necessary permits and for verifying the accuracy of the information contained herein. The user of this drawing is also responsible for obtaining all necessary insurance and for obtaining all necessary approvals from the appropriate authorities.

REV#	DATE	DESCRIPTION
1	09/20/23	APPENDIX #1
2	09/20/23	APPENDIX #2
Issue Date: 09-07-23		
Project #: 23016		

COVER SHEET

CS

DIVISION 1 - GENERAL REQUIREMENTS

1. GENERAL REQUIREMENTS 01000
2. The General Conditions of the Contract for Construction of A.I.A. Document A201, latest edition, forms part of this contract as if herein bound.
3. Satisfy all applicable local codes and ordinances. Reference the cover sheet for list of codes.
4. Contractor to pay for Construction Permit Fees, Excise Tax, Tap Fees, Ect. as applicable to the local Municipalities and Utility Companies.
5. Contractor is to meet all Building Owner Standards and Instructions for work.

PRODUCTS 01600

1. Where a specific manufacturer's product is named including make or model number or other designation, it has been selected to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics of the product. Unless otherwise indicated, provided the named product or a product that is equal to or exceeds the specified product.
2. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft. Comply with manufacturer's written instructions.
3. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
4. All products, and materials used in conjunction with, are to be installed in strict conformance with manufacturers instruction.

SPECIAL CONDITIONS 01700

1. General Contractor shall provide all water, light, and power necessary during construction until the completion of the building. All extensions, controls, and equipment beyond the points of temporary service shall be provided under the work of the respective Division requiring the same.
2. The General Contractor shall do all final cleaning of the building construction areas and wash windows.

CUTTING AND PATCHING

1. Contractor is to include as part of his scope all cutting and patching required through careful evaluation of the existing site and the construction documents. All holes, damages, defects, ect. in existing surfaces are to be patched to match existing conditions. Contractor shall coordinate the cutting of existing construction necessary to permit installation or performance of other Work.
2. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations. Patch with durable seams that are as invisible as possible. Use materials identical to existing materials. If identical materials are unavailable or cannot be used, use materials that, when installed, will match the visual and functional performance of existing materials. For exposed surfaces, use materials that visually match existing adjacent surfaces to the fullest extent possible. Before patching, verify compatibility with and suitability of substrates, including compatibility with existing and new finishes or primers.
3. Cutting: Cut existing construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots as small as possible, neatly to size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use. Provide temporary support of Work to be cut. Cut concrete using a cutting machine, such as an abrasive saw or a diamond-core drill.

DIVISION 2 - SITE WORK

NO WORK THIS SECTION

DIVISION 3 - CONCRETE

REFER TO CUTTING AND PATCHING

DIVISION 4 - MASONRY

NO WORK THIS SECTION

DIVISION 5 - METALS

METAL STUD FRAMING

1. Metal Studs and Runners: shall be as manufactured by Dietrich, Inryco/Milcor, USC, or approved equal. Studs shall be sized as indicated on the drawings and of gauge recommended by the manufacturers literature. Double studs at door jams shall be 20 gauge minimum. Standard stud spacing at no more than 16" O.C. unless otherwise noted on drawings.
2. At all walls indicated to extend to underside of decking provide Dietrich SLP-TRK slotted deflection track. Install and finish per manufacturer's recommendations.

DIVISION 6 - WOODS AND PLASTIC

CARPENTRY

1. Each piece of framing lumber shall be identified by the trademark of an approved inspection agency or association. Wood framing and all rough carpentry items shall be installed in accordance with UBC and/or FHA requirements whichever is most restrictive.

DIVISION 7 - THERMAL AND MOISTURE PROTECTION

INSULATION

1. Where insulating materials listed below will not be covered with gypsum board substitute specified insulation w/ product of same thickness and R-value and similar facing, but such shall have a flame spread rating of 25 or less and a smoke developed rating of 50 or less when tested in accordance with ASTM E84 unless more stringent requirements are listed for a specific product.
2. Insulation Schedule

2.1. Exterior Walls: batts of fiberglass with foil skim kraft (FSK) vapor barrier in thickness to match cavity depth

2.2. Gaps and voids around door and window areas and in built up wood lintels.Minimal expanding foam insulation shall be Dow Chemical Great Stuff. It is to be Tack Free in 20 minutes and with full cure in 8 hours at room temperature and 50% relative humidity. It is to be paintable and stainable.

2.3. Interior non-loadbearing walls: Unfaced Fiberglass Batts - Certainteed CertaPRO AcoustaTherm Batts in thickness to fill entire cavity.

SEALANTS

1. Mildew-Resistant Silicone Rubber Sealant: Silicone rubber-based, one part elastomeric sealant, complying with F5 TT-S-0021543, Class A, compounded specifically for mildew resistance and recommended by manufacturer for interior joints in wet areas; passing ANSI A136.1 test for mold growth.
2. Silicone Sealant: One-part nonacid-curing silicone sealant complying with ASTM C920; Type S, Grade NS, Class 25, paintable, for uses at casings, window casings and hollow metal to drywall and masonry.
3. Joints and spaces to be caulked shall be clean, dry and free of dust, loose mortar or other foreign materials. After joints have been filled, they shall be neatly tooled to eliminate air pockets or voids and to provide a smooth, neat appearing surface.
4. Non-Elastomeric Sealants and Caulking Compounds: 1-component acrylic sealant: F5-TT-S-00230, Class B, Type 11, solvent based solids 45% acrylic for uses at exterior window and door frame perimeters and flashing

DIVISION 8 - DOORS AND WINDOWS

PLASTIC LAMINATE CLAD DOORS

1. Single swing interior doors shall be solid core premium grade plastic laminate clad with matching edges. Plastic Laminate to be Wilsonart wood look laminate with fine grain T5 premium Finish as selected by interior designer. Comply with requirements of ANSI/NWMA I.S. 1 and Section 1400 of ANI "Architectural Woodwork Quality Standards" except as otherwise indicated. Coordinate stain color with interior designer.

FINISH HARDWARE

1. Provide finish hardware for all doors in project. The Contractor shall verify all keying requirements with owner prior to installation. Finish to be 264. Hardware mounting heights by the door and hardware Institute "Recommended Locations For Builders Hardware". Comply with all ADA requirements for hardware.

DIVISION 9 - FINISHES

GYPSUM DRYWALL

1. Materials shall meet the following standards:

a. Gypsum Wallboard - ASTM C36

b. Nails - ASTM C380

c. Metal Accessories - ASA A97.1

d. Water Resistant Gypsum Backing Board - ASTM C1278 (paragraph 6.1)
2. Use gypsum board fasteners that are recommended by gypsum board manufacturer except as otherwise indicated.
3. Furnish and install all trim accessories, adhesives and joint treatments per manufacturer's recommendations.
4. All gypsum board to be finished to Level 4 unless noted otherwise.
5. Schedule: (basis of design)

5.1. Interior side of exterior walls: 5/8" Gold Bond XP Gypsum Board. Gypsum Board is to be installed from floor to underside of deck above.

5.2. Interior partitions, ceilings and soffits - general: 5/8" Gold Bond XP Gypsum Board.

5.3. Interior partitions in wet areas/toilet rooms: 5/8" Gold Bond XP Gypsum Board.

5.4. Interior partitions to receive wall tile: 5/8" Gold Bond eXP Tile Backer

5.5. Where called out to receive sound board: 5/8" Gold Bond Sound Break gypsum board. When multiple layers are indicated all joints are to be staggered.

FLOORING GENERAL

1. Patch, level and prepare all floors as recommended by flooring manufacturer for each type of flooring to be placed. Use trowelable leveling and patching compound to fill cracks, holes, and depressions in substrates.Trowelable Leveling and Patching Compounds shall be of Latex-modified, portland cement based or blended hydraulic cement based Formulation provided or approved by floor covering manufacturer for applications indicated.
2. Transitions between floor finishes: Floor Finishes are to be tightly butted together (unless edge protection is specified or is required by the manufacturer.) At all transitions where finished floor height of a flooring is higher then adjacent floor finish, raise adjacent flooring with ROPEE SUBLEVELER TS-1 so finish heights are equal. Where flooring is to be tightly butted against ceramic or porcelain tile in addition to subleveler installation beneath the thinner floor material, edge protection is to be provided on tile as indicated in the finish legend.

PAINTING GENERAL

1. Paint shall be as manufactured by Sherwin Williams Paints or approved equal.

SURFACE PREPARATION FOR PAINT

1. General: Protect adjacent and underlying surfaces. Remove or mask electrical plates, hardware, light fixture trim, escutcheons, and fittings prior to preparing surfaces of finishing. Correct defects and clean surfaces capable of affecting work of this section. Seal marks that may bleed through surface finishes with compatible sealer.
2. Galvanized Steel: Remove surface contamination and oils and wash with solvent.
3. Uncoated Ferrous Metals: Remove grease, mill scale weld splatter, dirt and rust. Where heavy coatings of scale are evident, remove by hand or power tool wire brushing or sandblasting; wash with solvent. Apply treatment of phosphoric acid solution, ensuring weld joints, bolts and nuts are similarly cleaned. Spot Prime paint after repairs.
4. Shop primed Ferrous Metals: Sand and scrape to remove loose primer and rust. Feather edges to make patches inconspicuous. Clean with solvent. Prime bare steel surfaces.
5. Other existing Surfaces: Remove loose, flaking, powdery, and peeling paints. Light sand painted surfaces. Fill holes, cracks, depressions and other imperfections with compatible patching compound; sand flush with surface. Remove oil, grease, and wax by scraping; solvent wash and thoroughly rinse. Remove rust by wire brushing to expose base metal.

PAINTING SCHEDULE

1. Paint all new interior gypsum board walls:

1.1. 1 ct. PrepRite 200 Latex Primer and

1.2. 2 cts. ProMar 200 Int. Latex Eg-Shel
2. Paint all new and existing interior gypsum board walls in wet areas (Toilet and Janitor Rooms):

2.1. 1 ct. PrepRite 200 Latex Primer and

2.2. 2 cts. Waterbased Catalyzed Epoxy
3. Interior gypsum board ceilings and soffits (unless noted otherwise):

3.1. 1 ct. PrepRite 200 Latex Primer

3.2. 2 cts. ProMar 200 Int. Latex Flat
4. Interior and Exterior Ferrous metal (metal frames, exposed steel structure, misc. metal):

4.1. Touch up factory prime coat with compatible Metal Primer or

4.2. 1 ct. Sprayed All Surface Enamel oil Primer

4.3. 2 cts. Sprayed Promar 200 Int. Alkyd Eg-Shel Enamel

DIVISION 10 - SPECIALTIES

FIRE EXTINGUISHER

1. Provide fire extinguishers as indicated per plan. Fire extinguisher shall be Cosmic BE (2A,10B,C) by J.L Industries or approved equal. Cabinets to be Ambassador by J.L Industries or approved equal, Not Fire-Rated, Two - 10 1/2 x 24 x 5 1/2 inches. Trim Material - Steel, white epoxy primer Finish, Trim Style Semi recessed 3" rolled edge. Door Style - Vertical Duo Panel with pull handle, Door Glazing - Clear Safety Glass, with Die Cut Letters - Vertical Red Reverse.

DIVISION 11 - EQUIPMENT

COORDINATE EQUIPMENT INSTALLATION WITH OWNER AND OWNER'S EQUIPMENT SUPPLIER.

DIVISION 12 - FURNISHINGS

CASEWORK

1. The General Contractor or his Subcontractor shall provide all necessary work to provide plastic laminate casework at locations indicated on these documents. Work under the contract shall include all labor, materials, and incidentals necessary to execute a complete workmanlike job in accordance with the requirements of all applicable codes and ordinances including the Americans with Disabilities Act Guidelines. The General Contractor or his Subcontractor to review shop drawings with Owner to verify casework layout and dimensions.
2. Casework shell units are to be constructed with 3/4" particle board sides and 1/2" particle board backs with plastic laminate on all exterior exposed vertical faces and also on the bottom face of upper wall units. Exposed edges to be .020 polyvinyl chloride impact/chip/mar-resistant edges. All interior surfaces on units with doors/drawers to be 85 gram melamine. For open units interiors to have plastic laminate to match exteriors unless noted otherwise. Base cabinets are to be nominal 24" deep. Upper cabinets are to 14" deep O.A. from back of cabinet at wall to face of doors. Full height cabinets are to be 26" deep unless noted otherwise. Full height cabinets are to be constructed with solid center shelf with doors above and below.
3. Countertops: Outside corners of all countertops to have 1/2" radius.



3.1. Plastic Laminate countertops are to be 1/4" thick with plastic laminate faces and 3mm (1/8") flexible PVC edges. Backsplashes are to be provided, and are to have matching plastic laminate on all exposed faces.

3.2. Solid Surface countertops shall be as indicated on Finish Legend. Surfaces of material are to be adhesively joined with inconspicuous seams. Nominal 1/4" thick matching backsplashes are to be provided.

3.3. Quartz Surfacing shall be as indicated on Finish Legend. Surfaces of material are to be epoxy joined with inconspicuous seams. Nominal 3/4" thick matching backsplashes are to be provided.
4. Plastic Laminate Door, Drawer, and False Front Panels to have plastic laminate faces, 85 gram melamine backs, and 3mm (1/8") high impact resistant PVC edges.
5. Shelving to be 1" particle board fully adjustable on 1-1/4" centers. Edge to be .020 polyvinyl chloride impact/chip/mar-resistant edge. Shelving inside units with doors to have 85 gram melamine on top and bottom. Shelving of open units are to have plastic laminate to match the exterior.
6. Hardware shall be heavy-duty satin chrome. Hinges shall be European concealed heavy duty hinges. All doors over 36" tall to have three hinges. All pulls are to be 4" bent wire pulls, unless otherwise noted. Finish to be 26D. Removable panels are to be secured with Hafele Kaku push fit fasteners.
7. Drawer boxes to be Blum Meta-Box system or Grass UniDrawer (Unless noted otherwise). Slides to have 100 pound load rate. Drawer box depth is to be within 2" of drawer face panel height. Drawers indicated on drawings as FILE are to have white melamine box with KV 8505 slides and Hafele letter width file frame kit.
8. Provide one 2" dia standard plastic grommet with hole liner and slotted cover for every three linear feet of countertop that has knee space below. If knee space is less than three feet wide provide two grommets. Also provide one 2" dia standard plastic grommet at each location with power and/or data installed in cabinet. Color as selected by interior designer. Exact locations of grommets to be established and be confirmed by owner prior to installation.
9. All particle board is to be of 45-pound density particle board. All plastic laminate is to be General Purpose Type 107 H65 laminate as manufactured by Wilsonart or approved equal.
10. Provide fillers to match casework at sides of all casework abutting adjacent vertical surfaces. Also provide filler panels above upper cabinets where distance between upper cabinet and ceiling above is less than 8".



GUY GRONBERG
ARCHITECTS, P.C.
113 SE 24th St.
Lee's Summit, MO 64063
Phone: 816.524.0970
Fax: 816.524.0970



Abby Jewell DDS
ORTHODONTICS
2070 NW LOWENSTEIN DR., Unit A, LEES SUMMIT, MO 64081


This drawing has been provided as an instrument of service by the architect, or instrument of service by the architect, or use on this project only. It is not to be used for any other purpose, including, but not limited to, reprints, reproductions, alterations, or any other use without the written consent of the architect. The architect assumes no responsibility for the accuracy or completeness of the information contained herein, or for the results of any action taken thereon. GUY GRONBERG ARCHITECTS, P.C.

REV#	DATE	DESCRIPTION
1	09/20/23	APPENDIX H1
Issue Date:		09-07-23
Project #:		23016

SPECIFICATIONS

A0

FINISH SCHEDULE									
RM. # 205 #	ROOM NAME	FLOOR	BASE	WALL				NOTES	
				NORTH	EAST	SOUTH	WEST		
100	LOBBY	NVT	B5B	PT1	PT1	PT1	PT1/PT2	1, 2	
101	WAITING	NVT	B5B	PT1	PT1	PT1	PT1	2	
102	CONSULT	NVT	B5B	PT1	PT1	VNC	-	2	
103	HALL	NVT	B5B	-	PT1	VNC	PT1	2	
104	PANO	NVT	B5B	PT1/PT3	-	VNC	PT1	2	
105	TOILET	TL1	TL2	SEE ELEVATIONS 24-21 SHEET A3					
106	TREATMENT	NVT	B5B	PT1	PT1/PT2	PT3	VNC	2	
107	PRIVATE	NVT	B5B	PT1	PT1	VNC	PT1	2	
108	STERILE	NVT	RMB	PT1	PT1	PT1	PT1		
109	HALL	NVT	RMB	PT1	PT1	PT1	PT1		
110	TOILET	NVT	RMB	PT4	PT4	PT4	PT4		
111	EQPT.	CONC	RMB	FRP	FRP	FRP	FRP		
112	I.T.	NVT	RMB	PT1	PT1	PT1	PT1		
113	DRESSING	NVT	RMB	PT4	PT4	PT4	PT4		
114	DOCTOR	NVT	RMB	VNC	PT1	PT1	PT1		
115	LAB	NVT	RMB	PT1	PT1	PT1	PT1		
116	GALLERY	NVT	RMB	PT1	PT1	PT1	PT1		
117	CLOSET	NVT	RMB	PT1	PT1	PT1	PT1		
NOTES									
1. PROVIDE T14" ON FACE OF DESK PER INTERIOR ELEVATIONS. 2. PROVIDE 1" B1" METAL LAMINATE BASE AT TOEICKS OF ALL BASE CABINETS THIS ROOM OR AREA.									
FINISH GENERAL NOTES									
1. FINISH MATERIALS LISTED HERE-IN ARE TO ESTABLISH THE SIGNIFICANT QUALITIES RELATED TO TYPE, FUNCTION, DIMENSION, PRICE, PHYSICAL PROPERTIES, APPEARANCE, AND OTHER CHARACTERISTICS OF THE PRODUCT. FINAL SELECTION OF ALL FINISHES ARE TO BE CONFIRMED BY OWNER OR OWNER'S INTERIOR DESIGNER.									
2. PAINT FINISHES INDICATED TO BE ACCENT COLOR ARE TO BE VERIFIED BY OWNER IN FIELD PRIOR TO BEING APPLIED TO WALLS OR SOFFITS.									
3. WHERE NEW FLOOR FINISHES ARE INDICATED ON THE FINISH SCHEDULE, ANY EXISTING FLOORING IS TO BE REMOVED AND DISCARDED. SUBFLOOR IS TO BE PREPARED AS REQUIRED TO RECEIVE NEW FINISH INDICATED.									
4. PATCH, LEVEL AND PREPARE ALL FLOORS AS RECOMMENDED BY FLOORING MANUFACTURER FOR EACH TYPE OF FLOORING TO BE PLACED. USE TRONELABLE LEVELING AND PATCHING COMPOUND TO FILL CRACKS, HOLES, AND DEPRESSIONS IN SUBSTRATES. TRONELABLE LEVELING AND PATCHING COMPOUNDS SHALL BE OF LATEX-MODIFIED, PORTLAND CEMENT BASED OR BLENDED HYDRAULIC CEMENT BASED FORMULATION PROVIDED OR APPROVED BY FLOOR COVERING MANUFACTURER FOR APPLICATIONS INDICATED.									
5. INTERIOR FINISHES MUST CONFORM TO THE GOVERNING CODE FOR "CLASS III" MAX. 25 FOR SMOKE DENSITY CLASSIFICATION. MAX. FLAME SPREAD OF 200									
6. COLOR OF ALL LIGHT SWITCHES, RECEPTACLES AND PLATE COVERS TO BE SELECTED BY INTERIOR DESIGNER.									



WALL TYPE NOTES									
1. FURR-OUT AROUND THE STRUCTURAL COLUMNS AND MECHANICAL CHASES AS REQUIRED. MINIMIZE DEPTH OF FURRING.									
2. PROVIDE SOLID BLOCKING FOR DOORS, WINDOWS, TOILET PARTITION, ACCESSORIES, HANDRAILS, LAVATORY BRACES, CASEWORK, SHELVING ETC. AS REQUIRED BY MANUFACTURER AND ALL WORK DONE BY CARPENTRY AND MILLWORK TRADES. ALL WORK REQUIRED BY BUILDING CODES SHALL MEET ALL REQUIREMENTS TO THE CODE OF UNDERWRITERS LABORATORIES, INC. VERIFY THE DEPTH OF WALLS PRIOR TO INSTALLING RECESSED FIXTURES.									
3. ALL EXPOSED EDGES AND / OR CORNER ON ALL GYPSUM WALL BOARD CONSTRUCTION SHALL HAVE A METAL CORNER TRIM, TAPED AND SPACKLED.									
4. ALL EXISTING TO REMAIN AND NEW GYPSUM BOARD PARTITIONS IN AREA OF WORK TO BE PROPERLY PREPARED, PATCHED, SPACKLED AND SANDED, ETC., TO PROVIDE A SMOOTH FINISH AND AS REQUIRED TO RECEIVE NEW FINISHES.									
5. ALL OPENINGS IN GYPSUM BOARD PARTITIONS SHALL BE DOUBLE STUDDED.									
6. TOP OF ALL WALLS INDICATED IN WALL TYPES THIS SHEET ARE TO BE LATERALLY BRACED AS FOLLOWS: 6.1. FOR WALLS INDICATED TO BE EXTEND TO UNDERSIDE OF STRUCTURAL ELEMENTS OR DECKING: PROVIDE DEEP LEG DEFLECTION TRACK AT TOP OF WALL INSTALLED PER MANUFACTURER'S INSTRUCTIONS. 6.2. FOR ALL OTHER WALLS: 6.2.a. FOR WALLS UNDER 8'-0" IN LENGTH (WITHOUT A PERPENDICULAR WALL ON EITHER SIDE) THE TOP TRACK SHALL RESIST LATERAL LOADS. 6.2.b. FOR WALLS ABOVE 8'-0" AND UNDER 16'-0" CONTRACTOR IS TO PROVIDE 1-1/2" 16GA U-CHANNEL LOCATED IN PUNCHED STUDS WITHIN 1'-0" OF TOP OF WALL AND SECURED WITH DIETRICH EASYCLIP U-SERIES AT EACH STUD. U-CHANNEL TO BE AND IS TO RUN CONTINUOUS FULL LENGTH OF WALL. (AT CONTRACTORS OPTION STUD KICKERS AS INDICATED BELOW MAY BE USED IN LIEU OF U-CHANNEL.) 6.2.c. FOR WALLS ABOVE 16'-0" PROVIDE 45" STUD KICKERS UP TO STRUCTURE AT 4'-0" O.C. ALTERNATING DIRECTIONS.									
7. IN THE FOLLOWING ROOMS PROVIDE MOISTURE RESISTANT GYPSUM BOARD IN LIEU OF THE STANDARD GYPSUM BOARD INDICATED IN WALL TYPES BELOW: TOILET 105, TOILET 110, AND EQUIPMENT 111.									
8. WHERE INDICATED BY PLAN NOTE #1 PROVIDE 6" STUDS IN LIEU OF SIZED INDICATED BY WALL TYPE									
WALL TYPE LEGEND									
EXISTING WALL TO REMAIN.									
3/8" 25 GAUGE MTL. STUDS @ 16" O.C. WITH 3/4" GYPSUM BOARD EACH SIDE AND 3/4" UNFACED BATT INSULATION. TOP TRACK TO BE AT 9'-0" AFF.									
3/8" 25 GAUGE MTL. STUDS @ 16" O.C. WITH 3/4" GYPSUM BOARD EACH SIDE AND 3/4" UNFACED BATT INSULATION. TOP TRACK TO BE AT 9'-4 1/2" AFF.									
3/8" 25 GAUGE MTL. STUDS @ 16" O.C. WITH 3/4" GYPSUM BOARD EACH SIDE AND 3/4" UNFACED BATT INSULATION. TOP TRACK TO BE AT 10'-8" AFF.									


FINISH LEGEND									
EX EXISTING TO REMAIN FINISH									
FLOORING									
NVT LUXURY VINYL TILE, MANNINGTON COMMERCIAL ANTICO WOOD TILE WITH A TQXK FINISH AND INSTALLED IN A RANDOM BOND. INSTALL WITH ANTICO RPB18 ADHESIVE. COLORWAY TO BE SELECTED FROM MANUFACTURERS FULL RANGE.									
BASE									
B5B BASEBOARD - 1/2" x 5/8" FINGER JOINTED PINE OR PRIMED MDF BASE MOLDING - PAINT PT5									
RMB JOHNSONITE 4" COVE BASE, CONTINUOUS COIL, TO MATCH EXISTING WALL BASE.									
L7B METAL PLASTIC LAMINATE BASE. PROVIDE BASE OF METAL PLAS. LAM. LT ON 3/8" MDF. SHIP LOOSE AND INSTALL AFTER FLOORING IS INSTALLED. REFER TO DETAIL 19/A4.									
WALL PROTECTION									
VNC VINYL WALL COVERING: CONTRACTOR SHALL PROVIDE FOR AN ALLOWANCE OF \$2.00 A SQUARE FOOT FOR THE PURCHASE OF THE VNC MATERIAL ONLY. THIS PRICE DOES NOT INCLUDE LABOR, OVERHEAD AND PROFIT, SHIPPING, TAXES, AND MATERIALS FOR INSTALLATION. ALL OF THESE ARE ADDITIONAL TO THE ALLOWANCE AND SHOULD BE ADDED TO THE PRICE AND INCLUDED IN THE BASE BID. INSTALL VNC PER MANUFACTURER'S RECOMMENDATIONS. WRAP VNC AROUND THE ENDS OF THE WALLS.									
FRP FIBERGLASS REINFORCED PANEL. 0.90" THICK WITH WHITE FINISH. INSTALL FROM TOP OF BASE TO 52" AFF. PROVIDE MATCHING PERIMETER TRIM. PAINT WALL ABOVE WITH PT1.									
PAINT COLORS									
NOTE: ALSO REFER TO PAINT SCHEDULE IN SPECIFICATIONS FOR PAINTS.									
PT1 PRIMARY FIELD COLOR: (TO BE DETERMINED)									
PT2 ACCENT COLOR: (TO BE DETERMINED)									
PT3 ACCENT COLOR: (TO BE DETERMINED)									
PT4 EPOXY PAINT COLOR: (TO BE DETERMINED)									
PT5 SOFFIT COLOR: (TO BE DETERMINED)									
PT6 CEILING WHITE: (MATCH WHITE COLOR OF CEILING TILES)									
PT1 METAL FRAMES: (TO BE DETERMINED)									
PT8 MOLDINGS, SILLS, AND BASEBOARDS: (TO BE DETERMINED)									

TITLE									
NOTE: EDGE OF ALL WALL TILE IS TO BE CAPPED WITH SCHLUTER SCHEN ANODIZED ALUMINUM TRIM. WHERE WALL TILE IS INSTALLED ABOVE NON-TILE FLOORING ALSO CAP BOTTOM EDGE OF TILE WITH SCHLUTER SCHEN ANODIZED ALUMINUM TRIM. CAULK JOINT BETWEEN TRIM AND FLOORING. PROVIDE SCHLUTER SCHEN AT EDGE OF ALL FLOOR TILE AT TRANSITION TO CARPET. PROVIDE SCHLUTER RENOV AT EDGE OF ALL FLOOR TILE AT TRANSITION TO FLOORING LESS THAN 1/2" THICK. GROUT FOR TILE IS TO BE TEG POWER GROUT WITH SEPARATE COLOR SELECTED FROM MANUFACTURERS FULL RANGE FOR EACH TYPE OF TILE. SEAL GROUT PER MANUFACTURER'S RECOMMENDATIONS.									
TL1 12" X 24" PORCELAIN FLOOR TILE: TILE IS TO BE SET IN A RUNNING BOND PATTERN. CONTRACTOR SHALL PROVIDE FOR AN ALLOWANCE OF \$7.00 A SQUARE FOOT FOR THE PURCHASE OF THE TILE MATERIAL ONLY. THIS PRICE DOES NOT INCLUDE LABOR, OVERHEAD AND PROFIT, SHIPPING, TAXES, AND MATERIALS FOR INSTALLATION INCLUDING MASTIC AND GROUT. ALL OF THESE ARE ADDITIONAL TO THE ALLOWANCE AND SHOULD BE ADDED TO THE PRICE AND INCLUDED IN THE BASE BID. INSTALL TILE PER MANUFACTURER'S RECOMMENDATIONS.									
TL2 6" X 12" PORCELAIN WALL TILE: TILE IS TO BE SET IN A RUNNING BOND PATTERN. CONTRACTOR SHALL PROVIDE FOR AN ALLOWANCE OF \$7.00 A SQUARE FOOT FOR THE PURCHASE OF THE TILE MATERIAL ONLY AS INDICATED FOR TL1 TILE ABOVE									
TL3 3" X 6" PORCELAIN WALL TILE: TILE IS TO BE SET IN A RUNNING BOND PATTERN. CONTRACTOR SHALL PROVIDE FOR AN ALLOWANCE OF \$5.00 A SQUARE FOOT FOR THE PURCHASE OF THE TILE MATERIAL ONLY AS INDICATED FOR TL1 TILE ABOVE									
TL4 MOSAIC WALL TILE: CONTRACTOR SHALL PROVIDE FOR AN ALLOWANCE OF \$15.00 A SQUARE FOOT FOR THE PURCHASE OF THE TILE MATERIAL ONLY AS INDICATED FOR TL1 TILE ABOVE									
TRIMS AND MOLDINGS									
TR1 WALL CAP PER DETAIL 9/A4. PAINT PT8									
TR2 TOP OF WALL HORIZONTAL TRIM PER DETAIL 10/A4. PAINT PT8									
SL1 WINDOW SILL AND APRON PER DETAILS 11 AND 12 SHEET A4. PAINT PT8									


CASEWORK AND MILLWORK FINISHES									
L1 WILSONART WOOD LOOK LAMINATE WITH FINE GRAIN T8 PREMIUM FINISH (TO BE DETERMINED)									
L2 WILSONART HD HIGH DEFINITION LAMINATE WITH 35, 45, OR 55 PREMIUM FINISH (TO BE DETERMINED)									
L3 WILSONART GENERAL PURPOSE TYPE 107 H65 LAMINATE. (TO BE DETERMINED)									
L4 WILSONART GENERAL PURPOSE TYPE 107 H65 LAMINATE. (TO BE DETERMINED)									
L5 WILSONART GENERAL PURPOSE TYPE 107 H65 LAMINATE. (TO BE DETERMINED)									
L6 WILSONART GENERAL PURPOSE TYPE 107 H65 LAMINATE. (TO BE DETERMINED)									
L7 PLASTIC LAMINATE: WILSONART TYPE 419 MATTE NATURAL ALUMINUM 6252									
L8 WILSONART WOOD LOOK LAMINATE WITH FINE GRAIN T8 PREMIUM FINISH (TO BE DETERMINED)									
S61 SOLID SURFACE SHALL BE WILSONART SOLID SURFACE. COLOR TO BE SELECTED FROM FROM PRICE GROUP 5.									
QTZ QUARTZ SURFACE SHALL BE WILSONART QUARTZ. COLOR TO BE SELECTED FROM MANUFACTURER'S FULL RANGE									

HARDWARE SCHEDULE									
HN SET. 01 (passage) EACH TO HAVE: 3 EA HINGE SBB1 4.5 X 4.5 652 IVE 1 EA PASSAGE J-TS-F US26D DH 1 EA WALL STOP NS407GCV 630 IVE 1 SET SEALS 5050C CHR NSP									
HN SET. 02 (office) EACH TO HAVE: 3 EA HINGE SBB1 4.5 X 4.5 652 IVE 1 EA OFFICE J-92-F US26D DH 1 EA WALL STOP NS407GCV 630 IVE 1 SET SEALS 5050C CHR NSP									
HN SET. 03 (privacy) EACH TO HAVE: 3 EA HINGE SBB1 4.5 X 4.5 652 IVE 1 EA PRIVACY M-19ND-FE US26D DH 1 EA CH STOP 905 630 GLY 1 SET SEALS 5050C CHR NSP									
HN SET. 04 (pocket) EACH TO HAVE: 1 SET POCKET DOOR SYSTEM 1500SC SERIES WITH SOFT OPEN/CLOSE JOHNSON HDW 1 SET ONE SET BACK TO BACK PULL HANDLES RM3300-BTB 48"OA 36"CTC US26D ROC									
HN SET. 05 (acoustic) EACH TO HAVE: 3 EA HINGE SBB1 4.5 X 4.5 652 IVE 3 EA CLASSROOM J-84-F US26D DH 1 EA CH STOP 905 630 GLY 1 EA SURFACE DOOR BOTTOM 2225A NSP 1 SET SEALS 5050C CHR NSP									
HN SET. 06 (doc privacy) EACH TO HAVE: 3 EA HINGE SBB1 4.5 X 4.5 652 IVE 3 EA PRIVACY M-19ND-FE US26D DH 1 EA CH STOP 905 630 GLY 1 SET SEALS 5050C CHR NSP 1 EA MORTISE DOOR BOTTOM 2255 BLK NSP									
HN SET. 07 (passage w/ closure) EACH TO HAVE: 3 EA HINGE SBB1 4.5 X 4.5 652 IVE 1 EA PASSAGE J-TS-F US26D DH 1 EA CLOSER 316 684 DH 1 EA WALL STOP NS407GCV 630 IVE 1 SET SEALS 5050C CHR NSP									
HN SET. 08 (passage w/ ch stop) EACH TO HAVE: 3 EA HINGE SBB1 4.5 X 4.5 652 IVE 1 EA PASSAGE J-TS-F US26D DH 1 EA CH STOP 905 630 GLY 3 EA SILENCER SR64 GRV IVE									


DOOR AND FRAME SCHEDULE						
DOOR #	DOOR SLAB SIZE (UNLESS NOTED OTHERWISE)	FRAME	DOOR	HRDW #		
102A	ALL GLASS SEE ELEVATION 8/A3					
102B	ALL GLASS SEE ELEVATION 3/A3					
104	ALL GLASS SEE ELEVATION 6/A3					
105	3'-0" x 7'-0" x 1-3/4"	A	1	03		
107	3'-0" x 7'-0" x 1-3/4"	A	2	01		
108	3'-6" x 7'-0" CASED OPENING	C	-	-		
109	3'-6" x 7'-0" x 1-3/4"	B	2	04		
110	3'-0" x 7'-0" x 1-3/4"	A	1	03		
111	3'-0" x 7'-0" x 1-3/4"	A	1	05		
112	2'-6" x 7'-0" x 1-3/4"	A	1	02		
113	3'-0" x 7'-0" x 1-3/4"	A	1	06		
114	3'-0" x 7'-0" x 1-3/4"	A	2	02		
115	3'-0" x 7'-0" x 1-3/4"	A	1	07		
116	3'-0" x 7'-0" x 1-3/4"	A	2	07		
117	3'-0" x 7'-0" x 1-3/4"	A	1	08		
GLASS TYPES						
GL1 1/2" CLEAR TEMPERED SAFETY GLASS WITH APPLIED AND/OR FILM TO BE SOLYX 500P-VF WHITE FROST. VERIFY FILM W/ OWNER						
GL2 1/2" CLEAR TEMPERED SAFETY GLASS						
DOOR TYPES						
1 PLASTIC LAMINATE CLAD DOOR		2 PLASTIC LAMINATE CLAD DOOR				




3 SOFFIT DETAIL
3/4"x1'-0"




4 SOFFIT DETAIL
3/4"x1'-0"




5 SOFFIT DETAIL
3/4"x1'-0"



6 SOFFIT DETAIL
3/4"x1'-0"



1 LOW CEILING PLAN
1/4"x1'-0"



2 HIGH CEILING PLAN
1/4"x1'-0"

CEILING LEGEND

8'-9" ELEVATION OF CEILING ABOVE FINISHED FLOOR.

24" x 48" ARMSTRONG DUNE BEVELED TEGULAR 1171 ACOUSTICAL TILE IN SUPRAPINE 3/8" EXPOSED T GRID

SOFFIT OR CEILING OF ONE LAYER OF 3/8" GYP. BD. ON BOTTOM AND VERTICAL EXPOSED FACES OF METAL STUD FRAMING. FINISH AND PAINT GYPSUM BOARD


PROVIDE 3/4" PLYWOOD OVER 6" METAL STUD FRAMING PER DETAILS 3 THRU 6 THIS SHEET.

CEILING OF TWO LAYERS OF 3/8" THICK GOLDBOND SOUND BREAK GYPSUM BOARD ON 6" METAL STUDS AT 16" O.C.

- CEILING PLAN NOTES**
- C001 CONSTRUCT KNEE WALL OF ONE LAYER OF 3/8" GYPSUM BOARD ON 3/8" METAL STUD FRAMING. KNEE WALL IS TO BUILT FROM TOP OF 3/4" PLYWOOD DECK TO 10'-8" AFF
 - C002 REFER TO DETAIL 5/A2 FOR SUSPENDED FRAMING AND FINISHES THIS AREA.
 - C003 CONTINUE WALL ABOVE LOW CEILING WITH ONE LAYER OF 3/8" GYPSUM BOARD ON 3/8" METAL STUD FRAMING. EXTEND TO 10'-8" AFF



GUY GRONBERG ARCHITECTS, P.C.
113 SE 5th St.
Lee's Summit, MO 64063
Phone: 816.524.0970
Fax: 816.524.0570








Abby Jewell DDS
ORTHODONTICS
2070 NW LOWENSTEIN DR. UNIT A, LEE'S SUMMIT, MO 64081


This drawing has been provided as an instrument of service by the architect. It is to be used for the purpose intended and is not to be used for any other purpose without the written consent of the architect. The architect assumes no responsibility for the accuracy or completeness of the information contained herein, or for the results of the use of the information contained herein.

REV#	DATE	DESCRIPTION
1	09/20/23	APPENDIX #1
Issue Date: 09-07-23		
Project #: 23016		

CEILING PLAN
A2



GUY GRONBERG
ARCHITECTS, P.C.
113 SE 24th St.
Lee's Summit, MO 64063
Phone: 913.524.0970
Fax: 913.524.0970




Abby Jewell DDS
ORTHODONTICS
2070 NW LOWENSTEIN DR. UNIT A, LEE'S SUMMIT, MO 64081

This drawing has been provided as a service to the client and is not to be used for any other purpose without the written consent of Guy Gronberg Architects, P.C. The client is responsible for obtaining all necessary permits and approvals from the appropriate authorities. The client is also responsible for obtaining all necessary insurance coverage for the project. The client is further responsible for obtaining all necessary contracts and agreements from the appropriate parties. The client is also responsible for obtaining all necessary permits and approvals from the appropriate authorities. The client is further responsible for obtaining all necessary contracts and agreements from the appropriate parties.



REV#	DATE	DESCRIPTION
1	09/20/23	APPENDIX #1
2	9/28/23	APPENDIX #2
Issue Date: 09-07-23		
Project #: 23016		

INTERIOR
ELEVATIONS

A3



EQALG	ALGER LIGHT; AT PART OF ALTERNATE BID CONTRACTOR IS TO PROVIDE ALGERLIGHT LED WITH FOOTSWITCH CONTROL AL-LED-RF-F (WWW.ALGERING.COM) BASE BID IS TO INCLUDE ELECTRICAL CONNECTION FROM ABOVE CEILING DOWN TO SUSPENDED CLOUD.
EQART	ARTWORK: FURNISHED AND INSTALLED BY OWNER.
EQCOF	COFFEE MAKER: FURNISHED AND INSTALLED BY OWNER
EQDEG	DENTAL EQUIPMENT: MISCELLANEOUS FURNISHED AND INSTALLED BY OWNERS VENDOR. CONTRACTOR IS TO DO ALL FINAL PLUMBING, MECHANICAL AND ELECTRICAL CONNECTIONS
EQEFR	FURNITURE: FURNISHED AND INSTALLED BY OWNERS VENDOR.
EQMNV	MICROWAVE: FURNISHED AND INSTALLED BY OWNER.
EQPC	COMPUTER: FURNISHED AND INSTALLED BY OWNER'S VENDOR
EQPTD	PAPER TONER DISPENSER; FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR.
EQREF	REFRIGERATOR: FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR.
EQSGN	SIGN: OWNER FURNISHED CONTRACTOR INSTALLED. CONTRACTOR IS TO DO FINAL ELECTRICAL CONNECTIONS
EQTC	TRASH CAN: FURNISHED AND INSTALLED BY OWNER.
EQTV	FLAT SCREEN TV / MONITOR; SCREEN AND MOUNT TO BE FURNISHED BY OWNER. INSTALLED BY CONTRACTOR INCLUDING ALL FINAL ELECTRICAL CONNECTIONS. PROVIDE BLOCKING AS RECOMMENDED BY VENDOR.
EQUCF	UNDERCOUNTER REFRIGERATOR: FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR.



Abby Jewell DDS

ORTHODONTICS

instrument of service by the architect, or under his supervision and is intended for use on this project only. Inherent to the Architectural Works Copyright Protection Act of 1990 is the right of the architect to create and design, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrightable work of the designer/Architect. Any reproduction use, in whole or in part, without the written disclosure of information contained herein without prior written consent of the Architect.

**6 COPYRIGHT 2023 GUY
KRONBERG ARCHITECTS, P.C.**

NEW*	DATE	DESCRIPTION
1	04/20/23	ADDENDUM #1

Issue Date: 04-07-23

Project #: 23016

INTERIOR DETAILS

A4

MECHANICAL SPECIFICATIONS

1. GENERAL PROVISIONS:
- A. PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, NECESSARY FOR THE COMPLETE INSTALLATION OF THE PLUMBING AND MECHANICAL SYSTEMS OUTLINED.
- B. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE AUTHORITIES.
- C. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION OVER THE SITE.
- D. ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.
- E. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, PIPE, DUCT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNDAMAGED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERINGS SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.
- F. PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS AS NECESSARY. PATCHES AND REPAIRS SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.
- G. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
2. OPERATION AND MAINTENANCE MANUALS:
- A. DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, WIRING DIAGRAMS, CATALOG CUTS, LUBRICATION AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.
- B. ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATION AND MAINTENANCE MANUALS.
- C. ALL LITERATURE LISTED ABOVE AND ALL PAPERS LISTING MANUFACTURERS, ETC. SHALL BE BOUND IN A SINGLE BINDER AND LABELED WITH THE PROJECT NAME, ADDRESS, ARCHITECT, ENGINEER, CONTRACTORS, ETC.
3. MANUFACTURERS:
- A. MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSTRUED AS LIMITING COMPETITION. QUALITY, ARTICLES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO STRUCTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN, UNLESS NOTED OTHERWISE.
4. MOTORS:
- A. PROVIDE THERMAL OVERLOAD PROTECTION FOR EACH MOTOR PROVIDED BY THIS WORK.
5. TESTING, BALANCING, AND CLEANING:
- A. ALL PIPING SHALL BE TESTED FOR LEAKS BEFORE BEING CONCEALED IN WALL CONSTRUCTION OR COVERED WITH INSULATION.
- B. SEWER AND VENT PIPING SHALL BE HYDROSTATICALLY TESTED WITH NO LESS THAN 10 FEET OF HEAD FOR A PERIOD OF NOT LESS THAN 15 MINUTES, PER THE LOCAL PLUMBING CODE, WITH NO LEAKS.
- C. DUCTWORK AND PIPING SHALL BE BALANCED BY QUALIFIED INDEPENDENT BALANCING PERSONNEL, WHO HAVE PREVIOUS EXPERIENCE WITH BALANCING PROCEDURES AND ARE CERTIFIED BY THE ASSOCIATED AIR BALANCE COUNCIL (AABC) OR NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB).
- 1) BALANCING SHALL INCLUDE THE BALANCING OF THE EQUIPMENT AND AIR DISTRIBUTION SYSTEMS TO PROVIDE DESIGN QUANTITIES INDICATED AND VERIFICATION OF PERFORMANCE OF ALL EQUIPMENT AND AUTOMATIC CONTROLS.
- 2) WITH IN 30 DAYS OF THE COMPLETION OF THE TESTING AND BALANCING WORK, SUBMIT THE TEST AND BALANCE REPORTS TO THE ARCHITECT. THE SIGNATURE OF THE TEST AND BALANCE PERSONNEL, WHO REPORTS SHALL BE CERTIFIED PROOF THAT THE SYSTEMS HAVE BEEN TESTED, ADJUSTED, AND BALANCED IN ACCORDANCE WITH THE REFERENCED STANDARDS; ARE AN ACCURATE REPRESENTATION OF HOW THE SYSTEMS HAVE BEEN INSTALLED AND ARE OPERATING. REPORTS SHALL BE BOUND IN A VINYL BINDER OR THE BINDER LABELED OR MAY BE AN ELECTRONIC PDF SUBMITTAL.
- D. BEFORE DOMESTIC WATER PIPING IS PLACED IN SERVICE, ALL DOMESTIC WATER DISTRIBUTION SYSTEMS, INCLUDING HOT WATER PIPING AND HOT WATER SYSTEMS SHALL BE DISINFECTED, STERILIZED AND CHLORINATED IN ACCORDANCE WITH HEALTH DEPARTMENT REGULATIONS. THE SYSTEMS SHALL BE THOROUGHLY FLUSHED OF ALL DIRT AND FOREIGN MATTER, THEN FILLED WITH WATER TREATED WITH 50 PPM OF CHLORINE. VALVES AND FITTINGS SHALL BE OPENED SEVERAL TIMES TO ASSURE TREATMENT OF THE ENTIRE SYSTEM. THE TREATED WATER SHALL BE LEFT IN THE SYSTEM FOR 24 HOURS AFTER WHICH TIME THE SYSTEM SHALL BE FLUSHED. IF THE RESIDUAL CHLORINE IS NOT LESS THAN 10 PPM, THE FLUSHING SHALL BE REPEATED. AFTER STERILIZATION, SAMPLES OF WATER IN THE SYSTEM SHALL BE APPROVED BY THE BOARD OF HEALTH.
6. PLUMBING:
- A. PROVIDE AN APPROVED WATER HAMMER ARRESTOR FOR EACH PLUMBING FIXTURE SUPPLY AS REQUIRED BY FIXTURE MANUFACTURERS.
- B. ALL EXPOSED WASTE PIPE SHALL BE CHROME PLATED BRASS PIPE, NO FERROUS PIPE.
- C. PROVIDE CLEANOUTS AT EACH CHANGE OF DIRECTION AND AT 100 FOOT INTERVALS IN STRAIGHT RUNS.
- D. PROVIDE ACCESS PANELS FOR ALL CONCEALED VALVES AND TRAPS.
- E. CLEANOUTS:
- 1) VINYL TILE FLOOR: JR SMITH 4140, OR EQUAL.
- 2) QUARRY TILE FLOOR: JR SMITH 4420, OR EQUAL.
- 3) CARPETED FLOOR: JR SMITH 4420-Y, OR EQUAL.
- 4) UNFINISHED FLOOR: JR SMITH 4420, OR EQUAL.
- 5) WALL: JR SMITH 4420, OR EQUAL, 2" ABOVE THE FLOOR.
- F. PROVIDE DIELECTRIC UNIONS WITH APPROPRIATE END CONNECTIONS TO MATCH THE PIPE SYSTEM IN WHICH INSTALLED (SCORED, SOLDERED, OR FLANGED). PROVIDE DIELECTRIC UNIONS ON ALL PIPING CONNECTIONS TO HOT WATER HEATERS AND EXPANSION TANKS.
- G. WATER HEATERS:
- 1) EVERY WATER HEATER SHALL HAVE AN APPROVED MEANS INSTALLED ON THE COLD WATER SUPPLY LINE ABOVE THE EQUIPMENT TO PREVENT BIPHONING OF A STORAGE WATER HEATER OR TANK.
- 2) BOTTOM FED WATER HEATERS AND TANKS CONNECT TO WATER HEATERS WITH A VACUUM RELIEF VALVE INSTALLED, ANSI Z21.22.
- 3) STORAGE HEATERS OPERATING ABOVE ATMOSPHERIC PRESSURE SHALL HAVE AN APPROVED PRESSURE RELIEF VALVE AND/OR TEMPERATURE RELIEF VALVE.
- H. ALL SEWER PIPING LOCATED INSIDE THE BUILDING SHALL BE INSTALLED WITH THE FOLLOWING SLOPES:
- 1) INSTALL 2-1/2" AND SMALLER PIPE AT 1/4" PER FOOT FALL.
- 2) INSTALL 3" AND LARGER PIPE AT 1/8" PER FOOT FALL.
7. PIPING:
- A. DOMESTIC COLD, HOT, AND HOT WATER REGULATING (ABOVEGROUND).
- 1) TYPE L HARD DRAIN COPPER TUBING, ASTM B-88.
- a) WROUGHT COPPER SOLDERED FITTINGS, ASTM B75 ALLOY C12200, ANSI B16.22, MSS SP-104.
- b) MECHANICAL PRESS COPPER FITTINGS FOR USE IN PLUMBING OR MECHANICAL APPLICATIONS, ASME B16.22, ASME B16.51, OR ASME B16.16. MECHANICAL PRESS COPPER FITTINGS SHALL CONFORM TO IWACO PS-117 OR ASME B16.51.
- 2) FLEX, HIGH-DENSITY CROSS-LINKED POLYETHYLENE TUBING SHALL BE MANUFACTURED TO THE REQUIREMENTS OF BOTH FPEX AND MEET STANDARD GRADE HYDROSTATIC PRESSURE RATINGS FROM PLASTIC PIPE INSTITUTE IN ACCORDANCE WITH TR-4/03.
- a) FPEX-A AND FPEX-B MEETING ANSI/NSF 61 AND ANSI/NSF 312 STANDARDS FOR POTABLE WATER SAFETY AND LEAD-FREE STANDARDS MUST BE MARKED WITH "FPEX-A", "NSF-61-0", OR OTHER NSF-APPROVED MARKING, ASTM F2025 FOR USE WITH CHLORINATED WATER.
- b) FPEX MECHANICAL, CRIMP/INSERT OR EXPANSION FITTINGS INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. PIPE SIZES GIVEN ARE NOMINAL COPPER PIPE SIZE. INCREASE PEX PIPING SIZE TO EQUAL OR EXCEED COPPER PIPE INSIDE DIAMETER FOR SUPPLY MAINS.
- 3) VALVES:
- a) TO BE INSTALLED ON THE FIXTURE SUPPLY TO EACH PLUMBING FIXTURE.
- b) TO BE INSTALLED ON THE WATER SUPPLY SIDE TO EACH APPLIANCE OR MECHANICAL EQUIPMENT.
- c) TYPES:
1. GATE VALVE: JOHAR T-9-3015 OR EQUAL, LEAD-FREE NSF 61, ANSI B1.20.1.
2. GLOBE VALVE: JOHAR T-66 OR EQUAL.
3. BALL VALVE: JOHAR JPI00XP OR EQUAL, COMPACT LEAD FREE BRASS BALL VALVE, UL442, CSA 337.1 & 337.42, FM, CALIFORNIA CODE AB576, ANSI A APPROVED.
4. BALL VALVE: JOHAR T-100NE OR EQUAL, UL442, FM, CSA, NSF 61-B, MSS SP-110.
- B. LEAD CONTENT OF WATER SUPPLY PIPE AND FITTINGS:
- 1) PIPE AND PIPE FITTINGS, INCLUDING VALVES AND FAUCETS, UTILIZED IN THE WATER SUPPLY SYSTEM SHALL NOT HAVE MORE THAN .01% LEAD.
- 2) PIPE, PIPE FITTINGS, JOINTS, VALVES, FAUCETS, AND FIXTURE FITTINGS UTILIZED TO SUPPLY WATER FOR DRINKING OR COOKING PURPOSES SHALL COMPLY WITH NSF 312 AND SHALL HAVE A WEIGHTED AVERAGE LEAD CONTENT OF 0.25% OR LESS.
- C. SANITARY SEWER AND VENTS (UNDERGROUND, INTERIOR TO THE BUILDING).
- 1) ABS PIPE AND FITTINGS: ABS PIPE AND FITTINGS SHALL COMPLY WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS," FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKING WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SEWER" FOR PLASTIC SEWER PIPING. SOLID-WALL ABS PIPE, ASTM D 2661, SCHEDULE 40. CELLULAR-CORE ABS PIPE, ASTM F 626, SCHEDULE 40. ABS SOCKET FITTINGS: ASTM D 2661, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS, SOLVENT CEMENT, ASTM D 2235.
- 2) PVC PIPE AND FITTINGS: PVC PIPE AND FITTINGS SHALL COMPLY WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS," FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKING WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SEWER" FOR PLASTIC SEWER PIPING. SOLID-WALL PVC PIPE, ASTM D 2665, DRAIN, WASTE, AND VENT, PVC SOCKET FITTINGS: ASTM D 2665, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS AND TO FIT SCHEDULE 40 PIPE. ADHESIVE PRIMER: ASTM F 656, SOLVENT CEMENT, ASTM D 2564.
- 3) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 800 AND CSPI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO CSPI STANDARD 310 AND BE CERTIFIED BY NSF INTERNATIONAL.
- 4) HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 74.
- D. SANITARY SEWER AND VENTS (ABOVE GROUND, INTERIOR TO THE BUILDING).
- 1) ABS PIPE AND FITTINGS: ABS PIPE AND FITTINGS SHALL COMPLY WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS," FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKING WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SEWER" FOR PLASTIC SEWER PIPING. SOLID-WALL ABS PIPE, ASTM D 2661, SCHEDULE 40. CELLULAR-CORE ABS PIPE, ASTM F 626, SCHEDULE 40. ABS SOCKET FITTINGS: ASTM D 2661, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS, SOLVENT CEMENT, ASTM D 2235.
- 2) PVC PIPE AND FITTINGS: PVC PIPE AND FITTINGS SHALL COMPLY WITH NSF 14, "PLASTICS PIPING SYSTEMS COMPONENTS AND RELATED MATERIALS," FOR PLASTIC PIPING COMPONENTS, INCLUDE MARKING WITH "NSF-DWV" FOR PLASTIC DRAIN, WASTE, AND VENT PIPING AND "NSF-SEWER" FOR PLASTIC SEWER PIPING. SOLID-WALL PVC PIPE, ASTM D 2665, DRAIN, WASTE, AND VENT, PVC SOCKET FITTINGS: ASTM D 2665, MADE TO ASTM D 3311, DRAIN, WASTE, AND VENT PATTERNS AND TO FIT SCHEDULE 40 PIPE. ADHESIVE PRIMER: ASTM F 656, SOLVENT CEMENT, ASTM D 2564.
- 3) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 800 AND CSPI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO CSPI STANDARD 310 AND BE CERTIFIED BY NSF INTERNATIONAL.
- 4) HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 74.
- E. CONDENSATE DRAINS 4 INDIRECT WASTE (ABOVEGROUND).
- 1) DWV, WROUGHT COPPER, AND B-16-24 (CONDENSATE INSIDE BUILDINGS).
- 2) POLYVINYLCHLORIDE (PVC) DWV PIPE, SCHEDULE 40, SOLVENT JOINT (INDIRECT WASTE).
- 3) DWV, WROUGHT COPPER, AND B-16-24 (WATER HEATER TIE).
- F. ALL PIPE HANGERS AND SUPPORTS SHALL BE STANDARD PRODUCTS OF GRINNELL, FEE AND MASON, OR ELGEN. HANGER SPACING SHALL BE IN ACCORDANCE WITH MSS-SP-64.

MECHANICAL SPECIFICATIONS (CONTINUED)

6. SLEEVES
- 1) PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK. ALL SLEEVES SHALL BE OF SUFFICIENT SIZE TO PERMIT PIPE MOVEMENT DUE TO EXPANSION AND CONTRACTION, AND TO ACCOMMODATE PIPE INSULATION.
- 2) INTERIOR PARTITIONS: 16 GAGE GALVANIZED STEEL, PACK BETWEEN PIPE AND SLEEVE WITH FIRE RATING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.
- 3) ROOF: PROSET OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WATERPROOF SEAL. COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF WARRANTY.
- 4) PROTECTION AGAINST CONTACT: METALLIC PIPING, EXCEPT FOR CAST IRON, DUCTILE IRON AND GALVANIZED STEEL SHALL NOT BE PLACED IN DIRECT CONTACT WITH STEEL, FRAMING MEMBERS, CONCRETE, OR GINDER WALLS AND FLOORS OR OTHER MASONRY. METALLIC PIPING SHALL NOT BE PLACED IN DIRECT CONTACT WITH CORROSIVE SOIL. SHEATHING USED TO PREVENT DIRECT CONTACT SHALL HAVE A THICKNESS OF GREATER THAN .005, AND THE SHEATHING SHALL BE MADE OF PLASTIC. ANY PIPE THAT PASSES THROUGH A FOUNDATION WALL OR FOOTING SHALL BE PROVIDED WITH A RELIEVING ARG, OR A PIPE SLEEVE SHALL BE BUILT INTO THE FOUNDATION WALL. THE SLEEVE SHALL BE TWO SIZES GREATER THAN THE PIPE PASSING THROUGH THE WALL OR FOOTING.
- 5) PLUMBING VENTS: FLASH ROOF VENT INTO ROOFING SYSTEM AS REQUIRED BY THE ROOFING CONTRACTOR TO MAINTAIN EXISTING ROOF WARRANTY. ALL PLUMBING VENT TERMINALS SHALL TERMINATE A MINIMUM OF 12" ABOVE ROOF OR EQUAL TO HEIGHT OF PARAPET, WHICHEVER IS GREATER.
- H. PROVIDE CHROME PLATED ESCUTCHEONS ON ALL PIPE ENTERINGS FINISHED AREAS.
- I. CATEGORY 2 OR 3 DENTAL COMPRESSED AIR:
- 1) TYPE L HARD DRAIN COPPER TUBING, ASTM B-88.
- a. WROUGHT BRONZE SOLDERED FITTINGS.
- b. JOINTS: JOINTS SHALL BE BRAZED, SOLDERED, THREADED, FLARED, OR THE COMPRESSION TYPE.
- 2) WHERE JOINTS ARE BRAZED, THEY SHALL COMPLY WITH THE REQUIREMENTS OF 18.4-B.
- 3) SOLDERED JOINTS SHALL BE MADE IN ACCORDANCE WITH ASTM B826, STANDARD PRACTICE FOR MAKING CAPILLARY JOINTS BY SOLDERING OF COPPER AND COPPER ALLOY TUBE AND FITTINGS, USING A "LEAD-FREE" SOLDER FILLER METAL CONTAINING NOT MORE THAN 0.2 PERCENT LEAD BY VOLUME THAT COMPLIES WITH ASTM B92, STANDARD SPECIFICATION FOR SOLDER METAL.
- c. PIPING SHALL BE SUBJECTED TO 24 HOUR STANDING PRESSURE TEST USING OIL FREE DRY NITROGEN PER NFPA 19.4-8.1.7.
- J. CATEGORY 3 OR 4 DENTAL VACUUM:
- 1) TYPE L HARD DRAIN COPPER TUBING, ASTM B-88.
- a. WROUGHT BRONZE SOLDERED FITTINGS.
- b. JOINTS: JOINTS SHALL BE BRAZED, SOLDERED, THREADED, FLARED, OR THE COMPRESSION TYPE.
- 2) WHERE JOINTS ARE BRAZED, THEY SHALL COMPLY WITH THE REQUIREMENTS OF 18.4-B.
- 3) SOLDERED JOINTS SHALL BE MADE IN ACCORDANCE WITH ASTM B826, STANDARD PRACTICE FOR MAKING CAPILLARY JOINTS BY SOLDERING OF COPPER AND COPPER ALLOY TUBE AND FITTINGS, USING A "LEAD-FREE" SOLDER FILLER METAL CONTAINING NOT MORE THAN 0.2 PERCENT LEAD BY VOLUME THAT COMPLIES WITH ASTM B92, STANDARD SPECIFICATION FOR SOLDER METAL.
- c. COPPER PIPING SHALL BE SUBJECTED TO 24 HOUR STANDING PRESSURE TEST USING OIL FREE DRY NITROGEN PER NFPA 19.4-8.1.7.
- 2) PVC PLASTIC PIPE SHALL BE SCHEDULE 40 OR SCHEDULE 80, COMPLYING WITH ASTM D 1789, STANDARD SPECIFICATION FOR POLY (VINYL CHLORIDE) (PVC) LOGIC PIPE, SCHEDULES 40, 80, AND 120.
- b. PVC PLASTIC FITTINGS SHALL BE SCHEDULE 40 OR SCHEDULE 80 TO MATCH THE PIPE, COMPLYING WITH ASTM D 2466, STANDARD SPECIFICATION FOR POLY (VINYL CHLORIDE) (PVC) PLASTIC PIPE FITTINGS, SCHEDULE 40, OR ASTM D 2467, STANDARD SPECIFICATION POLY (VINYL CHLORIDE) (PVC) PLASTIC PIPE FITTINGS, SCHEDULE 80.
- d. JOINTS IN PVC PLASTIC PIPING SHALL BE SOLVENT-CEMENTED IN ACCORDANCE WITH ASTM D 2672, STANDARD SPECIFICATION FOR JOINTS FOR RPS PVC PIPE USING SOLVENT CEMENT.
- e. VACUUM DISTRIBUTION PIPING, INCLUDING SCAVENGING, SHALL BE SUBJECTED TO A STANDING VACUUM TEST PER NFPA 19.5.1.3.5.
- D. DENTAL AIR, VACUUM, AND SCAVENGING PIPING INSTALLATION:
- A. INSTALL AIR AND VACUUM PIPING SYSTEMS IN ACCORDANCE WITH THE MANUFACTURERS INSTRUCTIONS AND NFPA 99 - 2021.
- B. JOINTS
- 1) SOLDERED JOINTS SHALL BE MADE IN ACCORDANCE WITH ASTM B826, STANDARD PRACTICE FOR MAKING CAPILLARY JOINTS BY SOLDERING OF COPPER AND COPPER ALLOY TUBE AND FITTINGS, USING A "LEAD-FREE" SOLDER FILLER METAL CONTAINING NOT MORE THAN 0.2 PERCENT LEAD BY VOLUME THAT COMPLIES WITH ASTM B92, STANDARD SPECIFICATION FOR SOLDER METAL.
- 2) WHERE JOINTS ARE BRAZED, BRAZING PROCEDURES AND BRAZING PERFORMANCE FOR THE INSTALLATION OF DENTAL PIPING SHALL BE IN ACCORDANCE WITH EITHER SECTION IX "WELDING AND BRAZING QUALIFICATIONS," OF THE ASME BOILER AND PRESSURE VESSEL CODE, OR ASME B9.2/B9.2M, SPECIFICATION FOR BRASSING FOR BRASSING DISSIMILAR MATERIALS, AVOID LEAVING EXCESS FLUX INSIDE OF PIPE AND FITTINGS. DURING BRAZING OF PIPE CONNECTIONS, PURGE INTERIOR OF PIPE CONTINUOUSLY WITH OIL FREE DRY NITROGEN.
- 3) EFFECT CHANGES IN SIZE WITH REDUCING FITTINGS. MAKE CHANGES IN DIRECTION OF REQUIRED TURNS OR OFFSETS WITH FITTINGS OR TUBING SHAPED BY BENDING TOOLS. BENDS SHALL BE FREE OF FLATTENING, BUCKLING OR THINNING OF TUBE WALL.
- D. GRADE PIPING DOWN IN DIRECTION OF FLOW.
- E. PROVIDE PIPE SLEEVES WHERE PIPES AND TUBING PASS THROUGH WALLS, FLOORS, ROOFS, AND PARTITIONS. FINISH FLUSH AT BOTH ENDS. EXTEND 2 INCHES (50MM) ABOVE FINISHED FLOORS. PACK SPACE BETWEEN PIPE OR TUBING AND SLEEVE, AND CAULK.
- G. IDENTIFY PIPING IN ACCORDANCE WITH MIL-STD 101, WITH TAPE AND DECALS TO FEPFPP-T-66. PROVIDE PIPING IDENTIFICATION CODE AND SCHEMATIC. LABELLING SHALL APPEAR ON PIPE AT INTERVALS OF NOT MORE THAN 20 FEET AND AT LEAST ONCE IN EACH ROOM AND EACH STORY TRAVERSED BY PIPELINE.
- H. SUPPORT GAS PIPING WITH PIPE HOOKS OR HANGERS SUITABLE FOR SIZE OF PIPE, SPACED:
- 1) 1/2 INCH PIPE: 18 INCHES; 12 INCHES.
- 2) 3/4 INCH OR ONE INCH PIPE OR TUBING: 96 INCHES.
- 3) 1-1/4 INCHES OR LARGER (HORIZONTAL): 120 INCHES.
- 4) 1-1/4 INCHES OR LARGER (VERTICAL): EVERY FLOOR LEVEL.
- I. PIPING SYSTEMS CLEANING AND PRESSURE TESTING:
- 1) AFTER ERECTION OF PIPE AND TUBING BUT PRIOR TO INSTALLATION OF SERVICE OUTLET VALVES, BLOW SYSTEMS CLEAR OF FREE MOISTURE AND FOREIGN MATTER WITH NITROGEN GAS.
- 2) INSTALL SERVICE OUTLET VALVES, SUBJECT SYSTEM TO TEST PRESSURE OF 150 PSIG WITH NITROGEN OR DRY COMPRESSED AIR. CHECK WITH SOAPY WATER. PROVIDE 24-HOUR STANDING PRESSURE TEST.
9. WATER HEATERS
- A. COMMERCIAL, LIGHT-DUTY, STORAGE, ELECTRIC, DOMESTIC-WATER HEATERS:
1. STANDARD: UL 174
2. STORAGE-TANK CONSTRUCTION: STEEL, VERTICAL ARRANGEMENT.
- a. PRESSURE RATINGS: 150 PSIG.
- b. INTERIOR FINISH: COMPLY WITH NSF 61 AND NSF 312 BARRIER MATERIALS FOR POTABLE-WATER TANK.
- c. LININGS, INCLUDING EXTENDING MATERIAL, TO TAPPINGS.
3. FACTORY-INSTALLED, STORAGE-TANK APPURTENANCES:
- a. ANODE ROD: REPLACEABLE MAGNESIUM.
- b. DIP TUBE: REQUIRED UNLESS COLD-WATER INLET IS NEAR BOTTOM OF TANK.
- c. DRAIN VALVE: CORROSION-RESISTANT METAL WITH HOSE-END CONNECTION.
- d. INSULATION: COMPLY WITH ASHRAE 15-101.
- e. JACKET: STEEL WITH ENAMELED FINISH OR HIGH-IMPACT COMPOSITE MATERIAL.
- f. HEAT-TRAP FITTINGS: INLET TYPE IN COLD-WATER INLET AND OUTLET TYPE IN HOT-WATER OUTLET.
- g. HEATING ELEMENTS: ELECTRIC, SCREW-IN IMMERSION TYPE.
- h. TEMPERATURE CONTROL: ADJUSTABLE THERMOSTAT.
- i. SAFETY CONTROL: HIGH-TEMPERATURE-LIMIT CUTOFF DEVICE OR SYSTEM.
- j. RELIEF VALVE: ASME RATED AND STAMPED FOR COMBINATION TEMPERATURE-AND-PRESSURE RELIEF VALVES, INCLUDE RELIEFING CAPACITY AT LEAST AS GREAT AS HEAT INPUT, AND INCLUDE PRESSURE SETTING LESS THAN WORKING-PRESSURE RATING OF DOMESTIC-WATER HEATER. SELECT RELIEF VALVE WITH SENSING ELEMENT THAT EXTENDS INTO STORAGE TANK.
- B. DOMESTIC-WATER EXPANSION TANKS:
1. DESCRIPTION: STEEL, PRESSURE-RATED TANK CONSTRUCTED WITH WELDED JOINTS AND FACTORY-INSTALLED BUTYL-RUBBER DIAPHRAGM. INCLUDE AIR PRECHARGE TO MINIMUM SYSTEM-OPERATING PRESSURE AT TANK.
2. CONSTRUCTION:
- a. TAPPINGS: FACTORY-FABRICATED STEEL, WELDED TO TANK BEFORE TESTING AND LABELING. INCLUDE ASME B1.20.1 PIPE THREADING.
- b. INTERIOR FINISH: COMPLY WITH NSF 61 AND NSF 312 BARRIER MATERIALS FOR POTABLE-WATER TANK LININGS, INCLUDING EXTENDING FINISH INTO AND THROUGH TANK FITTINGS AND OUTLETS.
- c. AIR-CHARGING VALVE: FACTORY INSTALLED.
3. CAPACITY AND CHARACTERISTICS:
- a. WORKING-PRESSURE RATING: 150 PSIG.
10. INSULATION AND DUCT LINING:
- A. ALL INSULATIONS AND ACCESSORIES SHALL HAVE A FIRE HAZARD CLASSIFICATION WITH A FLAME SPREAD RATINGS OF NOT OVER 25, A FUEL CONTRIBUTION RATING OF NOT OVER 50, AND A SMOKE DEVELOPED RATINGS OF NOT OVER 50, IN ACCORDANCE WITH NFPA.
- B. PIPE INSULATION - ABOVE GRADE:
- 1) THE PIPING INSULATION USED SHALL HAVE A THERMAL CONDUCTIVITY OF 0.21 Btu PER IN-HI*94F-1F OR LESS.
- 2) FIBERGLASS INSULATION WITH FACTORY APPLIED VAPOR BARRIER, ASU JACKET, FACTORY APPLIED PRESSURE SEALING JOINT, NO STAPLES, ZESTON PROHIBITED PVC FITTING COVERS. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- 3) FLEXIBLE CLOSED CELL ELASTOMERIC THERMAL INSULATION, UNSLIT OR PRESLIT WITH PRESSURE SENSITIVE ADHESIVE SYSTEM FOR CLOSURE AND VAPOR SEALING, EQUAL TO ARMAFLEX OR ARMAFLEX 2000.
- 4) FOR NON CIRCULATING SYSTEMS, THE FIRST 8 FEET OF INLET AND OUTLET PIPING BETWEEN THE TANK AND THE HEAT TRAP (INCLUDING THE HEAT TRAP) MUST BE INSULATED.
- 5) FOR CIRCULATING SYSTEMS, ALL HOT WATER PIPING IN THE CIRCULATION LOOP MUST BE INSULATED AS SPECIFIED BELOW.
- C. INSULATION SCHEDULE:
- a) DOMESTIC COLD WATER 1/2"
- b) DOMESTIC HOT WATER 1"
- c) HOT WATER REGULATING 1" FOR PIPING UP TO 1-1/4", & 1-1/2" FOR PIPING 1-1/2" AND LARGER
- d) CONDENSATE DRAINS INSIDE BUILDING 1"
- D. DUCTWORK: ACoustical INSULATION:
- 1) DUCT LINING: 2 LB/CF, THICKNESS AS SCHEDULED, AIR STREAM SIDE COATED, INSTALL PER SMACNA STANDARDS.
- 2) DUCT LINING SCHEDULE:
- a) RECTANGULAR SUPPLY DUCT 1/2": THROUGHOUT THE FIRST 10 FEET OF DUCT.
- b) RETURN AIR DUCT 1/2": THROUGHOUT THE FIRST 10 FEET OF DUCT.
- c) SOUND BOOTS 2"
- D. DUCTWORK: THERMAL INSULATION:
- 1) DUCT COVERING: 3/4 LB/CF, FIBERGLASS BLANKET WITH FACTORY APPLIED VAPOR BARRIER AND FACING, THICKNESS AS SCHEDULED, INSTALLATION IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
- a) DUCT COVERING SCHEDULE: MINIMUM R-8
- b) DUCT COVERING SCHEDULE: MINIMUM R-2
- c) RECTANGULAR SUPPLY DUCT 2"
- d) RECTANGULAR SUPPLY DUCT 2"
- e) RETURN AIR DUCT 2"
- E. DUCTWORK: THERMAL INSULATION (NONCONDITIONED ATTIC)
- 1) DUCT COVERING: 3/4 LB/CF, FIBERGLASS BLANKET WITH FACTORY APPLIED VAPOR BARRIER AND FACING, THICKNESS AS SCHEDULED, INSTALLATION IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
- a) DUCT COVERING SCHEDULE: MINIMUM R-8
- b) DUCT COVERING SCHEDULE: MINIMUM R-2
- c) RECTANGULAR SUPPLY DUCT 3"
- d) RETURN AIR DUCT 3"

MECHANICAL SPECIFICATIONS (CONTINUED)

11. DUCTWORK:
- A. ALL DUCTWORK, UNLESS OTHERWISE INDICATED, SHALL BE FABRICATED FROM GALVANIZED SHEET STEEL COMPLYING WITH ASTM A 521, LOGARFORMING QUALITY, WITH 6 TO 10 ZINC COATING IN ACCORDANCE WITH ASTM A 525, AND MILL PHOSPHATIZED FOR EXPOSED LOCATIONS.
- B. WHERE DUCTWORK IS EXPOSED TO VIEW IN OCCUPIED SPACES, PROVIDE MATERIALS WHICH ARE FREE FROM VISUAL IMPERFECTIONS INCLUDING PITTING, SEAM MARKS, ROLLER MARKS, STAINS AND DISCOLORATIONS, AND OTHER IMPERFECTIONS, INCLUDING THOSE WHICH WOULD IMPAIR PAINTING.
- C. DUCTWORK, METAL GAUSES, REINFORCING, ETC. SHALL BE CONSTRUCTED IN ACCORDANCE WITH SMACNA HVAC DUCT CONSTRUCTION STANDARDS, LATEST EDITION FOR A 2 INCH WATER GAUGE STATIC PRESSURE.
- 1) RECTANGULAR DUCT:
- a) ELBOWS, UNLESS INDICATED OTHERWISE SHALL BE CONSTRUCTED WITH CENTERLINE RADIUS OF NOT LESS THAN 1.5 DUCT WIDTH OR SQUARE ELBOW WITH DOUBLE WALL STREAMLINE VANES.
- b) RETURN AIR ACoustical ELBOWS AND SOUND BOOTS SHALL BE A SQUARE ELBOW WITH NO TURNING VANES.
- c) SLOPES FOR TRANSITIONS OR OTHER CHANGES IN DIMENSIONS SHALL BE MINIMUM 1 TO 3.
- D. DUCT SIZES SHOWN ON THE DRAWINGS ARE SHEETMETAL SIZES, ALLOWANCE FOR DUCT LINER HAS BEEN MADE WHERE APPLICABLE.
- E. INSTALLATION OF METAL DUCTWORK:
- 1) GENERAL: ASSEMBLE AND INSTALL DUCTWORK IN ACCORDANCE WITH RECOGNIZED INDUSTRY PRACTICES WHICH WILL ACHIEVE AIR-TIGHT SYSTEMS (MAXIMUM RIL LEAKAGE) WITH NO OBJECTIONABLE NOISE AND CAPABLE OF PERFORMING INDICATED SERVICE. INSTALL EACH RUN WITH MINIMUM NUMBER OF JOINTS. ALIGN DUCTWORK ACCURATELY WITH INTERNAL SURFACES SMOOTH. SUPPORT DUCTS RIGIDLY WITH SUITABLE STRAPS, BRACES, HANGERS AND ANCHORS IN ACCORDANCE WITH SMACNA HVAC DUCT CONSTRUCTION STANDARDS' LATEST EDITION. DUCT HANGERS SHALL BE OF 18 GAUGE STEEL OR 1/2" DIA. GALVANIZED STEEL OR 1/2" DIA. GALVANIZED BUCKLING. SUPPORT VERTICAL DUCTS AT EVERY FLOOR.
- 2) AUXILIARY STEEL: PROVIDE AUXILIARY STEEL AS REQUIRED TO ADEQUATELY SUPPORT DUCTWORK. GULCHING AND OTHER STRUCTURAL AND PERMANENT ENCLOSURE ELEMENTS OF BUILDINGS, WHENEVER POSSIBLE IN FINISHED AND OCCUPIED SPACES, CONCEAL DUCTWORK FROM VIEW BY LOCATING IN MECHANICAL SHAFTS, HOLLOW WALL CONSTRUCTION OR ABOVE SUSPENDED CEILINGS. DO NOT ENCASE SOLID-STATE RUNS IN SOLID PARTITIONS, EXCEPT AS SPECIFICALLY SHOWN. COORDINATE LAYOUT WITH SUSPENDED CEILING AND LIGHTING LAYOUTS AND SIMILAR FINISHED WORK.
- 4) DO NOT ROUTE DUCTWORK THROUGH ELECTRICAL EQUIPMENT SPACES AND ENCLOSURES, UNLESS INDICATED OTHERWISE.
- 5) PENETRATIONS:
- a) WHERE DUCTS PASS THROUGH INTERIOR PARTITIONS OR EXTERIOR WALLS, AND ARE EXPOSED TO VIEW, CONCEAL SPACE BETWEEN OPENING AND DUCT OR DUCT INSULATION WITH SHEET METAL FLANGES OF SAME GAGE AS DUCT. OVERLAP OPENING ON 4 SIDES BY AT LEAST 1-1/2" FASTEN TO DUCT AND WALL.
- b) WHERE DUCTS PASS THROUGH FIRE-RATED FLOORS, WALLS, OR PARTITIONS, PROVIDE FIRESTOPPING BETWEEN DUCT AND WALL.
- 6) COORDINATION: COORDINATE DUCT INSTALLATIONS WITH INSTALLATION OF ACCESSORIES, DAMPERS, COIL FRAMES, EQUIPMENT, CONTROLS, AND OTHER ASSOCIATED WORK OF THE DUCTWORK SYSTEM.
- 7) INSTALLATION: INSTALL METAL DUCTWORK IN ACCORDANCE WITH SMACNA HVAC DUCT CONSTRUCTION STANDARDS', LATEST EDITION.
- F. EQUIPMENT CONNECTIONS:
- 1) CONNECT METAL DUCTWORK TO EQUIPMENT AS INDICATED, PROVIDE FLEXIBLE CONNECTION FOR EACH DUCTWORK CONNECTION TO EQUIPMENT MOUNTED ON VIBRATION ISOLATORS, AND/OR EQUIPMENT CONTAINS ROTATING AND VIBRATING PARTS. PROVIDE ACCESS DOORS AS REQUIRED.
- G. SEAL ALL CONCEALED DUCTWORK JOINTS WITH NON-HARDENING, NON-MIGRATING MASTIC SEALANT, AS RECOMMENDED FOR SEALING SEAMS AND JOINTS IN DUCTWORK. OIL BASE CAULKING AND GLAZING COMPOUNDS SHALL NOT BE ACCEPTABLE. DUCTS SHALL BE SEALED TO THE GLASS LEVEL LISTED BELOW.
- 1) UNCONDITIONED SPACES CLASS B CLASS A CLASS C CLASS D
- 2) CONDITIONED SPACES (PLENUM) CLASS C CLASS B CLASS B CLASS C
- SUPPLY: 2" K/C SUPPLY: 2" K/C EXHAUST/DRYER RETURN
12. FLEXIBLE DUCT:
- A. ATCO 4076 (R-6), OR EQUAL.
- B. FACTORY APPLIED INSULATION AND VAPOR BARRIER.
- C. MAXIMUM LENGTH OF 5'-0".
13. EXHAUST FANS:
- A. CENTRIFUGAL CEILING EXHAUSTERS SHALL BE ELECTRICALLY POWERED CENTRIFUGAL TYPE FAN SUITABLE FOR MOUNTING IN THE CEILING WITH A PERFORATED OFF-WINDING METAL GRILLE WITH A THUMBSCREW ATTACHMENT FOR EASY ACCESS TO FAN HOUSING. UNIT SHALL CONSIST OF A GALVANIZED STEEL HOUSING LINED WITH ACoustical INSULATION AND SHALL INCLUDE AN INTEGRAL BACKDRAFT DAMPER ON FAN DISCHARGE. MOTOR SHALL BE A PERMANENT SPLIT-CAPACITOR TYPE MOTOR, PERMANENTLY LUBRICATED, WITH THERMAL OVERLOAD PROTECTION. PROVIDE DISCONNECT SWITCH OR OTHER MEANS OF DISCONNECT AT MOTOR IN FAN HOUSING.
14. REMODELING WORK:
- A. DEMOLITION: DISCONNECT, DEMOLISH, AND REMOVE ABANDONED MECHANICAL MATERIALS AND EQUIPMENT INDICATED TO BE REMOVED AND NOT INDICATED TO BE SALVAGED OR REMAIN.
- B. EQUIPMENT TO BE SALVAGED:
- 1) DISCONNECT AND REMOVE EXISTING MECHANICAL EQUIPMENT INDICATED TO BE REMOVED AND SALVAGED. DELIVER EQUIPMENT TO THE LOCATION DESIGNATED BY THE OWNER FOR STORAGE.
- 2) ALL MATERIALS AND EQUIPMENT INDICATED TO BE REUSED OR RELOCATED SHALL BE CAREFULLY REMOVED AND STORED UNTIL NEEDED FOR REMODELING WORK. ALL ITEMS SHALL BE RESTORED TO LIKE NEW CONDITION WITH RUST OR CORROSION REMOVED, SURFACE PAINT TOUCHED UP OR REPAINTED AS REQUIRED TO MATCH NEW CONSTRUCTION, AND THOROUGHLY CLEANED AND INSPECTED. ANY ITEMS WHICH BECOME DAMAGED BEYOND REPAIR AS A RESULT OF CONSTRUCTION OR DEMOLITION ACTIVITY SHALL BE REPLACED WITH NEW MATERIAL EQUIVALENT IN EVERY RESPECT.
- C. DISPOSAL AND CLEANUP: REMOVE FROM THE SITE AND LEGALLY DISPOSE OF DEMOLISHED MATERIALS AND EQUIPMENT NOT INDICATED TO BE SALVAGED.
- D. PROTECT ADJACENT MATERIALS INDICATED TO REMAIN. INSTALL AND MAINTAIN DUST AND NOISE BARRIERS TO KEEP DIRT, DUST, AND NOISE FROM BEING TRANSMITTED TO ADJACENT AREAS. REMOVE PROTECTION AND BARRIERS AFTER REMODELING OPERATIONS ARE COMPLETE.
- E. LOCATE, IDENTIFY, AND PROTECT MECHANICAL SERVICES PASSING THROUGH REMODELING AREA AND SERVING OTHER AREAS OUTSIDE THE REMODELING LIMITS. MAINTAIN SERVICES TO AREAS OUTSIDE REMODELING LIMITS. WHERE MECHANICAL SERVICES ARE LOCATED IN A WALL, ETC. TO BE DEMOLISHED, REROUTE PIPING TO NEW OR EXISTING CONSTRUCTION TO MAINTAIN CONTINUITY OF THE SYSTEM. WHEN SERVICES MUST BE INTERRUPTED, INSTALL TEMPORARY SERVICES FOR AFFECTED AREAS.
- F. REMOVE ALL PIPING TO BE DEMOLISHED BACK TO PIPE MAIN OR EDGE OF PROJECT AREA, AND CAP PIPE.
- G. PIPING AND DUCTS EMBEDDED IN FLOORS, WALLS, AND CEILINGS MAY REMAIN IF SUCH MATERIALS DO NOT INTERFERE WITH NEW INSTALLATIONS. PIPING AND DUCTS TO REMAIN SHALL BE APPROVED BY THE ARCHITECT. REMOVE MATERIALS ABOVE ACCESSIBLE CEILINGS, DRAIN AND CAP PIPING AND DUCTS ALLOWED TO REMAIN ABOVE CEILING OR BELOW FLOOR, CONCEALED FROM VIEW, EXCEPT AS OTHERWISE NOTED. PATCH FLOOR TO MATCH EXISTING.
- H. PIPE AND DUCT SHALL BE CONCEALED WITH NEW OR EXISTING CONSTRUCTION WHENEVER POSSIBLE, UNLESS INDICATED OTHERWISE.

BC PROJECT #:

MISSOURI PE COA #209003629


This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Design Engineer and is intended for use on the project only. Pursuant to the Architectural Board's Copyright Protection Act of 1985, all drawings, specifications, and other designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Design Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.

8/28/2023



GUY GRONBERG
ARCHITECTS, P.C.

119 SE 3rd St.
Lee's Summit, MO 64063
Phone: 816-524-0516
Fax: 816-524-2516



BC ENGINEERS
INCORPORATED

5720 Reseller Shawnee, KS 66203 (913) 662-1772

Abby Jewell DDS
ORTHODONTICS

2070 NW LOWENSTEIN DR. Unit A, LEE'S SUMMIT, MO 64081


REV#	DATE	DESCRIPTION
1	07/20/23	APPENDUM #1
Issue Date:		04-07-23
Project #:		23016

MECHANICAL
SPECIFICATIONS

MP0

REV#	DATE	DESCRIPTION
1	04/20/23	ADDENDUM #1

Issue Date:	04-07-23
Project #:	23016




1. CONNECT 1/2" CN TO MODEL TRIMMER WITH SHUT OFF ABOVE COUNTER PER THE MANUFACTURER'S REQUIREMENTS.
2. CONNECT 1/2" CN TO VACUUM PUMP WITH RPZ AS REQUIRED BY DENTAL EQUIPMENT MANUFACTURER. ROUTE DRAIN FROM RPZ TO FLOOR SINK WITH AIR GAP AS REQUIRED.
3. INTERCEPT EXISTING 1" WATER SERVICE BELOW FLOOR. RUN WATER BELOW SLAB TO EQUIPMENT 111. VERIFY EXACT LOCATION PRIOR TO INSTALLATION OF ANY PIPING.
4. CONNECT HOT WATER REGRG. PIPING BACK TO WATER HEATER AS REQUIRED. REFER TO RISER DIAGRAM FOR DETAILS.
5. PROVIDE ICE MAKER BOX WITH VALVE FOR CONNECTION TO REFRIGERATOR BY OTHERS.
6. CAP EXISTING WATER LINE IN FLOOR AS REQUIRED.
7. RELOCATE EXISTING RPZ/PRV TO LOCATION SHOWN AS REQUIRED. ROUTE DISCHARGE PIPING TO FLOOR SINK WITH AIR GAP.
8. PROVIDE RECESSED ICE MAKER BOX WITH VALVE FOR CONNECTION TO COFFEE TO BE INSTALLED BELOW COUNTER IN BASE CABINET.
9. EXISTING RPZ IS TO BE RELOCATED TO EQUIP 111. REMOVE CN TO BELOW FLOOR AND CAP. REMOVE ALL UNUSED CN ABOVE FLOOR.
10. CAP 1/2" CN LINE WITH SHUT OFF VALVE IN WALL FOR FUTURE USE.

BC PROJECT #:	23542 LD/FS
MISSOURI	PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.



GUY GRONBERG
ARCHITECTS, P.C.
Lee S Summit, MO 64069
Phone 816.524.0316
Fax 816.524.2510




BC ENGINEERS
INCORPORATED
5720 Reeder Shawnee, KS 66203 (913) 262-1772

Abby Jewell DDS
ORTHODONTICS
2070 NW LOWENSTEIN DR, Unit A, LEE'S SUMMIT, MO 64081


REV#	DATE	DESCRIPTION
1	09/20/23	APPENDIX #1
Issue Date: 09-07-23		
Project #: 23016		

PLUMBING
AIR AND VACUUM
FLOOR PLAN

P3



PLUMBING AIR AND VACUUM FLOOR PLAN
SCALE: 1/4" = 1'-0"
NORTH




UNDERFLOOR MED GAS JUNCTIONS
SCALE: 1/4"=1"

VACUUM LINE SIZING CHART	
NUMBER OF OPERATORIES SUPPLIED THROUGH LINE	MAIN LINE (PVC) PIPE DIAMETER IN INCHES
1	3/4
2	1
3	1
4	1 1/4
5	1 1/4
6	1 1/4
7	1 1/2
8	1 1/2
9	2
10	2
11	2

AIR LINE SIZING CHART	
COMPRESSOR CFM @ 80 psig	MAIN HEADER LINE SIZE
5 - 10	3/8" ODT
10 - 20	1/2" ODT
20 - 30	5/8" ODT
30 - 40	3/4" ODT

- PLUMBING PLAN NOTES:**
- STUB UP 3/4" VACUUM PIPING AND 1/2" AIR PIPING FOR FUTURE CONNECTION TO ORTHO CHAIRSIDE DELIVERY STUBBED UP IN UTILITY BOX. COORDINATE EXACT LOCATION WITH DENTAL EQUIPMENT SUPPLIER. PROVIDE 3/8" COMPRESSION SHUT-OFF VALVE ON AIR LINES. CONNECT AS REQUIRED BY MANUFACTURER. UTILITY BOX SUPPLIED BY E.C.
 - PROVIDE AND INSTALL 3/4" VAC LINE ABOVE SINK CABINET.
 - PROVIDE AND INSTALL AIR LINE WITH 3/8" COMPRESSION SHUT-OFF VALVE ABOVE SINK CABINET. COORDINATE EXACT LOCATION WITH OWNER.
 - CUT EXISTING ROOF AND FLASH INTO ROOF AS REQUIRED. ALL ROOFING WORK SHALL BE PERFORMED BY LANDLORD'S ROOFING CONTRACTOR (AT THIS CONTRACTOR'S EXPENSE) TO MAINTAIN EXISTING ROOF WARRANTY. VERIFY APPROVED ROOFING CONTRACTOR WITH LANDLORD PRIOR TO PERFORMING WORK.
 - CONNECT 2" VACUUM PIPE TO AMALGAM SEPARATOR AND VACUUM PUMP AS REQUIRED BY THE MANUFACTURER.
 - CONNECT 3/4" COMPRESSED AIR PIPE TO OWNER FURNISHED AIR COMPRESSOR AS REQUIRED BY MANUFACTURER.
 - ROUTE 2" METALLIC VACUUM PUMP EXHAUST VENT UP THROUGH ROOF AND PROVIDE GOOSENECK. MAINTAIN 10' CLEARANCE FROM OUTDOOR AIR INTAKES.
 - ROUTE 2" OUTSIDE AIR INTAKE FOR AIR COMPRESSOR UP THROUGH ROOF AND PROVIDE GOOSENECK.
 - PROVIDE AND INSTALL 3/4" VAC LINE ABOVE SINK CABINET. COORDINATE LOCATION WITH TENANT.
 - PROVIDE AND INSTALL AIR LINE WITH 3/8" COMPRESSION SHUT-OFF VALVE ABOVE SINK CABINET. COORDINATE LOCATION WITH TENANT.
 - SLOPE A MINIMUM OF 1/4" / 10' WITH LOW END TOWARDS TANK. USE 45 DEGREE ELBOWS. BRANCH LINES TO BE CONNECTED TO MAIN LINES USING PVC SWEEPING WYE AND/OR 45 DEGREE ELBOW (DO NOT USE STANDARD TEE). ALL BRANCH LINES TO BE STAGGERED. IF AN INLINE LOW SPOT IS UNAVOIDABLE, PLACE IT IN A KNOWN LOCATION AND INCORPORATE A CLEANOUT.

BC PROJECT #: 23542 LD/FS
MISSOURI PE COA #2009003629
This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Design Engineer and is intended for use on the project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of space and elements appearing herein, constitute the original, copyrighted work of the Design Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.

[illegible]

PIPE SIZES GIVEN ON THE DRAWINGS ARE NOMINAL COPPER PIPE SIZE. IF PEX PIPING IS USED, INCREASE PEX PIPING ONE SIZE ABOVE LISTED SIZES AS REQUIRED TO EQUAL OR EXCEED COPPER PIPE INSIDE DIAMETER.

<u>PLUMBING DRAINAGE CALCULATIONS</u>			
<u>FIXTURE</u>	<u>QUANTITY</u>	<u>FU</u>	<u>TOTAL FU</u>
WATER CLOSETS	2	4	8
LAVATORIES	5	1	5
SINKS	5	2	10
FLOOR DRAIN	1	2	2
FLOOR SINK	1	2	2
MOP BASIN	1	2	2
<u>TOTAL</u>			<u>29 FU</u>
VENT MAINS - 3"			
WASTE MAIN - 4"			

PLUMBING FIXTURE WATER COUNT						
FIXTURE	QUANTITY	CN FU	CU FU	HN FU	TOTAL FU	COMBINED TOTAL FU
WATER CLOSETS	3	5	10	0	0	5
LAVATORIES	5	1.5	7.5	1.5	7.5	2
DENTAL SINKS	2	1.5	3	1.5	3	2
SINKS	3	2.25	6.75	0.25	6.75	3
VACUUM PUMP	1	2.25	2.25	0.25	2.25	3
MOP BASIN	1	1	1	0.25	0	1
MODEL TRIMMER	1				0	
ICE BOX	1	.25	.25			.25
			31.25 FU		19.5 FU	39.25 FU
COLD WATER MAIN - 1"						
HOT WATER MAIN - 1"						

FIXTURE	WASTE	VENT	GVN	HVN
WATER CLOSET (TANK TYPE)	3"	2"	1/2"	- "
LAVATORY	1-1/4"	1-1/4"	1/2"	1/2"
DENTAL SINK	1-1/2"	1-1/2"	1/2"	1/2"
SINK	1-1/2"	1-1/2"	1/2"	1/2"
FLOOR DRAIN	2"	2"	- "	- "
FLOOR SINK	3"	2"	- "	- "
ICE BOX	- "	- "	1/2"	- "
MOP BASIN	1-1/2"	1-1/2"	1/2"	1/2"


NOTE: INDIVIDUAL VENTS FOR FIXTURES ON PLANS AND RISER DIAGRAMS HAVE BEEN INCREASED WHERE HORIZONTAL VENT LENGTH IS IN EXCESS OF THE MAXIMUM DISTANCE INDICATED BY THE CODE.

PIPE HANGER SCHEDULE		
PIPE MATERIAL	MAXIMUM HANGER SPACING	HANGER ROD DIAMETER
ABS (All sizes)	4'	3/8"
PVC (All Sizes)	4'	3/8"
CPVC, 1 inch and smaller	3'	1/2"
CPVC, 1-1/4 inches and larger	4'	1/2"
Cast Iron (All Sizes)	5'	5/8"
Cast Iron (All Sizes) with 10 foot length of pipe	10'	5/8"
Copper Tube, 1-1/4 inches and smaller	6'	1/2"
Copper Tube, 1-1/2 inches and larger	10'	1/2"
Steel, 3 inches and smaller	12'	1/2"
Steel, 4 inches and larger	12'	5/8"
Pex, 1" and below without support channel	32"	3/8"
Pex, 1-1/4" and above without support channel	48"	3/8"
Pex 3/4" and below with support channel	6'	3/8"
Pex 1" and above with support channel	8'	3/8"

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by this Designer/Engineer and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2003 BC Engineers, Inc.



**GUY GRONBERG
ARCHITECTS, P.C.**
Lee S Summit, MO 64069
Phone 816.524.0216
Fax 816.524.2510




**BC ENGINEERS
INCORPORATED**
5720 Reeder Shawnee, KS 66203 (913) 262-1772

**Abby Jewell DDS
ORTHODONTICS**
2070 NW LOWENSTEIN DR. Unit A, LEES SUMMIT, MO 64081

REV/#	DATE	DESCRIPTION
1	07/20/23	APPENDIX #1
Issue Date: 09-07-23		
Project #: 23016		

MECHANICAL
FLOOR PLAN

M1



MECHANICAL FLOOR PLAN

SCALE: 1/4" = 1'-0"

MECHANICAL GENERAL NOTES:

- COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
- THIS CONTRACTOR SHALL PERFORM ALL WORK INDICATED AND/OR AS REQUIRED FOR THE PROPER INSTALLATION AND OPERATION OF THE MECHANICAL SYSTEMS.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATIONS OF DIFFUSERS.
- INSTALL ALL DUCT, PIPE, ETC. AS HIGH AS POSSIBLE.
- DUCT SIZES SHOWN ARE ACTUAL SHEET METAL SIZES AND INCLUDE AN ALLOWANCE FOR DUCT LINER WHERE APPLICABLE.
- PROVIDE FLEXIBLE CONNECTION BETWEEN DUCTWORK AND ROOFTOP UNITS, EXHAUST FANS, AND OTHER MOTORIZED EQUIPMENT.
- NO DUCT SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
- ALL MECHANICAL SYSTEMS SHALL BE BALANCED BY A CERTIFIED BALANCING CONTRACTOR. REFER TO SPECIFICATIONS FOR DETAILS.

MECHANICAL SYMBOLS

- NEW SUPPLY DIFFUSER
- NEW RETURN AIR GRILLE
- EXHAUST GRILLE/FAN
- THERMOSTAT, MOUNTED AT 48" AFF
- NEW DUCTWORK
- 32"x14" SIZE OF RECTANGULAR DUCT
- 6"Ø SIZE OF ROUND DUCT
- FLEXIBLE DUCTWORK
- FLEXIBLE CONNECTION TO FAN
- FLOOR PLAN NOTE DESIGNATION
- S.A. SUPPLY AIR
- R.A. RETURN AIR
- EXH. EXHAUST AIR
- TRANSITION IN DUCT SIZE
- MANUAL VOLUME DAMPER
- MOTORIZED CONTROL DAMPER
- SUPPLY AIR DUCT UP/DOWN
- RETURN AIR DUCT UP/DOWN
- EXHAUST AIR DUCT UP/DOWN
- RTU-1 SCHEDULED MECHANICAL EQUIPMENT

MECHANICAL PLAN NOTES:


- EXISTING ROOF TOP UNIT, EX RTU-1, IS EXISTING TO REMAIN. SET CFM TO 1,600 CFM AND OA INTAKE TO 210 CFM.
- EXISTING ROOF TOP UNIT, EX RTU-2, IS EXISTING TO REMAIN. SET CFM TO 1,600 CFM AND OA INTAKE TO 210 CFM.
- SUPPORT FAN FROM STRUCTURE AS REQUIRED BY THE MANUFACTURER.
- THERMAL TRANSFER DUCT SHALL BE ROUTED TO RETURN AIR DUCT AS SHOWN AND AS REQUIRED.
- PROVIDE TRANSFER AIR SOUND BOOT FROM HALL SPACE DOWN TO 48" AFF IN EQUIPMENT ROOM. PROVIDE 1" SOUND ABSORBING DUCT LINING AND SEAL GAPS AROUND WALL PENETRATION TO MAINTAIN SOUND RATING.
- PROVIDE THERMOSTAT IN LOCATION SHOWN. MOUNT AT 48" AFF. THERMOSTAT SHALL BE COOL ONLY SET TO 80°F. COORDINATE WITH ELECTRICAL SO THAT THERMOSTAT ENERGIZES EXHAUST FAN.
- RELOCATE EXISTING THERMOSTAT SENSOR TO LOCATION SHOWN. MOUNT 48" A.F.F.
- CUT EXISTING ROOF AND FLASH INTO ROOF AS REQUIRED. ALL ROOFING WORK SHALL BE PERFORMED BY BUILDING OWNER'S ROOFING CONTRACTOR (AT THIS CONTRACTOR'S EXPENSE) TO MAINTAIN EXISTING ROOF WARRANTY. VERIFY APPROVED ROOFING CONTRACTOR WITH BUILDING OWNER PRIOR TO PERFORMING WORK.
- PROVIDE WEATHER HEAD WITH BACKDRAFT DAMPER FOR EXHAUST FAN. SEAL PENETRATIONS WEATHERTIGHT. MAINTAIN A 10'-0" CLEARANCE FROM ALL OUT DOOR AIR INTAKES.
- PROVIDE THERMOSTAT AT 48" AFF FOR VAV DIFFUSER. MASTER CONTROLLER AND POWER SUPPLY LOCATED ABOVE CEILING. CONTRACTOR TO PROVIDE LOW VOLTAGE COMMUNICATION WIRING BETWEEN CONTROLLER, TSTAT, AND EACH DIFFUSER.
- HIGH/LOW RETURN AIR GRILLES - IT SIDE GRILLE LOCATED AT 12" AFF. DOCTOR SIDE LOCATED AT 8" AFF. ADD SHEET METAL DUCT INSIDE WALL IF WOOD STUD CONSTRUCTION.
- INSTALL EXHAUST GRILLE ON BOTTOM SIDE OF CASEWORK ABOVE COUNTER AS REQUIRED. COORDINATE WITH G.C. TO ROUTE 6"Ø DUCT INSIDE OF CASEWORK COORDINATE EXACT LOCATION WITH OWNER.
- PROVIDE THERMOSTAT AT 48" AFF FOR VAV DAMPER. MASTER CONTROLLER AND POWER SUPPLY LOCATED ABOVE CEILING. CONTRACTOR TO PROVIDE LOW VOLTAGE COMMUNICATION WIRING BETWEEN CONTROLLER, TSTAT, AND DAMPER.

BC PROJECT #: 23542 LD/FS
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Design Engineer and is intended for use on the project only. Pursuant to the Architectural Rules, Copyright Protection Act of 1980, all drawings, specifications, plans and designs, including the overall form, arrangement and composition of space and elements appearing herein, constitute the original, copyrighted work of the Design Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.




GUY GRONBERG
ARCHITECTS, P.C.
119 SE 3rd St.
Lee's Summit, MO 64063
Phone 816324-0510
Fax 816324-2510



BC ENGINEERS
INCORPORATED
5720 Reeder Shawnee, KS 66203 (913)862-1772

Abby Jewell DDS
ORTHODONTICS
2070 NW LOWENSTEIN DR. Unit A, LEE'S SUMMIT, MO 64081




REV#	DATE	DESCRIPTION
1	09/20/23	APPENDIX #1
Issue Date:		09-07-23
Project #:		23016

MECHANICAL
DETAILS AND SCHEDULE

M2


OUTDOOR AIR CALCULATIONS

UNIT	Area (sqft)	OCCUPANCY CLASSIFICATION	Occupant Density #/1000 sqft	People outdoor airflow rate in breathing zone, (Rp) cfm/person	Area outdoor airflow rate in breathing zone, (Ra) cfm/sqft	Exhaust airflow rate cfm/sqft	Breathing zone outdoor airflow (Vbz)	Zone air distribution effectiveness (Ez)	Zone outdoor airflow (cfm)
EX RTU-1	652	Office spaces	5	5	0.06		55	0.8	64
	153	Break Room	25	5	0.06		28	0.8	35
	114	Corridors	0	0	0.06		7	0.8	4
	80	Toilet rooms public	0	0	0	50/10	0	0.8	0
	58	Storage rooms	0	0	0.12		7	0.8	4
Total									122
EX RTU-2	637	Office spaces	5	5	0.06		54	0.8	63
	362	Main entry lobbies	10	5	0.06		40	0.8	50
	104	Corridors	0	0	0.06		6	0.8	8
	53	Toilet rooms public	0	0	0	50/10	0	0.8	0
Total									125



* MAY VARY AS REQUIRED FOR
CLEARANCE WITH LIGHT FIXTURES, ETC.

RA SOUND BOOT DETAIL
NO SCALE



DIFFUSER DETAIL
SCALE: NONE

DIFFUSER SCHEDULE

MARK	MFGR	MODEL	BORDER TYPE	NECK SIZE	FACE SIZE	FINISH	DAMPER	ACCESSORIES	NOTES
SD-1	TITUS	OMNI	3	6"Ø	12"x12"	WHITE	OPPOSED BLADE	GYP. FRAME	-
SD-2				6"Ø	24"x24"		-		-
SD-3				8"Ø			-		-
SD-4				10"Ø			-		-
SD-VAV		T35Q-2		8"Ø			INTERNAL VAV		2
RG-1		PAR		15"x15"			-		-
RG-2		PAR		10"x22"	12"x24"		-		4
T6-1		35ORL	1	10"x10"	12"x12"		-		1,3
T6-2		35ORL	1	12"x8"	- -		-		-
EG-1		PAR	1	6"Ø	12"x12"		-		-

- NOTES:
- SEE RA SOUND BOOT DETAIL FOR CLARITY.
 - PROVIDE 120/24VAC TRANSFORMERS (T3PM120) AND CONTROLLER/THERMOSTATS AND MASTER COMMUNICATION MODULES (MCMSA-STAND ALONE) AND ALL ASSOCIATED ACCESSORIES AND WIRING FOR A COMPLETE OPERATIONAL SYSTEM.
 - CENTER GRILLE IN TILE, PROVIDE FLANGE.
 - PROVIDE REQUIRED BACK PLATE ADAPTOR FOR CONNECTION TO ROUND DUCT.

EXHAUST/TRANSFER FAN SCHEDULE

MARK	MFGR	MODEL	CFM	EXTERNAL STATIC P. IN. WG.	RPM	ELECTRICAL		FAN TYPE	CONTROLS	NOTES
						VOLT/Ø/HZ	PAW			
EF-1	COOK	GC-148	75	0.3	1,075	120/1/60	32 W	CEILING EXH.	LIGHT SWITCH	1
EF-2		GC-148	75		1,075		33 W		LIGHT SWITCH	1
EF-3		GC-148	75		1,075		32 W		LIGHT SWITCH	1
EF-4		GN-148	75	0.3	1,075		32 W	IN-LINE	SWITCH	5
EF-5		GC-186	150	0.35	1,100		67 W	CEILING EXH.	SWITCH	1,4
EF-6		GC-186	150	0.35	1,100		67 W		SWITCH	1,4
TF-7		GC-188	150	0.2	1,450		69 W		THERMOSTAT	2,3
TF-8		GC-642	400	0.15	1,500		124 W		THERMOSTAT	2,3

- NOTES:
- PROVIDE CEILING GRILLE, INTEGRAL BACK DRAFT DAMPER, VARI-SPEED CONTROLLER (NEAR FAN AND ABOVE CEILING), FACTORY MEANS OF DISCONNECT AND WEATHER HEAD.
 - PROVIDE CEILING GRILLE, INTEGRAL BACK DRAFT DAMPER, VARI-SPEED CONTROLLER (NEAR FAN AND ABOVE CEILING), AND FACTORY MEANS OF DISCONNECT.
 - PROVIDE LINE VOLTAGE COOLING ONLY THERMOSTAT FOR CONTROL OF FAN. SET TO 80°F.
 - CENTER GRILLE IN TILE, PROVIDE FLANGE.
 - PROVIDE INTEGRAL BACK DRAFT DAMPER, VARI-SPEED CONTROLLER (NEAR FAN), AND FACTORY MEANS OF DISCONNECT.

EXISTING GAS HEAT ROOFTOP UNIT SCHEDULE

MARK	MFGR.	MODEL NO.	NOM. TONS	EVAP. CFM	EXT. STATIC P. IN. WG. (NOTE 2)	COOLING		HEATING BTUH INPUT	ELECTRICAL		MINIMUM OUTDOOR AIR (CFM)	SEER	TOTAL HEIGHT (LBS)	NOTES
						COOLING STAGES	TOTAL BTUH		VOLT/Ø/HZ	AMPS				
RTU-1	TRANE	YSC 048 E3	4	1,600	0.7	(1) SCROLL	44,000	80,000	208/3/60	35	210	14.0	800	1
RTU-2	TRANE	YSC 048 E3	4	1,600	0.7	(1) SCROLL	44,000	80,000	208/3/60	35	210	14.0	800	1

- NOTES:
- ROOF TOP UNIT IS EXISTING TO REMAIN.

LINEAR DIFFUSER SCHEDULE

MARK	MFGR	MODEL	# SLOTS	DUCT WIDTH	LENGTH	FINISH	NOTES
LS-1	TITUS	ML-38 3/4	2	5-1/8"	48"	WHITE	1 - XV FLANGE
LS-2	TITUS	ML-38 3/4	1	2-1/2"	48"	WHITE	1, 2 - XV FLANGE

- NOTES:
- PROVIDE INSULATED PLENUM BOX FOR SUPPLY DIFFUSER.
 - PROVIDE MODEL SC2D-08 8" PRESSURE DEPENDENT ROUND MODULATING CONTROL DAMPER WITH 24V ACTUATOR AND SC220T ROOM THERMOSTAT AND ALL ASSOCIATED ACCESSORIES AND WIRING FOR A COMPLETE OPERATIONAL SYSTEM.

BC PROJECT #: 23542 LD/FS
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Design Engineer and is intended for use on the project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of space and elements appearing herein, constitute the original, copyrighted work of the Design Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.

ELECTRICAL SPECIFICATIONS

1. GENERAL PROVISIONS:
- A. PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, NECESSARY FOR THE COMPLETE INSTALLATION OF THE ELECTRICAL SYSTEMS OUTLINED.
- B. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE AUTHORITIES.
- C. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST APPROVED EDITION OF THE NATIONAL ELECTRIC CODE (NEC), AND ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION OVER THE SITE.
- D. ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.
- E. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, CONDUIT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNDAMAGED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERING SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.
- F. PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS AS NECESSARY. PATCH AROUND ALL OPENINGS SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.
- G. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
- H. CONTRACTOR SHALL PROVIDE ACCESS PANELS WHERE NECESSARY FOR CONCEALED ELECTRICAL COMPONENTS.
2. CONTRACTOR SHALL PROMPTLY CALL ENGINEERS ATTENTION TO ANY APPARENT CONDUCTIONS, AMBIGUITIES, ERRORS, DISCREPANCIES, OR OMISSIONS IN THE PLANS OR SPECIFICATIONS.
3. OPERATION AND MAINTENANCE MANUALS:
- A. DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, WIRING DIAGRAMS, CATALOG CUTS, LUBRICATION AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.
- B. ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATION AND MAINTENANCE MANUALS.
- C. ALL LITERATURE LISTED ABOVE AND ALL PAPERS LISTING WARRANTIES, ETC. SHALL BE COLLATED AND LABELED WITH THE PROJECT NAME, ADDRESS, ARCHITECT, ENGINEER, CONTRACTORS, ETC. CONTRACTORS, ETC. DOCUMENTS SHALL BE COMPILED AND BOUND IN DIGITAL FILE OR 3 RING BINDER.
4. MANUFACTURERS:
- A. MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSTRUED AS LIMITING COMPETITION. ARTICLES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO STRUCTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN, UNLESS NOTED OTHERWISE.
5. TESTS, AND BALANCING:
- A. ALL CIRCUITS SHALL BE TESTED FOR CONTINUITY, SHORTS, AND GROUNDS BEFORE CONNECTING TO THE PROPER PHASE AS DESIGNED TO BALANCE THE LOADS BETWEEN PHASES.
- B. POWER AND LIGHTING PANELS SHALL BE PROPERLY PHASED TO DISTRIBUTE THE LOAD AND SHALL BE CONNECTED AND ADJUSTED TO OPERATE AS SPECIFIED.
- C. ALL MOTORS AND SIMILAR EQUIPMENT SHALL BE CHECKED FOR PROPER PHASE ROTATION AND OPERATION.
6. RACEWAYS:
- A. CONDUIT INSIDE THE BUILDING SHALL BE METALLIC TUBING (EMT), BEARING THE UL LABEL, WITH COMPRESSION TYPE FITTINGS OR SCREW SET FITTINGS.
- B. CONDUIT EXPOSED TO THE WEATHER, INSTALLED UNDERGROUND, IN CONCRETE, OR USED FOR SERVICE ENTRANCE SHALL BE STANDARD RIGID CONDUIT (GALVANIZED) WITH THREADED FITTINGS.
- C. UNDERGROUND CONDUIT MAY BE POLYVINYL CHLORIDE WITH A DEFLECTION TEMPERATURE, UNDER LOAD AT 264 PSI, OF 19 DEGREES C AND A TENSILE STRENGTH OF 5,200 PSI. JOINTS SHALL BE FLUSH SOLVENT WELDED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE EQUAL TO CARLON POWER AND COMMUNICATIONS DUCT TYPE DB (DIRECT BURIAL). CONDUIT AND FITTINGS SHALL BE PROVIDED BY THE SAME MANUFACTURER.
- D. FLEXIBLE METAL CONDUIT SHALL ONLY BE USED FOR CONNECTIONS TO MOTORS, TRANSFORMERS, AND LIGHT FIXTURES. MAXIMUM LENGTH SHALL BE 6'-0".
7. CONDUCTORS:
- A. WIRES SHALL BE CONTINUOUS WITHOUT SPLICES OR TAPS IN CONDUIT RUNS. ALL SPLICES SHALL BE MADE IN JUNCTION, PULL, OR OUTLET BOXES. ALL WIRE SHALL BE INSTALLED IN CONDUIT, WIRERAYS, OR OTHER PROTECTIVE COVER SANCTIONED BY CODES.
- B. CONDUCTORS FOR LIGHTING AND POWER SHALL BE COPPER, MINIMUM NO. 12 AL#6, 600 VOLT.
- C. NO. 10 GAUGE AND SMALLER CONDUCTORS SHALL BE TYPE THHN (WET LOCATIONS) OR THHN (DRY LOCATIONS), SOLID CONDUCTOR, UNLESS OTHERWISE INDICATED.
- D. NO. 8 GAUGE AND LARGER CONDUCTORS SHALL BE TYPE THHN (WET LOCATIONS) OR THHN (DRY LOCATIONS), STRANDED, UNLESS OTHERWISE INDICATED.
- E. SERVICE ENTRANCE AND PANEL FEEDER CONDUCTORS, NO. 3 GAUGE AND LARGER SHALL BE TYPE XHHW-2 (WET LOCATIONS) OR THHN (DRY LOCATIONS), STRANDED COPPER, UNLESS OTHERWISE INDICATED.
- F. ALUMINUM SERVICE WIRE MAY BE USED FOR SERVICE ENTRANCE CONDUCTORS AND/OR PANEL FEEDERS ONLY. ALL OTHER WIRING SHALL BE COPPER CONDUCTORS AS HEREBEFORE SPECIFIED.
- G. ALUMINUM CONDUCTORS SHALL BE TYPE XHHW-2; ALCAN, "STABILLOY" TYPE ALLOY CONDUCTORS UTILIZING "A4-3030" ALUMINUM ALLOY. CONDUCTORS SHALL BE UL LISTED.
- H. ALL ALUMINUM CONDUCTORS SHALL BE TERMINATED IN CONNECTIONS OR LUGS WHICH ARE DUAL RATED (AL/CU OR AL/ALU) AND ARE LISTED BY UL FOR USE WITH ALUMINUM OR COPPER CONDUCTORS AND SHALL BE SIZED TO ACCEPT ALUMINUM CONDUCTORS OF THE AMPACITY SPECIFIED.
8. MC CABLE:
- A. MC CABLE SHALL CONSIST OF INTERLOCK ARMORED CABLE MADE OF THREE OR FOUR TYPE THHN SOLID 18 AWG AND LARGER MAY BE STRANDED COPPER CONDUCTORS RATED 90°C FOR DRY LOCATIONS, WITH NYLON OR EQUIVALENT UL LISTED JACKET, PER UL STANDARD 83 THE THREE CONDUCTORS SHALL BE TWISTED TOGETHER WITH THE COPPER GROUNDING CONDUCTOR, SUITABLE FILLERS, AND WRAPPED IN BINDER TAPE. THE ASSEMBLY SHALL BE ARMORED WITH SPIRALLY WRAPPED INTERLOCKED ARMOR OF ALUMINUM OR GALVANIZED STEEL.
- B. CABLES SHALL BE TESTED IN ACCORDANCE WITH UL STANDARD 1564 FOR TYPE MC CABLE AND RATED AT 600 VOLTS, 90 DEG. C FOR DRY LOCATIONS AND 75 DEG. C FOR WET LOCATIONS.
- C. MC CABLE INSTALLED IN PATIENT CARE AREAS SHALL BE "HCF" TYPE WITH GREEN INSULATED COPPER GROUNDING CONDUCTOR, BARE ALUMINUM GROUNDING/BONDING CONDUCTOR AND INTERLOCKED GREEN ALUMINUM ARMOR LISTED FOR USE AS AN EQUIPMENT GROUNDING CONDUCTOR IN CONJUNCTION WITH THE BARE ALUMINUM BONDING CONDUCTOR.
- 1) CABLES SHALL MEET ALL NEC REQUIREMENTS FOR ARTICLE 517 AND SHALL BE UL LISTED FOR USE IN HEALTH CARE FACILITIES.
- 2) HCF CABLE SHALL NOT BE USED IN HAZARDOUS ANESTHETIZING AREAS.
- D. MC CABLE INSTALLED UNDERGROUND IN PATIENT CARE AREAS SHALL BE "HCF MCAP" TYPE PVC JACKETED ALL PURPOSE CABLE WITH GROUNDING CONDUCTOR, BARE ALUMINUM GROUNDING/BONDING CONDUCTOR AND INTERLOCKED GREEN ALUMINUM ARMOR LISTED FOR USE AS AN EQUIPMENT GROUNDING CONDUCTOR IN CONJUNCTION WITH THE BARE ALUMINUM BONDING CONDUCTOR.
- 1) CABLES SHALL MEET ALL NEC REQUIREMENTS FOR ARTICLE 517 AND SHALL BE UL LISTED FOR DIRECT BURIAL IN EARTH, EMBEDDED IN CONCRETE AND SUITABLE FOR WET LOCATIONS.
- 2) HCF MCAP CABLE SHALL NOT BE USED IN HAZARDOUS ANESTHETIZING AREAS.
9. WIRING DEVICES:
- A. WALL SWITCHES SHALL BE SPECIFICATION GRADE, QUIET TYPE, FLUSH TOGGLE SWITCH, RATED FOR 20 AMPS, WITH THERMOPLASTIC COVER PLATES.
- 1) SINGLE POLE: HUBBELL #C51221-X, OR EQUAL.
- 2) THREE WAY: HUBBELL #C51223-X, OR EQUAL.
- 3) AS SPECIFIED ON PLANS.
- B. RECEPTACLES SHALL BE SPECIFICATION GRADE, DUPLEX, GROUNDING, THREE-WIRE TYPE, RATED FOR 20 AMPS, WITH THERMOPLASTIC COVER PLATES. HUBBELL #C85952-X, OR EQUAL.
- C. GROUND FAULT INTERRUPTER RECEPTACLES (GFI) SHALL BE HUBBELL #GF20-XL. DEVICE COVER PLATES SHALL BE AS HEREBEFORE SPECIFIED.
- D. ISOLATED GROUND RECEPTACLES (IG) SHALL BE HUBBELL #C85952IG, ORANGE COLOR. DEVICE COVER PLATES SHALL BE AS HEREBEFORE SPECIFIED.
- E. RECEPTACLES OUTSIDE BUILDING AND WHERE NOTED AS WEATHERPROOF, SHALL BE LISTED WEATHER-RESISTANT HUBBELL #GFTR20-X OR EQUAL AND SHALL BE INSTALLED IN A WEATHERPROOF ENCLOSURE WHICH SHALL BE INTERMATIC WPD1000ND OR WPD1000ND DECAST METAL WEATHERPROOF RECEPTACLE COVER. COVER SHALL BE WEATHER PROOF RATED WHILE IN USE.
- F. VERIFY DEVICES AND DEVICE COVERPLATES COLOR AND STYLE WITH ARCHITECT.
10. BOXES:
- A. HOT DIPPED GALVANIZED STEEL BOXES. PROVIDE TYPE TO SUIT CONDITIONS FOR INSTALLATION.
- B. ALL BOXES SHALL BE FLUSH MOUNTED, UNLESS INDICATED OTHERWISE.

ELECTRICAL SPECIFICATIONS (CONTINUED)

11. PANELBOARDS:
- A. FURNISH AND INSTALL CIRCUIT BREAKER PANELBOARDS AS SHOWN ON THE DRAWINGS. PANELBOARDS SHALL BE LISTED BY UL AND SO LABELED, AND SHALL BE FULLY RATED FOR THE VOLTAGE AND CURRENT CAPACITY INDICATED ON THE PANEL SCHEDULE. PANELBOARDS SHALL BE EQUAL TO SQUARE D TYPE NG OR NF WITH BOLT IN TYPE BREAKERS. PANELBOARD LUGS SHALL BE RATED AT 75°C.
- 1) CIRCUIT BREAKER INTERRUPTING CAPACITIES SHALL MEET OR EXCEED THE AVAILABLE RMS SYMMETRICAL FAULT CURRENTS INDICATED AND AS REQUIRED TO MEET OR EXCEED THE AVAILABLE FAULT CURRENT FROM LOCAL UTILITY.
- B. CIRCUIT BREAKERS SHALL MEET APPLICABLE PORTIONS OF UL STANDARD 484 AND NEMA AB-1. CIRCUIT BREAKERS SHALL BE BOLT-ON, GROUP MOUNTED, AMBIENT MAGNETIC WITH COMMON TRIP, UL RATED TO CARRY 50% OF NAMEPLATE RATING CONTINUOUSLY IN FREE AIR AT 40° C. CIRCUIT BREAKERS SHALL BE TRIP INDICATING AND FULLY INTERCHANGEABLE WITHOUT DISTURBING ADJACENT UNITS. WIRE TERMINALS SHALL BE RATED 75 DEGREES C. THE OPERATING MECHANISM SHALL BE TRIP-FREE SO THAT CONTACTS CANNOT BE HELD CLOSED AGAINST ANY ABNORMAL OVERCURRENT OR SHORT CIRCUIT CONDITION.
- a) BREAKERS SHALL MEET APPLICABLE NEMA AND/OR UL SPECIFICATIONS.
- C. PANELBOARD BOXES SHALL BE GALVANIZED SHEET STEEL WITH AMPLE WIRING GUTTER SPACE IN ACCORDANCE WITH NEC. FRONTS SHALL BE OF SHEET STEEL PAINTED LIGHT GREY OVER A SUITABLE RUST INHIBITOR PRIMER. PANELBOARDS SHALL BE EQUIPPED WITH ONE PIECE DOOR, CYLINDER TUMBLER TYPE LOCK, DIRECTORY CARD-HOLDER AND QUARTER-TURN ADJUSTABLE TRIM CLAMPS.
- D. PANELBOARD INTERIORS SHALL CONSIST OF REINFORCED GALVANIZED SHEET STEEL FRAMES WITH ALUMINUM BUS BARS AND CIRCUIT BREAKERS, PROPERLY SUPPORTED TO PREVENT VIBRATIONS AND BREAKAGE IN HANDLING. BUS BARS SHALL BE SEQUENCE PHASED. PANELBOARD SHALL HAVE A FULL SIZED SOLID ALUMINUM NEUTRAL AND GROUND BUS.
- E. BUS BAR BRACINGS SHALL BE UL LISTED AS INDICATED ON DRAWINGS. ADDITIONAL BRACINGS SHALL BE PROVIDED AS REQUIRED TO MEET OR EXCEED INDICATED AVAILABLE FAULT CURRENTS.
- F. DIRECTORY CARDS SHALL BE COMPLETELY FILLED IN BY TYPEWRITER, LISTING CIRCUIT NUMBERS AND LOAD SERVED, INCLUDING EXISTING CIRCUITS. CIRCUIT BREAKERS SHALL BE IDENTIFIED BY CIRCUIT NUMBER LABELS AS HEREBEFORE SPECIFIED.
- EXISTING PANELBOARDS:
- A. PANELBOARDS ARE EXISTING AND SHALL BE REUSED. PROVIDE ADDITIONAL BREAKERS AS REQUIRED TO CONNECT CIRCUITS AS SHOWN ON THE DRAWINGS. ADDITIONAL BREAKERS SHALL BE THERMAL MAGNETIC, QUICK-BREAK, BOLT ON CATCH RATING BREAKERS WITH ONE HANDLE FOR SINGLE OR MULTI-POLE RATINGS AND SHALL BE COMPATIBLE WITH EXISTING PANELS.
- B. COMPLETE EXISTING DIRECTORY AS REQUIRED TO IDENTIFY NEW CIRCUIT, LISTING LOAD SERVED AND OTHER PERTINENT DATA.
12. DISCONNECTS:
- A. DISCONNECTS SHALL BE EXTERNALLY OPERATED, QUICK-MAKE, QUICK-BREAK, SAFETY, WITH PROVISIONS FOR PAD LOCKING. FUSED AND NON-FUSED DISCONNECT SWITCHES SHALL BE PROVIDED AS INDICATED.
- B. INDOOR SWITCHES SHALL BE NEMA 1 AND OUTDOOR SWITCHES SHALL BE NEMA 3R, UNLESS INDICATED OTHERWISE.
13. FUSES:
- A. FUSES PROTECTING CIRCUIT BREAKER PANELS SHALL BE CURRENT LIMITING UL CLASS RK-1 FUSES WITH 200,000 AMPERES RMS 5YM INTERRUPTING CAPACITY. FUSING ELEMENTS SHALL BE SILVER FOR RATINGS ABOVE 60 AMPERES.
- B. ALL OTHER FUSES SHALL BE UL CLASS RK-5, DUAL-ELEMENT WITH A MINIMUM TIME-DELAY OF 10 SECONDS AT 800% RATING. FUSES SHALL HAVE CURRENT-LIMITING SHORT-CIRCUIT LINKS AND 200,000 AMPERES RMS 5YM INTERRUPTING CAPACITY. FUSING ELEMENTS SHALL BE COPPER.
14. LIGHT FIXTURES:
- A. WHERE LIGHT FIXTURES ARE MOUNTED IN A LAY-IN CEILING, PROVIDE A MINIMUM OF 2 SUPPORT WIRES ATTACHED DIRECTLY BETWEEN EACH LIGHT FIXTURE AND THE BUILDING STRUCTURE. SUPPORT WIRES SHALL BE A MINIMUM OF 12 GAUGE GALVANIZED STEEL WIRE, SOFT ANNEALED.
- B. FIXTURES ARE REQUIRED AT ALL LIGHTING OUTLETS SHOWN ON THE DRAWINGS. APPROVED LIGHTING FIXTURE WIRE IS REQUIRED IN ALL FIXTURES AND FIXTURE RACEWAYS. WEATHERPROOF WIRING IS REQUIRED FOR EXTERIOR FIXTURES. ALL PARTS OF FIXTURES AND WIRING SHALL BE IN ACCORDANCE WITH NEC REQUIREMENTS.
- C. ALL FIXTURES SHALL CARRY UL AND ETL LABELS.
15. SLEEVES:
- A. PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK.
- B. INTERIOR PARTITIONS: 16 GAGE GALVANIZED STEEL, PACK BETWEEN CONDUIT AND SLEEVE WITH FIRE SAFING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.
- C. ROOF: PROSET OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WEATHERPROOF SEAL. COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF WARRANTY.
16. GROUNDING:
- A. GROUND ALL ELECTRICAL APPARATUS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE (NEC) 250, AND ANY LOCAL REQUIREMENTS. INSURE CONTINUOUS BOND WHERE FLEXIBLE CONDUIT IS USED. PROVIDE BONDING JUMPER INSIDE ALL FLEXIBLE CONDUIT.
- B. BOND METAL PIPING SYSTEMS IN COMPLIANCE WITH NEC 250.41(A)(4).

ELECTRICAL SYMBOLS LIST

CIRCUITING & NOTES	
+46"	SPECIAL MOUNTING HEIGHT FOR ASSOCIATED DEVICE (CENTERLINE OF DEVICE)
GFI	GROUND FAULT CIRCUIT INTERRUPTER DEVICE
WP	WEATHERPROOF ENCLOSURE ON DEVICE
WR	WEATHERPROOF RESISTANT DEVICE
EM	EMERGENCY BATTERY BACKUP
TR	TAMPER RESISTANT OUTLET
USB	COOPER #TRTTS6-X OR EQUAL DUPLEX RECEPTACLE WITH DUAL USB CHARGING PORTS. PROVIDE 2-1/8" DEEP BACK BOX.
(TIE)	PARTIAL HOMERUN. REFER TO PLANS FOR ADDITIONAL DEVICES CONNECTED TO THIS CIRCUIT.
[X]	ELECTRICAL FLOOR PLAN NOTE WITH DESIGNATION
LP	CONDUIT CONCEALED WHERE POSSIBLE OR AS NOTED, ARROWS INDICATE HOME RUN TO PANEL. CIRCUIT NUMBERS INDICATED
[WIRE]	#12 WIRE IN CONDUIT, UNLESS NOTED OTHERWISE ON DRAWINGS OR SPECIFICATION
[GROUNDING]	GROUNDING CONDUCTOR, #12 WIRE UNLESS NOTED OTHERWISE ON DRAWINGS OR SPECIFICATION
[ROUTED]	CONDUIT ROUTED UNDER FLOOR/GRADE
LIGHTING	
[TWIN HEAD]	EMERGENCY TWIN HEAD LIGHT FIXTURE
[EXIT]	EXIT LIGHT WITH DIRECTIONAL ARROWS INDICATED
[STRIP]	STRIP FIXTURE WITH TYPE DESIGNATION
[RECESSED]	RECESSED OR SURFACE MOUNTED FIXTURE WITH TYPE DESIGNATION
[NIGHT]	NIGHT LIGHT, CONNECT TO UNSWITCHED CIRCUIT
[CEILING]	CEILING OR RECESSED FIXTURE WITH TYPE DESIGNATION
[WALL]	WALL MOUNTED FIXTURE WITH TYPE DESIGNATION
POWER DEVICES	
[DUPLEX]	DUPLEX RECEPTACLE, BOTTOM OF BOX AT 16" AFF, UNLESS NOTED OTHERWISE
[FOURPLEX]	FOURPLEX RECEPTACLE, BOTTOM OF BOX AT 16" AFF, UNLESS NOTED OTHERWISE
[DEVICE]	DEVICE MOUNTED ABOVE COUNTER AND/OR SPLASH GUARD
[HEAVY DUTY]	HEAVY DUTY OUTLET - NEMA CONFIGURATION SIZE PER EQUIPMENT MANUFACTURER'S RECOMMENDATION
[PANEL BOARD]	PANEL BOARD, TOP OF BOX 6'-0" AFF
[JUNCTION BOX]	JUNCTION BOX
[NON-FUSED]	NON-FUSED DISCONNECT SWITCH
[FUSED]	FUSED DISCONNECT SWITCH
[MOTOR]	MOTOR WITH DESIGNATION
[FLOOR BOX]	FLOOR BOX
CONTROLS	
S	SINGLE POLE WALL SWITCH, TOP OF BOX AT 48" AFF
S3	THREE-WAY WALL SWITCH, TOP OF BOX AT 48" AFF
S2P	DIMMER SWITCH, TOP OF BOX AT 48" AFF
S+	MANUAL MOTOR STARTER WITH OVERLOADS
OCCUPANCY SENSORS	
1. DUAL TECHNOLOGY/ULTRASONIC CEILING SENSORS SHALL BE MOUNTED 6' FROM SUPPLY/EXHAUST AIR DIFFUSERS. 2. LOW VOLTAGE CEILING SENSORS SHALL BE PROVIDED WITH 6' SLACK CONDUCTOR COILED AT SENSOR.	
S<	WALL MOUNTED DUAL-TECHNOLOGY OCCUPANCY SENSOR, WATT STOPPER #DSW-301, TOP OF BOX AT 48" AFF
COMMUNICATIONS	
[DATA/TELEPHONE]	DATA/TELEPHONE OUTLET WITH MINIMUM 3/4" CONDUIT STUBBED UP TO ABOVE ACCESSIBLE CEILING, BOTTOM OF BOX AT 16", UNLESS NOTED OTHERWISE. PROVIDE WITH PULL STRING
[TV]	FLAT SCREEN TELEVISION - PROVIDE AND INSTALL ONE (1) HUBBELL #RR1510X RECESSED TAMPER-RESISTANT DUPLEX RECEPTACLE WITH COVERPLATE AND ONE(1) HUBBELL #HBL260 TWO GANG LARGE CAPACITY WALL BOX (UP TO 2" KNOCKOUT) W/ V MUD RING AND COVERPLATE FOR DATA. PROVIDE 2"X WITH PULL STRING TO ABOVE ACCESSIBLE CEILING FOR DATA CABLES. MOUNT BOX AT 7'-6" AFF UNLESS NOTED OTHERWISE (VERIFY)
MISCELLANEOUS	
[COMBINATION]	COMBINATION POWER AND DATA FLOORBOX
[THERMOSTAT]	LINE VOLTAGE THERMOSTAT PROVIDED BY MECHANICAL CONTRACTOR. ELECTRICAL CONTRACTOR TO PROVIDE AND INSTALL WIRING
[TRANSFORMER]	120 - 24 VOLT INDUSTRIAL CONTROL TRANSFORMER 50 VA VA MINIMUM 1V CIRCUIT BREAKER (MANUAL RESET) FOR ALL VAV BOXES AND BYPASS DAMPERS, VERIFY EXACT REQUIREMENTS WITH MECHANICAL UNITS BEING SUPPLIED

ELECTRICAL GENERAL NOTES:

1. COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
2. WHERE CONDUIT IS SHOWN UNDER FLOOR, VERIFY IF FLOOR IS STRUCTURAL SLAB OR SLAB ON GRADE. IF STRUCTURAL SLAB, CORE DRILL PENETRATION AND ROUTE CONDUIT IN SPACE BELOW. IF SLAB ON GRADE, SAW CUT EXISTING FLOOR SLAB AS REQUIRED FOR INSTALLATION OF UNDER FLOOR CONDUIT. NO STRUCTURAL ELEMENTS SHALL BE CORE DRILLED OR SAW CUT. WHEN SAW CUTTING, PATCH FLOOR TO MATCH EXISTING SURFACE AS REQUIRED.
3. IT IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY TO PROPERLY BALANCE ALL BRANCH CIRCUITS BETWEEN THE PHASES OF THE SYSTEM REGARDLESS OF CIRCUITING INDICATED.
4. ALL EXPOSED RACEWAYS SHALL BE IN EMT CONDUIT, MC CABLE IS NOT PERMITTED IN EXPOSED AREAS.
5. ELECTRICAL CONTRACTOR TO COORDINATE MANUFACTURER ELECTRICAL REQUIREMENTS FOR HVAC EQUIPMENT BEING FURNISHED WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN. EQUIPMENT DISCONNECTS TO BE PROVIDED BY ELECTRICAL CONTRACTOR UNLESS NOTED OTHERWISE IN MECHANICAL SCHEDULES.
6. REFER TO ARCHITECTURAL & STRUCTURAL DRAWINGS FOR REQUIREMENTS FOR SUPPORTING TRANSFORMERS, EQUIPMENT, ETC. FROM THE STRUCTURE. PROVIDE ADDITIONAL STEEL AS REQUIRED TO PROPERLY SUPPORT SYSTEMS FROM THE STRUCTURE.
7. ALL MATERIALS EXPOSED WITHIN PLENUMS SHALL BE NONCOMBUSTIBLE OR SHALL HAVE A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE-DEVELOPED INDEX OF NOT MORE THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM E 84.
8. EACH BRANCH CIRCUIT SHALL HAVE A DEDICATED NEUTRAL PER NEC 210.4.
9. ALL BRANCH CIRCUITS SHALL BE SIZED TO ALLOW FOR A MAXIMUM OF 3% VOLTAGE DROP. ALL FEEDERS SHALL BE SIZED TO ALLOW FOR A MAXIMUM OF 2% VOLTAGE DROP. ELECTRICAL CONTRACTOR SHALL VERIFY WIRING INDICATED IS SUFFICIENT AND INCREASE CONDUCTOR SIZE AS REQUIRED BASED OFF ACTUAL INSTALLED LENGTH OF CONDUCTORS.
10. PROVIDE LOW VOLTAGE WIRING BETWEEN ALL 0-10V DIMMING DRIVERS CONTROLLED BY 0-10V DIMMERS PER MANUFACTURER'S INSTRUCTIONS.
11. ALL 120 VOLT 20 AMP RECEPTACLES IN KITCHEN SHALL BE GFCI PROTECTED PER NEC 210.8 (B)(2). (GFCI DEVICE OR GFCI BREAKER AS INDICATED ON PLANS)
12. WHEREVER POSSIBLE, CONDUIT SHALL BE RUN CONCEALED WITHIN WALLS, CEILINGS, SOFFITS, ETC. SURFACE MOUNTED CONDUIT IN FINISHED SPACES MUST BE APPROVED BY THE ENGINEER OR ARCHITECT PRIOR TO INSTALLATION. EXTERIOR CONDUIT SHALL NOT BE RUN EXPOSED IN PUBLICLY VISIBLE AREAS WITHOUT APPROVAL OF THE ARCHITECT OR ENGINEER.

HEALTH CARE FACILITY NOTES:


1. PATIENT AREAS (TREATMENT ROOMS) SHALL COMPLY WITH NEC ARTICLE 517 FOR HEALTH CARE FACILITIES.
2. ALL BRANCH CIRCUITS SUPPLYING PATIENT AREAS SHALL HAVE REDUNDANT GROUNDING PER NEC 517.13(a) & (b). ALL UNDER FLOOR CONDUITS FOR BRANCH CIRCUITS SHALL BE METALLIC.
3. ALL DEVICES IN PATIENT CARE AREAS SHALL BE HOSPITAL GRADE, GROUNDING, THREE WIRE TYPE, RATED FOR 20 AMPS, WITH COVER PLATES. HUBBELL #HBL8300-H, OR EQUAL. VERIFY COLOR WITH ARCHITECT.
4. NEC 2017 - ALL RECEPTACLES INSTALLED IN BUSINESS OFFICES, CORRIDORS, WAITING ROOMS, AND SIMILAR ROOMS ACCESSIBLE TO THE PUBLIC SHALL BE TAMPER RESISTANT PER NEC 406.12(B)
5. REFER TO DENTAL EQUIPMENT SUPPLIER DRAWINGS FOR ADDITIONAL INFORMATION.

9/20/2023



GUY GRONBERG
ARCHITECTS, P.C.

Lee S Summit, MO 64083
119 SE 3rd St.
Phone 816-534-0516
Fax 816-524-2516



BC ENGINEERS
INCORPORATED

5720 Resder Shawnee, KS 66203 (913)662-1772

Abby Jewell DDS
ORTHODONTICS

2070 NW LOWENSTEIN DR, Unit A, LEES SUMMIT, MO 64081


REV#	DATE	DESCRIPTION
1	09/20/23	ADDENDUM #1
Issue Date:		09-07-23
Project #:		23016

BC PROJECT #: 23542 LD/FS
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Design Engineer and is intended for use on the project only. Pursuant to the Architectural Rules, Copyright Protection Act of 1980, all drawings, specifications, plans and designs, including the overall form, arrangement and composition of space and elements appearing herein, constitute the original, copyrighted work of the Design Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.


ELECTRICAL
SPECIFICATIONS, SYMBOL
LEGEND, AND NOTES

E0



**GUY GRONBERG
ARCHITECTS, P.C.**

113 SE 3rd St.
Lee's Summit, MO 64063
Phone: 816.524.0210
Fax: 816.524.2510




**BC ENGINEERS
INCORPORATED**

5720 Reeder Shawnee, KS 66203 (913) 262-1772

**Abby Jewell DDS
ORTHODONTICS**

2070 NW LOWENSTEIN DR. Unit A, LEE'S SUMMIT, MO 64081




ELECTRICAL LIGHTING PLAN

SCALE: 1/4" = 1'-0"

LIGHTING PLAN NOTES:

- 1 JUNCTION BOX WITH DISCONNECTING MEANS PER NEC FOR CONNECTION TO BUILDING MOUNTED SIGNAGE. VERIFY EXACT LOCATION AND CONNECT TO SIGN PER MANUFACTURER'S INSTRUCTIONS. ROUTE CIRCUIT THRU TIMECLOCK, SEE DETAIL, THIS SHEET.
- 2 OWNER FURNISHED SIGN MOUNTED ON BACK WALL. PROVIDE J-BOX WITH WHIP FOR CONNECTION. VERIFY EXACT ROUGH-IN LOCATION WITH OWNER. SIGN TO BE CONTROLLED BY PROGRAMMABLE TIME SWITCH AS SCHEDULED.



LIGHTING CONTROL DETAIL

SCALE: NONE

BC PROJECT #: 23542 LD/FS
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Engineer and is intended for use on the project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, plans and designs, including the overall form, arrangement and composition of space and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.

REV#	DATE	DESCRIPTION
1	09/20/23	APPENDIX #1
2	09/27/23	APPENDIX #2

Issue Date: 09-07-23
Project #: 23016


LIGHTING PLAN

E1



GUY GRONBERG
ARCHITECTS, P.C.

113 SE Summit, MO 64069
Phone 816.524.0210
Fax 816.524.0210




BC ENGINEERS
INCORPORATED

5720 Reeder Shawnee, KS 66203 (913)262-1772

Abby Jewell DDS
ORTHODONTICS

2070 NW LOWENSTEIN DR. Unit A, LEES SUMMIT, MO 64081



ELECTRICAL POWER PLAN
NORTH
SCALE: 1/4" = 1'-0"

POWER PLAN NOTES:

- 1 ALGER (CEILING) - PROVIDE WHIP ABOVE CEILING FOR LIGHT FIXTURE. VERIFY LOCATION AND CONNECT PER MANUFACTURER'S SPECIFICATIONS. ADD ALTERNATE: ALGER LIGHTS TO BE PROVIDED AND INSTALLED BY CONTRACTOR.
- 2 CHAIR DUPLEX RECEPTACLE; FLUSH FLOOR DUPLEX CONVENIENCE OUTLET AT LOCATION SHOWN. VERIFY LOCATION WITH DENTAL EQUIPMENT SUPPLIER.
- 3 PROVIDE (1) 1" CONDUIT FOR POWER.
- 4 PROVIDE (1) 1" CONDUIT WITH FULLSTRING FOR DATA.
- 5 POWER TO PANO X-RAY. COORDINATE ALL REQUIREMENTS WITH EQUIPMENT SUPPLIER.
- 6 X-RAY REMOTE EXPOSURE BUTTON: ROUTE 1" CONDUIT FROM BOX AT X-RAY TO A JUNCTION BOX AT X-RAY REMOTE. MOMENTARY CONTACT BUTTON AND CONDUCTORS BY OTHERS.
- 7 VERIFY LOCATION OF 2X4X3/4" FIRE RETARDANT PLYWOOD TELEPHONE BACKBOARD WITH GROUND BAR AND #6 CU BOND TO BUILDING ELECTRODE SYSTEM PROVIDE 2" C TO PROPERTY LINE FOR BUILDING TELEPHONE AND INTERNET SERVICE. TERMINATE AS DIRECTED BY SERVICE PROVIDER. VERIFY ROUTING AND DISTANCE.
- 8 DISCONNECT SWITCH FOR POWER TO VACUUM AND AIR COMPRESSOR. PROVIDE BOOST TRANSFORMER PER EQUIPMENT SUPPLIER'S INSTRUCTIONS.
- 9 MASTER CONTROL PANEL: PROVIDED BY DENTAL EQUIP SUPPLIER. RUN (10) #18 WIRES FROM PANEL TO COMPRESSOR, VACUUM PUMP AND WATER SOLENOID. CONNECT CONTACTORS ON FINISH AND TIE INTO SYSTEM.
- 10 CIRCULATING PUMP: FIELD VERIFY REQUIREMENTS FOR CIRCULATING PUMP. FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR BRANCH CIRCUIT CONDUCTORS, CONNECTION, AND OVERCURRENT PROTECTION. PROVIDE RELAY TO SHUT-OFF WITH WATER SOLENOID.
- 11 DUPLEX RECEPTACLE MOUNTED UNDER SINK IN CASEWORK FOR POWER TO GARBAGE DISPOSAL. DEVICE TO BE GFCI PROTECTED BY GFCI BREAKER IN PANEL.
- 12 VERIFY EXACT LOCATION OF MICROWAVE.
- 13 DEVICES MOUNTED IN CASEWORK. ROUTE ALL WIRES/CONDUIT CONCEALED TO NEAREST FULL HEIGHT WALL. VERIFY EXACT LOCATION.
- 14 ROOF TOP UNITS ARE EXISTING TO REMAIN. INTERCEPT AND EXTEND FEEDER TO RELOCATED PANEL AS REQUIRED.
- 15 VERIFY EXACT LOCATIONS AND MOUNTING HEIGHTS OF ELECTRICAL DEVICES WITH ARCHITECT AND DENTAL EQUIPMENT PLANS IN THIS ROOM.
- 16 PROVIDE 120 VOLT POWER TO VAV. SD AND LINEAR SLOT POWER SUPPLY LOCATED ABOVE THE CEILING. COORDINATE LOCATION WITH HVAC CONTRACTOR.

BC PROJECT #: 23542 LD/FS
MISSOURI PE COA #2009003629

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Design Engineer and is intended for use on the project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, plans and designs, including the overall form, arrangement and composition of space and elements appearing herein, constitute the original, copyrighted work of the Design Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.

REV#	DATE	DESCRIPTION
1	09/20/23	APPENDIX #1
2	09/27/23	APPENDIX #2

Issue Date: 09-07-23
Project #: 23016

POWER PLAN

E2


REV#	DATE	DESCRIPTION
1	09/20/23	ADDENDUM #1




Issue Date: 09-07-23

Project #: 23016

EXIST. PANEL: P1		VOLTS: 120/208V		PH: 3Ø		WIRE: 4/0		LOCATION: HALL 109		MOUNTING: FLUSH						
BUS: 225A		MAIN: 200A MCB								FEEDER: SEE RISER DIAGRAM						
CKT	DESCRIPTION	AMPS	POLE	WIRE	ØA	ØB	ØC	ØA	ØB	ØC	WIRE	POLE	AMPS	DESCRIPTION	CKT NO	
1	STERILE COUNTER RCPT [EX]	20	1	12	900			3,360							2	
3	STERILE DROP IN EQUIP [GF]	20	1	12		600			3,360		Ø	Ø	ØØ	EX RTU-1 [EX]	4	
5	STERILIZER [GF]	20	1	12			1,200			3,360					6	
7	STERILIZER [GF]	20	1	12	1,200			3,360							8	
9	STERILE/Private RCPT [EX]	20	1	12		1,200			3,360		Ø	Ø	ØØ	EX RTU-2 [EX]	10	
11	LAB EQUIPMENT [GF]	20	1	12			1,000			3,360					12	
13	LAB COUNTER RCPT [EX]	20	1	12	1,080			360			12	1	20	ROOF RCPT [EX]	14	
15	LAB EQUIPMENT [EX]	20	1	12		600			360		12	1	20	PHONEBOARD RCPT [EX]	16	
17	GALLEY FRIDGE [GF]	20	1	12			1,000			3,360	12	1	20	IT RCPT [EX]	18	
19	GALLEY MICROWAVE [GF]	20	1	12	1,000							1	20	SPARE [EX]	20	
21	GALLEY COUNTER RCPT [EX]	20	1	12		360						1	20	SPARE [EX]	22	
23	GALLEY DISPOSAL [EX]	20	1	12			200					1	20	SPARE [EX]	24	
25	SPARE [EX]	20	1									1	20	SPARE [EX]	26	
27	SPARE [EX]	20	1					900			12	1	20	PANO COMPUTER RCPT [EX]	28	
29	SPARE [EX]	20	1									1	20	SPARE [EX]	30	
31	WATER HEATER	30	2	10	2,250			180			12	1	20	RECIRC PUMP [EX]	32	
33						2,250			1,664		12	2	20	PANO XRAY	34	
35	AIR COMPRESSOR	20	2	12			1,664			1,664					36	
37					1,664			4,825							38	
39	VAC PUMP	20	2	12		1,664			5,542		Ø	Ø	100	PANEL P1A	40	
41							1,664			4,158					42	
NOTES:					Ø,094	6,734	6,728	12,005	15,186	12,902						
[EX]-EXISTING BRKR, [GF]-GFCI BRKR 5ma					20,179		21,120		19,630		TOTAL CONNECTED LOAD:				61,129 VA	
											NEG DEMAND LOAD:				57,716 VA	
											DEMAND AMPS @ 2ØØ VOLT / 3Ø:				160.37	

PANEL: F1A				VOLTS: 120/208V				FH: 3Ø		WIRE: 4W		LOCATION: HALL 104				MOUNTING: FLUSH			
BUS: 125A				MAIN: 100A MLO				IG: 22,000		RMS 5YM AMP'S				FEEDER: SEE RISER DIAGRAM					
CKT	DESCRIPTION			AMPS	POLE	WIRE	GA	GB	GC	GA	GB	GC	WIRE	POLE	AMPS	DESCRIPTION			CKT NO.
1	TREATMENT/OFFICE LTG			20	1	12	1,268			540			12	1	20	TREATMENT BAY TV'S			2
3	WAITING/HALL LTG			20	1	12		1,402			540		12	1	20	TREATMENT BAY CHAIRS			4
5	SIGNAGE			20	1	12			1,200			360	12	1	20	TREATMENT BAY CHAIRS			6
7	LOBBY RCPT			20	1	12	120			500			12	1	20	TREATMENT BAY LTG			8
9	SFARE			20	1						1,260		12	1	20	GALLEY/HALL RCPT			10
11	SFARE			20	1							120	12	1	20	PRIVATE 101 CHAIR			12
13	SFARE			20	1					1,000			12	1	20	CONSULT 102 RCPT/CHAIR			14
15	SFARE			20	1						900		12	1	20	WAITING 101 RCPT			16
17	SFARE			20	1							180	12	1	20	WAITING 101 BEV STATION (SIF)			18
19	SFARE			20	1				120				12	1	20	LOBBY DESK RCPT			20
21	DOCTOR 114 RCPT			20	1	12		1,440						1	20	SFARE			22
23	TREATMENT BAY RCPT			20	1	12			900			195	12	1	20	TP-7/TP-8			24
NOTES:							1,935	2,842	2,100	2,840	2,700	2,050							
[SIF]-GFCI BRKR 50mA							4,825		5,542		4,150		TOTAL CONNECTED LOAD:				14,525 VA		
												NEG DEMAND LOAD:				15,611 VA			
												DEMAND AMP'S @ 208 VOLT / 3Ø:				43.35			



LIGHT FIXTURE SCHEDULE					
MARK NO.	MANUFACTURER & CATALOG NUMBER	VOLTS MATTS	LIGHT SOURCE	DESCRIPTION	EQUIVALENT MANUFACTURERS
A	LITHONIA LS1X 4FT 80CRI 40K BFR SWL MINIO EZT MYOLT MM	120 33.3	LED 4000 LUM 4000 K	LED 4" RECESSED LINEAR LAY-IN, 4000 LUMEN, 4000 KELVIN, BEZEL FRAME, MATTE WHITE	COLUMBIA WILLIAMS OR EQUAL
A1	LITHONIA LS1X 4FT 80CRI 40K BFR SWL MINIO EZT MYOLT MM	120 17	LED 2000 LUM 4000 K	LED 2" RECESSED LINEAR LAY-IN, 2000 LUMEN, 4000 KELVIN, BEZEL FRAME, MATTE WHITE	COLUMBIA WILLIAMS OR EQUAL
B	LITHONIA CSS L48 AL03 MYOLT SWWS 80CRI	120 27/36/43	LED SWITCHABLE	LED 4" SURFACE MOUNT STRIP, SWITCHABLE, ROUND LENS, MOUNT FIXTURE TO PROVIDE INDIRECT LIGHTING TO CEILING. REFER TO ARCHITECTURAL DETAILS FOR LOCATION	COLUMBIA WILLIAMS OR EQUAL
B1	LITHONIA CSS L24 AL015 MYOLT SWWS 80CRI	120 13/16/19	LED SWITCHABLE	LED 2" SURFACE MOUNT STRIP, SWITCHABLE, ROUND LENS, MOUNT FIXTURE TO PROVIDE INDIRECT LIGHTING TO CEILING. REFER TO ARCHITECTURAL DETAILS FOR LOCATION	COLUMBIA WILLIAMS OR EQUAL
B2	LITHONIA CSS L48 4000LM MYOLT 40K 80CRI	120 35.3	LED 4000 LUM 4000 K	LED 4" SURFACE MOUNT STRIP, 4000 LUMEN, 4000 KELVIN, ROUND LENS	COLUMBIA WILLIAMS OR EQUAL
B3	LITHONIA CSS L24 2000LM MYOLT 40K 80CRI	120 15.3	LED 2000 LUM 4000 K	LED 2" SURFACE MOUNT STRIP, 2000 LUMEN, 4000 KELVIN, ROUND LENS	COLUMBIA WILLIAMS OR EQUAL
C	36 LIGHTING 36-1RLI D750 S80 40K UNV DIM FX FL S 4"	120 20.0	LED 3000 LUM 4000 K	LED 4" RECESSED STRIP, 3000 LUMEN, 4000 KELVIN, FLANGELESS, FLUSH LENS, DIMMING DRIVER	
C1	36 LIGHTING 36-1RLI D750 S80 40K UNV DIM XTR DASY S 4"	120 20.0	LED 3000 LUM 4000 K	LED 4" SURFACE MOUNT STRIP, 3000 LUMEN, 4000 KELVIN, TRIMLESS, ASYMMETRIC LENS, DIMMING DRIVER	
D	JUNO TC20LED 64 20LM 40K MVOLT ZT1 204 CWH	120 25.1	LED 2000 LUM 4000 K	5" RECESSED CAN LED DOWNLIGHT, 2,000 LUMEN, 4000 KELVIN, DIMMING DRIVER	COLUMBIA WILLIAMS OR EQUAL
DE	JUNO TC20LED 64 20LM 40K MVOLT ZT1 BR 204 CWH	120 25.1	LED 2000 LUM 4000 K	5" RECESSED CAN LED DOWNLIGHT, 2,000 LUMEN, 4000 KELVIN, DIMMING DRIVER WITH EMERGENCY BATTERY BACKUP	COLUMBIA WILLIAMS OR EQUAL
F	LITHONIA RLNK L48 120 35K 80CRI M4	120 19.7	LED 1950 LUM 3500 K	LED 4" SURFACE MOUNT LINKABLE STRIP UNDERCABINET, 1950 LUMEN, 3500 KELVIN	COLUMBIA WILLIAMS OR EQUAL
F1	LITHONIA RLNK L24 120 35K 80CRI M4	120 9.9	LED 940 LUM 3500 K	LED 2" SURFACE MOUNT LINKABLE STRIP UNDERCABINET, 940 LUMEN, 3500 KELVIN	COLUMBIA WILLIAMS OR EQUAL
G	ITC LIGHTED MIRROR 69455-2448.30K.LR. RMT	120 14	LED 1500 LUM 3000 K	LOOK INER ITCHED TWO BAR INTEGRATED LED BACKLIT MIRROR, 24"x36"	
H	DAINOLITE PIC222-24LED-SC	120 30	LED	LED SATIN CHROME WITH FROSTED GLASS DIFFUSER PICTURE LIGHT	
P	PENDANT BY OWNER INSTALLED BY CONTRACTOR	120	LED INCL	DECORATIVE PENDANT TO BE SELECTED BY OWNER. \$250 ALLOWANCE PER EACH FIXTURE	COLUMBIA WILLIAMS OR EQUAL
P1	PENDANT BY OWNER INSTALLED BY CONTRACTOR	120	LED INCL	DECORATIVE PENDANT TO BE SELECTED BY OWNER. \$500 ALLOWANCE PER EACH FIXTURE	COLUMBIA WILLIAMS OR EQUAL
	DUAL-LITE EV4D-02L	120 2	INCL	EMERGENCY LIGHT WITH TWIN ADJUSTABLE 2" MATT LED HEADS AND BATTERY, MOUNT AT 7'-6" TO CLEAR OBSTACLES. (PROVIDES 1 FC AVG. ON 3' CENTER FIXTURE SPACING) DAMP LOCATION RATED.	SURE-LITES LITHONIA OR EQUAL
	LITHONIA ED6 SERIES	120 1	INCL	EDGE LIT EXIT LED LIGHT, RED LETTERS ON WHITE BACKGROUND, SURFACE MOUNT, BATTERY BACKUP	SURE-LITES LITHONIA OR EQUAL
	LITHONIA EC6R SERIES	120 1	INCL	EXIT LIGHT WITH LED LIGHTBAR, RED LETTERS ON WHITE BACKGROUND, SURFACE MOUNT, BATTERY BACKUP	SURE-LITES LITHONIA OR EQUAL

NOTES:
1. MEDICAL - ALL LAMPS SHALL BE 4000° KELVIN AND A MINIMUM CRI OF .82 UNLESS SPECIFIED OTHERWISE

BC PROJECT #:	23542 LD/FS
MISSOURI	BE COA #2000003630

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2023 BC Engineers, Inc.