


STRUCTURAL NOTES:

1. ALL CONSTRUCTGION SHALL CONFORM TO 2018 INTERNATION RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.

ELEVATIONS:


- GARAGE DOORS SHALL MEET DASMA OR ULTIMATE DESIGN WIND SPEED OF 115 1.
- MPH REQUIREMENTS.
- WALL FRAMING SHALL BE DOUGLAS FIR LARCH #2 UNLESS OTHERWISE NOTED.
 IN BEARING WALLS, STUDS WHICH ARE NOT MORE THAN TEN FEET IN LENGTH SHALL BE SAPCED NOT MORE THAN IS SPECIFIED BY IRC TABLE R602.3(5) FOR CORRESPONDING STUD SIZE.
- WATER-RESISTIVE EXTERIOR WALL BARRIER IN WALL SECTION SHALL COMPLY 4. WITH IRC R703.2.
- WHEN APPLICABLE, CONTINUOUS STUDS BETWEEN FLOOR AND ROOF/CEILING 5.
- DIAPHRAGM SHALL COMPLY WITH IRC R602.3. ALL UNMARKED HEADERS SHALL BE A MINIMUM #2 DOUGLAS FIR LARCH (2) 2 X 6.
- 10 ON LOAD BEARING WALLS. SHIPLAP SIDING MUST BE FASTENED AT BOTH UNDERLAP AND OVERLAP. 7.



FRON



 1.41 6X6 CEDAR POST 1.71 CONCRETE WINDOW WELL FOR PROVED SLEEVE THROUGH WA DRAIN. TOP OF WINDOW WELL OF FOUNDATION. 2.62 DOUBLED 1X8" LP SMART TRIN 3.11 LP SMART LAP SIDING WITH 5 AROUND DOORS, WINDOWS, AN NOTED OTHERWISE. 3.13 LP SMART PANEL SIDING WITH TRIM AROUND DOORS, WINDOW UNLESS NOTED OTHERWISE. BI SHALL BE A MINIMUM OF 6". 3.14 CEDAR SHAKE SHINGLE SIDING 3.17 MANUFACTURED STONE VENEE 3.18 CAST STONE CAP 3.45 BOX BASE WITH STONE VENEE 3.55 6"X8"X11" CEDAR CORBEL WIT 3.62 CEDAR SHUTTERS. ALL SHUTT USING (3) 2X6 BOARDS. LP S INSTALLED AROUND WINDOW F INSTALLATION. 	EGRESS WITH LADDER. ALL FOR FOUNDATION TO BE 3" BELOW TOP M. 6/4X6 LP SMART TRIM ND CORNERS UNLESS A 3/4X4 LP SMART VS, AND CORNERS OTTOM OF SIDING ABOVE GRADE. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5	<section-header><section-header><section-header><text><text><text></text></text></text></section-header></section-header></section-header>
VENTS 4.11 MINIMUM ROOFING COMPOSITIO SHINGLES ON 15# FELT ON 1/ AS REQUIRED BY CODE. 4.31 BUILD CRICKET VALLEY AWAY FOR POSITIVE DRAINAGE.	ER INDUSTRY STANDARD ING IS EXPECTED TO VARY	ADDRESS: 3204 SW ARBOR SOUND DR LEE'S SUMMIT, MO CRAFTSMAN 4 BEDS, 3 BATHS 4 BEDS, 3 BATHS
		PROFESSIONAL SEAL:
FINISHED MAIN FLOOR LOWER LEVEL TOTAL	1787 1140 2927	EVERSTEAD IS RESPONSIBLE FOR STRUCTURAL SPECIFICATIONS ONLY. ARCHITECTURAL PLANS WERE PROVIDED BY OTHERS. EVERSTEAD 3741 NE TROON DR. LEES SUMMIT, MO 64064 816-399-4901
UNFINISHED LOWER LEVEL - UNFINISHED COVERED PATIO GARAGE	434 148 650	VERSION: 1.2
ENGINEER TRUSS EVERSTEAD PREMIER	I-JOIST 	ISSUE DATE: 11.20.23
REVISIONS NO. DATE DESCRI 1 1 2 1 3 1	IPTION	SHEET NUMBER:
	1.12 TOP OF FOOTING DEPTH DETE 1.41 6X6 CEDAR POST 1.71 CONCRETE WINDOW WELL FOR PROVED SUEEVE THROUGH WA DRAIN. TOP OF WINDOW WELL OF FOUNDATION. 2.62 DOUBLED 1X8" LP SMART TRIM AROUND DOORS, WINDOWS, AN NOTED OTHERWISE. 3.11 LP SMART LAP SIDING WITH 5 AROUND DOORS, WINDOW UNLESS NOTED OTHERWISE. 3.13 LP SMART PANEL SIDING WITH TRIM AROUND DOTRS, WINDOW UNLESS NOTED OTHERWISE. 3.14 CEDAR SHAKE SHINGLE SIDING 3.17 3.14 CEDAR SHAKE SHINGLE SIDING 3.17 3.14 CEDAR SHATTERS ALL SHOT USING (3) 2X6 BOARDS. LP 3 INSTALLED AROUND WINDOW FING 3.45 3.45 BOX BASE WITH STONE VENEE SINSTALLED AROUND WINDOW FING 3.18 4.00 COVERING WILL HAVE 1 ROOF VENTS 4.11 MINIMUM ROOFING COMPOSITIC SHINGLES ON 15# FELT ON 1, AS REQUIRED BY CODE. 4.31 BUILD CRICKET VALLEY AWAY FOR POSITIVE DRAINAGE. 5HEET INDEX A1. FRONT AND REAR ELEVATI A2. LEFT AND RIGHT ELEVATIC A3. FOUNDATION LEVEL PLAN A4. MAIN LEVEL PLAN A5. ROOF PLAN A4. MAIN FLOOR LOWER LEVEL TOTAL TOTAL TOTAL IOWER LEVEL TOTAL IOWER LEVEL TOTAL IOWER LEVEL PREMIER IOWER LEVEL <t< th=""><th>112 TOP OF FOOTING DEPTH DETERMINED PER SITE. 141 EXAC CEDAR POST 171 CONCRETE WINDOW WELL FOR ECRESS WTH LADDER. 171 CONCRETE WINDOW WELL FOR ECRESS WTH LADDER. 171 DESMART LAP SIDING WITH 5/4X6 LP SWART TRIM. 171 LP SWART LAP SIDING WITH 3/4X6 LP SWART TRIM. 171 LP SWART LAP SIDING WITH 3/4X6 LP SWART TRIM. 171 LP SWART LAP SIDING WITH 3/4X6 LP SWART TRIM. 171 LP SWART LAP SIDING WITH 3/4X6 LP SWART TRIM. 171 LOTORES, WINDOWS, AND CORNERS UNLESS. 172 MANUFACTURED STORE VENEER. 174 CORD ROOTS, WINDOWS, AND CORNERS UNLESS. 175 MANUFACTURED STORE VENEER. 176 MANUFACTURED STORE VENEER. 177 CONCENS WITH STORE VENEER. 178 CAST STORE CAP 179 WANUFACTURED STORE VENEER. 170 COVERING WILL HAVE 1 RODE VENT AND 4 SOFTT 171 MINIUM ROOFING COMPOSITION - 30 YR COMPOSITE 171 MI</th></t<>	112 TOP OF FOOTING DEPTH DETERMINED PER SITE. 141 EXAC CEDAR POST 171 CONCRETE WINDOW WELL FOR ECRESS WTH LADDER. 171 CONCRETE WINDOW WELL FOR ECRESS WTH LADDER. 171 DESMART LAP SIDING WITH 5/4X6 LP SWART TRIM. 171 LP SWART LAP SIDING WITH 3/4X6 LP SWART TRIM. 171 LP SWART LAP SIDING WITH 3/4X6 LP SWART TRIM. 171 LP SWART LAP SIDING WITH 3/4X6 LP SWART TRIM. 171 LP SWART LAP SIDING WITH 3/4X6 LP SWART TRIM. 171 LOTORES, WINDOWS, AND CORNERS UNLESS. 172 MANUFACTURED STORE VENEER. 174 CORD ROOTS, WINDOWS, AND CORNERS UNLESS. 175 MANUFACTURED STORE VENEER. 176 MANUFACTURED STORE VENEER. 177 CONCENS WITH STORE VENEER. 178 CAST STORE CAP 179 WANUFACTURED STORE VENEER. 170 COVERING WILL HAVE 1 RODE VENT AND 4 SOFTT 171 MINIUM ROOFING COMPOSITION - 30 YR COMPOSITE 171 MI




STRUCTURAL NOTES:


ALL CONSTRUCTGION SHALL CONFORM TO 2018 INTERNATION RESIDENTIAL 1. CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.


ELEVATIONS:

- GARAGE DOORS SHALL MEET DASMA OR ULTIMATE DESIGN WIND SPEED OF 115
- MPH REQUIREMENTS. WALL FRAMING SHALL BE DOUGLAS FIR LARCH #2 UNLESS OTHERWISE NOTED. IN BEARING WALLS, STUDS WHICH ARE NOT MORE THAN TEN FEET IN LENGTH SHALL BE SAPCED NOT MORE THAN IS SPECIFIED BY IRC TABLE R602.3(5) FOR
- CORRESPONDING STUD SIZE. WATER-RESISTIVE EXTERIOR WALL BARRIER IN WALL SECTION SHALL COMPLY
- WITH IRC R703.2. WHEN APPLICABLE, CONTINUOUS STUDS BETWEEN FLOOR AND ROOF/CEILING
- DIAPHRAGM SHALL COMPLY WITH IRC R602.3. ALL UNMARKED HEADERS SHALL BE A MINIMUM #2 DOUGLAS FIR LARCH (2) 2 X
- 10 ON LOAD BEARING WALLS.
- SHIPLAP SIDING MUST BE FASTENED AT BOTH UNDERLAP AND OVERLAP.




	IS	OLATEI	D FOOTINGS AND	D COLUMN PA	DS		ISOI		DTINGS AND		PADS					
SYM	PIER		MINIM REINFORCEM 40 KSI S	1UM ENT GRADE	SCHEDULE 40		DIED	DEDTU		REINFORC 40 KSI ST	EMENT GI	RADE				
Â	30"x30"	1'-0"	(5) #4 BA	R E.W.	3" DIAMETER	G	12"	3'-0"		(4) VERTIC	AL #4					
B	36"x36"	1'-0"	(6) #4 BA	R E.W.	3" DIAMETER	H	16"	3'-0"		(4) VERTIC	AL #4					
Ċ	42"x42"	1'-2"	(7) #4 BA	R E.W.	3" DIAMETER		18"	3'-0"		(4) VERTIC	AL #4					
	48"x48"	1'-4"	(8) #4 BA	R E.W.	3" DIAMETER	K	24"	3'-0"		(4) VERTIC	AL #4		/			
E	54"x54"	1'-4"	(9) #4 BA	R E.W.	3.5" DIAMETER		28"	3'-0"		(4) VERTIC	AL #4		-	8'-0"	/	
F	60"x60"	1'-6"	(10) #4 BA	AR E.W.	3.5" DIAMETER				NOT REQUIR			GHT		¥ 4'-4	<u>'</u>	
						DESIG	MNS GREAT		10' REQUIRE . ACING OF 6"							9' (28"X10"
						COVE	R.			1						
STR	UCTURAL	NOTES):								3-8"					
<u>•</u>	1.	ALL C	 ONSTRUCTION S NATION RESIDEI								×					
FOU	INDATION I	ENGIN	IEER SPECIFICA													FLUSH
	1.	DEPT	OOTINGS MEET (H OF 36".								6'-4"				4040 SLIDER EGRESS @ 8' h	2X10
	2. 3.	COMP COMP	BEARING CAPACI RESSSIVE STRE RESSIVE STREN	NGTH OF CO	NCRETE FC					2"	×			╷╵┠╧╧╴	++ - 	
		THE F METH	PROOFING SHAL OOTING TO THE OD OF DAMPPRO BE A MINIMUM (FINISHED GR	ADE (R-406.1). /ATERPROOFING	ì				21'-11 1/2"						1 24
		OVER	POROUS GRAVE R SLAB PER R40	EL BASE UNDI	ER BASEMENT									(1.11		
	4. 5.	SECTI FOUN	DATION WALLS S ON R406. DATION DRAINAG	GE WILL BVE							11'-11 3/4"			-7 1/2"	i	
	6.	BASE ACCO	IRC SECTION R4 MENT EGRESS O RDANCE WITH IF	PENINGS SHA	R310.1.						11-1			11-7		
	7. 8.	AND C BASE	ITERIOR FOOTIN COLUMNS SHALL MENT FLOOR SL/ NCHOR BOLTS S	BE ISOLATED AB.	FROM THE	S										N/ TILE AB
	o. 9.	THAN MINIM	3' O.C. AND BE E UM OF 7". SEMENT SLAB EL	MBEDDED IN	TO THE CONCRE	TE A							_ <u>+</u>			ABOVE
DEA	.D MAN SP	CONS	ULT ENGINEER.								-			↓↓	EGRES <u>SI</u> 	
	1.	ALL DI FROM	EAD MAN SHALL EGRESS WELL,	REAR GARAG	GE WALL, 24" RET						4'-8"			(1.71)	3050 EGR	10 FLUSH
	2.	DEAD WALL	OUNDATION WAL MEN ARE NOT R S OR FOUNDATIO	REQUIRED ON	EXTERIOR GARA						x		╵ <u>┤</u> ╎╎┍╸		<u> </u>	(2) 2X101
	3.	MORE REQU	TRANSITIONING THAN 5' TALL W IRED WITHIN 8' C	ITH STEP DOV OF STEP DOW	WNS: A DEAD MA N (tRANSITIONIN	G			58'-0"	13'-11"					Ĺ	j~ e
			LESS THAN 5' TA TION) ON WALL 5			ALL					9'-3"			° ₽ ₽ ₽ CLOSE	`~ т	2X10 FJ
											0,				<u> </u>	
								9' CONC	FND WALL				¦ [[
															15' - 0"	
														10' - 0"		
															Г	
											5 .					X
										22'-1 1/2"	20'-1 1/2"				L	
										NC FND WA				** R	EFER TO	PLOT P
										" W/ (2) #4 (10' - 4 3/4"
																10
														(1.21)		
											_			⊥ €		
	FOUNDA	ATION V		FROM INSIDE	E TENSION FACE)					2'-0"					
			NOMINAL WALL THICKNESS	AND SI	(2) #4	AND SIZE	P &	U.N.O. ON	CIFICATION PLANS							
	RENCH FOO		16"	#4 BARS @1	B	DT. CONT.							1'-4"	8'-4"		#
	8'-0" WALL			#4 BARS @1				' x 8" CON(2) #4 BARS	C. FTG. W/					10'-0"		
	9'-0" WALL		8"	#4 BARS @1		RS @ 24"		∠ <i>) #</i> 4 dakt								
1	0'-0" WALL			#4 BARS @	8" O.C.											
1	1'-0" WALL		10"	#4 BARS @	9" O.C.			4" x 12" CO								
1	2'-0" WALL		10"	#4 BARS @	6" O.C.		W/	/ (3) #4 BAF	ςο CONΓ.							





DEADMAN, SEE NOTES




	MAIN FLOOR PLAN NOTES	
	 1.22 EXPOSED TOP OF FOUNDATION WALL. 2.11 DOUBLE 2X4 STUD WALL 2.12 2X6 STUD WALL 2.31 SIX SIDED TUB ASSEMBLY INCLUDING THERMOPLY ON EXTERIOR WALL TO 2" ABOVE TOP OF TUB DECK OR TUB/SHOWER UNIT 2.41 CURB STAIR SYSTEM WITH OPEN HANDRAILS 2.51 3 STUDS BETWEEN WINDOW UNITS 3.45 BOX BASE WITH STONE VENEER TO 4'-6" AND 6X6 CEDAR POST. SEE PLAN FOR FINISHED SIZE. 4.51 SINGLE BOX VAULT 5.05 HOSE BIBB 5.22 TILE BASE WITH TILE WALLS. SEE DETAIL. 6.42 HVAC FLOOR OPENING. HEADER OFF FLOOR JOISTS AS REQUIRED. BUMP TRUSSES AS NECESSARY FOR HVAC ACCESS. 6.51 1'-10"X3'-0" MINIMUM ATTIC ACCESS WITH 3/4" BACKER BOARD AND 2 LATCHES. BUMP TRUSSES FOR ATTIC ACCESS. 7.21 DIRECT VENT FIREPLACE. INSTALL PER MANUFACTURER'S RECOMMENDATIONS. FIREPLACE PLATFORM DIMENSIONS 7 ³/₄" TALL, 37" WIDE, 16" DEEP. INSTALL INSULATION AND AIR BARRIER BEHIND PLATFORM. 7.41 OPEN HANDRAILS 7.42 PROVIDE ADDITIONAL BLOCKING UNDER SUBFLOOR @ 6'-0" O.C. FOR OPEN HANDRAIL. 7.71 20 MINUTE FIRE RATED SOLID CORE WITH SELF-CLOSING HINGES 7.72 FLAT ASTRAGAL LOCK- +1" ON ROUGH OPENING FOR UPPER DOOR LOCK 7.88 CHANGE IN FLOORING MATERIAL 8.14 24" CABINET + 24" OVERHANG WITH LEGS. VERIFY LOCATION WITH PERSONAL BUILDER. 	<section-header><section-header><section-header><section-header><text><text><text></text></text></text></section-header></section-header></section-header></section-header>
36 114"	8.22 CONTINUOUS FLAT VANITY 8.44 BENCH WITH COAT HOOKS 8.52 FOLDING TABLE	SOMERVIEW CRAFTSMAN CRAFTSMAN HAWTHORN RIDGE #169 4 BEDS, 3 BATHS
NL 2		PROFESSIONAL SEAL:
20' - 8 7/8"	GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED,	EVERSTEAD IS RESPONSIBLE FOR STRUCTURAL SPECIFICATIONS ONLY. ARCHITECTURAL PLANS WERE PROVIDED BY OTHERS. EVERSTEAD 3741 NE TROON DR. LEES SUMMIT, MO 64064 816-399-4901
BWL 3	 NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR. PROVIDE BLOCKING AT ALL CEILING JUMPS FOR INSULATION. 2X6 EXTERIOR WALL OVER 12' SHALL BE DOUGLAS FIR #2. SMOKE AND CARBON MONOXIDE DETECTORS SHOW ON PLANS ARE TO BE CONSIDERED RECOMMENDATIONS ONLY. FINAL PLACEMENT IS TO BE DETERMINED BY MUNICIPAL 	VERSION: 1.2 ISSUE DATE: 11.20.23 SHEET NUMBER:
$\frac{\text{FLOOR PLAN}}{\text{SCALE: } 1/4' = 1'-0'} (1)$	REQUIREMENTS. WINDOW SIZES ARE WRITTEN IN FEET AND INCHES PER INDUSTRY STANDARDS. EX: 3050 SH = 3'-0" X 5'-0" SINGLE HUNG, 3066 FIX = 3'-0" X 6'-6" FIXED.	A4.0

- **TRUSS FRAMED ROOF NOTES**1.ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATIONAL RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.
- DESIGNED FOR LIGHT ROOF COVERING, UNO. SEE G000 FOR MINIMUM LOADING. ALL EXTERIOR AND/OR LOAD BEARING WALL HEADERS SHALL BE MIN. (2) #2 2X10 UNO.
- CONSULT ENGINEER IF TRUSSES BEAR ON INTERIOR WALLS SHOWN AS NON-LOAD BEARING ON APPROVED POINTS.
- PROVIDE 2X SOLID BLOCKING SUPPORT BELOW ALL POINT LOADS CONTINUOUS TO
- BEARING STRUCTURE AND/OR FOUNDATION BELOW. WOOD TRUSSES SHALL BE IN ACCORDANCE WITH IRC 802.10.
- CONSULT ENGINEER IF TRUSSES BEAR ON INTERIOR WALLS SHOWN AS NON-LOAD
- BEARING ON APPROVED PRINTS. GIRDER TRUSSES MUST HAVE LOAD CARRIED DOWN TO THE FOUNDATION OR LOAD
- SUPPORTING MEMBER. STUD PACK / COLUMN SHOWN ON PLANS. ROOF COVERING SHALL BE ASPHALT SHINGLES AND SHALL COMPLY WITH IRC 2018
- SECT. R905.2
- MINIMUM ROOF SLOPE FOR ASPHALT SHINGLES SHALL BE 2:12. 10 11. ROOF SLOPES IN BETWEEN 4:12 AND 2:12 SHALL REQUIRE DOUBLE UNDERLAYMENT IN ACCORDANCE WITH IRC 2018 TABLE R905.1.1(2).
- EVERSTEAD STRUCTURAL SCOPE ENDS AT TOP PLATE FOR ROOF TRUSSES. 12.

TRUSS DIRECTION

GIRDER TRUSS LOCATION

INTERIOR LOAD BEARING WALL



ROOF PLAN NOTES CPG DBA 4.00 COVERING WILL HAVE 1 ROOF VENT AND 4 SOFFIT VENTS 4.11 MINIMUM ROOFING COMPOSITION- 30 YR COMPOSITE SHINGLES ON 15# FELT ON 1/2" OSB SHEATHING OR AS REQUIRED BY CODE. **SUMMIT** 4.31 BUILD CRICKET VALLEY AWAY FROM INTERSECTION FOR POSITIVE DRAINAGE. HOMES 120 SE 30TH ST. LEE'S SUMMIT, MO 64082 816-246-6700 COPYRIGHT 2017 HIS DRAWING HAS BEEN PREPARED BY SUMMIT HOMES, OR UNDER THEIR DIRECT SUPERVISION AS AN INSTRUMENT OF SERVICE AND IS INTENDED FOR USE ONLY ON THIS PROJECT. ALL DRAWINGS, SPECIFICATIONS, AND DESIGNS, INCLUDING THE OVERALL LAYOUT, FORM, AND COMPOSITION OF SPACES ARE PROTECTED BY COPYRIGHT REGISTERED TO CPG, INC. ANY REPRODUCTION, USE, OR DISCLOSURE OF THE INFORMATION CONTAINED HEREIN WITHOUT THE WRITTEN CONSENT FROM CPG, INC. D/B/A SUMMIT HOMES EXCEPT AS REQUIRED FOR BIDDING AND CONSTRUCTION OF THIS PROJECT IS STRICTLY PROHIBITED. ADDRESS: 3204 SW ARBOR SOUND DR LEE'S SUMMIT, MO 69 SOMERVIEW CRAFTSMAN AWTHORN RIDGE #16 4 BEDS, 3 BATHS SMAN SIDGI BATI PROFESSIONAL SEAL: CHRISTOPH NUMBER PE-2015016986 12/06/2023 EVERSTEAD IS RESPONSIBLE FOR STRUCTURAL SPECIFICATIONS ONLY. ARCHITECTURAL PLANS WERE PROVIDED BY OTHERS. EVERSTEAD 3741 NE TROON DR. LEES SUMMIT, MO 64064 816-399-4901 GENERAL NOTES ROOF AND CEILING FRAMING ARE PRE-ENGINEERED ROOF VERSION: TRUSSES. 1.2 ASPHALT SHINGLES MIN 2/12. FLASH ALL PENETRATIONS AND INTERSECTIONS. VENT EACH ENCLOSED ATTIC SPACE. NET AREA OPENING = ISSUE DATE: 1/50TH OF VENTED AREA OR 1/300TH IF 580% OF VENTING 11.20.23 SHEET NUMBER: **A5.0** PROVIDE BLOCKING AT ALL CEILING JUMPS FOR INSULATION.

NEAR TOP.

PLAN

SCALE: 1/4" = 1'-0"

ROOF

BUILD CRICKET VALLEY AWAY FROM INTERSECTION FOR POSITIVE DRAINAGE. SEE FRAMING SPECIFICATIONS FOR DETAILS.

DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.

PROVIDE FOAM INSULATION AT EXTERIOR WHERE MAIN LEVEL ROOF LINE MEETS UPPER LEVEL WALLS.

А.	GENERAL NOTES IRC 2018	C.5	CONCRETE (CONT.)	
A .1	PLANS SHALL COMPLY WITH 2018 INTERNATIONAL RESIDENTIAL CODE (IRC) WITH AMENDMENTS AS ADOPTED BY THE APPROPRIATE GOVERNING JURISDICTION. THE CONTRACTOR SHALL NOTIFY THE		CONCRETE MIX TO UTILIZE A MAXIMUM WATE APPLICATIONS. ADMIXTURES SHALL NOT CON	R-CEMENT MATERIALS RATIO OF 0.45 FOR ALL TAIN ANY CHLORIDES.
	ENGINEER OF RECORD IF ANY CHANGES OR DEVIATIONS FROM THE PLAN ARE MADE DURING CONSTRUCTION. THE ENGINEER OF RECORD MAY REQUIRE REVISED DRAWING OR CALCULATIONS		CONCRETE POURED AGAINST AN EXISTING SI	JRFACE SHOULD BE ROUGHENED TO A MINIMUN
	AT ITS DISCRETION. IF DISCREPANCIES ARE IDENTIFIED THE MOST CONSERVATIVE SPECIFICATION SHALL APPLY.		 OF 1/4 INCH AMPLITUDE. REBAR PLACEMENT SHALL BE AS FOLLOWS: 	
A.2	LOADING ASSUMPTIONS		REDAR PLACEMENT SHALL BE AS FOLLOWS. CONCRETE CAST AGAINST AND PERM	ANENTLY EXPOSED TO EARTH 3.0 IN CLR
	DEAD ROOF 10 PSF UNO		 CONCRETE EXPOSED TO EARTH OR W NOT EXPOSED TO WEATHER OR GROUP 	/EATHER 1.5 IN CLR
	ROOF + CEILING (NO STORAGE)15 PSFROOF + CEILING (STORAGE)20 PSF		 SLABS, WALLS, JOISTS BEAMS, COLUMNS 	3/4 IN CLR 1.5 IN CLR
	CEILING JOISTS (STORAGE) 10 PSF EXTERIOR BALCONY / DECK 10 PSF			R-ENTRAINED FOR GARAGE SLABS, FOOTINGS,
	INTERIOR FLOOR (MAIN FLOOR)15 PSFINTERIOR FLOOR (UPPER FLOORS)10 PSF8" THICK MASONRY WALL96 PSF		 WALLS, OR FLATWORK EXPOSED TO WEATHE SHORING AND SUPPORTING FORMWORK SHA 	
	6" THICK MASONRY WALL 72 PSF EXTERIOR LIGHT FRAMED WOOD WALLS 15 PSF		MEMBERS BEFORE CONCRETE STRENGTH RE CYLINDERS OR 28 DAYS.	
	INTERIOR LIGHT FRAMED WOOD WALLS 10 PSF (INTERIOR WALLS INCLUDED IN 15 PSF DEAD LOAD)			GRADE SPACE SHALL BE DAMPPROOFED. THE DGE OF THE FOOTING TO THE FINISHED GRADE.
	ROOF LIVE LOAD20 PSFFLOOR LIVE LOAD40 PSF (HABITABLE)	C.6	CONCRETE WALLS WITH REINFORCEMENT STEEL	
	GARAGE50 PSF WITH 2000 LB POINT LOADSTORAGE20 PSF (UNINHABITABLE)GUARDRAIL:50 PSF (UNINHABITABLE)		REINFORCING STEEL SHALL CONFORM TO AS	TM A615, GRADE 40.
	CONTINUOUS LINEAR 50 PLF MAXIMUM POINT 200 LBS		SMOOTH BARS OR WELDED WIRE FABRIC SH	ALL CONFORM TO ASTM 185.
	SNOW		90 DEG. HOOK SHOWN IN DRAWINGS SHALL B	
	GROUND SNOW LOAD 20 PSF		 STRAIGHT EXTENSION LENGTH = 12X I BEND DIAMETER = 12X BAR DIA. 	BAR DIA.
	WIND VELOCITY 115 MPH EXPOSURE CATEGORY B		HOOKED DOWELS:	
В.	SOIL AND SITE ASSUMPTIONS			IS TO WALL SHALL BE PROVIDED TO MATCH (TENDED TO 3" CLEAR FROM BOTTOM OF
B.1	FOUNDATION DESIGN ASSUMES MINIMUM SOIL BEARING FOR THE SITE OF 1,500 PSF (2,000 PSF FOR KANSAS CITY, MO) UNLESS OTHERWISE NOTED. CONTRACTOR TO VISUALLY INSPECT THE SITE OR PROVIDE GEOTECHNICAL INVESTIGATION TO VERIFY MINIMUM ACCEPTABLE SOIL CONDITIONS FOR CL		 HOOKED DOWELS MATCH SLAB REINF FOUNDATION. 	ORCING FROM SLAB TO WALLS OR SLAB TO
	(SILTY CLAY) AS DEFINED BY 2018 IRC. THE CONTRACTOR IS RESPONSIBLE FOR ANY SOIL CONDITION THAT DOES NOT MEET THE MINIMUM REQUIREMENTS AND FOR CONTACTING THE ENGINEER OF		PROVIDE (2) - #5 BARS AROUND PERIMETER C	F ALL SUSPENDED SLABS.
	RECORD.			RCEMENT, THE LENGTH OF LAP SPLICE SHALL BI
B.2	ACCESSORY STRUCTURES WITH AN EAVE HEIGHT LESS THAN 10'-0" AND AN AREA LESS THAN 600 FT MAT PROVIDE A MINIMUM SOIL COVER OF 12 INCHES MEASURED FROM THE BOTTOM OF CONCRETE.			A LAP SPLICE SHALL NOT EXCEED THE SMALLER ND 6 INCHES (152MM) [SEE FIGURE R608.5.4.(1)].
B.3	LATERAL SOIL PRESSURES UNLESS OTHERWISE NOTED ACTIVE 60 PSF		TOP HORIZONTAL REINFORCEMENT SHALL BE	
B.4	AT REST 100 PSF SITE GRADING SHALL PROVIDE POSITIVE DRAINAGE AWAY FROM THE STRUCTURE AT A MINIMUM OF		WALL. HORIZONTAL WALL REINFORCEMENT SHALL 1	ERMINATE AT THE END OF THE WALL WITH A
	O.5% (6" IN THE FIRST 10'-0"). ALTERNATE APPROACHES MAY BE APPROVED IF THE ALTERNATE DESIGN IS EQUIVALENT IN EFFECTIVENESS AND PERFORMANCE, AND PROVIDES FOR POSITIVE SITE DRAINAGE.		STANDARD HOOK	
C.	FOUNDATION NOTES	C.7		
C.1	FOUNDATION ANCHORAGE (IRC R403.1.6)		COLD WEATHER IS DEFINED AS THREE CONSI TEMPERATURE DROPS BELOW 40 DEGREES F FAHRENHEIT FOR MORE THAN HALF OF ANY (AHRENHEIT AND NOT ABOVE 50 DEGREES
	• SILL PLATES SHALL BE BOLTED TO THE FOUNDATION WALL WITH A MINIMUM ¹ / ₂ " DIAMETER		COLD WEATHER CONCRETE WORK SHALL CO	
	 ANCHOR BOLTS EMBEDDED AT LEAST 7" INTO THE CONCRETE. BOLTS SHALL BE SPACED NO GREATER THAN 6'-0" O.C. 			OR PROTECTION SHALL BE AVAILABLE AT THE
	THERE SHALL BE A MINIMUM OF TWO BOLTS PER PLATE SECTION, WITH A BOLT PLACED		PROJECT SITE BEFORE COLD WEATHER CON	CRETING BEGINS. IE SUPPLIER SHALL AT A MINIMUM REACH THE
	WITHIN 12" AND NOT CLOSER THAN 7 BOLT DIAMETERS OF THE END OF EACH PLATE SECTION.			STRENGTH IN MINIMUM 72 HOURS OR 2000 PSI -
	 A PROPERLY SIZED NUT AND WASHER SHALL BE TIGHTENED ON EACH BOLT TO THE PLATE, (NOTE: 7" EMBEDMENT + 1-1/2" SILL PLATE + 3/4" FOR NUT AND WASHER EQUALS A 9-1/4" LONG BOLT). 		THE TEMPERATURE OF CONCRETE AT PLACE FAHRENHEIT .	MENT SHALL BE A MINIMUM OF 55 DEGREES
	• WALL BRACING METHODS (IRC R602) MAY REQUIRE ADDITIONAL ANCHORAGE.		THE MINIMUM CONCRETE TEMPERATURE AT DEGREES FAHRENHEIT.	THE TIME OF MIXING SHALL NOT BE BELOW 65
C.2	CONCRETE SLABS		ALL SNOW, ICE AND FROST MUST BE REMOVE	D PRIOR TO PLACING CONCRETE
	 CONCRETE SLABS PLACED ON FILL MATERIAL WHICH SHALL BE COMPARED TO ENSURE UNIFORM SUPPORT OF THE SLAB AND SHALL NOT EXCEED 24" OF COMPACTED GRANULATED MATERIAL (SAND OR GRAVEL) OR 8" OF EARTH: 		THE CONTRACTOR SHALL PROVIDE ADEQUAT	E PROTECTION FOR CONCRETE AGAINST
	THIS MAY OCCUR AT GARAGE FLOOR FILLS, OR OVER EXCAVATED AREAS UNDER		FREEZING AND MAINTAIN A CONCRETE TEMPI HOUR PERIOD AFTER CONCRETE PLACEMEN INSULATING BLANKETS AND/OR THE USE OF 1	
	 FLOOR SLABS. THE DESIGN AND INSTALLATION DETAILS IN THIS DOCUMENT (WHERE APPLICABLE 			CEMENT OF SLAB OR FOOTINGS SHALL NOT BE
	BASED ON SIZE AND SPACING LIMITATIONS) MAY BE USED IN LIEU OF PROVIDING A SEPARATE DESIGN.		 LESS THAN 35 DEGREES FAHRENHEIT. INSULATION, FORMS AND HEATERS MAY BE R 	EMOVED AFTER 72 HOURS
	 STRUCTURAL SLABS EXCEEDING THE SPANS AND CONDITIONS OF THE APPROVED DETAILS SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER. 		MAINTAIN ADEQUATE PROTECTION OF SUB G EXPOSED CONCRETE ELEMENT TO PREVENT	RADE AND ADEQUATE DRAINAGE AWAY FROM
	SLABS AT MAX 4'-0" OVER-DIG ADJACENT TO FOUNDATION WALL:	C.8	FOOTNOTES	
	 WHERE SOIL IS EXCAVATED FOR A MAXIMUM DIMENSION OF 4'-0" HORIZONTALLY ADJACENT TO A FOUNDATION WALL, THE STANDARD OVER-DIG DETAIL MAY BE USED IN LIEU OF A COMPLETE STRUCTURAL SLAB. 		VERTICAL REINFORCEMENT FOR CONCRETE REINFORCEMENT SPACED 24" O.C. MAY BE PL WALLS SHALL HAVE VERTICAL REINFORCEME	ACED IN THE MIDDLE OF THE WALL. OTHER
	SEE "TYPICAL FOOTING/FOUNDATION WALL/STANDARD SLAB AT MAX 4'-0" OVER-DIG" DETAIL.		 8" WALL – MINIMUM 2" FROM TENSION 10" WALL – MINIMUM 6-3/4" FROM THE 	FACE OUTSIDE FACE
C.3	VAPOR RETARDER / BARRIER (IRC R506.2.3)		 EXTEND BARS TO WITHIN 8" OF THE TO HORIZONTAL REINFORCEMENT: 	JP OF THE WALL
	A 6 MILLIMETER POLYETHYLENE OR APPROVED VAPOR RETARDER WITH JOINTS LAPPED A MINIMUM OF 6" IS REQUIRED BETWEEN THE CONCRETE FLOOR SLAB AND THE BASE COURSE		ONE BAR SHALL BE PLACED WITHIN 12	2" OF THE TOP OF THE WALL
	OR PREPARED SUBGRADE, (NOT REQUIRED FOR GARAGE SLABS OR DETACHED UNHEATED ACCESSORY BUILDINGS).		HORIZONTAL BARS SHOULD BE AS CL	CED WITH SPACING NOT TO EXCEED 24" O.C. OSE TO THE TENSION FACE AS POSSIBLE
C.4	FOOTINGS		SUPPLEMENTAL REINFORCEMENT AT	L REINFORCEMENT (I.E. 2" FROM INSIDE FACE) CORNERS – PLACE 1 #4 REBAR 48" LONG AT 45
	• THE BOTTOM OF ALL FOOTINGS SHALL EXTEND NOT LESS THAN 36" BELOW GRADE FOR FROST PROTECTION (IRC R403.1.4).		THE EDGE OF INSIDE CORNERS.	NINGS. PLACE REINFORCEMENT WITHIN 6" OF
	 FOOTINGS FOR FREESTANDING ACCESSORY STRUCTURES WITH AN AREA OF 600 SQ. FT. OR LESS AND AN EAVE HEIGHT OF 10'-0" OR LESS SHALL EXTEND BELOW GRADE A MINIMUM OF 12". 		EXCEED A DEPTH OF MORE THAN 24" BELOW	ICKNESS SHALL BE 3-1/2". LEDGES SHALL NOT THE TOP OF THE WALL FOR WALL THICKNESS I 24" O.C. TO WITHIN 8" OF THE TOP OF THE WALI
	 EXTERIOR WALLS, BEARING WALLS, COLUMNS AND PIERS SHALL BE SUPPORTED ON CONTINUOUS SOLID MASONRY OR CONCRETE FOOTINGS, OR APPROVED STRUCTURAL SYSTEM TO SAFELY SUPPORT THE IMPOSED LOADS AND SHALL BE SIZED AND REINFORCED IN 		THE SHORTEST DIMENSION BETWEEN INTERS	LL LENGTH SHALL BE MEASURED USING INSIDE
	 ACCORDANCE WITH THIS STANDARD OR SHALL BE ENGINEERED DESIGN. FOOTINGS UNDER FOUNDATION WALLS SHALL BE CONTINUOUS AROUND THE STRUCTURE 		SECTION). MINIMUM SPECIFIED COMPRESS	
	 THE CONTINUOUS TRANSITIONS BETWEEN FOOTINGS AT DIFFERENT LEVELS ENCLOSING 		PER TABL TYPE OR LOCATION OF CONCRETE	
	USABLE SPACE SHALL BE MADE BY APPROVED SOLID JUMPS OR SUPPORT SYSTEMS TO PROVIDE SAFE SUPPORT OF THE STRUCTURE.		CONSTRUCTION	FOR SEVER WEATHERING POTENTIAL
	SEE "TYPICAL FOOTING/FOUNDATION WALLS/STANDARD SLAB AT MAXIMUM 4" OVER-DIG" AND "FOOTING JUMP" DETAILS.		BASEMENT WALLS, FOUNDATIONS AND OTHER CONCRETE NOT EXPOSED TO THE WEATHER	2,500
C.5	CONCRETE		BASEMENT SLABS AND INTERIOR SLABS ON GRADE, EXCEPT GARAGE FLOOR SLABS	2,500
	• ALL CONCRETE CONSTRUCTION SHOULD CONFORM TO ACI 318-14 (OR ACI 332) OR 2018 IRC.		BASEMENT WALLS, FOUNDATION WALLS, EXTERIOR	
	THE MINIMUM CONCRETE 28 DAY COMPRESSIVE STRENGTH SHALL BE AS SPECIFIED IN IRC TABLE R402.2.		WALLS AND OTHER VERTICAL CONCRETE WORK EXPOSED TO THE WEATHER	3,000
			PORCHES, CARPORT SLABS AND STEPS	

EXPOSED TO THE WEATHER, AND GARAGE FLOOR SLABS

SUSPENDED SLABS

MUM WATER-CEMENT MATERIALS RATIO OF 0.45 FOR ALL NOT CONTAIN ANY CHLORIDES. EXISTING SURFACE SHOULD BE ROUGHENED TO A MINIMUM

FOLLOWS:

ND PERMANENTLY EXPOSED TO EARTH	3.0 IN CLF 1.5 IN CLF
OR GROUND	3/4 IN CLF
S	1.5 IN CLF

STEEL

OUNDATIONS TO WALL SHALL BE PROVIDED TO MATCH ING AND EXTENDED TO 3" CLEAR FROM BOTTOM OF

REE CONSECUTIVE DAYS WHERE THE AVERAGE DAILY DEGREES FAHRENHEIT AND NOT ABOVE 50 DEGREES F OF ANY ONE OF THOSE THREE DAYS.

ONCRETE WALLS THAT ARE NOT FULL HEIGHT AND FOR . MAY BE PLACED IN THE MIDDLE OF THE WALL. OTHER

COMPRESSIVE STRENGTH OF CONCRETE

PER TABLE R402.2			
E	MINIMUM SPECIFIED COMPRESSIVE STRENGTH (f'c) FOR SEVER WEATHERING POTENTIAL		
	2,500		
N	2,500		
exterior Work	3,000		
E	3,500		
	4,000		

D.1

	<u>/ING/STRUCTURE</u>			
FRAM	AING NOTES			
•	ALL TREATED LUMBER SIZ			
•	ALL NON TREATED LUMBE PINE UNLESS OTHERWISE		SIZES ARE #2 TREATED	SOUTHERN YELLOW
•	ALL UNMARKED HEADERS BEARING WALLS.	S SHALL BE A MINIMUM #	2 DOUGLAS FIR-LARCH	(2) 2X10 ON LOAD
•	ALL HEADERS/BEAMS TO SHALL BE PROVIDED AT A			
•	DOUBLE JOIST UNDER PA	RALLEL INTERIOR NON-	LOAD BEARING WALLS.	
•	CANTILEVERS, OVER BEA	MS AND DOOR JAMBS S	HALL BE BLOCKED.	
•	ANY WOOD MEMBER IN C ATTACHED TO) SHALL BE			HE FURRING THEY ARE
•	IN BEARING WALLS, STUD SPACED NOT MORE THAN SIZE. THOSE STUDS GREA PROFESSIONAL ENGINEE	I IS SPECIFIED IN IRC TA ATER THAN 10'-0" FEET I	BLE R602.3(5) FOR THE N LENGTH SHALL BE DE	CORRESPONDING STUD
•	ALL WOOD STRUCTUAL P. SPECIFICATION AND SUPF OCCUR OVER SUPPORTS ADJACENT PANELS. PROV MOISTURE CONTENT SHA	PLEMENTS OF THE APA AND SHALL BE STAGGE /IDE 1/8" INCH SPACE AT	OR EQUIVALENT. ALL PA RED ONE HALF PANEL PANEL ENDS. WOOD S	ANEL END JOINTS SHALL LENGTH FROM
• •	OR BETTER. EXTERIOR WALLS EXTERIOR OSB SH EDGES, 12" O. C. II 2X4 OR 2X6 INTER LOAD BEARING, BI PLY BEING FIELD A FIELD APPLIED LA FIELD APPLIED LA LOAD BEARING HE THE TOP PLATE W INTERIOR NON LO DOUBLE TOP PLAT HEADER CRIPPLE NON LOAD BEARIN CRIPPLE FRAMING CLEAR HEIGHT IS ALL LUMBER IN CONTACT PRESSURE TREATED (PT) FIELD APPLIED SIL BOTTOM (SOLE) P ALL PRESSURE TREATED PRESERVATIVES. PRESSU C2, LP-22, AND IRC SECTIO PRESSURE TREATED. FASTENERS, INCLUDING N DIPPED, ZINC-COATED GA COATING TYPES AND WEI WOOD SHALL BE IN ACCO	RIOR WALLS AS PERMIT TO BE CONTINUOUSLY IEATHING TO BE FASTE N THE FIELD. IOR LOAD BEARING WAI RACED, AND SHEAR WA APPLIED WITH A MIN. 24 P SPLICED TOP PLATE: I EADERS PER HEADER S EADERS TO BE FABRICA 'ITH CRIPPLE FRAMING I AD BEARING WALLS: DF TE IS NOT REQUIRED FO SPACING CAN BE 24" O. NG WALLS S NOT REQUIRED ABOVE 22" OR LESS FOR NON-I WITH MASONRY OR OT L PLATE: PT DF-L #2 LATE IN CONTACT WITH WOOD SHALL BE PRES JRE TREATMENT SHALL DN R317. ALL LUMBER <	TED BY CODE: DOUGLAS SHEATHED WITH MIN. 7 NED WITH 8D COMMON LLS DF-L #2 OR BETTER LLS, REQUIRE A DOUBL ' LAP SPLICE DF-L #2 OR BETTER CHEDULE OR AS SHOW TED WITH THE HEADER BELOW AS NEEDED UNG -L #2 STUD GRADE OR F OR INTERIOR NON LOAD C. REGARDLESS OF WA E OR BELOW OPENINGS DAD BEARING WALLS. HERWISE EXPOSED TO MASONRY: PT DF-L #2 SURE TREATED WITH W COMPLY WITH THE REG 8" ABOVE THE FINISHED NECTOR MANUFACTUF	NAILS; 6" O. C. AT PANEL E TOP PLATE. THE TOP N ON FRAMING PLANS. AT THE UNDER SIDE OF D. BETTER BEARING WALLS ALL STUD SPACING FOR WHERE THE VERTICAL WEATHERING TO BE ATER-BORNE QUIREMENTS OF AWPB, D GRADE SHALL BE O WOOD SHALL BE HOT- BRONZE OR COPPER. RESSURE TREATED RER'S
[RECOMMENDATIONS. IN T ASTM A653 TYPE G185 ZIN EXCEPTIONS, REFER TO F ENGINEE	IC-COATED GALVANIZEI R317.3.1.		IT, SHALL BE USED. FOR
-		F _b (PSI)	E (PSI)	F _v (PSI)
-	LVL	3100	1.9X10 ⁶	285
	DOUGLAS FIR-LARCH	900	1.6X10 ⁶	180
	GLU-LAM	2400	1.8X10 ⁶	230
STRU • •	JCTURAL STEEL STEEL DESIGN, FABRICAT STEEL CONSTRUCTION. STEEL PIPE COLUMNS SH STEEL GRADE AND SPECI	ALL BE A MINIMUM OF S	CHEDULE 40. FOLLOWS:	
	 HOLLOW STRUCT CHANNELS, PLATE WIDE FLANGES: 	URAL SECTIONS: ES, ANGLES, AND COLUI	MNS: AS	GTM A500 (F _Y = 46 KSI) GTM A36 (F _Y = 36 KSI) GTM A992 (F _Y = 50 KSI)

WIDE FLANGES: STEEL PIPE COLUMN

ANCHOR RODS:

BOLTS SHALL CONFORM TO ASTM A307

WELDING SHALL CONFORM TO THE AWS CODES FOR BUILDING CONSTRUCTION, WELDING SHALL BE PERFORMED IN ACCORDANCE TO WELDING PROCEDURE SPECIFICATIONS (WPS) AS REQUIRED IN AWS D1.1. THE WPS VARIABLES SHALL BE WITHIN THE PARAMETERS ESTABLISHED BY THE FILLER-METAL MANUFACTURER.

WELDS SHALL USE E70XX ELECTRODES AND A MINIMUM OF 3/16" SIZE UNLESS NOTED OTHERWISE.

ALL WELDS SPECIFIED AS FIELD WELDS MAY BE SHOP WELDED AT THE CONTRACTOR'S OPTION IF ERECTION CAN STILL BE EXECUTED.

E. <u>GLAZING</u>

D.2

- GLAZING IN HAZARDOUS LOCATIONS AS IDENTIFIED IN IRC R308.4 SHALL BE OF APPROVED • SAFETY GLAZING MATERIALS.
 - GLASS IN STORM DOORS: INDIVIDUAL FIXED OR OPERABLE PANELS ADJACENT TO A DOOR WHERE THE NEAREST VERTICAL EDGE OF THE GLAZING IS WITHIN A 24" ARC OF EITHER VERTICAL EDGE OF THE DOOR IN A CLOSED POSITION AND WHERE THE BOTTOM EDGE OF THE GLAZING IS LESS THAN 60" ABOVE THE FLOOR.
 - GLAZING ADJACENT TO THE LANDING AT THE BOTTOM OF THE STAIRWAY WHERE THE • GLAZING IS LESS THAN 36 INCHES ABOVE THE LANDING AND WITHIN A 60 IN HORIZONTAL ARC LESS THAN 180 DEGREES FROM THE BOTTOM TREAD NOSING SHALL BE CONSIDERED A HAZARDOUS LOCATION.
 - GLAZING IN WALLS, ENCLOSURES OR FENCES CONTAINING OR FACING HOT TUBS, SPAS, • WHIRLPOOLS, SAUNAS, STEAM ROOMS, BATHTUBS, SHOWERS, AND INDOOR OR OUTDOOR SWIMMING POOLS WHERE THE BOTTOM EXPOSED EDGE OF THE GLAZING IS LESS THAN 60" MEASURED VERTICALLY ABOVE ANY STANDING OR WALKING SURFACE.
- WINDOW FALL PROTECTION SHALL BE PROVIDED IN ACCORDANCE WITH IRC R312.2.

F. <u>STAIRWAYS</u>

STAIRWAYS SHALL PROVIDE A MAXIMUM 7-3/4" RISE AND A MINIMUM 10" RUN.

REQUIRED GUARD RAILS AT OPEN-SIDED WALKING SURFACES, INCLUDING STAIRS, PORCHES, BALCONIES, OR LANDINGS, SHALL NOT BE LESS THAN 36" HIGH MEASURED VERTICALLY ABOVE THE ADJACENT WALKING SURFACE.

- EXCEPTION (1): GUARD RAILS ON THE OPEN SIDES OF STAIRS SHALL HAVE A HEIGHT NOT LESS THAN 34" MEASURED VERTICALLY FROM A LINE CONNECTING THE LEADING EDGES OF THE TREADS.
- EXCEPTION (2): WHERE THE TOP OF THE GUARD ALSO SERVES AS A HANDRAIL ON THE • OPEN SIDES OF STAIRS, THE TOP OF THE GUARD SHALL NOT BE LESS THAN 34" AND NOT MORE THAN 38" MEASURED VERTICALLY FROM A LINE CONNECTING THE LEADING EDGES OF THE TREADS.

GUARD RAIL ENCLOSURES SHALL HAVE INTERMEDIATE RAILS OF ORNAMENTAL PATTERNS THAT DO NOT ALLOW PASSAGE OF A SPHERE 4" IN DIAMETER.

EACH STAIRWAY OF FOUR OR MORE RISERS SHALL PROVIDE A CONTINUOUS HANDRAIL ON AT LEAST ONE SIDE BETWEEN 34" AND 38" ABOVE THE NOSING OF THE TREADS.

HANDRAILS SHALL HAVE A CIRCULAR CROSS SECTION OF 1-1/4" TO 2" OR OTHER APPROVED GRASPABLE SHAPE PER IRC R311.7.8.5.

MINIMUM 6'-8" OF HEADROOM CLEARANCE IS REQUIRED IN STAIRWAYS.

ENCLOSED ACCESSIBLE SPACE UNDER STAIRWAYS SHALL HAVE WALLS AND THE UNDERSIDE OF THE STAIR AND LANDING PROTECTED WITH 1/2" GYPSUM BOARD ON ENCLOSURE PER IRC R302.7.

<u>GARAGES</u>

G.

THE GARAGE FLOOR SHALL SLOPE 1/8" PER 12" TO DRAIN OR VEHICLE ENTRY DOORWAYS.

DOORS BETWEEN THE GARAGE AND THE DWELLING TO BE: SELF CLOSING, MINIMUM 1-3/8" SOLID CORE OR HONEYCOMBED STEEL DOOR, AND AT LEAST 20 MINUTE FIRE RATED.

THE GARAGE SHALL BE SEPARATED FROM THE DWELLING AND ITS ATTIC AREAS BY A MINIMUM 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE WHERE A FLOOR/CEILING SPACE IS PROVIDED ABOVE.

THE GARAGE COLUMNS AND BEAMS SUPPORTING THE SEPARATION SHALL ALSO BE PROTECTED WITH 1/2" GYPSUM BOARD OR EQUIVALENT.

WHERE HABITABLE SPACE OCCURS ABOVE THE GARAGE FLOOR/CEILING ASSEMBLY SHALL BE PROTECTED WITH A MINIMUM 5/8" TYPE "X" GYPSUM BOARD ON THE GARAGE CEILING.

GARAGE DOOR AND FRAME – THE "H" FRAME FOR THE ATTACHMENT OF THE TRACK AND COUNTER BALANCE SHALL CONSIST OF THE FOLLOWING: 2X6 VERTICAL JAMBS RUNNING FROM THE FLOOR TO CEILINGS, ATTACHED WITH 1-3/4" X 0.120" NAILS AT 7" O.C. STAGGERED WITH (7) 3-1/4" X 0.120" NAILS THROUGH THE JAMB INTO THE HEADER, 2X8 HEADER (MINIMUM) FOR ATTACHMENT OF COUNTER BALANCE SYSTEM.

GARAGE VEHICLE DOORS AND FRAMES SHALL BE DESIGNED AND INSTALLED TO MEET THE 115 MPH WIND LOAD REQUIREMENT OF DASMA 108 AND ASTM E330-96 (IRC R301.2.1).

<u>ROOF</u>

Н.

ASTM A992 ($F_{Y} = 50$ KSI)

ASTM F1554 (F_Y = 36 KSI)

ASTM A53 GR.B (F_Y = 35 KSI)

THE ROOF IS DESIGNED FOR 20 PSF GROUND SNOW LOAD (MINIMUM).

PROVIDE 2X SOLID BLOCKING SUPPORT BELOW ALL POINT LOADS CONTINUOUS TO BEARING STRUCTURE AND/OR FOUNDATION BELOW.

ROOF IS ENGINEERED TO COMPLY WITH IRC R802.

ROOF TO BE ASPHALT SHINGLES UNO AND SHALL COMPLY WITH IRC 2018 SECT. R905.2

MINIMUM ROOF SLOPE FOR ASPHALT SHINGLES SHALL BE 2:12.

ROOF SLOPES IN BETWEEN 2:12 AND 4:12 SHALL REQUIRE DOUBLE UNDERLAYMENT IN ACCORDANCE WITH IRC 2018 SECTION R905.2.2:

"APPLY A 19-INCH (483MM) STRIP OF UNDERLAYMENT FELT PARALLEL TO AND STARTING AT THE EAVES, FASTENED SUFFICIENTLY TO HOLD IN PLACE. STARTING AT THE EAVE, APPLY 36-INCH-WIDE (914 MM) SHEETS OF UNDERLAYMENT, OVERLAPPING SUCCESSIVE SHEETS 19 INCHES (483MM), AND FASTENED SUFFICIENTLY TO HOLD IN PLACE. END LAPS SHALL BE 4-INCH (102MM) AND SHALL BE OFFSET BY 6 FEET (1829 MM). DISTORTIONS IN THE UNDERLAYMENT SHALL NOT INTERFERE WITH THE ABILITY OF THE SHINGLES TO SEAL."

SAFETY REQUIREMENTS

I.1 EMERGENCY EGRESS AND RESCUE

PROVIDE ONE WINDOW FROM EACH BEDROOM THAT HAS A MINIMUM OPENABLE AREA OF 5.7 SQ. FT. WITH A MINIMUM OPENABLE HEIGHT OF 24" AND WIDTH OF 20".

I.2 SMOKE AND CARBON MONOXIDE SAFETY (PER IRC R314)

BASEMENT EGRESS TO MEET THE REQUIREMENTS OF IRC R310.

PROVIDE SMOKE ALARMS IN EACH SLEEPING ROOM, OUTSIDE OF EACH SLEEPING AREA AND ON EACH FLOOR INCLUDING BASEMENTS.

SMOKE ALARMS SHALL BE INTERCONNECTED IN SUCH A MANNER THAT THE ACTUATION OF

ONE ALARM WILL ACTIVATE ALL OF THE ALARMS IN THE DWELLING.

CARBON MONOXIDE DETECTORS SHALL BE INSTALLED AS REQUIRED PER IRC R315.

J. <u>ENERGY REQUIREMENTS</u>

LIGHTING FIXTURES PENETRATING THE THERMAL ENVELOPE SHALL BE IC-RATED, LEAKAGE RATED AND SEALED TO THE GYPSUM WALLBOARD AS REQUIRED PER IRC N1102.4.5.

PROGRAMMABLE THERMOSTATS SHALL BE INSTALLED AS REQUIRED PER IRC N1103.1.1.

AIR HANDLERS SHALL BE RATED FOR MAXIMUM 2% AIR LEAKAGE RATE PER IRC N1103.3.2.1. BUILDING FRAMING CAVITIES SHALL NOT BE USED AS DUCTS OR PLENUMS.

HOT WATER PIPES SHALL BE INSULATED AS REQUIRED PER IRC N1103.4.

ALL EXHAUST FANS SHALL TERMINATE TO THE BUILDING EXTERIOR AS REQUIRED PER IRC M1504.3.

MAKEUP AIR SYSTEMS SHALL BE INSTALLED FOR KITCHEN EXHAUST HOODS THAT EXCEED 400

AN AIR HANDLING SYSTEM SHALL NOT SERVE BOTH THE LIVING SPACE AND THE GARAGE PER IRC M1601.6 ENERGY CONSERVATION.

ABBREVIATIONS

Κ.

•

AFF: ABOVE FINISHED FLOOR

CFM AS REQUIRED PER IRC M1503.6.

CLR: CLEAR

- EFF: EFFECTIVE EFP: EQUIV FLUID PRESSURE EOR: ENGINEER OF RECORD EQUIV: EQUIVALENT MAX: MAXIMUM MIN: MINIMUM NTS: NOT TO SCALE O.C.: ON CENTER PCF: POUNDS PER CUBIC FOOT
- PLF: POUNDS PER LINER FOOT PSF: POUNDS PER SQUARE FOOT
- PSI: POUNDS PER SQUARE INCH UNO: UNLESS NOTED OTHERWISE FV: FIELD VERIFY





EVERSTEAD 3741 NE TROON DRIVE, SUITE 200 LEE'S SUMMIT, MO 64064 EVERSTEAD.COM (816)399-4901

U \mathbf{O} 5

 \mathbf{O} S 7 2 2 \leq 00 Σ В Т Ŕ S S ≥ S ш S \mathbf{O}

 \sim

 \mathbf{m}

 $\boldsymbol{\Omega}$

σ

Q

 \supset

 \cup

REVISIONS


DATE

SCALE

STRUCTURAL **GENERAL NOTES**

SOOO

10/10/2023 11:03:15 AM 1/4" = 1'-0"



BLOCK FIRST THREE JOIST BAYS @ 24" OC WHER FJ RUN PARALLEL

FJ, PER PLAN


CRIPPLE WALL


TO FOUNDATION WALL


EXTEND ANCHOR BOLTS


EXTERIOR SHEATHING

(PER PLAN)










WALL OR CURB





REINFORCEMENT SHALL LAP A MINIMUM OF 24 INCHES AT ENDS, SPLICES, AND


INSIDE FACE)


AROUND CORNERS.

3 TYPICAL WALL SECTION DETAIL NTS













DATE SCALE

As indicated









	MINIMUM	CONNECTION CRITERIA		
METHODS, MATERIAL	THICKNESS	FASTENERS	SPACING	
WSP - WOOD STRUCTURAL PANEL AND CS-WSP CONTINUOUSLY SHEATHED	3/8" PANEL W/ MINIMUM 24/0 STRUCTURAL PANEL SPAN RATING	6d COMMON NAILS (2.0" x .113") W/ MINIMUM 1.5" PENETRATION	6" EDGES, 12 FIELD	
WOOD STRUCTURAL PANEL	7/16" PANEL W/ MINIMUM 24/16 STRUCTURAL PANEL SPAN RATING	8d COMMON NAILS (2.5" x .131") W/ MINIMUM 1.75" PENETRATION	6" EDGES, 12' FIELD	
PFH - PORTAL FRAME WITH HOLD-DOWNS	3/8"	SEE DETAIL ON THIS PAGE	SEE DETAIL C THIS PAGE	
PFG - PORTAL FRAME AT GARAGE	3/8"	SEE IRC SECTION R602.10.6.3	SEE IRC SECTIO R602.10.6.3	
LIB LET-IN-BRACING	1x4 WOOD OR APPROVED METAL	WOOD: 2-8d COMMON NAILS OR 3-8d (2-1/2" LONG x .113" DIA.) NAILS	WOOD: PER ST AND TOP AND BOTTOM PLATE	
	STRAPS AT 45 TO 60 DEGREE ANGLES FOR MAX 16" STUD SPACING	SIMPSON WB/WBC INSTALLED IN "X" PAIRS OR IN OPPOSING "V" FASHION AND FASTENED W/ (2) 16d COMMON NAILS FOR PLATE AND (1) 8d COMMON NAIL FOR STUDS	METAL: PER STU AND TOP AND BOTTOM PLATE	
		1/2" INTERIOR SHEATHING W/ STUDS AT 16" O.C.: 13 GAGE, 1-3/8" LONG, 19/64" HEAD; .098" DIA., 1-1/4" LONG, ANNULAR-RINGED; 5d COOLER NAIL, .086" DIA., 1-5/8" LONG, 15/64" HEAD; OR GYPSUM BOARD NAIL, .086" DIA. 1-5/8" LONG, 9/32" HEAD PER TABLE R702.3.5 (SEE TABLE FOR OTHER PANEL THICKNESS OPTIONS)	FOR ALL BRACE WALL PANEL LOCATIONS: 7 EDGES (INCLUDING TC AND BOTTOM PLATES) 7" FIEL	
GB-GYPSUM BOARD	1/2"	EXTERIOR 1/2" SHEATHING: 1-1/2" GALVANIZED ROOFING NAIL; STAPLE GALVANIZED, 1-1/2" LONG; 1-1/4" SCREWS, TYPE W OR S PER TABLE R602.3(1)		
		EXTERIOR 5/8" SHEATHING: 1-3/4" GALVANIZED ROOFING NAIL; STAPLE GALVANIZED, 1-5/8" LONG; 1-5/8" SCREWS, TYPE W OR S PER TABLE R602.3(1)		

DESCRIPTION OF BUILDING MATERIALS	NUMBER AND TYPE OF FASTENER	SPACING AND LOCATION OF FASTENERS	DESCRIPTION OF BUILDIN MATERIALS
	ROOF		
BLOCKING BETWEEN JOISTS OR RAFTERS TO TOP PLATE	4-8d BOX (2-1/2"x0.113") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 3-3"x0.131" NAILS	TOE NAIL	JOIST TO SILL, TOP PLATE, GIRDER
CEILING JOISTS TO PLATE	4-8d BOX (2-1/2"x0.131") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10 BOX (3"x0.128") OR 3-3"x0.131" NAILS	TOE NAIL	RIM JOIST, BAND JOIST C BLOCKING TO SILL OR TOP F (ROOF APPLICATIONS ALS
CEILING JOISTS NOT ATTACHED TO PARALLEL RAFTER LAPS OVER PARTITIONS	4-10d BOX (3"x0.128") OR 3-16d COMMON (3-1/2"x0.162") OR 4-3"x0.131" NAILS	FACE NAIL	1"x6" SUBFLOOR OR LESS EACH JOIST
COLLAR TIE TO RAFTER, FACE NAIL OR 1-1/4"x20 GAGE RIDGE STRAP	4-10d BOX (3"x0.128") OR 3-10d COMMON (3"x0.148") OR 4-3"x0.131" NAILS	FACE NAIL EACH RAFTER	2" SUBFLOOR TO JOIST O GIRDER
RAFTER OR ROOF TRUSS TO TOP PLATE, TOE NAIL	4-16d BOX (3-1/2"x0.135") OR 3-10d COMMON (3"x0.148") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS	2 TOE NAILS ON ONE SIDE AND 1 TOE NAIL ON OPPOSITE SIDE OF EACH RAFTER OR TRUSS	2" PLANKS (PLANK & BEAM-FLO ROOF)
ROOF RAFTERS TO	4-16d BOX (3-1/2"x0.135") OR 3-10d COMMON (3"x0.148") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS	TOE NAIL	BAND OR RIM JOIST TO JOI
RIDGE, VALLEY OR HIP RAFTERS	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162") OR 3-10d BOX (3"x0.128") OR 3-3"x0.131" NAILS	END NAIL	
	WALL		BUILT-UP GIRDERS AND BEAM LUMBER LAYERS
STUD TO STUD (NOT AT BRACED WALL	16d COMMON (3-1/2"x0.162")	24" O.C. FACE NAIL	LUMBER LAYERS
PANELS)	10d BOX (3"x0.128") OR 3"x0.131" NAIL	16" O.C. FACE NAIL	
STUD TO STUD AND ABUTTING STUDS AT INTERSECTION WALL CORNERS	16d BOX (3-1/2"x0.135") OR 3"x0.131" NAIL	12" O.C. FACE NAIL	
(AT BRACED WALL PANELS)	16d COMMON (3-1/2"x0.162")	16" O.C. FACE NAIL	JOISTS OR RAFTERS
	16d COMMON (3-1/2"x0.162")	16" O.C. EACH EDGE FACE NAIL	
BUILT-UP HEADER, TWO PIECES WITH 1/2" SPACER	16d BOX (3-1/2"x0.135")	12" O.C. EACH EDGE FACE NAIL	BRIDGING OR BLOCKING T JOIST
CONTINUOUS HEADER TO STUD	5-8d BOX (2-1/2"x0.113") OR 4-8d COMMON (2-1/2"x0.131") OR 4-10d BOX (3"x0.128")	TOE NAIL	DESCRIPTION OF BUILDIN MATERIALS
	16d COMMON (3-1/2"x0.162")	16" O.C. FACE NAIL	WOOD STRUCTURA [SEE TABLE R602.3(3)
TOP PLATE TO TOP PLATE	10d BOX (3"x0.128") OR 3"x0.131" NAIL	12" O.C. FACE NAIL	
DOUBLE TOP PLATE SPLICE	8-16d COMMON (3-1/2"x0.162") OR 12-16d BOX (3-1/2"x0.135") OR 12-10d BOX (3"x0.128") OR 12-3"x0.131" NAILS	FACE NAIL ON EACH SIDE OF END JOINT (MINIMUM 24" LAP SPLICE LENGTH EACH SIDE OF END JOINT)	3/8" - 1/2"
BOTTOM PLATE TO JOIST, RIM JOIST,	16d COMMON (3-1/2"x0.162")	16" O.C. FACE NAIL	19/32" - 1"
BAND JOIST, OR BLOCKING (NOT BRACED WALL PANELS)	-16d BOX (3-1/2"x0.135") OR 3"x0.131" NAIL	12" O.C. FACE NAIL	
BOTTOM PLATE TO JOIST, RIM JOIST, BAND JOIST, OR BLOCKING (AT BRACED WALL PANELS)	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162") OR 4-3"x0.131" NAILS	3 EACH 16" O.C. FACE NAIL 2 EACH 16" O.C. FACE NAIL 4 EACH 16" O.C. FACE NAIL	1-1/8" - 1-1.4"
	4-8d BOX (2-1/2"x0.113") OR 3-16d BOX (3-1/2"x0.135") OR 4-8d COMMON (2-1/2"x0.131") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS	TOE NAIL	1/2" STRUCTURAL CELLULO FIBERBOARD SHEATHING
TOP OR BOTTOM PLATE TO STUD	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162") OR 3-10d BOX (3"x0.128") OR	END NAIL	25/32" STRUCTURAL CELLULO FIBERBOARD SHEATHING
TOP PLATES, LAPS AT CORNERS AND INTERSECTIONS	3-3"x0.131" NAILS 3-10d BOX (3"x0.128") OR 2-16d COMMON (3-1/2"x0.162") OR 3-3"x0.131" NAILS	FACE NAIL	1/2" GYPSUM INTERIOR COVE (R702.3.5) 5/8" GYPSUM INTERIOR COVE
1" BRACE TO EACH STUD AND PLATE	3-8d BOX (2-1/2"x0.113") OR 2-8d COMMON (2-1/2"x0.131") OR 2-10d BOX (3"x0.128") OR 2 STAPLES 1-3/4"	FACE NAIL	(R702.3.5) WOOD STRUC
1"x6" SHEATHING TO EACH BEARING	2 STAPLES 1-3/4 3-8d BOX (2-1/2"x0.113") OR 2-8d COMMON (2-1/2"x0.131") OR 2-10d BOX (3"x0.128") OR 2 STAPLES, 1" CROWN, 16 GA., 1-3/4" LONG	FACE NAIL	3/4" AND LESS
	3-8d BOX (2-1/2"x0.113") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 3 STAPLES, 1" CROWN, 16 GA., 1-3/4" LONG		7/8" - 1"
1"x8" AND WIDER SHEATHINGTO EACH BEARING	WIDER THAN 1"x8": 4-8d BOX (2-1/2"x0.113") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 4 STAPLES, 1" CROWN, 16 GA., 1-3/4" LONG	FACE NAIL	1-1/8" - 1-1/4"
	. ,		

BUILDING LS	NUMBER AND TYPE OF FASTENER	SPACING AND LOCATION OF FASTENERS		
	FLOOR			
P PLATE, OR R	4-8d BOX (2-1/2"x0.113") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 3-3"x0.131" NAILS	TOE	ENAIL	
) JOIST OR	8d BOX (2-1/2"x0.113")	4" O.C.	TOE NAIL	
OR TOP PLATE IONS ALSO)	8d COMMON (2-1/2"x0.131") OR 10d BOX (3"x0.128") OR 3"x0.131" NAIL	6" O.C. TOE NAIL		
OR LESS TO IST	3-8d BOX (2-1/2"x0.113") OR 2-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 2 STAPLES, 1" CROWN, 16 GA., 1-3/4" LONG	FAC	ENAIL	
JOIST OR	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162")	BLIND ANI	D FACE NAIL	
BEAM-FLOOR &	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162")	AT EACH BEA	RING FACE NAIL	
ST TO JOIST	3-16d COMMON (3-1/2"x0.162") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS OR 4 3"x14 GA. STAPLES, 7/16" CROWN	END) NAIL	
	20d COMMON (3"x0.128")	O.C AT TOP END	ER AS FOLLOWS: 32' D AND BOTTOM AND GGERED.	
ND BEAMS, 2" YERS	10d BOX (3"x0.128") OR 3"x0.131" NAIL	BOTTOM STAGG	NAIL AT TOP AND ERED ON OPPOSITE SIDES	
	AND: 2-20d COMMON (4"x0.192") OR 3-10d BOX (3"x0.128") OR 3-3"x0.131" NAILS	FACE NAIL AT ENDS AND AT EAG SPLICE		
IPPORTING FTERS	4-16d BOX (3-1/2"x0.135") OR 3-16d COMMON (3-1/2"x0.162") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS	AT EACH JOIST OR RAFTER, FACI NAIL		
OCKING TO	2-10d BOX (3"x0.128") OR 2-8d COMMON (2-1/2"x0.131") OR 2-3"x0.131" NAILS	EACH END, TOE NAIL		
BUILDING LS	NUMBER AND TYPE OF FASTENER	EDGES (IN)	INTERMEDIATE SUPPORTS (IN)	
UCTURAL PANE	LS, SUBFLOOR, ROOF AND INTERIOR WALL SH ARTICLEBOARD WALL SHEATHING TO FRAMIN	IEATHING TO FRAM IG	1ING AND	
R602.3(3) FOR W	OOD STRUCTURAL PANEL EXTERIOR WALL SH	EATHING TO WALL	FRAMING]	
n	6d COMMON (2"x0.113") NAIL (SUBFLOOR, WALL) OR 8d COMMON (2-1/2"x0.131") NAILS (ROOF) OR RSRS-01 (2-3/8"x0.113") NAIL (ROOF)	6	12	
"	8d COMMON NAIL (2-1/2"x0.131") OR RSRS-01 (2-3/8"x0.113") NAIL (ROOF)	6	12	
.4"	10d COMMON (3"x0.148") NAIL OR 8d (2-1/2"x0.131") DEFORMED NAIL	6	12	
	OTHER WALL SHEATHING			
CELLULOSIC	1-1/2" GALVANIZED ROOFING NAIL, 7/16" HEAD DIAMETER OR 1-1/4" LONG 16 GA. STAPLE WITH 7/16" OR 1" CROWN	3	6	
CELLULOSIC IEATHING	1-3/4" GALVANIZED ROOFING NAIL, 7/16" HEAD DIAMETER OR 1-1/2" LONG 16 GA. STAPLE WITH 7/16" OR 1" CROWN	3	6	
DR COVERING	1-1/2" GALVANIZED ROOFING NAIL: STAPLE GALVANIZED, 1-1/2" LONG; 1-1/4" SCREWS, TYPE "W" OR "S"	7	7	
DR COVERING	1-3/4" GALVANIZED ROOFING NAIL: STAPLE GALVANIZED, 1-5/8" LONG; 1-5/8" SCREWS, TYPE "W" OR "S"	7	7	
D STRUCTURAL	PANELS, COMBINATION SUBFLOOR UNDERLA	YMENT TO FRAMIN	G	
ESS	6d DEFORMED (2"x0.120") NAIL OR 8d COMMON (2-1/2"x0.131") NAIL	6	12	
	8d COMMON (2-1/2"x0.131") NAIL OR 8d DEFORMED (2-1/2"x0.120") NAIL	6	12	
/4"	10d COMMON (3"x0.148") NAIL OR 8d DEFORMED (2-1/2"x0.120") NAIL	6	12	

TABLE R507.9.1.3(2) PLACEMENT OF LAG SCREWS AND BOLTS IN DECK LEDGERS AND BAND JOISTS					
	MINIMUM END AND EDGE DISTANCES AND SPACING BETWEEN ROWS (INCHES)				
	TOP EDGE	BOTTOM EDGE	ENDS	ROW SPACING	
LEDGER	2	3/4	2	1-5/8 MIN. 5 MAX	
BAND JOIST 3/4 2 2 1-5/8 Mill 5 MAX					

	RSTEAD ERING & DESIGN
LEE'S	EVERSTEAD CON DRIVE, SUITE 200 SUMMIT, MO 64064
SUMMIT HOMES	HAWTHORN 169 3204 SW ARBOR SOUND DR LEES SUMMIT, MO
REVISIONS	
	STENING CHEDULE
DATE SCALE	\$550 10/10/2023 10:22:09 AM 1/4" = 1'-0"

GENERAL NOTES


Α.

- ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATIONAL RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE. THE INFORMATION PROVIDED ON THIS PLAN SHEET IS DESIGNED AND REVIEWED IN ACCORDANCE WITH THE IRC.
- CONCRETE WINDOW WELLS SHALL BE MINIMUM 3000 PSI COMPRESSIVE STRENGTH. ASSUMED SOIL MINIMUM BEARING CAPACITY 1500 PSF.
- CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF EXISTING CONDITIONS AND DIMENSIONS CRITICAL FOR CONSTRUCTION OF NEW WORK.
- MEANS AND METHODS OF CONTRUCTION ARE OUT OF SCOPE OF THE DESIGN PROVIDED. TEMPORARY SUPPORTS SHALL BE INSTALLED BEFORE REMOVAL OF LOAD BEARING STRUCTURES.
- DIMENSIONAL LUMBER SHALL BE MINIMUM DOUGLAS FIR LARCH NO. 2. LVL BEAMS SHALL HAVE MINIMUM 2.0E AND $3100F_b$
- STEEL POST COLUMNS SHALL BE MINIMUM SCHEDULE 40, Fy=35KSI. 10. 11. MINIMUM HEADERS

WINDOW EGRESS (NTS)


ASSUMES LOADING FOR BUILDING WITH MAXIMIMUM WIDTH OF 36 FT (ROOF WITH 30PSF SNOW LOADS, CEILING, AND TWO FLOORS W/ CENTER BEARING) PER TABLE R602.7(1)

FLIN TADLE NOUZ. (1)		
HEADER	MAX CLEAR SPAN	MIN JACK STUDS
(2) 2X10	4'-0"	2
(3) 2X10	5'-1"	2
(2) 2X12	4'-9"	3
(3) 2X12	5'-11"	2
(2) 1.75X9.25 LVL	7'-6"	3
(2) 1.75X11.25 LVL	9'-3"	3




WINDOW WELL FOR EGRESS (NTS)





- A. INSTALL PER MANUFACTURER'S WRITTEN INSTRUCTIONS В.
- B. INSTALLED TO EXISTING FOUNDATION
- CONCRETE WINDOW WELL Α.



WINDOWS

S560

10/10/2023 10:22:12 AM As indicated

DATE SCALE