


LOWER LEVEL - 1,008 SQ. FT.  
MAIN FLOOR - 1,962 SQ. FT.  
SECOND FLOOR - 964 SQ. FT.  
TOTAL 3,934 SQ. FT.

DECK 216 SQ. FT.  
GARAGE 627 SQ. FT.  
UNFINISHED 759 SQ. FT.

DISCLAIMER  
ACTUAL PLANS AND ELEVATIONS MAY VARY  
FROM ARCHITECTURAL DRAWINGS.  
DUE TO TERRAIN/BACKFILL PROCESS.  
FRONT ELEVATIONS ARE ARCHITECTURAL  
DRAWINGS AND MAY VARY DUE TO  
MATERIAL AVAILABILITY.

NOTE:  
PLANS DESIGNED PER IRC AS  
ADOPTED BY GOVERNING JURISDICTION

New Mark Homes  
P.O. Box 12025  
Parkville, Missouri 64152  
Ph. (816) 969-9010



APEX ENGINEERS, INC.  
1659 LOCUST ST.  
KANSAS CITY, MO 64108  
816.421.3222

STRUCTURAL DESIGN REVIEW  
KANSAS ENGINEERING LICENSE: 090  
MISSOURI ENGINEERING LICENSE: 200304673

Rawson Residence  
2083 N.W. Obrien Rd. - Woodside Ridge - Lot 176  
Lees Summit, Missouri

Copyright 2023

DRAWN BY: CJD


CHECKED BY: CA

DATE:12/1/2023

A1

PROJ. 23-378





FOUNDATION PLAN  
SCALE: 1/4" = 1'-0"

ALL WINDOWS SIZES ARE EXPRESSED  
IN FEET AND INCHES TO THE UNIT  
SIZE.

STRUCTURAL NOTES:

- ALL UNMARKED HEADERS MIN (2)#2-2x10
- ALL HEADERS AND BEAMS MIN #2 GRADE DFL (OR EQ.)
- BEARINGS WALL
- STRUCTURE NOTED AS FLUSH TO BE FLUSH WITH SUB-FLOOR ABOVE.

BRACED WALL METHODOLOGY

CONTINUOUS EXTERIOR SHEATHING PER WSP METHOD (BELOW)  
UNLESS OTHERWISE NOTED ON THE PLAN

XXXX EXTERIOR BRACED WALLS:

WSP METHOD: WOOD STRUCTURAL PANEL SHEATHING WITH A THICKNESS NOT LESS THAN 3/4" WITH MINIMUM SPAN RATING OF 24/0 FOR 16" OC STUD SPACING WITH 6d COMMON NAILS AT 6" OC EDGES AND 12" OC FIELD OR SHEATHING THICKNESS NOT LESS THAN 7/16" WITH MINIMUM SPAN RATING OF 2 3/16 FOR 24" OC SPACING WITH 8d COMMON NAILS AT 6" OC EDGES AND 12" OC IN FIELD.  
(NOTE: FRAMING MEMBERS 16" OC MAX UNBLOCKED, AND WITH SHEATHING APPLIED DIRECTLY TO FRAMING MEMBERS)

///// INTERIOR BRACED WALLS (REF 2-S4.0):

GB METHOD: 1/2" MIN. GYPSUM BOARD OVER STUDS SPACED 24" MAX. FASTENED WITH No 6 - 1 1/2" TYPE 'W' OR 'S' DRYWALL SCREWS AT 7" OC EDGES AND FIELD (MIN. 4'-0" SECTION FOR BOTH SIDES.)

OR

LIB METHOD: 1x4 WOOD FASTENED WITH (3) 8d COMMON NAILS OR SIMPSON / USP 16 GA. TYPE WB (OR EQUAL) STL. X-BRACE(S) AT 45° TO 60° ANGLES, MAXIMUM 16" O.C. STUD FASTENED PER MANUFACTURER'S SPECIFICATIONS.

COLUMN & PIER PAD SCHEDULE (REF. 5/S2.0)

COLUMN MARK	PAD SIZE	REINFORCEMENT	COLUMN SIZE
△	30" x 30" x 12"	(4) #4 BAR E.W.	3" SCH 40 (3.5" OD)
△	36" x 36" x 12"	(4) #4 BAR E.W.	3" SCH 40 (3.5" OD)
△	42" x 42" x 12"	(5) #4 BAR E.W.	3" SCH 40 (3.5" OD)
△	48" x 48" x 12"	(6) #4 BAR E.W.	3 1/2" SCH 40 (4" OD)
△	54" x 54" x 16"	(8) #4 BAR E.W.	REF PLAN
△	60" x 60" x 16"	(10) #4 BAR E.W.	REF PLAN

1. COLUMN & PAD SIZES SHOWN ARE FOR MAXIMUM ADJUSTABLE COLUMN HEIGHT OF 9'-1". REQUIRES SEPARATE ENGRD DESIGN IF GREATER THAN 9'-1" TALL. COLUMNS SIZED AS QWIK-ADJUST COLUMN, BY QUALITY WAY PRODUCTS, LLC. REFER TO SAFE LOADING CAPACITIES PER MANUF SPECS, OR SUBSTITUTION TO ANOTHER PRODUCT ONLY WITH PRIOR APPROVAL BY APEX ENGINEERS.
2. COLUMN & PIER PAD SIZES SHOWN ARE BASED ON AN ASSUMED MINIMUM ALLOWABLE SOIL BEARING CAPACITY OF 2,000PSF.

COLUMN & PIER SCHEDULE

MARK	COLUMN SIZE	PIER DIA.
△	6x6	12"
△	6x6	16"
△	6x6	18"
△	6x6	24"
△	6x6	28"

1. ALL PIERS TO BEAR ON ORIGINAL UNDISTURBED SOIL OF 2,000 PSF BEARING CAPACITY OR FILL COMPACTED AND TESTED TO CONFORM TO THE RECOMMENDATIONS OF A GEOTECHNICAL ENGINEER.
2. PIERS SHALL EXTEND BELOW THE FROST LINE: MIN. DEPTH OF 36" BELOW GRADE.
3. POST SHALL BE TREATED OR CEDAR WITH SIMPSON ABU66 POST BASE

DETAIL REFERENCES

- |           |   |           |  |
|-----------|---|-----------|--|
| 1<br>S2.0 | TYPICAL FOUNDATION WALL DETAIL                | 2<br>S2.1 | STRUCTURAL GARAGE SLAB PIER PAD DETAIL                 |
| 2<br>S2.0 | TYPICAL "UNRESTRAINED" FOUNDATION WALL DETAIL | 3<br>S2.1 | STRUCTURAL GARAGE SLAB / WALL SECTION                  |
| 3<br>S2.0 | TYPICAL DEAD MAN DETAIL                       | 6<br>S2.1 | TYPICAL OVERDIG DETAIL AT BASEMENT SLAB                |
| 4<br>S2.0 | FOUNDATION WALL JUMP DETAIL                   | 1<br>S4.0 | ALTERNATE BRACED WALL PANEL DETAIL                     |
| 5<br>S2.0 | COLUMN PAD DETAIL                             | 1<br>S4.0 | APA NARROW WALL BRACING METHOD WITHOUT HOLD-DOWNS ALT. |
| 1<br>S2.1 | TYPICAL STRUCTURAL GARAGE SLAB PLAN           | △         | COLUMN AND PIER PAD SCHEDULE (SHEET S2.0)              |



EXPANSIVE SOILS DISCLAIMER:

THESE PLANS HAVE BEEN PREPARED BASED ON A PRESUMPTIVE ALLOWABLE BEARING CAPACITY AS ALLOWED BY IRC CODE AND THE LOCAL ENFORCING JURISDICTION.

APEX ENGINEERS, INC. (APEX) RECOMMENDS THAT ALL FOOTING EXCAVATIONS BE EVALUATED BY A LICENSED GEOTECHNICAL ENGINEER PRIOR TO THE PLACEMENT OF ANY FOUNDATION ELEMENTS. GEOTECHNICAL INVESTIGATION AND/OR TESTING IS NOT A SERVICE PROVIDED OR OFFERED BY APEX.

APEX HAS NOT BEEN RETAINED TO DETERMINE THE EXPANSIVE SOIL CHARACTERISTICS OF THE SUBGRADE SOIL AND THEREFORE CANNOT BE HELD RESPONSIBLE FOR THE VOLUMETRIC CHANGES OF THE SOIL (INCLUDING BELOW THE BASEMENT SLAB) BY USE OF THESE PLANS WITHOUT AN ACCOMPANYING GEOTECHNICAL ENGINEERING REPORT. APEX SHALL NOT BE HELD LIABLE FOR ANY FUTURE MOVEMENT AND/OR DIFFERENTIAL MOVEMENT OF THE PROPOSED STRUCTURE AND THE POSSIBLE DAMAGE THAT MAY BE CAUSED AS A RESULT OF SUCH MOVEMENT. DAMAGE FROM EXPANSIVE SOILS AND/OR SETTLEMENT CAN RESULT IN AMONGST OTHER THINGS, THE FOLLOWING: BASEMENT SLAB HEAVE, SHEETROCK CRACKS, WINDOWS AND DOOR BECOMING OUT OF PLUMB AND STICKING AND/OR NOT OPENING, DAMAGE TO TILE, MOULDING, AND OTHER COSMETIC FINISHES.

New Mark Homes  
P.O. Box 12025  
Parkville, Missouri 64152  
Ph. (816) 969-9010



APEX ENGINEERS, INC.  
1659 LOCUST ST.  
KANSAS CITY, MO 64108  
816.421.3222

STRUCTURAL DESIGN REVIEW  
992  
KANSAS ENGINEERING LICENSE:  
MISSOURI ENGINEERING LICENSE:  
2003004673

Rawson Residence  
2083 N.W. Obrien Rd. - Woodside Ridge - Lot 176  
Lees Summit, Missouri

Copyright 2023

DRAWN BY: CJD

CHECKED BY: CA


DATE:12/1/2023

A2

PROJ. 23-378

NOTE:  
PLANS DESIGNED PER IRC AS  
ADOPTED BY GOVERNING JURISDICTION





MAIN FLOOR PLAN  
SCALE: 1/4" = 1'-0"

ALL WINDOWS SIZES ARE EXPRESSED  
IN FEET AND INCHES TO THE UNIT  
SIZE.

STRUCTURAL NOTES:  
- ALL UNMARKED HEADERS MIN  
(2)#2-2x10  
- ALL HEADERS AND BEAMS MIN #2  
GRADE DFL (OR EQ.)  
- XXXXXX= BEARING WALL  
- STRUCTURE NOTED AS FLUSH TO BE  
FLUSH WITH SUB-FLOOR ABOVE.

BRACED WALL METHODOLOGY  
CONTINUOUS EXTERIOR SHEATHING PER WSP METHOD (BELOW)  
UNLESS OTHERWISE NOTED ON THE PLAN

XXXX EXTERIOR BRACED WALLS:

WSP METHOD: WOOD STRUCTURAL PANEL SHEATHING WITH A THICKNESS NOT LESS THAN  
3/4" WITH MINIMUM SPAN RATING OF 24/0 FOR 16" OC STUD SPACING WITH 6d  
COMMON NAILS AT 6" OC EDGES AND 12" OC FIELD OR SHEATHING  
THICKNESS NOT LESS THAN 7/16" WITH MINIMUM SPAN RATING OF 24/0 FOR 24"  
OC SPACING WITH 8d COMMON NAILS AT 6" OC EDGES AND 12" OC IN FIELD.  
(NOTE: FRAMING MEMBERS 16" OC MAX, UNBLOCKED, AND WITH SHEATHING APPLIED DIRECTLY TO FRAMING  
MEMBERS.)


IIII INTERIOR BRACED WALLS (REF 2-S4.0):

GB METHOD: 1/2" MIN. GYPSUM BOARD OVER STUDS SPACED 24" MAX. FASTENED WITH  
No 6 - 1 1/2" TYPE 'W' OR 'S' DRYWALL SCREWS AT 7" OC EDGES AND FIELD  
(MIN. 4'-0" SECTION FOR BOTH SIDES.)

OR

LIB METHOD: 1x4 WOOD FASTENED WITH (3) 8d COMMON NAILS OR SIMPSON / USP 16 GA.  
TYPE WB (OR EQUAL) STL. X-BRACE(S) AT 45° TO 60° ANGLES, MAXIMUM 16"  
O.C. STUD FASTENED PER MANUFACTURER'S SPECIFICATIONS.

New Mark Homes  
P.O. Box 12025  
Parkville, Missouri 64152  
Ph. (816) 969-9010



APEX ENGINEERS, INC.  
1659 LOCUST ST.  
KANSAS CITY, MO 64108  
816.421.3222

STRUCTURAL DESIGN REVIEW  
KANSAS ENGINEERING LICENSE: 692  
MISSOURI ENGINEERING LICENSE: 200304673

Rawson Residence  
2083 N.W. Obrien Rd. - Woodside Ridge - Lot 176  
Lees Summit, Missouri

© Copyright 2023


DRAWN BY: CJD  
CHECKED BY: CA  
DATE: 12/1/2023

A3

PROJ. 23-378


NOTE:  
PLANS DESIGNED PER IRC AS  
ADOPTED BY GOVERNING JURISDICTION





STRUCTURAL DESIGN REVIEW  
KANSAS ENGINEERING LICENSE:  
992  
MISSOURI ENGINEERING LICENSE:  
2003004873

Copyright 2023




PROJ. 23-378


LIB METHOD: 1x4 WOOD FASTENED WITH (3) 8d COMMON NAILS OR SIMPSON / USP 16 GA. TYPE WB (OR EQUAL) STL. X-BRACE(S) AT 45° TO 60° ANGLES, MAXIMUM 16" O.C. STUD FASTENED PER MANUFACTURER'S SPECIFICATIONS.

ALL WINDOWS SIZES ARE EXPRESSED  
IN FEET AND INCHES TO THE UNIT  
SIZE.


NOTE:  
PLANS DESIGNED PER IRC AS  
ADOPTED BY GOVERNING JURISDICTION



SCALE:  $1/4'' = 1'-0''$



ROOF PLAN  
SCALE: 1/4" = 1'-0"

STRUCTURAL NOTES:  
- ALL UNMARKED HEADERS MIN (2)#2-2x10  
- ALL HEADERS AND BEAMS MIN #2 GRADE DFL (OR EQ.)  
-  = BEARING WALL  
- STRUCTURE NOTED AS FLUSH TO BE FLUSH WITH SUB-FLOOR ABOVE.

ROOF FRAMING NOTES  
  
ROOF DESIGNED FOR LIGHT ROOF COVERING  
30psf TOTAL LOAD [10psf DL, 20psf LL (SL)]  
  
ROOF SYSTEM IS DESIGNED TO MEET REQUIREMENTS OF IRC 802

\*RAFTERS (HEM-FIR, DOUG-FIR, OR EQUAL):  
SEE SPAN CHARTS BELOW

CODE MINIMUM		
RAFTERS	SPACING	MAX HORIZONTAL CLEARSPAN
#2-2x6	AT 24" OC	11'-7"
#2-2x6	AT 16" OC	14'-2"
#2-2x8	AT 24" OC	14'-8"
#2-2x8	AT 16" OC	17'-11"
#2-2x10	AT 24" OC	17'-10"
#2-2x10	AT 16" OC	21'-11"

NOTE: CODE MINIMUM ALLOWS FOR A RAFTER DEFLECTION OF L/180 TOTAL LOAD

HIGHER PERFORMANCE		
RAFTERS	SPACING	MAX HORIZONTAL CLEARSPAN
#2-2x6	AT 24" OC	8'-6"
#2-2x6	AT 16" OC	9'-9"
#2-2x8	AT 24" OC	11'-3"
#2-2x8	AT 16" OC	12'-9"
#2-2x10	AT 24" OC	14'-3"
#2-2x10	AT 16" OC	16'-3"

APEX ENGINEERS, INC. RECOMMENDED  
DEFLECTION = L/360 LIVE LOAD, L/240 TOTAL LOAD

\*RIDGE BOARDS ARE (UNLESS OTHERWISE NOTED)

#2-2x10 UP TO 9:12 PITCH

#2-2x12 OVER 9:12 PITCH

\*ALL HIPPS AND VALLEYS ARE (UNLESS OTHERWISE NOTED)

#2-2x10 UP TO 9:12 PITCH

#2-2x12 OVER 9:12 PITCH

#2-2x10 HIP/VALLEY, MAX CLEAR SPAN: 11'-11"

#2-2x12 HIP VALLEY, MAX HORIZ. CLEAR SPAN: 12'-11"

\*PURLINS ARE 2x6 MIN

- PURLIN STRUTS ARE AT 4'-0" OC

- PURLIN STRUTS SHALL BE INSTALLED AT NOT LESS THAN A 45 DEGREE ANGLE WITH THE HORIZONTAL

- ALL PURLIN STRUTS SHALL HAVE A MAX UNBRACED LENGTH OF 8'-0"



- PURLIN STRUTS SHALL BE CONSTRUCTED IN A "T" CONFIGURATION AND PER THE FOLLOWING CHART:


PURLIN STRUT	MAX PURLIN STRUT LENGTH
(2)2x4	8'-0"
(1)2x4 AND (1)2x6	12'-0"
(1)2x6 AND (1)2x8	20'-0"
(2)2x6 AND (1)2x8	30'-0"
CONSULT ARCH ENGR	>30'-0"

\*EACH END OF STRUT SHALL BE FASTENED WITH MIN (3)#8d OR (2)#16d NAILS

\*RIDGE BRACERS ARE SAME AS PURLIN BRACES-SPACING, SIZE, CONFIGURATION, AND INSTALLATION (SEE PURLIN BRACE NOTES ABOVE)

\*HIP AND VALLEY BRACES ARE THE SAME AS PURLINS SIZE, CONFIGURATION, AND INSTALLATION (SEE PURLIN BRACE NOTES ABOVE)


 = ROOF BRACE/STRUT (PER CHART)  
- SLASH IS TOP END OF BRACE  
- CIRCLE IS BOTTOM END OF BRACE  
  
 = PURLIN STRUTS AT 48" OC (PER CHART) U.N.O.  
- SLASH IS TOP END OF BRACE  
- ARROW IS BEARING LOCATION

 DENOTES BEARING WALL  
- - - - - DENOTES PURLIN  
- - - - - DENOTES BEARING STRUCTURE

1. THIS IS AN ENGINEERED ROOF STRUCTURE DESIGNED FOR COMPLIANCE WITH IRC 802.3, BUILD AS SHOWN WITH NO DEVIATIONS.
2. ALL HIPPS ARE DESIGNED TO BE CONTROLLED BY BENDING.
3. SHEAR AT BEARING WITH MIN 5 1/2" DEPTH DOES NOT CONTROL DESIGN. FOR VALLEYS REF 4/S3.2

NOTE:  
PLANS DESIGNED PER IRC AS  
ADOPTED BY GOVERNING JURISDICTION

New Mark Homes  
P.O. Box 12025  
Parkville, Missouri 64152  
Ph. (816) 969-9010



APEX ENGINEERS, INC.  
1659 LOCUST ST  
KANSAS CITY, MO 64108  
816.421.3222  
STRUCTURAL DESIGN REVIEW  
KANSAS ENGINEERING LICENSE: 692  
MISSOURI ENGINEERING LICENSE: 200304673

Rawson Residence  
2083 N.W. Obrien Rd. - Woodside Ridge - Lot 176  
Lees Summit, Missouri

©Copyright 2023

DRAWN BY: CJD  
CHECKED BY: CA  
DATE:12/1/2023

A5

PROJ. 23-378



SHEATHING AND FRAMING FASTENING SCHEDULE		
BUILDING COMPONENT	MATERIAL	FASTENING
ROOF SHEATHING¹	7/16" PLYWOOD	16 GA x 1-3/4" STAPLES AT 3" OC EDGES AND 6" OC IN FIELD
	1x4 #3 FURRING	1/2" CROWN STAPLES
FLOOR SHEATHING¹	3/4" T&G YELLOW PINE PLYWOOD APPLIED PERPENDICULAR TO JOISTS AND ENDS STAGGERED	8d COMMON NAILS AT 6" OC EDGES AND 12" OC IN THE FIELD
		14 GA x 2" STAPLES AT 4" OC EDGES AND 8" OC IN THE FIELD
CEILING COVERING¹	1/2" GYPSUM SHEATHING	12.5 GA x 1-1/2" RING OR SCREW SHANK NAILS AT 6" OC EDGES AND 8" OC IN THE FIELD
		7" OC NAILED / 12" OC SCREWED WITH 13 GA, 1-3/8" LONG, 19/64" HEAD, 0.098 DIA, 1-1/4" LONG, ANG-RINGED, 5d COOLER NAIL, 0.086 DIA, 1-5/8" LONG, 15/64" HEAD; OR GYP BD NAIL, 0.086 DIA, 1-5/8" LONG, 9/32" HEAD
INTERIOR WALL COVERING¹	1/2" GYPSUM SHEATHING	8d COMMON NAILS: 1-5/8" GALVANIZED STAPLES, 1-1/4" SCREWS, TYPE W OR S AT 4" OC EDGES AND 8" OC IN THE FIELD
EXTERIOR WALL SHEATHING	MIN 3/8" APA RATED SHEATHING	8d COMMON NAILS AT 6" OC EDGES AND 12" OC IN THE FIELD
CONVENTIONAL WOOD FRAMED WALLS	*SUPPORTING 2 FLOORS, ROOF, AND CEILING OR LESS. *HEIGHT: 10'-0" OR LESS SIZE: NOM 2x4 (NOM 2x6 WHEN SUPPORTING 2 FLOORS, CEILING, AND ROOF) *SPECIES: DOUG-FIR, HEM-FIR, SOUTHW PINE, SPRUCE-PINE-FIR *MAXIMUM SPACING 16" OC *STUDS 10' LENGTH OR LESS SHALL BE #3 STANDARD, OR STUD GRADE *STUDS OVER 10' LENGTH SHALL BE MIN #2 GRADE	*TOE NAIL RIM JOIST TO SILL OR TOP AT 16" OC *TOE NAIL STUD TO TOP AND SOLE PLATE: (4) 8d COMMON; (3) 3"x0.131" *END NAIL TOP AND SOLE PLATE TO STUD: (2) 16d COMMON; (3) 3"x0.131" *FACE NAIL BUILT-UP CORNER STUDS: 16d AT 24" OC; 3"x0.131" AT 16" *FACE NAIL BUILT-UP CORNER STUDS (AT BRACED WALL PANELS): 16d COMMON NAILS AT 16" OC; 3"x0.131" AT 12" OC *FACE NAIL JACK STUDS/TRIMMERS SUPPORTING HEADERS WITH: 10d NAILS AT 6" OC; 16d COMMON AT 16" OC; 3"x0.131" AT 12" OC; 3"x0.128" AT 12" OC *FACE NAIL DBL TOP PLATE: (8) 16d COMMON; (12) 3"x0.131"; (12) 3"x0.128" *DBL TOP PLATES WITH MIN 48" OFFSET OF EACH FACE NAIL LAPPED WITH: (6) 16d COMMON; (12) 3"x0.131"; (12) 3"x0.128" *FACE NAIL DBL TOP PLATES AT LAPPED CORNERS AND INTERSECTIONS WITH: (2) 16d COMMON; (3) 3"x0.131"; (3) 3"x0.128" *FACE NAIL SOLE PLATE TO FRAMING SYSTEM WITH: 16d COMMON AT 16" OC; 3"x0.131" AT 12" OC *TODNAL BRIDGING TO JOIST: EACH END: 16d COMMON; (2) 3"x0.131"; (3) 3"x0.128" *FACE NAIL LEDGER STRIPS SUPPORTING JOISTS OR RAFTERS WITH: (3) 16d COMMON; (4) 3"x0.131"; (4) 3"x0.128"
CONVENTIONAL WOOD HEADER FRAMING	PER PLAN	*TOE NAIL HEADERS TO WALL STUDS WITH (4) 8d NAILS AT EACH END. *FACE NAIL DOUBLE PIECE HEADERS WITH 16d NAILS AT 16" CENTERS ALONG EACH EDGE.
RAFTER TIES²	MIN 2x4 MEMBERS AT EACH RAFTER	REF TABLE R802.5.2
COLLAR TIES	MIN 1x4 MEMBERS AT 48" OC	FACENAIL TO RAFTERS IN UPPER 1/3 OF ATTIC SPACE WITH (3) 10d NAILS AT EACH
1. NOTE: ALL SHEATHING MATERIALS TO BE APPLIED PERPENDICULAR TO JOISTS AND ENDS STAGGERED. 2. RAFTER TIES SHALL NOT BE REQUIRED WHEN A STRUCTURAL RIDGE HAS BEEN PROVIDED AND ADEQUATELY DESIGNED (AS IN A FULLY VAULTED ROOM) SUCH SHALL BE NOTED AS "STRUCTURAL" ON THE PLAN.		
BUILDING COMPONENT	FASTEN TO	FASTEN WITH
RAFTERS	TO RIDGE/VALLEY/HIP RAFTERS	TOENAIL WITH (4) 16d ENDNAIL WITH (3) 16d
	TO PLATE	TOENAIL WITH (2) 16d
CEILING JOISTS	TO TOP PLATE	TOENAIL WITH (3) 8d AT EACH END
	WHERE CEILING JOISTS RUN PARALLEL TO RAFTERS FACENAIL TO RAFTERS WITH (3) 10d MIN	
FLOOR JOISTS	TO SILL OR GIRDER	TOENAIL WITH: (3) 8d COMMON; (3) 3"x0.131"; (4) 3"x0.128"
	TO RIM JOIST	ENDNAIL WITH: (3) 16d COMMON; (4) 3"x0.131"; (4) 3"x0.128"
BRACED WALL PANELS PIERS TO FRAMING MEMBERS ABOVE/BELOW: PARALLEL TO FRAMING MEMBERS ABOVE/BELOW:	TO FRAMING MEMBER	SOLE PL, 16" OC WITH: (3) 16d COMMON; (4) 3"x0.131" TOP PL, 6" OC WITH: 8d COMMON; 3"x0.131"
	TO FRAMING AND BLOCKING AT 16" OC	SOLE PL, 16" OC WITH: (3) 16d COMMON; (4) 3"x0.131" AND AT EACH BLOCK: (3) 16d COMMON; (4) 3"x0.131" TOP PL, 6" OC WITH: 8d COMMON; 3"x0.131" AND AT EACH BLOCK: (3) 8d COMMON; 3"x0.131"
NOTE: MEMBER THICKNESS AND FASTENING LISTED IN THIS SCHEDULE ARE MINIMUM IRC REQUIREMENTS. SPECIFIC PROJECT REQUIREMENTS NOTED WITHIN THE STRUCTURAL OR ARCHITECTURAL DRAWINGS, IF REQUIRED BY APEX ENGINEERS DESIGN NEEDING TO BE MORE STRINGENT, SHALL BE FOLLOWED.		

## ENERGY REQUIREMENTS

- LIGHTING FIXTURES PENETRATING THE THERMAL ENVELOPE SHALL BE IC-RATED, LEAKAGE RATED, AND SEALED TO THE GYPSUM WALLBOARD AS REQUIRED PER N1102.4.5.
- PROGRAMMABLE THERMOSTATS SHALL BE INSTALLED AS REQUIRED PER N1103.1.1.
- AIR HANDLERS SHALL BE RATED FOR MAXIMUM 2% AIR LEAKAGE RATE PER N1103.3.2.1.
- BUILDING FRAMING CAVITIES SHALL NOT BE USED AS DUCTS OR PLENUMS PER N1103.3.5
- HOT WATER PIPES SHALL BE INSULATED AS REQUIRED PER N1103.4.
- ALL EXHAUST FANS SHALL TERMINATE TO THE BUILDING EXTERIOR AS REQUIRED PER M1501.1.
- MAKEUP AIR SYSTEMS SHALL BE INSTALLED FOR KITCHEN EXHAUST HOODS THAT EXCEED 40 CFM AS REQUIRED PER M1503.6.
- AN AIR HANDLING SYSTEM SHALL NOT SERVE BOTH THE LIVING SPACE AND THE GARAGE PER M1601.6.

## ENERGY CONSERVATION

THE ENERGY EFFICIENCY OF THE DWELLING SHALL COMPLY WITH THE FOLLOWING TABLE(S) (WHERE THERE ARE DISCREPANCIES BETWEEN THIS TABLE AND THE PLANS, THE MOST RESTRICTIVE SHALL APPLY). IF TABLE 1 IS NOT COMPLETED AND ACCOMPANIED BY RESCHECK CALCULATIONS, THEN TABLE 2 SHALL BE APPLIED.

TABLE 1 - ResCheck COMPLIANCE SOFTWARE (FILL IN APPLICABLE VALUES FROM ResCheck CALC.S.)

BUILDING ELEMENT	MIN VALUE
WALLS - FRAMED	R-
WALLS - BASEMENT	R-
FLOORS - UNCONDITIONED SPACE	R-
FLOORS - OVER OUTSIDE AIR	R-
FLOORS - CRAWL SPACE	R-
SLAB - PERIMETER	R-
CEILING - FLAT	R-
CEILING - CATHEDRAL	R-
DOORS - GLASS	U-
DOORS - SOLID	U-
WINDOWS - OPERABLE	U-
WINDOWS - FIXED	U-
WINDOWS - OTHER	U-
FURNACE	AFUE-
AIR CONDITIONER	SEER-

NOTE: FOR USE OF TABLE 1 A ResCheck COMPLIANCE FORM MUST BE SUBMITTED WITH PLANS.

TABLE 2 - PRESCRIPTIVE ENVELOPE (MIN PRESCRIPTIVE APPROACH ACCEPTABLE FOR ANY DWELLING.)

BUILDING ELEMENT	MIN VALUE
CEILING - FLAT	R-49
CEILING - CATHEDRAL**	R-30
CEILING - CATHEDRAL	R-38
FLOORS - UNCONDITIONED SPACED	R-19
FLOORS - OVER OUTSIDE AIR	R-30
WALLS - BASEMENT	R-10 (CONT) OR R-13 (CAVITY)
CONCRETE SLAB ON GRADE	R-10 (FOR 2FT)
SKYLIGHTS	U=0.55
WALLS - EXTERIOR (2x4)	R-13 (CAVITY) + R-5 (CONT)
WALLS - EXTERIOR (2x6)	R-20
WALLS - CRAWL SPACE	R-19
GLAZING*	U<=0.32
GLAZING*	SHGF<=0.40

NOTE:  
TABLE 2 PER IRC TABLE N1102.1.2  
\*DEFAULT U-FACTOR FOR DOUBLE PANE, ARGON FILLED LOW-E TREATMENT IS U=0.35  
\*\*LIMITED TO AREAS LESS THAN 500 SQ-FT OR 20% OF CEILING AREA.

## DEFERRED SUBMITTALS

- THE ARCHITECT OR ENGINEER OF RECORD SHALL LIST THE DEFERRED SUBMITTALS ON THE PLANS FOR REVIEW BY THE BUILDING OFFICIAL. DOCUMENTS FOR DEFERRED SUBMITTAL ITEMS SHALL BE SUBMITTED TO THE ARCHITECT OR ENGINEER OF RECORD WHO SHALL REVIEW THEM AND FORWARD THEM TO THE BUILDING OFFICIAL WITH A NOTATION INDICATING THAT THE DEFERRED SUBMITTAL DOCUMENTS HAVE BEEN REVIEWED AND FOUND TO BE IN THE GENERAL CONFORMANCE TO THE DESIGN OF THE BUILDING. THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THE DEFERRED SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL. DEFERRED SUBMITTALS ARE DEFINED AS THOSE PORTIONS OF THE DESIGN THAT ARE NOT SUBMITTED AT THE TIME OF THE APPLICATION AND THAT ARE TO BE SUBMITTED TO THE BUILDING OFFICIAL WITH A SPECIFIED PERIOD. DEFERRAL OF ANY SUBMITTAL ITEMS SHALL HAVE THE PRIOR APPROVAL OF THE BUILDING OFFICIAL.
- DEFERRED SUBMITTAL ITEMS (WHEN APPLICABLE):

- TRUSSES
- JOISTS
- GUARDRAILS AND HANDRAILS
- STEEL FABRICATED STAIRS
- PRE-MANUFACTURED CANOPIES AND AWNINGS
- PRECAST HOLLOW CORE SLABS
- GROUND IMPROVEMENT AND/OR STRUCTURAL FOUNDATION SOLUTIONS (SUCH AS DRILLED PIERS)

## CONCRETE SCHEDULE

MINIMUM STRUCTURAL CONCRETE COVER					COVER
FORMED SURFACES EXPOSED TO GROUND OR WEATHER					2"
UNFORMED SURFACE IN CONTACT WITH THE GROUND					3"
WALLS AND SLABS NOT EXPOSED TO GROUND OR WEATHER					1"
INTERIOR BEAMS AND COLUMNS (TO TIES OF STIRRUPS)					1 1/2"
EPOXY GROUTING APPLICATIONS					
THREADED ROD ANCHORS			HILTI HIT-HY 200 A OR SIMPONS SET XP		
REINFORCING BARS			HILTI HIT-HY 200 R OR SIMPONS SET XP		
CONCRETE USE	28 DAY STRENGTH	CEMENT TYPE	W/C RATIO	SLUMP LIMIT (in.)	% AIR ENTRAINMENT
FOOTINGS/PIERS	3000 psi	N/A	0.55 (MAX)	5" (+/-1")	6% +/- 1%
FOUNDATION WALLS	3500 psi	N/A	0.50 (MAX)	4" (+/-1")	6% +/- 1%
INTERIOR SLABS	4000 psi	N/A	0.50 (MAX)	3" (+/-1")	3% MAX
SUSPENDED SLABS	4000 psi	N/A	0.50 (MAX)	3" (+/-1")	3% MAX

## EMERGENCY EGRESS AND RESCUE

- PROVIDE ONE WINDOW FROM EACH BEDROOM THAT HAS A MINIMUM OPENABLE AREA OF 5.7 SQUARE FEET WITH A MINIMUM OPENABLE HEIGHT OF 24 INCHES AND WIDTH OF 20 INCHES.
- BASEMENT EGRESS TO MEET THE REQUIREMENTS OF IRC SECTION 310.
- SMOKE ALARMS SHALL BE INSTALLED AS REQUIRED PER IRC 2018 SECTION R314.
- PROVIDE SMOKE ALARMS IN EACH SLEEPING ROOM, OUTSIDE OF EACH SLEEPING AREA, ON EACH FLOOR INCLUDING BASEMENTS AND HABITABLE ATTICS, AND NOT LESS THAN 3'-0" HORIZONTALLY FROM DOOR OR OPENING OF A BATHROOM THAT CONTAINS A BATHTUB OR SHOWER. ALARMS SHALL BE INTERCONNECTED IN SUCH A MANNER THAT THE ACTIVATION OF ONE ALARM WILL ACTIVATE ALL OF THE ALARMS IN THE DWELLING.
- CARBON MONOXIDE ALARMS SHALL BE INSTALLED AS REQUIRED PER IRC 2018 SECTION R315.
- CARBON MONOXIDE ALARMS SHALL BE INSTALLED OUTSIDE OF EACH SEPARATE SLEEPING AREA, WHERE A FUEL-BURNING APPLIANCE IS LOCATED WITHIN A BEDROOM OR ITS ATTACHED BATHROOM, A CARBON MONOXIDE ALARM SHALL BE INSTALLED WITHIN THE BEDROOM.

## FRAMING GENERAL

- ALL LUMBER SIZES ARE FOR DOUGLAS FIR-LARCH UNLESS NOTED OTHERWISE.
- ALL HEADERS TO BE MIN (2) #2-2X10 UNLESS NOTED OTHERWISE.
- BLOCK CANTILEVERS, DOORJAMBS, AND OVER BEAMS.
- ALL HEADERS TO BEAR ON A MINIMUM OF (2) 2X4 STUD POSTS UNLESS NOTED OTHERWISE.
- INTERIOR NON-BEARING WALLS, OTHER THAN THOSE RESTING DIRECTLY ON THE FOOTING SHALL BE ISOLATED FROM THE FLOOR FRAMING ABOVE.
- WHERE JOISTS RUN PARALLEL TO FOUNDATION WALLS, SOLID BLOCKING FOR A MINIMUM OF (2) JOIST SPACES BE PROVIDED TO A MAXIMUM OF 2'-0" CENTERS TO TRANSFER LATERAL LOADS ON THE WALL TO THE FLOOR DIAPHRAGM. THE BLOCKING SHALL BE SECURELY NAILED TO THE JOISTS AND FLOORING. NAIL JOISTS AND BLOCKING TO SILL PLATE WITH 0x10d NAILS (IRC SECTION R802.3.(1)).
- IF DUCTS ARE INSTALLED IN THE FIRST JOIST SPACE(S), NAIL 2x4s FLAT AT 2'-0" CENTERS WITHIN THE JOIST SPACE(S) AND THEN PROVIDE SILL BLOCKING, INSTALLED UPRIGHT, IN THE NEXT TWO JOIST SPACES. SECURE THE 2x4s TO THE SILL PLATE WITH (4) 10d NAILS.
- ALL SILLS AND SLEEPERS SUPPORTED ON CONCRETE OR MASONRY AND FURRING ATTACHED TO CONCRETE OR MASONRY SHALL BE OF DECAY RESISTANT MATERIALS.
- JOISTS UNDER BEARING PARTITIONS SHALL BE DOUBLED AND COMPLY WITH IRC SECTION R502.4.
- JOISTS FRAMING FROM OPPOSITE SIDES OVER BEARING SUPPORTS SHALL LAP A MINIMUM 3" AND SHALL BE NAILED TOGETHER WITH A MINIMUM 10d FACE NAILS.
- JOISTS FRAMING INTO A WOOD GIRDER OR BEAM SHALL BE SUPPORTED BY APPROVED FRAMING ANCHORS OR MINIMUM 2"x2" LEDGER STRIPS.
- FRAMING OF OPENINGS - HEADERS AND TRIMMERS SHALL BE OF SUFFICIENT CROSS SECTION TO SUPPORT THE FLOOR FRAMING. TRIMMER JOISTS SHALL BE DOUBLED WHEN THE HEADER IS SUPPORTED MORE THAN 3'-0" FROM THE TRIMMER JOIST BEARING. WHEN THE HEADER SPAN EXCEEDS 4'-0", THE HEADER AND TRIMMER SHALL BE DOUBLED.
- JOISTS AT SUPPORTS SHALL BE SUPPORTED Laterally AT THE ENDS BY FULL-DEPTH SOLID BLOCKING NOT LESS THAN 2" NOMINAL THICKNESS OR BY ATTACHMENT TO A HEADER, BAND OR RIM JOIST OR TO AN ADJOINING STUD OR OTHERWISE PROVIDED WITH LATERAL SUPPORT TO PREVENT ROTATION.
- WATER-RESISTIVE BARRIER SHALL BE PROVIDED OVER ALL EXTERIOR WALLS. ONE LAYER OF (2) 1/2" POLYESTER FELT OR ANY OTHER BARRIER THAT MEETS ASTM D226 TYPE 1 FELT. (R703.2)
- WHERE CEILING JOISTS ARE NOT INSTALLED CONNECTED TO THE RAFTERS AT THE TOP PLATE AND/OR WHERE CEILING JOISTS ARE NOT INSTALLED PARALLEL TO THE RAFTERS, RAFTER TIES SHALL BE INSTALLED IN THE LOWER 1/3 OF THE ATTIC SPACE AND IN CONFORMANCE WITH TABLE 1-S1.
- COLLAR TIES SHALL BE PROVIDED IN THE UPPER 1/3 OF THE ATTIC SPACE IN ACCORDANCE WITH TABLE 1-S1.0.

## GARAGE

- THE GARAGE FLOOR SHALL SLOPE TOWARDS THE GARAGE DOORWAYS.
- DOORS BETWEEN THE GARAGE AND THE DWELLING - MINIMUM 1-3/8" SOLID CORE OR HONEY COMBED STEEL DOOR OR 20-MINUTE FIRE RATED.
- THE GARAGE SHALL BE SEPARATED FROM THE RESIDENCE AND ITS ATTIC AREA BY 5/8", TYPE X GYPSUM BOARD, OR EQUIVALENT MATERIALS APPROVED FOR ONE-HOUR FIRE-RESISTIVE CONSTRUCTION, APPLIED TO GARAGE SIDE.
- WHERE THE SEPARATION IS A FLOOR-CEILING ASSEMBLY, THE STRUCTURE SUPPORTING THE SEPARATION SHALL ALSO BE PROTECTED BY 5/8", TYPE X GYPSUM BOARD, OR MATERIALS APPROVED FOR ONE-HOUR FIRE-RESISTIVE CONSTRUCTION OR EQUIVALENT, APPLIED TO THE GARAGE SIDE. PULL DOWN STAIRS LOCATED WITHIN GARAGE SHALL BE RATED TO BE ADEQUATELY PROTECTED WITH MATERIALS APPROVED FOR ONE-HOUR FIRE-RESISTIVE CONSTRUCTION. ATTIC ACCESS PANELS LOCATED WITHIN GARAGE SHALL BE OF 5/8", TYPE X GYPSUM BOARD, OR MATERIALS FOR ONE-HOUR FIRE-RESISTIVE CONSTRUCTION.
- GARAGE DOOR AND FRAME- THE H-FRAME FOR THE ATTACHMENT OF THE TRACK AND COUNTER BALANCE SHALL CONSIST OF THE FOLLOWING: 2x6 VERTICAL JAMBS RUNNING FROM THE FLOOR TO CEILING ATTACHED WITH 1-3/4" x 0.120" NAILS AT 7" OC STAGGERED WITH (7) 3-1/4" x 0.120" NAILS THRU THE JAMB INTO THE HEADER, MINIMUM 2x8 HEADER FOR ATTACHMENT OF COUNTER BALANCE SYSTEM.
- SELF-CLOSING DEVICES SHALL BE INSTALLED FOR GARAGE AND/OR DWELLING SEPARATION DOORS PER R302.6.1.

## STAIRWAYS

- STAIRWAYS SHALL PROVIDE A MAXIMUM 7-3/4" RISE AND MINIMUM 10" RUN.
- PROVIDE MINIMUM 36" GUARDRAILS ON THE OPEN SIDES OF RAISED FLOORS, PORCHES, AND BALCONIES. MINIMUM 34" GUARDRAILS ON THE OPEN SIDES OF STAIRWAYS LOCATED MORE THAN 30" ABOVE THE FLOOR OR GRADE BELOW. GUARDRAIL ENCLOSURES SHALL HAVE INTERMEDIATE RAILS OR ORNAMENTAL PATTERNS THAT DO NOT ALLOW PASSAGE OF A SPHERE 4" IN DIAMETER.
- EACH STAIRWAY OF THREE OR MORE RISERS SHALL PROVIDE A CONTINUOUS HANDRAIL ON AT LEAST ONE SIDE BETWEEN 34" AND 38" ABOVE THE NOSING OF THE TREADS.
- HANDRAILS SHALL HAVE A CIRCULAR CROSS SECTION OF 1-1/4" MINIMUM TO 2" MAXIMUM OR OTHER APPROVED GRASPABLE SHAPER PER IRC SECTION 311.7.8.5.
- PROVIDE A MINIMUM 6'-8" OF HEADROOM CLEARANCE IN STAIRWAYS.
- ENCLOSED ACCESSIBLE SPACE UNDER STAIRWAYS SHALL HAVE WALLS AND THE UNDERSIDE OF THE STAIR AND LANDING PROTECTED WITH 1/2" GYPSUM BOARD ON ENCLOSURE SIDE PER IRC SECTION 302.7.
- SPIRAL STAIRS TO BE CONSTRUCTED PER IRC SECTION 311.7.10.1.
- SPACE STRINGERS AT 16" OC MAX.

## GENERAL

- PLANS SHALL COMPLY WITH THE 2018 INTERNATIONAL RESIDENTIAL CODE WITH AMENDMENTS AS ADOPTED BY THE GOVERNING JURISDICTION. IF ANY CHANGES OR DEVIATIONS FROM THE PLANS ARE MADE DURING CONSTRUCTION, CONTRACTOR SHALL NOTIFY THE APPROPRIATE AUTHORITY AND ENGINEER OF RECORD, EITHER (OR BOTH) OF WHOM MAY REQUIRE REVISED DRAWINGS OR CALCULATIONS AT ITS DISCRETION.
- REPRODUCTION, ALTERATION, OR RE-USE BY ANY METHOD OF ALL OR PORTIONS OF THESE STRUCTURAL PLANS OR VARIATIONS THEREOF WITHOUT WRITTEN PERMISSION FROM APEX ENGINEERS, INC. IS STRICTLY PROHIBITED. THE DRAWINGS AND DETAILS OF THIS SHEET SET, BEING INSTRUMENTS OF SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF APEX ENGINEERS, INC. AN UNSEALED VERSION OR A VERSION VOID OF APEX ENGINEERS' LOGO AND/OR TITLE BLOCK, SHALL BE CONSIDERED AN UNAUTHORIZED REPRODUCTION.
- WHERE DISCREPANCIES EXIST BETWEEN THE STANDARD COMMENTS, NOTES FROM THE DESIGN PROFESSIONAL OR THE CODE, THE MOST RESTRICTIVE SHALL APPLY. THE DWELLING SHALL COMPLY WITH THE FOLLOWING LOAD CONDITIONS:

AREA	MIN DEAD LOAD	MIN LIVE LOAD
EXTERIOR BALCONIES	10 PSF	60 PSF
DECKS	10 PSF	40 PSF
CEILING JOISTS/ATTICS NO STORAGE - SCUTTLE ACCESS ONLY ROOF SLOPE 3:12 OR LESS	5 PSF	10 PSF
CEILING JOISTS/ATTICS WITHOUT STORAGE - SCUTTLE ACCESS ONLY ROOF SLOPE OVER 3:12 OR LESS	10 PSF	10 PSF
CEILING JOISTS/ATTICS WITH STORAGE - DOOR/PULL DOWN LADDER ACCESS	10 PSF	20 PSF
ROOMS - NON-SLEEPING	10 PSF	40 PSF
ROOMS - SLEEPING	10 PSF	30 PSF
ROOF - LIGHT ROOF COVERING	10 PSF	20 PSF
ROOF - HEAVY ROOF COVERING CONCRETE/TILE/SLATE	20 PSF	20 PSF

NOTE: HEAVY ROOF COVERING WILL NOT BE INSTALLED OR USED IN THE DESIGN CALCULATIONS UNLESS IT IS SPECIFICALLY NOTED ON THE PLANS THAT THE DESIGN IS FOR HEAVY ROOF COVERINGS.

## FOUNDATIONS

- THE FOUNDATION DESIGN SHALL BE BASED ON A MINIMUM SOIL BEARING CAPACITY OF 2000 PSF, UNLESS OTHERWISE INDICATED ON THE PLANS OR IF MODIFIED BY AN ENGINEERING REPORT BASED ON ACTUAL SITE CONDITIONS.
- REFERENCE CONCRETE SCHEDULE, THIS SHEET, FOR APPLICABLE FOUNDATION CONCRETE MIX DESIGNS.
- FOOTINGS SHALL EXTEND BELOW THE FROST LINE; MINIMUM DEPTH 36 INCHES BELOW GRADE.
- UNLESS OTHERWISE NOTED ON THE PLANS OR IF SITE CONDITIONS REQUIRE OTHERWISE, FOOTINGS SHALL BE A MINIMUM OF 16" WIDE AND 8" DEEP WITH (2) #4 BARS CONTINUOUS.
- COLUMN PADS SHALL BE A MINIMUM 30"x30"x12" WITH (4) #4 BARS EACH WAY UNLESS NOTED OTHERWISE.
- UNLESS NOTED OTHERWISE ON THE PLANS, FOUNDATION WALLS SHALL BE MINIMUM 8" THICK X 8'-0" (OR 9'-0") TALL AND REINFORCED PER DETAIL 1-S2.0 (AND 2-S2.0 WHERE APPLICABLE). FOUNDATION WALLS GREATER THAN 10'-0" TALL REQUIRE A SEPARATE ENGINEERED DESIGN. PROVIDE A 2'-0" LONG INTERIOR OR EXTERIOR DEAD-MAN FOR ANY STRAIGHT WALL PANELS EXCEEDING 20'-0" IN LENGTH (REF 3-S2.0).
- REINFORCEMENT SHALL BE MINIMUM GRADE 40 UNLESS NOTED OTHERWISE. REINFORCEMENT SHALL LAP A MINIMUM OF 24" AT ENDS, SPLICES, AND AROUND CORNERS.
- FOUNDATION WALLS SHALL BE BACKFILLED WITH A CLEAN LEAN CLAY (OR BETTER) LOW VOLUME CHANGE MATERIAL. ON-SITE MATERIAL MAY BE USED IF DEEMED ACCEPTABLE BY THE GEOTECHNICAL ENGINEER OF RECORD.
- FOUNDATION WALLS WILL NOT ACHIEVE FULL STRENGTH UNTIL THE BASEMENT FLOOR SLAB AND THE FIRST FLOOR DECK HAVE BEEN PROPERLY PLACED. IF BACKFILLING THE INTERIOR OF THE FOUNDATION WALL WITH GREATER THAN 8" OF EARTHEN FILL OR 24" OF GRANULAR FILL, A STRUCTURAL BASEMENT SLAB, OR ALTERNATE ENGINEERED SOLUTION (I.E. ENGINEERED FILL) WILL BE REQUIRED.
- WHERE JUMPS OR STEPS IN ELEVATION OCCUR FOUNDATION WALLS AND FOOTINGS SHALL BE FORMED CONTINUOUS AND POURED PER DETAIL 4-S2.0.
- CONCRETE FLOOR SLABS SHALL BE A MINIMUM 4" THICK OVER A MINIMUM 4" BASE OF 1/2" OR 3/4" CLEAN GRADED ROCK, UNLESS NOTED OTHERWISE OR IF SITE CONDITIONS REQUIRE OTHERWISE.
- PROVIDE A MINIMUM 4" PERFORATED DRAIN AROUND USABLE SPACE BELOW GRADE OR OTHER EQUIVALENT MATERIALS PER IRC SECTION 405.1. THE PIPE SHALL BE PLACED ON A MINIMUM OF 2" OF WASHED GRAVEL OR CRUSHED ROCK AND COVERED WITH NOT LESS THAN 6" OF THE DRAIN SHALL DAYLIGHT TO THE EXTERIOR BELOW THE FLOOR LEVEL OR TERMINATE IN A MINIMUM 24" DIAMETER OR 20" SQUARE SUMP PIT EXTENDING A MINIMUM 24" BELOW THE BOTTOM OF BASEMENT FLOOR.
- INTERIOR BEARING WALLS AND COLUMNS SHALL BE ISOLATED FROM THE BASEMENT FLOOR SLAB.
- INTERIOR NON-BEARING WALLS, OTHER THAN THOSE RESTING DIRECTLY ON THE FOOTING SHALL BE ISOLATED FROM THE FLOOR FRAMING ABOVE.
- ALL EARTH RETAINING STRUCTURES ON THE SITE GREATER THAN 4'-0" TALL (EXCLUDING CONCRETE FOUNDATION WALLS RESTRAINED AT BOTH TOP AND BOTTOM) SHALL REQUIRE A SEPARATE ENGINEERED DESIGN (I.E. RETAINING WALLS, WING WALLS, ETC.).
- INSULATION SHALL BE INSTALLED FOR ALL BASEMENT WALLS AS REQUIRED PER N1102.2.9.
- A CONCRETE ENCASED GROUNDING ELECTRODE CONNECTION SHALL BE PROVIDED TO THE ELECTRICAL SERVICES PER E3608.1.
- ANY GEOTECHNICAL IMPROVEMENT METHODS AND/OR STRUCTURAL SOLUTIONS (SUCH AS DRILLED PIERS) EMPLOYED TO ADDRESS UNACCEPTABLE SUBGRADE CONDITIONS SHALL BE SUBMITTED TO EOR AS ENGINEERED SHOP DRAWINGS FOR REVIEW AND APPROVAL.

### EXPANSIVE SOILS DISCLAIMER:

THESE PLANS HAVE BEEN PREPARED BASED ON A PRESUMPTIVE ALLOWABLE BEARING CAPACITY AS ALLOWED BY IRC CODE AND THE LOCAL ENFORCING JURISDICTION.

APEX ENGINEERS, INC. (APEX) RECOMMENDS THAT ALL FOOTING EXCAVATIONS BE EVALUATED BY A LICENSED GEOTECHNICAL ENGINEER PRIOR TO THE PLACEMENT OF ANY FOUNDATION ELEMENTS. GEOTECHNICAL INVESTIGATION AND/OR TESTING IS NOT A SERVICE PROVIDED OR OFFERED BY APEX.

APEX HAS NOT BEEN RETAINED TO DETERMINE THE EXPANSIVE SOIL CHARACTERISTICS OF THE SUBGRADE SOIL AND THEREFORE CANNOT BE HELD RESPONSIBLE FOR THE VOLUMETRIC CHANGES OF THE SOIL (INCLUDING BELOW THE BASEMENT SLAB). BY USE OF THESE PLANS WITHOUT AN ACCOMPANYING GEOTECHNICAL ENGINEERING REPORT, APEX SHALL NOT BE HELD LIABLE FOR ANY FUTURE MOVEMENT AND/OR DIFFERENTIAL MOVEMENT OF THE PROPOSED STRUCTURE AND THE POSSIBLE DAMAGE THAT MAY BE CAUSED AS A RESULT OF SUCH MOVEMENT. DAMAGE FROM EXPANSIVE SOILS AND/OR SETTLEMENT CAN RESULT IN AMONGST OTHER THINGS, THE FOLLOWING: BASEMENT SLAB HEAVE, SKEWCRACKS, CRACKS, WINDOWS AND DOOR BECOMING OUT OF PLUMB AND STICKING AND/OR NOT OPENING, DAMAGE TO TILE, MOULDING, AND OTHER COSMETIC FINISHES.



STRUCTURAL DESIGN REVIEW  
KANSAS ENGINEERING LICENSE:  
E-392  
MISSOURI ENGINEERING LICENSE:  
200306673

PROJECT:  
Woodside Ridge - Lot 176  
2083 N.W. Obrien Rd.  
Lee's Summit, Missouri  
CLIENT:  
New Mark Homes

PROJECT #: 23-1964  
DRAWN BY: TDA  
CHECKED BY: BDC  
SUBMITTAL DATE: 2023.12.04

COMMENTS

DATE


#

SHEET:

GENERAL NOTES

S1.0





#### CONCRETE DIMENSIONS

"A"	"B"	"C"	"D"	"E"	"F"	"G"	"H"
8'-0"	1'-4"	4"	8"	4"	8"	7'-6"	20'-0"
9'-0"	1'-4"	4"	8"	4"	8"	8'-6"	20'-0"
10'-0"	1'-8"	5"	10"	5"	10"	9'-6"	20'-0"

#### REINFORCING BARS (GRADE 40 BARS)

"W"	"X"	"Y"	"Z"
(2) #4	2 1/2"	#4 BARS AT 24" OC	#4 BARS AT 24" OC
(2) #4	2 1/2"	#4 BARS AT 24" OC	#4 BARS AT 24" OC
(2) #4	2 1/2"	#4 BARS AT 18" OC	#4 BARS AT 18" OC

##### NOTES:

- DIMENSION SHOWN IS FOR MAXIMUM UNINTERRUPTED WALL PANEL LENGTH BEFORE A DEAD-MAN SHALL BE INSTALLED. NOTE, A MINIMUM 2'-0" RETURN OR OFFSET IN THE FOUNDATION WALL SHALL SUBSTITUTE AS A DEAD-MAN AND/OR BREAK IN THE WALL PANEL LENGTH.
- VERTICAL REINFORCING STEEL TO EXTEND TO WITHIN 8" OF TOP WALL. MINIMUM (1) #4 HORIZONTAL BAR WITHIN 12" OF TOP AND BOTTOM OF WALL.
- BURIED CONCRETE FOUNDATION WALLS UP TO 9'-0" TALL MAY BE 8" NOMINAL THICKNESS WITH #4 BARS AT 24" OC BOTH WAYS OVER 16"x8" CONCRETE FOOTINGS WITH (2) #4 BARS CONTINUOUS, UNLESS OTHERWISE REQUIRED BY ENGINEERING REPORT BASED ON ACTUAL SITE CONDITIONS.
- WALL WILL NOT ACHIEVE FULL STRENGTH UNTIL FIRST FLOOR DECK AND BASEMENT SLAB HAVE BEEN PLACED.

#### 1 TYPICAL FOUNDATION WALL DETAIL


S2.0 3/4" = 1'-0"

#### COLUMN AND PIER PAD SCHEDULE

COLUMN MARK	PAD SIZE	REINFORCING	COL SIZE
A	30"x30"x12"	(4) #4 BARS E-W	3" SCH 40 (3.5" OD)
B	36"x36"x12"	(4) #4 BARS E-W	3" SCH 40 (3.5" OD)
C	42"x42"x12"	(5) #4 BARS E-W	3" SCH 40 (3.5" OD)
D	48"x48"x12"	(6) #4 BARS E-W	3 1/2" SCH 40 (4" OD)
E	54"x54"x16"	(8) #4 BARS E-W	REF PLAN
F	60"x60"x16"	(10) #4 BARS E-W	REF PLAN


##### NOTES:

- COLUMN AND PIER PAD SIZES SHOWN ARE FOR MAXIMUM ADJUSTABLE COLUMN HEIGHT OF 9'-1". REQUIRES SEPARATE ENGINEERED DESIGN IF GREATER THAN 9'-1" TALL. COLUMNS SIZED AS QWIK-ADJUST COLUMN, BY QUALITY WAY PRODUCTS, LLC. REFER TO SAFE LOADING CAPACITIES PER MANUF SPECS, OR SUBSTITUTION TO ANOTHER PRODUCT ONLY WITH PRIOR APPROVAL BY APEX ENGINEERS.
- COLUMN AND PIER PAD SIZES SHOWN ARE BASED ON AN ASSUMED MINIMUM ALLOWABLE SOIL BEARING CAPACITY OF 2,000 PSF.



#### 5 COLUMN PAD DETAIL

S2.0 3/4" = 1'-0"




##### NOTES:

- MIN 3000 PSI FOOTING COMPRESSIVE CONCRETE STRENGTH.
- MIN 3000 PSI WALL COMPRESSIVE CONCRETE STRENGTH.
- AIR ENTRAINED BETWEEN 5% & 7% OF CONCRETE VOLUME.
- GRADE 40 REINFORCING STEEL UNLESS OTHERWISE NOTED.
- LAP SPLICES 24" MIN
- WALL SHALL BE BACK-FILLED WITH CLEAN, LEAN CLAY (OR BETTER) LOW VOLUME CHANGE MATERIAL. ON-SITE MATERIAL MAY BE USED IF DEEMED ACCEPTABLE BY THE GEOTECHNICAL ENGINEER.
- ASSUMED 2,000 PSF BEARING (TO BE VERIFIED BY GEOTECHNICAL ENGINEER).

#### 3 TYPICAL DEAD-MAN SECTION

S2.0 3/4" = 1'-0"



#### CONCRETE DIMENSIONS


"A"	"B"	"C"	"D"	"E"	"F"	"G"	"H"
4'-0"	1'-4"	4"	8"	4"	8"	3'-4"	20'-0"
6'-0"	1'-4"	4"	8"	4"	8"	4'-4"	20'-0"
9'-0"	1'-8"	5"	8"	4"	8"	4'-4"	20'-0"

##### NOTES:

- DIMENSION SHOWN IS FOR MAXIMUM UNINTERRUPTED WALL PANEL LENGTH BEFORE A DEAD-MAN SHALL BE INSTALLED. NOTE, A MINIMUM 2'-0" RETURN OR OFFSET IN THE FOUNDATION WALL SHALL SUBSTITUTE AS A DEAD-MAN AND/OR BREAK IN THE WALL PANEL LENGTH.
- VERTICAL REINFORCING STEEL TO EXTEND TO WITHIN 8" OF TOP WALL. MINIMUM (1) #4 HORIZONTAL BAR WITHIN 12" OF TOP AND BOTTOM OF WALL.
- THE BASEMENT SLAB IS AN INTEGRAL PART OF THE 'UNRESTRAINED' FOUNDATION WALL DESIGN THEREFORE, IF THE WALL IS BACKFILLED PRIOR TO PLACEMENT OF THE BASEMENT SLAB, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROPERLY BRACING THE WALL UNTIL THE BASEMENT SLAB HAS BEEN PLACED.

#### 2 TYPICAL 'UNRESTRAINED' FOUNDATION WALL DETAIL





S2.0 3/4" = 1'-0"



#### 4 FOUNDATION WALL JUMP DETAIL

S2.0 1/2" = 1'-0"







1	TYPICAL STRUCTURAL GARAGE SLAB PLAN
S2.1	3/8" = 1'-0"



	<b>TYPICAL EGRESS WINDOW SECTION DETAIL</b>
<b>S2.1</b>	3/4" = 1'-0"

6	TYPICAL OVERDIG DETAIL AT BASEMENT SLAB
S2.1	3/4" = 1'-0"




2	STRUCTURAL GARAGE SLAB PIER PAD DETAIL
S2.1	3/4" = 1'-0"

3	STRUCTURAL GARAGE SLAB/WALL SECTION
S2.1	3/4" = 1'-0"




<b>9</b>	<b>POUR STOP DETAIL</b>
<b>S2.1</b>	3/4" = 1'-0"


<b>10</b>	<b>GARAGE SLAB BEARING</b>
<b>S2.1</b>	3/4" = 1'-0"



<b>11</b>	<b>GARAGE SLAB BEAM BEARING</b>
<b>S2.1</b>	3/4" = 1'-0"



PIER SCHEDULE		
COLUMN MARK	COL SIZE	PIER DIAMETER
G	PER PLAN	12"
H	PER PLAN	16"
J	PER PLAN	18"
K	PER PLAN	24"
L	PER PLAN	28"





NOTE: ALL CONC. PIERS SHALL BE  
DRILLED MIN 36" DEEP TO  
COMPETENT  
ORIGINAL SOIL WITH MIN 2,000 PSF  
BEARING CAPACITY (TYP UNO)

7	SUSPENDED PORCH STOOP DETAIL
S2.1	3/4" = 1'-0"

**8 | POST BASE DETAIL**


---

**S2.1**  $3/4" = 1'-0"$



12	POUR STOP DETAIL
63.4	3.15" - 4.00"

13	GARAGE SLAB BEAM BEARING
----	--------------------------



14	CONCRETE HEADER DETAIL
----	------------------------

<b>SZ.1</b>	$\frac{3}{4}" = 1'-0"$	<b>SZ.1</b>	$\frac{3}{4}" = 1'-0"$
<b>STEEL DECKING NOTES:</b>			
<ul style="list-style-type: none"> <li>MINIMUM 1-1/2" BEARING</li> <li>FASTEN TO SUPPORT STEEL WITH 5/8" VISIBLE PUDDLE WELDS AT EDGE RIBS AND 12" CENTERS ALONG END BEARING</li> <li>FASTEN SIDE LAPS AND PERIMETER EDGES AT 36" CENTERS WITH #10 TEK SCREWS OR 5/8" PUDDLE WELDS</li> <li>MAX UNINSUPPORTED CONSTRUCTION SPAN 6'-0", UN ON PLAYS BY APEX</li> </ul>			






TABLE R602.3 (5) - SIZE, HEIGHT, AND SPACING OF WOOD STUDS*				
STUD SIZE (IN)	LATERALLY UNSUPPORTED STUD HEIGHT*	STRUCTURE SUPPORTED		
		ROOF ONLY	ROOF AND (1) FLOOR	ROOF AND (2) FLOORS
2x4	10 FEET	24" OC*	16" OC*	N/A
2x6	10 FEET	24" OC	24" OC	16" OC



A. LISTED HEIGHTS ARE DISTANCES BETWEEN POINTS OF LATERAL SUPPORT PLACED PERPENDICULAR TO THE PLANE OF THE WALL. BEARING WALLS SHALL BE SHEATHED ON NOT LESS THAN ONE SIDE OR BRIDGING SHALL BE INSTALLED NOT GREATER THAN 4 FEET APART MEASURED VERTICALLY FROM EITHER END OF THE STUD. INCREASES IN UNSUPPORTED HEIGHT ARE PERMITTED WHERE IN THE COMPLIANCE WITH EXCEPTION 2 OF SECTION R602.3.1 OR DESIGNED IN ACCORDANCE WITH ACCEPTED ENGINEERING PRACTICE.

B. A HABITABLE ATTIC ASSEMBLY SUPPORTED BY 2x4 STUDS IS LIMITED TO A ROOF SPAN OF 32 FEET. WHERE THE ROOF SPAN EXCEEDS 32 FEET, THE WALL STUDS SHALL BE INCREASED TO 2x6 OR THE STUDS SHALL BE DESIGNED IN ACCORDANCE WITH ACCEPTED ENGINEERING PRACTICE.


TABLE R602.3 (6) - ALTERNATE WOOD BEARING WALL STUD SIZE, HEIGHT AND SPACING				
ULTIMATE DESIGN WIND SPEED = 115 MPH				
STUD HEIGHT	SUPPORTING	STUD SPACING,	MAX ROOF/FLOOR SPAN,	
			12 FEET	24 FEET
11 FEET	ROOF ONLY	12 IN	2x4	2x4
		16 IN	2x4	2x4
	ROOF AND ONE FLOOR	24 IN	2x6	2x6
		12 IN	2x4	2x6
12 FEET	ROOF ONLY	12 IN	2x4	2x4
		16 IN	2x4	2x6
	ROOF AND ONE FLOOR	24 IN	2x6	2x6
		12 IN	2x4	2x6

A. WALL STUDS NOT EXCEEDING 16" OC SHALL BE SHEATHED WITH MINIMUM 1/2" GYPSUM BOARD ON THE INTERIOR AND 3/8" WOOD STRUCTURAL PANEL SHEATHING ON THE EXTERIOR. WOOD STRUCTURAL PANEL SHEATHING SHALL BE ATTACHED WITH 8d (2.5" x 0.131") NAILS NOT GREATER THAN 6" OC ALONG PANEL EDGES AND 12" OC AT INTERMEDIATE SUPPORTS, AND ALL PANEL JOINTS SHALL OCCUR OVER STUDS OR BLOCKING.


B. THE MAXIMUM SPAN IS APPLICABLE TO BOTH SINGLE AND MULTIPLE SPAN ROOF AND FLOOR CONDITIONS. THE ROOF ASSEMBLY SHALL NOT CONTAIN A HABITABLE ATTIC.




10 TYPICAL STAIR/RAIL DETAIL  
S3.0 3/4" = 1'-0"




9 UPSET STEEL BEAM/JOIST CONNECTION  
S3.0 1 1/2" = 1'-0"



8 LEDGER FASTENER PLACEMENT  
S3.0 1 1/2" = 1'-0"




7 TYPICAL CANTILEVER FRAMING WITH DECK ATTACHMENT  
S3.0 3/4" = 1'-0"




DECK LEDGER ATTACHMENT CHART		
DECK JOIST SPAN	1/2" DIA LAG SPACING	EQUIVALENT SPACING FOR 16" OC JOIST BAYS
UP TO 10'-0"	16" OC	N/A
10'-1" TO 12'-0"	15" OC	16" OC DBL EVERY OTHER
12'-1" TO 14'-0"	13" OC	16" OC DBL EVERY OTHER
14'-1" TO 16'-0"	11" OC	16" OC DBL EVERY JOIST BAY
16'-1" TO 18'-0"	10" OC	16" OC DBL EVERY JOIST BAY

NOTE: CHART IS APPLICABLE ONLY WHEN DECK IS SHOWN ON APPROVED PLAN.


6 TYPICAL LEDGER ATTACHMENT  
S3.0 3/4" = 1'-0"




5 TYPICAL LEDGER BOLT SPACING  
S3.0 3/4" = 1'-0"




4 SPLICED DECK COLUMN CONNECTION  
S3.0 1 1/2" = 1'-0"



3 SPLICED DECK COLUMN CONNECTION  
S3.0 1 1/2" = 1'-0"




2 DECK BEAM/COLUMN CONNECTION  
S3.0 1 1/2" = 1'-0"




1 DECK BEAM/COLUMN CORNER CONDITION  
S3.0 3/4" = 1'-0"






12 | RIDGE BEAM DETAIL  
S3.1 | 3/4" = 1'-0"




11 | TYPICAL WOOD HEADER DETAIL  
S3.1 | NOT TO SCALE

2 - PLY	3 - PLY	4 - PLY
(3) ROWS OF 16d x 3-1/2" NAILS AT 6" OC	(3) ROWS OF 16d x 3-1/2" NAILS AT 4" OC	(2) ROWS OF 1/2" DIA. A307 THRU-BOLTS AT 12" OC STAGGERED
NOTES: 1. NAILING SHOWN APPLIES UNLESS SPECIFICALLY NOTED IN DETAILS. 2. SPACE NAILS EVENLY THROUGHOUT DEPTH OF BEAM.		


10 | MULTIPLE PLY BEAM NAILING SCHEDULE  
S3.1 | NOT TO SCALE




9 | WOOD PLATE TO STEEL BEAM CONNECTION  
S3.1 | 1 1/2" = 1'-0"




8 | FLUSH STEEL BEAM CONNECTION  
S3.1 | 1 1/2" = 1'-0"



7 | FLUSH WOOD BEAM CONNECTION  
S3.1 | 1 1/2" = 1'-0"



6 | ROOF SUPPORTING BEAM HOLD DOWN  
S3.1 | 3/4" = 1'-0" (COMPLIANCE WITH IRC R802.11)



ALTERNATE FOR OBLONG BORED HOLES


WALL SIZE	BORED HOLE SIZE		WALL NOTCH	
	STUDS LOAD BEARING OR EXTERIOR WALL	NON LOAD BEARING WALL	LOAD BEARING WALL	NON LOAD BEARING WALL
2x4	1 3/8"	2 1/8"	7/8"	1 3/8"
(2) 2x4	-	2 1/8"	7/8"	1 3/8"
2x6	2 1/4"	3 5/16"	1 3/8"	2 1/4"
(2) 2x6	-	3 5/16"	1 3/8"	2 1/4"
2x8	2 7/8"	4 3/8"	1 13/16"	2 7/8"
(2) 2x8	-	4 3/8"	1 13/16"	2 7/8"

PLATES:  
TOP AND BOTTOM PLATE HOLE, CUT OR NOTCH THAT IS 50% MORE OF WIDTH MUST BE REPAIRED USING 16 GA (MIN) METAL TIE THAT IS AT LEAST 1-1/2" WIDE IF WALL IS A SHEAR WALL IT MUST BE REPAIRED USING HARDY FRAME SADDLE (HFS).


NOTE:  
SEE SECTION R602.6 AND FIGURES R602.6.1 AND R602.6.2

WALL SIZE	HOLE SIZE	VERTICAL HOLE SIZE (H)
2x4	1 3/4"	D+1/2" AT Lvl 1&2
2x6	2 3/4"	D+1" AT Lvl 3
2x8	3 5/8"	D+1 1/4" AT Lvl 4
		D+1 1/2" AT Lvl 5

5 | DRILLING & NOTCHING DETAIL  
S3.1 | 3/4" = 1'-0"




4 | FLUSH STEEL BEAM TO STEEL BEAM  
S3.1 | 1 1/2" = 1'-0"




3 | BEAM TO GIRDER CONNECTION  
S3.1 | 1 1/2" = 1'-0"

BEAM CONNECTION SCHEDULE		
BEAM SIZE	# OF BOLTS "N"	# OF BOLTS "M"
W8, W10	2	4
W12, W14	3	6
W16, W18	4	8
NOTES: 1. THESE CONNECTIONS ARE TYPICAL, UNO. 2. NUMBER OF BOLTS IN UPSET BEAM CONNECTIONS DETERMINED BY SMALLER OF TWO BEAMS AT CONNECTION. 3. ALL AROUND 1/4" FILLET WELD MAY BE SUBSTITUTED FOR EITHER BOLTED CONNECTION. 4. ALL BOLTS, 3/4" DIAMETER, A325-N, UNO.		




2 | BEAM SPLICE DETAIL  
S3.1 | 1 1/2" = 1'-0"




NOTES:  
1. EACH 2x PLY SHALL BE FASTENED WITH (1) ROW OF 10d NAILS AT 9" OC, ALTERNATING SIDE TO SIDE.  
2. 1.4" MIN EDGE DISTANCE, AND STARTING 2 1/2" FROM EACH END.  
3. EXTEND FULL AREA OF COLUMN AS SOLID BLOCKING THROUGH JOIST BAYS AND WALLS TO LOAD-BEARING BEAM/WALL BELOW

1 | BUILT-UP STUD COLUMN  
S3.1 | 1 1/2" = 1'-0"









SECTION

FASTEN KING STUD  
TO HEADER WITH (8)  
16d SINKER NAILS

FASTEN TOP PLATE TO  
HEADER WITH TWO  
ROWS OF 16d SINKER  
NAILS AT 3" OC, TYP

MIN 7/16" WOOD  
STRUCTURAL PANEL  
SHEATHING

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER

FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/2" DIA. ANCHOR BOLT WITH 2"x2"x3/16"  
PLATE WASHER 7" MIN EMBEDMENT, TYP.

CONCRETE FOUNDATION WITH MIN  
(1) #4 BAR AT TOP AND BOTTOM OF  
FOOTING. LAP BARS MIN 15"

10'-0" MAX. HEIGHT

12'-0" MAX TOTAL WALL HEIGHT

PONY WALL  
HEIGHT

IF NEEDED, PANEL SPLICE  
EDGES SHALL OCCUR  
OVER AND BE NAILED TO  
COMMON BLOCKING  
WITHIN THE MIDDLE 24" OF  
THE PORTAL-LEG HEIGHT.  
ONE ROW OF 3" OC NAILING  
IS REQUIRED IN EACH  
PANEL EDGE.

TYPICAL PORTAL  
FRAME  
CONSTRUCTION

(2) 2x4 STUDS MIN

TYPICAL BRACED  
WALL SEGMENT

TOP PLATE CONTINUITY  
REQUIRED

TENSION STRAP OPPOSITE  
SHEATHING, PER TABLE R602.10.6.4  
(THIS SHEET)

3"x11 1/4" NET HEADER


FASTEN SHEATHING TO HEADER WITH 8d  
COMMON OR GALVANIZED BOX NAILS IN 3"  
GRID PATTERN AS SHOWN & 3" OC IN ALL FRAMING  
(STUDS, BLOCKING, AND SILLS) TYP

MIN 2x4 FRAMING

7/16" MIN THICKNESS WOOD  
STRUCTURAL PANEL SHEATHING

1/






**BRACED WALL PANEL  
CONNECTION WHEN  
PERPENDICULAR TO  
FLOOR/CEILING FRAMING**

S4.1

3/4\" = 1'-0"



**BRACED WALL PANEL  
CONNECTION WHEN PARALLEL  
TO FLOOR/CEILING FRAMING**

S4.1

3/4\" = 1'-0"


**CONT. SHEATHED BRACED WALL END CONDITIONS**

END CONDITION 1	END CONDITION 2
END CONDITION 3	END CONDITION 4
END CONDITION 5	REQUIREMENTS
	<p><b>RETURN PANEL:</b> 24\" FOR BRACED WALL LINE SHEATHED WITH WOOD STRUCTURAL PANELS. 32\" FOR BRACED WALL LINES SHEATHED WITH STRUCTURAL FIBERBOARD.</p> <p><b>DISTANCE D:</b> 24\" FOR BRACED WALL LINES SHEATHED WITH WOOD STRUCTURAL PANELS. 32\" FOR BRACED WALL LINES SHEATHED WITH STRUCTURAL FIBERBOARD.</p> <p><b>HOLD-DOWN DEVICE:</b> 800 LBS CAPACITY FASTENED TO THE EDGE OF THE BRACED WALL PANEL CLOSEST TO THE CORNER AND TO THE FOUNDATION OR FLOOR FRAMING BELOW</p>


**CONTINUOUS SHEATHED BRACED  
WALL END CONDITIONS**

S4.1

NOT TO SCALE. (COMPLIANCE WITH IRC R602.10.7)




**OVER CONCRETE OR MASONRY BLOCK FOUNDATION**



**OVER RAISE WOOD FLOOR - FRAMING ANCHOR OPTION**

(WHEN PORTAL SHEATHING DOES NOT LAP OVER BAND OR RIM JOIST)



**OVER RAISE WOOD FLOOR - OVERLAP OPTION**

(WHEN PORTAL SHEATHING LAPS OVER BAND OR RIMBOARD)

**BRACED WALL PANEL-IRC  
METHOD CS-PF CONTINUOUSLY  
SHEATHED PORTAL FRAME  
1 PANEL CONSTRUCTION**

S4.1

3/4\" = 1'-0"

(PER IRC R602.10.6.4)