




LEFT ELEVATION
1/8" = 1'-0"



REAR ELEVATION
1/8" = 1'-0"



RIGHT ELEVATION
1/8" = 1'-0"



FRONT ELEVATION
1/4" = 1'-0"



NOTE: DESIGN AND CONSTRUCTION SHALL CONFORM TO 2018 IRC.
ASSUMED SOIL BEARINGS PRESSURE = 1500 PSF.

BUILDING ADDRESS: 1404 NE Ernest Way
Lees Summit MO 64086


CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS AND JOB SITE CONDITIONS PRIOR TO CONSTRUCTION.

NOTE: THE CONTRACTOR IS RESPONSIBLE TO INSURE THAT THIS STRUCTURE IS BUILT IN STRICT COMPLIANCE WITH ALL GOVERNING CODES (COUNTY, STATE, & FED.) ALL CONSTRUCTION TO MEET 2018 IRC AND LOCAL BUILDING PRACTICES. ANY DEVIATION FROM PLANS MUST BE APPROVED BY OWNER PRIOR TO EXECUTION. FOLEY CAD SERVICES OR AFFILIATES OR ASSIGNS SHALL NOT BE LIABLE FOR STRUCTURAL DESIGN OR FUNCTION OF THESE HOUSE PLANS.

FOLEY CAD SERVICES, LLC	
PHONE: (816) 318-3973	"NOT A REGISTERED ARCHITECT"
PLAN: MEDLIN	DATE: 12/26/2023
	PAGE: 1 OF 4

COLUMN MARK	PAD SIZE	REINFORCEMENT	COLUMN SIZE	COLUMN TYPE
△	30" x 30" x 12"	(4) #4 BAR E.W.	3" DIA.	SCHEDULE 40 STEEL PIER #3 (F _y = 36 ksi MIN.)
△	36" x 36" x 12"	(4) #4 BAR E.W.	PER PLAN	
△	42" x 42" x 12"	(5) #4 BAR E.W.	PER PLAN	
△	48" x 48" x 12"	(6) #4 BAR E.W.	3" DIA.	
△	54" x 54" x 16"	(8) #4 BAR E.W.	3 1/2" DIA.	
△	60" x 60" x 16"	(10) #4 BAR E.W.	3 1/2" DIA.	

1. COLUMN & PAD SIZES SHOWN ARE FOR MAXIMUM COLUMN HEIGHT OF 10'-0". REQUIRES SEPARATE ENGRD DESIGN IF GREATER THAN 10'-0" TALL.
 2. COLUMN & PIER PAD SIZES SHOWN ARE BASED ON AN ASSUMED MINIMUM ALLOWABLE SOIL BEARING CAPACITY OF 2,000PSF.



- ⊙ = GYPSUM BOARD
- ⊙ = PORTAL FRAME GARAGE
- ⊙ = WOOD STRUCTURAL PANEL

BASEMENT
 1/4" = 1'-0" 1068 FINISHED SQ. FT.



STRUCTURAL NOTES:
 - ALL UNMARKED HEADERS MIN (2)#2 X 10
 - ALL HEADERS AND BEAMS MIN #2 GRADE DF/L (OR EQ.)
 - BEARING WALL


BUILDING ADDRESS: 1404 NE Ernest Way
 Lees Summit MO 64086

FOLEY CAD SERVICES, LLC

PHONE: (816) 318-3973 "NOT A REGISTERED ARCHITECT"
 PLAN: MEDLIN DATE: 12/26/2023 PAGE: 2 OF 4


CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS AND JOB SITE CONDITIONS PRIOR TO CONSTRUCTION.

NOTE: THE CONTRACTOR IS RESPONSIBLE TO INSURE THAT THIS STRUCTURE IS BUILT IN STRICT COMPLIANCE WITH ALL GOVERNING CODES (COUNTY, STATE, & FED.) ALL CONSTRUCTION TO MEET 2018 IRC AND LOCAL BUILDING PRACTICES. ANY DEVIATION FROM PLANS MUST BE APPROVED BY OWNER PRIOR TO EXECUTION. FOLEY CAD SERVICES OR AFFILIATES OR ASSIGNS SHALL NOT BE LIABLE FOR STRUCTURAL DESIGN OR FUNCTION OF THESE HOUSE PLANS.



- ⊙ GB = GYPSUM BOARD
- ⊙ PFG = PORTAL FRAME GARAGE
- ⊙ WSP = WOOD STRUCTURAL PANEL

MAIN LEVEL
1/4" = 1'-0" 1216 SQ. FT.



STRUCTURAL NOTES:
 - ALL UNMARKED HEADERS MIN (2)#2-2x10
 - ALL HEADERS AND BEAMS MIN #2 GRADE DF/L (OR EQ.)
 - BEARING WALL

MAIN LEVEL: 1216 FINISHED
BASEMENT: 1068 FINISHED
FRONT PORCH: 226 SQ. FT.
COVERED DECK: 336 SQ. FT.
UNFINISHED STORAGE GARAGE: 227 SQ. FT. - GARAGE TOTAL: 802 SQ. FT.
UNFINISHED SPACE UNDER SUSPENDED GARAGE SLAB: 770 SQ. FT.
UNFINISHED SPACE UNDER SUSPENDED GARAGE SLAB: 770 SQ. FT.


BUILDING ADDRESS: 1404 NE Ernest Way
Lees Summit MO 64086

FOLEY CAD SERVICES, LLC


PHONE: (816) 318-3973 "NOT A REGISTERED ARCHITECT"
 PLAN: MEDLIN DATE: 12/26/2023 PAGE: 3 OF 4

CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS AND JOB SITE CONDITIONS PRIOR TO CONSTRUCTION.


NOTE: THE CONTRACTOR IS RESPONSIBLE TO INSURE THAT THIS STRUCTURE IS BUILT IN STRICT COMPLIANCE WITH ALL GOVERNING CODES (COUNTY, STATE, & FED.) ALL CONSTRUCTION TO MEET 2018 IRC AND LOCAL BUILDING PRACTICES. ANY DEVIATION FROM PLANS MUST BE APPROVED BY OWNER PRIOR TO EXECUTION. FOLEY CAD SERVICES OR AFFILIATES OR ASSIGNS SHALL NOT BE LIABLE FOR STRUCTURAL DESIGN OR FUNCTION OF THESE HOUSE PLANS.



OVER CONCRETE OR MASONRY BLOCK FOUNDATION




OVER RAISED WOOD FLOOR - FRAMING ANCHOR OPTION (WHEN PORTAL SHEATHING DOES NOT LAP OVER BAND OR RIM JOIST)



OVER RAISED WOOD FLOOR - OVERLAP OPTION (WHEN PORTAL SHEATHING LAPS OVER BAND OR RIM JOIST)

3 METHOD CS-PF CONT SHEATHED PORTAL FRAME PANEL (R602.10.6.4)

SCALE: 1" = 1'-0"



4 INTERIOR BRACED WALL (LIB)


SCALE: N.T.S.

METHOD	WALL LENGTH PER PORTAL HEADER HEIGHT					
	8 FEET	9 FEET	10 FEET	11 FEET	12 FEET	
PFH	SUPPORTING ROOF ONLY	16"	16"	16"	(c)	(c)
	SUPPORTING ONE STORY AND ROOF	24"	24"	24"	(c)	(c)
PFG		24"	27"	30"	(d)	(d)
CS-PF	SEISMIC DESIGN CATEGORY A, B, C	16"	18"	20"	(e)	(e)
	SEISMIC DESIGN CATEGORY D ₁ , D ₂ , D ₃	16"	18"	20"	(e)	(e)

- (c) MAXIMUM HEADER HEIGHT FOR PFH IS 10 FEET IN ACCORDANCE WITH FIGURE R602.10.6.2, BUT WALL HEIGHT MAY BE INCREASED TO 12 FEET WITH PONY WALL.
- (d) MAXIMUM HEADER HEIGHT FOR PFG IS 10 FEET IN ACCORDANCE WITH FIGURE R602.10.6.3, BUT WALL HEIGHT MAY BE INCREASED TO 12 FEET WITH PONY WALL.
- (e) MAXIMUM HEADER HEIGHT FOR CS-PF IS 10 FEET IN ACCORDANCE WITH FIGURE R602.10.4, BUT WALL HEIGHT MAY BE INCREASED TO 12 FEET WITH PONY WALL.


INTERIOR BRACED WALL SCHEDULE

SIMPSON MODEL NO.	STRAP LENGTH	WALL DIM'S HEIGHT x WIDTH	ANGLE FROM HORIZONTAL	FASTENERS	
				PLATES	EA STUD
WB106	9'-5 5/8"	8'-0" x 5'-0"	60°	(2) 16d	(1) 8d
WB126	11'-4 3/8"	8'-0" x 8'-0"	45°	(2) 16d	(1) 8d
WB106C	9'-6"	8'-0" x 5'-0"	60°	(2) 16d	(1) 8d
WB126C	11'-4 13/16"	8'-0" x 8'-0"	45°	(2) 16d	(1) 8d
WB143C	14'-3"	10'-0" x 10'-0"	45°	(2) 16d	(1) 8d



1 PFH-PORTAL FRAME WITH HOLD-DOWNS (R602.10.6.2)

SCALE: 1" = 1'-0"



2 PORTAL FRAME AT GARAGE (PFG - R602.10.6.3)

SCALE: 1" = 1'-0"

COPYRIGHT 2023 BY SDC ENGINEERING, INC. DRAWINGS MAY NOT BE DUPLICATED WITHOUT WRITTEN PERMISSION.

THIS DRAWING HAS BEEN DEVELOPED BY SDC ENGINEERING, INC. EXCLUSIVELY FOR MR. MEDLIN FOR THE PROJECT LISTED IN THIS TITLE BLOCK. ANY OTHER UNAUTHORIZED USE IS PROHIBITED.



ENGINEERING, INC.
Consulting Structural and Civil Engineers
5907 Raytown Trafficway
Raytown, Missouri 64133
816-356-1445



DATE:	12/14/23
REVISION	
1	
2	
3	
4	

DWG. 5


MINIMUM LENGTH OF CS-WSP BRACED WALL PANELS					
ADJACENT CLEAR OPENING HEIGHT	WALL HEIGHT				
	8'	9'	10'	11'	12'
<64"	24"	27"	30"	33"	36"
68"	26"	27"	30"	33"	36"
72"	27"	27"	30"	33"	36"
76"	30"	29"	30"	33"	36"
80"	32"	30"	30"	33"	36"
84"	35"	32"	32"	33"	36"
88"	38"	35"	33"	33"	36"
92"	43"	37"	35"	35"	36"
96"	48"	41"	38"	36"	36"
100"		44"	40"	38"	38"
104"		49"	43"	40"	39"
108"		54"	46"	43"	41"
112"			50"	45"	43"
116"			55"	48"	45"
120"			60"	52"	48"
124"				56"	51"
128"				61"	54"
132"				66"	58"
136"					62"
140"					66"
144"					72"

REF. TABLE R602.10.5

NOTE: BRACED WALL PANELS MUST COVER 3 STUD SPACES MINIMUM WHEN STUDS ARE AT 16" ON CENTER OR COVER 2 STUD SPACES MINIMUM WHEN STUDS ARE AT 24" ON CENTER.

MINIMUM PANEL THICKNESS = 3/8" AT 16" STUD SPACING, 7/16" AT 24" STUD SPACING.

REF. TABLES R602.3(3) AND R602.10.4.



ALL PANEL EDGES MUST BE SUPPORTED BY THE USE OF BLOCKING WITH A MINIMUM THICKNESS OF 1-1/2".

6d NAILS @ 6" O.C. AT PANEL EDGES AND @ 12" O.C. IN FIELD AT 16" STUD SPACING. 8d NAILS @ 6" O.C. AT PANEL EDGES AND @ 12" O.C. IN FIELD AT 24" STUD SPACING.

WSP SHEAR PANEL BRACING DETAIL
N.T.S.

MINIMUM LENGTH OF WSP BRACED WALL PANELS				
WALL HEIGHT				
8'	9'	10'	11'	12'
48"	48"	48"	53"	58"


REF. TABLE R602.10.5

REQUIREMENTS

RETURN PANEL:
24" FOR BRACED WALL LINES SHEATHED WITH WOOD STRUCTURAL PANELS
32" FOR BRACED WALL LINES SHEATHED WITH STRUCTURAL FIBERBOARD

DISTANCE D:
24" FOR BRACED WALL LINES SHEATHED WITH WOOD STRUCTURAL PANELS
32" FOR BRACED WALL LINES SHEATHED WITH STRUCTURAL FIBERBOARD

HOLD-DOWN DEVICE:
800 lbs CAPACITY FASTENED TO THE EDGE OF THE BRACED WALL PANEL CLOSEST TO THE CORNER AND TO THE FOUNDATION OR FLOOR FRAMING BELOW



1 END CONDITIONS FOR BRACED WALL LINES WITH CONTINUOUS SHEATHING R602.10.7

SCALE: NTS



ENGINEERING, INC.
Consulting Structural and Civil Engineers
5907 Raytown Trafficway
Raytown, Missouri 64133
816-356-1445



DATE:	12/14/23
REVISION	
1	
2	
3	
4	

CHAPTER 11 MANDATORY PROVISIONS	
IRC CODE REFERENCE	DESCRIPTION
N1101.14	REQUIRES POSTING A PERMANENT CERTIFICATE THAT LISTS THE ENERGY EFFICIENT COMPONENTS INSTALLED AND CONSTRUCTED IN THE HOUSE.
N1102.4	REQUIRES THAT AN AIR LEAKAGE TEST (BLOWER DOOR) BE CONDUCTED, VERIFYING THE HOUSE ACHIEVES 3 AIR CHANGES PER HOUR OR LESS LEAKAGE.
N1103.1.1	REQUIRES THAT EACH HVAC SYSTEM BE PROVIDED WITH A PROGRAMMABLE THERMOSTAT.
N1103.1.2	REQUIRES THAT HEAT PUMPS MEET SUPPLEMENTARY ELECTRIC HEAT ENERGY EFFICIENCY REQUIREMENTS
N1103.3.2	REQUIRES THAT DUCTS, AIR HANDLERS AND FILTER BOXES JOINTS AND SEAMS BE SEALED.
N1103.6	REQUIRES MECHANICAL VENTILATION SYSTEMS TO MEET MINIMUM EFFICIENCY REQUIREMENTS.
N1103.10	REQUIRES POOLS AND SPAS TO MEET MINIMUM ENERGY EFFICIENCY LEVELS.

NAILING SCHEDULE		
DESCRIPTION OF BLDG. ELEMENTS	# AND NAIL TYPE	SPACING
SOLE PLATE TO JOIST	16d	16" O. C.
SOLE PLATE TO STUD, END NAIL	2-16d	-
DOUBLE STUDS, FACE NAIL	10d	24" O. C.
DOUBLE TOP PLATES, FACE NAIL	10d	24" O. C.
RIM JOIST- TOP PLATES, TOE NAIL	8d	6" O. C.
CLG. JOIST TO PLATE, TOE NAIL	3-8d	-
RAFTER TO PLATE, TOE NAIL	2-16d	-
RAFTER TO RIDGE, VALLEY OR HIP		
TOE NAIL	4-16d	-
FACE NAIL	3-16d	-

DWELLING MUST MEET OR EXCEED THE MINIMUM REQUIREMENTS OF 2018 IRC TABLE N1102.1.2.

TABLE N1102.1.2 ALTERNATE INSULATION VALUES (WINDOW AREA NOT LIMITED)			
CEILING R-VALUE	R-49	EXTERIOR WALL	R-20
CATHEDRAL CEILING R-VALUE	R-30	CRAWL SPACE WALL	R-13
FLOOR OVER UNHEATED SPACE	R-19	GLAZING	U ≤ 0.40
FLOOR OVER OUTSIDE AIR	R-30		N/A
DUCTS OUTSIDE OF THE CONDITIONED SPACE	SUPPLY AND RETURN		R-8
	IN FLOOR & CEILING ASSEMBLY		R-6
BASEMENT WALL	R-13 INSULATION CONCRETE WALLS ADJACENT TO FINISHED SPACE.		
ON GRADE TRENCH FOOTINGS	R10, R15 FOR HEATED SLABS		

DWELLING SHALL COMPLY WITH THE FOLLOWING LOAD CONDITIONS

AREA	MINIMUM DEAD LOAD	MINIMUM LIVE LOAD
EXTERIOR BALCONIES	10	60
DECKS	10	40
CEILING JOISTS/ATTICS W/O STORAGE SCUTTLE ACCESS ONLY	10	10
CEILING JOISTS/ATTICS W/ STORAGE-DOOR /PULL DOWN LADDER ACCESS	10	20
ROOMS - NON-SLEEPING	10	40
SLEEPING ROOMS	10	30
ROOF - LIGHT ROOF COVERING	10	20
ROOF - HEAVY ROOF COVERING - CONCRETE/TILE/SLATE	20	20

COPYRIGHT 2023 BY SDC ENGINEERING, INC. DRAWINGS MAY NOT BE DUPLICATED WITHOUT WRITTEN PERMISSION.

THIS DRAWING HAS BEEN DEVELOPED BY SDC ENGINEERING, INC. EXCLUSIVELY FOR: MR. MEDLIN FOR THE PROJECT LISTED IN THIS TITLE BLOCK. ANY OTHER UNAUTHORIZED USE IS PROHIBITED.

FOUNDATION NOTES:

- BASEMENT FLOOR TO BE MIN. 4" THICK CONC. SLAB OVER 4" CRUSHED ROCK W/ A 6-MIL-THICK POLYETHYLENE MOISTURE BARRIER BETWEEN SLAB AND ROCK.
- ASSUMED SOIL BEARING CAPACITY-1500 PSF MINIMUM. CONTRACTOR TO VERIFY.
- CONCRETE SHALL BE AIR ENTRAINED WITH A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 4000 PSI FOR BASEMENT AND INTERIOR FLOOR SLABS, 3000 PSI FOR BASEMENT AND FOUNDATION WALLS AND 4000 PSI FOR PORCHES AND GARAGE FLOOR SLABS.
- LAP FOUNDATION WALL CORNER AND END BARS 24" MINIMUM. LAP FOOTING BARS 24" MINIMUM.
- FOOTINGS TO BE POURED CONTINUOUS AT FOOTING STEPS. (SOLID JUMPS)
- FLOOR SLABS TO HAVE INSTALLED CONTROL JOINTS TO MINIMIZE THE AMOUNT OF RANDOM CRACKING. JOINTS TO BE SAW CUT WITHIN 18 HOURS OF POURING OR MAY BE TOOLED INTO SLAB.
- FOOTINGS SHALL EXTEND BELOW FROST LINE - MINIMUM DEPTH OF 36" BELOW GRADE IS REQUIRED IN THE KANSAS CITY AREA.
- FOUNDATION DRAIN SHALL BE MIN. 4" PERFORATED DRAIN AROUND USABLE SPACE BELOW GRADE OR OTHER EQUIVALENT MATERIALS (2018 IRC SECTION R405.1). DRAIN TO BE COVERED WITH NOT LESS THAN 6" OF WASHED GRAVEL OR CRUSHED ROCK AND SHALL DRAIN TO DAYLIGHT TO THE EXTERIOR BELOW FLOOR LEVEL OR TERMINATE IN A MIN. 20 GALLON SUMP PUMP.
- STEEL REBAR TO BE MIN. OF GRADE 40.
- ANCHOR BOLT SPACING SHALL NOT EXCEED 72" O. C. W/ 7" MINIMUM EMBEDMENT INTO CONCRETE.
- FOUNDATION WALLS TO BE DAMP-PROOFED (2018 IRC SECTION R406)

STRUCTURAL NOTES:


- EXTERIOR WALLS TO BE 2 x 6'S (STUD GRADE) @ 16" O. C. W/ 7/16" CDX PLYWOOD OR OSB SHEATHING AS SUB-SIDING. (R-20 BATT INSULATION)
 - PROVIDE SOLID BLOCKING BELOW BEAMS AND LOAD BEARING HEADERS.
 - STAIRS TO HAVE 3 STRINGERS NOT TO EXCEED 18" O. C.
 - ALL SILLS, SLEEPERS AND FURRING ATTACHED TO CONCRETE SHALL BE OF DECAY-RESISTANT MATERIALS.
 - FRAMING OF OPENINGS: HEADERS & TRIMMERS SHALL BE OF SUFFICIENT CROSS SECTION TO SUPPORT THE FLOOR FRAMING. TRIMMER JOISTS SHALL BE DOUBLED WHEN THE HEADER IS SUPPORTED MORE THAN 3' FROM THE TRIMMER JOIST BEARING. WHEN THE HEADER SPAN EXCEEDS 4', THE HEADER AND TRIMMER SHALL BE DOUBLED.
 - STUDS SHALL BE CONTINUOUS FROM THE FLOOR TO THE ROOF/CEILING DIAPHRAGM. 2018 IRC 602.3.
- NOTE:**
EXTERIOR WALLS TO BE CONSTRUCTED IN ACCORDANCE WITH IRC 2018 SECTION R602.10.4 METHOD WSP FOR BRACED WALL CONSTRUCTION WITH CONTINUOUS EXTERIOR WOOD STRUCTURAL PANEL SHEATHING.
- ROOF NOTES:**
- A. PROVIDE ROOF VENTS TOTALING MIN. 1 SQ. FT. NET FREE VENTILATING AREA FOR EA. 300 SQ. FT. OF ATTIC SPACE WITH AN EQUAL AMOUNT OF SOFFIT VENTS.
 - B. ALL ROOF RAFTERS TO BE #2 D.F.L. 2"x6" @ 16" O.C. UNLESS OTHERWISE SPECIFIED.
- PLAN NOTES:**
- A. ALL DIMENSIONS, JOIST, MICROLAMS LVL'S, BEAMS AND POINT LOADS SHALL BE REVIEWED BY CONTRACTORS AND THEIR SUB CONTRACTORS AND VERIFIED. SDC ENGINEERING WILL NOT BE RESPONSIBLE FOR ANY INFORMATION WHICH IS NOT VERIFIED.
 - B. CONTRACTOR SHALL NOTIFY SDC ENGINEERING IMMEDIATELY OF ANY DISCREPANCY FOUND WITHIN THESE PLANS.
 - C. CONTRACTOR SHALL ADHERE TO ALL LOCAL, STATE AND FEDERAL CODES REGARDING CONSTRUCTION OF THIS PLAN.
 - D. PLANS ARE DESIGNED AND HOME SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE 2018 INTERNATIONAL RESIDENTIAL CODE FOR ONE AND TWO FAMILY DWELLINGS AND ANY AMENDMENTS THAT MAY APPLY.
 - E. DESIGN CRITERIA WITHIN THIS PLAN ARE SPECIFIED TO PROVIDE WHAT SDC ENGINEERING FEELS IS BEST FOR THE STRUCTURAL INTEGRITY OF THE PLAN. ANY CHANGES TO THOSE SPECIFICATIONS ARE AT THE BUILDERS DISCRETION, HOWEVER SDC ENGINEERING WILL ASSUME NO LIABILITY FOR THE STRUCTURE OF THE PLAN IF CHANGES ARE MADE TO THESE SPECIFICATIONS.
 - F. DOOR BETWEEN THE GARAGE AND THE DWELLING SHALL BE 1 3/8" THICK SOLID WOOD, 1 3/8" THICK MINIMUM SOLID CORE OR HONEY COMBED STEEL DOOR OR 20-MINUTE FIRE RATED. DOOR SHALL BE EQUIPPED WITH A SELF-CLOSING DEVICE.
 - G. ALL WALLS BETWEEN THE GARAGE AND HOUSE ARE TO BE CONSTRUCTED WITH 5/8" FIRE ROCK.
 - H. ALL WINDOWS IN SLEEPING ROOMS OVER 6' ABOVE GRADE MUST BE A MINIMUM OF 24" ABOVE FINISHED FLOOR.

NOTES:


- GLASS IN HAZARDOUS LOCATIONS SHALL BE OF APPROVED SAFETY GLAZING MATERIALS: GLASS IN STORM DOORS; INDIVIDUAL FIXED OR OPENABLE PANELS ADJACENT TO A DOOR WHERE THE NEAREST VERTICAL EDGE IS WITHIN A 24" ARCH OF THE DOOR IN A CLOSED POSITION AND WHOSE BOTTOM EDGE IS WITHIN 60" OF THE FLOOR; WALLS ENCLOSING STAIRWAYS AND LANDINGS WHERE THE GLAZING IS WITHIN 60" OF THE TOP OR BOTTOM OF THE STAIR; ENCLOSURES FOR SPAS, TUBS, SHOWERS AND WHIRLPOOLS; AND GLAZING IN FIXED OR OPENABLE PANELS EXCEEDING 9 SQ. FT. AND WHOSE BOTTOM EDGE IS LESS THAN 18" ABOVE THE FLOOR OR WALKING SURFACE WITHIN 36".
- ALL EXTERIOR WINDOWS AND GLASS DOORS TO BE DESIGNED AND INSTALLED IN ACCORDANCE WITH THE 2018 IRC.
- EMERGENCY EGRESS WINDOWS ARE NOTED AT REQUIRED LOCATIONS IN EACH BEDROOM. THE "EGRESS" WINDOW SHALL HAVE A MINIMUM OPENABLE AREA OF 5.7 SQUARE FEET WITH A MINIMUM OPENABLE HEIGHT OF 24 INCHES AND WIDTH OF 21 INCHES. THE SILL HEIGHT OF THE WINDOW SHALL NOT EXCEED 44 INCHES.
- THE BUILDING THERMAL ENVELOPE IS REQUIRED TO BE SEALED (2018 IRC N1102.4.1).
- RECESSED LIGHTING SHALL BE SEALED TO PREVENT LEAKAGE BETWEEN CONDITIONED & UNCONDITIONED SPACE.
- DUCTS, AIR HANDLERS, FILTER BOXES AND BUILDING CAVITIES USED AS DUCTS SHALL BE SEALED (2018 IRC SECTION N1103.3).
- THE MINIMUM SEER RATING FOR THE AIR CONDITIONER IS 13.
- THE MINIMUM EFFICIENCY RATING FOR THE FORCED AIR FURNACE IS 78%.
- PROVIDE A MECHANICAL VENTILATION SYSTEM FOR ALL BATHROOM & WATER CLOSET ROOMS WHICH DO NOT HAVE A MINIMUM 3 SQUARE FT. EXTERIOR WINDOW, 1/2 OF WHICH IS OPENABLE.
- STAIRWAYS TO HAVE A MAXIMUM 7 1/4" RISER AND A MINIMUM 10" TREAD. (IRC 2018 R311.7.5)
- GUARDRAILS AND HANDRAILS TO BE CONSTRUCTED SUCH THAT A 4" SPHERE CANNOT PASS THRU.
- PROVIDE SMOKE ALARMS OUTSIDE AND INSIDE OF EACH SLEEPING ROOM, AND ON EACH FLOOR INCLUDING BASEMENTS. ALARMS SHALL BE INTERCONNECTED IN SUCH A MANNER THAT ACTUATION OF ONE ALARM WILL ACTIVATE ALL OF THE ALARMS IN THE DWELLING.
- ALL ELECTRICAL OUTLETS SERVING BATHROOMS, KITCHEN COUNTERS, GARAGE AND WITHIN 6' OF ANY SINK SHALL HAVE GFCI PROTECTION.
- ALL OPERABLE WINDOWS W/SILLS MORE THAN 72" ABOVE FINISHED GRADE OR OUTSIDE SURFACE AND ARE LESS THAN 24" ABOVE FINISHED FLOOR ARE TO BE EQUIPPED WITH A WINDOW OPENING CONTROL DEVICE. THESE MECHANISMS ARE REQUIRED TO COMPLY WITH ASTM 2090.
- CARBON MONOXIDE ALARMS ARE REQUIRED OUTSIDE OF AND IN THE IMMEDIATE VICINITY OF ALL SLEEPING ROOMS. IRC R315.3.
- TAMPER RESISTANT RECEPTACLES ARE REQUIRED AS DESCRIBED BY IRC SECTION E4002.14.
- ARC-FAULT CIRCUIT INTERRUPTER PROTECTION IS ONLY REQUIRED FOR ALL BRANCH CIRCUITS SERVING 15 & 20 AMP RECEPTACLES IN BEDROOMS.
- WHOLE HOUSE VENTILATION REQUIRED WHERE UNDER 3 ACH - R303.

NOTES:

- ALL NEW HOMES ARE REQUIRED TO HAVE AN AIR LEAKAGE TEST (BLOWER DOOR TEST) PERFORMED TO VERIFY THAT THE AIR LEAKAGE RATE DOES NOT EXCEED 3 AIR CHANGES PER HOUR AT A PRESSURE DIFFERENTIAL OF 50 PASCALS. THE DETAILS OF THE TEST ARE IN SECTION N1102.4.1.2 OF THE 2018 IRC.
- NEW HOMES THAT HAVE AN AIR LEAKAGE RATE OF LESS THAN 3 AIR CHANGES PER HOUR ARE REQUIRED TO PROVIDE "WHOLE HOUSE MECHANICAL VENTILATION" AS DESCRIBED IN SECTION M1505.4 OF THE 2018 IRC.
- AMENDMENTS TO CHAPTER 11 ENERGY EFFICIENCY OF THE 2018 IRC PROVIDE FOR 3 DIFFERENT COMPLIANCE PATHS:
 - 1.) PRESCRIPTIVE ALTERNATIVE
 - 2.) PERFORMANCE ALTERNATIVE
 - 3.) HERS OPTION
 THE NEW HOME COMPLIANCE PATH OPTION MUST BE INDICATED AT THE TIME OF PERMIT APPLICATION.
- CHAPTER 11 MANDATES SOME REQUIREMENTS, REGARDLESS OF THE COMPLIANCE PATH CHOSEN. THESE REQUIREMENTS ARE LISTED IN THE TABLE ABOVE.



TYPICAL WALL SECTION
SCALE: 1/2" = 1'-0"



TYPICAL WALL SECTION - WALK OUT
SCALE: 1/2" = 1'-0"

PLANS WERE DESIGNED AND REVIEWED IN ACCORDANCE WITH THE 2018 IRC AS ADOPTED BY THE GOVERNING AUTHORITY.



ENGINEERING, INC.
Consulting Structural and Civil Engineers
5807 Raytown Trafficway
Raytown, Missouri 64133
816-358-1445



DATE:	12/14/23
REVISION	
1	
2	
3	
4	