



WOODSPRING SUITES

PROJECT DATA

JOB ADDRESS:	APPLICABLE CODES:
1010 NW WARD RD LEE'S SUMMIT, MO 64086	BUILDING CODE: 2018 INTERNATIONAL BUILDING CODE MECHANICAL CODE: 2018 INTERNATIONAL MECHANICAL CODE ELECTRICAL CODE: 2017 NATIONAL ELECTRIC CODE PLUMBING CODE: 2018 INTERNATIONAL PLUMBING CODE ENERGY CODE: 2018 INTERNATIONAL ENERGY CONSERVATION CODE FIRE PROTECTION: 2018 INTERNATIONAL FIRE CODE ACCESSIBILITY: ICC A117.1-2009
ZONING:	BUSINESS
BUILDING FLOOR AREA	
GROUND FLOOR	12,835 SF
SECOND FLOOR	12,545 SF
THIRD FLOOR	12,545 SF
FOURTH FLOOR	12,545 SF
GRAND TOTAL	50,470 SF
GENERAL NOTES	
1. DRAWINGS ARE DIAGRAMMATIC REPRESENTATIONS OF A FINISHED PRODUCT. CONSULT THE DRAWINGS AND MANUFACTURERS' SPECIFICATIONS FOR DETAILED INSTALLATION, CONSTRUCTION METHODS, SPECIFICATIONS AND ADDITIONAL MATERIALS AND COMPONENTS REQUIRED FOR A COMPLETED PROJECT. THE DRAWINGS IN COMBINATION WITH THE SPECIFICATIONS, MANUFACTURERS' SPECIFICATIONS AND INSTRUCTIONS AND BUILDING CODES DESCRIBE A FINISHED PRODUCT. ALL WORK IS TO CONFORM TO ALL LOCAL, STATE AND NATIONAL BUILDING CODES. NOTIFY THE ARCHITECT PRIOR TO CONSTRUCTION OF ANY DISCREPANCIES. 2. CONTRACTOR TO COORDINATE THE INSTALLATION OF ALL OWNER'S EQUIPMENT. 3. ALL WORK IS TO BE CONSIDERED NEW AND TO BE PROVIDED AND INSTALLED. VERIFY ANY DISCREPANCIES WITH THE ARCHITECT PRIOR TO BIDDING AND CONSTRUCTION. 4. ALL SCHEDULES, IF SHOWN, ARE FOR THE CONVENIENCE OF THE CONTRACTOR. SCHEDULES DO NOT LIST ALL THE ITEMS CONTAINED IN THE DRAWINGS OR MANUFACTURERS' SPECIFICATIONS. CONTRACTOR TO VERIFY COORDINATION OF ALL ITEMS IN ALL SCHEDULES. 5. ALL ENTRANCES TO THE BUILDING ARE TO MEET ACCESSIBILITY REQUIREMENTS ADOPTED BY THE JURISDICTION HAVING AUTHORITY, INCLUDING BUT NOT LIMITED TO MAXIMUM THRESHOLD ELEVATION AND MAXIMUM SLOPE AT LANDINGS. 6. THE CONSTRUCTION SITE AND THE WORK IS TO BE AVAILABLE TO THE OWNER AND OWNER'S REPRESENTATIVES AT ALL TIMES. 7. ALL ACCESSIBLE RAMPS ARE TO HAVE A MAXIMUM OF 1 TO 12 SLOPE AND TO MEET LOCALLY ADOPTED REQUIREMENTS FOR PEDESTRIAN RAMPS AS DETERMINED FOR A CITY STREET. 8. FIELD VERIFY ALL SITE CONDITIONS AND ELEVATIONS PRIOR TO CONSTRUCTION. 9. ALL EXT. DIMENSIONS ARE FROM FACE OF SLAB TO FACE OF SLAB. INTERIOR DIMENSIONS ARE FROM FACE OF STUD TO FACE OF STUD UNLESS OTHERWISE NOTED. 10. THIS PROJECT IS A NEW CONSTRUCTION. THE CONTRACTOR IS TO NOTE THAT NOT ALL CONDITIONS CAN BE REPRESENTED IN THE DRAWINGS AND SPECIFICATIONS. THE CONTRACTOR IS TO ACCOUNT FOR ALL REASONABLE UNFORESEEN CONDITIONS WHEN SUBMITTING A BID OR PRICING FOR THIS WORK. ALL CONTRACTORS AND SUBCONTRACTORS ARE TO FIELD VERIFY CONDITIONS PRIOR TO THE SUBMITTAL OF A BID OR PRICE FOR THEIR WORK. 11. SUBMIT SAMPLES FOR REVIEW AND APPROVAL PER THE SPECIFICATIONS. 12. THE CONTRACTOR IS RESPONSIBLE FOR ALL PERMITS AND FEES. 13. ALL ABBREVIATIONS ARE STANDARDIZED. THE CONTRACTOR IS RESPONSIBLE TO VERIFY THE UNDERSTANDING OF ALL ABBREVIATIONS ON ALL DRAWINGS AND MANUFACTURERS' SPECIFICATIONS PRIOR TO CONSTRUCTING THIS PROJECT. 14. ALL WORK SHALL BE DONE IN A SAFE AND WORKMANLIKE MANNER AND IN STRICT ACCORDANCE WITH THE LOCAL AND/OR STATE (IF APPLICABLE) BUILDING CODES, NATIONAL ELECTRIC CODE, ADA-ADAAGS AND OTHER ADOPTED ACCESSIBILITY STANDARDS, OSHA, AND ALL APPLICABLE CODES, REGULATIONS, ORDINANCES AND AUTHORITIES HAVING JURISDICTION. 15. EACH SUBCONTRACTOR IS RESPONSIBLE FOR HAVING A THOROUGH KNOWLEDGE OF ALL DRAWINGS AND SPECIFICATIONS IN THEIR RELATED FIELD. THE FAILURE TO ACQUAINT HIMSELF WITH THIS KNOWLEDGE DOES NOT RELIEVE HIM OF ANY RESPONSIBILITY FOR PERFORMING HIS WORK PROPERLY. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED BECAUSE OF CONDITIONS THAT OCCUR DUE TO FAILURE TO FAMILIARIZE WORKERS WITH THIS KNOWLEDGE. 16. THE CONTRACTOR SHALL KEEP THE WORK AREA CLEAN AND FREE OF DEBRIS AND REMOVE ALL TRASH AND DEBRIS FROM THE CONSTRUCTION AREA DAILY. NO FLAMMABLE MATERIALS OR LIQUIDS MAY BE STORED IN THE EXISTING BUILDING OR IN ANY NEW ADDITION. MUD AND DEBRIS TRACKED ONTO OWNER PAVING OR CITY STREETS TO BE CLEANED IMMEDIATELY. 17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE TIMELY ORDERING OF MATERIALS TO PROHIBIT DELAYS OF THE CONSTRUCTION SCHEDULE OF THIS PROJECT. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE DELIVERY OF MATERIALS IN A TIMELY MANNER. 18. THE GENERAL CONTRACTOR SHALL RESPOND TO ALL REQUIREMENTS OF THE ARCHITECT AND CONSULTANTS FOR VERIFICATIONS, RESPONSES, AND SUBMISSIONS. 19. THE PROJECT SPECIFICATIONS ARE A PART OF THESE CONSTRUCTION DOCUMENTS AND MUST BE REFERRED TO FOR COMPLETE DOCUMENTATION. 20. GC TO FOLLOW CONSTRUCTION DOCUMENTS AS DETAILED AND DIMENSIONED. DO NOT SCALE DRAWING. 21. ANY DISCREPANCY WITH THE EXISTING SITE CONDITIONS AND/OR THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT FOR CLARIFICATION AND INSTRUCTION. IF DISCREPANCIES ARE FOUND BETWEEN WHAT IS SHOWN ON THE DRAWINGS AND EXISTING FIELD CONDITIONS, CONTACT THE CONSTRUCTION MANAGER AND THE ARCHITECT IMMEDIATELY TO DETERMINE WHAT ACTION SHOULD BE TAKEN TO MATCH EXISTING CONDITIONS. THE BEGINNING OF CONSTRUCTION BY THE GENERAL CONTRACTOR MEANS ACCEPTANCE OF THE EXISTING CONDITIONS. 22. ALL UTILITY LOCATIONS SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL FIELD VERIFY THE EXACT LOCATION OF ALL EXISTING UTILITIES (WHETHER SHOWN OR NOT) PRIOR TO THE SUBMISSION OF HIS BID OR THE COMMENCEMENT OF CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER AND ARCHITECT OF THE DISCOVERY OF EXISTING UTILITIES NOT SHOWN OR NOTED ON DRAWINGS. 23. THE CONTRACTOR SHALL VERIFY EXACT LOCATIONS AND DEPTHS OF UNDERGROUND UTILITY SERVICES PRIOR TO ANY EXCAVATION.	

1010 NW WARD RD
LEE'S SUMMIT, MO 64086

OWNER
GENESIS COMPANIES
4420 MADISON AVE
KANSAS CITY, MO 64111

BUILDING DESCRIPTION

FOUR STORY SLAB-ON-GRADE, WOOD FRAMED BUILDING WITH COMPOSITION SHINGLE ROOF. AUTOMATIC SPRINKLER SYSTEM IS PROVIDED PER NFPA 13 STANDARDS. BUILDING IS USED FOR GUESTROOMS, REGISTRATION, LAUNDRY AND MECHANICAL AND ELECTRICAL ROOMS. STAIR ENCLOSURES ARE PROTECTED BY A TWO-HOUR RATED, INTERIOR SEPARATION. ACCESSIBLE ROOMS ARE LOCATED ON THE FIRST THROUGH FOURTH FLOORS. THE ROOFING IS CLASS "B". FIRE DETECTION SYSTEM (DETECTORS, ALARMS & SPRINKLERS ARE INCLUDED)

BUILDING ENVELOPE COMPLIANCE REQUIREMENTS		
	DESCRIPTION	IDENTIFICATION
WALLS / FLOORS / ROOF		
EXTERIOR WALLS	BATT INSULATION	MIN. R-19, FACED INSULATION
INTERIOR WALLS	BATT INSULATION	MIN. R-11, UNFACED INSULATION
ROOF	BLOWN-IN INSULATION	MIN. R-60, CAVITY FACED INSULATION
SLAB ON GRADE	NO INSULATION	R-5
DOORS / WINDOWS		
EXT. SWING DOOR	U FACTOR	U-2.2, OPAQUE HOLLOW METAL
EXT. ENTRANCE - STOREFRONT	U FACTOR/ SHGC / VT	U-.60 / SHGC .27 / VT .69
STOREFRONT WINDOWS	U FACTOR/ SHGC/ VT	U-.65 / SHGC .27 / VT .69
VINYL WINDOWS (GUESTROOM)	U FACTOR/ SHGC/ VT	U-.45 / SHGC .27 / VT .69

PROJECT DIRECTORY

ARCHITECT	CIVIL ENGINEER
BRR ARCHITECTURE, INC 8131 METCALF AVE, #300 OVERLAND PARK, KS 66204	OWN, INC 4240 PHILIPS FARM RD, #101 COLUMBIA, MO 65201
STRUCTURAL ENGINEER	MECHANICAL ENGINEER / PLUMBING ENGINEER
BSE STRUCTURAL ENGINEERS, LLC 11320 W. 79TH STREET LENEXA, KS 66214	ACERTUS CONSULTING GROUP, LLC 11880 COLLEGE BLVD, #475 OVERLAND PARK, KS 66210
ELECTRICAL ENGINEER	BIDDING CONTACT
ACERTUS CONSULTING GROUP, LLC 11880 COLLEGE BLVD, #475 OVERLAND PARK, KS 66210	RENITA SOMMERS BUILT BY GENESIS RENITA@BUILTBYGENESIS.COM

CITY, STATE & FIRE DISTRICT SUBMITTALS

PLANS FOR THE DEFERRED SUBMITTAL ITEMS (LISTED BELOW) SHALL BE SUBMITTED IN A TIMELY MANNER THAT ALLOWS A MINIMUM OF 30 WORKING DAYS FOR INITIAL PLAN REVIEW. ALL COMMENTS RELATED TO THE DEFERRED SUBMITTAL MUST BE ADDRESSED TO THE SATISFACTION OF THE PLAN CHECK DIVISION PRIOR TO APPROVAL OF THE SUBMITTAL ITEMS.

1. SPRINKLER SYSTEM
2. FIRE ALARM SYSTEM
3. ROOF WOOD TRUSS
4. SIGN PACKAGE

DRAWING INDEX

		Project Issue Date
GENERAL		
TT.1	COVER SHEET	08/16/23
G1.1	GENERAL INFORMATION	08/16/23
G1.2	ICC REFERENCE DETAILS	08/16/23
G1.3	ICC REFERENCE DETAILS	08/16/23
LS1.1	BUILDING CODE AND FIRST FLOOR LIFE SAFETY PLAN	08/16/23
LS1.2	TYPICAL UPPER FLOOR LIFE SAFETY PLAN	08/16/23
SP1.2	TRASH ENCLOSURE & DETAILS	08/16/23
STRUCTURAL		
S0.0	GENERAL NOTES	08/16/23
S0.1	GENERAL NOTES	08/16/23
S0.2	ISOMETRIC	08/16/23
S0.3	BUILDING SECTION	08/16/23
S1.1	FOUNDATION PLAN	08/16/23
S2.1	2ND FLOOR FRAMING PLAN	08/16/23
S2.2	3RD FLOOR FRAMING PLAN	08/16/23
S2.3	4TH FLOOR FRAMING PLAN	08/16/23
S2.4	ROOF FRAMING PLAN	08/16/23
S3.1	TYPICAL FOUNDATION DETAILS	08/16/23
S3.2	FOUNDATION DETAILS	08/16/23
S4.1	TYPICAL FRAMING DETAILS	08/16/23
S4.2	TYPICAL FRAMING DETAILS	08/16/23
S4.3	TYPICAL STAIR FRAMING PLAN & DETAILS	08/16/23
S4.4	FRAMING DETAILS	08/16/23
S4.5	FRAMING DETAILS	08/16/23
S4.6	FRAMING DETAILS	08/16/23
S4.7	PARAPET FRAMING DETAILS	08/16/23
S5.1	CANOPY FRAMING PLAN AND DETAILS	08/16/23
S5.2	TRASH ENCLOSURE FRAMING PLAN AND DETAILS	08/16/23
ARCHITECTURAL		
A1.1	FIRST FLOOR PLAN	08/16/23
A1.2	SECOND FLOOR PLAN	08/16/23
A1.3	THIRD FLOOR PLAN	08/16/23
A1.4	FOURTH FLOOR PLAN	08/16/23
A1.5	ROOF PLAN & DETAILS	08/16/23
A1.6	FIRST FLOOR RCP	08/16/23
A1.7	TYPICAL FLOOR RCP	08/16/23
A1.8	FIRST FLOOR FINISH PLAN	08/16/23
A1.9	TYPICAL UPPER FLOOR FINISH PLAN	08/16/23
A2.1	EXTERIOR ELEVATIONS	08/16/23
A2.2	EXTERIOR ELEVATIONS	08/16/23
A3.1	BUILDING SECTIONS	08/16/23
A3.2	WALL SECTIONS	08/16/23
A3.3	WALL SECTIONS & DETAILS	08/16/23
A3.4	EXTERIOR DETAILS	08/16/23
A3.5	PARAPET DETAILS	08/16/23
A4.1	ENLARGED PUBLIC PLANS	08/16/23
A4.2	ENLARGED FINISH PLANS	08/16/23
A4.3	INTERIOR ELEVATIONS	08/16/23
A4.4	INTERIOR ELEVATIONS	08/16/23
A5.1	GUESTROOM - QUEEN SUITE	08/16/23
A5.2	GUESTROOM - ACCESSIBLE QUEEN SUITE	08/16/23
A5.3	GUESTROOM - DOUBLE QUEEN SUITE	08/16/23
A5.4	GUESTROOM - ACCESSIBLE DOUBLE QUEEN SUITE	08/16/23
A5.5	GUESTROOM - DELUXE QUEEN SUITE	08/16/23
A5.6	GUESTROOM - ACCESSIBLE DELUXE QUEEN SUITE	08/16/23
A5.7	GUESTROOM BATHROOMS	08/16/23
A5.8	GUESTROOM BATHROOMS	08/16/23
A6.1	STAIR PLANS, SECTIONS & DETAILS	08/16/23
A6.2	ELEVATOR PLANS & SECTIONS	08/16/23
A6.3	ELEVATOR DETAILS	08/16/23
A7.1	PARTITIONS, FINISH SCHEDULE & DETAILS	08/16/23
A7.2	ASSEMBLIES & DETAILS	08/16/23
A7.3	ASSEMBLY PENETRATION DETAILS	08/16/23
A8.1	DOOR SCHEDULE & DOOR DETAILS	08/16/23
A8.2	WINDOW SCHEDULE, ELEVATIONS & DETAILS	08/16/23
A9.1	ENLARGED CANOPY PLANS & SECTIONS	08/16/23
A9.2	CANOPY DETAILS	08/16/23
A10.1	FIRE RATED ASSEMBLIES	08/16/23
A10.2	FIRE RATED ASSEMBLIES	08/16/23
A10.3	FIRE RATED ASSEMBLIES	08/16/23
A10.4	FIRE RATED ASSEMBLIES	08/16/23
A10.5	FIRE RATED ASSEMBLIES	08/16/23
A10.6	FIRE RATED ASSEMBLIES	08/16/23
A10.7	FIRE RATED ASSEMBLIES	08/16/23
A10.8	FIRE RATED ASSEMBLIES	08/16/23
A10.9	FIRE RATED ASSEMBLIES	08/16/23
MECHANICAL		
M-1	MECHANICAL NOTES, SCHEDULES, AND LEGENDS	08/16/23
M-2	MECHANICAL FIRST FLOOR PLANS	08/16/23
M-3	MECHANICAL SECOND FLOOR PLANS	08/16/23
M-4	MECHANICAL THIRD FLOOR PLANS	08/16/23
M-5	MECHANICAL FOURTH FLOOR PLANS	08/16/23
M-6	MECHANICAL ROOF PLAN	08/16/23
M-7	MECHANICAL FIRST FLOOR ENLARGED PLANS	08/16/23
PLUMBING		
P-3	PLUMBING WASTE AND VENT PLANS - 2ND FLOOR	08/16/23
P-5	PLUMBING WASTE AND VENT PLANS - 4TH FLOOR	08/16/23
P-7	PLUMBING WATER PLANS - 3RD FLOOR	08/16/23
P-1	PLUMBING NOTES AND LEGENDS	08/16/23
P-2	PLUMBING WASTE AND VENT PLANS - 1ST FLOOR	08/16/23
P-4	PLUMBING WASTE AND VENT PLANS - 3RD FLOOR	08/16/23
P-6	PLUMBING WATER PLANS - 1ST FLOOR	08/16/23
P-8	PLUMBING WASTE & VENT RISERS	08/16/23
P-9	PLUMBING DOMESTIC WATER RISERS	08/16/23
P-10	PLUMBING ENLARGED PLANS	08/16/23
ELECTRICAL		
E-1	ELECTRICAL RISER DIAGRAM	08/16/23
E-2	ELECTRICAL PANELS AND SCHEDULES	08/16/23
E-3	ELECTRICAL PLANS - FIRST FLOOR	08/16/23
E-4	ELECTRICAL PLANS - SECOND FLOOR	08/16/23
E-5	ELECTRICAL PLANS - THIRD FLOOR	08/16/23
E-6	ELECTRICAL PLANS - FOURTH FLOOR	08/16/23
E-7	ELECTRICAL PLANS - ROOF	08/16/23
E-8	ELECTRICAL ENLARGED PLANS	08/16/23
E-9	FIRE ALARM SYSTEM PLANS	08/16/23
E-10	ELECTRICAL SITE PLAN	08/16/23
E-11	ELECTRICAL GENERAL NOTES	08/16/23



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO



Drawn By:

JP

Checked By:

TL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160


Sheet Title

COVER SHEET

Sheet No.

T1.1

BRR Original printed on recycled paper




GENERAL NOTES		
1. PROVIDE SILICONE CAULK AT ALL CABINET, COUNTERTOP, AND BACK SPLASH LOCATIONS WHERE INSTALLATION MEETS A SURFACE. CAULKING MUST BE LEVEL OR SLIGHTLY COVERED AT JOINT. UTILIZE BACKER ROD WHERE JOINT EXCEEDS 1/4". TOOL AND FINISH JOINTS. LEAVE NO VISIBLE GAPS. TYPICAL ALL LOCATIONS. COLOR TO MATCH ADJACENT SURFACE.		
2. PROVIDE CAULK AT ALL CABINET END PANELS WHERE INSTALLATION MEETS A SURFACE. IF JOINT EXCEEDS 1/8" WIDE INSTALL TRIM MOLDING TO MATCH CABINET FINISH AND CAULK. CAULK COLOR TO MATCH LAMINATED SURFACE.		
3. PROVIDE ADDITIONAL FRAMING FOR OUTLETS AS REQUIRED TO MOUNT IN POSITIONS AS SHOWN. (4" MAX HORIZONTAL TOLERANCE).		
4. PROVIDE INSTALLATION KIT WITH COOK TOP, CUT OUT COUNTER FOR COOK TOP TO MAX 1/2" TOLERANCE. SECURE CABLE TO BACK OF CABINET BEHIND SHELF. INSTALL SECURELY WITH CLEAR SILICONE.		
5. ALL BLOCKING FOR ACCESSIBLE COMPONENTS TO BE WOOD BETWEEN STUDS.		
6. PROVIDE VINYL BASE AT BOTTOM OF ALL EXPOSED PORTIONS OF CABINETS AS WELL AS AROUND WALLS. VINYL BASE TO BE FURNISHED FROM ROLL STOCK INSTALLED IN THE LONGEST LENGTHS POSSIBLE WITH INSIDE AND OUTSIDE CORNERS SECURED TIGHTLY TO WALL SURFACES.		
7. TRIP LEVER ON ADA TOILETS TO BE LOCATED ON SINK SIDE OF TANK.		
8. ALL BLOCKING FOR FURNITURE SHALL BE COORDINATED WITH FURNITURE SUPPLIER SHOP DRAWINGS.		
9. NO FLOORING TILE LENGTHS TO BE CUT LESS THAN THE WIDTH OF THE TILE AND NO RIPS LESS THAN HALF THE TILE WIDTH, TYPICAL.		
10. REF STRUC DWGS FOR P3B SHEARWALL LOCATIONS (TYP).		
11. SEE SHEETS A1-1 AND A1-2 FOR WINDOW LOCATIONS, DIMENSIONS, AND TYPES.		
12. PROVIDE CORNER GUARD AT ALL 90 DEGREE CORNERS. REF SPECS		
13. HEAVY TIMBER CANOPY TRUSSES TO BE COVERED AND PROTECTED FROM THE ELEMENTS PRIOR TO INSTALLATION. ALL STAMPS, MARKINGS, ETC. TO BE REMOVED FROM SURFACE PRIOR TO STAINING TIMBER TRUSSES.		
14. ALL PTAC AND WINDOW FLASHING AT FIRST FLOOR TO HAVE ALL SHARP EDGES REMOVED.		
15. CONSTRUCTION SIGN REQUIREMENT: THE TEMPLATE MUST BE PRINTED AS 4' x 8' AND IN FULL COLOR. THE GC MAY HAVE ADDITIONAL SIGNAGE WITH THEIR COMPANY LOGO/INFORMATION BUT IT CANNOT INFRINGE ON THE 4' x 8' WOODSPRING SUITES SIGN. THE SIGN SHOULD BE INSTALLED WITHIN 30 DAYS FROM CONSTRUCTION START AND MUST BE REMOVED PRIOR TO OPENING. GRAPHIC TO BE PROVIDED BY WOODSPRING HOTELS. NOTE: LOCATION OF CONSTRUCTION SIGN TO BE VERIFIED BY OWNER'S REPRESENTATIVE.		
IMPORTANT: 1. ALL CALCULATIONS FOR MEMBRANE PROTECTION FOR FIRE RATED WALLS HAVE BEEN MADE ON THE BASIS OF 100 SQUARE INCHES OF OPENING IN 100 SQUARE FEET OF MEMBRANE SURFACE. OUTLET SIZES SHOWN I.E. DUPLEX (2X4) OR DOUBLE DUPLEX (4X4) WILL MEET THIS REQUIREMENT. DO NOT SUBSTITUTE LARGER ELECTRICAL BOXES WITH REDUCERS FOR ANY OF THE OUTLETS SHOWN UNLESS VERIFIED WITH LOCAL CODE OFFICIALS AND DOCUMENTED IN WRITING.		

FINISH SCHEDULE		
MARK	DESCRIPTION	COMMENTS
CPT-1	SHAW INC. CORRESPOND TILE 57353 - 52516 "TOGETHER" (24"x24)	CORRIDORS (QUARTER TURN)
FRP-1	KOROGARD - "RELAXED GRAY" (5A) - P1 DUNE TEXTURE - LENO WEAVE FINISH - ASTM E-84	ALL PUBLIC SPACES KITCHENETTE BACKSPLASH
LVT-1	SHAW HARD SURFACE - SOLITUDE #0648V - COLOR "48506 SMOKE" (6"x48")	ALL PUBLIC SPACES (ASHLAR), LOBBY (HERRINGBONE) ACCEPTABLE ALTERNATE FOR CORRIDORS; VERIFY WITH OWNER
LVT-2	KARNDEAN LOOSELAY K TRADE "SICILIA LLP 142" (41"x10")	GUESTROOMS (ASHLAR)
PL-1	PLASTIC LAMINATE - WILSONART 8201-K-12 "GREY ELM"	FF&E CASEWORK
PL-2	FORMICA 933-58 "MISSION WHITE"	WINDOW SILLS
PL-3	PLASTIC LAMINATE - WILSONART 4857-60 "SHADOW ZEPHYR"	KITCHEN COUNTERTOPS
PL-4	PLASTIC LAMINATE - WILSONART 5023-19 "NIGHTFALL"	LOBBY FRONT DESK FACE, COFFEE BAR CASEWORK
PT-1	SW7065 "ARGOS"	PRIMARY RECEPTION, LOBBY, ELEVATOR LOBBY, STAFF/GUEST LAUNDRY, PUBLIC RESTROOM, FITNESS CENTER, CORRIDOR WALL COLOR, TRAINING
PT-2	SW9633 "SILVER LAKE"	ACCENT WALLS: GUESTROOM WALL, GUEST BATHROOM WALL
PT-3	SW7611 "TRANQUIL AQUA"	ACCENT WALLS: CORRIDOR WALL, PUBLIC RESTROOM, GUEST LAUNDRY, FITNESS
PT-4	SW7636 "ORIGAMI WHITE"	PRIMARY GUESTROOM WALL COLOR, CEILINGS THROUGHOUT
RF-1	ECOSURFACES - ECOFIT 8MM (3.2MM WEAR LAYER OVER 5MM BACKING) - 1213 ACTION! (ROLLS 4'X25')	FITNESS FLOORING
WB-1	SHAW - 4" COVE WALL BASE - 168CA - 40 "CLAY"	THROUGHOUT UNLESS OTHERWISE NOTED
NOTE: REFER TO SPECIFICATIONS FOR "NATIONAL ACCOUNT PRICING AND CONTACT INFORMATION"		


HEARING IMPAIRED DEVICES		
SYMBOL	DEVICE	NOTES
	BUTTON FOR DOOR SIGNAL	OUTSIDE DOOR ON STRIKE SIDE, +46" AFF TO CL FACTORY LABEL ON COVER PLATE
	2-GANG BOX W/ TRANSFORMER FOR DOOR BELL	+84" AFF ALIGNED WITH SMOKE/FIRE STROBE
	DOORBELL DISABLE SWITCH	WALL BEHIND ENTRY DOOR, NEAR LIGHT SWITCH "DOORBELL DISABLE SWITCH" PLAQUE
	SMOKE STROBE, REMOTE	COMPATIBLE WITH SMOKE DETECTOR, BATHROOM +84" AFF "SMOKE" LABEL INTEGRAL TO DEVICE

A. PLAN DIAGRAM SHOWS GENERAL CONFIGURATION OF DOORBELL DEVICES - MODIFY AS REQUIRED FOR ACTUAL GUESTROOM CONFIGURATION AND LOCAL REQUIREMENTS.

B. PLAQUES (EXCEPT AS NOTED); PROVIDE AS REQUIRED; PLAQUES SHALL BE BLACK PHENOLIC W/ 1/4" WHITE ENGRAVED LETTERS.




ACCESSORIES SCHEDULE		
TA = TOILET ACCESSORY		
TA #	ACCESSORY DESCRIPTION	BRAND / MODEL
TA-1	TOILET PAPER HOLDER (SURFACE MTD)	LIBERTY / VOISIN EK33
TA-2	STRAIGHT SHOWER CURTAIN ROD (SURFACE MTD)	WINGIT / WOC5N15
TA-3	5' STD BOW SHOWER ROD (NON-ACCESSIBLE)	WINGIT / WOC5N5NMC
TA-4	TOWEL BAR (SURFACE MTD)	OWNER PROVIDED AND INSTALLED
TA-4A	18" POLISHED CHROME TOWEL HOLDER (SURFACE MTD)	MOEN / 5207-181CH
TA-5	GRAB BAR - TOILET (SURFACE MTD)	BRADLEY / 8120-001420
TA-6	GRAB BAR - TOILET (SURFACE MTD) GRAB BAR - TOILET (SURFACE MTD)	BRADLEY / 8120-001360 BRADLEY / 8120-001180
TA-8	24"x36" DECORATIVE FRAMED MIRROR (SURFACE MTD)	OWNER PROVIDED AND INSTALLED
TA-8A	48"x36" DECORATIVE FRAMED MIRROR (SURFACE MTD)	OWNER PROVIDED AND INSTALLED
TA-9	ROBE HOOK (SURFACE MTD)	TAYMOR / 02-D9402



2 1 1/2" = 1'-0"


FIRE EXTINGUISHER CAB DETAIL

NOTE: WHEN INSTALLING ELECTRICAL OUTLET BOXES IN SHEAR WALL CONTRACTOR SHALL CUT OPENINGS NEATLY, IN ACCORDANCE WITH AND MAINTAINING STRUCTURAL, FIRE AND SOUND RATINGS.



ELECTRICAL WALL BOX LOCATION AND LAYOUT


THE LOCATION OF ELECTRICAL SWITCHES, OUTLETS AND OTHER RECEPTACLE TYPES SHOWN ON THE PLANS AND DETAILS SHOULD BE ADJUSTED SO THAT NO TWO BOXES ARE BACK TO BACK. PLACE AS CLOSE AS POSSIBLE TO LOCATION SHOWN AND PROVIDE APPROPRIATE VERTICAL AND HORIZONTAL BLOCKING SO THAT EACH DEVICE IS ISOLATED WITHIN ITS OWN CAVITY.



REFER TO GENERAL NOTE 3/G1.1

REFER TO DETAIL 1/A7.2 FOR PUTTY PAD INFORMATION WHERE REQUIRED BY AHJ.

ABBREVIATION LEGEND	
@ = AT # = POUND & = AND	M MAINT = MAINTENANCE MAX = MAXIMUM MECH = MECHANICAL MEP = MECHANICAL, ELECTRICAL & PLUMBING MFR = MANUFACTURER MIN = MINIMUM MIR = MIRROR MISC = MISCELLANEOUS MLWK = MILLWORK MO = MASONRY OPENING MR = MOISTURE RESISTANT MTL = METAL MW = MICROWAVE N N = NORTH N/C = NOT IN CONTRACT NO = NUMBER NOM = NOMINAL NTS = NOT TO SCALE O OCC = OCCUPANT OF/OI = OWNER FURNISHED/OWNER INSTALLED OFS = OUTSIDE FACE OF STUD OS = OVERFLOW SCUPPER OH = OVERHEAD OPNG = OPENING P PL = PROPERTY LINE PLAM = PLASTIC LAMINATE PLBG = PLUMBING PNL = PANEL PR = PAIR PRELIM = PRELIMINARY PROP = PROPERTY PT = PAINT Q QTY = QUANTITY R R = RADIUS R = RISER RAF = RESILIENT ATHLETIC FLOORING RB = RUBBER BASE RCP = REFLECTED CEILING PLAN RD = ROOF DRAIN REC = RECESSED RECPT = RECEPTACLE REF = REFERENCE REFR = REFRIGERATOR REQ OR REQD = REQUIRE OR REQUIRED RFS = ROOM FINISHES SCHEDULE RM = ROOM RO = ROUGH OPENING S S = SOUTH SAN = SANITARY SC = SEALED CONCRETE SCHD = SCHEDULE SECT = SECTION SD = SHOWER DRAIN SHT = SHEET SIM = SIMILAR SM = SMALL SP = STANDPIPE SPEC = SPECIFICATION SS = SOLID SURFACE SST = STAINLESS STEEL ST = STAIRS STC = SOUND TRANSMISSION CLASS STD = STANDARD STOR = STORAGE STRUC = STRUCTURAL SW = SWITCH SYM = SYMBOL T T = THERMOSTAT (T) = TEMPERED GLASS TEL = TELEPHONE TEMP = TEMPORARY TO = TOP OF TOB = TOP OF BEAM TOC = TOP OF COLUMN TOF = TOP OF FOOTING/FOUNDATION TOS = TOP OF STEEL TOW = TOP OF WALL TS = TRANSITION STRIP TV = TELEVISION TYP = TYPICAL U UCD = UNDERCUT DOOR UL = UNDERWRITERS LABORATORIES UNO = UNLESS NOTED OTHERWISE V VAN = VANITY VB = VINYL BASE VCT = VINYL COMPOSITION TILE VENT = VENTILATION OR VENTILATOR VERT = VERTICAL VEST = VESTIBULE VIP = VERIFY IN FIELD VER = VERIFY VTR = VENT THROUGH ROOF VWC = VINYL WALL COVERING W W = WEST WI = WITH W/O = WITHOUT WAP = WIRELESS ACCESS POINT WB = WALL BORDER WC = WALL COVERING WD = WOOD WP = WALL PROTECTION WPM = WATERPROOF MEMBRANE WR = WEATHER RESISTANT WS = WEATHERSTRIP WSOT = WAINSCOT WT = WINDOW TREATMENT



brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

WOODSPRING SUITES

Drawn By:
JP

Checked By:
AL

Document Date:
08/16/23

Protocol:
WSS_v5_2023.1 (05/05/23)

Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409

BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

08/17/2023

GENERAL INFORMATION

G1.1

BRR Original printed on recycled paper




Figure 703.3.10
Height of Tactile Characters Above Finish Floor or Ground




Figure 703.3.11
Location of Tactile Signs at Doors




Figure 611.4
Height of Laundry Compartment Opening




Figure 610.3.2
L-Shaped Shower Compartment Seat




Figure 610.3.1
Rectangular Shower Compartment Seat




Figure 610.2
Bathtub Seats




Figure 609.3
Spacing of Grab Bars




Figure 609.2
Size of Grab Bars




Figure 608.4.3
Alternate Roll-In Type Shower Control and Handshower Location




Figure 608.4.2
Standard Roll-In Type Shower Control and Handshower Location




Figure 608.4.1
Transfer Type Shower Compartment Control Location





Figure 608.3.3
Grab Bars in Alternate Roll-In Type Showers






Figure 608.2.2
Standard Roll-In Type Shower Compartment Size and Clearance




Figure 607.5
Bathtub Control Location




Figure 607.4.2
Grab Bars for Bathtubs with Removable In-Tub Seats




Figure 607.4.1
Grab Bars for Bathtubs with Permanent Seats




Figure 607.2
Clearance for Bathtubs




Figure 604.3.1
Wheelchair Accessible Compartment Door Openings

Figure 608.2.1
Transfer Type Shower Compartment Size and Clearance




Figure 604.3.2
Wheelchair Accessible Toilet Compartments




Figure 604.7
Dispenser Outlet Location




Figure 604.5.2
Rear Wall Grab Bar for Water Closet




Figure 604.5.1
Side Wall Grab Bar for Water Closet




Figure 604.4
Water Closet Seat Height




Figure 604.3
Size of Clearance at Water Closets




Figure 604.2
Water Closet Location




Figure 602.5
Drinking Fountain Spout Location

GENERAL NOTE

THIS DATA IS PROVIDED AS AN ADDITIONAL RESOURCE TO THE TEAM OF OWNER, CLIENT, ARCHITECT, ENGINEER, AND SPECIFICALLY, CONTRACTOR. THIS IS A TOOL TO APPRISE ALL PARTIES OF GENERAL ACCESSIBLE CONDITIONS AS PUBLISHED PER THE ICC A117.1, AND THE ACCESSIBILITY GUIDELINES FOR BUILDINGS AND FACILITIES. THE DIAGRAMS ARE VERBATIM DUPLICATIONS OF THE ICC A117.1 STANDARDS AND ARE NOT INDICATIVE OF ALL CONDITIONS AND CERTAINLY DO NOT FULLY REPRESENT THE ENTIRETY OF THE WRITTEN GUIDELINES AS CONTAINED IN THE STANDARDS. THIS DATA IS IN SUPPORT OF GENERAL ARCHITECTURAL AND ENGINEERING DOCUMENTATION, WHICH IS INTENDED TO BE CONSISTENT WITH ACCESSIBLE CONDITIONS. HOWEVER, ICC A117.1 IS NOT A BUILDING CODE AND NOT NECESSARILY REVIEWABLE OR ENFORCEABLE BY TRADITIONAL BUILDING AUTHORITIES. ICC A117.1 IS A CIVIL STATUTE. THEREFORE, THE ENTIRE TEAM OF OWNER, CLIENT, ARCHITECT, ENGINEER, AND SPECIFICALLY, CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE TO THE SPECIFIC INTENT OF THE LAW. THIS DATA IS PROVIDED TO ACT AS AN ADDED SAFEGUARD TO FULLY FAMILIARIZE THE TEAM WITH EXPECTATIONS ASSOCIATED WITH THE ICC A117.1 AND TO ASSIST THE TEAM IN ACHIEVING FULLY ACCESSIBLE CONDITIONS AS REQUIRED BY CIVIL LAW.

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol: WSS_v5_2023.1 (05/05/23)


Revisions Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title

ICC REFERENCE
DETAILS

Sheet No.

G1.3

BRR Original printed on recycled paper



TOTAL	71	37	14	122
-------	----	----	----	-----

FIRE RESISTIVE RATINGS		(TABLE 601)		
STRUCTURAL ELEMENT	FR RATING PER CODE	FR RATING PER DESIGN	DESIGN NUMBER	DETAIL REFERENCE
BEARING WALLS (V-A)				
EXT. WALLS (R1)	1 HOUR	1 HOUR	U.L. #U356	A10.5
INT. WALLS	1 HOUR	1 HOUR	U.L. #U305	A10.2 & A10.3
CORRIDOR WALLS (R1)	30 MIN	1 HOUR	U.L. #U327	A10.3
OPENING PROTECTION	20 MIN	20 MIN	---	---
GUESTROOM SEPARATION	1 HOUR	1 HOUR	U.L. #U327	A10.3
OPENING PROTECTION	45 MIN	60 MIN	---	---
STAIR (INT. WALLS)	2 HOUR	2 HOUR	U.L. #U301	A10.1 & A10.2
STAIR (EXT. WALLS)	1 HOUR	1 HOUR	U.L. #U356	A10.5
OPENING PROTECTION	90 MIN	90 MIN	---	---
ELEVATORS	2 HOUR	2 HOUR	U.L. #U905	A10.6
OPENING PROTECTION	90 MIN	90 MIN	---	---
CEILING	2 HOUR	2 HOUR	GA FILE NO. FC 5725	HA5/A7.2
STORAGE	1 HOUR	1 HOUR	U.L. #U305	A10.2 & A10.3
OPENING PROTECTION	45 MIN	45 MIN	---	---
LAUNDRY (GUEST)	1 HOUR	1 HOUR	U.L. #U305	A10.2 & A10.3
OPENING PROTECTION	45 MIN	45 MIN	---	---
LAUNDRY TO GUEST	1 HOUR	1 HOUR	U.L. #U341	A10.4
FLOOR - CEILING	1 HOUR	1 HOUR	ICC ESR-1153 ASSEMBLY B	HA1/A7.2
FLOOR-CEILING @ CORR	1 HOUR	1 HOUR	IBC TABLES: 722.6.2(1) & 722.6.2(2)	HA2/A7.2 & A10.9
ROOF - CEILING @ STAIR	2 HOUR	2 HOUR	GA FILE NO. FC 5725	HA5/A7.2
ROOF - CEILING	1 HOUR	1 HOUR	GA FILE NO. RC 2602	HA4/A7.2
ROOF - CEILING @ 4th FLOOR CORRIDOR	1 HOUR	1 HOUR	U.L. #U305 (IBC 708.4 EXCEPTION 3)	A10.2 & A10.3



8/16/2023 12:51:13 PM

Special Inspector:

1. The following items require special inspection in accordance with the building code.

a. Reinforced masonry construction - level 1 inspection

b. Concrete & masonry grout design mix

c. Placing of concrete & reinforcing steel

d. Bolts & anchors embedded in concrete & masonry

e. Concrete formwork

f. Structural steel fabrication

g. Structural steel bolting & welding

h. Inspection of roof & deck attachment

i. Post installed anchors in masonry & concrete

j. In-situ soils, excavations, filling & compaction

2. The Contractor shall request special inspection of the items listed above prior to those items becoming inaccessible & unobservable due to progression of the work.

3. The Special Inspector shall be a qualified person who shall demonstrate competence, to the satisfaction of the building official, for inspection of the particular type of construction or operation requiring special inspection.

4. The Special Inspector shall observe the work assigned for conformance with the approved design drawings and specifications.

5. The Special Inspector shall furnish inspection reports to the Building Official, the Engineer and Architect of record, and other designated persons. All discrepancies shall be brought to the immediate attention of the Contractor for correction, then if uncorrected, to the proper design authority and to the Building Official.

6. The Special Inspector shall submit a final signed report stating whether the work requiring special inspection was, to the best of the inspector's knowledge, in conformance with the approved plans and specifications and the applicable workmanship provisions of the governing building codes.

Earthwork:

1. The Inspector must verify that the preparation of the natural ground and the placement of engineered fill is performed in accordance with the GEOTECHNICAL engineer's recommendations as stated in the GEOTECHNICAL report.
2. The Inspector must monitor the placement of all fill to determine whether the type of material, moisture content, and degree of compaction are within the recommended limits contained in the GEOTECHNICAL report. Proceed with subsequent earthwork only after test results for previously completed work comply with recommended limits contained in the GEOTECHNICAL report.
3. All Subgrade supporting footings and slabs must be inspected immediately prior to the placement of reinforced concrete.
4. Paved and building slab areas shall be tested at Subgrade and at each compacted fill and backfill layer, at least once for every 2000 sq. ft. or less of paved or building slab areas, but in no case fewer than 3 tests.
5. Foundation wall backfill shall be tested at each compacted initial and final backfill layer, at least once for each 100 ft. or less of wall length, but no fewer than 2 tests.
6. Trench backfill shall be tested at each compacted initial and final backfill layer, at least once for each 150 ft. or less of trench length, but no fewer than 2 tests.
7. Test compaction of soils-in-place in accordance with ASTM D 1556, ASTM D 2167, ASTM D 2922, and ASTM D 2937, as applicable.
8. Test Reporting: Test results must be reported to BSE and the general contractor in writing within 24 hours after testing, via fax. Reports must contain the project name, the date of the test and the location of the test.

Concrete:

1. Strength test cylinders shall be prepared for each day's pour of each concrete mix and at a minimum frequency of every 50 cu. yd. on all concrete placed. Conform to ASTM C39.
2. Four (4) test cylinders are to be made and cured on site for the first 24 hours. Test one of the specimens at 7 days and two at 28 days. Hold the fourth specimen in reserve for later testing if needed.
3. Slump, air content and temperature tests shall be conducted at a minimum when strength specimens are made and at any other times as specified by the Engineer.
4. Perform slump tests on a representative concrete sample at the point of discharge. Perform additional tests when concrete consistency seems to have changed. The maximum allowable field slump is 5 inches. Conform to ASTM C143.
5. Perform air content tests on all concrete specified to be air-entrained. Conform to ASTM C231.
6. Perform a temperature test every hour when air temperature is 40°F and below, or when air temperature is 80°F and above. Conform to ASTM C 1064.
7. Prior to the closing of forms or the delivery of concrete to the job site, the inspector shall verify that the reinforcing steel is in conformance with the city-approved plans, specifications and shop drawings. The inspector shall confirm that the reinforcing steel is of the correct size and grade and ensure that the proper spacing, clearances, splice lengths and embedded items have been provided. All reinforcing steel shall be in place prior to the placement of concrete and be secured against displacement.
8. The Inspector shall verify that the bolt size, location and embedment length of all anchor bolts are in conformance with the city-approved plans, specifications and shop drawings.
9. Anchor rods 3/4"Ø or smaller may be floated in place following concrete placement, provided that anchor bolts are worked easily by hand into the fresh concrete to allow for full contact with the shank of the bolt. Bolts shall be placed by means of a template and shall be worked into concrete in vertical alignment.
10. Test Reporting: Test results must be reported to BSE and the General Contractor in writing within 24 hours after testing, via fax or email. Reports of compressive strength tests must contain the project name, the date of concrete placement, the location of concrete placement within the structure and the concrete mix design being used.

Structural Steel:

1. Bolts: Bolts that are not identified as being slip-critical nor in direct tension need not be inspected other than to verify that the plies of connected elements are brought into snug-tight condition in properly-aligned holes.
2. Field Welding: Inspection is required for single-pass fillet welds, multi-pass fillet welds, complete, and partial-penetration groove welds, floor and roof deck welding, and stairs and railing systems. Prior to the start of the work, materials, qualifications of welding procedures and welder qualifications shall be verified. Provide continuous or periodic inspection of the structural welding as indicated in Table 1704.3 of the referenced IBC. Inspections may occur periodically, as defined below. A visual inspection to ensure proper type, size, length and quality of all field welds is required prior to work being concealed by other materials.
3. Periodic inspection: "Periodic" is defined as generally once a week at a minimum, and more often as needed to observe work requiring inspections, as outlined above, prior to being covered by subsequent construction.
4. Shear connector stud welds will be inspected and tested according to AWS D1.1 for stud welding. Shear connector stud welds shall be visually inspected. Bend tests shall be performed if visual inspections reveal less than a 360-degree flash or welding repairs to any shear connector stud.
5. Structural steel bar joists and metal buildings fabricated on the premises of a facility/plant not certified by a nationally recognized organization, shall have in-plant special inspections. AISC, ICBO, CWB and SJI are certified fabricators.
6. Test Reporting: Test results must be reported to BSE and the General Contractor in writing within 24 hours of testing, via fax or email. Reports must contain the project name, the date of the test and the location of the test.

Masonry:

1. Mortar properties, grout, brick, concrete masonry unit and prism tests and evaluations are to be performed during construction for each 5,000 sq. ft. of wall area or portion thereof.
2. Mortar properties are to be tested per ASTM C 780.
3. Grout will be sampled and tested for compressive strength per ASTM C 1019.
4. Brick tests for each type and grade of brick indicated are to be performed according to ASTM C 67.
5. Concrete masonry unit tests for each type of concrete masonry unit indicated are to be performed per ASTM C 140.
6. Masonry prisms are to be tested per ASTM C 1314. Prepare one (1) set of prisms for testing at 7 days and one (1) set for testing at 28 days.
7. Special inspection of masonry construction is required during preparation and taking of any required prisms or test specimens, placing of all masonry units, placement of reinforcement and inspection of grout space immediately prior to closing cleanouts, and during all grouting operations.
8. Test Reporting: Test results must be reported to BS and the general contractor in writing within 24 hours of testing, via fax. Reports must contain the project name, the date of the test and the location of the test.

Required Verification and Inspection of Steel Construction Other Than Structural Steel Per IBC Table 1705.2.2			
Type	Continuous Special Inspection	Periodic Special Inspection	Referenced Standard
1. Material verification of cold-formed steel deck: <div>a. Identification markings to conform to ASTM standards specified in the approved construction documents.</div> <div>b. Manufacturer's certified test reports.</div>	-	X	Applicable ASTM material standards
2. Inspection of welding and attachment: <div>a. Cold-formed steel deck:<div>1. Floor and roof deck welds and other means of attachment.</div></div> <div>b. Reinforcing steel:<div>1. Verification of edibility of reinforcing steel other than ASTM A 706.</div><div>2. Reinforcing steel resisting flexural and axial forces in intermediate and special moment frames, and boundary elements of special structural walls of concrete and shear reinforcement.</div><div>3. Shear reinforcement.</div><div>4. Other reinforcing steel.</div></div>	-	X	AWS D1.3
			AWS D1.4 ACI 318: Section 3.5.2

a. Where applicable, see also Section 1705.11 Special inspections for seismic resistance.

Required Special Inspections and Tests of Concrete Construction Per IBC Table 1705.3			
Type	Continuous Special Inspection	Periodic Special Inspection	Referenced Standard
1. Inspect reinforcement, including prestressing tendons, and verify placement.	-	X	ACI 318 Chp. 20, 25.2, 25.3, 26.6.1-.26.6.3.
2. Reinforcing bar welding: <div>a. Verify weldability of reinforcing bars other than ASTM A706</div> <div>b. Inspect single-pass fillet welds, maximum 5/16"; and</div> <div>c. Inspect all other welds.</div>	-	X	AWS D1.4 ACI 318: 26.6.4
3. Inspect anchors cast in concrete.	-	X	ACI 318: 17.8.2
4. Inspect anchors post-installed in hardened concrete members <div>a. Adhesive anchors installed in horizontally or upwardly inclined orientations to resist sustained tension loads.</div> <div>b. Mechanical anchor and adhesive anchors not defined in 4.a.</div>	X	-	ACI 318: 17.8.2.4
	-	X	ACI 318: 17.8.2.
5. Verify use of required design mix.	-	X	ACI 318: Chp. 19, 26.4.3, 26.4.4
6. Prior to concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the concrete.	X	-	ASTM C172 ASTM C31 ACI 318: 26.4, 26.12
7. Inspect concrete and shotcrete placement for proper application techniques.	X	-	ACI 318: 26.5
8. Verify maintenance of specified curing temperatures and techniques.	-	X	ACI 318: 26.5.3-26.5.5
9. Inspect prestressed concrete for: <div>a. Application of prestressing forces; and</div> <div>b. Grouting of bonded prestressing tendons.</div>	X X	-	ACI 318: 26.10
10. Inspect erection of precast concrete members.	-	X	ACI 318: Chp. 26.8
11. Verify in-situ concrete strength, prior to stressing of tendons in post-tensioned concrete and prior to removal of shores and forms from beams and structural slabs.	-	X	ACI 318: 26.11.2
12. Inspect framework for shape, location and dimensions of the concrete member being formed.	-	X	ACI 318: 26.11.1.2(B)

a. Where applicable, see also Section 1705.12, Special inspections for seismic resistance.
b. Specific requirements for special inspection shall be included in the research report for the anchor issued by an approved source in accordance with 17.8.2 in ACI 318, or other qualification procedures. Where specific requirements are not provided, special inspection requirements shall be specified by the registered design professional and shall be approved by the building official prior to the commencement of the work.

Required Special Inspections and Tests of Soils Per IBC Table 1705.6		
Type	Continuous Special Inspection	Periodic Special Inspection
1. Verify materials below shallow foundations are adequate to achieve the design bearing capacity.	-	X
2. Verify excavations are extended to proper depth and have reached proper material.	-	X
3. Perform classification and testing of compacted fill materials.	-	X
4. Verify use of proper materials, densities and lift thicknesses during placement and compaction of compacted fill.	X	-
5. Prior to placement of compacted fill, inspect subgrade and verify that site has been prepared properly.	-	X

Required Special Inspections and Tests of Driven Deep Foundation Elements Per IBC Table 1705.7		
Type	Continuous Special Inspection	Periodic Special Inspection
1. Verify element materials, sizes and lengths comply with the requirements.	X	-
2. Determine capacities of test elements and conduct additional load tests, as required.	X	-
3. Inspect driving operations and maintain complete and accurate records for each element.	X	-
4. Verify placement locations and plumbness, confirm type size of hammer, record number of blows per foot of penetration, determine required penetrations to achieve design capacity, record tip and butt elevations and document any damage to foundation element.	X	-
5. For steel elements, perform additional special inspections in accordance with Section 1705.2.	-	-
6. For concrete elements and concrete-filled elements, perform tests and additional special inspections in accordance with Section 1705.3.	-	-
7. For specialty elements, perform additional inspections as determined by the registered design professional in responsible charge.	-	-

Required Quality Control Inspections (QCI) & Quality Assurance Inspections (QAI) of Steel Construction Per AISC 360, Specification Chapter M & N		
Type	Frequency of Inspections	Referenced Standard
1. The fabricator's QCI shall inspect the following as a minimum, as applicable: <div>a. Shop welding, high strength bolting and details in accordance with AISC 360, Section N5.</div> <div>b. Shop cut and finished surfaces in accordance with AISC 360, section M2.</div> <div>c. Shop heating for straightening, cambering and curving in accordance with AISC 360, Section M2.1.</div> <div>d. Tolerances for shop fabrication in accordance with the Code of Standard Practice, Section 6.</div>	Per AISC Per AISC Per AISC	AISC 360 Chp. M & N TABLE N5.4-1 TABLE N5.4-2 TABLE N5.4-3 TABLE N5.6-1 TABLE N5.6-2 TABLE N5.6-3 TABLE N6.1 Code of Standard Practice Sec. 6
2. The erector's QCI shall inspect the following as a minimum, as applicable: <div>a. Field welding, high strength bolting and details in accordance with AISC 360, Section N5.</div> <div>b. Steel deck and headed steel stud anchor placement and attachment in accordance with AISC 360, Section N6.</div> <div>c. Field cut surfaces in accordance with AISC 360, Section M2.2.</div> <div>d. Field heating for straightening in accordance with AISC 360, Section M2.1.</div> <div>e. Tolerances for field erection in accordance with the Code of Standard Practice, Section 7.13.</div>	Per AISC Per AISC Per AISC Per AISC	AISC 360 Chp. M&N TABLE N5.4-1 TABLE N5.4-2 TABLE N5.4-3 TABLE N5.6-1 TABLE N5.6-2 TABLE N5.6-3 TABLE N6.1 Code of Standard Practice Sec. 6
3. QAI shall be performed by others. All required inspection and non-destructive testing, as applicable, shall be in accordance with AISC 360	Per AISC & IBC	AISC 360 Chp. M&N

Required Special Inspections and Tests of Masonry Per IBC Table 1705.4				
LEVEL A - QUALITY ASSURANCE				
MINIMUM TESTS				
None				
MINIMUM INSPECTION				
Verify compliance with the approved submittals				
LEVEL B - QUALITY ASSURANCE				
MINIMUM TESTS				
Verification of Slump flow and Visual Stability Index (VSI) as delivered to the project site in accordance with Specification Article 1.5 B.1.b.3 for self-consolidating grout				
Verification of $f_{m'}$ and f_{acc} in accordance with Specification Article 1.4 B prior to construction, expect where specifically exempted by Code				
MINIMUM INSPECTION				
Type	FREQUENCY ^(a)		REFERENCE FOR CRITERIA	
	Continuous	Periodic	TMS 402/ACI 530/ASCE 5	TMS 602/ACI 530.1/ASCE 6
1. Verify compliance with the approved submittals	X			Art. 1.5
2. As masonry construction begins, verify that the following are in compliance:				
a. Proportions of site-prepared mortar		X		Art. 2.1, 2.6 A
b. Construction of mortar joints		X		Art. 3.3 B
c. Grade and size of prestressing tendons and anchorages		X		Art. 2.4 B, 2.4 H
d. Locations of reinforcement, connectors, and prestressing tendons and anchorages		X		Art. 3.4, 3.6 A
e. Prestressing technique		X		Art. 3.6 B
f. Properties of thin-bed mortar for ACC masonry	X ^(b)	X ^(c)		Art. 2.1 C
3. Prior to grouting, verify that the following are all in compliance:				
a. Grout space		X		Art. 3.2 D, 3.2 F
b. Grade, type and size of reinforcement and anchor bolts, and prestressing tendons and anchorages		X	SEC. 1.16	Art. 2.4, 3.4
c. Placement of reinforcement, connectors, and prestressing tendons and anchorings		X	SEC. 1.16	Art. 3.2 E, 3.4, 3.6 A
d. Proportions of site-prepared grout and prestressing grout for bonded tendons		X		Art. 2.6 B, 2.4 G.1.b
e. Construction of mortar joints		X		Art. 3.3 B
4. Verify during Construction:				
a. Size and Location of structural elements		X		Art. 3.3 F
b. Type, size and location of anchors, including other details of anchorage of masonry to structural members, frames or other construction		X	SEC 1.16.43, 1.17.1	
c. Welding of reinforcement	X		SEC 2.1.7.7.2, 3.3.3.4 (d), 8.3.3.4 (b)	
d. Preparation, construction and protection of masonry during cold weather (temperatures below 40° F) or hot weather (temperatures above 90° F)		X		Art. 1.8 C, 1.8 D
e. Application and measurement of prestressing forces	X			Art. 3.6 B
f. Placement of grout and prestressing grout for bonded tendons is in compliance	X			Art. 3.5, , 3.6 C
g. Placement of AAC masonry units and construction if thin-bed mortar joints	X ^(b)	X ^(c)		Art. 3.3 B.8
5. Observe preparation of grout specimens, mortar specimens, and/or prisms		X		Art. 1.4 B.2.a.3, 1.4 B.2.b.3, 1.4 B.2.c.3, 1.4 B.3, 1.4 B.4

(a) Frequency refers to the frequency of inspection, which may be continuous during the task listed or periodically during listed task, as defined in the table.
(b) Required for the first 5000 square feet AAC masonry
(c) Required after the first 5000 square feet AAC masonry



Architect of Record:
BRR Architecture, Inc.

8131 HETCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD
LEE'S SUMMIT, MO.



Drawn By:

AG

Checked By:

AG

Document Date:

08/15/2023

Protocolcycle:

WSS_v5_2023.1 (05/05/23)

Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal




Sheet Title

GENERAL NOTES

Sheet No.

S0.1



NOTES:
1.) ISOMETRIC VIEWS ARE SHOWN FOR SCHEMATIC PURPOSES ONLY.
ACTUAL CONSTRUCTION TO MATCH CONSTRUCTION DOCUMENTS.
REFERENCE ARCHITECTURAL, MECHANICAL, CIVIL, & STRUCTURAL
DOCUMENTS.



Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project, site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION

Project Name
WoodSpring Suites

Project Address
1010 NW WARD ROAD
LEE'S SUMMIT, MO.



Drawn By:
AG
Checked By:
AG
Document Date:
08/15/2023
Protocycle:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08


Project No.
31000541

Professional Seal



Sheet Title

8/15/2023 6:06:46 PM



NOTES:

1.) BUILDING SECTIONS ARE SHOWN FOR SCHEMATIC PURPOSES ONLY. ACTUAL CONSTRUCTION TO MATCH CONSTRUCTION DOCUMENTS. REFERENCE ARCHITECTURAL, MECHANICAL, CIVIL, & STRUCTURAL DOCUMENTS.

BUILDING SECTION | 01

3/8" = 1'-0" S0.3

brr

Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

**1010 NW WARD ROAD
LEE'S SUMMIT, MO.**

Drawn By:
AG
Checked By:
AG
Document Date:
08/15/2023
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.

31000541


Professional Seal

Sheet Title

BUILDING SECTION
Sheet No.
S0.3

BRR Original printed on recycled paper

8/15/2023 6:06:56 PM



- NOTES:
- SEE DRAWING S0.0 FOR GENERAL NOTES, SYMBOLS LEGEND, MATERIALS LEGEND, & ABBREVIATION LIST.
 - REFERENCE DRAWING S4.1 FOR TYPICAL FRAMING DETAILS.
 - SEE DRAWING S0.2 FOR ISOMETRIC VIEW & S0.3 FOR FULL BUILDING SECTIONS.
 - REFERENCE ARCHITECTURAL DRAWINGS TO VERIFY SIZE & LOCATIONS OF ALL ROOF & WALL OPENINGS.
 - COORDINATE STEEL HSS COLUMNS AND ALL MISC. STEEL WITH ELEVATOR MANUF.
 - # = DENOTES HEADER REFER TO SCHEDULE & TYP. DETAILS
 - ◁ = DENOTES SHEAR WALL SCHEDULE REFER TO SCHEDULE & TYP. DETAILS - SEE FOUNDATION PLAN HOLD DOWNS FOR EXTENTS OF SHEAR WALL BOUNDARIES
 - NOT ALL HEADER LOCATIONS ARE SHOWN REF. ARCH. DRAWINGS FOR ALL WALL OPENING LOCATIONS
 - CMU WALLS ARE 8" U.N.O.
 - G.C. & TRUSS MANUF. TO COORD. FLOOR TRUSS LOCATIONS W/ VERT. PIPE LOCATIONS PER M.E.P. & ARCH. DRAWINGS.
 - ★ INDICATES HOLD DOWN LOCATION - REFER TO TYP. DETAILS. IF NO HOLD DOWN PRESENT, REFER TO PLAN DIMENSIONS FOR SHEAR WALL BOUNDARY LOCATIONS.
 - G.C. TO COORDINATE FINAL LOCATION OF FLOOR FRAMING TO ACCOMMODATE PLUMBING CONDITIONS.
 - REFER TO CIVIL PLANS FOR BUILDING ORIENTATION AND LOCATION ON THE SITE.

3RD FLOOR FRAMING PLAN | 01

3/32" = 1'-0" S2.2



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD
LEE'S SUMMIT, MO.



Drawn By:

AG

Checked By:

AG

Document Date:

08/15/2023

Protocol:

WSS_v5_2023.1 (05/05/23)

Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal




Sheet Title

3RD FLOOR FRAMING
PLAN

Sheet No.

S2.2

BRR Original printed on recycled paper




NOTE:
1.) ALL CORRIDOR SHEAR WALLS TO BE CONTINUALLY SHEATHED
2.) AT SHEATHING PANEL JOINTS NAILS SPACED 3" OR CLOSER
SHALL FASTEN TO 3X OR (2)2X MEMBERS

NOTE:
1.) UPSET HEADERS AS REQ'D. & PROVIDE SIMPSON HANGER
2.) BEARING STUDS REQUIRED AT EACH END OF HEADER PER HEADER SCHEDULE

8/15/2023 6:07:00 PM

10/5/2023 11:40:10 AM




SHEAR WALL SCHEDULE						
SHEAR WALL MARK	SHEATHING MATERIAL	PANEL EDGE BLOCKING	FASTENING	FLOOR-TO-FLOOR CONNECTION AT LEVEL ABOVE	HOLD DOWN AT FOUNDATION	SILL PLATE ANCHORS
1	7/16" APA RATED SHEATHING (1) SIDE	BLOCKED	8d NAILS @ 4" SPA. PERIMETER & 6" SPA. FIELD	(1) SIMPSON HDU8-SDS-2.5 W/ (3) 2X POST	(1) SIMPSON HD12 W/ 8X POST	1" Ø THREADED ROD ANCHORS - ANCHOR USING ADHESIVE ANCHORING SYSTEM - EMBED 10" MIN.
2	7/16" APA RATED SHEATHING (1) SIDE	BLOCKED	8d NAILS @ 4" SPA. PERIMETER & 12" SPA. FIELD	(1) SIMPSON HDU5-SDS-2.5 W/ 6X POST	N/A	N/A
3	7/16" APA RATED SHEATHING (1) SIDE	BLOCKED	8d NAILS @ 6" SPA. PERIMETER & 12" SPA. FIELD	(1) SIMPSON HDU2-SDS2.5 W/ (2) 2X POST	N/A	N/A
4	7/16" APA RATED SHEATHING (1) SIDE	BLOCKED	8d NAILS @ 6" SPA. PERIMETER & 12" SPA. FIELD	N/A	N/A	1/2" Ø CONC. SCREW ANCHOR @ 32" SPA. - EMBED 3 1/2" MIN.

NOTE:
1.) ALL CORRIDOR SHEAR WALLS TO BE CONTINUALLY SHEATHED.
2.) AT SHEATHING PANEL JOINTS NAILS SPACED 3" OR CLOSER SHALL FASTEN TO 3X OR (2)2X MEMBERS

HEADER/BEAM SCHEDULE			
MARK	SIZE	BEARING STUDS	KING STUDS
H1	(2) 2X8	(2) 2x4	(2) 2x4
H2	(2) 2X10	(2) 2x4	(2) 2x4
H3	(2) 2X12	(2) 2x6	(2) 2x4
H4	(3) 2X8	(2) 2x6	(2) 2x6
H5	(3) 2X10	(2) 2x6	(2) 2x6
H6	(3) 2X12	(2) 2x6	(2) 2x6
H7	(2) 1 3/4" x 16" 2.OE LVL	(2) 2x6	(2) 2x6
H8	(3) 1 3/4" x 16" 2.OE LVL	4X8	N/A
H9	(3) 1 3/4" x 16" 2.OE LVL	(3) 2x6	(2) 2x6
H10	(4) 1 3/4" x 16" 2.OE LVL	4x8 POST	N/A
H11	(5) 1 3/4" x 16" 2.OE LVL	4x8 POST	N/A

NOTE:
1.) UPSET HEADERS AS REQ'D. & PROVIDE SIMPSON HANGER
2.) BEARING STUDS REQUIRED AT EACH END OF HEADER PER HEADER SCHEDULE



SNOW DRIFT DIAGRAM | 02
3/8" = 1'-0" S2.4

- NOTES:
- SEE DRAWING S0.0 FOR GENERAL NOTES, SYMBOLS LEGEND, MATERIALS LEGEND, & ABBREVIATION LIST.
 - REFERENCE DRAWING S4.1 FOR TYPICAL FRAMING DETAILS.
 - SEE DRAWING S0.2 FOR ISOMETRIC VIEW & S0.3 FOR FULL BUILDING SECTIONS.
 - REFERENCE ARCHITECTURAL DRAWINGS TO VERIFY SIZE & LOCATIONS OF ALL ROOF & WALL OPENINGS.
 - COORDINATE STEEL HSS COLUMNS AND ALL MISC. STEEL WITH ELEVATOR MANUF.
 - Ø = DENOTES HEADER REFER TO SCHEDULE & TYP. DETAILS
 - △ = DENOTES SHEAR WALL SCHEDULE REFER TO SCHEDULE & TYP. DETAILS - SEE FOUNDATION PLAN HOLD DOWNS FOR EXTENTS OF SHEAR WALL BOUNDARIES
 - NOT ALL HEADER LOCATIONS ARE SHOWN REF. ARCH. DRAWINGS FOR ALL WALL OPENING LOCATIONS
 - CMU WALLS ARE 8" U.N.O.
 - G.C. & TRUSS MANUF. TO COORD. FLOOR TRUSS LOCATIONS W/ VERT. PIPE LOCATIONS PER M.E.P. & ARCH. DRAWINGS.
 - ★ INDICATES HOLD DOWN LOCATION - REFER TO TYP. DETAILS. IF NO HOLD DOWN PRESENT, REFER TO PLAN DIMENSIONS FOR SHEAR WALL BOUNDARY LOCATIONS.
 - G.C. TO COORDINATE FINAL LOCATION OF FLOOR FRAMING TO ACCOMMODATE PLUMBING CONDITIONS.
 - REFER TO CIVIL PLANS FOR BUILDING ORIENTATION AND LOCATION ON THE SITE.

brr
Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants
.....

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name
WoodSpring Suites

Project Address
**1010 NW WARD ROAD
LEE'S SUMMIT, MO.**











Drawn By:
AG
Checked By:
AG
Document Date:
08/15/2023
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541

Professional Seal

Sheet Title
.....

ROOF FRAMING PLAN
Sheet No.
S2.4
BRR Original printed on recycled paper



brr
Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project, site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name
WoodSpring Suites

Project Address
**1010 NW WARD ROAD
LEE'S SUMMIT, MO.**

Drawn By:
AG
Checked By:
AG
Document Date:
08/15/2023
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541


Professional Seal

Sheet Title
**FOUNDATION
DETAILS**

Sheet No.
S3.2


FOOTNOTES
BRR Original printed on recycled paper

8/15/2023 6:07:13 PM




TYP. MULTI FLOOR SHEAR WALL ELEVATION DETAIL | 01

1/2" = 1'-0" S4.1




TYP. MULTI FLOOR PERFORATED SHEAR WALL ELEVATION DETAIL | 02

1/2" = 1'-0" S4.1




TYP. TOP CHORD SPLICE DETAIL | 03

N.T.S. S4.1




ALLOWABLE WOOD NOTCHES & PENETRATIONS | 04

3/4" = 1'-0" S4.1




TYP. STUD PENETRATION - SHRINKAGE | 07

3/4" = 1'-0" S4.1




TYP. STUD PENETRATION DETAIL | 06

3/4" = 1'-0" S4.1




TYP. HEADER/WALL OPENING DETAIL | 08

N.T.S. S4.1




ALLOWABLE TJI WEB PENETRATIONS | 09

3/4" = 1'-0" S4.1




REQ'D BLOCKING @ CONDUIT/PIPE & FRAMING INTERFERENCE LOCATIONS | 10

1/2" = 1'-0" S4.1




TYP. FLOOR-TO- FLOOR HOLD DOWN DETAIL | 11

3/4" = 1'-0" S4.1




TYP. RIM BOARD SPLICE | 12

1/2" = 1'-0" S4.1



WOOD FRAMING CANOPY DETAIL | 15

3/4" = 1'-0" S4.1



WOOD CANOPY/TIE-ROD BLOCKING | 16

1 1/2" = 1'-0" S4.1



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD
LEE'S SUMMIT, MO.



Drawn By:

AG

Checked By:

AG

Document Date:

08/15/2023

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal




Sheet Title

TYPICAL FRAMING
DETAILS






Sheet No.

S4.1

BRR Original printed on recycled paper



$1\ 1/2'' = 1'-0''$	S4.2
---------------------	------


$$\frac{3}{4}'' = 1'-0'' \quad \$4.2$$


Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD
LEE'S SUMMIT, MO.



Drawn By:

AG

Checked By:

AG

Document Date:

08/15/2023

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal




Sheet Title

TYPICAL STAIR
FRAMING PLAN &
DETAILS

Sheet No.

S4.3




NOTES:

- SEE DRAWING S0.0 FOR GENERAL NOTES, SYMBOLS LEGEND, MATERIALS LEGEND, & ABBREVIATION LIST.
- REFERENCE DRAWING S4.1 FOR TYPICAL FRAMING DETAILS.
- SEE DRAWING S0.1 FOR ISOMETRIC VIEW & S0.2 FOR FULL BUILDING SECTIONS.
- REFERENCE ARCHITECTURAL DRAWINGS TO VERIFY SIZE & LOCATIONS OF ALL ROOF & WALL OPENINGS.


TYP. STAIR FRAMING PLAN | 01

1/4" = 1'-0" | S4.3




SECTION | 02

3/4" = 1'-0" | S4.3




SECTION | 03

3/4" = 1'-0" | S4.3




SECTION | 04

3/4" = 1'-0" | S4.3




SECTION | 05

3/4" = 1'-0" | S4.3






SECTION | 06

3/4" = 1'-0" | S4.3







SECTION | 07

3/4" = 1'-0" | S4.3




SECTION | 05

3/4" = 1'-0" S4.5




SECTION | 06

3/4" = 1'-0" S4.5



SECTION | 07

1 1/2" = 1'-0" S4.5



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD
LEE'S SUMMIT, MO.



Drawn By:

AG

Checked By:

AG

Document Date:

08/15/2023

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal




Sheet Title

FRAMING DETAILS

Sheet No.


S4.5

BRR Original printed on recycled paper




SECTION | 01

3/4" = 1'-0" S4.6



SECTION | 02

3/4" = 1'-0" S4.6



SECTION | 03

3/4" = 1'-0" S4.6

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name

WoodSpring Suites

Project Address

**1010 NW WARD ROAD
LEE'S SUMMIT, MO.**



Drawn By:
AG
Checked By:
AG
Document Date:
08/15/2023
Protocolcycle:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal



Sheet Title

FRAMING DETAILS
Sheet No.
S4.6

BRR Original printed on recycled paper



www.brrarch.com

tel: 913-262-9095
fax: 913-262-9044

consultants



Copyright Notice

This drawing was prepared for use on a specific project contemporaneously with its issue date and is not suitable for use on a different project, site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

[illegible]

Project Name

WoodSpring Suites

Project Address

010 NW WARD ROAD
EE'S SUMMIT, MO.



Drawn By:

Checked By

GL

Document Date: 12/17/2025

08/15/2023

rotocycle:

VSS_v5_2023.1 (05/05/2

Bulletins Through:

Project No.

31000541



Sheet Title


PARAPET FRAMING DETAILS

Sheet No.

S4.7


BRR Original printed on recycled paper

8/15/2023 6:07:21 PM




TRASH ENCLOSURE PLAN | 01

1/2" = 1'-0" | SS.2



TYP. TRASH ENCLOSURE SECTION | 02

3/4" = 1'-0" | SS.2



Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION

Project Name
WoodSpring Suites

Project Address
1010 NW WARD ROAD
LEE'S SUMMIT, MO.



Drawn By:
AG
Checked By:
AG
Document Date:
08/15/2023
Protocycle:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08


Project No.
31000541

Professional Seal



Sheet Title
TRASH ENCLOSURE
FRAMING PLAN AND
DETAILS

Sheet No.
S5.2



1 FIRST FLOOR PLAN
1/8" = 1'-0"



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160


Sheet Title

FIRST FLOOR PLAN


Sheet No.

A1.1

BRR Original printed on recycled paper



1 SECOND FLOOR PLAN
1/8" = 1'-0"



1 THIRD FLOOR PLAN
1/8" = 1'-0"

brr
Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project, site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

Drawn By:
JP

Checked By:
JL

Document Date:
08/16/23

Protocol:
WSS_v5_2023.1 (05/05/23)

Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal

STATE OF MISSOURI
TREVOR TYSON HOLCOMB
ARCHITECT
NUMBER
A-2022000409
ARCHITECT

08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title

THIRD FLOOR PLAN

Sheet No.

A1.3

NORTH

BRR Original printed on recycled paper

Copyright Notice

This drawing was prepared for use on a specific project contemporaneously with its issue date and is not suitable for use on a different project or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

[illegible]

Project Name

WoodSpring Suites

Project Address

010 NW WARD ROAD LEE
SUMMIT, MO



Drawn By:

Checked By _____

L

Document Date
08/16/22

08/16/23

protocol:

VSS_V5_

Bulletins Thru
1122 2 1

VSS_v2_1


100

Project No. _____

210005

10005

Discussion



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
 LICENSE NO. 2022000409

BRR ARCHITECTURE, INC.

CHITECTURAL CORPORATION
OURI LICENSE NO. ARC 00016

Figure 1. 1998-1999


Sheet Title

FOURTH FLOOR PLAN

Sheet No.


A1.4

BRR Original printed on recycled paper



8/16/2023 12:49:50 PM

8/16/2023 12:49:54 PM



1 FIRST FLOOR RCP
1/8" = 1'-0"



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT

LICENSE NO. 2022000409

BRR ARCHITECTURE, INC.

ARCHITECTURAL CORPORATION

MISSOURI LICENSE NO. ARC 000160

Sheet Title


FIRST FLOOR RCP

Sheet No.

A1.6

BRR Original printed on recycled paper

10/6/2023 2:41:58 PM



1 TYPICAL UPPER FLOOR RCP
1/8" = 1'-0"

brr
Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for use on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV #2

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocycle:

WSS_v5_2023.1 (05/05/23)

Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal

STATE OF MISSOURI

TREVOR TYSON HOLCOMB

ARCHITECT

NUMBER A-2022000409

10/09/2023

TREVOR TYSON HOLCOMB

ARCHITECT

LICENSE NO. 2022000409

BRR ARCHITECTURE, INC.

ARCHITECTURAL CORPORATION

MISSOURI LICENSE NO. ARC 000160

Sheet Title

TYPICAL FLOOR RCP


Sheet No.

A1.7

NORTH

BRR Original printed on recycled paper

8/16/2023 12:49:57 PM



1 FIRST FLOOR FINISH PLAN
1/8" = 1'-0"

REFERENCE SPEC FOR
ELEVATOR FINISH
INFORMATION

PAINT CORRIDOR WALLS
SW7065 "ARGOS". REFER TO
PLANS FOR ACCENT WALL
COLOR LOCATIONS

PAINT GYP CEILINGS SW7636
"ORIGAMI WHITE" UNLESS
NOTED OTHERWISE

KEY			
	LVT-1		ACCENT WALL (PAINT), REF G1.1 - FINISH SCHEDULE FOR COLOR
	LVT-2		ACCENT WALL (WALL COVERING), REF G1.1 - FINISH SCHEDULE
	CARPET		WALL PROTECTION: 2'-0" OR 4'-0" HIGH, REF INTERIOR ELEVATIONS AND SPECS
	SEALED CONCRETE (SC) / GYPCRETE (GC)		WALL BUMPER GUARD AT TOP OF WALL PROTECTION, REF SPECS
	RUBBER FLOOR TILES		
	RUBBER - STAIR TREADS, RISERS AND LANDINGS		

PROVIDE CONCRETE
HOUSEKEEPING PAD
MINIMUM 4" HIGH AND 6"
LARGER THAN WATER
HEATERS ON EACH SIDE
OR ON LISTED AND
APPROVED SHELF, REF
STRUC AND MEP

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)


Revisions Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title

FIRST FLOOR FINISH
PLAN

Sheet No.

A1.8

BRR Original printed on recycled paper

10/6/2023 2:42:01 PM



1 TYP. UPPER FLOOR FINISH PLAN
1/8" = 1'-0"

REFERENCE SPEC FOR
ELEVATOR FINISH
INFORMATION

PAINT CORRIDOR WALLS
SW7065 "ARGOS". REFER TO
PLANS FOR ACCENT WALL
COLOR LOCATIONS

PAINT GYP CEILINGS SW7636
"ORIGAMI WHITE" UNLESS
NOTED OTHERWISE

KEY			
	LVT-1		ACCENT WALL (PAINT), REF G1.1 - FINISH SCHEDULE FOR COLOR
	LVT-2		ACCENT WALL (WALL COVERING), REF G1.1 - FINISH SCHEDULE
	CARPET		WALL PROTECTION: 2'-0" OR 4'-0" HIGH, REF INTERIOR ELEVATIONS AND SPECS
	SEALED CONCRETE (SC) / GYPCRETE (GC)		WALL BUMPER GUARD AT TOP OF WALL PROTECTION, REF SPECS
	RUBBER FLOOR TILES		
	RUBBER - STAIR TREADS, RISERS AND LANDINGS		



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV #2

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)

Revisions Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



10/09/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title

TYPICAL UPPER
FLOOR FINISH PLAN

Sheet No.

A1.9





BRR Original printed on recycled paper



8/31/2023 1:57:12 PM

KEYNOTE LEGEND	
1.01	SIGNAGE BY OWNER; UNDER SEPARATE PERMIT, CONTRACTOR TO COORDINATE BLOCKING WITH MANUFACTURER
4.01	ADHERED MANUFACTURED STONE VENEER: REF INSTALLATION DETAIL 6-A2.2
4.02	ADHERED MANUFACTURED STONE VENEER DRIPLEGE
5.01	ALUMINUM GUTTERS AND DOWNSPOUTS
6.01	EIFS TRIM: 2-1/2"x4"
6.02	CEMENT BOARD TRIM AT STONE: 5/4"x4"
6.03	TRIM FASCIA
7.02	1-1/2" EXTERIOR EIFS: SEE COLOR SCHEDULE
7.03	1-1/2" EXTERIOR EIFS PARAPET: SEE COLOR SCHEDULE
7.06	SCUPPER
7.07	OVERFLOW SCUPPER
8.02	HOLLOW METAL DOOR
8.03	SLIDING WINDOW, TYP.: SEE SPECS
15.01	THRU-WALL HVAC UNIT
16.01	LIGHT WALL PACK, REF ELEC. DWGS.

COLOR SCHEDULE:


-  COLOR: SW7646 "FIRST STAR"
 COLOR: SW7024 "FUNCTIONAL GRAY"
 COLOR: SW7674 "PEPPERCORN"
 COLOR: SW3079 "STONE"

NOTES:


1. GC TO COORDINATE ELECTRICAL, ROUGH-IN WITH CONTRACTOR AND SIGN VENDOR PRIOR TO DRYWALL.
2. REFER TO SIGN PACKAGE FOR ALL BLOCKING AND MOUNTING DETAILS.
3. ALIGN EXHAUST VENTS BOTH VERTICAL AND HORIZONTAL.
4. EXTERIOR SIGNAGE: OWNER TO COORDINATE WITH SIGN VENDOR AND LOCAL JURISDICTION.
5. EXTERIOR DOWNSPOUTS, PARAPET CAP AND FLASHING TO BE SELECTED FROM MANUFACTURER'S STANDARD COLORS TO MATCH ADJACENT FINISHES, SUBMIT FOR APPROVAL.
6. ALL CORNER TRANSITIONS OCCUR AT INSIDE CORNERS NOT OUTSIDE CORNERS.

GENERAL NOTE:

PROVIDE WEATHER BARRIER OVER ALL EXTERIOR SHEATHING PRIOR TO THE INSTALLATION OF ANY EXTERIOR FINISH MATERIAL. INSTALL PER MANUFACTURER'S SPECIFICATIONS AND PROVIDE ALL MANUFACTURER'S ACCESSORIES TO FULLY FLASH AND COUNTER-FLASH AT ALL WINDOWS, DOORS, AND EXTERIOR PENETRATIONS. PROVIDE A WEATHER TIGHT BARRIER AT ALL SURFACES. COORDINATE FLASHING WITH WINDOW, DOOR, VENT, ETC. MANUFACTURERS' FOR A WEATHERTIGHT SEAL AT ALL OPENINGS.




2 LEFT SIDE ELEVATION
1/8" = 1'-0"



1 RIGHT SIDE ELEVATION

ROOF LINE AND HEAT PUMPS ADDED TO ELEVATIONS FOR THE FINAL DEVELOPMENT PLAN REVIEW REQUIREMENTS.

NOTE: THIS SHEET IS
INTENDED TO BE PRINTED
IN COLOR FOR CLARITY.



10/09/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409

BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title

EXTERIOR ELEVATIONS

Sheet No.

A2.2



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project, site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

**1010 NW WARD ROAD LEE'S
SUMMIT, MO**



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160


Sheet Title

BUILDING SECTIONS

Sheet No.


A3.1

BRR Original printed on recycled paper




4 BUILDING CROSS SECTION

3/16" = 1'-0"




3 BUILDING CROSS SECTION

3/16" = 1'-0"



2 BUILDING CROSS SECTION

3/16" = 1'-0"




1 BUILDING CROSS SECTION

3/16" = 1'-0"


8/16/2023 12:50:11 PM

8/16/2023 12:50:13 PM




TYP EXTERIOR WALL
AT STAIR TOWER

4
3/8" = 1'-0"



TYP EXTERIOR WALL AT
BUILDING MID SECTION

2
3/8" = 1'-0"



TYP EXTERIOR WALL AT ENTRANCE

1
3/8" = 1'-0"

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)

Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title

WALL SECTIONS


Sheet No.

A3.2


BRR Original printed on recycled paper

8/16/2023 12:50:15 PM



9 TYP CORRIDOR SECTION
3/8" = 1'-0"




3 TYP SHEARWALL SECTION
3/8" = 1'-0"



2 SHOWER PLUMBING WALL
1 1/2" = 1'-0"




6 ROLL-IN SHOWER DETAILS
1 1/2" = 1'-0"




8 TYP. CORRIDOR
3/4" = 1'-0"


5 WASHER DRAIN DETAILS
1" = 1'-0"



7 TYP @ 4TH FLOOR CORRIDOR
3/4" = 1'-0"



1 SECTION THRU TUB/SHOWER
1 1/2" = 1'-0"



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160


Sheet Title

WALL SECTIONS &
DETAILS

Sheet No.


A3.3

BRR Original printed on recycled paper




8/16/2023 12:50:19 PM


FIXTURE & EQUIPMENT LEGEND			
	QUANTITY	DESCRIPTION	NOTES
FT-100-EQ	2	932I TREADMILL	PROVIDED BY OWNER
FT-200-EQ	1	EFX 536I ELLIPTICAL FITNESS CROSSTRAINER	PROVIDED BY OWNER
FT-300-EQ	1	FTS GLIDE	PROVIDED BY OWNER
GL-100-EQ	5	QUANTUM COMMERCIAL TOP LOAD WASHER	PROVIDED BY OWNER
GL-200-EQ	1	QUANTUM COMMERCIAL FRONT LOAD WASHER	PROVIDED BY OWNER
GL-300-EQ	4	MICRO DISPLAY COMMERCIAL STACK DRYER	PROVIDED BY OWNER
LB-300-CG	1	SIDE CONSOLE	PROVIDED BY OWNER
LB-301-TA	1	COMMUNAL TABLE	PROVIDED BY OWNER
LB-302-TA	1	COFFEE TABLE	PROVIDED BY OWNER
LB-303-TA	1	SIDE TABLE	PROVIDED BY OWNER
LB-304-CD	1	COFFEE DISPENSER	PROVIDED BY OWNER
LB-305-AR	1	6'X8' AREA RUG	PROVIDED BY OWNER
LB-400-SG	1	SOFA	PROVIDED BY OWNER
LB-400.1-SG	2	SOFA PILLOW A FABRICATION	PROVIDED BY OWNER
LB-400.2-SG	2	SOFA PILLOW B FABRICATION	PROVIDED BY OWNER
LB-400.3-SG	1	SOFA PILLOW C FABRICATION	PROVIDED BY OWNER
LB-401-SG	1	LOUNGE CHAIR	PROVIDED BY OWNER
LB-402-SG	6	COUNTER STOOL	PROVIDED BY OWNER
LB-600-LT	1	FLOOR LAMP	PROVIDED BY OWNER
LB-601-LT	1	TABLE LAMP	PROVIDED BY OWNER
LB-700-ART	1	ARTWORK	PROVIDED BY OWNER
LB-701-VG	1	LEAF LOGO	PROVIDED BY OWNER
LC-1	2	LUGGAGE CART	PROVIDED BY OWNER
REF-2	1	REFRIGERATOR	PROVIDED BY GC
SL-100-EQ	2	MAYTAG MULTI-LOAD RIGID-MOUNT WASHER	PROVIDED BY GC
SL-200-EQ	2	MAYTAG COMMERCIAL ON-PREMISES DRYING TUMBLER	PROVIDED BY GC
SL-300-SS	3	SANDUSKYLEE BULK STORAGE RACK 77"X24"X72"	PROVIDED BY OWNER
SL-400-TA	1	HERITAGE FOLDING TABLE 30"X60"	PROVIDED BY OWNER
TR-301-TA	1	TABLE BASE 33"X33"	PROVIDED BY OWNER
TR-301-TAT	1	TABLE TOP 42" D	PROVIDED BY OWNER
TR-900-AC	1	WALL MOUNTED COAT RACK	PROVIDED BY OWNER
TR-400-SG	2	DESK CHAIR	PROVIDED BY OWNER



2 FIRST FLOOR FURNITURE PLAN
1/4" = 1'-0"



4 ENLARGED PLAN
1/4" = 1'-0"



1 FIRST FLOOR ENTRANCE PLAN
1/4" = 1'-0"

- GENERAL NOTES:
- GC TO COORDINATE DELIVERY AND STORAGE W/ FF&E SUPPLIER.
 - INTERIOR SIGNAGE PROVIDED AND INSTALLED BY OWNER'S VENDOR.
 - GC TO INSTALL OWNER FURNISHED GROMMETS. GC TO COORDINATE WITH OWNER FOR THE LOCATION, SIZE AND NUMBER OF GROMMET HOLES AT OFFICE COUNTER FOR OFFICE EQUIPMENT CABLES AND WIRING.
 - PROVIDE WEATHER STRIP AROUND DRYER TO INSULATE FROM AIR INTAKE BY LOUVER
 - REF. DIMENSIONS OF MECHANICAL WALL PENETRATIONS ON MECHANICAL DRAWINGS.
 - PROVIDE FULL HEIGHT CORNER GUARDS AT ALL PUBLIC AREA 90° CORNERS. REF SPECS FOR COLORS.

brr
Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project, site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for use on another project is not authorized and may be contrary to the law.

Issues & Revisions
NO. DATE DESCRIPTION

Project Name
WoodSpring Suites

Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO

Drawn By:
JP
Checked By:
JL
Document Date:
08/16/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541


Professional Seal
STATE OF MISSOURI
TREVOR TYSON HOLCOMB
ARCHITECT
NUMBER
A-2022000409
08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160


Sheet Title
ENLARGED PUBLIC PLANS
Sheet No.
A4.1

BRR Original printed on recycled paper

12/7/2023 10:03:17 AM



2 FIRST FLOOR FINISH PLAN
3/16" = 1'-0"



1 FIRST FLOOR REFLECTED CEILING PLAN
3/16" = 1'-0"

CEILING FINISH KEY	FLOOR FINISH KEY
<div></div> 2x2' ACOUSTICAL CEILING TILE	<div></div> LVT-1
<div></div> FR GYP BD WITH KNOCK DOWN TEXTURE	<div></div> LVT-2
<div></div> FR GYP BD	<div></div> RUBBER FLOOR TILE
<div></div> SURFACE/RECESSED LIGHT FIXTURE	<div></div> CARPET
<div></div> FLUORESCENT LIGHT FIXTURE	<div></div> WALL PROTECTION, 2'-0" OR 4'-0" HIGH, REF INTERIOR ELEVATIONS AND SPECS
<div></div> PENDANT LIGHT FIXTURE, REF ELECTRICAL	<div></div> WALL BUMPER GUARD AT TOP OF WALL PROTECTION, REF SPECS
<div></div> ALL CEILING LIGHTS TO BE CENTERED WITHIN CEILING TILES	
<div></div> EXIT LIGHT FIXTURE, REF ELEC	
PAINT GYP CEILINGS SW7636 "ORIGAMI WHITE" UNLESS NOTED OTHERWISE	

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for use on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
3	12/08/23	REV #3

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

Drawn By:

JP

Checked By:

DL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)

Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal

STATE OF MISSOURI

TREVOR TYSON HOLCOMB

ARCHITECT

NUMBER

A-2022000409

12/07/2023

TREVOR TYSON HOLCOMB

ARCHITECT

LICENSE NO. 2022000409

BRR ARCHITECTURE, INC.

ARCHITECTURAL CORPORATION

MISSOURI LICENSE NO. ARC 000160

Sheet Title

ENLARGED FINISH PLANS

Sheet No.

A4.2


BRR Original printed on recycled paper

8/16/2023 12:50:24 PM


QUEEN SUITE FIXTURE & EQUIPMENT LEGEND			
	QUANTITY	DESCRIPTION	PROVIDED BY:
GR-300-CG	1	QUEEN HEADBOARD - PLAM	OWNER
GR-301-CG	1	NIGHTSTAND - 20"	OWNER
GR-302-CG	1	CLOSET - 27"	OWNER
GR-304-CG	1	DRESSER	OWNER
GR-305-CG	1	DESK - 2'-10"	OWNER
GR-308-CG	1	CUBBY	OWNER
GR-400-SG	1	LOUNGE CHAIR	OWNER
GR-402-SG	1	DESK CHAIR	OWNER
GR-500-BDS	1	QUEEN MATTRESS	OWNER
GR-501-BDS	1	QUEEN BED FRAME	OWNER
GR-502-BD	1	QUEEN MATTRESS PAD	OWNER
GR-503-BD	1	QUEEN CUMULUS TOP COVER	OWNER
GR-504-BD	1	QUEEN XL FLAT SHEET	OWNER
GR-505-BD	1	QUEEN SNOWSTORM BLANKET	OWNER
GR-506-BD	1	QUEEN BEDSKIRT FABRICATION	OWNER
GR-514-BD	2	STANDARD PILLOWCASE	OWNER
GR-521-WT	1	WINDOW BLINDS	OWNER
GR-600-LT	1	TABLE LAMP	OWNER
GR-703-ART	1	WALL ARTWORK	OWNER
REF-1	1	REFRIGERATOR	GC
CT-1	1	STOVE TOP	GC

NOTE:
PROVIDE WOOD BLOCKING FOR ALL WALL MOUNTED ITEMS SHOWN, INCLUDING ITEMS FURNISHED AND INSTALLED BY OWNER.


SYMBOL LEGEND	
	RECEPTACLE
	PHONE/DATA OUTLET
	SWITCH
	TELEVISION
	SPECIAL OUTLET
	LIGHT/TIME DELAY SWITCH
REF ELECTRICAL FOR SWITCH AND RECEPTACLE INFORMATION	




7 QS - ENTRY WALL
1/2" = 1'-0"




5 QS - BED WALL
1/2" = 1'-0"




6 QS - TV WALL
1/2" = 1'-0"




4 QS - WINDOW WALL
1/2" = 1'-0"



3 QS - ELECTRICAL
3/8" = 1'-0"



2 QS - FURNITURE
3/8" = 1'-0"



1 QS - ARCHITECTURAL
3/8" = 1'-0"

brr
Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for use on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV #2

Project Name
WoodSpring Suites

Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO

Drawn By:
JP
Checked By:
JL
Document Date:
08/16/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541

Professional Seal

10/09/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title
GUESTROOM - QUEEN SUITE

Sheet No.
A5.1


BRR Original printed on recycled paper

10/6/2023 2:42:10 PM



ACC QUEEN SUITE FIXTURE & EQUIPMENT LEGEND			
	QUANTITY	DESCRIPTION	PROVIDED
GR-300-CG	1	QUEEN HEADBOARD - PLAM	OWNER
GR-301-CG	1	NIGHTSTAND - 20"	OWNER
GR-302.2-CG	1	CLOSET - 24"	OWNER
GR-304-CG	1	DRESSER	OWNER
GR-305.1-CG	1	DESK - 3'-6"	OWNER
GR-308-CG	1	CUBBY	OWNER
GR-400-SG	1	LOUNGE CHAIR	OWNER
GR-402-SG	1	DESK CHAIR	OWNER
GR-500-BDS	1	QUEEN MATTRESS	OWNER
GR-501-BDS	1	QUEEN BED FRAME	OWNER
GR-502-BD	1	QUEEN MATTRESS PAD	OWNER
GR-503-BD	1	QUEEN CUMULUS TOP COVER	OWNER
GR-504-BD	1	QUEEN XL FLAT SHEET	OWNER
GR-505-BD	1	QUEEN SNOWSTORM BLANKET	OWNER
GR-506-BD	1	QUEEN BEDSKIRT FABRICATION	OWNER
GR-514-BD	2	STANDARD PILLOWCASE	OWNER
GR-521-WT	1	WINDOW BLINDS	OWNER
GR-600-LT	1	TABLE LAMP	OWNER
GR-700A-MR	1	DECORATIVE FRAMED MIRROR ADA	OWNER
GR-703-ART	1	WALL ARTWORK	OWNER
REF-2	1	REFRIGERATOR (ADA)	GC
CT-1	1	STOVE TOP	GC

NOTE:
PROVIDE WOOD BLOCKING FOR ALL WALL MOUNTED ITEMS SHOWN, INCLUDING ITEMS FURNISHED AND INSTALLED BY OWNER.


SYMBOL LEGEND	
	RECEPTACLE
	PHONE/DATA OUTLET
	SWITCH
	TELEVISION
	SPECIAL OUTLET
	LIGHT/TIME DELAY SWITCH
REF ELECTRICAL FOR SWITCH AND RECEPTACLE INFORMATION	





5 ACC. QS - ELECTRICAL
3/8" = 1'-0"




7 ACC. QS - BED WALL
1/2" = 1'-0"





4 ACC. QS - ELECTRICAL
3/8" = 1'-0"




6 ACC. QS - TV WALL
1/2" = 1'-0"





3 ACC. QS - FURNITURE
3/8" = 1'-0"




6 ACC. QS - TV WALL
1/2" = 1'-0"



2 ACC. QS - ARCHITECTURAL
3/8" = 1'-0"



1 ACC. QS - ARCHITECTURAL
3/8" = 1'-0"



1 ACC. QS - ARCHITECTURAL
3/8" = 1'-0"



Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for use on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV #2

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO



Drawn By:

JP

Checked By:

DL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)

Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



10/09/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title

GUESTROOM - ACCESSIBLE QUEEN SUITE

Sheet No.


A5.2

BRR Original printed on recycled paper


DOUBLE QUEEN SUITE FIXTURE & EQUIPMENT LEGEND			
	QUANTITY	DESCRIPTION	PROVIDED BY:
GR-300-CG	2	QUEEN HEADBOARD - PLAM	OWNER
GR-301-CG	1	NIGHTSTAND - 20"	OWNER
GR-302.2-CG	2	CLOSET - 27"	OWNER
GR-304-CG	1	DRESSER	OWNER
GR-305.2-CG	1	DESK - 4'-0"	OWNER
GR-308-CG	1	CUBBY	OWNER
GR-402-SG	2	DESK CHAIR	OWNER
GR-500-BDS	2	QUEEN MATTRESS	OWNER
GR-501-BDS	2	QUEEN BED FRAME	OWNER
GR-502-BD	2	QUEEN MATTRESS PAD	OWNER
GR-503-BD	2	QUEEN CUMULUS TOP COVER	OWNER
GR-504-BD	2	QUEEN XL FLAT SHEET	OWNER
GR-505-BD	2	QUEEN SNOWSTORM BLANKET	OWNER
GR-506-BD	2	QUEEN BEDSKIRT FABRICATION	OWNER
GR-514-BD	4	STANDARD PILLOWCASE	OWNER
GR-521-WT	1	WINDOW BLINDS	OWNER
GR-600-LT	1	TABLE LAMP	OWNER
GR-701A-MR	1	DECORATIVE FRAMED MIRROR	OWNER
GR-703-ART	1	WALL ARTWORK	OWNER
REF-1	1	REFRIGERATOR	GC
CT-1	1	STOVE TOP	GC

NOTE:
PROVIDE WOOD BLOCKING FOR ALL WALL MOUNTED ITEMS SHOWN, INCLUDING ITEMS FURNISHED AND INSTALLED BY OWNER.


SYMBOL LEGEND	
	RECEPTACLE
	PHONE/DATA OUTLET
	SWITCH
	TELEVISION
	SPECIAL OUTLET
	LIGHT/TIME DELAY SWITCH
REF ELECTRICAL FOR SWITCH AND RECEPTACLE INFORMATION	




7 DOUBLE QS - ENTRY WALL
1/2" = 1'-0"




6 DOUBLE QS - TV WALL
1/2" = 1'-0"




5 DOUBLE QS - BED WALL
1/2" = 1'-0"




4 DOUBLE QS - WINDOW WALL
1/2" = 1'-0"



3 DOUBLE QS - ELECTRICAL
3/8" = 1'-0"



2 DOUBLE QS - FURNITURE
3/8" = 1'-0"



1 DOUBLE QS - ARCHITECTURAL
3/8" = 1'-0"

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for use on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV #2

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

WOODSPRING SUITES

Drawn By:
JP

Checked By:
JL

Document Date:
08/16/23

Protocol:
WSS_v5_2023.1 (05/05/23)

Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal

10/09/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title

GUESTROOM -
DOUBLE QUEEN
SUITE

Sheet No.

A5.3

BRR Original printed on recycled paper


DELUXE QUEEN SUITE FIXTURE & EQUIPMENT LEGEND			
QUANTITY	DESCRIPTION	PROVIDED BY:	
GR-300-CG	1 QUEEN HEADBOARD - PLAM	OWNER	
GR-301-CG	2 NIGHTSTAND - 16"	OWNER	
GR-302.2-CG	1 CLOSET - 4'-6"	OWNER	
GR-304-CG	1 DRESSER	OWNER	
GR-305.2-CG	1 DESK - 4'-0"	OWNER	
GR-308-CG	1 CUBBY	OWNER	
GR-401-SG	2 OTTOMAN	OWNER	
GR-402-SG	2 DESK CHAIR	OWNER	
GR-403-SG	1 SOFA-FULL SLEEPER	OWNER	
GR-500-BDS	1 QUEEN MATTRESS	OWNER	
GR-501-BDS	1 QUEEN BED FRAME	OWNER	
GR-502-BD	1 QUEEN MATTRESS PAD	OWNER	
GR-503-BD	1 QUEEN CUMULUS TOP COVER	OWNER	
GR-504-BD	1 QUEEN XL FLAT SHEET	OWNER	
GR-505-BD	1 QUEEN SNOWSTORM BLANKET	OWNER	
GR-506-BD	1 QUEEN BEDSKIRT FABRICATION	OWNER	
GR-514-BD	2 STANDARD PILLOWCASE	OWNER	
GR-521-WT	1 WINDOW BLINDS	OWNER	
GR-600-LT	2 TABLE LAMP	OWNER	
GR-701A-MR	1 DECORATIVE FRAMED MIRROR	OWNER	
GR-703-ART	1 WALL ARTWORK	OWNER	
REF-1	1 REFRIGERATOR	GC	
CT-1	1 STOVE TOP	GC	

NOTE:
PROVIDE WOOD BLOCKING FOR ALL WALL MOUNTED ITEMS SHOWN,
INCLUDING ITEMS FURNISHED AND INSTALLED BY OWNER.


SYMBOL LEGEND	
	RECEPTACLE
	PHONE/DATA OUTLET
	SWITCH
	TELEVISION
	SPECIAL OUTLET
	LIGHT/TIME DELAY SWITCH
REF ELECTRICAL FOR SWITCH AND RECEPTACLE INFORMATION	

OBTAIN CASE GOOD LINE DRAWINGS, COORDINATE AND FIELD VERIFY 2x10 BLOCKING AND ELECTRICAL DEVICE LOCATIONS


SILICONE CAULKING TO MATCH COLOR OF COUNTERTOP




7 DELUXE QS - TV WALL
1/2" = 1'-0"




5 DELUXE QS - BED WALL
1/2" = 1'-0"




6 DELUXE QS - ENTRY WALL
1/2" = 1'-0"




4 DELUXE QS - WINDOW WALL
1/2" = 1'-0"



3 DELUXE QS - ELECTRICAL
3/8" = 1'-0"









2 DELUXE QS - FURNITURE
3/8" = 1'-0"




1 DELUXE QS - ARCHITECTURAL
3/8" = 1'-0"


NO.	DATE	DESCRIPTION
2	10/04/23	REV #2

SYMBOL LEGEND	
	RECEPTACLE
	PHONE/DATA OUTLET
	SWITCH
	TELEVISION
	SPECIAL OUTLET
	LIGHT/TIME DELAY SWITCH
REF ELECTRICAL FOR SWITCH AND RECEPTACLE INFORMATION	


SILICONE CAULKING
TO MATCH COLOR
OF COUNTERTOP




7 ACC DELUXE QS - TV WALL
1/2" = 1'-0"




5 ACC DELUXE QS - WINDOW WALL
1/2" = 1'-0"




4 ACC DELUXE QS - BED WALL
1/2" = 1'-0"



3 ACC DELUXE QS - ELECTRICAL
3/8" = 1'-0"



2 ACC DELUXE QS - FURNITURE
3/8" = 1'-0"



1 ACC DELUXE QS - ARCHITECTURAL
3/8" = 1'-0"




This drawing was prepared for use on a specific site contemporaneously with its issue date and is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

[illegible]

WoodSpring Suites


1010 NW WARD ROAD LEE
SUMMIT, MO



Sheet No. _____

Sheet No. **A5.6**


10/6/2023 2:42:26 PM



ACCESSIBLE
BATHROOM
ELEVATION

10


1/2" = 1'-0"



ACCESSIBLE BATHROOM
ELEVATION

9


1/2" = 1'-0"



ACCESSIBLE BATHROOM
ELEVATION

8


1/2" = 1'-0"



ACCESSIBLE BATHROOM
ELEVATION

7


1/2" = 1'-0"



ACCESSIBLE BATHROOM

6


1/2" = 1'-0"



STANDARD BATHROOM
ELEVATION

5


1/2" = 1'-0"



STANDARD BATHROOM
ELEVATION

4


1/2" = 1'-0"



STANDARD BATHROOM
ELEVATION

3


1/2" = 1'-0"



STANDARD BATHROOM
ELEVATION

2

1/2" = 1'-0"



STANDARD BATHROOM
TUB/SHOWER

1

1/2" = 1'-0"

GENERAL NOTES

1. CAULKING TO MATCH COLOR OF SOLID SURFACE COUNTERTOP
2. 1/8" MAX GAP AT EACH SIDE OF VANITY
3. LENGTH OF COUNTERTOPS AND BACKSPLASHES TO BE LARGER THAN OPENING, CUT TO LENGTH IN THE FIELD
4. GO TO VERIFY CLEARANCES NOTED PRIOR TO INSTALLING FIXTURES

NOTE:
DIMENSION SHOWN ON PLAN VIEW IS TO FACE OF STUD UNO.
DIMENSION SHOWN ON ELEVATION VIEW IS TO FACE OF FINISH.

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for use on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV #2

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



10/09/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160

Sheet Title

GUESTROOM
BATHROOMS

Sheet No.


A5.7

BRR Original printed on recycled paper







8/16/2023 12:50:52 PM




4 ELEVATOR OPENING JAMB
1 1/2" = 1'-0"



3 ELEVATOR OPENING SILL
1 1/2" = 1'-0"



2 ELEVATOR OPENING HEAD
1 1/2" = 1'-0"



1 ELEV SILL AT FIRST FLOOR
1 1/2" = 1'-0"



Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160


Sheet Title

ELEVATOR DETAILS


Sheet No.

A6.3








BRR Original printed on recycled paper



ROOM FINISH NOTES:			
1. MOISTURE RESISTANT GYPSUM BOARD AT WET WALLS. 2. WASHING MACHINE PAD PAINTED SW7650 "ELLIE GRAY" LINT COVER PAINTED SHERWIN WILLIAMS PRO INDUSTRIAL ZERO VOC. COLOR - SW7650 "ELLIE GRAY"			
FINISH SCHEDULE ABBREVIATIONS LEGEND:			
ACT	ACOUSTICAL CEILING TILE - 2x2' LAY-IN	PNT	PAINT
FRP	FIBERGLASS REINFORCED PANEL	SC	SEALED ROUND FLOORING
GB	GYPSUM BOARD	SC	SEALED CONCRETE
GWT	GYPSUM WALL TEXTURE FINISH - KNOCKDOWN	WB	WALL BASE
LVT	LAMINATE VINYL TILE		



- | PARTITION TYPE NOTES: | |
|-----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1. | SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR FINISHES, TRIM, AND PANELING. |
| 2. | SEE FLOOR PLANS AND ENLARGED PLANS FOR LOCATIONS OF VARIOUS PARTITION TYPES. |
| 3. | SOME INSTANCES SOME PARTITION TYPES SHOWN HEREIN WILL BE SHEARWALLS WITH SHEATHING EVEN THOUGH THEY ARE NOT CALLED OUT AS SHEARWALLS IN THE SCHEDULE - SEE STRUCTURAL PLANS FOR LOCATIONS AND NAILING INFORMATION. |
| 4. | IF ANY DISCREPANCY IS FOUND BETWEEN PARTITION TYPES SHOWN ON THE ARCHITECTURAL PLANS AND SHEARWALL LOCATIONS INDICATED ON STRUCTURAL PLANS, THE STRUCTURAL PLANS SHALL GOVERN. |
| 5. | SEE STRUCTURAL PLANS FOR STUD SPACING REQUIREMENTS. |
| 6. | REF STRUCTURAL PLANS FOR SHEAR WALL LOCATIONS. WHERE SHEAR WALL OCCURS, SHEATHING SHALL BE ON THE ROOM SIDE. |
| 7. | ALL PARTITIONS TO BE FULL HEIGHT U.O. |
| 8. | STC RATING BASED ON 15TH. ED. GYPSUM ASSOC. FIRE RESISTANCE DESIGN MANUAL AND SOUND, NOISE AND VIBRATION CONTROL BY LYLE F. YERGES. |
| 9. | ALL PENETRATIONS TO BE CAULKED WITH ACOUSTICAL SEALANT ON ALL CORRIDORS AND PARTY WALLS. |
| 10. | MOISTURE RESISTANT FR GYP BD IN ALL WET AREAS. |
| 11. | MINIMUM STC OF 50 AT GUESTROOMS (DEMISING WALLS AND CORRIDOR WALLS). |



This category covers proprietary compositions which are used to maintain the hourly ratings of fire resistive walls containing flush mounted devices such as outlet boxes electrical cabinets and mechanical cabinets. The individual classifications indicate the specific applications and the method of installation for which the materials have been evaluated. The basic standard used to investigate products in this category is ANSI/UL 263, "Fire test of building construction and materials".

Look for classification marking on product.

This classification marking of underwriters laboratories, inc. (shown above) on the product or container is the only method provided by underwriters laboratories, inc. Wall opening protective materials produced to identify under its classification and follow-up service.

UNDERWRITERS LABORATORIES, INC. CLASSIFIED WALL OPENING PROTECTIVE MATERIAL FIRE RESISTANCE CLASSIFICATION. SEE PRODUCT CATEGORY IN UL FIRE RESISTANCE DIRECTORY MINNESOTA MINING & MFG CO 3M CENTER, ST PAUL, MN 55144

Type MPP-4S+ moldable putty pads for use with max 4-11/16 x 4-11/16 flush device UL listed metallic outlet boxes in fire rated GYP wallboard wall assemblies framed with min 3 1/2" wide wood or steel studs and constructed as specified in the individual U300 or U400 series wall and partition designs in the fire resistance directory. Moldable putty pads are to be installed to completely cover the exterior surface of the box within the stud cavity with a ball of putty material used to plug the end of each electrical metallic tube or conduit at its connection to the box. A min 1/8 in. thickness of putty material is required on the exterior surfaces of flush device boxes in 1 and 2 hr fire rated wall and partition designs. When the moldable putty pad outlet box protective material is used as directed, the horizontal separation between outlet boxes on opposite sides of the wall may be less than 24 " provided that the outlet boxes are not installed back to back.

WALL OPENING PROTECTIVE MATERIALS (CLIV)

UL DESIGN NO. UL R9700 (N)

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

Drawn By:
JP

Checked By:
JL

Document Date:
08/16/23

Protocolycle:
WSS_v5_2023.1 (05/05/23)

Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal

STATE OF MISSOURI

TREVOR TYSON HOLCOMB

NUMBER A-2022000409

ARCHITECT

08/17/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409

BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160


Sheet Title

ASSEMBLIES & DETAILS

Sheet No.

A7.2

BRR Original printed on recycled paper



1. **Floor Assembly** -- The fire rated wood truss or combination wood and steel truss Floor-Ceiling assembly shall be constructed of the materials and in the manner described in the individual L500 Series Design in the UL Fire Resistance Directory and shall include the following construction features:

A. **Trusses** -- Min. 12" deep parallel chord trusses fabricated from nom 2 x 4 lumber in conjunction with galv. steel truss plates or *Structural Wood Members** with bridging as required.

B. **Flooring** -- 3/4" thick plywood flooring with or without *Floor Topping Mixture**. Max diam. of opening hole-sawed in flooring is 5 in.

C. **Furring Channels** -- Rigid or resilient galv. steel furring channels installed perpendicular to bottom chord of trusses.

D. **Wallboard, Gypsum*** -- 4 ft. wide by 5/8 in. thick, screw attached to furring channels. Max diam. of hole-sawed opening in gypsum wallboard ceiling is 5 in.

2. **Pipe or Conduit** -- 4" diam (or smaller) Schedule 10 (or heavier) steel pipe, steel conduit or steel EMT, or cast iron pipe or 3" diam. (or smaller) Type L (or heavier) copper tubing. Pipe to be installed approx. midway between trusses and centered in circular cutouts in flooring (Item 1B) and gypsum wallboard ceiling (Item 1D). Diam. of circular cutouts in flooring and gypsum wallboard ceiling to be 1/4 in. to 1/2 in. larger than diam. of pipe. Pipe to be rigidly supported on both sides of Floor-Ceiling assembly.


3. **Fill, Void or Cavity Materials*** -- Caulk -- Caulk forced into annular space throughout the thickness of the flooring and gypsum wallboard ceiling and with a min. 1/4" diam bead of caulk applied to perimeter of pipe at its egress from the top of the flooring and the underside of the gypsum wallboard ceiling.
Minnesota Mining & Mfg. Co.-Type CP-25 WB, CP-25 WB+

*Bearing the UL Classification Marking

UL SYSTEM NO. F-C-1006
(STUD WALLS, SIM)
(FORMERLY SYSTEM NO. 453)
F RATING - 1 HR
T RATING - 1 HR

PIPE PENETRATION AT CEILING/FLOOR ASSEMBLY

1 1/2" = 1'-0"



1. **Floor-Ceiling Assembly** -- The fire rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in the individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The general construction details of the floor-ceiling assembly are summarized below:

A. **Flooring System** -- Lumber or plywood subfloor with finish floor of lumber, plywood or *Floor Topping Mixture** as specified in the individual Floor-Ceiling Design. Max diam. of opening is 5 in.

B. **Wood Joists** -- 2 x 10 lumber joists spaced 16" O.C. with 1 x 3 lumber bridging and with ends firestopped. As an alternate to lumber joists, 10" deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or *Structural Wood Members** with bridging as required with ends firestopped.

C. **Furring Channels** -- Resilient galv. steel furring installed perpendicular to wood joists (Item 1B) between wallboard (Item 1D) and wood joists as required in the individual Floor-Ceiling Design.

D. **Wallboard Gypsum*** -- 4 ft wide by 5/8 in. thick as specified in the individual Floor-Ceiling Design. Wallboard secured to wood joists as specified in the individual Floor-Ceiling Design.

2. **Drain Piping** -- 4" diam. (or smaller) Schedule 40 polyvinyl chloride (PVC) or acrylonitrile butadiene styrene (ABS) drain piping and fittings. Diam of circular opening hole through flooring (Item 1A) to be max. 1/2 in. larger than outside diam of pipe. Short length of pipe with 90 degree elbow fitting cemented into bottom socket of closet flange (Item 5). Drain piping cemented to elbow.

3. **Firestop System** -- The firestop system shall consist of the following:

A. **Fill, Void or Cavity Material *** -- Wrap Strip -- 1/4" thick intumescent material faced on both sides with plastic film, supplied in 1-1/2" wide strips. 1-1/2" wide strips tightly-wrapped around nonmetallic pipe with the edges butted against the underside of flooring around the entire perimeter of the hole sawed opening. Two layers of wrap strip are required. Each layer of wrap strip to be installed with butted seam, butted seams in successive layers staggered or aligned. Wrap strip layer(s) temporarily held in position using aluminum foil tape. Specified Technologies Inc. -- SpecSeal RED Strip

B. **Steel Collar** -- Collar fabricated from coils of precut .016 in. thick (30 MSG) galv. sheet steel available from wrap strip manufacturer. Collar shall be nom 1-1/2" deep with min four 1 in. wide by 2 in. long anchor tabs for securement to top surface of flooring. Retainer tabs, 3/4 in. wide tapering down to 1/4" wide and located opposite the anchor tabs, are folded 90 degrees toward though-penetrate surface to maintain the annular space around the though-penetrate and to retain the wrap strips. Steel collar wrapped around wrap strips and through-penetrate with a 1" wide overlap along its perimeter joint and secured together by means of min 1/2" wide by 0.028 in. thickness stainless steel hose clamp at mid-height of the steel collar. An alternate to the steel hose clamp, the steel collar can be secured together by means of three No.8 by 3/8 in. long steel sheet metal screws. Anchor tabs of collar bent outwards and secured to top surface of flooring or underside of floor using min 3/4 in. long steel wood screws in conjunction with 1/4 in. by 1-1/4 in. diam. steel fender washers.


4. **Closet Flange** -- PVC or ABS closet stub sized to accommodate top pipe. Closet flange installed in hole-sawed opening in flooring system with flange secured to top of flooring with steel screws.

5. **Water Closet** -- (Not Shown) -- Floor mounted vitreous china

UL SYSTEM NO. F-C-2037
F RATING - 1 HOUR
T RATING - 1 HOUR

DRAIN PIPE PENETRATION

1 1/2" = 1'-0"



1. **Wall Assembly** -- The 1 or 2 hr. fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. **Stud** -- Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of 2 x 4 lumber spaced 16" O.C. Steel studs to be min. 2-1/2 in. wide and spaced 24" O.C.

B. **Wallboard, Gypsum*** -- 5/8 in. thick, 4 ft wide with square or tapered edges. The gypsum wallboard type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual U300 or U400 Series Design in the UL Fire Resistance Directory. Max diam of opening is 2-1/2"

2. **Cables** - One cable to be centered within the firestop system. A Nonannular space of 1/4" is required within the firestop system. Cable to be rigidly supported on both sides of wall assembly. The following types and sizes of cables may be used:

A. Max 50 pair No. 24 AWG (or smaller) copper conductor telephone cables with polyvinyl chloride (PVC) insulation and jacket materials.

B. Max 3/C (with ground) - No. 10 AWG (or smaller) PVC insulated and jacketed non metallic sheathed (Romex) Cable.

C. Max 3/C (with ground) - No. 2/0 AWG aluminum conductor service entrance cable with PVC insulation and jacket materials.

2A. **Through-Penetrants** -- As an alternate to Item 2, max four copper conductor No. 2 AWG (or smaller) aluminum or steel Armored Cable* or 4/C No. 2/0 AWG Metal-Clad Cable*, Max one armored cable or metal clad cable centered within the firestop system. The annular space between the through- penetrating product and the periphery of the opening shall be 3/8 in. Through- Penetrating product to be rigidly supported on both sides of wall assembly.

KAF-TECH Inc.

3. **Fill, Void or Cavity Material*** -- Sealant or Putty-- Fill material applied within the annulus, flush with both surfaces of wall. Additional fill material to be installed such that a crown is formed around the penetrating item. The T Rating of the firestop system is dependent upon the hourly rating of the wall type of though penetrant and type and thickness of fill material as tabulated below:

Hourly Rating of Wall (HR)	Type of Through Penetrant	Type of Fill Material	Thickness of Fill Material (In.)	Thickness of Fill Material (Crown In.)	T Rating (Hr.)
1	Telephone Cable	Sealant	5/8	1/4	1
2	Telephone Cable	Sealant	5/8	1/4	2
1	Telephone Cable	Putty	5/8	3/8	1
2	Telephone Cable	Putty	3/4	1/4	2
1	Romex Cable	Sealant	5/8	3/8	1
2	Romex Cable	Sealant	3/4	1/4	2
1	Romex Cable	Putty	5/8	3/8	1
2	Romex Cable	Putty	3/4	1/4	2
2	Service Cable	Sealant	5/8	1/4	1/2
1	Service Cable	Sealant	5/8	1/4	1/2
2	Armored Cable	Sealant	5/8	1/4	1/2
1	Armored Cable	Sealant	5/8	1/4	1/2
2	Metal Clad Cable	Sealant	5/8	1/4	1/2
1	Metal Clad Cable	Sealant	5/8	1/4	1/2

Specified Technologies Inc. - SpecSeal 100, 101, 102 or 105 Sealant or SpecSeal Putty


*Bearing the UL Classification Marking

*Bearing the UL Listing Mark

UL SYSTEM NO. W-L-2138
F RATING - 1 HR
T RATING - 1 HR

PIPE PENETRATION AT WALL

1 1/2" = 1'-0"



1. **Wall Assembly** -- The hr. fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. **Stud** -- Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of 2 x 4 lumber spaced 16" O.C. Steel studs to be min. 2-1/2 in. wide and spaced 24" O.C.

B. **Wallboard, Gypsum*** -- One Layer of 5/8 in. thick GYP bd., as specified in the individual wall and partition design. Max diam of opening is 3-1/8"

2. **Through-Penetrants** -- One nonmetallic pipe or tubing installed either concentrically or eccentrically within the firestop system. Pipe or tubing to be rigidly supported on both sides of wall assembly. The following types and sizes of nonmetallic pipes or tubing may be used:

A. **Polyvinyl Chloride (PVC) Pipe** -- 2" diam. (or smaller) Schedule 40 solid core PVC pipe for use in closed (process or supply) piping systems.

B. **Chlorinated Polyvinyl Chloride (CPVC) Pipe** -- 2" diam. (or smaller) SDR 17 CPVC pipe for use in closed (process or supply) piping systems.

C. **Crosslinked Polyethylene (PEX) Tubing** - 3/4" diam. (or smaller) SDR 9 PEX tubing for use in closed (process or supply) piping systems. The annular space between tubing and periphery of opening shall be min 1/4" to max 5/8"

3. **Fill, Void or Cavity Material*** -- Sealant -- Min 5/8" thickness of fill material applied within the annulus, flush both surfaces of wall


OSI Sealants, Inc. - Flame Seal

*Bearing the UL Classification Marking

UL SYSTEM NO. W-L-2138
F RATING - 1 HR
T RATING - 1 HR

PIPE PENETRATION AT WALL

1 1/2" = 1'-0"



1. **Wall Assembly** -- The fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. **Stud** -- Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of 2 x 4 lumber spaced 16" O.C. Steel studs to be min. 2-1/2 in. wide and spaced 24" O.C.

B. **Wallboard, Gypsum*** -- One layers of 5/8 in. thick GYP bd., as specified in the individual Wall and Partition Design. Max. diam of opening is 2-1/4"

2. **Through-Penetrants** -- One nonmetallic pipe or conduit for use in closed (process or supply) or vented (drain, waste or vent) piping systems, installed either concentrically or eccentrically within the firestop system. The annular space between the pipe or conduit and the edge of the opening shall be min 3/8" to max 13/16" Pipe or conduit to be rigidly supported on both sides of wall assembly. The following types and sizes of nonmetallic pipes or conduits may be used:

A. **Polyvinyl Chloride (PVC) Pipe** -- 3/4" diam. (or smaller) Schedule 40 cellular or solid core PVC pipe.

B. **Chlorinated Polyvinyl Chloride (CPVC) Pipe** -- 3/4" Diam. (or smaller) SDR17 Pipe.

3. **Fill, Void or Cavity Material*** -- Sealant -- Min thickness of 5/8" of fill material applied within annulus between pipe or conduit and periphery of the opening, flush with both surfaces of wall assembly.


The Restoreseal Corp. - Metacaulk 835+

*Bearing the UL Classification Marking

UL SYSTEM NO. W-L-2134
F RATING - 1 HOUR
T RATING - 1 HOUR

PIPE PENETRATION AT WALL

1 1/2" = 1'-0"



1. **Wall Assembly** -- The fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. **Stud** -- Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of 2 x 4 lumber spaced 16" O.C. Steel studs to be min. 2-1/2 in. wide and spaced 24" O.C.

B. **Wallboard, Gypsum*** -- Two layers of 5/8 in. thick GYP bd., as specified in the individual Wall and Partition Design. Max. diam of opening is 3"

2. **Through-Penetrants** -- One nonmetallic pipe to be centered within the firestop system. Pipe to be rigidly supported on both sides of the wall assembly. The following types and sizes of nonmetallic pipes or conduit may be used:

A. **Polyvinyl Chloride (PVC) Pipe** -- 2" diam. (or smaller) Schedule 40 cellular or solid core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. A nom annular space of 5/16" is required in the firestop system.

B. **Acrylonitrile Butadiene Styrene (ABS) Pipe** -- 2" diam. (or smaller) Schedule 40 cellular or solid core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. A nom annular space of 5/16" is required in the firestop system.

3. **Fill, Void or Cavity Material*** -- Wrap Strip -- 1/4 in. thick by 1in. wide intumescent wrap strip. The wrap strip is continuously wrapped around the outer circumference of the pipe once and slid into annular space such that the ends are flush with the surface of the wall. Wrap strips are installed on each surface of the wall.


The Restoreseal Corp. - Metacaulk Wrap Strip

* Bearing the UL Classification Marking

UL SYSTEM NO. W-L-2121 OR W-L-2122
F RATING - 2 HOUR
T RATING - 0 HOUR

PIPE PENETRATION AT WALL

1 1/2" = 1'-0"



1. **Floor-Ceiling Assembly** -- The 1 hr fire-rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in the individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The 2 hr fire-rated wood joist floor-ceiling assembly shall be constructed of the materials and in the manner specified. The F and T Ratings of the firestop system are equal to the hourly fire rating of the floor-ceiling assembly. The general construction features of the floor-ceiling assembly are summarized below:

A. **Flooring System** -- Lumber or plywood subfloor with finish floor of lumber, plywood or *Floor Topping Mixture** as specified in the individual Floor-Ceiling Design. Max Diam. of floor opening is 4-3/4".

B. **Wood Joists** -- For 1 hr fire - rated floor ceiling assemblies, 10 in. deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or *Structural Wood Members** with bridging as required and with ends firestopped. For 2 hr fire - rated floor - ceiling assemblies, 2 x 10 lumber joists spaces 16" O.C. with 1 x 3 lumber bridging and with ends firestopped.

C. **Furring Channels** -- (not shown) -- In 2 hr fire rated assemblies resilient galv. steel furring installed perpendicular to wood joists between first and second layers of wallboard (Item 1D). Furring channels spaced max 24" O.C. In 1 hr fire - rated assemblies, resilient galv. steel furring installed perpendicular to wood joists between wallboard and wood joists as specified in the individual *Floor Ceiling Design*. Furring channels spaced max 24" O.C.

D. **Wallboard, Gypsum*** -- 4 ft wide by 5/8 in. thick as specified in the individual *Floor Ceiling design*. First layer of wallboard secured to wood joists or furring channel as specified in the individual Floor Ceiling Design. Second layer of wallboard (2 hr fire-rated assembly) screw attached to furring channels as specified in the individual Floor Ceiling Design. Max diam. of ceiling opening is 4-3/4".

2. **Nonmetallic Pipe** -- 4" (or smaller) Schedule 40 solid core polyvinyl chloride (PVC) pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. One pipe to be installed either concentrically or eccentrically within the firestop system. For pipes 2" in diam. (or smaller) the annular space shall be min. 0" to max 3/8". Pipe to be rigidly supported on both sides of floor of wall assembly.

3. **Firestop System** -- The firestop system shall consist of the following:

A. **Fill, Void or cavity Material*** -- Caulk -- Min. 3/4" thickness of fill material applied within the annulus on top surface of floor. Additional fill material to be installed such that a min. 3/4" crown is formed around the penetrating item on top surface of floor. Min. 1/4" thickness of fill material applied within the annulus, flush with bottom surface of ceiling. Additional fill material to be installed such that a min. 1/4" crown is formed around the penetrating item on the bottom surface of the ceiling.

B. **Firestop Device*** -- Firestop device shall be installed in accordance with the accompanying installation instructions. Device wrapped over the pipe and secured by using the attached hose clamp. Device slid along the pipe until it abuts the bottom of the ceiling. Device secured to floor with 1/4 in. by 1-3/4 in. long hollow wall anchors in conjunction with 1-1/4" diameter fender washers.


Tremco Inc. -- TREMstop D.

*Bearing the UL Classification Marking

SYSTEM NO. F-C-2049
F RATINGS - 1 AND 2 HR (SEE ITEM 1)
T RATINGS - 1 AND 2 HR (SEE ITEM 1)

PIPE PENETRATION AT CEILING/FLOOR

1 1/2" = 1'-0"



1. **Wall Assembly** -- The 1 or 2 hr. fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. **Stud** -- Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of 2 x 4 lumber spaced 16" O.C. Steel studs to be min. 2-1/2 in. wide and spaced 24" O.C.

B. **Wallboard, Gypsum*** -- 5/8 in. thick, 4 ft. wide square or tapered edges. The gypsum wallboard, type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual U300 or U400 Series Design in the UL Fire Resistance Directory. Max. diam. opening is 4-3/8 in. The hourly F and T Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed.

2. **Through-Penetrants** -- One nonmetallic pipe or conduit to be centered within the firestop system. The max. diam. of the through penetrant and annular space within the firestop system is dependent upon the type of fill material (Item 3). Pipe or conduit to be rigidly supported on both sides of the wall assembly. The following types and sizes of nonmetallic pipes or conduit may be used:

A. **Polyvinyl Chloride (PVC) Pipe** -- 2" diam. (or smaller) Schedule 40 solid core PVC pipe for use in closed (process or supply) piping systems.

B. **Chlorinated Polyvinyl Chloride (CPVC) Pipe** -- 2" diam. (or smaller) SDR 17 CPVC pipe for use in closed (process or supply) piping systems.


C. **Rigid Nonmetallic Conduit** -- 2" diam. (or smaller) Schedule 40 PVC conduit installed in accordance with Article 347 of the National Electrical Code (NECA No. 70).

3. **Fill, Void or Cavity Material*** -- Sealant -- In 2 hr. fire rated assemblies, min. 1-1/4" thickness of fill material applied within the annulus, flush with both surfaces of wall. In 1 hr. fire rated assemblies, min. 5/8" thickness of fill material applied within the annulus, on both surfaces of wall. Additional fill material to be installed such that a min. 5/8" thick crown is formed around the penetrating item and lapping a min. 1" beyond the periphery of the opening. The max. diam. of the through penetrant and annular space within the firestop system is dependent upon the type of fill material as tabulated below:


Max. Diam. of through Non. Annular Penetrant In.	Space In.	Fill Material Type	EP
1	1/2	1	1
2	1	1	1
Isolatak International - Types EP and I			
*Bearing the UL Listing Mark			
* Bearing the UL Classification Marking			
			UL SYSTEM NO. W-I-20

10/11/2023 3:03:14 PM

DOOR TYPES




FRAME TYPES




DOOR SCHEDULE

MARK	ROOM NAME	DOOR								FRAME					HARDWARE SET	REMARKS
		W	H	T	MATERIAL	FINISH	TYPE	GLAZING	LABEL	TYPE	MATERIAL	HEAD	JAMB	SILL		
GUESTROOMS																
A	GUESTROOM	3'-0"	6'-8"	1 3/4"	SC WOOD	PRE-FIN	A	-	20 MIN	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	013, 014	DOOR HARDWARE SET 014 AT ADA ROOMS
B	RESTROOM	3'-0"	6'-8"	1 3/4"	SC WOOD	PRE-FIN	B	-	-	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	016	1/2" UNDERCUT
STAIRS																
150A	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	-	A	HOLLOW METAL	7/A8.1	6/A8.1	4/A8.1	003	TEMPERED GLASS, FIRE EXIT HARDWARE; NOTE 1
150B	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	90 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1 SIM	009	90 MIN FIRE GLASS, FIRE EXIT HARDWARE; NOTE 1
152A	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	-	A	HOLLOW METAL	7/A8.1	6/A8.1	4/A8.1	003	TEMPERED GLASS, FIRE EXIT HARDWARE; NOTE 1
152B	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	90 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1 SIM	009	90 MIN FIRE GLASS, FIRE EXIT HARDWARE; NOTE 1
250	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	90 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1 SIM	009	90 MIN FIRE GLASS, FIRE EXIT HARDWARE; NOTE 1
252	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	90 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1 SIM	009	90 MIN FIRE GLASS, FIRE EXIT HARDWARE; NOTE 1
350	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	90 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1 SIM	009	90 MIN FIRE GLASS, FIRE EXIT HARDWARE; NOTE 1
352	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	90 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1 SIM	009	90 MIN FIRE GLASS, FIRE EXIT HARDWARE; NOTE 1
450	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	90 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1 SIM	009	90 MIN FIRE GLASS, FIRE EXIT HARDWARE; NOTE 1
452	STAIRS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	5"x20" VP	90 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1 SIM	009	90 MIN FIRE GLASS, FIRE EXIT HARDWARE; NOTE 1
FIRST FLOOR																
135A	VESTIBULE	6'-0"	7'-0"	1 3/4"	ALUMINUM	PRE-FIN	D	FULL GLASS	-	B	ALUMINUM	13/A8.1	12/A8.1	11/A8.1	001	PAIR 3'-0" DOORS, CLEAR TEMPERED GLASS
135B	VESTIBULE	6'-0"	7'-0"	1 3/4"	ALUMINUM	PRE-FIN	D	FULL GLASS	-	B	ALUMINUM	18/A8.1	17/A8.1	16/A8.1	005	PAIR 3'-0" DOORS, CLEAR TEMPERED GLASS
136	CORRIDOR	3'-6"	7'-0"	1 3/4"	ALUMINUM	PRE-FIN	D	FULL GLASS	-	B	ALUMINUM	15/A8.1	14/A8.1	11/A8.1	004	CLEAR TEMPERED GLASS
137B	AHU	2'-6"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	015A	NOTE 1
139	RESTROOM	3'-0"	6'-8"	1 3/4"	SC WOOD	PRE-FIN	A	-	-	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	007	-
140	MECHANICAL ROOM	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	HOLLOW METAL	7/A8.1	6/A8.1	4/A8.1	002	NOTE 1
141	STAFF LAUNDRY	2'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	015	NOTE 1
142A	GUEST LAUNDRY	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	HALF GLASS	45 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1	012	45 MIN. FIRE GLASS; NOTE 1
142B	AHU	2'-6"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	015A	NOTE 1
142C	GUEST LAUNDRY	2'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	015	NOTE 1
143A	STAFF LAUNDRY	3'-6"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	45 MIN	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	011	NOTE 1
143B	AHU	2'-6"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	015	NOTE 1
143C	TRAINING	3'-0"	6'-8"	1 3/4"	SC WOOD	PRE-FIN	A	-	45 MIN	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	010	-
144	STORAGE	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1	002	NOTE 1
145	ELECTRICAL ROOM	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	HOLLOW METAL	7/A8.1	6/A8.1	4/A8.1	022	NOTE 1
146	LOBBY	6'-0"	7'-0"	1 3/4"	ALUMINUM	PRE-FIN	D	FULL GLASS	-	B	ALUMINUM	18/A8.1	17/A8.1	16/A8.1	005	PAIR 3'-0" DOORS, CLEAR TEMPERED GLASS
147	FITNESS	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	HALF GLASS	45 MIN	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1	012	45 MIN. FIRE GLASS; NOTE 1
148A	REGISTRATION	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	010	RETURN AIR LOUVER; NOTE 1
148B	REGISTRATION	8'-0"	3'-8"	1 3/4"	WOOD COIL	PRE-FIN	F	-	-	-	WOOD	12/A4.4	10/A4.4	-	-	ALL HARDWARE BY OVERHEAD DOOR MFR; NOTE 2
154	STORAGE	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	-	A	HOLLOW METAL	10/A8.1	9/A8.1	8/A8.1	015	NO LOCK; NOTE 1
SECOND FLOOR																
240	UTILITY ROOM	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	45 MIN	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	008	NOTE 1
241	HALL	3'-6"	7'-0"	1 3/4"	HOLLOW METAL	PAINT	C	NONE	20 MIN	A	HOLLOW METAL	2/A6.3	3/A6.3	8/A8.1 SIM	021	20 MIN FIRE GLASS; WALL MAGNET TO BE TIED INTO FIRE ALARM SYSTEM; NOTE 1
THIRD FLOOR																
340	UTILITY ROOM	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	45 MIN	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	008	NOTE 1
341	HALL	3'-6"	7'-0"	1 3/4"	HOLLOW METAL	PAINT	C	NONE	20 MIN	A	HOLLOW METAL	2/A6.3	3/A6.3	8/A8.1 SIM	021	20 MIN FIRE GLASS; WALL MAGNET TO BE TIED INTO FIRE ALARM SYSTEM; NOTE 1
FOURTH FLOOR																
440	UTILITY ROOM	3'-0"	6'-8"	1 3/4"	HOLLOW METAL	PAINT	C	-	45 MIN	A	H.M. TIMELY	3/A8.1	2/A8.1	1/A8.1	008	NOTE 1
441	HALL	3'-6"	7'-0"	1 3/4"	HOLLOW METAL	PAINT	C	NONE	20 MIN	A	HOLLOW METAL	2/A6.3	3/A6.3	8/A8.1 SIM	021	20 MIN FIRE GLASS; WALL MAGNET TO BE TIED INTO FIRE ALARM SYSTEM; NOTE 1


GENERAL NOTES:
1. DOOR AND FRAME TO BE PAINTED "BROWNTONE" TO MATCH GUESTROOM/CORRIDOR FRAME COLOR; REF SPECS
2. OVERHEAD DOOR AND FRAME TO BE PREFINISHED; REF ELEVATION FOR COLOR



20 PHOTOLUMINESCENT DOOR SIGN



19 ELEVATION AT GUEST SUITE DOOR




18 HEAD

1 1/2" = 1'-0"

15 ALUMINUM FRAME HEAD - EIFS

1 1/2" = 1'-0"



17 JAMB


1 1/2" = 1'-0"

16 SILL

1 1/2" = 1'-0"


14 ALUMINUM FRAME JAMB - EIFS

1 1/2" = 1'-0"



13 ALUMINUM FRAME HEAD - STONE

1 1/2" = 1'-0"




12 ALUMINUM FRAME JAMB - STONE

1 1/2" = 1'-0"


11 ALUMINUM FRAME SILL

1 1/2" = 1'-0"




10 HOLLOW METAL FRAME HEAD

1 1/2" = 1'-0"



9 HOLLOW METAL FRAME JAMB

1 1/2" = 1'-0"




8 HOLLOW METAL FRAME SILL

1 1/2" = 1'-0"


7 HOLLOW METAL FRAME HEAD

1 1/2" = 1'-0"




6 HOLLOW METAL FRAME JAMB

1 1/2" = 1'-0"



5 HOLLOW METAL FRAME SILL

1 1/2" = 1'-0"




4 HOLLOW METAL FRAME SILL

1 1/2" = 1'-0"


3 FRAME HEAD

1 1/2" = 1'-0"




2 FRAME JAMB

1 1/2" = 1'-0"



1A THRESHOLD

1 1/2" = 1'-0"



1 FRAME SILL

1 1/2" = 1'-0"



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for use on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV#2

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

JP

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)


Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



10/12/2023

TREVOR TYSON HOLCOMB
ARCHITECT
LICENSE NO. 2022000409
BRR ARCHITECTURE, INC.
ARCHITECTURAL CORPORATION
MISSOURI LICENSE NO. ARC 000160






Sheet Title


DOOR SCHEDULE &
DOOR DETAILS


Sheet No.

A8.1

BRR Original printed on recycled paper



<div><div>3/9/22, 2:11 PM</div><div>BXUV.U301 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div>13A. Foamed Plastic* — (Optional, Not Shown - For use with Item 4S) — Spray applied, foamed plastic insulation, at any thickness from partial fill to completely filling stud cavity. GACO WESTERN L L C — Types GacoEZSpray F4500, GacoProFI FR6500R, Gaco 052N, GacoOnePass F1850, GacoOnePass Low GWP F1880, and Gaco WallFoam 183M.</div><div>13B. Foamed Plastic* — (Optional, Not Shown - For use with Item 4T) — Spray applied, foamed plastic insulation, at any thickness from partial fill to completely filling stud cavity. CARLISLE SPRAY FOAM INSULATION — Types SealTite Pro Closed Cell (CC), SealTite Pro Open Cell (OC), SealTite Pro OCK, SealTite Pro No Trim 21, SealTite Pro One Zero, Foamulate Closed Cell, Foamulate OCK, Foamulate 70, and Foamulate HFO.</div><div>14. Foamed Plastic* — (Optional, Not Shown - For use over Gypsum Board, Item 4) - Polyisocyanurate foamed plastic boards, any thickness applied vertically with vertical joints located over studs. May be used with Molded Plastic, Item 5 or any exterior facing, as authorized by the Authority Having Jurisdiction and installed in accordance with the manufacturer's installation instructions. HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — "Xci Class A", "Xci 286", "Xci Foil (Class A)", "Xci CG", "Xci Foil", "Xci CG NH", "Xci CG NH", "Xci Foil NH"</div><div>15. Building Units* — (Optional, Not Shown - For use over Gypsum Board, Item 4) Polyisocyanurate composite foamed plastic boards, any thickness, applied vertically with vertical joints located over studs. May be used with Molded Plastic, Item 5 or any exterior facing, as authorized by the Authority Having Jurisdiction and installed in accordance with the manufacturer's installation instructions. HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — "Xci NB", "Xci PLY"</div><div><div>* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.</div><div>Last Updated on 2022-02-14</div></div><div><div>The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.</div><div>UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"</div></div><div><div>https://iq.ulprospector.com/en/profile?e=14884</div><div>9/9</div></div></div>	<div><div>3/9/22, 2:05 PM</div><div>BXUV.U305 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div>UL Product IQ™</div><div>BXUV.U305 - Fire-resistance Ratings - ANSI/UL 263</div><div>Design/System/Construction/Assembly Usage Disclaimer</div><div><ul style="list-style-type: none">Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.Authorities Having Jurisdiction should be consulted before construction.Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.Only products which bear UL's Mark are considered Certified.</div><div>Fire-resistance Ratings - ANSI/UL 263</div><div>BXUV - Fire Resistance Ratings - ANSI/UL 263 Certified for United States</div><div>BXUV7 - Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada</div><div><div>See General Information for Fire-resistance Ratings - ANSI/UL 263 Certified for United States</div><div>Design Criteria and Allowable Variances</div><div>See General Information for Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada</div><div>Design Criteria and Allowable Variances</div></div><div>Design No. U305</div><div>February 14, 2022</div><div>Bearing Wall Rating — 1 Hr</div><div>Finish Rating — See Items 3, 3A, 3D, 3E, 3F, 3G, 3H, 3J and 3L</div><div>STC Rating - 56 (See Item 9)</div><div>This design was evaluated using a load design method other than the Limit States Design Method (e.g., Working Stress Design Method). For jurisdictions employing the Limit States Design Method, such as Canada, a load restriction factor shall be used — See Guide BXUV or BXUV7</div><div><div>* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.</div><div></div></div><div><div>DETAIL 2 - WALL ASSEMBLY UL DESIGN NO. U305 INTERIOR BEARING WALL FIRE RATING - 1 HOUR</div><div>1/12</div></div><div><div>https://iq.ulprospector.com/en/profile?e=14888</div><div>2/12</div></div></div>	<div><div>3/9/22, 2:05 PM</div><div>BXUV.U305 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div></div><div>1. Wood Studs — Nom 2 by 4 in. spaced 16 in. OC max, effectively firestopped.</div><div>2. Joints and Nail-Heads — Joints covered with joint compound and paper tape. Joint compound and paper tape may be omitted when square edge boards are used. As an alternate, nom 3/32 in. thick gypsum veneer plaster may be applied to the entire surface of Classified veneer baseboard with the joints reinforced with paper tape. Nailheads exposed or covered with joint compound.</div><div>3. Gypsum Board* — 5/8 in. thick paper or vinyl surfaced, with beveled, square, or tapered edges, applied either horizontally or vertically. Gypsum panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. When used in widths other than 48 in., gypsum panels are to be installed horizontally. For an alternate method of attachment of gypsum panels, refer to Items 6 through 6F. Steel Framing Members* When Items 6, 6B, 6C, 6D, 6E, or 6F, Steel Framing Members*, are used, gypsum panels attached to furring channels with 1 in. long Type S bugle-head steel screws spaced 12 in. OC.</div><div>When Item 6A, Steel Framing Members*, is used, two layers of gypsum panels attached to furring channels. Base layer attached to furring channels with 1 in. long Type S bugle-head steel screws spaced 12 in. OC. Face layer attached to furring channels with 1-5/8 in. long Type S bugle-head steel screws spaced 12 in. OC. All joints in face layers staggered with joints in base layers. One layer of gypsum board attached to opposite side of wood stud without furring channels as described in Item 3.</div><div>When Item 7, resilient channels are used, 5/8 in. thick, 4 ft wide gypsum panels applied vertically. Screw attached furring channels with 1 in. long, self-drilling, self-tapping Type S or S-12 steel screws spaced 8 in. OC, vertical joints located midway between studs.</div><div>AMERICAN GYPSUM CO — Types AGX-1 (finish rating 23 min), M-Glass (finish rating 23 min), Type AGX-11 (finish rating 26 min), Type AGX-12 (finish rating 22 min), Type LightRock (finish rating 23 min), or Type AG-C</div><div>BEIJING NEW BUILDING MATERIALS PUBLIC LTD CO — Type DBX-1 (finish rating 24 min)</div><div>CABOT MANUFACTURING ULC — Type X (finish rating 22 min), 5/8 Type X, Moisture Resistant Type X, Gypsum Sheathing Type X, Mold & Mildew Resistant Type X and Mold & Mildew Resistant AR Type X, Type Blueglass Exterior Sheathing</div><div><div>https://iq.ulprospector.com/en/profile?e=14888</div><div>2/12</div></div></div>	<div><div>3/9/22, 2:05 PM</div><div>BXUV.U305 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div>CERTAINTED GYPSUM INC — Type C, Type X or Type X-1 (finish rating 26 min); Type EGRG or GlasRoc (finish rating 23 min), GlasRoc-2, Type Habito (finish rating 26 min).</div><div>CGC INC — Type AR (finish rating 24 min), Type C (finish rating 24 min), Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min), Type IP-X1 (finish rating 24 min), Type IP-X2 (finish rating 24 min), Type SCX (finish rating 24 min), Type SHX (finish rating 24 min), Type WRC (finish rating 22 min), Type WRC (finish rating 24 min), Type WRX (finish rating 24 min), Type ULX (finish rating 20 min)</div><div>CERTAINTED GYPSUM INC — Type LGFC6A (finish rating 34 min), Type LGFC2A, Type LGFC-C/A, Type LGFC-WD, Type LGLX (finish rating 21 min), Type CLX (finish rating 24 min)</div><div>GEORGIA-PACIFIC GYPSUM L L C — Type 5 (finish rating 26 min), Type 6 (finish rating 23 min), Type 9 (finish rating 26 min), Type C (finish rating 26 min), Type DGG (finish rating 20 min), Type GPFS1 (finish rating 20 min), Type GPFS2 (finish rating 20 min), Type GPFS3 (finish rating 26 min), Type DS, Type DAP, Type DD (finish rating 20 min), Type DA, Type DAPC, Type LS (finish rating 23 min), Type X, Veneer Plaster Base - Type X, Water Rated - Type X, Sheathing - Type X, Soffit - Type X, Type LWX (finish rating 22 min), Veneer Plaster Base-Type LWX (finish rating 22 min), Water Rated-Type LWX (finish rating 22 min), Sheathing Type-LWX (finish rating 22 min), Soffit-Type LWX (finish rating 22 min), Type DGLW (finish rating 22 min), Water Rated-Type DGLW (finish rating 22 min), Sheathing Type- DGLW (finish rating 22 min), Soffit-Type DGLW (finish rating 22 min), Type LWX (finish rating 22 min), Type LWX2 (finish rating 22 min), Veneer Plaster Base - Type LWX2 (finish rating 22 min), Water Rated - Type LWX2 (finish rating 22 min), Sheathing - Type LWX2 (finish rating 22 min), Soffit - Type LWX2 (finish rating 22 min), Type DGLW2 (finish rating 22 min), Water Rated - Type DGLW2 (finish rating 22 min), Sheathing - Type DGLW2 (finish rating 22 min)</div><div>NATIONAL GYPSUM CO — Type FSK (finish rating 20 min), Type FSK-G (finish rating 20 min), Type FSW (finish rating 20 min), Type FSW-2 (finish rating 24 min), Type FSW-3 (finish rating 20 min), Type FSW-5 (finish rating 22 min), Type FSW-G (finish rating 20 min), Type FSK-C (finish rating 20 min), Type FSW-C (finish rating 20 min), Type FSMR-C2, Type FSW-6 (finish rating 20 min), Type FSL (finish rating 24 min), Type FSW-8, Type FSLX (finish rating 21 min), Type RSX (finish rating 26 min).</div><div>NATIONAL GYPSUM CO — Riyadh, Saudi Arabia — Type FR, or WR.</div><div>PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Types C, PG-2 (finish rating 20 min), PG-3 (finish rating 20 min), Types PG-3W, PG-5W (finish rating 20 min), Type PG-4 (finish rating 20 min), Type PG-6 (finish rating 23 min), Types PG-3WS, PG-5WS, PGS-WRS (finish rating 20 min), Types PG-5, PG-9 (finish rating 26 min), PG-11 PG-13 (Nails increased to 2 in.), Type PG-C or PG (finish rating 26 min)</div><div>PANEL REY S A — Type ARX, GREX, GRX, PRX, PRC, PRC2; Types RHX, Guard Rey, MDX, ETX (finish rating 22 min), PRX2 (finish rating 21 min)</div><div>SIAM GYPSUM INDUSTRY (SARABUR) CO LTD — Type EX-1 (finish rating 26 min)</div><div>THAI GYPSUM PRODUCTS PCL — Type C, Type X (finish rating 26 min)</div><div>UNITED STATES GYPSUM CO — Type AR (finish rating 24 min), Type C (finish rating 24 min), Type FRX-G (finish rating 29 min), Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min), Type IP-X1 (finish rating 24 min), Type IP-X2 (finish rating 24 min), Type SHX (finish rating 24 min), Type WRC (finish rating 24 min), Type SCX (finish rating 24 min), Type SGX (finish rating 24 min), Type ULX (finish rating 22 min), Type WRX (finish rating 24 min), Type WRC (finish rating 24 min), Type ULX (finish rating 20 min)</div><div>USG BORAL DRYWALL SFZ LLC — Type SGX (finish rating 24 min).</div><div>USG MEXICO S A DE C V — Type AR (finish rating 24 min), Type C (finish rating 24 min), Type WRX (finish rating 24 min), Type WRC (finish rating 24 min), Type IP-X1 (finish rating 24 min), Type IP-X2 (finish rating 24 min), Type SHX (finish rating 24 min), SCX (finish rating 24 min), Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min), Type ULX (finish rating 22 min)</div><div>3A. Gypsum Board* — (As an alternate to Item 3) — 5/8 in. thick gypsum panels, with beveled, square, or tapered edges, applied either horizontally or vertically. Gypsum panels fastened to framing with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board. When used in widths of other than 48 in., gypsum boards are to be installed horizontally.</div><div><div>https://iq.ulprospector.com/en/profile?e=14888</div><div>3/12</div></div></div>
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

<div><div>3/9/22, 2:11 PM</div><div>BXUV.U301 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div>13A. Foamed Plastic* — (Optional, Not Shown - For use with Item 4S) — Spray applied, foamed plastic insulation, at any thickness from partial fill to completely filling stud cavity. GACO WESTERN L L C — Types GacoEZSpray F4500, GacoProFI FR6500R, Gaco 052N, GacoOnePass F1850, GacoOnePass Low GWP F1880, and Gaco WallFoam 183M.</div><div>13B. Foamed Plastic* — (Optional, Not Shown - For use with Item 4T) — Spray applied, foamed plastic insulation, at any thickness from partial fill to completely filling stud cavity. CARLISLE SPRAY FOAM INSULATION — Types SealTite Pro Closed Cell (CC), SealTite Pro Open Cell (OC), SealTite Pro OCK, SealTite Pro No Trim 21, SealTite Pro One Zero, Foamulate Closed Cell, Foamulate OCK, Foamulate 70, and Foamulate HFO.</div><div>14. Foamed Plastic* — (Optional, Not Shown - For use over Gypsum Board, Item 4) - Polyisocyanurate foamed plastic boards, any thickness applied vertically with vertical joints located over studs. May be used with Molded Plastic, Item 5 or any exterior facing, as authorized by the Authority Having Jurisdiction and installed in accordance with the manufacturer's installation instructions. HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — "Xci Class A", "Xci 286", "Xci Foil (Class A)", "Xci CG", "Xci Foil", "Xci CG NH", "Xci CG NH", "Xci Foil NH"</div><div>15. Building Units* — (Optional, Not Shown - For use over Gypsum Board, Item 4) Polyisocyanurate composite foamed plastic boards, any thickness, applied vertically with vertical joints located over studs. May be used with Molded Plastic, Item 5 or any exterior facing, as authorized by the Authority Having Jurisdiction and installed in accordance with the manufacturer's installation instructions. HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — "Xci NB", "Xci PLY"</div><div><div>* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.</div><div>Last Updated on 2022-02-14</div></div><div><div>The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.</div><div>UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"</div></div><div><div>https://iq.ulprospector.com/en/profile?e=14884</div><div>9/9</div></div></div>	<div><div>3/9/22, 2:05 PM</div><div>BXUV.U305 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div>UL Product IQ™</div><div>BXUV.U305 - Fire-resistance Ratings - ANSI/UL 263</div><div>Design/System/Construction/Assembly Usage Disclaimer</div><div><ul style="list-style-type: none">Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.Authorities Having Jurisdiction should be consulted before construction.Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.Only products which bear UL's Mark are considered Certified.</div><div>Fire-resistance Ratings - ANSI/UL 263</div><div>BXUV - Fire Resistance Ratings - ANSI/UL 263 Certified for United States</div><div>BXUV7 - Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada</div><div><div>See General Information for Fire-resistance Ratings - ANSI/UL 263 Certified for United States</div><div>Design Criteria and Allowable Variances</div><div>See General Information for Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada</div><div>Design Criteria and Allowable Variances</div></div><div>Design No. U305</div><div>February 14, 2022</div><div>Bearing Wall Rating — 1 Hr</div><div>Finish Rating — See Items 3, 3A, 3D, 3E, 3F, 3G, 3H, 3J and 3L</div><div>STC Rating - 56 (See Item 9)</div><div>This design was evaluated using a load design method other than the Limit States Design Method (e.g., Working Stress Design Method). For jurisdictions employing the Limit States Design Method, such as Canada, a load restriction factor shall be used — See Guide BXUV or BXUV7</div><div><div>* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.</div><div></div></div><div><div>DETAIL 2 - WALL ASSEMBLY UL DESIGN NO. U305 INTERIOR BEARING WALL FIRE RATING - 1 HOUR</div><div>1/12</div></div><div><div>https://iq.ulprospector.com/en/profile?e=14888</div><div>2/12</div></div></div>	<div><div>3/9/22, 2:05 PM</div><div>BXUV.U305 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div></div><div>1. Wood Studs — Nom 2 by 4 in. spaced 16 in. OC max, effectively firestopped.</div><div>2. Joints and Nail-Heads — Joints covered with joint compound and paper tape. Joint compound and paper tape may be omitted when square edge boards are used. As an alternate, nom 3/32 in. thick gypsum veneer plaster may be applied to the entire surface of Classified veneer baseboard with the joints reinforced with paper tape. Nailheads exposed or covered with joint compound.</div><div>3. Gypsum Board* — 5/8 in. thick paper or vinyl surfaced, with beveled, square, or tapered edges, applied either horizontally or vertically. Gypsum panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. When used in widths other than 48 in., gypsum panels are to be installed horizontally. For an alternate method of attachment of gypsum panels, refer to Items 6 through 6F. Steel Framing Members* When Items 6, 6B, 6C, 6D, 6E, or 6F, Steel Framing Members*, are used, gypsum panels attached to furring channels with 1 in. long Type S bugle-head steel screws spaced 12 in. OC.</div><div>When Item 6A, Steel Framing Members*, is used, two layers of gypsum panels attached to furring channels. Base layer attached to furring channels with 1 in. long Type S bugle-head steel screws spaced 12 in. OC. Face layer attached to furring channels with 1-5/8 in. long Type S bugle-head steel screws spaced 12 in. OC. All joints in face layers staggered with joints in base layers. One layer of gypsum board attached to opposite side of wood stud without furring channels as described in Item 3.</div><div>When Item 7, resilient channels are used, 5/8 in. thick, 4 ft wide gypsum panels applied vertically. Screw attached furring channels with 1 in. long, self-drilling, self-tapping Type S or S-12 steel screws spaced 8 in. OC, vertical joints located midway between studs.</div><div>AMERICAN GYPSUM CO — Types AGX-1 (finish rating 23 min), M-Glass (finish rating 23 min), Type AGX-11 (finish rating 26 min), Type AGX-12 (finish rating 22 min), Type LightRock (finish rating 23 min), or Type AG-C</div><div>BEIJING NEW BUILDING MATERIALS PUBLIC LTD CO — Type DBX-1 (finish rating 24 min)</div><div>CABOT MANUFACTURING ULC — Type X (finish rating 22 min), 5/8 Type X, Moisture Resistant Type X, Gypsum Sheathing Type X, Mold & Mildew Resistant Type X and Mold & Mildew Resistant AR Type X, Type Blueglass Exterior Sheathing</div><div><div>https://iq.ulprospector.com/en/profile?e=14888</div><div>2/12</div></div></div>	<div><div>3/9/22, 2:05 PM</div><div>BXUV.U305 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div>CERTAINTED GYPSUM INC — Type X</div><div>CGC INC — Type SCX</div><div>PANEL REY S A — Type ARX, PRX</div><div>SIAM GYPSUM INDUSTRY (SARABUR) CO LTD — Type EX-1</div><div>THAI GYPSUM PRODUCTS PCL — Type X</div><div>UNITED STATES GYPSUM CO — Types SCX and SGX</div><div>USG BORAL DRYWALL SFZ LLC — Types SCX and SGX</div><div>USG MEXICO S A DE C V — Type SCX</div><div>3V. Gypsum Board* — (As an alternate to Item 3. For use with Item 5K) — Any 5/8 in. thick, 4 ft. wide, Gypsum Board listed in Item 3 above. Applied vertically with vertical joints centered over studs and staggered one stud cavity on opposite sides of studs. Gypsum panels secured to studs with 1-5/8 in. long Type W coarse thread gypsum panel steel screws spaced 8 in. OC at perimeter and in the field.</div><div>4. Steel Corner Fasteners — (Optional) — For use at wall corners. Channel shaped, 2 in. long by 1 in. high on the back side with two 1/8 in. wide flats protruding into the 5/8 in. wide channel, fabricated from 24 gauge galv steel. Fasteners applied only to the end or cut edge (not along tapered edges) of the gypsum board, no greater than 2 in. from corner of gypsum board, max spacing 16 in. OC. Nailed to adjacent stud through tab using one No. 6d cement coated nail per fastener. Corners of wall board shall be nailed to top and bottom plate using No. 6d cement coated nails.</div><div>5. Batts and Blankets* — (Optional) — Required when Item 6A is used (RC-1) — Glass fiber or mineral wool insulation. Placed to completely or partially fill the stud cavities. When Item 6A is used, glass fiber or mineral wool insulation shall be friction-fitted to completely fill the stud cavities.</div><div>CERTAINTED CORP</div><div>JOHNS MANVILLE</div><div>KNAUF INSULATION LLC</div><div>MANSON INSULATION INC</div><div>ROCKWOOL — Types Acoustical Fire Batts and Type AFB, min. density 1.69 pcf / 27.0 kg/m³</div><div>ROCKWOOL MALAYSIA SDN BHD — Type Acoustical Fire Batts</div><div>ROCK WOOL MANUFACTURING CO — Delta Board</div><div>THERMAFIBER INC — Type SAFB, SAFB FF</div><div>5A. Fiber, Sprayed* — (Not Shown — Not for use with Item 6) — As an alternate to Batts and Blankets (Item 5) — Spray applied cellulose material. The fiber is applied with water to completely fill the enclosed cavity in accordance with the application instructions supplied with the product with a nominal dry density of 2.7 lb/ft³. Alternate Application Method: The fiber is applied without water or adhesive at a nominal dry density of 3.5 lb/ft³, in accordance with the application instructions supplied with the product. When Item 6B is used, Fiber, Sprayed shall be INS73S, INS74S, INS75LD, INS76LD, INS773LD or SANCTUARY.</div><div><div>https://iq.ulprospector.com/en/profile?e=14888</div><div>7/12</div></div></div>
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

<div><div>3/9/22, 2:11 PM</div><div>BXUV.U301 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div>13A. Foamed Plastic* — (Optional, Not Shown - For use with Item 4S) — Spray applied, foamed plastic insulation, at any thickness from partial fill to completely filling stud cavity. GACO WESTERN L L C — Types GacoEZSpray F4500, GacoProFI FR6500R, Gaco 052N, GacoOnePass F1850, GacoOnePass Low GWP F1880, and Gaco WallFoam 183M.</div><div>13B. Foamed Plastic* — (Optional, Not Shown - For use with Item 4T) — Spray applied, foamed plastic insulation, at any thickness from partial fill to completely filling stud cavity. CARLISLE SPRAY FOAM INSULATION — Types SealTite Pro Closed Cell (CC), SealTite Pro Open Cell (OC), SealTite Pro OCK, SealTite Pro No Trim 21, SealTite Pro One Zero, Foamulate Closed Cell, Foamulate OCK, Foamulate 70, and Foamulate HFO.</div><div>14. Foamed Plastic* — (Optional, Not Shown - For use over Gypsum Board, Item 4) - Polyisocyanurate foamed plastic boards, any thickness applied vertically with vertical joints located over studs. May be used with Molded Plastic, Item 5 or any exterior facing, as authorized by the Authority Having Jurisdiction and installed in accordance with the manufacturer's installation instructions. HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — "Xci Class A", "Xci 286", "Xci Foil (Class A)", "Xci CG", "Xci Foil", "Xci CG NH", "Xci CG NH", "Xci Foil NH"</div><div>15. Building Units* — (Optional, Not Shown - For use over Gypsum Board, Item 4) Polyisocyanurate composite foamed plastic boards, any thickness, applied vertically with vertical joints located over studs. May be used with Molded Plastic, Item 5 or any exterior facing, as authorized by the Authority Having Jurisdiction and installed in accordance with the manufacturer's installation instructions. HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — "Xci NB", "Xci PLY"</div><div><div>* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.</div><div>Last Updated on 2022-02-14</div></div><div><div>The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.</div><div>UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"</div></div><div><div>https://iq.ulprospector.com/en/profile?e=14884</div><div>9/9</div></div></div>	<div><div>3/9/22, 2:05 PM</div><div>BXUV.U305 - Fire-resistance Ratings - ANSI/UL 263 UL Product IQ</div><div>screws spaced a max 8 in. OC, with last 2 screws 1 and 4 in. from edge of board or nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. When used in widths of other than 48 in., gypsum boards are to be installed horizontally.</div><div>GEORGIA-PACIFIC GYPSUM L L C — Type DGG (finish rating 20 min), GreenGlass Type X (finish rating 23 min)</div><div>3F. Gypsum Board* — (As an alternate to Items 3, 3A, 3B, 3C, 3D, and 3E) — 5/8 in. glass-mat faced with square edges, applied either horizontally or vertically. Gypsum panels nailed 7 in. OC around the perimeter and in the field with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. Nails shall be placed 1 inch and 3 inch from horizontal joints and 7 inch OC thereafter.</div><div>CGC INC — Type USGX (finish rating 22 min)</div><div>UNITED STATES GYPSUM CO — Type USGX (finish rating 22 min.)</div><div>USG BORAL DRYWALL SFZ LLC — Type USGX (finish rating 22 min.)</div><div>USG MEXICO S A DE C V — Type USGX (finish rating 22 min.)</div><div>3G. Gypsum Board* — (As an alternate to Items 3 through 3F) — 5/8 in. thick paper surfaced applied vertically. Gypsum panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads.</div><div>GEORGIA-PACIFIC GYPSUM L L C — Type X ComfortGuard Sound Deadening Gypsum Board (finish rating 27 min)</div><div>3H. Gypsum Board* — (As an alternate to Items 3) — Not to be used with items 6 or 7. 5/8 in. thick paper surfaced applied vertically only. Gypsum panels nailed 7</div></div>
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

Author

Checked By:

JL

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)

Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal

Sheet Title

FIRE RATED
ASSEMBLIES

Sheet No.

A10.2

BRR Original printed on recycled paper

FOR REFERENCE ONLY

3/9/22, 2:13 PM

BXUV.U905 - Fire-resistance Ratings - ANSI/UL 263 | UL Product iQ

UL Product iQ™

BXUV.U905 - Fire-resistance Ratings - ANSI/UL 263

Design/System/Construction/Assembly Usage Disclaimer

• Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.

• Authorities Having Jurisdiction should be consulted before construction.

• Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.

• When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.

• Only products which bear UL's Mark are considered Certified.

BXUV - Fire Resistance Ratings - ANSI/UL 263 Certified for United States

BXUV7 - Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada

See General Information for Fire-resistance Ratings - ANSI/UL 263 Certified for United States

Design Criteria and Allowable Variations

See General Information for Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada

Design Criteria and Allowable Variations

Design No. U905

November 09, 2020

Bearing Wall Rating — 2 HR.

Nonbearing Wall Rating — 2 HR

This design was evaluated using a load design method other than the Limit States Design Method (e.g., Working Stress Design Method). For jurisdictions employing the Limit States Design Method, such as Canada, a load restriction factor shall be used — See Guide BXUV or BXUV7


* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

https://iq.ulprospector.com/en/profile?e=15133

1/3

3/9/22, 2:13 PM

BXUV.U905 - Fire-resistance Ratings - ANSI/UL 263 | UL Product iQ



Horizontal Section

1. Concrete Blocks* — Various designs. Classification D-2 (2 hr). See Concrete Blocks category for list of eligible manufacturers.

2. Mortar — Blocks laid in full bed of mortar, nom. 3/8 in. thick, of not less than 2-1/4 and not more than 3-1/2 parts of clean sharp sand to 1 part Portland cement (proportioned by volume) and not more than 50 percent hydrated lime (by cement volume). Vertical joints staggered.

3. Portland Cement Stucco or Gypsum Plaster — Add 1/2 hr to classification if used. Where combustible members are framed in wall, plaster or stucco must be applied on the face opposite framing to achieve a max. Classification of 1-1/2 hr. Attached to concrete blocks (Item 1).

4. Loose Masonry Fill — If all core spaces are filled with loose dry expanded slag, expanded clay or shale (Rotary Kihl Process), water repellent vermiculite masonry fill insulation, or silicone treated perlite loose fill insulation add 2 hr to classification.

5. Foamed Plastic* — (Optional-Not Shown) — 1-1/2 in. thick max, 4 ft wide sheathing attached to concrete blocks (Item 1). ATLAS ROOFING CORP — "EnergyShield Pro Wall Insulation", "EnergyShield Pro 2 Wall Insulation", EnergyShield CGF Pro and EnergyShield Ply Pro

CARLISLE COATINGS & WATERPROOFING INC — Type R2+ SHEATHE

DUPONT DE NEMOURS, INC. — Types Thermax Sheathing, Thermax Light Duty Insulation, Thermax Heavy Duty Insulation, Thermax Metal Building Board, Thermax White Finish Insulation, Thermax ci Exterior Insulation, Thermax XARMOR ci Exterior Insulation, Thermax iH Insulation, Thermax Plus Liner Panel, Thermax Heavy Duty Plus (HDP), TUFF-R™ ci Insulation, Thermax Butler Stylwall Insulation Board and Thermax Morton Heavy Duty Insulation Board

FIRESTONE BUILDING PRODUCTS CO L L C — "Enverge™ CI Foil Exterior Wall Insulation" and "Enverge™ CI Glass Exterior Wall Insulation"

HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — Types "Xci-Class A", "Xci Foil (Class A)", "Xci 286"

RMAX, A BUSINESS UNIT OF SIKKA CORPORATION — Types "TSX-8500", "ECOMAXci FR", "TSX-8510", "ECOMAX ci FR White", "ECOMAXci", "ECOMAXci FR Air Barrier", "Thermasheath-XP", "Thermasheath", "Durasheath", "Thermasheath-3", "Durasheath-3"

JOHNS MANVILLE — Type "AP Foil-faced Foam Sheathing"

5A. Building Units* — As an alternate to Items 5, min. 1-in thick polyisocyanurate composite foamed plastic insulation boards, nom. 48 by 48 or 96 in.

HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — "Xci NB", "Xci Ply"

RMAX, A BUSINESS UNIT OF SIKKA CORPORATION — "Thermasheath-SI", "ECOBASect", "ThermaBase-CI", "ECOMAXci FR Ply", "ECOMAXci Ply"

DETAIL 6 - WALL ASSEMBLY
UL DESIGN NO. U905
BEARING WALL
FIRE RATING - 2 HOUR

https://iq.ulprospector.com/en/profile?e=15133

2/3

3/9/22, 2:13 PM

BXUV.U905 - Fire-resistance Ratings - ANSI/UL 263 | UL Product iQ

* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2020-11-09

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL," must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"

Design/System/Construction/Assembly Usage Disclaimer

• Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.

• Authorities Having Jurisdiction should be consulted before construction.

• Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.

• When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.

• Only products which bear UL's Mark are considered Certified.

https://iq.ulprospector.com/en/profile?e=15133

3/3

3/10/22, 9:08 AM

XHEZF-C-1160 - Through-penetration Firestop Systems | UL Product iQ

UL Product iQ™

XHEZF-C-1160 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

• Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.

• Authorities Having Jurisdiction should be consulted before construction.

• Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.

• When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.

• Only products which bear UL's Mark are considered Certified.

XHEZ - Through-penetration Firestop Systems

XHEZ7 - Through-penetration Firestop Systems Certified for Canada

See General Information for Through-penetration Firestop Systems

See General Information for Through-penetration Firestop Systems Certified for Canada

System No. F-C-1160

March 07, 2017

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Ratings - 1 and 2 Hr (See Item 1)	F Ratings -1 and 2 Hr (See Item 1)
	PH Ratings -1 and 2 Hr (See Item 1)
T Rating - 1/4 Hr	FT Rating - 1/4 Hr
	FTH Rating -1/4 Hr
L Rating At Ambient - Less Than 1 CFM/sq ft	L Rating At Ambient - Less Than 5.1 L/s/m ²

DETAIL 11 - PIPE PEN. @ FLOOR/CEILING
UL DESIGN NO. F-C-1160
F RATING - 1 & 2 HOUR (SEE ITEM 1)
T RATING - 1/4 HOUR

http://iq.ulprospector.com/en/profile?e=15137

1/3

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions


NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

3/10/22, 9:08 AM

XHEZF-C-1160 - Through-penetration Firestop Systems | UL Product iQ



SECTION A-A

1. Floor-Ceiling Assembly — The 1 hr fire-rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in the individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The 2 hr fire-rated wood joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in Design Nos. L505, L511 or L536 in the UL Fire Resistance Directory. The F Rating of the firestop system is equal to the hourly fire rating of the floor-ceiling assembly. The general construction features of the floor-ceiling assembly are summarized below:

A. Flooring System — Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture" as specified in the individual Floor-Ceiling Design. Max diam of opening is 7/8 in. (22 mm) larger than outside diam of penetrant.

B. Wood Joists — For 1 hr fire-rated floor-ceiling assemblies, nom 10 in. (254 mm) deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or Structural Wood Members* with bridging as required and with ends firestopped. For 2 hr fire-rated floor-ceiling assemblies, nom 2 by 10 in. (51 by 254 mm) lumber joists spaced 16 in. (406 mm) OC with nom 1 by 3 in. (25 by 76 mm) lumber bridging and with ends firestopped.

C. Furring Channels — In 2 hr fire-rated assemblies, resilient gyl steel furring installed perpendicular to wood joists between first and second layers of gypsum board (Item 1D). Furring channels spaced max 24 in. (610 mm) OC.

D. Gypsum Board* — Nom 4 ft (122 cm) wide by 5/8 in. (16 mm) thick as specified in the individual Floor-Ceiling Design. First layer of gypsum board secured to wood joists or furring channels as specified in the individual Floor-Ceiling Design. Second layer of gypsum board (2 hr fire-rated assembly) screw-attached to furring channels as specified in the individual Floor-Ceiling Design. Max diam of opening is 7/8 in. (22 mm) larger than outside diam of penetrant.

1.1 Chase Wall — (Optional, not shown) — The through penetrant (Item 2) may be routed through a fire-rated single, double or staggered wood stud/gypsum board chase wall having a fire rating consistent with that of the floor-ceiling assembly. The chase wall shall be constructed of the materials and in the manner specified in the individual U300 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. Studs — Nom 2 by 6 in. (51 by 152 mm) or double nom 2 by 4 in. (51 by 102 mm) lumber studs.

https://iq.ulprospector.com/en/profile?e=175137

2/3

3/10/22, 9:08 AM

XHEZF-C-1160 - Through-penetration Firestop Systems | UL Product iQ

B. Sole Plate — Nom 2 by 6 in. (51 by 152 mm) or parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly butted. Max diam of opening is 3 in. (76 mm).

C. Top Plate — The double top plate shall consist of two nom 2 by 6 in. (51 by 152 mm) or two sets of parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly butted. Max diam of opening is 3 in. (76 mm).

D. Gypsum Board* — Thickness, type, number of layers and fasteners shall be as specified in individual Wall and Partition Design.

2. Through Penetrants — One metallic pipe, conduit or tubing to be installed either concentrically or eccentrically within the firestop system. The space between pipe, conduit or tubing and periphery of opening shall be min 0 in. (point contact) to max 7/8 in. (22 mm). Pipe, conduit or tubing to be rigidly supported on both sides of floor or wall assembly. The following types and sizes of metallic pipes, conduits or tubing may be used:

A. Steel Pipe — Nom 8 in. (203 mm) diam (or smaller) Schedule 40 (or heavier) steel pipe.

B. Iron Pipe — Nom 8 in. (203 mm) diam (or smaller) cast or ductile iron pipe.

C. Conduit — Nom 4 in. (102 mm) diam (or smaller) steel electrical metallic tubing or nom 6 in. diam (or smaller) steel conduit.

D. Copper Tubing — Nom 4 in. (102 mm) diam (or smaller) Type L (or heavier) copper tubing.

E. Copper Pipe — Nom 4 in. (102 mm) diam (or smaller) Regular (or heavier) copper pipe.

3. Firestop System — The firestop system shall consist of the following:

A. Packing Material — (Optional) — Foam backer rod firmly packed into opening as a permanent form. Packing material to be recessed from top surface of floor or sole plate and bottom surface of ceiling or lower top plate as required to accommodate the required thickness of fill material.

B. Fill, Void or Cavity Material* — Caulk — Min 5/8 in. (16 mm) thickness of fill material applied within the annulus, flush with top surface of the floor or sole plate and bottom surface of the ceiling or lower top plate. Additional fill material to be installed such that a min 1/2 in. (13 mm) crown is formed around the penetrating item and lapping 1-1/4 in. (32 mm) beyond the periphery of the opening.

DAP PRODUCTS INC — DAP Blockade

* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2017-03-07

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL," must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"

DETAIL 12 - PIPE PEN. @ FLOOR/CEILING
UL DESIGN NO. F-C-2203
F RATING - 1 HOUR
T RATING - 1 HOUR

https://iq.ulprospector.com/en/profile?e=175137

3/3

3/10/22, 9:47 AM

XHEZF-C-2203 - Through-penetration Firestop Systems | UL Product iQ

UL Product iQ™

XHEZF-C-2203 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

• Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.

• Authorities Having Jurisdiction should be consulted before construction.

• Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.

• When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.

• Only products which bear UL's Mark are considered Certified.

See General Information for Through-penetration Firestop Systems

System No. F-C-2203

January 05, 2017

F Rating — 1 Hr


T Rating — 1 Hr

https://iq.ulprospector.com/en/profile?e=175186

1/3

3/10/22, 9:47 AM

XHEZF-C-2203 - Through-penetration Firestop Systems | UL Product iQ



SECTION A-A

1. Floor-Ceiling Assembly — The 1 hr fire-rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in the individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The general construction features of the floor-ceiling assembly are summarized below:

A. Flooring System — Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture" as specified in the individual Floor-Ceiling Design. Max diam of opening shall be 5 in. (127 mm).

B. Wood Joist* — Nom 10 in. (254 mm) deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or Structural Wood Members* with bridging as required and with ends firestopped.

C. Gypsum Board* — Nom 5/8 in. (16 mm) thick, 4 ft (1.2 m) wide as specified in the individual Floor-Ceiling Design.

2. Closet Flange — Acrylonitrile butadiene styrene (ABS) or polyvinyl chloride (PVC) closet stub sized to accommodate drain pipe. Closet flange installed over drain piping within floor opening with flange secured to plywood floor with steel screws. Diam of circular opening through flooring (Item 1A) to be max 1/2 in. (13 mm) larger than outside diam of closet flange.

3. Drain Piping — Nom 4 in. (102 mm) diam (or smaller) Schedule 40 acrylonitrile butadiene styrene (ABS) or polyvinyl chloride (PVC) drain pipe and 90 degree elbow for use in vented (drain, waste or vent) piping systems. Pipe installed concentrically within firestop system.

4. Fill, Void or Cavity Materials* — Sealant — Min 3/4 in. (19 mm) thickness of fill material applied within the annulus, flush with the bottom surface of floor.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant or FS-ONE MAX Intumescent Sealant

5. Water Closet — (Not Shown) — Floor mounted vitreous china water closet.

* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2017-01-05

https://iq.ulprospector.com/en/profile?e=175186

2/3

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

Drawn By:
ALW

Checked By:
JL

Document Date:
08/16/23

Protocol:
WSS_v4_2019.1 (01/31/19)

Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal

Sheet Title

FIRE RATED ASSEMBLIES

Sheet No.

A10.6

BRR Original printed on recycled paper

3/10/22, 9:47 AM

XHEZ.F-C-2203 - Through-penetration Firestop Systems | UL Product iQ

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL," must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"

https://iq.ulprospector.com/en/profile?e=175186

3/3

3/10/22, 9:43 AM

XHEZ.F-C-3128 - Through-penetration Firestop Systems | UL Product iQ

UL Product iQ™

XHEZ.F-C-3128 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

https://iq.ulprospector.com/en/profile?e=258648

1/3

XHEZ - Through-penetration Firestop Systems

XHEZ7 - Through-penetration Firestop Systems Certified for Canada

See General Information for Through-penetration Firestop Systems

See General Information for Through-penetration Firestop Systems Certified for Canada

System No. F-C-3128

August 02, 2019

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Rating - 1 Hr	F Rating -1 Hr
	FH Rating -1 Hr
T Rating - 1 Hr	FT Rating -1 Hr
	FTH Rating -1 Hr

DETAIL 14 - CABLE PEN. @ FLOOR/CEILING

UL DESIGN NO. F-C-3128

F RATING - 1 HOUR

T RATING - 1 HOUR

https://iq.ulprospector.com/en/profile?e=258648

1/3

3/10/22, 9:50 AM

XHEZ.F-C-2379 - Through-penetration Firestop Systems | UL Product iQ

UL Product iQ™

XHEZ.F-C-2379 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

System No. F-C-2379

October 26, 2020

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Rating - 1 Hr	F Rating -1 Hr
	FH Rating -1 Hr
T Rating - 1 Hr	FT Rating -1 Hr
	FTH Rating -1 Hr
L Rating At Ambient - Less than 1 CFM/sq ft	L Rating At Ambient - Less than 1 CFM/sq ft
L Rating At 400°F - Less than 1 CFM/sq ft	L Rating At 400°F

DETAIL 13 - PIPE PEN. @ FLOOR/CEILING

UL DESIGN NO. F-C-2379

F RATING - 1 HOUR

T RATING - 1 HOUR

https://iq.ulprospector.com/en/profile?e=175232

1/3

3/10/22, 9:43 AM

XHEZ.F-C-3128 - Through-penetration Firestop Systems | UL Product iQ

UL Product iQ™

XHEZ.F-C-3128 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

System No. F-C-3128

August 02, 2019

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Rating - 1 Hr	F Rating -1 Hr
	FH Rating -1 Hr
T Rating - 1 Hr	FT Rating -1 Hr
	FTH Rating -1 Hr

DETAIL 14 - CABLE PEN. @ FLOOR/CEILING

UL DESIGN NO. F-C-3128

F RATING - 1 HOUR

T RATING - 1 HOUR

https://iq.ulprospector.com/en/profile?e=258648

1/3

3/10/22, 9:50 AM

XHEZ.F-C-2379 - Through-penetration Firestop Systems | UL Product iQ

UL Product iQ™

XHEZ.F-C-2379 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

System No. F-C-2379

October 26, 2020

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Rating - 1 Hr	F Rating -1 Hr
	FH Rating -1 Hr
T Rating - 1 Hr	FT Rating -1 Hr
	FTH Rating -1 Hr
L Rating At Ambient - Less than 1 CFM/sq ft	L Rating At Ambient - Less than 1 CFM/sq ft
L Rating At 400°F - Less than 1 CFM/sq ft	L Rating At 400°F

DETAIL 13 - PIPE PEN. @ FLOOR/CEILING

UL DESIGN NO. F-C-2379

F RATING - 1 HOUR

T RATING - 1 HOUR

https://iq.ulprospector.com/en/profile?e=175232

1/3

3/10/22, 9:43 AM

XHEZ.F-C-3128 - Through-penetration Firestop Systems | UL Product iQ

UL Product iQ™

XHEZ.F-C-3128 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

System No. F-C-3128

August 02, 2019

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Rating - 1 Hr	F Rating -1 Hr
	FH Rating -1 Hr
T Rating - 1 Hr	FT Rating -1 Hr
	FTH Rating -1 Hr
L Rating At Ambient - Less than 1 CFM/sq ft	L Rating At Ambient - Less than 1 CFM/sq ft
L Rating At 400°F - Less than 1 CFM/sq ft	L Rating At 400°F

DETAIL 14 - CABLE PEN. @ FLOOR/CEILING

UL DESIGN NO. F-C-3128

F RATING - 1 HOUR

T RATING - 1 HOUR

https://iq.ulprospector.com/en/profile?e=258648

1/3

3/10/22, 9:50 AM

XHEZ.F-C-2379 - Through-penetration Firestop Systems | UL Product iQ

UL Product iQ™

XHEZ.F-C-2379 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

System No. F-C-2379

October 26, 2020

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Rating - 1 Hr	F Rating -1 Hr
	FH Rating -1 Hr
T Rating - 1 Hr	FT Rating -1 Hr
	FTH Rating -1 Hr
L Rating At Ambient - Less than 1 CFM/sq ft	L Rating At Ambient - Less than 1 CFM/sq ft
L Rating At 400°F - Less than 1 CFM/sq ft	L Rating At 400°F

DETAIL 13 - PIPE PEN. @ FLOOR/CEILING

UL DESIGN NO. F-C-2379

F RATING - 1 HOUR

T RATING - 1 HOUR

https://iq.ulprospector.com/en/profile?e=175232

1/3

3/10/22, 9:13 AM

XHEZ.W-L-2048 - Through-penetration Firestop Systems | UL Product iQ

UL Product iQ™

XHEZ.W-L-2048 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

System No. W-L-2048

October 11, 2021

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Ratings — 1 and 2 Hr (See Item 1)	F Ratings — 1 and 2 Hr (See Item 1)
T Ratings — 1, 1-3/4 and 2 Hr (See Items 2 and 4A)	FT Ratings — 1, 1-3/4 and 2 Hr (See Items 2 and 4A)
L Rating At Ambient — Less Than 1 CFM/ft ²	FH Ratings — 1 and 2 Hr (See Item 1)
L Rating At 400°F — Less Than 1 CFM/ft ²	FTH Ratings — 1, 1-3/4 and 2 Hr (See Items 2 and 4A)
	L Rating At Ambient — Less Than 5.1 L/s/m ²
	L Rating At 204°C — Less Than 5.1 L/s/m ²

DETAIL 15 - PIPE PEN. @ WALL

UL DESIGN NO. W-L-2048

F RATING - 1 & 2 HOUR (SEE ITEM 1)

T RATING - 1, 1 3/4 & 2 HOUR (SEE ITEM 2 & 4A)

https://iq.ulprospector.com/en/profile?e=176820

1/4

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

WOODSPRING SUITES™

CHOICE HOTELS

Drawn By:
ALW

Checked By:
JL

Document Date:
08/16/23

Protocol:
WSS_v4_2019.1 (01/31/19)

Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal

Sheet Title

FIRE RATED ASSEMBLIES

Sheet No.


A10.7

BRR Original printed on recycled paper

FOR REFERENCE ONLY

3/10/22, 9:13 AM

XHEZ.W-L-2048 - Through-penetration Firestop Systems | UL Product IQ



Section A-A

System tested with a pressure differential of 2.5 Pa between the exposed and the unexposed surfaces with the higher pressure on the exposed side.

1. **Wall Assembly** — The 1 or 2 hr fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner described in the individual U300, V300, U400, V400 or W400 Series Wall Series Wall or Partition Design in the UL Fire Resistance Directory and shall include the following construction features:
A. **Studs** — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC.

B. **Gypsum Board*** — The gypsum board type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual U300, V300, U400, V400 or W400 Series Design in the UL Fire Resistance Directory. Max diam of opening is 5 in. (127 mm).

The hourly F and FH Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed.

2. **Steel Sleeve (Optional)** — Nom 3 in. (76 mm) diam (or smaller) Schedule 40 (or thinner) steel pipe friction-fit into wall assembly, flush with both surfaces of wall. When steel sleeve is used, T, FT and FTH Ratings are 1 hr.

3. **Through Penetrants** — One nonmetallic pipe or conduit to be centered within the firestop system. The annular space shall be min 1/4 in. (6 mm) to max 1-1/4 in (32 mm). Pipe or conduit to be rigidly supported on both sides of the wall assembly. The following types and sizes of nonmetallic pipes or conduits may be used:
A. **Polyvinyl Chloride (PVC) Pipe** — Nom 3 in. (76 mm) diam (or smaller) Schedule 40 cellular or solid core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.

B. **Chlorinated Polyvinyl Chloride (CPVC) Pipe** — Nom 3 in. (76 mm) diam (or smaller) SDR 13.5 CPVC pipe for use in closed (process or supply) piping systems.

C. **Rigid Nonmetallic Conduit*** — Nom 3 in. (76 mm) diam (or smaller) Schedule 40 PVC conduit installed in accordance with the National Electrical Code (NFPA No. 70).

D. **Acrylonitrile Butadiene Styrene (ABS) Pipe** — Nom 3 in. (76 mm) diam (or smaller) Schedule 40 cellular or solid core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.

E. **Flame Retardant Polypropylene (FRPP) Pipe** — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 FRPP pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems.

https://iq.ulprospector.com/en/profile?e=176820

2/4

3/10/22, 9:13 AM

XHEZ.W-L-2048 - Through-penetration Firestop Systems | UL Product IQ

F. **Polypropylene (PP) Pipe** — Nom 1 in. (25 mm) diam (or smaller) Schedule 80 PP pipe for use in closed (process or supply) piping systems.

G. **Polyvinylidene Fluoride (PVDF) Pipe** — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 PVDF pipe for use in closed (process or supply) piping systems.

4. **Firestop System** — The firestop system shall consist of the following:
A. **Fill, Void or Cavity Material*** — **Wrap Strip** — Nom 1/8 in. (3.2 mm) or 3/16 in. (4.8 mm) thick intumescent material faced on both sides with a plastic film, supplied in 2 in. (51 mm) wide strips or 1/8 or 1/4 in. (3.2 or 6 mm) thick intumescent material faced on both sides with a plastic film, supplied in 1-1/2 in. (38 mm) wide strips. Single layer of wrap strip wrapped around the through penetrant with the ends butted and held in place by means of foil tape. The wrap strip is slid along the through penetrant into annulus such that 1/4 in. (6 mm) of the wrap strip protrudes from the wall. One set of wrap strips to be installed on each side of wall. As an option when 1/8 in. (3.2 mm) thick wrap strip (BLU2) is used, the strips may be cut to a width of 1-1/2 in. (38 mm). The T, FT and FTH Ratings of the firestop system is dependent upon the hourly rating of the wall, the type of through penetrant and the type of wrap strip used as tabulated below:

Type of Through Penetrant	Hourly Rating of Wall Hr	Type of Wrap Strip	T, FT, FTH Rating Hr
PVC, CPVC, PVDF, RNC, PP or FRPP	1	SpecSeal BLU, SpecSeal BLU2 or SpecSeal RED, RED2	1
ABS	1	SpecSeal BLU, SpecSeal BLU2 or SpecSeal RED, RED2	1
PVC, CPVC, PVDF, RNC, PP or FRPP	2	SpecSeal BLU, SpecSeal BLU2 or SpecSeal RED, RED2	2
ABS	2	SpecSeal BLU or SpecSeal BLU2	2
ABS	2	SpecSeal RED, RED2	1-3/4

SPECIFIED TECHNOLOGIES INC — SpecSeal BLU Wrap Strip, SpecSeal BLU2 Wrap Strip or SpecSeal RED Wrap Strip, SpecSeal RED2 Wrap Strip

B. **Fill, Void or Cavity Material*** — **Sealant** — When an annular space is present between the wrap strip and the edge of the opening, a min 5/8 in. (16 mm) depth of sealant shall be installed in the annular space flush with each surface of the wall. A min 1/4 in. (6 mm) diam bead of sealant shall be applied at the gypsum board/wrap strip interface on both surfaces of wall.
SPECIFIED TECHNOLOGIES INC — SpecSeal Series SSS Sealant, SpecSeal LCI Sealant or SpecSeal SL300 Sealant

* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2021-10-11

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"

https://iq.ulprospector.com/en/profile?e=176820

3/4

3/10/22, 9:17 AM

XHEZ.W-L-2100 - Through-penetration Firestop Systems | UL Product IQ

UL Product iQ™

XHEZ.W-L-2100 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

Through-penetration Firestop Systems

XHEZ - Through-penetration Firestop Systems

XHEZ7 - Through-penetration Firestop Systems Certified for Canada

See General Information for Through-penetration Firestop Systems

See General Information for Through-penetration Firestop Systems Certified for Canada

System No. W-L-2100

October 11, 2021

ANSI/UL1479 (ASTM E814)	CAN/ULC S115
F Ratings — 1 and 2 Hr (See Item 1)	F Ratings — 1 and 2 Hr (See Item 1)
T Ratings — 0, 1/4, 1 and 1-1/2 Hr (See Item 2)	FT Ratings — 0, 1/4, 1 and 1-1/2 Hr (See Item 2)
	FH Ratings — 1 and 2 Hr (See Item 1)
	FTH Ratings — 0, 1/4, 1 and 1-1/2 Hr (See Item 2)


DETAIL 16 - PIPE PEN. @ FLOOR/CEILING
UL DESIGN NO. W-L-2100
F RATING - 1 & 2 HOUR (SEE ITEM 1)
T RATING - 0, 1, 1 1/4 & 1 1/2 HOUR (SEE ITEM 2)

https://iq.ulprospector.com/en/profile?e=176850

1/3

3/10/22, 9:17 AM

XHEZ.W-L-2100 - Through-penetration Firestop Systems | UL Product IQ



Section A-A

System tested with a pressure differential of 2.5 Pa between the exposed and the unexposed surfaces with the higher pressure on the exposed side.

1. **Wall Assembly** — The 1 or 2 hr fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner described in the individual U300, V300, U400, V400 or W400 Series Wall or Partition Design in the UL Fire Resistance Directory and shall include the following construction features:
A. **Studs** — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced 16 in. (406 mm) OC. Steel studs to be min 3-5/8 in. (92 mm) wide and spaced max 24 in. (610 mm) OC.

B. **Gypsum Board*** — 5/8 in. (16 mm) thick, 4 ft (1.2 m) wide with square or tapered edges. The gypsum wallboard type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual Design in the UL Fire Resistance Directory. Max diam of opening is 3-1/2 in.

The hourly F and FH Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed.

2. **Nonmetallic Pipe** — One nonmetallic pipe or tubing to be centered within the firestop system. Pipe or tubing to be rigidly supported on both sides of wall assembly. The following types of nonmetallic pipes or tubing may be used:
A. **Polybutylene Pipe** — Nom 1 in (2 mm) diam (or smaller) SDR 11 (or heavier) polybutylene (PB) pipe for use in closed (process or supply) piping systems. A nom annular space of 1/4 in. (6 mm) is required within the firestop system.

B. **Cross Linked Polyethylene (PEX) Tubing** — Nom 1 in. (2mm) diam (or smaller) SDR 9 PEX tubing for use in closed (process or supply) piping systems. A nom annular space of 1/4 in. (6 mm) is required within the firestop system.

C. **Acrylonitrile Butadiene Styrene (ABS) Pipe** — Nom 1-1/2 in. (38 mm) diam (or smaller) Schedule 40 cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. The annular space shall be min 1/4 in. (6 mm) to max 1 in. (25 mm).

C. **Acrylonitrile Butadiene Styrene (ABS) Pipe** — Nom 1-1/2 in. (38 mm) diam (or smaller) Schedule 40 cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. The annular space shall be min 1/4 in. (6 mm) to max 1 in. (25 mm).

https://iq.ulprospector.com/en/profile?e=176850

2/3

3/10/22, 9:17 AM

XHEZ.W-L-2100 - Through-penetration Firestop Systems | UL Product IQ

D. **Polyvinyl Chloride (PVC) Pipe** — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 cellular or solid core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. The annular space shall be min 0 in. (point contact) to max 1 in. (25 mm).

E. **Chlorinated Polyvinyl Chloride (CPVC) Pipe** — Nom 2 in. (51 mm) diam (or smaller) SDR 17 CPVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. The annular space shall be min 0 in. (point contact) to max 1 in. (25 mm). The hourly T, FT and FTH Ratings of the firestop system are dependent on the hourly fire rating of the wall assembly in which it is installed and the type of through penetrant, as shown in the table below:

Rating of Wall Hr	Type of Through Penetrant	T, FT, FTH Rating Hr
2	PB pipe	1-1/2
2	PEX tubing	1-1/2
2	PVC or CPVC pipe	1/4
2	ABS pipe	0
1	PB pipe	1
1	PEX tubing	1
1	PVC or CPVC pipe	1/4
1	ABS pipe	0

3. **Fill, Void or Cavity Material*** — **Sealant** — Min 5/8 in. (16 mm) thickness of fill material applied within annulus, flush with both surfaces of wall. Additional fill material to be installed such that a min 1/4 in. thick crown is formed around the penetrating item.
SPECIFIED TECHNOLOGIES INC — SpecSeal Series SSS Sealant or SpecSeal LCI Sealant

* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2021-10-11

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"

https://iq.ulprospector.com/en/profile?e=176850

3/3

3/10/22, 9:29 AM

XHEZ.W-L-2542 - Through-penetration Firestop Systems | UL Product IQ

UL Product iQ™

XHEZ.W-L-2542 - Through-penetration Firestop Systems

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

Through-penetration Firestop Systems

XHEZ - Through-penetration Firestop Systems

See General Information for Through-penetration Firestop Systems

System No. W-L-2542

March 07, 2017

F Ratings — 1 and 2 Hr (See Items 1 and 2)

T Ratings — 0, 1 and 2 Hr (See Items 1 and 2)


DETAIL 17 - PIPE PEN. @ WALL
UL DESIGN NO. W-L-2542
F RATING - 1 & 2 HOUR (SEE ITEM 1 & 2)
T RATING - 0, 1 & 2 HOUR (SEE ITEM 1 & 2)

https://iq.ulprospector.com/en/profile?e=177156

1/3

3/10/22, 9:29 AM

XHEZ.W-L-2542 - Through-penetration Firestop Systems | UL Product IQ



SECTION A-A

1. **Wall Assembly** — The 1 or 2 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300, U400, V400 or W400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:
A. **Studs** — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced max 24 in. (610 mm) OC.

B. **Gypsum Board*** — 5/8 in. (16 mm) thick, 4 ft (122 cm) wide with square or tapered edges. The gypsum board type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual Wall and Partition Design. Max diam of opening is 4 in. (102 mm).

The hourly F and T Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed unless noted otherwise.

2. **Through Penetrants** — One nonmetallic pipe to be installed either concentrically or eccentrically within the firestop system. Pipe to be rigidly supported on both sides of wall assembly. The following types and sizes of nonmetallic pipes may be used:
A. **Polyvinyl Chloride (PVC) Pipe** — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 solid core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. The annular space between pipe and periphery of opening shall be min 0 in. (point contact) to max 7/8 in. (22 mm). For use with 1 hr wall constructions only. When used, F Rating is 1 hr and T Rating is 0 hr.

B. **Polyvinyl Chloride (PVC) Pipe** — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 solid core PVC pipe for use in closed (process or supply) piping systems. The annular space between pipe and periphery of opening shall be min 1/4 in. (6 mm) to max 1-3/8 in. (35 mm).

C. **Chlorinated Polyvinyl Chloride (CPVC) Pipe** — Nom 2 in. (51 mm) diam (or smaller) SDR13.5 CPVC pipe for use in closed (process or supply) piping systems. The annular space between pipe and periphery of opening shall be min 1/4 in. (6 mm) to max 1-3/8 in. (35 mm).

D. **Acrylonitrile Butadiene Styrene (ABS) Pipe** — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 solid-core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. The annular space between pipe and periphery of opening shall be min 1/4 in. (6 mm) to max 7/8 in. (22 mm).

E. **Crosslinked Polyethylene (PEX) Tube** — Nom 1 in. (25 mm) diam (or smaller) SDR 9 PEX tubing for use in closed (process or supply) piping systems. The annular space between tube and periphery of opening shall be min 1/4 in.(6 mm) to max 1-3/8 in. (35 mm).

https://iq.ulprospector.com/en/profile?e=177156

2/3

3/10/22, 9:29 AM

XHEZ.W-L-2542 - Through-penetration Firestop Systems | UL Product IQ

F. **Rigid Nonmetallic Conduit*** — Nom 2 in. (51 mm) diam (or smaller), Schedule 40 PVC conduit installed in accordance with the National Electrical Code (NFPA No. 70). The annular space between conduit and periphery of opening shall be min 1/4 in. (6 mm) to max 1-3/8 in. (35 mm).

G. **Chlorinated Polyvinyl Chloride (CPVC) Pipe** — Nom 2 in. diam (or smaller) FLOWGUARD GOLD® SDR11 CPVC for use in closed (process or supply) piping systems. The annular space between conduit and periphery of opening shall be min 1/4 in. (6 mm) to max 1-3/8 in. (35 mm).

H. **Chlorinated Polyvinyl Chloride (CPVC) Pipe** — Nom 2 in. diam (or smaller) BLAZEMASTER® SDR13.5 CPVC for use in closed (process or supply) piping systems. The annular space between conduit and periphery of opening shall be min 1/4 in. (6 mm) to max 1-3/8 in. (35 mm).

3. **Firestop System** — The firestop system shall consist of the following:
A. **Packing Material** — (Optional) - In 2 hr wall assemblies, foam backer rod firmly packed into opening as a permanent form. Packing material to be recessed from both surfaces of wall as required to accommodate the required thickness of fill material.

B. **Fill, Void or Cavity Material*** — **Caulk** — Min 5/8 in. (16 mm) thickness of fill material applied within the annulus, flush with both surfaces of wall. Additional fill material to be installed such that a min 1/4 in. (6 mm) crown is formed around the penetrating item.
DAP PRODUCTS INC — DAP Blockade

* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2017-03-07

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"

https://iq.ulprospector.com/en/profile?e=177156

3/3

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

Consultants

Copyright Notice

— This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

WOODSPRING SUITES

CHOICE HOTELS

Drawn By:
ALW

Checked By:
JL

Document Date:
08/16/23

Protocol:
WSS_v4_2019.1 (01/31/19)

Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal

Sheet Title


FIRE RATED ASSEMBLIES

Sheet No.

A10.8

BRR Original printed on recycled paper

FOR REFERENCE ONLY



1 MECHANICAL FIRST FLOOR PLAN
SCALE: 1/8" = 1'-0"

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION

Project Name
WoodSpring Suites


Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO




Drawn By:
MR / CB / TP
Checked By:
AR / CF
Document Date:
08/16/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541

Professional Seal



8/15/2023 4:43:40 PM



2 EXHAUST DUCTWORK DETAIL - FIRST, SECOND, & THIRD FLOORS
SCALE: NOT TO SCALE



1 MECHANICAL SECOND FLOOR PLAN
SCALE: 1/8" = 1'-0"

brr
Architect of Record:
BRR Architecture, Inc.
8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204
www.brrarch.com
Tel: 913-262-9095
Fax: 913-262-9044

ACERTUS CONSULTING GROUP
ACERTUS CONSULTING GROUP, LLC
11800 COLLEGE BLVD STE 475
OVERLAND PARK, KS 66204
PH: 913-250-1100
www.AcertusGroup.com

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION

Project Name
WoodSpring Suites


Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO



Drawn By:
MR / CB / TP
Checked By:
AR / CF
Document Date:
08/16/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08


Project No.
31000541

Professional Seal



Sheet Title
MECHANICAL SECOND FLOOR PLANS
Sheet No.
M-3

BRR Original printed on recycled paper



1 MECHANICAL THIRD FLOOR PLAN
SCALE: 1/8" = 1'-0"

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION

Project Name
WoodSpring Suites


Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO




Drawn By:
MR / CB / TP
Checked By:
AR / CF
Document Date:
08/16/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541


Professional Seal



8/15/2023 4:43:51 PM



2 EXHAUST DUCTWORK DETAIL - FOURTH FLOOR
SCALE: NOT TO SCALE



1 MECHANICAL FOURTH FLOOR PLAN
SCALE: 1/8" = 1'-0"

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

ACERTUS CONSULTING GROUP



Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:

MR / CB / TP

Checked By:

AR / CF

Document Date:

08/16/23

Protocol:

WSS_v5_2023.1 (05/05/23)

Bulletins Through:

WSS_v2_B08

Project No.

31000541

Professional Seal



08/16/23


Sheet Title

MECHANICAL
FOURTH FLOOR
PLANS

Sheet No.

M-5

BRR Original printed on recycled paper



1 MECHANICAL ROOF PLAN
SCALE: 1/8" = 1'-0"

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

ACERTUS CONSULTING GROUP, LLC

11880 COLLEGE BLVD STE 475
OVERLAND PARK, KS 66204
PH: 913-230-3300
www.AcertusGroup.com

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION

Project Name
WoodSpring Suites

Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO



Drawn By:
MR / CB / TP

Checked By:
AR / CF


Document Date:
08/16/23

Protocol:
WSS_v5_2023.1 (05/05/23)

Bulletins Through:
WSS_v2_B08


Project No.
31000541

Professional Seal




08/16/23


10/5/2023 12:00:31 PM




4 ELEVATION AT DRYER EXHAUST
SCALE: 1/4" = 1'-0"




5 ELEVATION AT WATER HEATER FLUES
SCALE: 1/4" = 1'-0"




6 SECTION AT GUEST DRYERS
SCALE: 1/4" = 1'-0"



3 ENLARGED MECH. ROOM PLAN
SCALE: 1/4" = 1'-0"



1 ENLARGED GUEST LAUNDRY PLAN
SCALE: 1/4" = 1'-0"



2 ENLARGED LOBBY / STAFF LAUNDRY PLAN
SCALE: 1/4" = 1'-0"

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

ACERTUS CONSULTING GROUP

ACERTUS
CONSULTING GROUP, LLC
11800 COLLEGE BLVD STE 475
OVERLAND PARK, KS 66204
PH: 913-262-9095
www.AcertusGroup.com

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:
MR / CB / TP

Checked By:
AR / CF

Document Date:
10/04/23

Protocol:
WSS_v5_2023.1 (05/05/23)

Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal













































Sheet Title

MECHANICAL FIRST
FLOOR ENLARGED
PLANS

Sheet No.

M-7

BRR Original printed on recycled paper

PLUMBING LEGEND				
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	ABBREVIATIONS
	GATE VALVE		FLOOR DRAIN / AREA DRAIN	AD AREA DRAIN, ACCESS DOOR
	CHECK VALVE		FLOOR SINK	AFC ABOVE FINISH CEILING
	PRESSURE		AHU AIR HANDLING UNIT	AFG ABOVE FINISH GRADE
	SOLENOID VALVE		RD ROOF DRAIN	AHU AIR HANDLING UNIT
	GLOBE VALVE (STRAIGHT PATTERN)		ORD OVERFLOW ROOF DRAIN	BFP BACKFLOW PREVENTER
	BUTTERFLY VALVE		ORD OVERFLOW ROOF DRAIN	BOP BOTTOM OF PIPE
	BALL VALVE		PLUMBING VEVT THRU ROOF	BOS BOTTOM OF STRUCTURE
	GAS COCK		POINT OF CONNECTION (CONNECT NEW TO EXISTING)	CO CONDENSATE
	PLUG VALVE		PLUMBING EQUIPMENT DESIGNATION	CO CLEANOUT
	FLOOR CLEAN OUT		PLUMBING RISER OR DETAIL DESIGNATION	CW DOMESTIC COLD WATER
	WALL CLEAN OUT		SANITARY SEWER PIPING	DD DECK DRAIN
	CLEAN OUT		STORM SEWER PIPING	DN DOWN
	HOSE BIBB		VENT PIPING	ETR EXISTING TO REMAIN
	FREEZE PROOF WALL HYDRANT		VENT PIPING (BELOW SLAB)	EWC ELECTRIC WATER COOLER
	SHOWER HEAD.		COLD WATER PIPING	FCO FLOOR CLEANOUT
	ELBOW DOWN		HOT WATER PIPING	FFA FROM FLOOR ABOVE
	ELBOW UP		HOT WATER RECIRCULATING PIPING	FP FIRE PROTECTION
	TEE UP		GAS PIPING	FS FLOOR SINK
	TEE DOWN		CONDENSATE PIPING	G GAS (NATURAL)
	STRAINER			GCO GRADE CLEANOUT
	UNION			GPM GALLONS PER MINUTE
	CAP			HB HOSE BIBB
	FLEX PIPE			HW DOMESTIC HOT WATER

GENERAL NOTES

- DEFINITIONS:
FURNISH: THE TERM "FURNISH" IS USED TO MEAN "SUPPLY AND DELIVER TO THE PROJECT SITE, READY FOR UNLOADING, UNPACKING, ASSEMBLY, INSTALLATION AND SIMILAR OPERATIONS."

INSTALL: THE TERM "INSTALL" IS USED TO DESCRIBE OPERATIONS AT THE PROJECT SITE INCLUDING THE ACTUAL "UNLOADING, UNPACKING, ASSEMBLY, ERECTION, PLACING, ANCHORING, APPLYING, WORKING TO DIMENSION, FINISHING, CURING, PROTECTING, CLEANING, AND SIMILAR OPERATIONS."

PROVIDE: THE TERM "PROVIDE" MEANS "TO FURNISH AND INSTALL, COMPLETE AND READY FOR THE INTENDED USE."
- EXCEPT AS OTHERWISE NOTED, ALL SCHEDULED PLUMBING FIXTURES SHALL BE PROVIDED BY THE PLUMBING CONTRACTOR. THE PLUMBING CONTRACTOR SHALL MAKE ALL ROUGH-IN AND FINAL CONNECTIONS TO ALL PLUMBING EQUIPMENT.
- REFER TO PLUMBING FIXTURE SCHEDULE FOR PIPING RUNOUT SIZES TO INDIVIDUAL PLUMBING FIXTURES.
- DO NOT ROUTE ANY PIPING OVER ELECTRICAL ROOMS, COMPUTER ROOMS, OR ELECTRICAL PANELS.
- WATER PIPING INSTALLED IN EXTERIOR WALLS SHALL BE INSTALLED ON CONDITIONED SIDE OF INSULATION.
- UNDERSLAB WATER PIPING SHALL BE TYPE 'K' SOFT DRAWN WITH NO JOINTS.
- ALL DOMESTIC WATER PIPING IN CEILING SPACE SHALL BE ROUTED BELOW CEILING INSULATION. DO NOT INSTALL WATER PIPING ABOVE TOP FLOOR CEILING DRYWALL.
- PROVIDE PRESSURE REDUCERS AS REQUIRED IN WATER SUPPLY LINES TO KEEP PRESSURE BELOW 70 PSI AT ALL OUTLETS.
- PROVIDE PROPERLY SIZED WATER HAMMER ARRESTORS ON QUICK CLOSING VALVES.
- PROVIDE APPROVED BACKFLOW PREVENTION OR ANTI-SIPHON DEVICES AT ALL FIXTURES THAT COULD CONTAMINATE THE POTABLE WATER SYSTEM.
- PROVIDE TRAP PRIMERS ON ALL FLOOR DRAINS. LOCATE TRAP PRIMER VALVES IN ACCESSIBLE LOCATION. DO NOT LOCATE TRAP PRIMER VALVES OR PIPING IN AREAS ACCESSIBLE TO THE PUBLIC.
- ALL WORK SHALL COMPLY WITH CURRENT FEDERAL, STATE, AND LOCAL CODES AND ORDINANCES AS WELL AS THE CONSTRUCTION DOCUMENTS. REPORT ANY CONFLICTS TO THE ENGINEER AS SOON AS THEY ARE DISCOVERED.
- REVIEW THE DRAWINGS AND SPECIFICATIONS PRIOR TO BIDDING JOB AND DURING CONSTRUCTION. EXCEPT AS OTHERWISE NOTED, PROVIDE ALL EQUIPMENT, MATERIALS, & LABOR FOR A COMPLETE PROJECT AS SHOWN IN THE DRAWINGS AND SPECIFICATIONS. DRAWINGS AND SPECIFICATIONS CARRY EQUAL IMPORTANCE AND ITEMS LISTED IN EITHER SHALL BE PROVIDED AS IF LISTED IN BOTH. ALSO REVIEW DETAILS AND RISER DIAGRAMS FOR ADDITIONAL ITEMS/INSTRUCTIONS WHETHER SPECIFICALLY REFERRED TO ON PLANS OR NOT.
- DRAWINGS ARE DIAGRAMMATIC IN NATURE AND SHOW THE GENERAL INSTALLATION OF EQUIPMENT & MATERIALS IN RELATIONSHIP TO STRUCTURE & OTHER TRADES. THEY MAY NOT SHOW EVERY REQUIRED OFFSET, FITTING, ETC. FIELD VERIFY ACTUAL JOB CONDITIONS AND COORDINATE WORK WITH OTHER TRADES PRIOR TO BIDDING JOB AND PRIOR TO ORDERING EQUIPMENT, FABRICATION OF MATERIALS, OR STARTING WORK. DO NOT SCALE THE DRAWINGS.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL ITEMS THAT AFFECT OTHER DISCIPLINES WITH THE CORRESPONDING CONTRACTOR AND THE GENERAL CONTRACTOR IF EQUIPMENT, MATERIALS, ETC. OTHER THAN THOSE SCHEDULED & SPECIFIED (PENDING PRE-APPROVAL) ARE FURNISHED.
- CHANGE ORDERS WILL NOT BE GRANTED DUE TO LACK OF COORDINATION WITH JOB CONDITIONS AND/OR OTHER CONTRACTORS.
- MAINTAIN ALL REQUIRED SERVICE, FRESH AIR, & ROOF EDGE CLEARANCES FOR ALL NEW AND EXISTING EQUIPMENT, AND PLUMBING VENTS.
- UPON COMPLETION OF THE PROJECT PROVIDE AS-BUILT DRAWINGS TO THE OWNER, ARCHITECT, AND ENGINEER SHOWING EQUIPMENT, PIPING, ETC. THAT DIFFERS FROM CONSTRUCTION DOCUMENTS AS THEY ARE ACTUALLY INSTALLED.
- THE RESPONSIBILITY OF EACH CONTRACTOR IS NOT LIMITED TO THEIR SPECIFIC DISCIPLINE'S DRAWING SHEETS. REFER TO OTHER DISCIPLINES' DRAWING SHEETS AS REQUIRED FOR ADDITIONAL INFORMATION/INSTRUCTIONS.
- FIRE SEAL ALL PENETRATIONS THROUGH RATED WALLS. SLEEVE IN ENTIRETY WITH APPROPRIATE SLEEVE MATERIAL.

NOTE:

NO SUBSTITUTIONS OF VENDORS OR PRODUCT ON EQUIPMENT UNLESS APPROVED BY WOODSPRING SUITES, THE ARCHITECT AND THE OWNER.

PLUMBING FIXTURE SCHEDULE

MARK	FIXTURE TYPE	MANFUACTURER	MODEL	CONSTRUCTION MATERIAL	SIZE (IN)	MOUNTING	TRIM		REMARKS
							FAUCET/VALVE MFG. & MODEL	STRAINER/ GRATE TYPE	
BP-1	BOOSTER PUMP	TOWLE WHITNEY	TW2000U-150G-40	DUPLEX SYSTEM					
ET-1	EXPANSION TANK	AMTROL	ST-42V						
FCO	CLEANOUT	ZURN	ZN1400-TX	CI W/NICKEL BRONZE COVER	SEE PLANS	FLOOR	--	--	--
GCO	CLEANOUT	ZURN	Z1400-BZ1	CAST IRON	SEE PLANS	FLOOR	--	--	--
FD	FLOOR DRAIN	ZURN	ZN415-5B	CI W/NICKEL BRONZE STRAINER	SEE PLANS	FLOOR	--	YES	16
LI	LINT INTERCEPTOR	STRIEM PRODUCTS	AA-4	POLYETHYLENE					19
P-1	WATER CLOSET	AMERICAN STANDARD	3517C101020, 4188A004020 ALT: GERBER GVP21562, GVP 28590WH	VITREOUS CHINA	N/A	FLOOR	--	--	1
P-1H	WATER CLOSET	AMERICAN STANDARD	3517A101020, 4188A004020 ALT: GERBER GVP21528, GVP 28590WH	VITREOUS CHINA	N/A	FLOOR	--	--	1
P-2	LAVATORY	PROFLO	PF1812UWH	--	--	COUNTER	DELTA 559LF-HGM-MPU	POP-UP	3
P-2H	LAVATORY	PROFLO	PF1812UWH	--	--	COUNTER	DELTA 559LF-HGM-MPU	POP-UP	3, 4
P-3	TUB/SHOWER	AQUATIC	2603SGM	GELCOAT	60X33	--	DELTA T17459 DELTA 52637	PROFLO PFW0352	5, 6, 8, 11, 12
P-3H	TUB/SHOWER	AQUATIC	2603SMTE	GELCOAT	60X33	--	DELTA T17459, T11861, RPW324HDF	PROFLO PFW0352	5, 7, 8, 11, 12, 22
P-4H	ROLL IN SHOWER	AQUATIC	16030BFSC	GELCOAT	62X33	--	DELTA T17259, T11861, RPW324HDF	PROFLO PF140NC	5, 9, 10, 11, 12, 22
P-5	SINK	PROFLO	PFU301A	STAINLESS STEEL	25X22	COUNTER	DELTA D1953LF	PROFLO F1435SS	13
P-5H	SINK	PROFLO	PFUC301A6	STAINLESS STEEL	25X22	COUNTER	PEERLESS P188200LF	PROFLO F1435SS	4, 13
P-6	LAVATORY	ZURN	Z5344	VITREOUS CHINA	20X18	WALL	DELTA 501LF-HDF	GRID	3, 4, 11, 14
P-7	MOP BASIN/TRENCH	--	---	--	--	FLOOR	DELTA 28C2063	--	15
P-8	WASHING MACHINE BOX	IPS CORP	82359	--	--	WALL	--	--	--
P-9	LAUNDRY SINK	MUSTEE	26F	DURASTONE	40X24	FLOOR	DELTA 2133LF	--	13
P-10	HOSE BIBB	WOODFORD	26C						
P-11	HOSE BIBB	WOODFORD	17CP-12-MH						
P-12	TRENCH DRAIN	JAY R. SMITH	9667-SG	STAINLESS STEEL	2X60	FLOOR			2, 21
RD	ROOF DRAIN	ZURN	Z100	CI W/POLY DOME	SEE PLANS	ROOF	--	YES	--
RP	RECIRC PUMP	GRUNDFOS	UP26-96F		115V/1PH		HONEYWELL L6006A1145, 121371B		
SP	SUMP PUMP	ZOELLER	Z940-0013		115V/1PH				20
TMV	THERMOSTATIC MIXING VALVE	SYMMONS	7-1000-W			WALL			
TP-1	TRAP PRIMER	PPP INC.	PR-500	BRASS	--	--	DUU	--	--
WCO	CLEANOUT	ZURN	Z1446	STAINLESS	SEE PLANS	WALL			
WH-1, 2, 3	WATER HEATER	A. O. SMITH	BTH199A00N00000 ALT: STATE SUF100199NEE		100 GAL				18


GENERAL FIXTURE ACCESSORY NOTES:

- PROVIDE CARRIERS FOR ALL WALL HUNG WATER CLOSETS, URINALS, LAVATORIES, & DRINKING FOUNTAINS.
- PROVIDE ALL ADA SINKS WITH REAR CENTERED DRAIN OPENINGS.
- PROVIDE ALL ADA LAVATORIES & SINKS NOT PROTECTED BY AN ARCHITECTURAL SKIRT PANEL WITH UNDERSINK PIPING COVERS EQUAL TO TRUEBRO LAVGARD 2.
- PROVIDE ALL ADA WATER CLOSETS & URINALS WITH THE FLUSH LEVER ON THE WIDE SIDE OF THE FIXTURE. SEE PLANS.
- PROVIDE ALL LAVATORY & SINK P-TRAPS WITH INTEGRAL CLEANOUT PLUGS.
- UNLESS OTHERWISE NOTED IN REMARKS SECTION, PROVIDE ALL WATER CLOSETS FURNISHED WITH WHITE OPEN FRONT SEATS, INCLUDING COVERS.
- UNLESS OTHERWISE NOTED, PIPING CONNECTION SIZES OF ALL FLOOR DRAINS, FLOOR SINKS, & CLEANOUTS SHALL MATCH PIPING RUNOUT SIZE SHOWN ON PLANS.
- SEE PLANS FOR ROOF DRAIN PIPING CONNECTION SIZES.
- VERIFY CORRECT DIMENSIONS WITH ARCHITECTURAL PLANS.
- PROVIDE RIGHT OR LEFT HAND DRAIN AS REQUIRED. REFER TO PLANS.
- PROVIDE WITH PROFLO PFTPB100 TAILPIECE, PFTPB403 P-TRAP, PFX146322 SUPPLIES, PFX1AC32CLK 1/4 TURN STOPS.
- PROVIDE LEONARD 170 MIXING VALVE AS REQUIRED BY LOCAL CODE.
- PROVIDE PROFLO PFSSHE HOSE & PF296 HOSE HANGER.
- PROVIDE WITH TRAP PRIMER CONNECTION.
- CLEANOUT FITTING & PLUG TO BE PROVIDED IN ROUGH-IN MATERIAL.
- 199MBTU 96% EFF, INCL STATE S9006328005 CONCENTRIC VENT KIT.
- PROVIDE EXTENSION IF REQUIRED.
- PROVIDE WITH ZOELLER 2" Z30-0101 BALL VALVE/CHECK VALVE, JACKEL FWB24X36FAGF, JC24B, SIH4, E200H. PROVIDE ALARM PANEL, OIL SWITCH, AND PUMP.
- 60" LENGTH FOR ROLL-IN SHOWER WITH NO FLASHING FLANGE.
- PROVIDE DELTA R11000 ROUGH IN VALVE.

ROUGH-IN & INSTALLATION NOTES:

- UNLESS OTHERWISE NOTED, PC SHALL FURNISH, INSTALL, & CONNECT ALL SCHEDULED PLUMBING FIXTURES.
- INSTALLATION OF ADA FIXTURES SHALL MEET FEDERAL ADA STANDARDS.
- SEE ARCHITECTURAL PLANS & ELEVATIONS FOR INSTALLATION HEIGHTS OF ALL PLUMBING FIXTURES.
- PROVIDE TRAP PRIMERS TO SERVE ALL FLOOR DRAINS.
- PLUMBING CONTRACTOR SHALL SUPPLY & INSTALL ALL ACCESSORIES, VALVES, WATER HAMMER ARRESTORS, ETC. NOT SCHEDULED OR CALLED OUT ON PLANS BUT REQUIRED TO MAKE THE PLUMBING SYSTEM COMPLETE.
- UNLESS OTHERWISE NOTED IN REMARKS SECTION, FIXTURE ROUGH-IN & CONNECTION PIPING SIZES SHALL BE AS INDICATED IN ADJACENT TABLE.

PLUMBING FIXTURE	TRAP	WASTE		VENT	COLD WATER	HOT WATER
		ABOVE GRADE	BELOW GRADE			
WATER CLOSET-FLUSH TANK	--	3"	3"	2"	1/2"	--
LAVATORY	1-1/2"	1-1/2"	2"	1-1/2"	1/2"	1/2"
BATHTUB/SHOWER	2"	2"	2"	1-1/2"	1/2"	1/2"
SINK-HAND, BAR, RESIDENTIAL KITCHEN	1-1/2"	1-1/2"	1/2"	1-1/2"	1/2"	1/2"
SINK-COMMERCIAL KITCHEN	1-1/2"	1-1/2"	2"	1-1/2"	3/4"	3/4"
RESIDENTIAL CLOTHES WASHER/WASHER BOX	2"	2"	2"	1-1/2"	3/4"	3/4"
MOP BASIN/SERVICE SINK	3"	3"	3"	2"	3/4"	3/4"
WALL HYDRANT/HOSE BIBB	--	--	--	--	3/4"	--




Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

ACERTUS CONSULTING GROUP



ACERTUS
CONSULTING GROUP, LLC

11800 COLLEGE BLVD STE 475
OVERLAND PARK, KS 66204
PH: 913-262-9095
www.AcetusGroup.com

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions


NO	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO



WOODSPRING
SUITES

Drawn By:
MR / CB / TP

Checked By:
AR / CF

Document Date:
08/16/23


Protocol:
WSS_v5_2023.1 (05/05/23)

Bulletin Through:
WSS_v2_B08

Project No.

31000541

Professional Seal



STATE OF MISSOURI
RANDALL A. NELSON
NUMBER
PE-2007003990
PROFESSIONAL ENGINEER

08/16/23


Sheet Title

PLUMBING NOTES AND LEGENDS

Sheet No.

P-1

BRR Original printed on recycled paper




DRAINAGE FIXTURE UNIT			
FIXTURE	QUANTITY	WASTE	TOTAL
WATER CLOSET	1	4	4
LAVATORY	1	1	1
BATHROOM GROUP	122	5	610
SINK	122	2	244
LAUNDRY SINK	1	2	2
3" FLOOR DRAIN	4	5	20
EMERGENCY FLOOR DRAIN	5	0	0
BREAK ROOM SINK	1	2	2
PUBLIC WASHING MACHINE	6	3	18
EXTRACTORS	2	6	12
MOP SINK	1	3	3
TOTAL			916

PROVIDE CLEANOUTS
AT THE BASE OF ALL
WASTE RISERS

1 FIRST FLOOR WASTE & VENT
SCALE: 1/8" = 1'-0"

10/5/2023 12:00:49 PM



1 SECOND FLOOR WASTE & VENT
SCALE: 1/8" = 1'-0"



Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

ACERTUS CONSULTING GROUP

ACERTUS
CONSULTING GROUP, LLC
11880 COLLEGE BLVD. STE. 475
OVERLAND PARK, KS 66204
PH: 913-251-5500
www.AcertusGroup.com

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name
WoodSpring Suites

Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO

Drawn By:
MR / CB / TP
Checked By:
AR / CF
Document Date:
10/04/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541


Professional Seal

Sheet Title
PLUMBING WASTE AND VENT PLANS - 2ND FLOOR

Sheet No.
P-3

BRR Original printed on recycled paper

10/5/2023 12:00:54 PM



1 THIRD FLOOR WASTE & VENT
SCALE: 1/8" = 1'-0"

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name
WoodSpring Suites


Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO



Drawn By:
MR / CB / TP
Checked By:
AR / CF
Document Date:
10/04/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541


Professional Seal



Sheet Title
PLUMBING WASTE AND VENT PLANS - 3RD FLOOR

Sheet No.
P-4

BRR Original printed on recycled paper



1 FOURTH FLOOR WASTE & VENT
SCALE: 1/8" = 1'-0"

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION

Project Name
WoodSpring Suites


Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO



Drawn By:
MR / CB / TP
Checked By:
AR / CF
Document Date:
08/16/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08


Project No.
31000541

Professional Seal



Sheet Title
PLUMBING WASTE AND VENT PLANS - 4TH FLOOR

Sheet No.
P-5



1

- | WATER FIXTURE UNIT | | | |
|--------------------|----------|-------|-------|
| FIXTURE | QUANTITY | WATER | TOTAL |
| WATER CLOSET | 1 | 2.2 | 2.2 |
| LAVATORY | 1 | 0.7 | 0.7 |
| BATHROOM GROUP | 122 | 3.6 | 439.2 |
| SINK | 122 | 1.4 | 170.8 |
| LAUNDRY SINK | 1 | 1.4 | 1.4 |
| WASHERS | 6 | 3 | 18 |
| COMMERCIAL WASHER | 2 | 4 | 8 |
| HOSE BIBB | 2 | 2.5/1 | 3.5 |
| MOP SINK FAUCET | 1 | 3 | 3 |
| BREAK ROOM SINK | 1 | 1.4 | 1.4 |
| | | TOTAL | 648.4 |

[illegible]

WoodSpring Suites

1010 NW WARD ROAD LEE
SUMMIT, MO




31000541



Sheet No. _____

Sheet No. **P-6**





1 THIRD FLOOR DOMESTIC WATER PLAN
SCALE: 1/8" = 1'-0"

- PLUMBING KEY NOTES (1,2,X)
- 2 1/2" HOT WATER UP FROM 1ST FLOOR CEILING.
 - 2 1/2" COLD WATER UP FROM 1ST FLOOR CEILING.
 - 1 1/2" HOT WATER RETURN DOWN TO 1ST FLOOR MECHANICAL ROOM.
 - SEE RISER DETAIL 1 ON SHEET P9.
 - SEE RISER DETAIL 2 ON SHEET P9.
 - DO NOT ROUTE WATER IN EXTERIOR WALLS. SINK SUPPLY TO BE THROUGH FLOOR.
 - PROVIDE CPVC EXPANSION JOINT PER MANUFACTURER'S INSTRUCTIONS. SIMILAR TO FLEXICRAFT MODEL CP. INSTALL AS REQUIRED THROUGHOUT WATER SYSTEM.
 - PROVIDE COPPER MANIFOLD FOR WATER DISTRIBUTION. PROVIDE ISOLATION VALVES UP STREAM OF MANIFOLD FOR COMPLETE SYSTEM ISOLATION. (TYPICAL) MANIFOLDS TO BE INSTALLED IN CORRIDOR. COORDINATE MANIFOLDS OUTSIDE OF CORRIDOR HARD LID CEILINGS. REF. ARCHITECTURAL PLANS FOR HARD LID CEILING LOCATIONS. REFER TO DETAIL 6/P6.

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

ACERTUS CONSULTING GROUP

ACERTUS
CONSULTING GROUP, LLC

11800 COLLEGE BLVD STE 475
OVERLAND PARK, KS 66204
PH: 913-262-9044
www.AcetusGroup.com

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO



Drawn By:
MR / CB / TP

Checked By:
AR / CF

Document Date:
08/16/23


Protocol:
WSS_v5_2023.1 (05/05/23)

Bulletins Through:
WSS_v2_B08


Project No.


31000541


Professional Seal




- 1 DOUBLE SANITARY TEE FITTING IS NOT TO BE USED AT BACK-TO-BACK WC. USE DOUBLE SANITARY WYE OR SINGLE FITTINGS.
- 2 PROVIDE CLEANOUTS AT THE BASE OF ALL WASTE RISERS.
- 3 AT KITCHEN SINKS IN GUESTROOM AREAS (P-5 AND P-5H), COORDINATE AND INSTALL THE HUB OF THE 3" WASTE STACKS ABOVE CEILINGS OR BELOW FLOORS.
- 4 GENERAL CONTRACTOR AND PLUMBING CONTRACTOR TO COORDINATE WITH OTHER TRADES TO ENSURE ADEQUATE SPACE FOR PIPING SYSTEMS.
- 5 PROVIDE TRAP PRIMERS ON ALL FLOOR DRAINS.









9 TRAP PRIMER DETAIL
SCALE: NOT TO SCALE




7 ENLARGED MECHANICAL ROOM PLAN
SCALE: 1/4" = 1'-0"




6 TYPICAL THIRD FLOOR WATER
SCALE: 1/4" = 1'-0"




5 TYPICAL FIRST FLOOR WATER
SCALE: 1/4" = 1'-0"




4 TYPICAL FOURTH FLOOR WASTE & VENT
SCALE: 1/4" = 1'-0"



3 TYPICAL THIRD FLOOR WASTE & VENT
SCALE: 1/4" = 1'-0"



2 TYPICAL SECOND FLOOR WASTE & VENT
SCALE: 1/4" = 1'-0"



1 TYPICAL FIRST FLOOR WASTE & VENT
SCALE: 1/4" = 1'-0"

NO.	DATE	DESCRIPTION
2	10/04/23	REV 2



1. IF REQUIRED BY LOCAL CODE, ELECTRICAL CONTRACTOR SHALL PROVIDE SHUNT TRIP BREAKERS IN PANEL MDP AND REMOTE EXTERIOR LOCABLE BUILDING POWER OFF DEVICE TO ACTIVATE SHUNT TRIPS TO KILL ALL POWER TO BUILDING. IF UTILITY COMPANY AVAILABLE FAULT CURRENT EXCEEDS 65K AIC, PROVIDE CURRENT LIMITERS ON EACH SERVICE ENTRANCE CONDUCTOR. VERIFY ALL REQUIREMENTS WITH THE LOCAL AUTHORITY HAVING JURISDICTION PRIOR TO BID.
2. CONTRACTOR SHALL VERIFY WITH THE OWNER IF LIGHTNING PROTECTION IS REQUIRED ON THE PROJECT. LIGHTNING PROTECTION SHALL BE INCLUDED IN BID WHEN REQUIRED.
3. ALL FLOOR MOUNTED ELECTRICAL EQUIPMENT SHALL BE MOUNTED ON 6" HIGH CONCRETE HOUSEKEEPING PAD.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THAT GEAR PROVIDED FOR PROJECT FITS IN THE SPACE PROVIDED.
5. ALL FEEDERS ARE TO BE ALUMINUM (UNLESS NOTED OTHERWISE). IF COPPER FEEDERS ARE REQUIRED BY LOCAL JURISDICTION, CONDUIT AND WIRE TO BE RESIZED BY ELECTRICAL ENGINEER. ALL BRANCH CIRCUITS ARE TO BE COPPER.
6. AVAILABLE FAULT CURRENT AT UTILITY TRANSFORMER IS ASSUMED TO BE 65,000A. LENGTH OF FEEDER FROM UTILITY TRANSFORMER TO MDP IS ASSUMED TO BE 50'-0". VERIFY ALL ASSUMPTIONS IN FIELD AND NOTIFY ENGINEER IF THERE ARE ANY DISCREPANCIES.

PANELBOARD DP2														
BUS AMPS: MAIN SIZE / TYPE: VOLTSPHASE: MOUNTING:				600A MLO 20R120V/ 3PH 4W SURFACE		LOCATION: NEMA RATING: AFC VALUE: ARC RATING:		UTILITY ROOM 440 NEMA 1 19.410A 65,000 SERIES RATED		GROUND BUS: ISOL. GROUND BUS: FEED THRU LUGS: SECTIONS:		YES NO NO 3 OF 1		
CKT #	CIRCUIT DESCRIPTION	BREAKER AMPS	P	WIRE SIZE	LOAD (VA)	CONNECTED PER PHASE (VA)			LOAD (VA)	WIRE SIZE	BREAKER P AMPS	CIRCUIT DESCRIPTION	CKT #	
						A	B	C						
1	PANELBOARD G (3 UNITS)	125	2	RD	22,575 14,232	45,150		28,464	22,575 14,232	RD	2	125	PANELBOARD G (3 UNITS)	2
3	PANELBOARD G (3 UNITS)	125	2	RD	22,575 14,232				45,150	RD	2	125	PANELBOARD G (3 UNITS)	4
5	PANELBOARD G (3 UNITS)	125	2	RD	22,575 14,232			52,675	33,208	RD	2	125	PANELBOARD G (4 UNITS)	6
7	PANELBOARD G (4 UNITS)	125	2	RD	30,100 18,976	60,200		37,952	30,100 18,976	RD	2	125	PANELBOARD G (4 UNITS)	8
9	PANELBOARD G (4 UNITS)	125	2	RD	30,100 18,976				60,200	RD	2	125	PANELBOARD G (4 UNITS)	10
11	PANELBOARD G (4 UNITS)	125	2	RD	30,100 18,976	37,952			30,100 18,976	RD	2	125	PANELBOARD G (4 UNITS)	12
13	PANELBOARD G (4 UNITS)	125	2	RD	30,100 18,976	60,200		37,952	30,100 18,976	RD	2	125	PANELBOARD G (4 UNITS)	14
15	PANELBOARD G (4 UNITS)	125	2	RD	30,100 18,976			37,952	30,100 18,976				SPACE ONLY	16
17	SPACE ONLY					18,976			30,100 18,976	RD	2	125	PANELBOARD G (4 UNITS)	18
PER PHASE SUB-TOTALS						250,942	247,343	225,586	LEGEND:					
TOTAL CONNECTED PANELBOARD (VA)						723,871	TS - VIA TIME SWITCH				ST - SHUNT TRIP			
TOTAL CONNECTED PANELBOARD (AMPS)						2,009	GF - GROUND FAULT INTERRUPTER				LK - LOCKING TAB			
TOTAL PANELBOARD DEMAND (VA)						154,475	FA - FIRE ALARM / RED / LOCKING TAB				IO - ISOLATED GROUND			
TOTAL PANELBOARD DEMAND (AMPS)						429	EM - EMERGENCY LTD / LOCKING TAB				IR - RISER DIAGRAM			

NOTE 1:
PER ARTICLE 250.92 CONTRACTOR SHALL INSTALL #400kcmil BONDING CONDUCTOR FROM EACH SERVICE ENTRANCE CONDUIT TO NEUTRAL BUS IN 'MDP' PROVIDE ALL BONDING OF EQUIPMENT AS REQUIRED.

PANELBOARD MDP														
BUS AMPS: MAIN SIZE / TYPE: VOLTS/PHASE: MOUNTING:				1600A MLO 208Y/120V, 3PH, 4W SURFACE		LOCATION: NEMA RATING: AFC VALUE ARC RATING:		ELECTRICAL ROOM 145 NEMA 1 / SE RATED 54.885A 85.000A FULLY RATED		GROUND BUS: ISOL. GROUND BUS: FEED THRU LUGS:		YES NO NO 1 OF 1		
CKT #	CIRCUIT DESCRIPTION	BREAKER AMPS	P	WIRE SIZE	LOAD (VA)	CONNECTED PER PHASE (VA)			LOAD (VA)	WIRE SIZE	BREAKER P	AMPS	CIRCUIT DESCRIPTION	CKT #
						A	B	C						
1	PANELBOARD DP1	600	3	RD	267,955	518,897			250,942	RD	3	600	PANELBOARD DP2	2
					250,612		506,955	247,343						
					245,360		470,966	225,586						
					11,943	38,541		26,896						
3	PANELBOARD A	225	3	RD	14,359		39,972	25,613	RD	3	225	PANELBOARD D	4	
					12,421			39,695						27,274
					5,404	35,387		29,983						
					5,404		37,332	31,928						
5	ELEVATOR	60	3	RD	5,404			35,820	RD	3	400	PANELBOARD B	6	
					5,404			30,422						
					5,404									
PER PHASE SUB-TOTALS						592,825	584,259	546,487	LEGEND:					
TOTAL CONNECTED PANELBOARD (VA)						1,701,970			TS - SHUNT TRIP					
TOTAL CONNECTED PANELBOARD (AMPS)						4,724			GF - GROUND FAULT INTERRUPTER					
TOTAL PANELBOARD DEMAND (VA)						528,065			FA - FIRE ALARM / REDUCING TAB					
TOTAL PANELBOARD DEMAND (AMPS)						1,466			EM - EMERGENCY LTG / LOCKING TAB					
ST - SHUNT TRIP LK - LOCKING TAB IG - ISOLATED GROUND RD - RE: RISER DIAGRAM														

SCALE: NOT TO SCALE




PANELBOARD DP2 DEMAND CALCULATION			
BASED ON NEC ARTICLE 220.84, OPTIONAL CALCULATION - MULTIFAMILY DWELLING			
NO. OF SUITES	SUITE TYPE	SUITE SQFT	TOTAL
34	QUEEN SUITE	257 SQFT=	8738.00
2	ACC. QUEEN SUITE	310 SQFT=	620.00
4	DELUXE QUEEN SUITE	330 SQFT=	1320.00
1	ACC. DELUXE QUEEN SUITE	420 SQFT=	420.00
16	DOUBLE QUEEN SUITE	310 SQFT=	4960.00
2	ACC. DOUBLE QUEEN SUITE	420 SQFT=	840.00
59	UNITS WITH A TOTAL SF OF:		16898.00
ROOM LIGHTING AND GENERAL RECEPTACLE WATTAGE (3W/SQFT)			50.69 KVA
SMALL APPLIANCE RECEPTACLES (3,000VA/SUITE)			177.00 KVA
RANGE CONNECTION (2,400VA/SUITE)			141.60 KVA
MICROWAVE RECEPTACLE (1,200VA/SUITE)			70.80 KVA
REFRIGERATOR RECEPTACLE (900VA/SUITE)			53.10 KVA
DISHWASHER RECEPTACLE (NA) (744VA/SUITE)			0.00 KVA
EXHAUST FAN CONNECTIONS (50VA/SUITE)			2.95 KVA
TOTAL LOAD (MINUS HVAC):			496.14 KVA
HVAC LOADS			
2500 HEATING (VA)		1373	COOLING (VA)
HEATING/COOLING FOR 59 SUITES:		147.50 KVA	81.01 KVA
LARGER OF HEATING/COOLING LOADS:		147.50 KVA	
TOTAL LOAD:		643.64 KVA	24% DEMAND:
			154.47 KVA
TOTAL AMPS AT 120/208V, 3PH:			428.78 AMPS

PANELBOARD A																										
BUS AMPS: MAIN SIZE / TYPE: VOLTS/PHASE: MOUNTING:					225A MLO 208Y/120V, 3PH, 4W SURFACE					LOCATION: NEMA RATING: AFC VALUE: AIC RATING:					ELECTRICAL ROOM 145 NEMA 1 41.311A 65,000A SERIES RATED					GROUND BUS: ISOL. GROUND BUS: FEED THRU LUGS: SECTIONS:					YES NO NO 1 OF 1	
CKT #	CIRCUIT DESCRIPTION	BREAKER AMPS	P	WIRE SIZE	LOAD (VA)	CONNECTED PER PHASE (VA)			LOAD (VA)	WIRE SIZE	BREAKER AMPS	P	AMPS	CIRCUIT DESCRIPTION	CKT #	1 OF 1										
						A	B	C																		
1	ELECTRICAL/MECHANICAL LIGHTING	20	1	12	297	1,497			1,200	6	1	20	BUILDING SIGNAGE	2												
3	FCU-6	40	2	8	2,877		4,077		1,200	8	1	20	BUILDING SIGNAGE	4												
5					2,877			4,077	1,200	10	1	20	BUILDING SIGNAGE	6												
7	MOTORIZED DAMPER	20	1	12	500	1,700			1,200	8	1	20	BUILDING SIGNAGE	8												
9	SPARE	20	1	1	0		1,188		1,188	4	1	20	SITE LIGHTING	10												
11	SPARE	20	1	1	0			1,040	1,040	4	1	20	SITE LIGHTING	12												
13	THIRD FLOOR PTAC-2	20	2	10	1,750	2,790			1,040	4	1	20	SITE LIGHTING	14												
15					1,750		2,494		744	12	1	20	WATER HEATER	16												
17	FOURTH FLOOR PTAC-2	20	2	10	1,750		2,494		744	12	1	20	WATER HEATER	18												
19					1,750	2,494			744	12	1	20	WATER HEATER	20												
21	EUH-2	20	2	12	1,500		3,250		1,750	12	2	20	FIRST FLOOR PTAC-2	22												
23					1,500			3,250	1,750					24												
25	EUH-4	20	2	12	1,500		3,250		1,750	12	2	20	SECOND FLOOR PTAC-2	26												
27					1,500			3,250	1,750					28												
29	CARD READER	20	1	8	500			680	180	12	1	20	ELECTRICAL ROOM RCPT	30												
31	SPARE	20	1	1	0	0			0	1	20	SPARE	32													
33	SPARE	20	1	1	0		100		100	12	1	20	TIME SWITCH / CONTACTORS	34												
35	SPARE	20	1	1	0			880	880	6	1	20	EXTERIOR BUILDING LIGHTING	36												
37	SPARE	20	1	1	0	212			212	8	1	20	EXTERIOR / EM LIGHTING	38												
39	SPARE	20	1	1	0		0		0	1	20	SPARE	40													
41	SPARE	20	1	1	0		0		0	1	20	SPARE	42													
PER PHASE SUB-TOTALS						11,943	14,359	12,421	LEGEND:																	
TOTAL CONNECTED PANELBOARD (VA)						38,722			TS - VIA TIME SWITCH				ST - SHUNT TRIP													
TOTAL CONNECTED PANELBOARD (AMPS)						107			GF - GROUND FAULT INTERRUPTER				LCK - LOCKING TAB													
TOTAL PANELBOARD DEMAND (VA)						42,393			FA - FIRE ALARM / RED / LOCKING TAB				IG - ISOLATED GROUND													
TOTAL PANELBOARD DEMAND (AMPS)						118			EM - EMERGENCY LTG. / LOCKING TAB				RD - RE. RISER DIAGRAM													
									C - ROUTE VIA CONTACTOR																	

PANELBOARD B																										
BUS AMPS: MAIN SIZE / TYPE: VOLTS/PHASE: MOUNTING:					400A MLO 208Y/120V, 3PH, 4W SURFACE					LOCATION: NEMA RATING: AFC VALUE: AIC RATING:					STORAGE 144 NEMA 1: 15,906A 42,000A SERIES RATED					GROUND BUS: ISOL. GROUND BUS: FEED THRU LUGS: SECTIONS:					YES NO NO 1 OF 1	
CKT #	#	CIRCUIT DESCRIPTION	BREAKER AMPS	P	WIRE SIZE	LOAD (VA)	CONNECTED PER PHASE (VA)			LOAD (VA)	WIRE SIZE	BREAKER AMPS	P	AMPS	CIRCUIT DESCRIPTION	CKT #										
							A	B	C																	
1		FIRST FLOOR PTAC-2	20	2	10	1,750	3,010			1,260	8	1	20		FIRST FLOOR RCPT	2										
3						1,750		2,886		1,136	10	1	20		FIRST FLOOR / EM LTG	4										
5		SECOND FLOOR PTAC-2	20	2	12	1,750			3,010	1,260	8	1	20		SECOND FLOOR RCPT	6										
7						1,750	2,560			810	10	1	20		SECOND FLOOR / EM LTG	8										
9		ELECTRIC ROOM PTAC-3	20	2	10	1,450		1,990		540	12	1	20		SECOND FLOOR UTILITY RCPT	10										
11						1,450			1,990	540	12	1	20		ROUTER	12										
13		SECOND FLOOR PTAC-2	20	2	8	1,750	2,310			560	10	1	20		STAIRWELL / EM LTG	14										
15						1,750		2,750		1,000	12	1	20		CATV	16										
17		SPARE	20	1	1	0			1,000	1,000	10	1	20		ITB	18										
19		SPARE	20	1	1	0	1,000			1,000	10	1	20		ITB	20										
21		EUH-1	20	2	10	1,500		2,500		1,000	12	1	20		TTB	22										
23						1,500			1,700	200	12	1	20		FIRE SMOKE DAMPERS	24										
25		EUH-3	20	2	8	1,500	2,500			1,000	12	1	20		PACP	26										
27						1,500		1,704		204	12	1	20		RCPT-1	28										
29		LOBBY RCPT	20	1	12	1,080			1,580	500	8	1	20		DOOR MAG-LOCK SYSTEM	30										
31		SUMP PUMP	20	1	12	1,170	1,670			500	12	1	20		OCV MONITORS	32										
33		ELEVATOR SHAFT RCPT	20	1	12	380		540		180	12	1	20		TWO-WAY COMM. STATION	34										
35		ELEVATOR CAB	20	1	12	1,000			2,500	1,500	12	1	20		VENDING	36										
37		ELEVATOR SHAFT LIGHTING	20	1	12	120	1,620			1,500	12	1	20		VENDING	38										
39		STORAGE AND BATHROOM LTG	20	1	12	243		1,743		1,500	12	1	20		VENDING	40										
41		SPARE	20	1	1	0			1,500	1,500	12	1	20		VENDING	42										
43		STORAGE AND VENDING RCPT	20	1	12	900	1,150			250						44										
45		STAFF WASHER	15	2	10	750		1,000		250	10	3	15		STAFF DRYER	46										
47						750			1,000	250						48										
49		STAFF WASHER	15	2	10	750		1,000		250						50										
51						750			1,000	250	10	3	15		STAFF DRYER	52										
53		COFFE MAKER	20	1	8	1,584			1,834	250						54										
55						12,963	13,163			200	12	1	20		EMPLOYEE TIME CLOCK	56										
57		PANELBOARD 'C'	150	3	RD	15,815		15,815		0	1	20			SPARE	58										
59						14,348			14,348	0	1	20			SPARE	60										
PER PHASE SUB-TOTALS						29,983	31,928	30,422	LEGEND:																	
TOTAL CONNECTED PANELBOARD (VA)						92,333			TS - VIA TIME SWITCH			ST - SHUNT TRIP														
TOTAL CONNECTED PANELBOARD (AMPS)						256			GF - GROUND FAULT INTERRUPTER			LCK - LOCKING TAB														
TOTAL PANELBOARD DEMAND (VA)						93,505			FA - FIRE ALARM / RED / LOCKING TAB			IG - ISOLATED GROUND														
TOTAL PANELBOARD DEMAND (AMPS)						260			EM - EMERGENCY LTG. / LOCKING TAB			RD - RE: RISER DIAGRAM														

PANEL TO HAVE BUILT-IN SPD WITH 120 KA SURGE RATING.

PANELBOARD C																										
BUS AMPS: MAIN SIZE / TYPE: VOLTS/PHASE: MOUNTING:					225A MLO 208Y/120V, 3PH, 4W SURFACE					LOCATION: NEMA RATING: AFC VALUE: AIC RATING:					UTILITY ROOM 340 NEMA 1: 6.398A 10,000A SERIES RATED					GROUND BUS: ISOL. GROUND BUS: FEED THRU LUGS: SECTIONS:					YES NO NO 1 OF 1	
CKT #	#	CIRCUIT DESCRIPTION	BREAKER AMPS	P	WIRE SIZE	LOAD (VA)	CONNECTED PER PHASE (VA)			LOAD (VA)	WIRE SIZE	BREAKER AMPS	P	AMPS	CIRCUIT DESCRIPTION	CKT #	#									
							A	B	C																	
1		FOURTH FLOOR RCPT	20	1	8	1,260	2,520			1,260	8	1	20		THIRD FLOOR RCPT	2	EM									
3		FOURTH FLOOR PTAC-2	20	2	8	1,750		3,500		1,750	8	2	20		THIRD FLOOR PTAC-2	4	EM									
5						1,750			3,500	1,750						6	EM									
7		FOURTH FLOOR PTAC-2	20	2	8	1,750	3,500			1,750	8	2	20		THIRD FLOOR PTAC-2	8	EM									
9						1,750			3,500	1,750						10	EM									
11		FOURTH FLOOR / EM LTG / EF-2	20	1	10	604				1,238	634	10	1	20	THIRD FLOOR / EM LTG / EF-6	12	EM									
13		FOURTH FLOOR UTILITY RCPT	20	1	12	360	720			360	12	1	20		THIRD FLOOR UTILITY RCPT	14	EM									
15		HP-6	35	2	8	2,751		4,631		1,880	8	2	25		HP-1	16										
17						2,751			4,631	1,880						18										
19		ROOF TOP RCPT	20	1	12	540	1,762			1,222	12	2	20		HP-2	20										
21		FCU-4	15	2	12	180		1,402		1,222						22										
23						180			3,419	3,239	8	2	35		HP-3	24										
25		HP-4	20	2	12	1,222	4,461			3,239						26										
27						1,222		2,782		1,560	12	2	15		HP-5	28										
29		SPARE	20	1	1	0			1,560	1,560						30										
31		SPACE ONLY				0	0								SPACE ONLY	32										
33		SPACE ONLY				0		0							SPACE ONLY	34										
35		SPACE ONLY	TG			0			0	0					SPACE ONLY	36										
37		SPACE ONLY				0	0	0		0					SPACE ONLY	38										
39		SPACE ONLY				0			0	0					SPACE ONLY	40										
41		SPACE ONLY				0			0	0					SPACE ONLY	42										
PER PHASE SUB-TOTALS						12,963	15,815	14,348	LEGEND:																	
TOTAL CONNECTED PANELBOARD (VA)						43,126	TS - VIA TIME SWITCH						ST - SHUNT TRIP													
TOTAL CONNECTED PANELBOARD (AMPS)						120	GF - GROUND FAULT INTERRUPTER						LK - LOCKING TAB													
TOTAL PANELBOARD DEMAND (VA)						43,555	FA - FIRE ALARM / RED / LOCKING TAB						IG - ISOLATED GROUND													
TOTAL PANELBOARD DEMAND (AMPS)						121	EM - EMERGENCY LTG / LOCKING TAB						IR - RESET CIRCUIT													



1 FIRST FLOOR ELECTRICAL PLAN
SCALE: 1/8" = 1'-0"

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name
WoodSpring Suites

Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO




Drawn By:
CB / MR / TP
Checked By:
AR / CF
Document Date:
10/04/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541
Professional Seal



10/5/2023 11:59:48 AM



1 SECOND FLOOR ELECTRICAL PLAN
SCALE: 1/8" = 1'-0"

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

ACERTUS CONSULTING GROUP

ACERTUS
CONSULTING GROUP, LLC

11800 COLLEGE BLVD STE 475
OVERLAND PARK, KS 66204
PH: 913-250-1100
www.AcertusGroup.com

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name
WoodSpring Suites

Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO

Drawn By:
CB / MR / TP
Checked By:
AR / CF
Document Date:
10/04/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541

Professional Seal

Sheet Title
ELECTRICAL PLANS - SECOND FLOOR
Sheet No.
E-4
BRR Original printed on recycled paper

[illegible]

Project Name

WoodSpring Suites

Project Address:

1010 NW WARD ROAD LEE'S
SUMMIT, MO



Drawn By:
CB / MR / TF

AR / CF

Document D

10/04/23

Protocol:

W33_V3_202

WSS v2 B08

Project No. _____

31000541

Professional Seal




Sheet Title

ELECTRICAL PLANS - THIRD FLOOR


Sheet No.

E-5

 BRR Original printed on recycled paper



1 THIRD FLOOR ELECTRICAL PLAN
SCALE: 1/8" = 1'-0"




1 FOURTH FLOOR ELECTRICAL PLAN
SCALE: 1/8" = 1'-0"

NOTE: COORDINATE FINAL LOCATION AND QUANTITY OF J-BOXES FOR SIGNAGE WITH ARCHITECT AND SIGN VENDOR PRIOR TO ROUGH-IN. (TYP.)

ELEVATOR KEYNOTES (1, 2, X)

1. PRIMARY ELEVATOR DISCONNECT. PROVIDE (1) 60A, 3P, 208V BUSSMANN POWER MODULE WITH SHUNT TRIP MECHANISM, 60A TIME-DELAY (CLASS J OR BUSSMANN LPJ) FUSES, AND AUXILIARY 24V CONTACT IN A NEMA-1 ENCLOSURE FOR ELEVATOR EQUIPMENT PER MANUFACTURER REQUIREMENTS. LOCATE DISCONNECT IN FOURTH FLOOR UTILITY ROOM 440. COORDINATE EXACT LOCATION WITH ELEVATOR MANUFACTURER PRIOR TO ROUGH-IN. PROVIDE CONDUIT AND WIRE, THE SAME SIZE AS THE ELEVATOR FEEDER, FROM PRIMARY ELEVATOR DISCONNECT TO AUXILIARY ELEVATOR DISCONNECT AS DIRECTED BY THE ELEVATOR MANUFACTURER. PROVIDE 24V WIRING FROM AUXILIARY CONTACT IN PRIMARY ELEVATOR DISCONNECT TO ELEVATOR CONTROL UNIT AS DIRECTED BY THE ELEVATOR MANUFACTURER. COORDINATE ALL REQUIREMENTS WITH ELEVATOR MANUFACTURER. PROVIDE ALL WIRING AND ACCESSORIES FOR A COMPLETE AND OPERATIONAL SYSTEM.
2. AUXILIARY ELEVATOR DISCONNECT SWITCH. PROVIDE (1) 60A, 3P, 208V NON-FUSED DISCONNECT SWITCH WITH AUXILIARY 24V CONTACT IN A NEMA-1 ENCLOSURE PER MANUFACTURER REQUIREMENTS. LOCATE DISCONNECT AT TOP OF HOISTWAY, COORDINATE EXACT LOCATION WITH ELEVATOR MANUFACTURER PRIOR TO ROUGH-IN. PROVIDE CONDUIT AND WIRE, THE SAME SIZE AS THE ELEVATOR FEEDER, FROM AUXILIARY ELEVATOR DISCONNECT TO ELEVATOR CONTROL UNIT AS DIRECTED BY THE ELEVATOR MANUFACTURER. PROVIDE 24V WIRING FROM AUXILIARY CONTACT TO ELEVATOR CONTROL UNIT AS DIRECTED BY THE ELEVATOR MANUFACTURER. COORDINATE ALL REQUIREMENTS WITH ELEVATOR MANUFACTURER. PROVIDE ALL WIRING AND ACCESSORIES FOR A COMPLETE AND OPERATIONAL SYSTEM.
3. ELEVATOR CAB DISCONNECT. PROVIDE (1) 20A, 1P, 120V DISCONNECT FUSED AT 15A IN A NEMA-1 ENCLOSURE FOR ELEVATOR CAB POWER. PROVIDE CONDUIT AND WIRE, SIZED FOR 20A AT 120V, FROM ELEVATOR CAB DISCONNECT TO ELEVATOR CONTROL UNIT AS DIRECTED BY THE ELEVATOR MANUFACTURER. COORDINATE ALL REQUIREMENTS WITH ELEVATOR MANUFACTURER. PROVIDE ALL WIRING AND ACCESSORIES FOR A COMPLETE AND OPERATIONAL SYSTEM.
4. PROVIDE ANALOG TELEPHONE LINE TO ELEVATOR CONTROL UNIT FOR CAB TELEPHONE. CONFIRM ALL REQUIREMENTS WITH ELEVATOR MANUFACTURER.
5. PROVIDE SECURITY CAMERA CONNECTION FOR ELEVATOR SECURITY CAMERA. CONFIRM ALL REQUIREMENTS WITH ELEVATOR MANUFACTURER PRIOR TO ROUGH-IN.



2 ELEVATOR ELECTRICAL PLAN
SCALE: 1/4" = 1'-0"

COORDINATE WITH CONSTRUCTION MANAGER FOR EXACT ELEVATOR INFORMATION. ELEVATOR SHOWN IN THESE DRAWINGS MAY DIFFER FROM ACTUAL ELEVATOR PURCHASED. COORDINATE BREAKER SIZE, FEEDER SIZE, LOCAL DISCONNECT, INSTALLATION REQUIREMENTS AND ANY ADDITIONAL REQUIREMENTS WITH ELEVATOR MANUFACTURER PRIOR TO WORK BEING STARTED.

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

Project Name
WoodSpring Suites


Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO



Drawn By:
CB / MR / TP
Checked By:
AR / CF
Document Date:
10/04/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541
Professional Seal





1 ROOF ELECTRICAL PLAN
SCALE: 1/8" = 1'-0"

Copyright Notice
This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing for reference or example on another project requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions		
NO.	DATE	DESCRIPTION

Project Name
WoodSpring Suites


Project Address
1010 NW WARD ROAD LEE'S SUMMIT, MO




Drawn By:
CB / MR / TP
Checked By:
AR / CF
Document Date:
08/16/23
Protocol:
WSS_v5_2023.1 (05/05/23)
Bulletins Through:
WSS_v2_B08

Project No.
31000541


Professional Seal






NO.	DATE	DESCRIPTION
2	10/04/23	REV 2

FIRE ALARM MATRIX		OUTPUTS															
INPUTS		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
COMMON AREA	MANUAL PULL BOX	A	●			●	●	●	●		●	●				●	A
	SMOKE DETECTOR	B	●			●	●	●	●		●	●				●	B
	HEAT DETECTOR	C	●			●	●	●	●		●	●				●	C
	DUCT DETECTOR	D	●	●		●				●	●						D
	ELEVATOR LOBBY SMOKE - NOT FLOOR 1	E	●			●	●	●	●		●	●				●	E
ELEVATOR	ELEVATOR LOBBY SMOKE - FLOOR 1	F	●			●	●	●	●		●	●		●			F
	SMOKE DETECTOR ELEVATOR MACHINE ROOM	G	●			●	●	●	●		●	●		●			G
	HEAT DETECTOR ELEVATOR MACHINE ROOM	H	●			●	●	●	●		●	●		●			H
	SMOKE DETECTOR ELEVATOR PIT	I	●			●	●	●	●		●	●		●			I
	HEAT DETECTOR ELEVATOR PIT	J	●			●	●	●	●		●	●		●			J
	SMOKE DETECTOR ELEVATOR TOP OF SHAFT	K	●			●	●	●	●		●	●		●			K
	HEAT DETECTOR ELEVATOR TOP OF SHAFT	L	●			●	●	●	●		●	●		●			L
	FLOW SWITCH ELEVATOR MACHINE ROOM	M	●			●	●	●	●		●	●		●			M
	TAMPER SWITCH ELEVATOR MACHINE ROOM	N	●	●		●	●	●	●		●	●		●			N
	FLOW SWITCH TOP OF SHAFT	O	●			●	●	●	●		●	●		●			O
FIRE SPRINKLER	TAMPER SWITCH TOP OF SHAFT	P	●	●		●	●	●	●		●	●		●			P
	FIRE PUMP RUN	Q	●	●		●	●	●	●		●	●		●			Q
	FIRE PUMP PHASE REVERSAL	R	●	●		●	●	●	●		●	●		●			R
	FIRE PUMP PHASE FAIL	S	●	●		●	●	●	●		●	●		●			S
	FLOW SWITCH	T	●	●		●	●	●	●		●	●		●			T
	TAMPER SWITCH	U	●	●		●	●	●	●		●	●		●			U
	DRY SYSTEM LOW HI/LOW	V	●	●		●	●	●	●		●	●		●			V
SYSTEM	HEAT TRACE FAULT	W	●	●		●	●	●	●		●	●		●			W
	SYSTEM ALARM	X	●			●	●	●	●		●	●		●			X
	SYSTEM SUPERVISORY	Y	●	●		●	●	●	●		●	●		●			Y
	SYSTEM TROUBLE	Z	●	●		●	●	●	●		●	●		●			Z
	GROUND FAULT	AA	●	●		●	●	●	●		●	●		●			AA
	FIRE ALARM SYSTEM LOW BATTERY	BB	●	●		●	●	●	●		●	●		●			BB
	FIRE ALARM AC POWER FAILURE	CC	●	●		●	●	●	●		●	●		●			CC
WITHIN SUITES	NOTIFICATION APPLIANCE SHORT CIRCUIT	DD	●	●		●	●	●	●		●	●		●			DD
	OPEN CIRCUIT	EE	●	●		●	●	●	●		●	●		●			EE
	SMOKE DETECTOR	FF	●	●		●	●	●	●		●	●		●			FF
	CO DETECTOR	GG	●	●		●	●	●	●		●	●		●			GG
	COMBINATION DETECTOR (SMOKE/CO)	HH	●	●		●	●	●	●		●	●		●			HH



2 FIRE ALARM 2ND FLOOR (TYPICAL FOR 3RD & 4TH FLOORS)
SCALE: 1/16" = 1'-0"



FIRE ALARM GENERAL NOTES

- VERIFY ALL OUTLET LOCATIONS ON THE JOB PRIOR TO ROUGH-IN.
- REFER TO RELATED ARCHITECTURAL, MECHANICAL, AND STRUCTURAL DRAWINGS FOR RELATED INFORMATION.
- REFER TO THE SPECIFICATIONS FOR DATA NOT ON THE DRAWINGS.
- COORDINATE OUTLET BOX LOCATIONS WITH MASONRY TO MINIMIZE CUTTING OF BRICK BLOCK.
- ALL MOUNTING HEIGHTS TO BOTTOM OF ITEM UNLESS NOTED OTHERWISE.
- WHERE AREA SMOKE DETECTORS ARE SHOWN ON THE DRAWINGS ELECTRICAL CONTRACTOR SHALL NOT LOCATE SMOKE DETECTORS CLOSER THAN 3 FEET FROM ANY MECHANICAL AIR SUPPLY OR RETURN DIFFUSER, GRILLE, OR REGISTER PER NFPA ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OTHER TRADES FOR LOCATION OF DETECTOR.
- ALL FIRE ALARM DEVICE LOCATIONS AND DETAILS ARE FOR REFERENCE ONLY. LOCAL GOVERNING CODES AND REQUIREMENTS SHALL TAKE PRECEDENCE OVER ALL DETAILS FOR LOCATIONS AND MOUNTING HEIGHTS. VERIFY LOCAL GOVERNING CODES AND REQUIREMENTS WITH LOCAL INSPECTION DEPARTMENT PRIOR TO BID. COMPLETE FIRE ALARM SYSTEM, INSTALLATION AND OPERATION SHALL MEET THE REQUIREMENTS OF THE LOCAL AUTHORITY HAVING JURISDICTION. ALL INITIATING DEVICES MUST BE ADDRESSABLE. "STAND ALONE" DEVICES WILL NOT BE ALLOWED UNLESS REQUIRED BY LOCAL AUTHORITY HAVING JURISDICTION.
- HEARING IMPAIRED SUITES REQUIRE ADDITIONAL STROBE LIGHTS, FIELD VERIFY ROOMS THAT REQUIRE ADDITIONAL STROBES. STROBES SHALL BE LOCATED AS REQUIRED BY NATIONAL, STATE, AND LOCAL ORDINANCES. RE: ARCHITECTURAL PLANS FOR HEARING IMPAIRED ROOM NUMBERS.
- RE: ARCHITECTURAL PLANS FOR ADA ROOM NUMBERS.
- ALL AUDIO DEVICES WITHIN SLEEPING AREAS SHALL PRODUCE A 520 HZ, LOW-FREQUENCY SIGNAL PER N.F.P.A. 72.
- ALL WALL MOUNTED VISIBLE NOTIFICATION APPLIANCES, LOCATED IN SLEEPING AREAS, SHALL BE NO CLOSER THAN 24" TO THE CEILING AND HAVE A CANDELA RATING NO LESS THAN 110cd. APPLIANCES MOUNTED ON THE WALL CLOSER THAN 24" TO THE CEILING OR ON THE CEILING SHALL HAVE A CANDELA RATING NOT LESS THAN 177cd PER N.F.P.A. 72.
- ALL NOTIFICATION APPLIANCES SHALL BE WHITE IN COLOR.
- PROVIDE CO DETECTION IN ALL GUEST ROOMS ADJACENT TO AND ABOVE ROOMS WITH GAS APPLIANCES AND ALL AREAS AND SUITES AS REQUIRED BY LOCAL CODES. CONFIRM ALL REQUIREMENTS WITH LOCAL AHJ.
- PROVIDE CO DETECTION IN ALL AREAS AND SUITES AS REQUIRED BY LOCAL CODES. CONFIRM ALL REQUIREMENTS WITH LOCAL AHJ.
- PROVIDE ALL INTERCONNECTION BETWEEN BDA SYSTEM AND FACP REQUIRED.

FIRE ALARM SYMBOL LIST		
SYMBOL	DESCRIPTION	MOUNTING
[P]	FIRE ALARM MANUAL PULL STATION	4'-0" TO TOP
[H-S]	COMBINATION F.A. HORN & STROBE SIGNAL	WALL 80" A.F.F.
[H-S]	FIRE ALARM STROBE SIGNAL	WALL 80" A.F.F.
[S]	AREA SMOKE DETECTOR, SEE F.A. GENERAL NOTE #6	CEIL./WALL
[■]	FIRE ALARM MAGNETIC DOOR HOLD OPEN (HOLD OPEN)	VERIFY
[S-R]	RESIDENT ROOM SMOKE DETECTOR AND SOUNDER BASE	CEIL./WALL
[H]	AREA HEAT DETECTOR	CEIL./WALL
[H-S]	HEARING IMPAIRED HORN & STROBE SIGNAL	WALL 80" A.F.F.

4 TYPICAL MOUNTING HEIGHT
SCALE: NOT TO SCALE

NO MODULES, RELAYS, RESETS, ANNUNCIATORS, OR OTHER DEVICE REQUIRED BY FA SYSTEM DESIGN, BUT NOT SHOWN ON THE CONTRACT DOCUMENTS, SHALL BE INSTALLED WITHOUT WRITTEN CONFIRMATION OF LOCATION FROM OWNER PRIOR TO SUBMISSION OF SHOP DRAWINGS. SHOP DRAWING APPROVAL SHALL NOT CONSTITUTE APPROVAL OF DEVICES NOT REVIEWED AND APPROVED IN ADVANCE.

brr

Architect of Record:
BRR Architecture, Inc.

8131 METCALF AVE,
SUITE 300
OVERLAND PARK, KS 66204

www.brrarch.com

Tel: 913-262-9095
Fax: 913-262-9044

ACERTUS CONSULTING GROUP

ACERTUS CONSULTING GROUP, LLC
11800 COLLEGE BLVD. STE. 475
OVERLAND PARK, KS 66204
www.AcertusGroup.com

Copyright Notice

This drawing was prepared for use on a specific site contemporaneously with its issue date and it is not suitable for use on a different project site or at a later time. Use of this drawing requires the services of properly licensed architects and engineers. Reproduction of this drawing for reuse on another project is not authorized and may be contrary to the law.

Issues & Revisions

NO.	DATE	DESCRIPTION

Project Name

WoodSpring Suites

Project Address

1010 NW WARD ROAD LEE'S SUMMIT, MO

WOODSPRING SUITES

Drawn By:
CB / MR / TP

Checked By:
AR / CF

Document Date:
08/16/23

Protocol:
WSS_v5_2023.1 (05/05/23)

Bulletins Through:
WSS_v2_B08

Project No.

31000541

Professional Seal

STATE OF MISSOURI
RANDALL A. NELSON
NUMBER
PE-2007003990
REGISTERED PROFESSIONAL ENGINEER
08/16/23

Sheet Title

FIRE ALARM SYSTEM PLANS

Sheet No.

E-9

BRR Original printed on recycled paper

 RRR Original printed on recycled paper