

SCOPE OF WORK DETAIL: Refer to all attachments in ORCA for specific requirements.
Specific Requirements: Reach info: Bill Coday 816-803-4924 [/wc7681@att.com](mailto:wc7681@att.com). Please update via email with what is placed and upon finishing project. All work to be done as shown on work prints unless otherwise noted here in scope of work detail. Final walk through or pics required for final billing. All changes must be pre-approved prior to work being done (Codes and Cost w/ email approval from LCE).

Project Number: A02S2BN

Project Name:	Cable @ NE Independence
Estimated In-Service Date:	07-MAR-2024
Project Description:	OTH--EE4160-DA1165; Cable relocation at Ne Independence
Project Notes:	<p>What: Project will cut around cable that was determined not to be deep enough for ingress being placed off of roadway. Cable depth was less than 12" at grade point.</p> <p>Project will cut around a new 12F, place 2 HHs for splices Project will cut around a 1200 copper with a 300 pair piece. Where: Address: NE Independence Ave at NE Town Centre Blvd. City/State: Lee's Summit, MO WC: Lee's Summit (816524) CLLI: KSCYMO41 Why: cable is not at depth Why this way: current company guidelines Why now: ECD: 3/7/24</p>