



		FRONT & REAR ELEVATION NOTES	CPG DBA
	WINDOW SKU REDUCTION SCHEDULE LOWER LEVEL (1) 4040 SLIDER	 1.12 TOP OF FOOTING DEPTH DETERMINED PER SITE. 1.71 CONCRETE WINDOW WELL FOR EGRESS WITH LADDER. PROVED SLEEVE THROUGH WALL FOR FOUNDATION DRAIN. TOP OF WINDOW WELL TO BE 3" BELOW TOP 	
	MAIN LEVEL (1) 4040 FIX CLR (3) 3066 FIX CLR TEMP (2) 3050 SH CLR	OF FOUNDATION. 2.62 DOUBLED 5/4"X8" LP SMART TRIM. 3.11 LP SMART PANEL LAP SIDING WITH 5/4X6 LP	SUMMIT
	60x68 SLIDER PATIO DOOR 2X4 JAMB 30x68 FRONT DOOR 2X4 JAMB UPPER LEVEL	SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. 3.13 LP SMART PANEL SIDING WITH 3/4X4 LP SMART	HOMES 120 SE 30TH ST.
	(2) 2040 SH CLR (7) 3050 SH CLR (1) 3066 FIX CLR TEMP	TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. BOTTOM OF SIDING SHALL BE A MINIMUM OF 6" ABOVE GRADE.	LEE'S SUMMIT, MO 64082 816-246-6700
к 🛧	STRUCTURAL DETAIL SHEET INDEX S000 STRUCTURAL GENERAL NOTES S501 FOUNDATION DETAILS S503 GARAGE/SLAB DETAILS S510 FRAMING STANDARDS S520 DECK DETAILS S530 BRACING DETAILS S550 FASTENING SCHEDULE S560 EGRESS WINDOW	 3.14 CEDAR SHAKE SHINGLE SIDING. 3.17 MANUFACTURED STONE VENEER. 3.18 CAST STONE CAP 3.43 BOX BASE WITH STONE VENEER TO 36" AND (2) 6X6 CEDAR POSTS. SPACE 10" O.C. SEE PLAN FOR FINISHED SIZE. 3.62 CEDAR SHUTTERS. ALL SHUTTERS TO BE 18" WIDE USING (3) 2X6 BOARDS. LP SMART TRIM TO BE INSTALLED AROUND WINDOW PRIOR TO SHUTTER 	COPYRIGHT 2017 THIS DRAWING HAS BEEN PREPARED BY SUMMIT HOMES, OR UNDER THEIR DIRECT SUPERVISION AS AN INSTRUMENT OF SERVICE AND IS INTENDED FOR USE ONLY ON THIS PROJECT. ALL DRAWINGS, SPECIFICATIONS, AND DESIGNS, INCLUDING THE OVERALL LAYOUT, FORM, AND COMPOSITION OF SPACES ARE PROTECTED BY COPYRIGHT REGISTERED TO CPG, INC. ANY REPRODUCTION, USE, OR DISCLOSURE OF THE INFORMATION CONTAINED HEREIN WITHOUT THE WRITTEN CONSENT FROM CPG, INC. D/B/A SUMMIT HOMES EXCEPT AS REQUIRED FOR BIDDING AND CONSTRUCTION OF THIS PROJECT IS STRICTLY PROHIBITED.
		INSTALLATION. 4.11 MINIMUM ROOFING COMPOSITION- 30 YR COMPOSITE	
Ψ		 SHINGLES ON 15# FELT ON 1/2" OSB SHEATHING OR AS REQUIRED BY CODE. 4.31 BUILD CRICKET VALLEY AWAY FROM INTERSECTION FOR POSITIVE DRAINAGE. 	ADDRESS: 3228 SW ARBOR SOUND DR LEE'S SUMMIT, MO 64082
			FIELD TSMAN N RIDGE #175 3.5 BATHS 3.5 BATHS
Ψ			LORN LORN LORN SCRAF
]nt	$\frac{\text{ELEVATION}}{\text{SCALE: } 1/4' = 1'-0'}$		AWT 4 BE
		GENERAL NOTES DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR. WINDOW SIZES ARE WRITTEN IN FEET AND INCHES PER INDUSTRY STANDARDS. EX: 3050 SH = 3'-0" X 5'-0" SINGLE HUNG, 3066 FIX = 3'-0" X 6'-6" FIXED.	
TE 📥		SHEET INDEX	PROFESSIONAL SEAL:
		 A1. FRONT AND REAR ELEVATION A2. LEFT AND RIGHT ELEVATION A3. FOUNDATION FLOOR PLAN A4. MAIN LEVEL PLAN A5. UPPER LEVEL PLAN A6. ROOF PLAN 	NUMBER PE-2023046346 S JONAL E
		FINISHED	EVERSTEAD IS RESPONSIBLE FOR STRUCTURAL SPECIFICATIONS ONLY. ARCHITECTURAL PLANS
		MAIN FLOOR1054UPPER LEVEL1270FINISHED STAIRS TO LOWER LEVEL0	EVERSTEAD 3741 NE TROON DR.
		TOTAL 2324	3741 NE TROON DR. LEES SUMMIT, MO 64064 816-399-4901
		UNFINISHEDLOWER LEVEL - UNFINISHED970PATIO144GARAGE660	VERSION: 1.2
		ENGINEERTRUSSI-JOISTEVERSTEADWHEELERN/A	ISSUE DATE: 03.04.24
G		REVISIONS	SHEET NUMBER:
T		NO. DATE DESCRIPTION	
AR	$\frac{\text{ELEVATION}}{\text{SCALE: } 1/4' = 1'-0'} (1)$		AI.U



STRUCTURAL NOTES:

- ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATION RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.
- ELEVATIONS:
- GARAGE DOORS SHALL MEET DASMA OR ULTIMATE DESIGN WIND SPEED OF 115
- MPH REQUIREMENTS. WALL FRAMING SHALL BE DOUGLAS FIR LARCH #2 UNLESS OTHERWISE NOTED.
- IN BEARING WALLS, STUDS WHICH ARE NOT MORE THAN TEN FEET IN LENGTH SHALL BE SPACED NOT MORE THAN IS SPECIFIED BY IRC TABLE R602.3(5) FOR
- CORRESPONDING STUD SIZE. WATER-RESISTIVE EXTERIOR WALL BARRIER IN WALL SECTION SHALL COMPLY
- WITH IRC R703.2. WHEN APPLICABLE, CONTINUOUS STUDS BETWEEN FLOOR AND ROOF/CEILING
- DIAPHRAGM SHALL COMPLY WITH IRC R602.3.
- ALL UNMARKED HEADERS SHALL BE A MINIMUM #2 DOUGLAS FIR LARCH (2) 2 X
- 10 ON LOAD BEARING WALLS. SHIPLAP SIDING MUST BE FASTENED AT BOTH UNDERLAP AND OVERLAP.

E FOR CONSTRUCTION



LEE'S SUMMIT, MISSOURI
03/26/2024

	WALL TYPE	NOMINAL WALL THICKNESS	VERTICAL SPACING AND SIZE	HORIZONTAL SPACING AND SIZE	FOOTING SPECIFICATION U.N.O. ON PLANS	
	3'-6" TRENCH FOOTING	16"	#4 BARS @18" O.C.	(2) #4 BARS TOP & BOT. CONT.		
	< 6'-0" WALL		#4 BARS @36" O.C.			
	8'-0" WALL		#4 BARS @16" O.C.		16" x 8" CONC. FTG. W/ (2) #4 BARS CONT.	
	9'-0" WALL	0	#4 BARS @12" O.C.	#4 BARS @ 24" O.C.		
	10'-0" WALL		#4 BARS @8" O.C.			
	11'-0" WALL	10"	#4 BARS @9" O.C.		24" x 12" CONC. FTG.	
		10"	#4 BARS @6" O.C.		W/ (3) #4 BARS CONT.	
-	FOR PLAN REVIEW PMENT SERVICES				·	

FROM INSIDE TENSION FACE)

FOUNDATION WALL AND FOOTING TABLE (3000 PSI CONCRETE AND 40 KSI REBAR PLACED 2"

(4) VERTICAL #4

COLUMNS GREATER THAN 10' REQUIRE A SEPARATE ENGINEERED DESIGN. FOOTINGS A-F SPACING OF 6" O.C. WITH 3" CLEAR COVER.

16" (4) VERTICAL #4 18" 3'-0" (4) VERTICAL #4 24" 3'-0" (4) VERTICAL #4 /K\ 28" 3'-0" (4) VERTICAL #4 *DENOTES STEEL COLUMN NOT REQUIRED COLUMN AND PAD SIZES ARE FOR A MAXIMUM COLUMN HEIGHT OF 10'.

12"

 $/G \setminus$

3'-0"

3'-0"

B	36"X36"	1'-0"		(6) #4 BAR E.W.	3" DIAMETER			
c	42"x42"	1'-2"		(7) #4 BAR E.W.	3" DIAMETER			
	48"x48"	1'-4"		(8) #4 BAR E.W.	3" DIAMETER			
E	54"x54"	1'-4"		(9) #4 BAR E.W.	3.5" DIAMETER			
F	60"x60"	1'-6"		(10) #4 BAR E.W.	3.5" DIAMETER			
ISOLATED FOOTINGS AND COLUMN PADS								
SYM	PIER DIAMETE	R DEPT	ГН	MINIMUM REINFORCEMENT GRADE 40 KSI STEEL				

	ISOLATED FOOTINGS AND COLUMN PADS										
ę	SYM	PIER PAD SIZE	DEPTH	MINIMUM REINFORCEMENT GRADE 40 KSI STEEL	SCHEDULE 40 STEEL COLUMN, MIN FY = 35 KSI						
2	Â	30"x30"	1'-0"	(5) #4 BAR E.W.	3" DIAMETER						
	B	36"x36"	1'-0"	(6) #4 BAR E.W.	3" DIAMETER						
	¢	42"x42"	1'-2"	(7) #4 BAR E.W.	3" DIAMETER						
	D	48"x48"	1'-4"	(8) #4 BAR E.W.	3" DIAMETER						
	E	54"x54"	1'-4"	(9) #4 BAR E.W.	3.5" DIAMETER						
	\wedge										

ALL DEAD MAN SHALL BE SPACED NO MORE THAN 16' FROM EGRESS WELL, REAR GARAGE WALL, 24" RETURN ON FOUNDATION WALL OR ANOTHER DEAD MAN. DEAD MEN ARE NOT REQUIRED ON EXTERIOR GARAGE WALLS OR FOUNDATION WALLS THAT ARE 5' OR LESS. WALL TRANSITIONING FROM ELSS THAN 5' TALL TO MORE THAN 5' TALL WITH STEP DOWNS: A DEAD MAN IS REQUIRED WITHIN 8' OF STEP DOWN (tRANSITIONING FROM LESS THAN 5' TALL TO MORE THAN 5' TALL WALL LOCATION) ON WALL 5' TALL OR MORE.

FOUNDATION WALLS SHALL BE DAMPPROOFED PER IRC SECTION R406. FOUNDATION DRAINAGE WILL BVE IN ACCORDANCE WITH IRC SECTION R405. BASEMENT EGRESS OPENINGS SHALL BE IN ACCORDANCE WITH IRC SECTION R310.1.

WATERPROOFING SHALL BE A MINIMUM 6-MIL. THICK MOISTURED BARRIER OVER

ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATION RESIDENTIAL CODE OR

- ALL INTERIOR FOOTINGS OF LOAD BEARINGS WALLS AND COLUMNS SHALL BE
- ISOLATED FROM THE BASEMENT FLOOR SLAB.
- ALL ANCHOR BOLTS SHALL NOT BE SPACED MORE THAN 3' O.C. AND BE EMBEDDED
- INTO THE CONCRETE A MINIMUM OF 7".

ATTACHED ENGINEER SPECIFICATIONS WHERE APLLICABLE.

SOIL BEARING CAPACITY SHALL BE 1500 PSF.

SHALL BE MINIMUM 6".

ALL FOOTINGS MEET OR EXCEED MINIMUM FROST DEPTH OF 36".


TO THE FINISHED GRADE (R-406.1). METHOD OF DAMPPROOFING OR

STRUCTURAL NOTES:

FOUNDATION NOTES:


1.


3.



BLOCKING NOTE:

SOLID BLOCKING BETWEEN JOISTS AT 48" O.C. EXTEND BLOCKING ONE JOIST BAY PAST EACH SIDE OF ISLAND ABOVE





GENERAL PLAN NOTES

- ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATIONAL RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.
- ALL DIMENSIONS ARE FROM FACE OF STUD U.N.O.
- MINIMUM DOUBLE JOIST UNDER INTERIOR NON-LOAD BEARING WALLS. CANTILEVERS. OVER BEAMS, AND DOOR JAMBS SHALL BE BLOCKED.
- CEILING JOISTS SHALL BE 2x6 @ 16" O.C. U.N.O. WALL CONSTRUCTION SHALL BE CAPABLE OF ACCOMMODATING ALL
- LOADS IMPOSED ACCORDING TO IRC R301.
- EXTERIOR WALLS SHALL BE CONSTRUCTED IN ACCORDANCE WITH IRC 602 & FIGURES R602.3(1) AND R602.3(2). ANY WOOD MEMBERS IN CONTACT WITH CONCRETE OR MASONRY (OR
- THE FURRING THEY ARE ATTACHED TO) SHALL BE OF DECAY RESISTANT MATERIAL. INTERIOR NON-LOAD BEARING WALLS SHALL BE ISOLATED FROM THE
- FLOOR FRAMING ABOVE UNLESS THE INTERIOR NON-LOAD BEARING WALL RESTS DIRECTLY ON A FOOTING. SOLID BLOCKING BETWEEN JOISTS AT 48" O.C. AND EXTEND BLOCKING 10
- ONE JOIST BAY PAST EACH SIDE OF KITCHEN ISLAND DOUBLE JOIST UNDER KITCHEN ISLAND AND TUBS
- 12. ALL JOIST HANGERS TO BE SIMPSON LUS HANGERS UNO

INTERIOR LOAD BEARING WALL


WALL BRACING NOTES:

- WALL BRACING IS DESIGNED IN ACCORDANCE WITH IRC R602.10
- BRACING METHODS SHALL BE PER PLAN AND SHALL BE CONSTRUCTED IN CONFORMANCE WITH 2018 IRC R602 10.4 AND R602 10.5 FOR METHOD CS-WSP STRUCTURAL PANEL SHEATHING SHALL BE INSTALLED ON
- ALL SHEATHABLE SURFACES ON ONE SIDE OF THE BRACED WALL LINE INCLUDING AREAS ABOVE AND BELOW OPENINGS AND GABLE END WALLS. END CONDITIONS SHALL MEET THE REQUIREMENTS OF R602.10.7 AND DETAIL 9-S400. ALL HORIZONTAL PANEL JOINTS SHALL OCCUR OVER AND BE
- NAILED TO COMMON FRAMING OR BLOCKING WITH AN APPROPRIATE PANEL EDGE-NAILING SCHEDULE IN ACCORDANCE WITH IRC R602.10.4.4
- INTERIOR FINISH OF EXTERIOR WALLS SHALL BE MINIMUM 1/2" GYPSUM BOARD INSTALLED ON THE INTERIOR SIDE.

BRACING METHODS

BRACING LIB F	PER IRC R602.10
MINIMUM LIB L	ENGTH PER 2018 IRC TABLE R602.10.5:
•	55" - 8' TALL WALL HEIGHT
•	62" - 9' TALL WALL HEIGHT
•	69" - 10' TALL WALL HEIGHT


BRACING PFH PER IRC R602.10.6.2



IRC TABLE N1102.1.2 (R402.1.2) INSULATION AND FENESTRATION REQUIREMENTS BY COMPONENT (PARTIAL) AND ENERGY CONSERVATION CODE COMPLIANCE

	CLIMATE ZONE	FENESTRATION U-FACTOR	SKYLIGHT U-FACTOR	GLAZED FENESTRATION SHGC	CEILING AND ATTICS R-VALUE	VAULTS R-VALUE	WOOD FRAME WALL R-VALUE	FLOOR R-VALUE	BASEMENT WALL R-VALUE	SLAB R-VALUE & DEPTH	CRAWL SPACE WALL R-VALUE	DUCTWORK R-VALUE
ASE			.55	.40	49	49	20 OR 13+5H	19	10/13	10, 2 FT	10/13	8

ENT SERVICES



GENERAL PLAN NOTES

- ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATIONAL RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.
- ALL DIMENSIONS ARE FROM FACE OF STUD U.N.O. MINIMUM DOUBLE JOIST UNDER INTERIOR NON-LOAD BEARING WALLS.
- CANTILEVERS, OVER BEAMS, AND DOOR JAMBS SHALL BE BLOCKED. CEILING JOISTS SHALL BE 2x6 @ 16" O.C. U.N.O.
- WALL CONSTRUCTION SHALL BE CAPABLE OF ACCOMMODATING ALL
- LOADS IMPOSED ACCORDING TO IRC R301. EXTERIOR WALLS SHALL BE CONSTRUCTED IN ACCORDANCE WITH IRC
- 602 & FIGURES R602.3(1) AND R602.3(2). ANY WOOD MEMBERS IN CONTACT WITH CONCRETE OR MASONRY (OR THE FURRING THEY ARE ATTACHED TO) SHALL BE OF DECAY RESISTANT
- MATERIAL. INTERIOR NON-LOAD BEARING WALLS SHALL BE ISOLATED FROM THE
- FLOOR FRAMING ABOVE UNLESS THE INTERIOR NON-LOAD BEARING WALL RESTS DIRECTLY ON A FOOTING. SOLID BLOCKING BETWEEN JOISTS AT 48" O.C. AND EXTEND BLOCKING
- ONE JOIST BAY PAST EACH SIDE OF KITCHEN ISLAND DOUBLE JOIST UNDER KITCHEN ISLAND AND TUBS

ALL JOIST HANGERS TO BE SIMPSON LUS HANGERS UNO 12

INTERIOR LOAD BEARING WALL

WALL BRACING NOTES:


- WALL BRACING IS DESIGNED IN ACCORDANCE WITH IRC R602.10
- BRACING METHODS SHALL BE PER PLAN AND SHALL BE CONSTRUCTED IN CONFORMANCE WITH 2018 IRC R602.10.4 AND R602.10.5 FOR METHOD CS-WSP STRUCTURAL PANEL SHEATHING SHALL BE INSTALLED ON ALL SHEATHABLE SURFACES ON ONE SIDE OF THE BRACED WALL LINE
- INCLUDING AREAS ABOVE AND BELOW OPENINGS AND GABLE END WALLS. END CONDITIONS SHALL MEET THE REQUIREMENTS OF R602.10.7 AND DETAIL 9-S400. ALL HORIZONTAL PANEL JOINTS SHALL OCCUR OVER AND BE
- NAILED TO COMMON FRAMING OR BLOCKING WITH AN APPROPRIATE PANEL EDGE-NAILING SCHEDULE IN ACCORDANCE WITH IRC R602.10.4.4
- INTERIOR FINISH OF EXTERIOR WALLS SHALL BE MINIMUM 1/2" GYPSUM BOARD INSTALLED ON THE INTERIOR SIDE.

BRACING METHODS

BRACING CS-WSP PER IRC R602.10


	PER IRC R602.10 LENGTH PER 2018 IRC TABLE R602.10.5:
•	55" - 8' TALL WALL HEIGHT
•	62" - 9' TALL WALL HEIGHT
•	69" - 10' TALL WALL HEIGHT

BRACING PFH PER IRC R602.10.6.2



IRC TABLE N1102.1.2 (R402.1.2) INSULATION AND FENESTRATION REQUIREMENTS BY COMPONENT (PARTIAL) AND ENERGY CONSERVATION CODE COMPLIANCE

	CLIMATE ZONE	FENESTRATION U-FACTOR	SKYLIGHT U-FACTOR	GLAZED FENESTRATION SHGC	CEILING AND ATTICS R-VALUE	VAULTS R-VALUE	WOOD FRAME WALL R-VALUE	FLOOR R-VALUE	BASEMENT WALL R-VALUE	SLAB R-VALUE & DEPTH	CRAWL SPACE WALL R-VALUE	DUCTWORK R-VALUE
ASE I OTEC	OR CONSTRUCTION MARINE FOR PLAN REVIEW	.32 ₩	.55	.40	49	49	20 OR 13+5H	19	10/13	10, 2 FT	10/13	8



UPPER LEVEL PLAN

SCALE: 1/4" = 1'-0"


TRUSS FRAMED ROOF NOTES

- ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATIONAL RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.
- DESIGNED FOR LIGHT ROOF COVERING, UNO. SEE G000 FOR MINIMUM LOADING.
- ALL EXTERIOR AND/OR LOAD BEARING WALL HEADERS SHALL BE MIN. (2) #2 2X10 UNO. CONSULT ENGINEER IF TRUSSES BEAR ON INTERIOR WALLS SHOWN AS NON-LOAD 4
- BEARING ON APPROVED POINTS. PROVIDE 2X SOLID BLOCKING SUPPORT BELOW ALL POINT LOADS CONTINUOUS TO
- BEARING STRUCTURE AND/OR FOUNDATION BELOW.
- WOOD TRUSSES SHALL BE IN ACCORDANCE WITH IRC 802.10. CONSULT ENGINEER IF TRUSSES BEAR ON INTERIOR WALLS SHOWN AS NON-LOAD
- BEARING ON APPROVED PRINTS.
- GIRDER TRUSSES MUST HAVE LOAD CARRIED DOWN TO THE FOUNDATION OR LOAD 8. SUPPORTING MEMBER. STUD PACK / COLUMN SHOWN ON PLANS.
- ROOF COVERING SHALL BE ASPHALT SHINGLES AND SHALL COMPLY WITH IRC 2018 SECT. R905.2
- MINIMUM ROOF SLOPE FOR ASPHALT SHINGLES SHALL BE 2:12. 10 11. ROOF SLOPES IN BETWEEN 4:12 AND 2:12 SHALL REQUIRE DOUBLE UNDERLAYMENT IN
- ACCORDANCE WITH IRC 2018 TABLE R905.1.1(2). EVERSTEAD STRUCTURAL SCOPE ENDS AT TOP PLATE FOR ROOF TRUSSES. 12.

TRUSS DIRECTION


_ _ _ _ _ _ _ GIRDER TRUSS LOCATION ____

INTERIOR LOAD BEARING WALL



TED FOR PLAN REVIEW OPMENT SERVICES 03/26/2024

SE FOR CONSTRUCTION



GENERAL NOTES

<u>roof</u> plan

SCALE: 1/4" = 1'-0"

ROOF AND CEILING FRAMING ARE PRE-ENGINEERED ROOF TRUSSES.

ASPHALT SHINGLES MIN 2/12. FLASH ALL PENETRATIONS AND INTERSECTIONS.

VENT EACH ENCLOSED ATTIC SPACE. NET AREA OPENING = 1/50TH OF VENTED AREA OR 1/300TH IF 580% OF VENTING NEAR TOP.

BUILD CRICKET VALLEY AWAY FROM INTERSECTION FOR POSITIVE DRAINAGE. SEE FRAMING SPECIFICATIONS FOR DETAILS.

DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.

HVAC DUCTWORK RUNNING THROUGH ATTIC SHALL BE HUNG FROM ABOVE TO ALLOW COMPLETE INSULATION SURROUND.

PROVIDE FOAM INSULATION AT EXTERIOR WHERE MAIN LEVEL ROOF LINE MEETS UPPER LEVEL WALLS.

WINDOW SIZES ARE WRITTEN IN FEET AND INCHES PER INDUSTRY STANDARDS. EX: 3050 SH = 3'-0" X 5'-0" SINGLE HUNG, 3066 FIX = 3'-0" X 6'-6" FIXED.

А.	GENERAL NOTES IRC 2018	C.5	CONCRETE (CONT.)	
A.1	PLANS SHALL COMPLY WITH 2018 INTERNATIONAL RESIDENTIAL CODE (IRC) WITH AMENDMENTS AS ADOPTED BY THE APPROPRIATE GOVERNING JURISDICTION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF RECORD IF ANY CHANGES OR DEVIATIONS FROM THE PLAN ARE MADE DURING CONSTRUCTION. THE ENGINEER OF RECORD MAY REQUIRE REVISED DRAWING OR CALCULATIONS AT ITS DISCRETION. IF DISCREPANCIES ARE IDENTIFIED THE MOST CONSERVATIVE SPECIFICATION		 CONCRETE MIX TO UTILIZE A MAXIMUM WATER- APPLICATIONS. ADMIXTURES SHALL NOT CONT. CONCRETE POURED AGAINST AN EXISTING SUP OF 1/4 INCH AMPLITUDE. 	AIN ANY CHLORIDES.
	SHALL APPLY.		REBAR PLACEMENT SHALL BE AS FOLLOWS:	
A.2	LOADING ASSUMPTIONS DEAD ROOF 10 PSF UNO ROOF + CEILING (NO STORAGE) 15 PSF		 CONCRETE CAST AGAINST AND PERMAI CONCRETE EXPOSED TO EARTH OR WE NOT EXPOSED TO WEATHER OR GROUN 1) SLABS, WALLS, JOISTS 	ATHER 1.5 IN CLR
	ROOF + CEILING (STORAGE)20 PSFCEILING JOISTS (STORAGE)10 PSFEXTERIOR BALCONY / DECK10 PSFINTERIOR FLOOR (MAIN FLOOR)15 PSF		 2) BEAMS, COLUMNS CONCRETE MIX DESIGN SHALL BE 6% (±1%) AIR WALLS, OR FLATWORK EXPOSED TO WEATHER 	1.5 IN CLR -ENTRAINED FOR GARAGE SLABS, FOOTINGS,
	INTERIOR FLOOR (UPPER FLOORS)10 PSF8" THICK MASONRY WALL96 PSF6" THICK MASONRY WALL72 PSFEXTERIOR LIGHT FRAMED WOOD WALLS15 PSF		 SHORING AND SUPPORTING FORMWORK SHALI MEMBERS BEFORE CONCRETE STRENGTH REA CYLINDERS OR 28 DAYS. 	
	INTERIOR LIGHT FRAMED WOOD WALLS 10 PSF (INTERIOR WALLS INCLUDED IN 15 PSF DEAD LOAD)		ALL FOUNDATION WALLS ENCLOSING BELOW G DAMPPROOFING SHALL EXTEND FROM THE EDG (IRC R406.1)	
	ROOF LIVE LOAD20 PSFFLOOR LIVE LOAD40 PSF (HABITABLE)GARAGE50 PSF WITH 2000 LB POINT LOAD	C.6	CONCRETE WALLS WITH REINFORCEMENT STEEL	
	STORAGE 20 PSF (UNINHABITABLE) GUARDRAIL:		REINFORCING STEEL SHALL CONFORM TO ASTI	M A615, GRADE 40.
	CONTINUOUS LINEAR50 PLFMAXIMUM POINT200 LBS		SMOOTH BARS OR WELDED WIRE FABRIC SHAL	
	SNOW GROUND SNOW LOAD 20 PSF		 90 DEG. HOOK SHOWN IN DRAWINGS SHALL BE STRAIGHT EXTENSION LENGTH = 12X BA 	
	WIND		• BEND DIAMETER = 12X BAR DIA.	
	VELOCITY 115 MPH EXPOSURE CATEGORY B		HOOKED DOWELS:	
В.	SOIL AND SITE ASSUMPTIONS		 HOOKED DOWELS FROM FOUNDATIONS VERTICAL WALL REINFORCING AND EXT FOUNDATION. 	TO WALL SHALL BE PROVIDED TO MATCH ENDED TO 3" CLEAR FROM BOTTOM OF
B.1	FOUNDATION DESIGN ASSUMES MINIMUM SOIL BEARING FOR THE SITE OF 1,500 PSF (2,000 PSF FOR KANSAS CITY, MO) UNLESS OTHERWISE NOTED. CONTRACTOR TO VISUALLY INSPECT THE SITE OR PROVIDE GEOTECHNICAL INVESTIGATION TO VERIFY MINIMUM ACCEPTABLE SOIL CONDITIONS FOR CL (SILTY CLAY) AS DEFINED BY 2018 IRC. THE CONTRACTOR IS RESPONSIBLE FOR ANY SOIL CONDITION			RCING FROM SLAB TO WALLS OR SLAB TO
	THAT DOES NOT MEET THE MINIMUM REQUIREMENTS AND FOR CONTACTING THE ENGINEER OF RECORD.		PROVIDE (2) - #5 BARS AROUND PERIMETER OF	
B.2	ACCESSORY STRUCTURES WITH AN EAVE HEIGHT LESS THAN 10'-0" AND AN AREA LESS THAN 600 FT MAT PROVIDE A MINIMUM SOIL COVER OF 12 INCHES MEASURED FROM THE BOTTOM OF CONCRETE.		WHERE SPLICES ARE NECESSARY IN REINFORCE IN ACCORDANCE WITH TABLE R608.5.4(1) AND F BETWEEN NONCONTACT PARALLEL BARS AT A OF ONE-FIFTH THE REQUIRED LAP LENGTH AND	IGURE R608.5.4(1). THE MAXIMUM GAP LAP SPLICE SHALL NOT EXCEED THE SMALLER
B.3	LATERAL SOIL PRESSURES UNLESS OTHERWISE NOTED ACTIVE 60 PSF AT REST 100 PSF		TOP HORIZONTAL REINFORCEMENT SHALL BE F WALL.	
B.4	SITE GRADING SHALL PROVIDE POSITIVE DRAINAGE AWAY FROM THE STRUCTURE AT A MINIMUM OF O.5% (6" IN THE FIRST 10'-0"). ALTERNATE APPROACHES MAY BE APPROVED IF THE ALTERNATE DESIGN IS EQUIVALENT IN EFFECTIVENESS AND PERFORMANCE, AND PROVIDES FOR POSITIVE SITE DRAINAGE.	C.7	HORIZONTAL WALL REINFORCEMENT SHALL TE STANDARD HOOK COLD WEATHER CONCRETE	RMINATE AT THE END OF THE WALL WITH A
C.	FOUNDATION NOTES	•	COLD WEATHER IS DEFINED AS THREE CONSEC	
C.1	FOUNDATION ANCHORAGE (IRC R403.1.6)		TEMPERATURE DROPS BELOW 40 DEGREES FA FAHRENHEIT FOR MORE THAN HALF OF ANY ON	
	 SILL PLATES SHALL BE BOLTED TO THE FOUNDATION WALL WITH A MINIMUM ½" DIAMETER ANCHOR BOLTS EMBEDDED AT LEAST 7" INTO THE CONCRETE. 		COLD WEATHER CONCRETE WORK SHALL CON	FORM TO ACI 306.
	• BOLTS SHALL BE SPACED NO GREATER THAN 6'-0" O.C.		ALL MATERIALS AND EQUIPMENT REQUIRED FO PROJECT SITE BEFORE COLD WEATHER CONCI	
	THERE SHALL BE A MINIMUM OF TWO BOLTS PER PLATE SECTION, WITH A BOLT PLACED WITHIN 12" AND NOT CLOSER THAN 7 BOLT DIAMETERS OF THE END OF EACH PLATE SECTION.		THE CONCRETE MIX DESIGN PROVIDED BY THE AVERAGE 28 DAY MIX DESIGN COMPRESSIVE S ⁻	
	• A PROPERLY SIZED NUT AND WASHER SHALL BE TIGHTENED ON EACH BOLT TO THE PLATE, (NOTE: 7" EMBEDMENT + 1-1/2" SILL PLATE + 3/4" FOR NUT AND WASHER EQUALS A 9-1/4" LONG BOLT).		 WHICHEVER IS GREATER. THE TEMPERATURE OF CONCRETE AT PLACEM FAHRENHEIT . 	
	• WALL BRACING METHODS (IRC R602) MAY REQUIRE ADDITIONAL ANCHORAGE.		THE MINIMUM CONCRETE TEMPERATURE AT TH	E TIME OF MIXING SHALL NOT BE BELOW 65
C.2	CONCRETE SLABS		 DEGREES FAHRENHEIT. ALL SNOW, ICE AND FROST MUST BE REMOVED 	
	 CONCRETE SLABS PLACED ON FILL MATERIAL WHICH SHALL BE COMPARED TO ENSURE UNIFORM SUPPORT OF THE SLAB AND SHALL NOT EXCEED 24" OF COMPACTED GRANULATED MATERIAL (SAND OR GRAVEL) OR 8" OF EARTH: THIS MAY OCCUR AT GARAGE FLOOR FILLS, OR OVER EXCAVATED AREAS UNDER 		THE CONTRACTOR SHALL PROVIDE ADEQUATE FREEZING AND MAINTAIN A CONCRETE TEMPEF HOUR PERIOD AFTER CONCRETE PLACEMENT.	PROTECTION FOR CONCRETE AGAINST RATURE OF 55 DEGREES FAHRENHEIT FOR A 72 THIS MAY BE ACHIEVED WITH THE USE OF
	 FLOOR SLABS. THE DESIGN AND INSTALLATION DETAILS IN THIS DOCUMENT (WHERE APPLICABLE BASED ON SIZE AND SPACING LIMITATIONS) MAY BE USED IN LIEU OF PROVIDING A 		 INSULATING BLANKETS AND/OR THE USE OF TE GROUND TEMPERATURE AT THE TIME OF PLAC LESS THAN 35 DEGREES FAHRENHEIT. 	
	SEPARATE DESIGN.		INSULATION, FORMS AND HEATERS MAY BE REI	MOVED AFTER 72 HOURS .
	 STRUCTURAL SLABS EXCEEDING THE SPANS AND CONDITIONS OF THE APPROVED DETAILS SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER. 		MAINTAIN ADEQUATE PROTECTION OF SUB GRA EXPOSED CONCRETE ELEMENT TO PREVENT FI	
	SLABS AT MAX 4'-0" OVER-DIG ADJACENT T0 FOUNDATION WALL:	C.8	FOOTNOTES	
	 WHERE SOIL IS EXCAVATED FOR A MAXIMUM DIMENSION OF 4'-0" HORIZONTALLY ADJACENT TO A FOUNDATION WALL, THE STANDARD OVER-DIG DETAIL MAY BE USED IN LIEU OF A COMPLETE STRUCTURAL SLAB. 		• VERTICAL REINFORCEMENT FOR CONCRETE W REINFORCEMENT SPACED 24" O.C. MAY BE PLA WALLS SHALL HAVE VERTICAL REINFORCEMEN	CED IN THE MIDDLE OF THE WALL. OTHER
C.3	 SEE "TYPICAL FOOTING/FOUNDATION WALL/STANDARD SLAB AT MAX 4'-0" OVER-DIG" DETAIL. VAPOR RETARDER / BARRIER (IRC R506.2.3) 		 8" WALL – MINIMUM 2" FROM TENSION FA 10" WALL – MINIMUM 6-3/4" FROM THE OF EXTEND BARS TO WITHIN 8" OF THE TOF 	UTSIDE FACE
	A 6 MILLIMETER POLYETHYLENE OR APPROVED VAPOR RETARDER WITH JOINTS LAPPED A MINIMUM OF 6" IS REQUIRED BETWEEN THE CONCRETE FLOOR SLAB AND THE BASE COURSE		HORIZONTAL REINFORCEMENT:	
	OR PREPARED SUBGRADE, (NOT REQUIRED FOR GARAGE SLABS OR DETACHED UNHEATED ACCESSORY BUILDINGS).			ED WITH SPACING NOT TO EXCEED 24" O.C.
C.4	 FOOTINGS THE BOTTOM OF ALL FOOTINGS SHALL EXTEND NOT LESS THAN 36" BELOW GRADE FOR FROST 		SUPPLEMÉNTAL REINFORCEMENT AT C DEGREE ANGLE AT CORNERS OF OPEN	REINFORCEMENT (I.E. 2" FROM INSIDE FACE) ORNERS – PLACE 1 #4 REBAR 48" LONG AT 45 INGS. PLACE REINFORCEMENT WITHIN 6" OF
	 PROTECTION (IRC R403.1.4). FOOTINGS FOR FREESTANDING ACCESSORY STRUCTURES WITH AN AREA OF 600 SQ. FT. OR LESS AND AN EAVE HEIGHT OF 10'-0" OR LESS SHALL EXTEND BELOW GRADE A MINIMUM OF 		 THE EDGE OF INSIDE CORNERS. AT MASONRY LEDGES THE MINIMUM WALL THIC EXCEED A DEPTH OF MORE THAN 24" BELOW THE EXCEED A DEPTH OF MORE THAN 24" BELOW THE 	HE TOP OF THE WALL FOR WALL THICKNESS
	 EXTERIOR WALLS, BEARING WALLS, COLUMNS AND PIERS SHALL BE SUPPORTED ON CONTINUOUS SOLID MASONRY OR CONCRETE FOOTINGS, OR APPROVED STRUCTURAL 		 LESS THAN 4". PROVIDE #4 BARS AT MAXIMUM 2 STRAIGHT WALLS MORE THAN 5'-0" TALL AND M WITH EXTERIOR BRACED RETURN WALLS. WALL 	ORE THAN 16-0''' LONG SHALL BE PROVIDED L LENGTH SHALL BE MEASURED USING INSIDE
	SYSTEM TO SAFELY SUPPORT THE IMPOSED LOADS AND SHALL BE SIZED AND REINFORCED IN ACCORDANCE WITH THIS STANDARD OR SHALL BE ENGINEERED DESIGN.		THE SHORTEST DIMENSION BETWEEN INTERSE SECTION).	``````````````````````````````````````
	 FOOTINGS UNDER FOUNDATION WALLS SHALL BE CONTINUOUS AROUND THE STRUCTURE AND FROM ONE LEVEL TO THE NEXT. 		MINIMUM SPECIFIED COMPRESSIV PER TABLE	R402.2
	 THE CONTINUOUS TRANSITIONS BETWEEN FOOTINGS AT DIFFERENT LEVELS ENCLOSING USABLE SPACE SHALL BE MADE BY APPROVED SOLID JUMPS OR SUPPORT SYSTEMS TO PROVIDE SAFE SUPPORT OF THE STRUCTURE. 		TYPE OR LOCATION OF CONCRETE CONSTRUCTION BASEMENT WALLS, FOUNDATIONS AND	MINIMUM SPECIFIED COMPRESSIVE STRENG FOR SEVER WEATHERING POTENTIAL
<u> </u>	SEE "TYPICAL FOOTING/FOUNDATION WALLS/STANDARD SLAB AT MAXIMUM 4" OVER-DIG" AND "FOOTING JUMP" DETAILS.		OTHER CONCRETE NOT EXPOSED TO THE WEATHER BASEMENT SLABS AND INTERIOR SLABS ON	2,500
C.5	ALL CONCRETE CONSTRUCTION SHOULD CONFORM TO ACI 318-14 (OR ACI 332) OR 2018 IRC.		GRADE, EXCEPT GARAGE FLOOR SLABS	2,500
	 THE MINIMUM CONCRETE 28 DAY COMPRESSIVE STRENGTH SHALL BE AS SPECIFIED IN IRC TABLE R402.2. 		BASEMENT WALLS, FOUNDATION WALLS, EXTERIOR WALLS AND OTHER VERTICAL CONCRETE WORK EXPOSED TO THE WEATHER	3,000
			PORCHES, CARPORT SLABS AND STEPS EXPOSED TO THE WEATHER, AND GARAGE FLOOR SLABS	3,500
TRUCTION N REVIEW			SUSPENDED SLABS	4,000

LEE'S 03/26/2024

RELEASE

AS NOTE DEVELO

MUM WATER-CEMENT MATERIALS RATIO OF 0.45 FOR ALL L NOT CONTAIN ANY CHLORIDES. EXISTING SURFACE SHOULD BE ROUGHENED TO A MINIMUM

FOLLOWS:

ND PERMANENTLY EXPOSED TO EARTH	3.0 IN CLF 1.5 IN CLF
OR GROUND	3/4 IN CLF
S	1.5 IN CLF

T STEEL

OUNDATIONS TO WALL SHALL BE PROVIDED TO MATCH CING AND EXTENDED TO 3" CLEAR FROM BOTTOM OF

IREE CONSECUTIVE DAYS WHERE THE AVERAGE DAILY DEGREES FAHRENHEIT AND NOT ABOVE 50 DEGREES LF OF ANY ONE OF THOSE THREE DAYS.

CONCRETE WALLS THAT ARE NOT FULL HEIGHT AND FOR . MAY BE PLACED IN THE MIDDLE OF THE WALL. OTHER NFORCEMENT PLACED AS FOLLOWS:

COMPRESSIVE STRENGTH OF CONCRETE

PER TABLE R402.2				
	MINIMUM SPECIFIED COMPRESSIVE STRENGTH (f'c) FOR SEVER WEATHERING POTENTIAL			
	2,500			
	2,500			
(TERIOR /ORK	3,000			
	3,500			
	4,000			

D.1

FRA	MING/STRUCTURE			
FRA	MING NOTES			
•	ALL TREATED LUMBER SIZ	ES ARE DOUGLAS FIR-I	_ARCH #2 UNLESS O ⁻	THERWISE NOTED.
•	ALL NON TREATED LUMBE PINE UNLESS OTHERWISE		SIZES ARE #2 TREATE	ED SOUTHERN YELLOW
•	ALL UNMARKED HEADERS BEARING WALLS.	SHALL BE A MINIMUM #	#2 DOUGLAS FIR-LAR	CH (2) 2X10 ON LOAD
•	ALL HEADERS/BEAMS TO SHALL BE PROVIDED AT A			
•	DOUBLE JOIST UNDER PA	RALLEL INTERIOR NON-	LOAD BEARING WAL	LS.
•	CANTILEVERS, OVER BEAI	MS AND DOOR JAMBS S	HALL BE BLOCKED.	
•	ANY WOOD MEMBER IN CO ATTACHED TO) SHALL BE			R THE FURRING THEY ARE
•	IN BEARING WALLS, STUDS WHICH ARE NOT MORE THAN 10'-0" FEET IN LENGTH SHALL BE SPACED NOT MORE THAN IS SPECIFIED IN IRC TABLE R602.3(5) FOR THE CORRESPONDING STUD SIZE. THOSE STUDS GREATER THAN 10'-0" FEET IN LENGTH SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER OR REGISTERED ARCHITECT.			HE CORRESPONDING STUD
•	OCCUR OVER SUPPORTS ADJACENT PANELS. PROV	PLEMENTS OF THE APA AND SHALL BE STAGGE 'IDE 1/8" INCH SPACE AT	OR EQUIVALENT. ALL RED ONE HALF PAN PANEL ENDS. WOOI	PANEL END JOINTS SHALL
•	 MOISTURE CONTENT SHALL BE LESS THEN OR EQUAL TO 16%. ALL STRUCTURAL FRAMING MEMBERS SHALL BE AS FOLLOWS UNO: 2X4 OR 2X6 EXTERIOR WALLS AS PERMITTED BY CODE: DOUGLAS FIR-LARCH #2 (DF-L #2) OR BETTER. EXTERIOR WALLS TO BE CONTINUOUSLY SHEATHED WITH MIN. 7/16" OSB EXTERIOR WALLS TO BE CONTINUOUSLY SHEATHED WITH MIN. 7/16" OSB EXTERIOR WALLS TO BE CONTINUOUSLY SHEATHED WITH MIN. 7/16" OSB EXTERIOR WALLS TO BE CONTINUOUSLY SHEATHED WITH MIN. 7/16" OSB EXTERIOR WALLS TO BE CONTINUOUSLY SHEATHED WITH MIN. 7/16" OSB EXTERIOR WALLS TO BE FASTENED WITH 8D COMMON NAILS; 6" O. C. AT PANEL EDGES, 12" O. C. IN THE FIELD. 2X4 OR 2X6 INTERIOR LOAD BEARING WALLS DF-L #2 OR BETTER. LOAD BEARING, BRACED, AND SHEAR WALLS, REQUIRE A DOUBLE TOP PLATE. THE TOP PLY BEING FIELD APPLIED LIED WITH A MIN. 24" LAP SPLICE FIELD APPLIED LAP SPLICED TOP PLATE: DF-L #2 OR BETTER LOAD BEARING HEADERS PER HEADER SCHEDULE OR AS SHOWN ON FRAMING PLANS. LOAD BEARING HEADERS TO BE FABRICATED WITH THE HEADER AT THE UNDER SIDE OF THE TOP PLATE WITH CRIPPLE FRAMING BELOW AS NEEDED UNO. INTERIOR NON LOAD BEARING WALLS: DF-L #2 STUD GRADE OR BETTER DOUBLE TOP PLATE IS NOT REQUIRED FOR INTERIOR NON LOAD BEARING WALLS MEADER CRIPPLE SPACING CAN BE 24" O. C. REGARDLESS OF WALL STUD SPACING FOR NON LOAD BEARING WALLS. CRIPPLE FRAMING NOT REQUIRED ABOVE OR BELOW OPENINGS WHERE THE VERTICAL CLEAR HEIGHT IS 22" OR LESS FOR NON-LOAD BEARING WALLS. ALL LUMBER IN CONTACT WITH MASONRY OR OTHERWISE EXPOSED TO WEATHERING TO BE PRESSURE TREATED WOOD SHALL BE PRESSURE TREATED WITH WATER-BORNE PRESSURE TREATED WOOD SHALL BE PRESSURE TREATED WITH WATER-BORNE PRESSURE TREATED WOOD SHALL BE PRESSURE TREATED WITH WATER-BORNE PRESSURE TREATED WOOD SHALL BE PRESSURE TREATED WOOD SHALL BE HOT-DIPPED, ZINC-COATED GALVANIZED STEL, STAINLESS STEL, SLICON BRONZE OR COPPER. CONTRG TYPES AND WEIGHT			
	RECOMMENDATIONS. IN THE ABSENCE OF MANUFACTURER'S RECOMMENDATIONS, A MIN. OF ASTM A653 TYPE G185 ZINC-COATED GALVANIZED STEEL, OR EQUIVALENT, SHALL BE USED. FOR EXCEPTIONS, REFER TO R317.3.1.			
	ENGINEE	RED LUMBER MIIMUM D		
		F₅ (PSI)	E (PSI)	F _v (PSI)
	LVL	3100	1.9X10 ⁶	285
	DOUGLAS FIR-LARCH	900	1.6X10 ⁶	180
	GLU-LAM	2400	1.8X10 ⁶	230
STRI	JCTURAL STEEL			
•	STEEL DESIGN, FABRICAT STEEL CONSTRUCTION.	ION, AND ERECTION SH	ALL CONFORM WITH	AMERICAN INSTITUTE OF
•	STEEL PIPE COLUMNS SH	ALL BE A MINIMUM OF S	CHEDULE 40.	
	STEEL GRADE AND SPECI HOLLOW STRUCTU CHANNELS, PLATE WIDE FLANGES: STEEL PIPE COLUI ANCHOR RODS:	JRAL SECTIONS: S, ANGLES, AND COLUN		ASTM A500 (F _Y = 46 KSI) ASTM A36 (F _Y = 36 KSI) ASTM A992 (F _Y = 50 KSI) ASTM A53 GR.B (F _Y = 35 KSI) ASTM F1554 (F _Y = 36 KSI)

BOLTS SHALL CONFORM TO ASTM A307

WELDING SHALL CONFORM TO THE AWS CODES FOR BUILDING CONSTRUCTION, WELDING SHALL BE PERFORMED IN ACCORDANCE TO WELDING PROCEDURE SPECIFICATIONS (WPS) AS REQUIRED IN AWS D1.1. THE WPS VARIABLES SHALL BE WITHIN THE PARAMETERS ESTABLISHED BY THE FILLER-METAL MANUFACTURER.

WELDS SHALL USE E70XX ELECTRODES AND A MINIMUM OF 3/16" SIZE UNLESS NOTED OTHERWISE

ALL WELDS SPECIFIED AS FIELD WELDS MAY BE SHOP WELDED AT THE CONTRACTOR'S OPTION IF ERECTION CAN STILL BE EXECUTED.

E. <u>GLAZING</u>

D.2

- GLAZING IN HAZARDOUS LOCATIONS AS IDENTIFIED IN IRC R308.4 SHALL BE OF APPROVED • SAFETY GLAZING MATERIALS.
 - GLASS IN STORM DOORS: INDIVIDUAL FIXED OR OPERABLE PANELS ADJACENT TO A DOOR WHERE THE NEAREST VERTICAL EDGE OF THE GLAZING IS WITHIN A 24" ARC OF EITHER VERTICAL EDGE OF THE DOOR IN A CLOSED POSITION AND WHERE THE BOTTOM EDGE OF THE GLAZING IS LESS THAN 60" ABOVE THE FLOOR.
 - GLAZING ADJACENT TO THE LANDING AT THE BOTTOM OF THE STAIRWAY WHERE THE • GLAZING IS LESS THAN 36 INCHES ABOVE THE LANDING AND WITHIN A 60 IN HORIZONTAL ARC LESS THAN 180 DEGREES FROM THE BOTTOM TREAD NOSING SHALL BE CONSIDERED A HAZARDOUS LOCATION.
 - GLAZING IN WALLS, ENCLOSURES OR FENCES CONTAINING OR FACING HOT TUBS, SPAS, • WHIRLPOOLS, SAUNAS, STEAM ROOMS, BATHTUBS, SHOWERS, AND INDOOR OR OUTDOOR SWIMMING POOLS WHERE THE BOTTOM EXPOSED EDGE OF THE GLAZING IS LESS THAN 60" MEASURED VERTICALLY ABOVE ANY STANDING OR WALKING SURFACE.
- WINDOW FALL PROTECTION SHALL BE PROVIDED IN ACCORDANCE WITH IRC R312.2.

F. <u>STAIRWAYS</u>

STAIRWAYS SHALL PROVIDE A MAXIMUM 7-3/4" RISE AND A MINIMUM 10" RUN.

REQUIRED GUARD RAILS AT OPEN-SIDED WALKING SURFACES, INCLUDING STAIRS, PORCHES, BALCONIES, OR LANDINGS, SHALL NOT BE LESS THAN 36" HIGH MEASURED VERTICALLY ABOVE THE ADJACENT WALKING SURFACE.

- EXCEPTION (1): GUARD RAILS ON THE OPEN SIDES OF STAIRS SHALL HAVE A HEIGHT NOT LESS THAN 34" MEASURED VERTICALLY FROM A LINE CONNECTING THE LEADING EDGES OF THE TREADS.
- EXCEPTION (2): WHERE THE TOP OF THE GUARD ALSO SERVES AS A HANDRAIL ON THE • OPEN SIDES OF STAIRS, THE TOP OF THE GUARD SHALL NOT BE LESS THAN 34" AND NOT MORE THAN 38" MEASURED VERTICALLY FROM A LINE CONNECTING THE LEADING EDGES OF THE TREADS.

GUARD RAIL ENCLOSURES SHALL HAVE INTERMEDIATE RAILS OF ORNAMENTAL PATTERNS THAT DO NOT ALLOW PASSAGE OF A SPHERE 4" IN DIAMETER.

EACH STAIRWAY OF FOUR OR MORE RISERS SHALL PROVIDE A CONTINUOUS HANDRAIL ON AT LEAST ONE SIDE BETWEEN 34" AND 38" ABOVE THE NOSING OF THE TREADS.

HANDRAILS SHALL HAVE A CIRCULAR CROSS SECTION OF 1-1/4" TO 2" OR OTHER APPROVED GRASPABLE SHAPE PER IRC R311.7.8.5.

MINIMUM 6'-8" OF HEADROOM CLEARANCE IS REQUIRED IN STAIRWAYS.

ENCLOSED ACCESSIBLE SPACE UNDER STAIRWAYS SHALL HAVE WALLS AND THE UNDERSIDE OF THE STAIR AND LANDING PROTECTED WITH 1/2" GYPSUM BOARD ON ENCLOSURE PER IRC R302.7.

<u>GARAGES</u>

G.

THE GARAGE FLOOR SHALL SLOPE 1/8" PER 12" TO DRAIN OR VEHICLE ENTRY DOORWAYS.

DOORS BETWEEN THE GARAGE AND THE DWELLING TO BE: SELF CLOSING, MINIMUM 1-3/8" SOLID CORE OR HONEYCOMBED STEEL DOOR, AND AT LEAST 20 MINUTE FIRE RATED.

THE GARAGE SHALL BE SEPARATED FROM THE DWELLING AND ITS ATTIC AREAS BY A MINIMUM 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE WHERE A FLOOR/CEILING SPACE IS PROVIDED ABOVE.

THE GARAGE COLUMNS AND BEAMS SUPPORTING THE SEPARATION SHALL ALSO BE PROTECTED WITH 1/2" GYPSUM BOARD OR EQUIVALENT.

WHERE HABITABLE SPACE OCCURS ABOVE THE GARAGE FLOOR/CEILING ASSEMBLY SHALL BE PROTECTED WITH A MINIMUM 5/8" TYPE "X" GYPSUM BOARD ON THE GARAGE CEILING.

GARAGE DOOR AND FRAME – THE "H" FRAME FOR THE ATTACHMENT OF THE TRACK AND COUNTER BALANCE SHALL CONSIST OF THE FOLLOWING: 2X6 VERTICAL JAMBS RUNNING FROM THE FLOOR TO CEILINGS, ATTACHED WITH 1-3/4" X 0.120" NAILS AT 7" O.C. STAGGERED WITH (7) 3-1/4" X 0.120" NAILS THROUGH THE JAMB INTO THE HEADER, 2X8 HEADER (MINIMUM) FOR ATTACHMENT OF COUNTER BALANCE SYSTEM.

GARAGE VEHICLE DOORS AND FRAMES SHALL BE DESIGNED AND INSTALLED TO MEET THE 115 MPH WIND LOAD REQUIREMENT OF DASMA 108 AND ASTM E330-96 (IRC R301.2.1).

<u>ROOF</u>

Н.

1.2

Κ.

•

THE ROOF IS DESIGNED FOR 20 PSF GROUND SNOW LOAD (MINIMUM).

PROVIDE 2X SOLID BLOCKING SUPPORT BELOW ALL POINT LOADS CONTINUOUS TO BEARING STRUCTURE AND/OR FOUNDATION BELOW.

ROOF IS ENGINEERED TO COMPLY WITH IRC R802.

ROOF TO BE ASPHALT SHINGLES UNO AND SHALL COMPLY WITH IRC 2018 SECT. R905.2

MINIMUM ROOF SLOPE FOR ASPHALT SHINGLES SHALL BE 2:12.

ROOF SLOPES IN BETWEEN 2:12 AND 4:12 SHALL REQUIRE DOUBLE UNDERLAYMENT IN ACCORDANCE WITH IRC 2018 SECTION R905.2.2:

"APPLY A 19-INCH (483MM) STRIP OF UNDERLAYMENT FELT PARALLEL TO AND STARTING AT THE EAVES, FASTENED SUFFICIENTLY TO HOLD IN PLACE. STARTING AT THE EAVE, APPLY 36-INCH-WIDE (914 MM) SHEETS OF UNDERLAYMENT, OVERLAPPING SUCCESSIVE SHEETS 19 INCHES (483MM), AND FASTENED SUFFICIENTLY TO HOLD IN PLACE. END LAPS SHALL BE 4-INCH (102MM) AND SHALL BE OFFSET BY 6 FEET (1829 MM). DISTORTIONS IN THE UNDERLAYMENT SHALL NOT INTERFERE WITH THE ABILITY OF THE SHINGLES TO SEAL."

SAFETY REQUIREMENTS

I.1 EMERGENCY EGRESS AND RESCUE

PROVIDE ONE WINDOW FROM EACH BEDROOM THAT HAS A MINIMUM OPENABLE AREA OF 5.7 SQ. FT. WITH A MINIMUM OPENABLE HEIGHT OF 24" AND WIDTH OF 20".

SMOKE AND CARBON MONOXIDE SAFETY (PER IRC R314)

BASEMENT EGRESS TO MEET THE REQUIREMENTS OF IRC R310.

PROVIDE SMOKE ALARMS IN EACH SLEEPING ROOM, OUTSIDE OF EACH SLEEPING AREA AND ON EACH FLOOR INCLUDING BASEMENTS.

SMOKE ALARMS SHALL BE INTERCONNECTED IN SUCH A MANNER THAT THE ACTUATION OF

ONE ALARM WILL ACTIVATE ALL OF THE ALARMS IN THE DWELLING. CARBON MONOXIDE DETECTORS SHALL BE INSTALLED AS REQUIRED PER IRC R315.

J. <u>ENERGY REQUIREMENTS</u>

LIGHTING FIXTURES PENETRATING THE THERMAL ENVELOPE SHALL BE IC-RATED, LEAKAGE RATED AND SEALED TO THE GYPSUM WALLBOARD AS REQUIRED PER IRC N1102.4.5.

PROGRAMMABLE THERMOSTATS SHALL BE INSTALLED AS REQUIRED PER IRC N1103.1.1.

AIR HANDLERS SHALL BE RATED FOR MAXIMUM 2% AIR LEAKAGE RATE PER IRC N1103.3.2.1. BUILDING FRAMING CAVITIES SHALL NOT BE USED AS DUCTS OR PLENUMS.

HOT WATER PIPES SHALL BE INSULATED AS REQUIRED PER IRC N1103.4.

ALL EXHAUST FANS SHALL TERMINATE TO THE BUILDING EXTERIOR AS REQUIRED PER IRC

MAKEUP AIR SYSTEMS SHALL BE INSTALLED FOR KITCHEN EXHAUST HOODS THAT EXCEED 400

CFM AS REQUIRED PER IRC M1503.6. AN AIR HANDLING SYSTEM SHALL NOT SERVE BOTH THE LIVING SPACE AND THE GARAGE PER

IRC M1601.6 ENERGY CONSERVATION.


ABBREVIATIONS

M1504.3.

AFF: ABOVE FINISHED FLOOR

- CLR: CLEAR
- EFF: EFFECTIVE EFP: EQUIV FLUID PRESSURE
- EOR: ENGINEER OF RECORD
- EQUIV: EQUIVALENT MAX: MAXIMUM
- MIN: MINIMUM
- NTS: NOT TO SCALE O.C.: ON CENTER
- PCF: POUNDS PER CUBIC FOOT
- PLF: POUNDS PER LINER FOOT PSF: POUNDS PER SQUARE FOOT
- PSI: POUNDS PER SQUARE INCH UNO: UNLESS NOTED OTHERWISE
- FV: FIELD VERIFY





EVERSTEAD 3741 NE TROON DRIVE, SUITE 200 LEE'S SUMMIT, MO 64064 EVERSTEAD.COM (816)399-4901

N

 ∞

40

Ó

Ο

Ž

MIT

 \geq

 \supset

S

S

Ш

Ш

R

 \Box

OND

Ο

Ś

OR

Ш

 $\mathbf{\mathcal{L}}$

 \triangleleft

 \geq

3228

 \mathcal{O} _ \geq \geq

S

 \square \geq S $\overline{}$ # ш **(ח**) 2 Ζ N \bigcirc -Ś \triangleleft

REVISIONS


DATE

SCALE

STRUCTURAL **GENERAL NOTES**

SOOO

10/10/2023 11:03:15 AM 1/4" = 1'-0"





NTS


TYPICAL "UNRESTRAINED" FOUNDATION WALL DETAIL

- PLACEMENT OF SLAB, DEADMAN, AND FLOOR SYSTEM. FOUNATION WALL TO BE CONSTRUCTED PER PLAN / TYPCIAL WALL SECTION. 4.
- FOUNDATION WALL MUST HAVE A SLAB AT THE BASE, UNO ON PLAN. DO NOT BACKFILL PRIOR TO
- FOUNDATION WALLS W/ CRIPPLE WALLS INSTALLED ATOP DEADMAN TO BE INSTALLED PER PLAN / DETAIL SPACING.

NOTE UNRESTRAINED WALLS ARE WALLS WITH FLOOR JOISTS RUNNING PARRALLEL TO THE FOUNDATION OR 1.











SLAB

BACKFILL PERMITED.

SPACED 12" OC.

NTS

















WALL OR CURB

SLAB (NOTE 3)

THICKENED EDGE,

PER PLAN





REINFORCEMENT SHALL LAP A MINIMUM OF 24 INCHES AT ENDS, SPLICES, AND

INSIDE FACE)

AROUND CORNERS.


3 TYPICAL WALL SECTION DETAIL NTS








LEE'S 03/26/2024

DEVELO










DEVELOP LEE'S SU

RELEASE FOR

AS NOTED FO

03/26/2024



DECK DETAILS

S520

OF MI

HANNAH

CHRISTINE JONES

NUMBER

64082

ОМ

SUMMIT,

Ы С

Ш

DR

SOUND

ARBOR

SW

3228

-SMAN

RAF

 \mathbf{O}

 \square

NFIEI

S


 \sim #1

Ш

RD

HAWTHORN

DATE SCALE 10/10/2023 10:22:03 AM As indicated



03/26/2024

RELEASE

AS NOTE DEVEL

	MINIMUM	CONNECTION CRITERIA		
METHODS, MATERIAL	THICKNESS	FASTENERS	SPACING	
WSP - WOOD STRUCTURAL PANEL AND CS-WSP CONTINUOUSLY SHEATHED	3/8" PANEL W/ MINIMUM 24/0 STRUCTURAL PANEL SPAN RATING	6d COMMON NAILS (2.0" x .113") W/ MINIMUM 1.5" PENETRATION	6" EDGES, 12 FIELD	
WOOD STRUCTURAL PANEL	7/16" PANEL W/ MINIMUM 24/16 STRUCTURAL PANEL SPAN RATING	8d COMMON NAILS (2.5" x .131") W/ MINIMUM 1.75" PENETRATION	6" EDGES, 12' FIELD	
PFH - PORTAL FRAME WITH HOLD-DOWNS	3/8"	SEE DETAIL ON THIS PAGE	SEE DETAIL (THIS PAGE	
PFG - PORTAL FRAME AT GARAGE	3/8"	SEE IRC SECTION R602.10.6.3	SEE IRC SECTIO R602.10.6.3	
LIB LET-IN-BRACING		WOOD: 2-8d COMMON NAILS OR 3-8d (2-1/2" LONG x .113" DIA.) NAILS	WOOD: PER ST AND TOP AND BOTTOM PLATE	
		SIMPSON WB/WBC INSTALLED IN "X" PAIRS OR IN OPPOSING "V" FASHION AND FASTENED W/ (2) 16d COMMON NAILS FOR PLATE AND (1) 8d COMMON NAIL FOR STUDS	METAL: PER ST AND TOP ANI BOTTOM PLATI	
		1/2" INTERIOR SHEATHING W/ STUDS AT 16" O.C.: 13 GAGE, 1-3/8" LONG, 19/64" HEAD; .098" DIA., 1-1/4" LONG, ANNULAR-RINGED; 5d COOLER NAIL, .086" DIA., 1-5/8" LONG, 15/64" HEAD; OR GYPSUM BOARD NAIL, .086" DIA. 1-5/8" LONG, 9/32" HEAD PER TABLE R702.3.5 (SEE TABLE FOR OTHER PANEL THICKNESS OPTIONS)	FOR ALL BRACE WALL PANEL LOCATIONS: 7' EDGES (INCLUDING TO AND BOTTOM PLATES) 7" FIEL	
GB-GYPSUM BOARD	1/2"	EXTERIOR 1/2" SHEATHING: 1-1/2" GALVANIZED ROOFING NAIL; STAPLE GALVANIZED, 1-1/2" LONG; 1-1/4" SCREWS, TYPE W OR S PER TABLE R602.3(1)		
		EXTERIOR 5/8" SHEATHING: 1-3/4" GALVANIZED ROOFING NAIL; STAPLE GALVANIZED, 1-5/8" LONG; 1-5/8" SCREWS, TYPE W OR S PER TABLE R602.3(1)		

DESCRIPTION OF BUILDING MATERIALS	NUMBER AND TYPE OF FASTENER	SPACING AND LOCATION OF FASTENERS	DESCRIPTION OF BUILDIN MATERIALS
	ROOF		
BLOCKING BETWEEN JOISTS OR RAFTERS TO TOP PLATE	4-8d BOX (2-1/2"x0.113") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 3-3"x0.131" NAILS	TOE NAIL	JOIST TO SILL, TOP PLATE, GIRDER
CEILING JOISTS TO PLATE	4-8d BOX (2-1/2"x0.131") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10 BOX (3"x0.128") OR 3-3"x0.131" NAILS	TOE NAIL	RIM JOIST, BAND JOIST C BLOCKING TO SILL OR TOP F (ROOF APPLICATIONS ALS
CEILING JOISTS NOT ATTACHED TO PARALLEL RAFTER LAPS OVER PARTITIONS	4-10d BOX (3"x0.128") OR 3-16d COMMON (3-1/2"x0.162") OR 4-3"x0.131" NAILS	FACE NAIL	1"x6" SUBFLOOR OR LESS EACH JOIST
COLLAR TIE TO RAFTER, FACE NAIL OR 1-1/4"x20 GAGE RIDGE STRAP	4-10d BOX (3"x0.128") OR 3-10d COMMON (3"x0.148") OR 4-3"x0.131" NAILS	FACE NAIL EACH RAFTER	2" SUBFLOOR TO JOIST O GIRDER
RAFTER OR ROOF TRUSS TO TOP PLATE, TOE NAIL	4-16d BOX (3-1/2"x0.135") OR 3-10d COMMON (3"x0.148") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS	2 TOE NAILS ON ONE SIDE AND 1 TOE NAIL ON OPPOSITE SIDE OF EACH RAFTER OR TRUSS	2" PLANKS (PLANK & BEAM-FLO ROOF)
ROOF RAFTERS TO	4-16d BOX (3-1/2"x0.135") OR 3-10d COMMON (3"x0.148") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS	TOE NAIL	BAND OR RIM JOIST TO JOI
RIDGE, VALLEY OR HIP RAFTERS	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162") OR 3-10d BOX (3"x0.128") OR 3-3"x0.131" NAILS	END NAIL	
	WALL		BUILT-UP GIRDERS AND BEAM LUMBER LAYERS
STUD TO STUD (NOT AT BRACED WALL	16d COMMON (3-1/2"x0.162")	24" O.C. FACE NAIL	LUMBER LAYERS
PANELS)	10d BOX (3"x0.128") OR 3"x0.131" NAIL	16" O.C. FACE NAIL	
STUD TO STUD AND ABUTTING STUDS AT INTERSECTION WALL CORNERS	16d BOX (3-1/2"x0.135") OR 3"x0.131" NAIL	12" O.C. FACE NAIL	
(AT BRACED WALL PANELS)	16d COMMON (3-1/2"x0.162")	16" O.C. FACE NAIL	JOISTS OR RAFTERS
	16d COMMON (3-1/2"x0.162")	16" O.C. EACH EDGE FACE NAIL	
BUILT-UP HEADER, TWO PIECES WITH 1/2" SPACER	16d BOX (3-1/2"x0.135")	12" O.C. EACH EDGE FACE NAIL	BRIDGING OR BLOCKING T JOIST
CONTINUOUS HEADER TO STUD	5-8d BOX (2-1/2"x0.113") OR 4-8d COMMON (2-1/2"x0.131") OR 4-10d BOX (3"x0.128")	TOE NAIL	DESCRIPTION OF BUILDIN MATERIALS
	16d COMMON (3-1/2"x0.162")	16" O.C. FACE NAIL	WOOD STRUCTURA [SEE TABLE R602.3(3)
TOP PLATE TO TOP PLATE	10d BOX (3"x0.128") OR 3"x0.131" NAIL	12" O.C. FACE NAIL	
DOUBLE TOP PLATE SPLICE	8-16d COMMON (3-1/2"x0.162") OR 12-16d BOX (3-1/2"x0.135") OR 12-10d BOX (3"x0.128") OR 12-3"x0.131" NAILS	FACE NAIL ON EACH SIDE OF END JOINT (MINIMUM 24" LAP SPLICE LENGTH EACH SIDE OF END JOINT)	3/8" - 1/2"
BOTTOM PLATE TO JOIST, RIM JOIST,	16d COMMON (3-1/2"x0.162")	16" O.C. FACE NAIL	19/32" - 1"
BAND JOIST, OR BLOCKING (NOT BRACED WALL PANELS)	-16d BOX (3-1/2"x0.135") OR 3"x0.131" NAIL	12" O.C. FACE NAIL	
BOTTOM PLATE TO JOIST, RIM JOIST, BAND JOIST, OR BLOCKING (AT BRACED WALL PANELS)	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162") OR 4-3"x0.131" NAILS	3 EACH 16" O.C. FACE NAIL 2 EACH 16" O.C. FACE NAIL 4 EACH 16" O.C. FACE NAIL	1-1/8" - 1-1.4"
	4-8d BOX (2-1/2"x0.113") OR 3-16d BOX (3-1/2"x0.135") OR 4-8d COMMON (2-1/2"x0.131") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS	TOE NAIL	1/2" STRUCTURAL CELLULO FIBERBOARD SHEATHING
TOP OR BOTTOM PLATE TO STUD	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162") OR 3-10d BOX (3"x0.128") OR	END NAIL	25/32" STRUCTURAL CELLULO FIBERBOARD SHEATHING
TOP PLATES, LAPS AT CORNERS AND INTERSECTIONS	3-3"x0.131" NAILS 3-10d BOX (3"x0.128") OR 2-16d COMMON (3-1/2"x0.162") OR 3-3"x0.131" NAILS	FACE NAIL	1/2" GYPSUM INTERIOR COVE (R702.3.5) 5/8" GYPSUM INTERIOR COVE
1" BRACE TO EACH STUD AND PLATE	3-8d BOX (2-1/2"x0.113") OR 2-8d COMMON (2-1/2"x0.131") OR 2-10d BOX (3"x0.128") OR	FACE NAIL	(R702.3.5) WOOD STRUC
1"x6" SHEATHING TO EACH BEARING	2 STAPLES 1-3/4" 3-8d BOX (2-1/2"x0.113") OR 2-8d COMMON (2-1/2"x0.131") OR 2-10d BOX (3"x0.128") OR 2 STAPLES, 1" CROWN, 16 GA., 1-3/4" LONG	FACE NAIL	3/4" AND LESS
	3-8d BOX (2-1/2"x0.113") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 3 STAPLES, 1" CROWN, 16 GA., 1-3/4" LONG		7/8" - 1"
1"x8" AND WIDER SHEATHINGTO EACH BEARING	WIDER THAN 1"x8": 4-8d BOX (2-1/2"x0.113") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 4 STAPLES, 1" CROWN, 16 GA., 1-3/4" LONG	FACE NAIL	1-1/8" - 1-1/4"

F BUILDING ALS	NUMBER AND TYPE OF FASTENER		ND LOCATION STENERS		
	FLOOR				
DP PLATE, OR ER	4-8d BOX (2-1/2"x0.113") OR 3-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 3-3"x0.131" NAILS	TOE NAIL			
D JOIST OR	8d BOX (2-1/2"x0.113")	4" O.C.	TOE NAIL		
OR TOP PLATE TIONS ALSO)	8d COMMON (2-1/2"x0.131") OR 10d BOX (3"x0.128") OR 3"x0.131" NAIL	6" O.C. TOE NAIL			
OR LESS TO DIST	3-8d BOX (2-1/2"x0.113") OR 2-8d COMMON (2-1/2"x0.131") OR 3-10d BOX (3"x0.128") OR 2 STAPLES, 1" CROWN, 16 GA., 1-3/4" LONG	FAC	ENAIL		
D JOIST OR R	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162")	BLIND ANI	D FACE NAIL		
BEAM-FLOOR &	3-16d BOX (3-1/2"x0.135") OR 2-16d COMMON (3-1/2"x0.162")	AT EACH BEA	RING FACE NAIL		
IST TO JOIST	3-16d COMMON (3-1/2"x0.162") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS OR 4 3"x14 GA. STAPLES, 7/16" CROWN	END) NAIL		
	20d COMMON (3"x0.128")	O.C AT TOP END	ER AS FOLLOWS: 32" O AND BOTTOM AND GGERED.		
AND BEAMS, 2" AYERS	10d BOX (3"x0.128") OR 3"x0.131" NAIL	BOTTOM STAGG	NAIL AT TOP AND ERED ON OPPOSITE SIDES		
	AND: 2-20d COMMON (4"x0.192") OR 3-10d BOX (3"x0.128") OR 3-3"x0.131" NAILS	FACE NAIL AT ENDS AND AT EACH SPLICE			
UPPORTING AFTERS	4-16d BOX (3-1/2"x0.135") OR 3-16d COMMON (3-1/2"x0.162") OR 4-10d BOX (3"x0.128") OR 4-3"x0.131" NAILS	AT EACH JOIST OR RAFTER, FACE NAIL			
OCKING TO	2-10d BOX (3"x0.128") OR 2-8d COMMON (2-1/2"x0.131") OR 2-3"x0.131" NAILS	EACH END, TOE NAIL			
F BUILDING ALS	NUMBER AND TYPE OF FASTENER	EDGES (IN)	INTERMEDIATE SUPPORTS (IN)		
F	LS, SUBFLOOR, ROOF AND INTERIOR WALL SH PARTICLEBOARD WALL SHEATHING TO FRAMIN	G			
R002.3(3) FOR W	OOD STRUCTURAL PANEL EXTERIOR WALL SH	EATHING TO WALL			
2"	6d COMMON (2"x0.113") NAIL (SUBFLOOR, WALL) OR 8d COMMON (2-1/2"x0.131") NAILS (ROOF) OR RSRS-01 (2-3/8"x0.113") NAIL (ROOF)	6	12		
1"	8d COMMON NAIL (2-1/2"x0.131") OR RSRS-01 (2-3/8"x0.113") NAIL (ROOF)	6	12		
1.4"	10d COMMON (3"x0.148") NAIL OR 8d (2-1/2"x0.131") DEFORMED NAIL	6	12		
	OTHER WALL SHEATHING				
CELLULOSIC HEATHING	1-1/2" GALVANIZED ROOFING NAIL, 7/16" HEAD DIAMETER OR 1-1/4" LONG 16 GA. STAPLE WITH 7/16" OR 1" CROWN	3	6		
L CELLULOSIC HEATHING	1-3/4" GALVANIZED ROOFING NAIL, 7/16" HEAD DIAMETER OR 1-1/2" LONG 16 GA. STAPLE WITH 7/16" OR 1" CROWN	3	6		
IOR COVERING .5)	1-1/2" GALVANIZED ROOFING NAIL: STAPLE GALVANIZED, 1-1/2" LONG; 1-1/4" SCREWS, TYPE "W" OR "S"	7	7		
IOR COVERING .5)	1-3/4" GALVANIZED ROOFING NAIL: STAPLE GALVANIZED, 1-5/8" LONG; 1-5/8" SCREWS, TYPE "W" OR "S"	7	7		
D STRUCTURAL PANELS, COMBINATION SUBFLOOR UNDERLAYMENT TO FRAMING					
.ESS	6d DEFORMED (2"x0.120") NAIL OR 8d COMMON (2-1/2"x0.131") NAIL	6	12		
"	8d COMMON (2-1/2"x0.131") NAIL OR 8d DEFORMED (2-1/2"x0.120") NAIL	6	12		
.1/4"	10d COMMON (3"x0.148") NAIL OR 8d DEFORMED (2-1/2"x0.120") NAIL	6	12		

TABLE R507.9.1.3(2) PLACEMENT OF LAG SCREWS AND BOLTS IN DECK LEDGERS AND BAND JOISTS				
MINIMUM END AND EDGE DISTANCES AND SPACING BETWEEN ROWS (INCHES)				EN ROWS
	TOP EDGE	BOTTOM EDGE	ENDS	ROW SPACING
LEDGER	2	3/4	2	1-5/8 MIN. 5 MAX
BAND JOIST	3/4	2	2	1-5/8 MIN 5 MAX

<image/>			
EV 3741 NE TROC	NUMBER 2-2023046346 3/20/2024 ON AL ERSTEAD ON DRIVE, SUITE 200		
	MMIT, MO 64064 COM (816)399-4901		
Samon Times Samon Sam	HAWTHORN RIDGE #175 - WINFIELD CRAFTSMAN 3228 SW ARBOR SOUND DR LEE'S SUMMIT, MO 64082		
FASTENING SCHEDULE			
	/10/2023 10:22:09 AM		

DATE SCALE 10/10/2023 10:22:09 AM 1/4" = 1'-0"


GENERAL NOTES

Α

- ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATIONAL RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE. THE INFORMATION PROVIDED ON THIS PLAN SHEET IS DESIGNED AND REVIEWED IN ACCORDANCE WITH THE IRC.
- CONCRETE WINDOW WELLS SHALL BE MINIMUM 3000 PSI COMPRESSIVE STRENGTH. ASSUMED SOIL MINIMUM BEARING CAPACITY 1500 PSF.
- CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF EXISTING CONDITIONS AND DIMENSIONS CRITICAL FOR CONSTRUCTION OF NEW WORK.
- MEANS AND METHODS OF CONTRUCTION ARE OUT OF SCOPE OF THE DESIGN PROVIDED. TEMPORARY SUPPORTS SHALL BE INSTALLED BEFORE REMOVAL OF LOAD BEARING STRUCTURES.
- DIMENSIONAL LUMBER SHALL BE MINIMUM DOUGLAS FIR LARCH NO. 2. LVL BEAMS SHALL HAVE MINIMUM 2.0E AND 3100Fb
- STEEL POST COLUMNS SHALL BE MINIMUM SCHEDULE 40, Fy=35KSI. 10. MINIMUM HEADERS 11.

ASSUMES LOADING FOR BUILDING WITH MAXIMIMUM WIDTH OF 36 FT (ROOF WITH 30PSF SNOW LOADS, CEILING, AND TWO FLOORS W/ CENTER BEARING) PER TABLE R602.7(1)

HEADER	MAX CLEAR SPAN	MIN JACK STUDS
(2) 2X10	4'-0"	2
(3) 2X10	5'-1"	2
(2) 2X12	4'-9"	3
(3) 2X12	5'-11"	2
(2) 1.75X9.25 LVL	7'-6"	3
(2) 1.75X11.25 LVL	9'-3"	3




WINDOW EGRESS (NTS)

RELEASE FOR ISTRUCTION AS NOTED FOR LAN REVIEW DEVELOP ERVICES LEE'S S 03/26/2024

WINDOW WELL FOR EGRESS (NTS)





10/10/2023 10:22:12 AM

As indicated

DATE

SCALE

- A. INSTALL PER MANUFACTURER'S WRITTEN INSTRUCTIONS В.
- B. INSTALLED TO EXISTING FOUNDATION
- Α.
- CONCRETE WINDOW WELL

