



Howerton Plumbing LLC

195 NW AA Highway

Kingsville, MO 64061

816-694-0303

4/11/2024

Customer Name	Andersen Contracting
Phone	
Address	294 SW Blue Parkway Lees Summit Mo

Description: Description/Material /Method sheet.

Job Consist of saw cutting concrete floor and move plumbing from current stool to different location approx. 5 feet away , along with Lavatory. Tie plumbing in with PVC , make appropriate connections, Repour cement floor. Install new Mini water heater above ceiling with appropriate mounting and drip pan being piped down to mop sink. Add in floor mounted mop sink.

Sch 40 pvc will be used and along with sch 40 DWV fittings. Pex will be used to supply water to new locations. Standard ada toto stool and lav installed and 20 gallon electric state water heater.

Labor and Material Total:	\$
---------------------------	----

Justin Howerton, Owner

Master Plumber

Licensed and Insured