

ELECTRICAL SCOPE

Demo light fixture, outlets, etc from new space. Demo outlets in wall between spaces and refeed

Run conduit/mc cables/wire to all new outlets, lights, switches, exit/emergency signs, data drops. Cost includes labor and material.

Install lights, outlets, switches, cover plates, breakers, exit/emergency, and data drops. Cost includes all labor and materials- including fixture costs.

Item QTY 0.00 Light fixture 26

Outlets 30

switches/dimmers. 11

Cat 6 Drops 3 Exit/Exit-Emergency 3 Bath Fan 1

All outlets, switches, lights, emergency lights in traction rooms, offices, and waiting room to be wired per 2017 NEC Article 517.13 and shall comply with 517.13(A) and (B) for wiring in patient care spaces. All MC cable used in these spaces shall be hospital grade with the appropriate connectors. All existing wiring methods that do not meet 517.13 shall be removed and replaced.