

RE: P240671-01 - Roof - HR Lot 79

Site Information:

Project Customer: Clayton Properties Project Name: Wildflower - Transitional 3C

Lot/Block: 79 Subdivision: Hawthorne Ridge

Model:

Address: 1543 Arbor Valley

City: Lee's Summit

State: MO

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2018/TPI2014

Wind Code: ASCE 7-16 Wind Speed: 115 mph

Roof Load: 45.0 psf

Design Program: MiTek 20/20 8.6

Design Method: MWFRS (Envelope)/C-C hybrid Wind ASCE 7-16

Floor Load: N/A psf

Mean Roof Height (feet): 35

Exposure Category: C

No.	Seal#	Truss Name	Date
1	I66610410	A5	7/3/24
2	I66610411	A4	7/3/24
3	I66610412	A3	7/3/24
4	I66610413	A2	7/3/24
5	I66610414	A1	7/3/24
6	I66610415	B1	7/3/24
7	I66610416	C3	7/3/24
8	I66610417	C2	7/3/24
9	I66610418	C1	7/3/24
10	I66610419	C4	7/3/24
11	I66610420	V1	7/3/24
12	I66610421	V2	7/3/24
13	I66610422	LG01	7/3/24
14	I66610423	V3	7/3/24
15	I66610424	V4	7/3/24
16	I66610425	CG1	7/3/24
17	I66610426	J1	7/3/24
18	I66610427	V5	7/3/24
19	I66610428	J2	7/3/24

The truss drawing(s) referenced above have been prepared by
MiTek USA, Inc. under my direct supervision based on the parameters
provided by Premier Building Supply (Springhill, KS)20300 W 207th Street.

Truss Design Engineer's Name: Sevier, Scott

My license renewal date for the state of Missouri is December 31, 2025.

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



July 3, 2024

Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	A5	Common Supported Gable	1	1	Job Reference (optional)


AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
166610410
LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:11 Page: 1

ID:ewrAceOsPybP0GqmZjh3U?zkXV?-RFC?PsB70Hq3NSgPqnL8w3ulTXBGKWrCDofr4423C#f

07/26/2024



Scale = 1:65.9

Plate Offsets (X, Y): [2:0-4-3,Edge], [24:0-4-3,Edge], [33:0-2-8,0-3-0], [35:0-2-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a	-	n/a	999	244/190
BCLL	0.0*	Rep Stress Incr	YES	WB	0.22	Horz(CT)	0.01	24	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 176 lb FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x3 SPF No.2
SLIDER	Left 2x4 SP No.2 -- 1-6-7, Right 2x4 SP No.2 -- 1-6-7

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	2=36-0-0, 24=36-0-0, 26=36-0-0, 27=36-0-0, 28=36-0-0, 29=36-0-0, 30=36-0-0, 31=36-0-0, 32=36-0-0, 33=36-0-0, 34=36-0-0, 35=36-0-0, 36=36-0-0, 37=36-0-0, 38=36-0-0, 39=36-0-0, 40=36-0-0, 41=36-0-0, 42=36-0-0
Max Horiz	2=148 (LC 16)
Max Uplift	2=-27 (LC 13), 24=-3 (LC 9), 26=-80 (LC 13), 27=-52 (LC 13), 28=-55 (LC 13), 29=-54 (LC 13), 30=-55 (LC 13), 31=-54 (LC 13), 32=-58 (LC 13), 33=-50 (LC 13), 35=-52 (LC 12), 36=-57 (LC 12), 37=-54 (LC 12), 38=-55 (LC 12), 39=-54 (LC 12), 40=-55 (LC 12), 41=-51 (LC 12), 42=-93 (LC 12)
Max Grav	2=160 (LC 1), 24=160 (LC 1), 26=178 (LC 26), 27=182 (LC 1), 28=180 (LC 26), 29=180 (LC 1), 30=180 (LC 26), 31=180 (LC 1), 32=179 (LC 26), 33=189 (LC 26), 34=185 (LC 22), 35=189 (LC 25), 36=179 (LC 25), 37=180 (LC 1), 38=180 (LC 25), 39=180 (LC 1), 40=180 (LC 25), 41=182 (LC 1), 42=178 (LC 25)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/0, 2-4=-196/72, 4-5=-135/78, 5-6=-102/90, 6-7=-81/111, 7-9=-60/133, 9-10=-58/156, 10-11=-73/194, 11-12=-88/239, 12-13=-103/279, 13-14=-103/279, 14-15=-88/239, 15-16=-73/194, 16-17=-58/151, 17-19=-43/107, 19-20=-43/63, 20-21=-53/25, 21-22=-73/18, 22-24=-126/38, 24-25=0/0
BOT CHORD	2-42=-38/146, 41-42=-38/146, 40-41=-38/146, 39-40=-38/146, 38-39=-38/146, 37-38=-38/146, 36-37=-38/146, 34-36=-38/146, 32-34=-38/146, 31-32=-38/146, 30-31=-38/146, 29-30=-38/146, 28-29=-38/146, 27-28=-38/146, 26-27=-38/146, 24-26=-38/146
WEBS	13-34=-145/13, 12-35=-149/82, 11-36=-139/94, 10-37=-140/88, 9-38=-140/89, 7-39=-140/90, 6-40=-139/89, 5-41=-142/112, 4-42=-135/166, 14-33=-149/82, 15-32=-139/94, 16-31=-140/88, 17-30=-140/89, 19-29=-140/90, 20-28=-139/89, 21-27=-142/113, 22-26=-135/163

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 4-0-0, Exterior(2N) 4-0-0 to 18-0-0, Corner(3R) 18-0-0 to 23-0-0, Exterior(2N) 23-0-0 to 36-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 1.5x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.



July 3, 2024

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of the design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	A5	Common Supported Gable	1	1	Job Reference (optional)

RELEASE FOR CONSTRUCTION

AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
166610410
LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:17 Page: 2
ID:ewrAceOsPybP0GqmZjh3U?zkXV?-RFC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoh744z3C#f

- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 2, 52 lb uplift at joint 35, 57 lb uplift at joint 36, 54 lb uplift at joint 37, 55 lb uplift at joint 38, 54 lb uplift at joint 39, 55 lb uplift at joint 40, 51 lb uplift at joint 41, 93 lb uplift at joint 42, 50 lb uplift at joint 33, 58 lb uplift at joint 32, 54 lb uplift at joint 31, 55 lb uplift at joint 30, 54 lb uplift at joint 29, 55 lb uplift at joint 28, 52 lb uplift at joint 27, 80 lb uplift at joint 26 and 3 lb uplift at joint 24.
- 11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

07/26/2024

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	A4	Common	18	1	Job Reference (optional)

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:11 Page: 1

ID:Do4JrdsVQdc4LgXOR7cmHVzkXB1-RfC?PsB70Hq3NSgPqnL8w3uITXbCKWwCD0rJ4LJC?F

07/26/2024



Scale = 1:65.9

Plate Offsets (X, Y): [2:0-3-11,0-0-11], [12:0-3-11,0-0-11]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.63	Vert(LL)	-0.31	14-16	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.83	Vert(CT)	-0.53	14-16	>808	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.48	Horz(CT)	0.15	12	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 159 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2 *Except* 1-5,9-13:2x4 SP 1650F 1.5E
BOT CHORD 2x4 SP 1650F 1.5E
WEBS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 3-5-1, Right 2x4 SP No.2 -- 3-3-9

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-7-11 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-9-0 oc bracing.

WEBS 1 Row at midpt 6-16, 8-16

REACTIONS (size) 2=0-5-8, 12=0-5-8
Max Horiz 2=148 (LC 12)
Max Uplift 2=-275 (LC 12), 12=-275 (LC 13)
Max Grav 2=1752 (LC 2), 12=1752 (LC 2)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/0, 2-4=-3328/512, 4-6=-3103/471, 6-7=-2247/433, 7-8=-2247/433, 8-10=-3102/471, 10-12=-3326/512, 12-13=0/0

BOT CHORD 2-18=-530/2942, 16-18=-360/2581, 14-16=-289/2581, 12-14=-383/2941

WEBS 7-16=-156/1367, 4-18=-273/212, 6-18=-33/542, 6-16=-790/287, 8-16=-791/287, 8-14=-33/541, 10-14=-272/212

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 18-0-0, Exterior(2R) 18-0-0 to 23-0-0, Interior (1) 23-0-0 to 36-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) All plates are 3x4 MT20 unless otherwise indicated.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 6) All bearings are assumed to be SP 1650F 1.5E crushing capacity of 565 psi.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 275 lb uplift at joint 2 and 275 lb uplift at joint 12.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79	RELEASE FOR CONSTRUCTION
P240671-01	A3	Common	8	1	Job Reference (optional)	AS NOTED FOR PLAN REVIEW DEVELOPMENT SERVICES 166610412 LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:11 Page: 1

ID: wv5pEcMn41RuWmuWX0N86szkXBg-RfC?PsB70Hq3NSgPqnL8w3uITXfGKwRCDu7J4zJC1

07/26/2024



Scale = 1:64.8									
Plate Offsets (X, Y): [2:0-3-3,0-2-7], [12:0-4-3,Edge], [17:0-3-0,0-3-0]									
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in (loc)	l/defl	L/d
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.17 2-18	>999	240
TCDL	10.0	Lumber DOL	1.15	BC	0.71	Vert(CT)	-0.35 2-18	>560	180
BCLL	0.0*	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.02 12	n/a	n/a
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S					
					Weight: 163 lb FT = 20%				

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 3-5-1, Right 2x4 SP No.2 -- 3-2-2

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-10-5 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 7-16

REACTIONS (size) 2=0-5-8, 12= Mechanical, 16=0-5-8
Max Horiz 2=148 (LC 12)
Max Uplift 2=-137 (LC 12), 12=-173 (LC 13), 16=-251 (LC 12)
Max Grav 2=620 (LC 25), 12=741 (LC 28), 16=2181 (LC 2)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/0, 2-4=-762/200, 4-6=-434/132, 6-7=0/693, 7-8=-460/294, 8-10=-1221/421, 10-12=-1237/305
BOT CHORD 2-18=-250/631, 16-18=-215/172, 14-16=-286/172, 13-14=-31/487, 12-13=-199/1060
WEBS 7-16=-1358/208, 4-18=-426/233, 6-18=-61/631, 6-16=-783/284, 8-14=-692/315, 7-14=-261/1035, 8-13=-224/811, 10-13=-374/230

NOTES
1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 18-0-0, Exterior(2R) 18-0-0 to 23-0-0, Interior (1) 23-0-0 to 36-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Bearings are assumed to be: Joint 2 SP No.2 crushing capacity of 565 psi, Joint 16 SP No.2 crushing capacity of 565 psi.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 137 lb uplift at joint 2, 251 lb uplift at joint 16 and 173 lb uplift at joint 12.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79	RELEASE FOR CONSTRUCTION
P240671-01	A2	Roof Special	2	1	Job Reference (optional)	AS NOTED FOR PLAN REVIEW
						DEVELOPMENT SERVICES
						166610413
						LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 E Apr 26 2024 Print: 8.630 E Apr 26 2024 MiTek Industries, Inc. Wed Jul 06 10:57:51 Page: 1

ID:CHDMs3BtTjmRKi7v_C9xqvzkXEU-0FdOLNkJcX8E9LS0JsqbqrXGHpjnQdbFeFsz260g

07/26/2024



Scale = 1:67.9

Plate Offsets (X, Y): [2:0-4-3,Edge], [4:0-3-0,Edge], [13:0-4-3,Edge], [16:0-2-4,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.25	14-16	>944	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.73	Vert(CT)	-0.42	13-14	>569	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.68	Horz(CT)	0.02	13	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 168 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP 1650F 1.5E *Except* 1-4,10-13:2x4 SP No.2
BOT CHORD 2x4 SP 1650F 1.5E *Except* 16-15:2x4 SP No.2
WEBS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 4-0-10, Right 2x4 SP No.2 -- 3-10-0

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 16-1-4, Exterior(2E) 15-1-8 to 20-1-8, Interior (1) 20-1-8 to 36-0-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 117 lb uplift at joint 2, 179 lb uplift at joint 17, 183 lb uplift at joint 13 and 208 lb uplift at joint 16.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-9-2 oc purlins, except end verticals.
Except:
6-0-0 oc bracing: 6-8
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 6-17, 9-16

REACTIONS All bearings 0-5-8. except 17=0-3-8, 13= Mechanical
(lb) - Max Horiz 2=-149 (LC 17)
Max Uplift All uplift 100 (lb) or less at joint(s) except 2=-118 (LC 12), 13=-184 (LC 13), 16=-208 (LC 13), 17=-180 (LC 12)
Max Grav All reactions 250 (lb) or less at joint (s) except 2=484 (LC 25), 13=793 (LC 28), 16=1649 (LC 2), 17=671 (LC 27)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-485/163, 3-19=-395/168, 4-19=-309/183, 4-5=-288/187, 5-20=0/419, 6-20=0/489, 6-16=-633/169, 6-8=-268/217, 9-10=-791/291, 10-11=-929/275, 11-24=-1071/348, 12-24=-1135/331, 12-13=-1227/326

LOAD CASE(S) Standard



July 3,2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of the design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)

MiTek®


16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79	RELEASE FOR CONSTRUCTION
P240671-01	A1	Roof Special Structural Gable	1	1	Job Reference (optional)	AS NOTED FOR PLAN REVIEW DEVELOPMENT SERVICES 166610414 LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 E Apr 26 2024 Print: 8.630 E Apr 26 2024 MiTek Industries, Inc. Wed Jul 03 10:55:05
ID: ZPE42GujG2XQkNP0IKB?1ezkXCH-9ebl2WX7D99Q4RRqX1DnygJ9QUbCi8b1cABT3z76Mc Page: 1

07/26/2024



Scale = 1:70.2

Plate Offsets (X, Y): [2:0-4-3,Edge], [15:0-4-0,0-2-0], [20:0-4-3,Edge], [24:0-2-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	-0.26	20-21	>908	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.95	Vert(CT)	-0.54	20-21	>445	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.59	Horz(CT)	0.02	20	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 197 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2
OTHERS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 4-0-10, Right 2x4 SP No.2 -- 3-10-0

WEBS
11-33=0/419, 33-41=0/398, 15-41=0/407,
24-34=-1062/275, 34-40=-1024/256,
16-40=-986/228, 15-16=-3/344,
16-21=-127/743, 18-21=-499/285

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-11-9 oc purlins, except end verticals. Except:
6-0-0 oc bracing: 11-13
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing, Except:
10-0-0 oc bracing: 22-24,21-22
2-2-0 oc bracing: 20-21.
JOINTS 1 Brace at Jt(s): 34, 35, 36, 40, 41

REACTIONS All bearings 11-0-0. except 20=0-3-8, 24=0-5-8
(lb) - Max Horiz 2=-147 (LC 17)
Max Uplift All uplift 100 (lb) or less at joint(s)
2, 28, 29, 30, 32 except 20=-155 (LC 13), 24=-247 (LC 13), 27=-225 (LC 12), 31=-225 (LC 28)
Max Grav All reactions 250 (lb) or less at joint (s) 2, 28, 29, 30, 31 except 20=777 (LC 28), 24=1558 (LC 2), 27=550 (LC 1), 32=360 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 7-8=-56/428, 8-9=-6/407, 9-10=0/420, 10-42=0/414, 11-42=0/441, 11-24=-534/127, 16-17=-762/229, 17-18=-865/215, 18-44=-1018/292, 19-44=-1081/276, 19-20=-1162/270
BOT CHORD 26-27=-395/264, 25-26=-395/264, 24-25=-395/264, 23-24=0/343, 22-23=0/343, 21-22=0/340, 20-21=-177/998

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-0-0, Interior (1) 4-0-0 to 16-1-4, Exterior(2E) 15-1-8 to 20-1-8, Interior (1) 20-1-8 to 36-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - All plates are 1.5x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 28, 29, 30, 32 except (jt=lb) 20=155, 27=225, 31=224, 24=247.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	B1	Roof Special Supported Gable	1	1	Job Reference (optional)


AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
166610415
LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:15 Page: 1

ID: bzCw6On6o49uPtGdBr3k7RzKXGI-RfC?PsB70Hq3NSgPqnL8w3uITXbGfWwCD0i734zC?

07/26/2024



Scale = 1:64.4

Plate Offsets (X, Y): [2:0-2-3,0-0-3], [20:0-2-3,0-0-3], [29:0-2-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.41	Vert(LL)	n/a	-	n/a	999	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.09	Vert(CT)	n/a	-	n/a	999	197/144
BCLL	0.0*	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.01	20	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 129 lb FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x3 SPF No.2
OTHERS	2x3 SPF No.2
SLIDER	Left 2x4 SP No.2 -- 1-6-8, Right 2x4 SP No.2 -- 1-6-7

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. Except: 6-0-0 oc bracing: 6-8
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing, Except: 10-0-0 oc bracing: 2-33,32-33,31-32.

REACTIONS (size)	2=25-8-0, 20=25-8-0, 22=25-8-0, 23=25-8-0, 24=25-8-0, 25=25-8-0, 26=25-8-0, 27=25-8-0, 28=25-8-0, 29=25-8-0, 30=25-8-0, 31=25-8-0, 32=25-8-0, 33=25-8-0
Max Horiz	2=-307 (LC 9)
Max Uplift	2=-40 (LC 11), 22=-111 (LC 13), 23=-49 (LC 13), 24=-56 (LC 13), 25=-54 (LC 13), 26=-54 (LC 13), 27=-55 (LC 13), 28=-53 (LC 13), 29=-64 (LC 13), 30=-45 (LC 9), 31=-173 (LC 13), 32=-51 (LC 9), 33=-102 (LC 12)
Max Grav	2=165 (LC 22), 20=206 (LC 20), 22=180 (LC 1), 23=181 (LC 26), 24=180 (LC 1), 25=180 (LC 26), 26=180 (LC 1), 27=180 (LC 26), 28=180 (LC 1), 29=182 (LC 26), 30=167 (LC 1), 31=206 (LC 1), 32=190 (LC 1), 33=158 (LC 25)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=0/0, 2-4=-262/116, 4-5=-207/105, 5-6=-208/139, 6-31=-166/347, 6-8=-142/241, 7-8=-26/0, 8-9=-104/79, 9-10=-130/60, 10-11=-157/71, 11-12=-200/86, 12-14=-243/101, 14-15=-287/116, 15-16=-330/131, 16-17=-374/147, 17-18=-414/161, 18-20=-504/191, 20-21=0/0
BOT CHORD	2-33=-161/464, 32-33=-161/464, 31-32=-161/464, 30-31=-169/459, 28-30=-169/459, 27-28=-169/459, 26-27=-169/459, 25-26=-169/459, 24-25=-169/459, 23-24=-169/459, 22-23=-169/459, 20-22=-169/459, 18-22=-137/227, 17-23=-142/105, 16-24=-140/91, 15-25=-140/89, 14-26=-140/89, 12-27=-140/89, 11-28=-140/88, 10-29=-142/117, 9-30=-128/122, 5-32=-148/130, 4-33=-121/161
WEBS	

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) 0-10-8 to 4-1-8, Exterior(2N) 4-1-8 to 5-9-4, Corner(3E) 4-9-8 to 9-8-0, Exterior(2N) 9-8-0 to 26-6-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 1.5x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.

- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 173 lb uplift at joint 31, 40 lb uplift at joint 2, 111 lb uplift at joint 22, 49 lb uplift at joint 23, 56 lb uplift at joint 24, 54 lb uplift at joint 25, 54 lb uplift at joint 26, 55 lb uplift at joint 27, 53 lb uplift at joint 28, 64 lb uplift at joint 29, 45 lb uplift at joint 30, 51 lb uplift at joint 32 and 102 lb uplift at joint 33.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. For additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com




Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79	RELEASE FOR CONSTRUCTION
P240671-01	C2	Hip	1	1	Job Reference (optional)	AS NOTED FOR PLAN REVIEW DEVELOPMENT SERVICES 166610417 LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:15 Page: 1

ID:tmBD8Uk7dBg1qo7SL0qAEz0OZQ-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoh7J42JC9f

07/26/2024



Scale = 1:42.8

Plate Offsets (X, Y): [2:0-0-3,0-2-3], [7:0-0-3,0-2-3]												
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.11	9-11	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.63	Vert(CT)	-0.25	9-11	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.05	7	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 89 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2 *Except* 4-5:2x4 SP 2400F 2.0E
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 3-5-3, Right 2x4 SP No.2 -- 3-5-3

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-7-13 oc purlins, except 2-0-0 oc purlins (4-8-7 max.): 4-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-3-8, 7=0-5-8
Max Horiz 2=57 (LC 16)
Max Uplift 2=-154 (LC 8), 7=-154 (LC 9)
Max Grav 2=1006 (LC 1), 7=1006 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/0, 2-4=-1707/352, 4-5=-1479/372, 5-7=-1709/352, 7-8=0/0
BOT CHORD 2-11=-244/1483, 9-11=-247/1478, 7-9=-234/1485
WEBS 4-11=0/311, 4-9=-169/171, 5-9=0/311

NOTES
1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 6-6-0, Exterior(2R) 6-6-0 to 13-6-14, Interior (1) 13-6-14 to 14-6-0, Exterior(2R) 14-6-0 to 21-6-14, Interior (1) 21-6-14 to 21-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 6) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 154 lb uplift at joint 2 and 154 lb uplift at joint 7.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®


16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	C1	Hip Girder	1	2	Job Reference (optional)

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:15 Page: 1
ID:ljrSGQAeiloLuci5CzhomJz0Oa9-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWCD0i7J4zSC7

07/26/2024



Scale = 1:42.7

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.11	9	>999	240	MT20 197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.52	Vert(CT)	-0.20	9	>999	180	
BCLL	0.0*	Rep Stress Incr	NO	WB	0.26	Horz(CT)	0.03	6	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 175 lb FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x6 SPF No.2
WEBS	2x3 SPF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (5-4-6 max.): 3-5.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size)	2=0-3-8, 6=0-5-8
Max Horiz	2=41 (LC 33)
Max Uplift	2=-432 (LC 8), 6=-438 (LC 9)
Max Grav	2=1599 (LC 1), 6=1610 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=0/6, 2-3=-3215/930, 3-4=-4170/1268, 4-5=-4170/1268, 5-6=-3185/919, 6-7=0/6
BOT CHORD	2-11=-776/2841, 9-11=-776/2819, 8-9=-763/2783, 6-8=-764/2805
WEBS	3-11=-13/471, 3-9=-447/1492, 4-9=-827/450, 5-9=-457/1527, 5-8=-13/470

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x3 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 4-6-0, Exterior(2R) 4-6-0 to 11-6-14, Interior (1) 11-6-14 to 16-6-0, Exterior(2E) 16-6-0 to 21-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SPF No.2 crushing capacity of 425 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 432 lb uplift at joint 2 and 438 lb uplift at joint 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Left Hand Hip) or equivalent at 4-6-6 from the left end to connect truss(es) to front face of bottom chord.
- Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Right Hand Hip) or equivalent at 16-5-10 from the left end to connect truss(es) to front face of bottom chord.
- Fill all nail holes where hanger is in contact with lumber.
- "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (lb/ft)

Vert: 1-3=-70, 3-5=-70, 5-7=-70, 2-6=-20

Concentrated Loads (lb)

Vert: 3=-79 (F), 5=-79 (F), 11=-263 (F), 9=-24 (F), 4=-79 (F), 8=-263 (F), 13=-79 (F), 14=-79 (F), 17=-79 (F), 18=-79 (F), 20=-24 (F), 21=-24 (F), 22=-24 (F), 23=-24 (F)



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of the design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com




Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79	RELEASE FOR CONSTRUCTION
P240671-01	V1	Valley	1	1	Job Reference (optional)	AS NOTED FOR PLAN REVIEW
						DEVELOPMENT SERVICES
						166610420
						LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:19 Page: 1

ID:3zT4jVig0TgS0zKJbRxMtuz0OYB-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi734zJC?F

07/26/2024



Scale = 1:36.6

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.37	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.20	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	5	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S						Weight: 64 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 1=19-5-3, 5=19-5-3, 6=19-5-3, 7=19-5-3, 9=19-5-3
Max Horiz 1=71 (LC 16)
Max Uplift 1=-19 (LC 12), 5=-31 (LC 13), 6=-154 (LC 13), 9=-154 (LC 12)
Max Grav 1=189 (LC 1), 5=189 (LC 1), 6=500 (LC 26), 7=250 (LC 1), 9=500 (LC 25)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-88/79, 2-3=-90/118, 3-4=-90/114, 4-5=-66/64

BOT CHORD 1-9=-11/56, 7-9=-11/56, 6-7=-11/56, 5-6=-11/56

WEBS 3-7=-195/30, 2-9=-381/231, 4-6=-381/231

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-9-1 to 5-9-3, Interior (1) 5-9-3 to 9-9-3, Exterior(2R) 9-9-3 to 14-9-3, Interior (1) 14-9-3 to 18-9-6 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- 4) Gable requires continuous bottom chord bearing.
- 5) Gable studs spaced at 4-0-0 oc.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 8) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 1, 31 lb uplift at joint 5, 154 lb uplift at joint 9 and 154 lb uplift at joint 6.
- 10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	LG01	Lay-In Gable	1	1	Job Reference (optional)

AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
166610422
LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:19
ID:ljrSGQAeiloLuci5CzhomJz0Oa9-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWCD0i7J423C7

07/26/2024



Scale = 1:43.1

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.07	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.04	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.09	Horiz(TL)	0.00	7	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S						Weight: 55 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 1=11-9-5, 7=11-9-5, 8=11-9-5,
9=11-9-5, 10=11-9-5, 11=11-9-5,
12=11-9-5
Max Horiz 1=-173 (LC 8)
Max Uplift 1=-58 (LC 10), 7=-33 (LC 11),
8=-145 (LC 13), 9=-142 (LC 13),
11=-143 (LC 12), 12=-144 (LC 12)
Max Grav 1=148 (LC 21), 7=136 (LC 22),
8=210 (LC 20), 9=214 (LC 20),
10=141 (LC 22), 11=216 (LC 19),
12=210 (LC 19)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-218/139, 2-3=-137/89, 3-4=-130/119,
4-5=-130/114, 5-6=-111/55, 6-7=-196/135
BOT CHORD 1-12=-108/161, 11-12=-109/161,
10-11=-109/161, 9-10=-109/161,
8-9=-109/161, 7-8=-108/161
WEBS 2-12=-199/162, 3-11=-201/168,
4-10=-102/62, 5-9=-201/167, 6-8=-199/163

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) 0-4-0 to 5-4-0,
Interior (1) 5-4-0 to 5-10-14, Exterior(2R) 5-10-14 to
10-10-14, Interior (1) 10-10-14 to 11-5-13 zone;
cantilever left and right exposed ; end vertical left and
right exposed;C-C for members and forces & MWFRS
for reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss
only. For studs exposed to wind (normal to the face),
see Standard Industry Gable End Details as applicable,
or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 1.5x4 MT20 unless otherwise indicated.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 2-0-0 oc.
- 7) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 8) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members.
- 9) All bearings are assumed to be SP No.2 crushing
capacity of 565 psi.
- 10) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 58 lb uplift at joint
1, 33 lb uplift at joint 7, 144 lb uplift at joint 12, 143 lb
uplift at joint 11, 142 lb uplift at joint 9 and 145 lb uplift at
joint 8.
- 11) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com

Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	V3	Valley	1	1	Job Reference (optional)


AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
166610423
LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:19 Page: 1

ID:3zT4jVig0TgS0zKJbRxMtuZ0OYB-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi734zJC?F

07/26/2024



Scale = 1:29.8

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.42	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.25	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.07	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 35 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 1=11-5-3, 3=11-5-3, 4=11-5-3
Max Horiz 1=40 (LC 12)
Max Uplift 1=-49 (LC 12), 3=-56 (LC 13), 4=-43 (LC 12)
Max Grav 1=207 (LC 25), 3=207 (LC 26), 4=496 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-106/64, 2-3=-106/70
BOT CHORD 1-4=-3/43, 3-4=-3/43
WEBS 2-4=-345/234

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 49 lb uplift at joint 1, 56 lb uplift at joint 3 and 43 lb uplift at joint 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	V4	Valley	1	1	Job Reference (optional)

AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
166610424
LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:19 Page: 1
ID:3zT4jVig0TgS0zKJbRxMtuZ0OYB-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDol734zJC?F

07/26/2024



Scale = 1:25.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.19	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.09	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 22 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 1=7-5-3, 3=7-5-3, 4=7-5-3
Max Horiz 1=24 (LC 12)
Max Uplift 1=-36 (LC 12), 3=-40 (LC 13), 4=-13 (LC 12)
Max Grav 1=137 (LC 1), 3=137 (LC 1), 4=269 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-55/43, 2-3=-55/48
BOT CHORD 1-4=-1/24, 3-4=-1/24
WEBS 2-4=-193/164

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 4-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 36 lb uplift at joint 1, 40 lb uplift at joint 3 and 13 lb uplift at joint 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	CG1	Diagonal Hip Girder	2	1	Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
166610425
LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:15 Page: 1
ID:OUW8fuvrt?1SFD0twMHetgz0OaV-RfC?PsB70Hq3NSgPqnL8w3ulTXbGtWwCDol734zJC7f

07/26/2024



Scale = 1:38.5

Plate Offsets (X, Y): [2:0-2-6,0-0-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.94	Vert(LL)	-0.08	2-5	>867	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.53	Vert(CT)	-0.17	2-5	>433	180		
BCLL	0.0*	Rep Stress Incr	NO	WB	0.00	Horz(CT)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 27 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 3-1-15

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-7-0, 5= Mechanical
Max Horiz 2=102 (LC 9)
Max Uplift 2=-116 (LC 8), 5=-67 (LC 12)
Max Grav 2=371 (LC 1), 5=267 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/0, 2-4=-133/79, 4-5=-206/266
BOT CHORD 2-5=-45/49

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Corner (3) -1-2-14 to 5-10-0,
Exterior(2R) 5-10-0 to 6-1-10 zone; cantilever left and
right exposed; end vertical left and right exposed; C-C
for members and forces & MWFRS for reactions shown;
Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members.
- 4) Bearings are assumed to be: Joint 2 SP No.2 crushing
capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.

- 6) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 67 lb uplift at joint
5 and 116 lb uplift at joint 2.
- 7) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.
- 8) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails
per NDS guidelines.
- 9) In the LOAD CASE(S) section, loads applied to the face
of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15,
Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-70, 2-5=-20



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com


Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79
P240671-01	J1	Jack-Open	7	1	Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
166610426
LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:19 Page: 1
ID:a3dRq1dPlw7j?hlS31NFRqz0Oas-RfC?PsB70Hq3NSgPqnL8w3uITXbGK?WvCDoi734zJC?F

07/26/2024



Scale = 1:28.5

Plate Offsets (X, Y): [2:0-1-8,0-0-3]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.41	Vert(LL)	-0.02	2-5	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.24	Vert(CT)	-0.05	2-5	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.01	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 19 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
SLIDER Left 2x4 SP No.2 -- 2-5-8

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-6-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-5-8, 4= Mechanical, 5= Mechanical
Max Horiz 2=97 (LC 12)
Max Uplift 2=-44 (LC 12), 4=-92 (LC 12)
Max Grav 2=267 (LC 1), 4=149 (LC 1), 5=89 (LC 3)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/0, 2-4=-90/49
BOT CHORD 2-5=0/0

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8,
Interior (1) 4-1-8 to 4-5-4 zone; cantilever left and right
exposed; end vertical left and right exposed; C-C for
members and forces & MWFRS for reactions shown;
Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf
on the bottom chord in all areas where a rectangle
3-06-00 tall by 2-00-00 wide will fit between the bottom
chord and any other members.
- 4) Bearings are assumed to be: , Joint 2 SP No.2 crushing
capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.

- 6) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 92 lb uplift at joint
4 and 44 lb uplift at joint 2.
- 7) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



July 3, 2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083.

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:05:13 Page: 1
ID: 3zT4jVig0TgS0zKJbRxMtuz0OYB-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi734zJC?F

Scale = 1:22.1

WARNING – Verify design parameters and READ NOTES ON THIS and INCLUDED MITER REFERENCE PAGE MP17475 Rev. 12/2023 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Components Association (www.sbcscomponents.com)

MiTek®
16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-IIS.com


Job	Truss	Truss Type	Qty	Ply	Roof - HR Lot 79	RELEASE FOR CONSTRUCTION
P240671-01	J2	Jack-Open	4	1	Job Reference (optional)	AS NOTED FOR PLAN REVIEW
						DEVELOPMENT SERVICES
						166610428
						LEE'S SUMMIT, MISSOURI

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Jun 17 2024 Print: 8.630 S Jun 17 2024 MiTek Industries, Inc. Mon Jul 01 15:07:19 Page: 1

ID:pogrrj6k3AhGRa4xA5Q1MJz0Oaj-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwVrCDoi7J44JC?r

07/26/2024



Scale = 1:27.1									
Plate Offsets (X, Y): [2:0-1-8,0-0-3]									
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	L/d
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.10	Vert(LL)	0.00	2-5	>999
TCDL	10.0	Lumber DOL	1.15	BC	0.06	Vert(CT)	0.00	2-5	>999
BCLL	0.0*	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	4	n/a
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P					
								PLATES	GRIP
								MT20	244/190
								Weight: 11 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
SLIDER Left 2x4 SP No.2 -- 1-5-9

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-4-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-5-8, 4= Mechanical, 5= Mechanical
Max Horiz 2=59 (LC 12)
Max Uplift 2=-33 (LC 12), 4=-50 (LC 12)
Max Grav 2=178 (LC 1), 4=71 (LC 1), 5=47 (LC 3)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/0, 2-4=-57/26
BOT CHORD 2-5=0/0

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - 4) Bearings are assumed to be: , Joint 2 SP No.2 crushing capacity of 565 psi.
 - 5) Refer to girder(s) for truss to truss connections.

- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 50 lb uplift at joint 4 and 33 lb uplift at joint 2.
 - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard



July 3,2024

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)


MiTek®

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200 / MiTek-US.com

Symbols

PLATE LOCATION AND ORIENTATION

Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in MITek software or upon request.

PLATE SIZE

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.


4 X 4

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:
ANSI/TP1.1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)

1 2 3 Joint ID typ.



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved



MITek Engineering Reference Sheet: MIL-7473 rev. 1/12/2023

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.