

A New Building For:



900 NE Colburn Rd
Lee's Summit, MO.

DRAWING SCHEDULE

COVER

ARCHITECTURAL

A0.0 - CODE REVIEW
A0.1 - ADA GUIDELINES
A100 - FLOOR PLAN / NOTES / WALL TYPES
A101 - INTERIOR ELEVATIONS / ENLARGED TOILET PLANS / DETAILS
A101.1 - INTERIOR ELEVATIONS
A102 - REFLECTED CEILING PLAN / DETAILS
A103 - ROOF PLAN / DETAILS
A200 - EXTERIOR ELEVATIONS
A201 - CANOPY ELEVATIONS
A300 - BUILDING SECTIONS / DETAILS
A301 - WALL SECTIONS
A302 - WALL SECTIONS
A303 - TRASH ENCLOSURE PLAN AND MONUMENT SIGN / ELEVATIONS / SECTION / DETAILS
A400 - SCHEDULES / DETAILS



STRUCTURAL

S001 STRUCTURAL NOTES
S100 - FOUNDATION PLAN
S200 - FRAMING PLAN
S300 - FOUNDATION AND MASONRY DETAILS
S400 - FRAMING DETAILS

MEP

MP00 - MECHANICAL AND PLUMBING SPEC'S
P100 - PLUMBING WASTE AND VENT
P101 - PLUMBING WATER AND GAS
P200 - PLUMBING SCHEDULE AND DETAIL
P201 - PLUMBING RISER DIAGRAMS

M100 - MECHANICAL FLOOR PLAN
M101 - SCHEDULES / DETAILS / NOTES
M200 - CAPTIVE AIRE HOOD
M201 - CAPTIVE AIRE HOOD
M202 - CAPTIVE AIRE HOOD
M203 - CAPTIVE AIRE HOOD
M204 - CAPTIVE AIRE HOOD

E000 - ELECTRICAL SPECS
E101 - ELECTRICAL LIGHTING PLAN
E102 - ELECTRICAL POWER PLAN
E103 - ELECTRICAL POWER PLAN
E201 - ELECTRICAL RISER DIAGRAM & FAULT CALC'S
E202 - ELECTRICAL SCHEDULES
E301 - ELECTRICAL SITE PLAN

ARCHITECT



24 NW CHIPMAN "B"
LEE'S SUMMIT, MO. 64063
PHONE: (816) 536-3472

DESIGN / BUILD CONTRACTOR



17211 E 199th St,
Pleasant Hill, MO 64080

STRUCTURAL ENGINEER



J & S STRUCTURAL ENGINEERS
15185 LOWELL AVE
OVERLAND PARK, KS 66223
913-549-4701

MEP ENGINEER




5720 Reeder St, Shawnee, KS 66203
Phone: (913) 262-1772

GENERAL NOTES

- ALL CONSTRUCTION WORK SHALL BE IN ACCORDANCE WITH THE INCLUDED DRAWINGS.
 - ALL CONSTRUCTION WORK SHALL COMPLY WITH GOVERNING BUILDING CODES IN EFFECT AT THE TIME CONSTRUCTION PERMITS ARE ISSUED FOR THIS PROJECT.
 - SUB-CONTRACTORS SHALL FIELD VERIFY ALL DIMENSIONS SHOWN, AND SHALL REPORT ANY DISCREPANCY TO THE ENGINEER PRIOR TO COMMENCING WITH ANY RELATED CONSTRUCTION WORK. SUB-CONTRACTORS SHALL FURTHER REPORT TO THE ENGINEER ALL DISCREPANCIES BETWEEN ACTUAL AND SHOWN CONDITIONS, PRIOR TO BEGINNING WORK RELATED THERETO.
 - DIMENSIONS ARE TO FACE OF FINISH WALL UNLESS NOTED OTHERWISE.
 - THE SUB-CONTRACTORS SHALL VERIFY LOCATION OF EXISTING UTILITIES, AND SHALL BE RESPONSIBLE FOR PROTECTING THESE UTILITIES DURING THE EXECUTION OF HIS WORK AND RELOCATION.
 - SUB-CONTRACTOR TO LAY OUT BUILDING PRIOR TO ANY CONSTRUCTION. NOTIFY ENGINEER OF ANY DISCREPANCY IMMEDIATELY.
 - SUB-CONTRACTOR TO ASSURE PROPER DRAINAGE AWAY FROM BUILDING.
 - THE SUB-CONTRACTORS SHALL BE SOLELY RESPONSIBLE FOR THE DESIGN, ADEQUACY, AND SAFETY OF ERECTION BRACING, SHORING AND TEMPORARY SUPPORTS, ETC. THE SUB-CONTRACTORS ARE RESPONSIBLE FOR THE STABILITY OF THE STRUCTURE PRIOR TO THE APPLICATION OF ALL SHEAR WALLS, ROOF SHEATHING, STRUCTURAL ELEMENTS AND FINISH MATERIALS.
 - THE SUB-CONTRACTORS ARE RESPONSIBLE FOR CHECKING ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSION FOR THEIR ACCURACY AND CONFIRMING THAT WORK IS BUILDABLE AS SHOWN BEFORE PROCEEDING WITH CONSTRUCTION. IF THERE ARE ANY QUESTIONS REGARDING THESE OR OTHER COORDINATION QUESTIONS, THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING CLARIFICATION FROM THE ENGINEER BEFORE PROCEEDING WITH THE WORK IN QUESTION OR ANY RELATED WORK.
- THE SUB-CONTRACTORS SHALL TAKE ABSOLUTE CARE TO PROTECT NEWLY INSTALLED MATERIALS, MILLWORK, BUILT-INS AND FINISHES.
- THE SUB-CONTRACTORS SHALL BE RESPONSIBLE FOR ALL DAMAGE TO EXISTING STRUCTURES, UTILITIES, WALKS, STREETS, PAVED AREAS, CURBS, TREES AND OTHER LANDSCAPING CAUSED THROUGH HIS OPERATIONS UNDER THIS CONTRACT.
- THE SUB-CONTRACTORS SHALL PERFORM HIGH QUALITY PROFESSIONAL WORK. JOIN MATERIALS TO UNIFORM, ACCURATE FITS SO THEY MEET WITH NEAT, STRAIGHT LINES, FREE OF SHEARS OR OVERLAPS. INSTALL EXPOSED MATERIALS APPROPRIATELY LEVEL, PLUMB AND AT ACCURATE RIGHT ANGLES OR FLUSH WITH ADJOINING MATERIALS. WORK OF EACH TRADE SHALL MEET ALL NATIONAL STANDARDS PUBLISHED BY THAT TRADE, EXCEPT IN THE CASE WHERE THE CONTRACT DOCUMENTS ARE MORE STRINGENT.

ABBREVIATIONS

A/C	AIR CONDITIONING	EA	EACH	JB	JUNCTION BOX	RM	ROOM
AB	ANCHOR BOLT	EJ	EXPANSION JOINT	JST	JOIST	RO	ROUGH OPENING
AC	ACCOUSTICAL	ELEG	ELECTRIC/ELECTRICAL	JT	JOINT	ROW	RIGHT OF WAY
ACT	ACCOUSTICAL TILE	EL	ELEVATION	L	LENGTH	RTU	ROOF TOP UNIT
AFF	ABOVE FINISHED FLOOR	EMERG	EMERGENCY ENCLOSURE	LAV	LAVATORY	RV	ROOF VENT
AGG	AGGREGATE	ENT	ENTRANCE	LT	LIGHT	SCHED	SCHEDULE
ALT	ALTERNATE	EP	ELECTRICAL PANEL	LVL	LEVEL	SECT	SECTION
ALUM	ALUMINUM	EQ	EQUAL	MAS	MASONRY	SF	SQUARE FEET
AND	AND	EQUIP	EQUIPMENT	MAX	MAXIMUM	SHT	SHEET
APPROX	APPROXIMATELY	EX	EACH WAY	MECH	MECHANICAL	SIM	SIMILAR
ARCH	ARCHITECTURAL	EXH	EXHAUST	MEMB	MEMBRANE	SPEC	SPECIFICATION
ASPH	ASPHALT	EXP	EXPANSION	MTL	METAL	SPK	SPEAKER
AVG	AVERAGE	EXT	EXTERIOR	MFG	MANUFACTURER	SQ	SQUARE
BD	BOARD	FD	FLOOR DRAIN	MISG	MISCELLANEOUS	SST	STAINLESS STEEL
B.F.F.	BELOW FINISHED FLOOR	FDN	FOUNDATION	MO	MASONRY OPENING	STD	STANDARD
BIT	BITUMINIOUS	FFE	FINISHED FLOOR ELEVATION	NIC	NOT IN CONTRACT	STL	STEEL
BKR	BREAKER	FLR	FLOOR	NOM	NOMINAL	STRUC	STRUCTURAL
BLDG	BUILDING	FLR	FLOOR	NTS	NOT TO SCALE	SUP	SUPPLY
BM	BEAM	FLASH	FLASHING	OA	OVERALL	SUSP	SUSPEND
BRG	BEARING	FLOUR	FLOURSCENT	OC	ON CENTER	TEMP	TEMPORARY
BTU	BRITISH THERMAL UNIT	FOS	FACE OF STUD	OD	OUTSIDE DIAMETER	THK	THICK
		FRM	FRAME	OFF	OFFICE	THRES	THRESHOLD
		FIBERGLASS	FIBERGLASS	OPNG	OPENING	TYP	TYPICAL
CCT	CIRCUIT	FT	FOOT	P	POLE	UC	UNDERCUT
CEM	CEMENT	FTG	FOOTING	PL	PLATE	UL	UNDERWRITER
CFM	CUBIC FEET/MINUTE	FUR	FURRING	PLG	PLUMBING	UNO	UNLESS NOTED OTHERWISE
CJ	CONTROL JOINT	GA	GAUGE	PLYWD	PLYWOOD	UR	URINAL
CLS	CELLING	GAL	GALLON	PNL	PANEL	UTIL	UTILITIES
CLR	CLEAR	GALV	GALVANIZED	PR	PAIR	VB	VOLT
CMU	CONCRETE MASONRY UNIT	GEN	GENERAL	PREFAB	PREFABRICATED	VERT	VERTICLE
CNDT	CONDUIT	GRD	GROUND	PSF	POUNDS/SQUARE FOOT	VEST	VESTIBULE
CO	CLEAN OUT	GYP	GYPSUM	PT	POUNDS/SQUARE INCH	VOL	VOLUME
COL	COLUMN	HDR	HOSE BIBB	PVC	POLYVINYL CHLORIDE	VTR	VENT THROUGH ROOF
CONC	CONCRETE	HDNR	HARDWARE	QT	QUARRY TILE	W/	WITH
COND	CONDENSATE	HGT	HEIGHT	R	RADIUS	WC	WATER CLOSET
CONN	CONNECTION	HORZ	HORIZONTAL	RSR	RISER	WD	WOOD
CONST	CONSTRUCTION	HP	HORSE POWER	R/A	RETURN AIR	WDR	WINDROW
CONT	CONTINUOUS	HR	HOUR	RCPT	RECEPTACLE	WH	WATER HEATER
CT	CERAMIC TILE	HTG	HEATING	RD	ROOF DRAIN	WP	WATER PROOFING
CM	GOLD WATER	HTR	HEATER	REG	REGRESSED	WPGCT	WAINSCOT
DBL	DOUBLE	ID	INSIDE DIAMETER	REF	REFERENCE	WT	WEIGHT
DEPT	DEPARTMENT	IN	INCHES	REG	REGISTER	WWF	WELDED WIRE FABRIC
DIA	DIAMETER	INSUL	INSULATION	REQD	REQUIRED	YD	YARD
DIM	DIMENSION	INT	INTERIOR	RFG	ROOFING		
DISC	DISCONNECT						
DN	DOWN						
DR	DOOR						
DS	DOWNSPOUT						
DTL	DETAIL						
DWG	DRAWING						
DWL	DOWNEL						



PROJECT CODE DATA CHART

- A) TYPE OF OCCUPANCY: GROUP: M (309 IBC 2018)
OCCUPANT LOAD 52 (SEE PLAN FOR CALCULATIONS):
- B) TYPE OF CONSTRUCTION: BUILDING TYPE VB, UNPROTECTED, BUILDING IS NON SPRINKLED
- C) CODE REFERENCES:
1. INTERNATIONAL BUILDING CODE - 2018 EDITION
 2. INTERNATIONAL PLUMBING CODE - 2018 EDITION
 3. INTERNATIONAL MECHANICAL CODE - 2018 EDITION
 4. INTERNATIONAL FIRE GAS CODE - 2018 EDITION
 5. INTERNATIONAL FIRE PREVENTION CODE - 2018 EDITION
 6. NATIONAL ELECTRICAL CODE - 2017 EDITION
 7. INTERNATIONAL FIRE CODE - 2018 EDITION
 8. AMERICAN NATIONAL STANDARD ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES (ANSI A117.1-2009)

D) HEIGHT AND AREA CALCULATIONS: TABLES 503.3, 504.4, 506.2

GROUP: M
AREA: ALLOWED: 9,000
ACTUAL AREA: 6,000 SQUARE FEET.
HEIGHT ALLOWABLE: 1 STORY; 40'
HEIGHT ACTUAL: 1 STORY; 24'-4"
HEIGHT STORIES: 1 STORY
HEIGHT ACTUAL: 1 STORY

E) MINIMUM FIRE RESISTANCE RATING REQUIREMENTS FOR BUILDING ELEMENTS

FIRE RATINGS OF STRUCTURAL ELEMENTS PER IBC TABLE 601: TYPE II B	
ELEMENTS	FIRE RATING REQUIRED
STRUCTURAL FRAME	0
BEARING WALLS	0
EXTERIOR	0
INTERIOR	0
NONBEARING EXT. WALLS	0
NONBEARING INT. WALLS	0
FLOOR CONSTRUCTION	0
ROOF CONSTRUCTION	0

F) PLUMBING FIXTURE REQUIREMENTS: CHAPTER 29

OCCUPANT LOAD: 52		WATER CLOSETS		REQUIRED	PROVIDED
26 FEMALE:	1 PER 500	1	2		
26 MALE:	1 PER 500	1	1		1 TOILET 1 URINAL
		LAVATORIES		REQUIRED	PROVIDED
26 FEMALE:	1 PER 750	1	2		
26 MALE:	1 PER 750	1	2		

(1) MOP SINKS PROVIDED

1 Code Plan
SCALE: 3/16"=1'



Construction Documents for:

HEARTLAND MARKET

900 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT,
ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23



REVISIONS:


ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

A0.0


Craig Luebbert
Architecture






2 ACCESSIBLE MOUNTING HEIGHTS AT TOILET ACCESSORIES

SCALE: 1/4" = 1'-0"




4 SIGNAGE

SCALE: 1/4" = 1'-0"



5 ACCESSIBLE FIRE EXTINGUISHER AND CABINET MOUNTING HEIGHT


SCALE: 1/4" = 1'-0"



6 ACCESSIBLE MOUNTING HEIGHTS AT CONTROLS AND OUTLETS


SCALE: 1/4" = 1'-0"

NOTE:
1. A 30"x48" CLEAR FLOOR SPACE AREA SHALL BE PROVIDED PERPENDICULAR TO THE WALL FOR A FORWARD REACH TO CONTROLS AND ACCESSIBLE OUTLETS.
2. ELECTRICAL OUTLETS ON WALLS OVER CABINETS MUST BE A MINIMUM 36" FROM A CORNER.



7 SIZE OF TURNING SPACE



SCALE: N.T.S.



8 CLEAR FLOOR SPACE


SCALE: N.T.S.

NOTE: X SHALL BE < 25"; Z SHALL BE > X, WHEN X ≤ 20", THEN Y SHALL BE 48" MAX. WHEN X IS ≥ 20" - 25", THEN Y SHALL BE 44" MAX.




9 PROTRUDING OBJECTS

SCALE: N.T.S.



1 MINIMUM ACCESSIBLE TOILET ROOMS

SCALE: 1/4" = 1'-0"



3 CHANGES IN LEVEL

SCALE: N.T.S.

GENERAL ACCESSIBILITY NOTES

1. DRAWINGS ON THIS SHEET ARE INTERPRETATIONS BASED UPON:
 - 1.1. AMERICAN NATIONAL STANDARD ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES (ICC/ANSI A117.1-2009) AS PUBLISHED BY INTERNATIONAL CODE COUNCIL IN MAY, 2004.
 - 1.2. INTERNATIONAL BUILDING CODE 2003 AS PUBLISHED BY INTERNATIONAL CODE COUNCIL IN JANUARY 2004
 - 1.3. AMERICANS WITH DISABILITIES ACT (ADA) ACCESSIBILITY GUIDELINES FOR BUILDINGS AND FACILITIES (ADAAG) AS PUBLISHED BY U.S. ARCHITECTURAL AND TRANSPORTATION BARRIERS COMPLIANCE BOARD (ACCESS BOARD)
2. THIS SHEET IS NOT INCLUSIVE OF ALL ACCESSIBILITY REQUIREMENTS BY ANY JURISDICTION AND IS NOT INTENDED TO REPLACE OR ALTER ANY CODIFIED REQUIREMENTS BY ANY JURISDICTION.
3. ACCESSIBILITY REQUIREMENTS SHALL BE MET IN ACCORDANCE WITH ANY AND ALL FEDERAL AND STATE, LOCAL AND OTHER MUNICIPAL JURISDICTIONS.
4. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND REPORT ANY CONFLICTS AND DISCREPANCIES TO ARCHITECT.
5. WALKWAYS WILL HAVE A SLOPE NO STEEPER THAN 1 : 20.
6. FLAT SURFACES SHALL HAVE A SLOPE NO STEEPER THAN 1 : 48 AT WET LOCATIONS.
7. PROVIDE NON-SLIP FLOOR SURFACES AT ALL WET LOCATIONS.
8. OPERABLE AND DISPENSING HEIGHTS SHALL BE 15" MINIMUM AND 44" MAXIMUM ABOVE FINISHED FLOOR UNLESS OTHERWISE REQUIRED AS DEFINED BY LOCAL AUTHORITY.
9. ALL FIXTURES AND ACCESSORIES SHALL BE INSTALLED PER MANUFACTURER'S INSTALLATION INSTRUCTIONS TO MEET ACCESSIBILITY REQUIREMENTS.
10. GRAB BARS SHALL NOT ROTATE WITHIN THEIR FITTINGS.
11. HANGING FIXTURES AND ACCESSORIES SHALL HAVE WALL BLOCKING TO MEET MINIMUM FORCE REQUIREMENTS.
12. EXPOSED PIPING AT LAVATORIES SHALL BE INSULATED. NO SHARP OR ABRASIVE SURFACES SHALL BE ALLOWED.
13. PROVIDE SOAP AND HAND TOWEL DISPENSERS AT ALL HAND WASHING LOCATIONS.
14. SEE DRAWINGS FOR ACTUAL FIXTURE AND ACCESSORY LOCATIONS.

Construction Documents for:

HEARTLAND MARKET

900 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23



REVISIONS:


ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

A0.1

Craig Luebert
Architecture





1 Floor Plan
SCALE: 3/16"=1'



NOTE: ALL DIMENSIONS ARE FROM FACE OF MASONRY BLOCK TO FACE OF STUD UNLESS SHOWN OTHERWISE.

CJ - CONTROL JOINT PER INDUSTRY STANDARDS, PROVIDE BACKER ROD AND CAULK TYP.

WALL TYPES

- A** 8" CMU BLOCK WALL W/ 3 5/8" MTL. STUDS @ 16" O.C. 5/8" GYP. BD. BATT INSULATION
- B** 3 5/8" MTL. STUDS W/ GYP. BD BOTH SIDES. EXTEND WALL TO B.O. OF TRUSSES. GYP. BD. TO B.O. TRUSSES (1) SIDE ONLY
- C** (2) 3 5/8" MTL. STUDS @ 16" O.C. PLUMBING WALL FACE OF STUD TO FACE OF STUD IS 8"
- D** 3 5/8" MTL. STUDS W/ GYP. BD BOTH SIDES. EXTEND WALL 4" ABOVE CEILING PROVIDE KICKER STUDS TO STRUCT AS REQUIRED


PLAN NOTES

- NOTE NOT USED
- PROVIDE 1" BETWEEN COOLER AND WALL
- COOLERS / FREEZERS SHALL MEET UL RATINGS AND CONFORMANCE WITH IBC 2018. WALK-IN COOLER SHALL CONFORM TO 2803.4 THERMAL BARRIER AND 2803.4.1.3 WALK-IN COOLERS IN NON-SPRINKLERED BUILDINGS.
- PROVIDE 2" RIGID INSUL. UNDER SLAB W/ 15 mil VAPOR BARRIER AT COOLERS AND FREEZER- INDICATED BY HATCH - FLOORS TO BE SEALED CONCRETE
- STEEL ROOF ACCESS LADDER SEE DETAIL SIA104
- SHELVING / FIXTURES BY OWNER
- FLOOR DRAIN
- 4" DIA. x 6'-6" TALL PIPE BOLLARD FILL W/ CONC. - 3'-6" FROM FIN. GRADE TO TOP OF BOLLARD TYP OF 23 IN FRONT OF BUILDING AND ON EAST SIDE
- PROVIDE STAINLESS STEEL BEHIND HOOD FROM FIN. FLOOR TO B.O. OF HOOD
- SOUND BATT INSULATE WALLS SURROUNDING TOILET ROOMS
- APPLY 1/2" GYP. BD. ON COOLER WALL - TYPICAL
- WALL ABOVE COOLER TO EXTEND TO B.O. OF ROOF DECKING W/ GYP. BD. ON BOTH SIDES
- 4" REINF. CONCRETE SLAB - G.C. TO VERIFY SIZE
- CHAIN LINK FENCE W/ GATE. SECURE TO FLOOR


EQUIPMENT LIST

G.C. TO VERIFY ALL EQUIPMENT W/ OWNER

- | | | |
|--|---|---|
| 01 SURE IMMERSION 312 FILTER STYLE COFFEE SYST. | 18 NEWCO - LEMONADE DISPENSER | 37 OUTDOOR CO2 TANK |
| 02 KAN PAK REFRIGERATED LIQUID DISPENSER (CREAMER) | 19 CORNELIUS - VIPER 4 FLAVOR FROZEN DISPENSER | 38 HOOD - REF MECHANICAL DRAWINGS. PROVIDE STAINLESS STEEL FROM B.O. OF HOOD TO FLOOR |
| 03 3-BURN DUAL SOFT HEAT COFFEE BREWER - SH-DBC-(3) | 20 Bunn ULTRA-2 HP Ultra Goumet Ice Frozen Drink Machine | 39 ATM |
| 04 CURTIS PRIMO CAPPUCCINO DISPENSING SYSTEMS - PCGT5 (2) | 21 HATCO ROUND WAFFLE MAKER - RWIM-2 | |
| 05 ICED TEA BREWING SYSTEM - TCT'S10600 | 22 RESFAB HOT FOOD CASE (CHICKEN) KK-4P | |
| 06 NEWCO ICED COFFE MACHINE - 736661 | 23 LOTTERY EQUIPMENT | |
| 07 BEVERAGE SOLUTIONS GROUP - CREAMER AND SUGAR STATION | 24 NEMCO COUNTER TOP WARMER 6055A-43 | |
| 08 ROYSTON DONUT CASE 60101610 | 25 MICALI PIZZA PREP TABLE - C-PP4HC | |
| 09 FEDERAL REFRIGERATED SELF-SERVE ISLAND. PROVIDE ELEC IN FLOOR - VERIFY LOCATION WITH MANUF. | 26 CADCO HEAVY DUTY COUNTERTOP CONVECTION OVEN | |
| 10 RESFAB FRYERS - (2) | 27 AVANTCO COUNTERTOP GRIDDLE | |
| 11 LINCOLN ELECTRIC OVEN (2) STACKED | 28 SHARP MICROWAVE OVEN R-21LCS | |
| 12 OUTDOOR GREASE TANK - 1,400 LB CAPACITY | 29 AVANTCO WORKTOP FREEZER SSINT | |
| 13 REGENCY (3) COMPARTMENT SINK WITH 2 DRAINBOARDS | 30 FREAL BLENDER | |
| 14 FEDERAL REFRIGERATED SELF-SERVE MERCHANDISER | 31 NEMCO DUAL SHELF MERCHANDISER - 6480-36S | |
| 15 GEHL'S MACHO DISPENSER (2) | 32 NEMCO DUAL SHELF MERCHANDISER - 648018S-B | |
| 16 LANCER ICE AND BEVERAGE DISPENSER BD 4500-44 - (2) | 33 APW WYOTT HOT ROD ROLLER - HR(S) - 50S W/ SNEEZE GUARD | |
| 17 MULTIPLEX FRESH BLENDER | 34 APW WYOTT BUN WARMER - BMD-75 | |
| | 35 SAMSUNG MICROWAVE MS14K6000AS | |
| | 36 HATCO GLO RAY PIZZA WARMER GRPVIS-3618D | |



Craig Luebbert
Architecture




Construction Documents for:
HEARTLAND MARKET
900 NE Colbern Rd.
Lee's Summit, MO.


COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A. Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:	7.14.23
REVISIONS:	
ARCHITECTURAL PROJECT NUMBER	


SHEET NUMBER
A101



8 Fountain Disp. Cabinet - Drive Thru 110
SCALE: 3/8" = 1'



7 POS Cabinet - Drive Thru 110
SCALE: 3/8" = 1'




2 Vanity Detail
SCALE: 1 1/2" = 1'





TOILET ACCESSORIES

ALL WASH-ROOM ACCESSORIES INSTALL PER MANUFACTURERS RECOMMENDATIONS AND PER ANSI A117.1-2009 AND LOCAL CODE. SEE SHEET A0.1 FOR FIXTURE / ACCESSORIES MOUNTING HEIGHTS. PROVIDE BLOCKING IN WALLS AS REQUIRED FOR INSTALLATION.


- A GRAB BARS ————— BOBRICK® B-5806x42, B-5806x36, B-5806x18
- B MIRROR ————— BRADLEY 28"X 36"
- C TOILET TISSUE DISPENSER — BOBRICK B-2892 SURFACE MOUNTED
- D SOAP DISPENSER ————— B-818615
- F SANITARY NAPKIN DISPOSAL — B-270
- G CHANGING STATION ————— FOUNTAINS 100 EH BP
- H HAND DRYER ————— ELECTRIC HAND DRYER - XL-SB
- J ADA SIGNS ————— SEE SHEET A0.1




1 Toilet Plan
SCALE: 1/4" = 1'




3 Toilet Elevations
SCALE: 3/8" = 1'



5 North Wall Cooler Elevation
SCALE: 3/8" = 1'



4 Cashier Elevation
SCALE: 3/8" = 1'



5A North Wall Cooler Elevation Cont'd
SCALE: 3/8" = 1'

1 East Wall Cooler / Freezer Elevation

SCALE: 3/8"=1'

Craig Luebbert
Architecture

C

L

A

Construction Documents for:

HEARTLAND MARKET

900 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.


DATE ISSUED:
7.14.23

REVISIONS:


ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A101.1




1 Reflected Ceiling Plan
SCALE: 3/16"=1'




6 Soffit Above Beverage Center
SCALE: 1 1/2"=1'




5 Soffit Detail
SCALE: 1 1/2"=1'



4 Bulkhead Detail @ Cooler
SCALE: 1 1/2"=1'



3 Ceiling Grid Detail / Light Attachment
SCALE: nts



2 Ceiling Grid Detail
SCALE: nts



Craig Luebbert
Architecture
CL A

Construction Documents for:

HEARTLAND MARKET

900 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.


DATE ISSUED:
7.14.23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER


SHEET NUMBER

A102




6 Roof Ladder Detail

SCALE: nts




1 Roof Plan

SCALE: 1/8"=1'




7 Roof Drain Detail

SCALE: nts



OVERFLOW LAMBS TONGUE
JOSAM SERIES OR EQUAL CAST BRONZE DOWNSPOUT NOZZLE, LOOSE WALL FLANGE AND INLET THREADED CONNECTION, 4" PIPE SIDE




NOTES:

- REFER TO PLANS FOR PIPE SIZE(S) AND LOCATION(S). USE WELDED OR SCREWED FITTINGS AS SPECIFIED FOR PIPE SIZE. LOCATE PENETRATION MINIMUM 18" FROM ADJACENT WALLS, EQUIPMENT CURBS, PARAPETS, EXPANSION JOINTS, ETCETERA.
- LOCATE SUPPORTS AT THE FOLLOWING SPACING: 1-1/2"=9', 1-1/4"=8', 1"=7' & 3/4"=6'. PROVIDE SUPPORTS AS CLOSE AS POSSIBLE TO EACH ELBOW AND TEE.


4 Pipe on Roof Detail

SCALE: nts



3 Roof Top Curb

SCALE: nts




2 Pipe Penetration


SCALE: nts

5 Roof Scupper & Overflow Drain Detail

SCALE: 1 1/2"=1'



Craig Luebbert
Architecture



Construction Documents for:

HEARTLAND MARKET

900 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.



DATE ISSUED:
7.14.23

REVISIONS:
A CITY COMMENTS - 6.6.22

ARCHITECTURAL PROJECT NUMBER


SHEET NUMBER

A103



6 Stucco Joint

SCALE: NTS




5 Precast Detail

SCALE: 1 1/2"=1'



1 South Elevation

SCALE: 3/16"=1'




3 East Elevation

SCALE: 3/16"=1'


2 West Elevation

SCALE: 3/16"=1'




4 North Elevation

SCALE: 3/16"=1'



Craig Luebbert
Architecture



Construction Documents for:
HEARTLAND MARKET
900 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A. LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A. Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.


DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS - 6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

A200




NOTE: CANOPY STRUCTURE AND FOOTINGS
DESIGNED BY OTHERS


1 Canopy Elevation
SCALE: NTS

Canopy Colors


- CS White (Canopy Deck, Canopy Columns, Store Exterior)**
 - Glidden Professional, Order #A0128, Spec #50GY 83/010, "White Wing"
 - Sherwin Williams, SW7006, "Extra White"
 - Benjamin Moore, OC-67, "Ice Mist" - P28 DTM (Gallon)
 - Anchor Paint, BP White - 4900 (Acrylic), 900 (Oil)
- CS Amoco Red**
 - Sherwin Williams, SW6869, "Stop"
 - Glidden Professional, PPG Amoco Red (Custom Mix)
- CS BP Warm Gray - Pump Islands**
 - Sherwin Williams, SW7053, "Adaptive Shade"
 - Glidden Professional, Order #A1860, Spec #40YY 25/074, "Gray Mountain"
 - Benjamin Moore, 2137-40, "Desert Twilight" - P28 DTM (Gallon)
 - Anchor Paint, BP Warm Gray - CC3068 (Acrylic), CC3115 (Oil)
- CS Amoco Dark Blue**
 - Sherwin Williams - SW6965, "Hyper Blue"
 - Glidden Professional, PPG Amoco Blue (Custom Mix)
- CS Amoco Light Blue**
 - Pantone Process BlueC (C100 M13 Y0 K0)
- CS Amoco Silver**
 - Match PMS 877C



2 Canopy Elevation
SCALE: NTS



Craig Luebbert
Architecture



Construction Documents for:

HEARTLAND MARKET

900 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT,
ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without
express written permission of the Architect. The drawings and
specifications are instruments of service and shall remain the
property of the Craig A Luebbert, Architect, LLC whether the
project for which they are made is executed or not. These
drawings and specifications shall not be used by anyone on
any other project for additions to this project by others except
by the express written permission of the Architect.



DATE ISSUED:
7.14.23

REVISIONS:


ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

A201




1 Cross Section
SCALE: 1/4"=1'



2 Longitudinal Section
SCALE: 1/4"=1'



Craig Luebbert
Architecture



Construction Documents for:

HEARTLAND MARKET

900 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A. Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.



DATE ISSUED:
7.14.23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

A300




09.22.36 (Metal Lath)







*All Dimensions Nominal

Ground	Length	Pcs./Ctn.	Ft./Ctn.	Wt./Ctn.	Ctn./Skid
1/2"	10'	24	240	54 lbs.	27
3/4"	10'	24	240	69 lbs.	30
7/8"	10'	24	240	76 lbs.	30

sto 
Building with conscience.

1)	StoGuard® Air and Water-Resistive Barrier
2)	Code compliant paper or felt Water-Resistive Barrier
3)	Code compliant minimumum 2.5 lbd/yd ² (1.4 kg/m ²) self-furred galvanized steel diamond mesh metal lath
4)	ASTM C926 compliant stucco scratch coat (as manufactured or listed by Sto Corp.)
5)	ASTM C926 compliant stucco brown coat (as manufactured or listed by Sto Corp.)
6)	Sto Primer
7)	<ul style="list-style-type: none"> Sto Textured Finishes

Page 1 of 2



HEARTLAND MARKET

SHEET NUMBER

A303

	DOOR SCHEDULE
--	---------------






ROOM FINISH SCHEDULE

<u>WALLS</u>		<u>FLOORING</u>	
P-1	PRIME WALLS - PROVIDE 2 COAT SATIN PAINT	PT-1	12"X12" PORCELAIN TILE
FRP-1	FIBERGLASS REINFORCED PANELS	SC-1	SEALED CONCRETE
PT-1	PORCELAIN TILE FLOOR TO CEILING		
SS	STAINLESS STEEL BEHIND HOOD FROM FLOOR TO B.O. HOOD		
<u>BASE</u>		<u>CEILINGS</u>	
VB-1	4" HIGH VINYL COVE BASE-BLACK	ACT-1	ACOUSTICAL TILE CEILING - 2 x 2 REGULAR
VB-2	6" HIGH VINYL COVE BASE	ACT-2	VINYL FACED ACOUSTICAL TILE CEILING - 2 x 2
		GYP-1	GYP.BD SOFFIT - 8'-0" AFF

NOTE: TEMPERED GLAZING / SAFETY GLAZING SHALL MEET THE SAFETY GLAZING IN HAZARDOUS LOCATIONS REQUIRED PER IBC 2406 AND IBC 2406.3

Technical drawing of a window unit with the following dimensions and labels:

- Overall width: $6' - 11\frac{1}{2}"$
- Left pane width: $3' - 0"$
- Right pane width: $3' - 11\frac{1}{2}"$
- Overall height: $4' - 11\frac{1}{2}"$
- Left pane height: $3' - \frac{1}{2}"$
- Right pane height: $1' - 4"$
- Labels:
 - AIR CURTAIN (pointing to the right pane)
 - ALUM STORE FRONT SYST. (pointing to the left pane)
 - READY ACCESS AUTOMATIC WINDOW (pointing to the right pane)



900 NE Colbern Rd.
Lee's Summit, MO.

A400

STRUCTURAL NOTES

2012 INTERNATIONAL BUILDING CODE

GENERAL NOTES:

1. DESIGN AND CONSTRUCTION SHALL CONFORM TO THE 2012 INTERNATIONAL BUILDING CODE.
2. THE DRAWINGS REPRESENT THE FINISHED STRUCTURE, NOT THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE NEW STRUCTURE DURING CONSTRUCTION INCLUDING, BUT NOT LIMITED TO, BRACING, SHORING FOR CONSTRUCTION LOADS AND EQUIPMENT, ETC. THE ARCHITECT-ENGINEER IS NOT RESPONSIBLE FOR THE CONTRACTOR'S MEANS AND METHODS, SEQUENCES OF CONSTRUCTION, OR THE SAFETY PROGRAM. OBSERVATION VISITS TO THE SITE BY THE ARCHITECT-ENGINEER WILL NOT INVOLVE REVIEW OF THESE ITEMS.
3. CONTRACTOR IS TO ESTABLISH AND VERIFY OPENINGS AND INSERTS FOR ITEMS TO BE INSTALLED BY OTHER TRADES PRIOR TO SUBMITTAL OF SHOP DRAWINGS AND CONSTRUCTION.
4. CONSTRUCTION MATERIAL AND EQUIPMENT PLACED ON FRAMED CONSTRUCTIONS SHALL BE SUCH THAT THE LOAD DOES NOT EXCEED THE DESIGN LIVE LOAD OF THE CONSTRUCTION. PROVIDE SHORING OF CONSTRUCTIONS WHERE NECESSARY FOR LOADS.
5. DETAILS THAT ARE NOTED AS "TYP." ON DETAIL TITLES ARE TO BE APPLIED TO THE PROJECT CONSTRUCTION AS GENERAL CONSTRUCTION METHODS UNLESS NOTED OTHERWISE. THESE DETAILS ARE NOT CUT AT ALL LOCATIONS THEY OCCUR AND MAY NOT BE CUT AT ALL.
- 6.

DESIGN:

ALL CONSTRUCTION SHALL COMPLY WITH THE FOLLOWING CODES AND STANDARDS, EXCEPT WHERE NOTED TO THE CONTRARY ON DRAWINGS OR WHERE MORE STRINGENT REQUIREMENTS ARE SHOWN.

ACI 117	STANDARD SPECIFICATIONS FOR TOLERANCE FOR CONCRETE CONSTRUCTION AND MATERIALS
ACI 301	SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS.
ACI 318	BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE
AISC	SPECIFICATIONS FOR STRUCTURAL STEEL FOR BUILDINGS
AISI-NAS	NORTH AMERICAN SPECIFICATION FOR THE DESIGN OF COLD-FORMED STEEL STRUCTURAL MEMBERS
AWS D1.1	STRUCTURAL WELDING CODE

DEAD LOADS:

20 PSF ROOF LOAD

LIVE LOADS:

20 PSF ROOF LOAD

SNOW LOADS:

SNOW LOADS IN ACCORD WITH THE 2012 INTERNATIONAL BUILDING CODE AND ASCE 7 INCLUDING DRIFTING SNOW LOADS CHAPTER 16.

C_s = 1.0 C_t = 1.0

I_s = 1.0 P_g = 20 PSF P_f(min) = 20 PSF

P_f = 16 PSF RAIN ON SNOW LOAD= 5 PSF

DESIGN SNOW LOAD SHALL BE WORST CASE OF:

CASE 1: 20 PSF + SNOW DRIFT (SEE 31/54.0 FOR JOIST SNOW DRIFT)

CASE 2: 25 PSF (BALANCED SNOW + RAIN-ON-SNOW)

WIND LOAD:

WIND LOADS IN ACCORD WITH THE 2012 INTERNATIONAL BUILDING CODE.

ULTIMATE DESIGN WIND SPEED = 115 MPH

EXPOSURE "C"

G_{Cpi} = +/- 0.18

SEISMIC LOAD:

SEISMIC DESIGN IN ACCORD WITH 2012 INTERNATIONAL BUILDING CODE.

I_e=1.0 SITE CLASS = D

MAPPED SPECTRAL RESPONSE COEFFICIENTS: S_s = 0.1005 S₁ = 0.0686

SPECTRAL RESPONSE COEFFICIENTS: S_{DS} = 0.107 S₀₁ = 0.110

SEISMIC DESIGN CATEGORY B

R = 3.5

C_s = 0.0306

LATERAL LOAD RESISTANCE SYSTEM:

LATERAL LOAD SYSTEM CONSISTS OF ROOF DIAPHRAGMS TRANSFERRING LATERAL LOADS TO MASONRY SHEAR WALLS SUPPORTED BY CONCRETE FOUNDATIONS.

FOUNDATIONS:

1. A GEOTECHNICAL REPORT HAS NOT BEEN COMPLETED. FOUNDATIONS HAVE BEEN DESIGNED TO BEAR ON STRUCTURAL SOIL CAPABLE OF SUPPORTING 1500PSF.
2. MINIMUM FROST DEPTH: 3'-0"

CONCRETE:

1. CONCRETE MIX DESIGNS:

FOOTINGS:

MIN 28 DAY COMPRESSIVE STRENGTH = 3,000 PSI

W/C RATIO = 0.50

MAX AGGREGATE SIZE = ¾"

SLUMP = 4"±1"

AIR CONTENT = 6% ±1.5% (ASTM C 260)

SLAB ON GRADE:

MIN 28 DAY COMPRESSIVE STRENGTH = 4,000 PSI

W/C RATIO = 0.45

MAX AGGREGATE SIZE = ¾"

MAX SLUMP = 4"

AIR CONTENT = 1.5% (ASTM C 260)

EXTERIOR CONCRETE:

MIN 28 DAY COMPRESSIVE STRENGTH = 4,500 PSI

W/C RATIO = 0.40

MAX AGGREGATE SIZE = ¾"

SLUMP = 4"±1"

AIR CONTENT = 6% ± 1.5% (ASTM C 260)

2. IF CONTRACTOR DESIRES TO INCREASE SLUMP ABOVE ALLOWABLE LIMITS TO FACILITATE PLACEMENT OR PUMPING, THIS SHALL BE DONE UTILIZING AN APPROPRIATE APPROVED ADMIXTURE. NO WATER SHALL BE ADDED AT THE PROJECT SITE WITHOUT THE ENGINEER'S PERMISSION. ALL ADMIXTURES SHALL BE APPROVED IN WRITING BY THE ENGINEER.
3. THE CONTRACTOR SHALL REJECT ANY CONCRETE THAT EXCEEDS THE SLUMP LIMITS NOTED ABOVE OR EXCEEDS THE TOTAL ALLOWABLE MIXING TIME.
4. FLY ASH MAY BE INCLUDED IN FOUNDATION CONCRETE.
5. NO ALUMINUM SHALL BE PLACED IN CONCRETE.
6. DURING HOT WEATHER (80 DEGREES F AND ABOVE, THE CONTRACTOR SHALL COMPLY WITH THE RECOMMENDATIONS ACI 305"HOT WEATHER CONCRETE." DURING COLD WEATHER (40 DEGREES F AND BELOW), THE CONTRACTOR SHALL COMPLY WITH THE RECOMMENDATIONS OF ACI-306 "COLD WEATHER CONCRETING."
7. THE CONCRETE MIX DESIGNS ARE TO BE SUBMITTED AS A FORMAL SUBMITTAL TO THE ENGINEER OF RECORD FOR REVIEW AND ACCEPTANCE. AFTER ACCEPTANCE OF THE MIX DESIGN BY THE ENGINEER OF RECORD, THE ACCEPTED DESIGNS MUST BE FORWARDED TO THE CITY INSPECTION DEPT. & THE SPECIAL INSPECTOR PRIOR TO CONCRETE BEING DELIVERED TO THE SITE.

CONCRETE REINFORCEMENT:

1. REINFORCING STEEL SHALL BE ASTM A615, GRADE 60.

2. CONCRETE COVER REQUIREMENTS FOR CAST-IN-PLACE, UNLESS OTHERWISE NOTED ON DETAILS:

CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH: 3"

OTHER: #6 BARS AND LARGER: 2"

#5 BARS AND SMALLER: 1-½"

3. REINFORCING BAR SPLICES SHALL BE IN ACCORD WITH THE REQUIREMENTS OF ACI 318-11 AND THE REINFORCING SPICE LENGTH TABLE SHOWN ON THE DRAWINGS.

MASONRY:

1. THE MINIMUM 28-DAY COMPRESSIVE STRENGTH OF THE CONCRETE MASONRY UNITS SHALL BE 1900 PSI ON THE NET AREA, PROVIDING A STRUCTURAL DESIGN COMPRESSIVE STRENGTH OF 1500 PSI PER THE 2012 INTERNATIONAL BUILDING CODE, TABLE 2105.2.2.1.2.

2. MORTAR SHALL BE TYPE S IN ACCORD WITH ASTM C270 AND ARTICLES 2.1 AND 2.6 A OF TMS 602/ACI S30.1/ASCE6, MORTAR PROPORTIONS FOR UNIT MASONRY, USING CEMENT LIME OR MORTAR CEMENT MIXES. (MASONRY CEMENT IS NOT ACCEPTABLE).

3. MINIMUM 28-DAY COMPRESSIVE STRENGTH OF GROUT SHALL BE THE GREATER OF 2500 PSI OR THE COMPRESSIVE STRENGTH OF THE MASONRY UNITS. AIR ENTRAINMENT AND OTHER ADDITIVES ARE NOT ACCEPTABLE IN GROUT MIX. GROUT SHALL HAVE A SLUMP OF 8 TO 11 INCHES.

4. MASONRY REINFORCING STEEL SHALL BE ASTM A615, GRADE 60.

5. HORIZONTAL JOINT REINFORCING SHALL BE STANDARD LADDER TYPE, GALVANIZED, AT 16-INCHES ON CENTER, UNLESS OTHERWISE NOTED ON PLAN.

6. MINIMUM BOND BEAM REINFORCING SHALL BE 2 - #4 IN 6" AND 8" BOND BEAMS AND 2 - #5 IN 12" BOND BEAMS. BOND BEAM REINFORCING SHALL BE CONTINUOUS THROUGH CONTROL JOINTS EXCEPT AS NOTED ON TYPICAL MASONRY WALL OPENING DETAIL.

7. SPICE LENGTHS FOR MASONRY REINFORCEMENT SHALL BE IN ACCORD WITH THE REINFORCING SPICE LENGTH TABLE OR AS SHOWN ON THE DRAWINGS.

8. PROVIDE BOND BEAMS AT TOP OF ALL WALLS, AT ROOFS, STRUCTURAL FLOORS, OVER ALL OPENINGS IN WALLS AND WHERE SHOWN ON THE DRAWINGS.

9. REINFORCING SHALL BE HELD IN PLACE PRIOR TO GROUTING WITH WIRE POSITIONERS PLACED AT INTERVALS NOT EXCEEDING 192 BAR DIAMETERS NOR 10 FEET. PROVIDE POSITIONERS AT REINFORCING SPLICES.

10. VERTICAL REINFORCING SHALL BE AS FOLLOWS, UNLESS OTHERWISE NOTED ON THE PLANS OR DETAILS.

8" CONC BLOCK 1-#5 @ 4'-0" OC

10" CONC BLOCK 1-#5 @ 4'-0" OC

12" CONC BLOCK 2-#6'S @ 4'-0" OC

11. PROVIDE #5 VERTICAL REINFORCING AT JAMB OPENINGS, ENDS AND CORNERS OF ALL WALLS AND EACH SIDE OF CONTROL JOINTS. SPECIAL JAMB REINFORCING, WHERE REQUIRED, IS CALLED OUT ON THE PLANS.

12. VERTICAL REINFORCING REQUIRED BY THESE NOTES OR SHOWN ON THE FOUNDATION PLANS SHALL EXTEND FROM FOUNDATION TO TOP OF WALL UNLESS OTHERWISE NOTED.

13. ELECTRICAL PANELS, CONDUITS, PIPES, FIRE EXTINGUISHER CABINETS, ETC., ARE TO BE LOCATED SO AS NOT TO INTERFERE WITH REINFORCED AND/OR GROUTED CELLS. PIPES AND CONDUITS PASSING HORIZONTALLY THROUGH WALLS SHALL BE SLEEVED. MINIMUM SPACING OF SLEEVES SHALL BE THREE DIAMETERS.

14. ALL MASONRY BELOW HIGHEST ADJACENT GRADE SHALL BE GROUTED SOLID.

15. GROUT SHALL BE MECHANICALLY CONSOLIDATED IN A MANNER TO FILL THE GROUT SPACE AND RECONSOLIDATED IN ACCORD WITH THE 2012 INTERNATIONAL BUILDING CODE.

16. PROVIDE GROUT AND MASONRY UNIT TESTING PRIOR TO AND DURING CONSTRUCTION IN ACCORD WITH THE 2012 INTERNATIONAL BUILDING CODE.

17. REINFORCEMENT PLACEMENT, GROUT SPACES AND GROUTING OPERATION SHALL BE INSPECTED BY TESTING LABORATORY IN ACCORD WITH THE 2012 INTERNATIONAL BUILDING CODE REQUIREMENTS. MORTAR FIN PROJECTION INTO THE GROUT SPACE SHALL NOT EXCEED ½ INCH.

STRUCTURAL STEEL:

1. FABRICATOR SHALL BE AN "APPROVED FABRICATOR" IN ACCORD WITH THE 2012 INTERNATIONAL BUILDING CODE SECTION 1704.2.5, REGISTERED AND APPROVED BY THE LOCAL BUILDING DEPARTMENT. IN LIEU OF THE PREVIOUS, FABRICATOR SHALL INCLUDE IN THEIR BID THE SERVICES OF A SPECIAL INSPECTOR TO PROVIDE INSPECTION/TESTING SERVICES FOR IN-SHOP WORK TO MEET THE REQUIREMENTS OF 2012 INTERNATIONAL BUILDING CODE SECTION 1704.

2. STRUCTURAL STEEL SHALL MEET ASTM A36 UNLESS NOTED OTHERWISE. STRUCTURAL STEEL WIDE FLANGE SHAPES SHALL MEET ASTM A992.

3. STEEL TUBES SHALL MEET ASTM A500, GRADE B.

4. STEEL PIPE SHALL MEET ASTM A53, TYPE E OR S, GRADE B.

5. BOLTS SHALL BE ¾" DIAMETER A325-N UNLESS OTHERWISE NOTED.

6. FIELD BOLTING INSTALLATION SHALL BE INSPECTED IN ACCORD WITH THE 2012 INTERNATIONAL BUILDING CODE AND THE AISC LRFD MANUAL, SECOND EDITION. BOLTS SHALL BE INSTALLED SNUG TIGHT UNLESS NOTES OTHERWISE NOTED. ASTM A-325-SC SHALL BE FULLY TIGHTENED USING LOAD INDICATOR WASHERS.

7. ALL WELDING SHALL CONFORM TO THE PROVISIONS OF THE AMERICAN WELDING SOCIETY CODE AWS D1.1-10. ELECTRODES SHALL MATCH BASE METALS AS SPECIFIED IN 2012 INTERNATIONAL BUILDING CODE.

8. ALL FIELD WELDING SHALL BE VISUALLY INSPECTED BY THE TESTING LABORATORY.

9. HOT DIP GALVANIZE ALL EXPOSED STEEL MEMBERS TO MEET ASTM 525 G60.

10. ALL STEEL BELOW GRADE SHALL BE ENCASED IN CONCRETE WHERE POSSIBLE; IF NOT POSSIBLE, STEEL SHALL BE THOROUGHLY COATED WITH TWO COATS OF ASPHALTIC PAINT.

11. SEE ARCHITECTURAL DRAWINGS FOR ANY ADDITIONAL STRUCTURAL STEEL NOT CALLED OUT ON STRUCTURAL DRAWINGS.

PREFABRICATED WOOD TRUSSES:

1. ROOF AND FLOOR TRUSSES SHALL BE DESIGNED IN ACCORDANCE WITH TRUSS PLATE INSTITUTES (TP) DESIGN SPECIFICATION FOR METAL PLATE CONNECTED WOOD TRUSSES AND THE NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION. BRACE TOP AND BOTTOM CHORDS OF TRUSSES DURING ERECTION PER MANUFACTURER RECOMMENDATIONS.

2. ROOF TRUSSES SHALL BE DESIGNED FOR AND CONSTRUCTED FOR A MAXIMUM LIVE LOAD DEFLECTION OF L/360. FLOOR TRUSSES SHALL BE DESIGNED AND CONSTRUCTED FOR A MAXIMUM LIVE LOAD DEFLECTION OF L/360 WITH NON BEARING WALLS BELOW AND L/480 AT CLEAR SPAN TRUSSES.

3. TRUSS SPACING IS AS DETERMINED BY TRUSS MANUFACTURER. MAXIMUM SPACING IS 24" OC.

4. LOADS ARE NOTED IN THE LOADING SECTION AND ARE MINIMUM. TRUSS DESIGNER IS RESPONSIBLE FOR ESTABLISHING. FINAL LOADS USED FOR DESIGN, INCLUDING LIVE, DEAD, SNOW (WITH DRIFTS) AND WIND LOADS. TRUSS FABRICATOR TO SUPPLY SEALED TRUSS SHOP DRAWINGS AND SEALED PLAN PLACEMENT DRAWINGS PREPARED UNDER THE SUPERVISION OF THE SAME LICENSED PROFESSIONAL ENGINEER IN THE STATE OF MISSOURI. SHOP DRAWINGS SHOULD INCLUDE DETAILED ERECTION DRAWINGS, AS WELL AS DESIGN INFORMATION FOR EACH TRUSS. PROVIDE ALL INFORMATION AS REQUIRED IN THE 2012 IBC SECTION 2303.4.1.

5. TRUSS MANUFACTURER IS RESPONSIBLE FOR DESIGNING ALL TRUSS-TO-TRUSS, TRUSS-TO-WALL AND TRUSS-TO-BEAM CONNECTIONS UNLESS NOTED OTHERWISE.

ROUGH CARPENTRY:

1. ALL WOOD FRAMING MEMBERS INDICATED ARE NOMINAL SIZES. PROVIDE ACTUAL DRESSED SIZES, KILN DRIED, WITH MAXIMUM IN PLACE MOISTURE CONTECT OF 19%.

2. ALL BOLTS ARE A36 OR A307, GRADE A, AND ALL NAILS ARE BOX NAILS UNLESS NOTED OTHERWISE.

3. SHEARWALL SHEATHING IS 7/16" SHEATHING ATTACHED WITH NO. 8D NAILS SPA AT 6" MAX UNLESS NOTED OTHERWISE. SEE SHEARWALL SCHEDULE.

4. UNLESS NOTED OTHERWISE, FASTENER QUALITY, QUANTITY SIZE AND SPACING SHALL COMPLY WITH THE 2012 IBC FASTENING SCHEDULE (TABLE 2304.9)

5. ALL WOOD IN CONTRACT WITH THE CONCRETE OR EXPOSED TO WEATHER SHALL BE PRESERVATIVE TREATED.

6. 15/32" ROOF SHEATHING STRUCTURAL WITH 10d NAILS AT 6" OC.

7. JOIST HEADERS AND WALL STUDS TO BE #2 DOUGLAS FIR AND LVL -E=1,900,000 PSI

POST-INSTALLED ANCHORS:

1. EXPANSION BOLTS INSTALLED IN CONCRETE SHALL BE HILTI KWIK BOLT-II ANCHORS OR APPROVED EQUAL WITH EMBEDMENT NOTED ON THE DRAWINGS OR EMBEDMENT AS RECOMMENDED BY MANUFACTURER WHERE NO EMBEDMENT IS SHOWN. INSTALL IN ACCORD WITH MANUFACTURER'S RECOMMENDATIONS AND ICBO REPORT ER-4627.

2. SCREW ANCHORS SHALL BE KWIK CON II CONCRETE ANCHORS BY HILTI, INC. OR APPROVED EQUAL. INSTALL IN ACCORD WITH MANUFACTURER'S RECOMMENDATIONS AND ICBO REPORT ER-5259

3. ADHESIVE ANCHORS SHALL BE HILTI INC., HIT HY 200 ADHESIVE ANCHORING SYSTEM OR APPROVED EQUAL, WITH EMBEDMENT NOTED ON THE DRAWINGS OR EMBEDMENT AS RECOMMENDED BY MANUFACTURER WHERE NO EMBEDMENT IS SHOWN. INSTALL IN ACCORD WITH MANUFACTURER'S RECOMMENDATIONS AND ICBO REPORT ESR-3187.

4. ANCHORS ARE NOT TO BE INSTALLED UNTIL CONCRETE OR GROUT HAS REACHED ITS DESIGN STRENGTH.

FIRE RATINGS:

1. FOR FIRE-RATING REQUIREMENTS AND METHODS, SEE ARCHITECTURAL DRAWINGS.

SPECIAL STRUCTURAL INSPECTIONS:

1. IN ACCORD WITH THE 2012 INTERNATIONAL BUILDING CODE, SECTION 1704, AS NOTED BELOW. TESTING AND INSPECTION SHALL BE BY AN INDEPENDENT TESTING/INSPECTION FIRM, UNDER THE SUPERVISION OF A LICENSED ENGINEER EMPLOYED BY THAT FIRM. THE BASIS FOR WELDING INSPECTOR QUALIFICATION SHALL BE AWS D1.1.

2. SPECIAL INSPECTION IS TO BE PROVIDED IN ADDITION TO THE INSPECTIONS CONDUCTED BY THE LOCAL DEPARTMENT OF BUILDING SAFETY AND SHALL NOT BE CONSTRUED TO RELIEVE THE OWNER OR HIS AUTHORIZED AGENT FROM REQUESTING THE PERIODIC AND CALLED INSPECTIONS REQUIRED BY THE 2012 INTERNATIONAL BUILDING CODE

3. VERIFICATION OF SOLLS: PER SECTION 1705.6 AND TABLE 1705.6.

4. CONCRETE: PER SECTION 1705.3 AND TABLE 1705.3.(ALL CONCRETE EXCEPT SLABS-ON-GRADE AND SIDEWALKS). ANCHOR BOLTS SHALL BE INSPECTED.

5. STEEL: PER SECTION 1705.2 AND TABLE 1705.2.2. PROVIDE INSPECTION OF ALL SHOP WELDING AT CONTRACTOR'S EXPENSE IF WELDING IS NOT DONE IN AN APPROVED FABRICATOR'S SHOP.

6. HIGH STRENGTH BOLTING: PER SECTION 1704.3.3.

7. STRUCTURAL MASONRY: PER SECTION 1705.4.

8. EXPANSION BOLT, SCREW ANCHOR AND EPOXY ANCHOR INSTALLATION TO VERIFY INSTALLATION IN ACCORD WITH ICBO REPORTS NOTED PREVIOUSLY OR APPROVED EQUAL.

9. THE INSPECTOR SHALL OBSERVE THE WORK ASSIGNED TO BE CERTAIN IT CONFORMS WITH THE APPROVED DESIGN DRAWINGS AND SPECIFICATIONS.

10. THE INSPECTOR SHALL FURNISH DAILY INSPECTION REPORTS ON THE WORK TO THE BUILDING OFFICIAL AND TO THE ENGINEER OF RECORD FOR CONFORMANCE TO THE CONTRACT DOCUMENTS. ALL DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION, AND, IF UNCORRECTED, TO THE ENGINEER OF RECORD AND THE BUILDING OFFICIAL.

11. THE TESTING/INSPECTION FIRM'S ENGINEER SHALL COMPLETE, SIGN AND SEAL A FINAL REPORT CERTIFYING THAT TO THE BEST OF HIS KNOWLEDGE, THE WORK IS IN CONFORMANCE WITH THE CONTRACT DOCUMENTS.

DEFERRED SUBMITTALS:

1. THE FOLLOWING ITEMS ARE DEFERRED SUBMITTAL ITEMS:
- STEEL JOISTS
 - PRE ENGINEERED WOOD TRUSSES

2. DEFERRED SUBMITTAL ITEMS SHALL BE PREPARED AND SEALED BY A LICENSED PROFESSIONAL ENGINEER IN THE STATE OF THE PROJECT WITH CALCULATIONS, DRAWINGS, DETAILS, AND CUT SHEETS SUBMITTED TO THE ENGINEER OF RECORD FOR REVIEW. ONCE REVIEWED, CONTRACTOR SHALL FORWARD TO THE BUILDING DEPARTMENT FOR APPROVAL. FABRICATION AND/OR INSTALLATION OF DEFERRED SUBMITTAL ITEMS SHALL NOT OCCUR UNTIL APPROVAL OF THE BUILDING DEPARTMENT IS RECEIVED.

SHOP DRAWING REVIEW:

1. J&S STRUCTURAL ENGINEERS, PA WILL REVIEW SHOP DRAWINGS AND RELATED SUBMITTALS FOR GENERAL CONFORMANCE WITH THE DESIGN CONCEPT AND THE INFORMATION GIVEN IN THE CONSTRUCTION DOCUMENTS. REVIEW OF A SPECIFIC ITEM SHALL NOT INCLUDE REVIEW OF AN ASSEMBLY OF WHICH THE ITEM IS A COMPONENT.

2. THE FOLLOWING IS A LIST OF REQUIRED SHOP DRAWINGS AND RELATED SUBMITTALS. THE CONTRACTOR SHALL REFER TO THE SPECIFICATIONS FOR MORE INFORMATION AND A COMPLETE LIST OF REQUIRED SUBMITTALS:


- CONCRETE MIX DESIGNS, TESTS AND MATERIAL CERTIFICATIONS
- CONCRETE REINFORCING SHOP DRAWINGS AND REINFORCING MATERIAL CERTIFICATIONS
- CONCRETE BLOCK COMPRESSION TESTS AND MATERIAL CERTIFICATIONS
- MASONRY GROUT AND AND MORTAR MIX DESIGNS
- MASONRY REINFORCING SHOP DRAWINGS
- STRUCTURAL STEEL SHOP DRAWINGS MATERIAL CERTIFICATIONS, WELDER CERTIFICATIONS.

ABBREVIATIONS:

ASD	ALLOWABLE STRESS DESIGN
ARCH	ARCHITECT
BPL	BASEPLATE
BTW	BETWEEN
BOTT	BOTTOM
BOTT OF BOL	BOTTOM OF
CIP	BOTTOM OF LINTEL
CL	CAST IN PLACE
CLR	CENTERLINE
CMU	CLEAR
COL	CONCRETE MASONRY UNIT
COMP	COLUMN
CONC	COMPRESSIBLE
CONT	CONCRETE
CJ	CONTINUOUS
DIM	CONTROL JOINT
EA	DIMENSION
EF	EACH
ELEV	EACH FACE
EMBED	ELEVATION
EQ	EMBEDMENT
EW	EQUAL
EXP	EACH WAY
FF	EXPANSION
FND	FINISH FLOOR
FTG	FOUNDATION
GALV	FOOTING
GB	GALVANIZED
HSS	GRADE BEAM
HORIZ	HOLLOW STRUCTURAL SECTION
IJ	HORIZONTAL
INFO	ISOLATION JOINT
INSUL	INSULATION
JT	JOINT
JB	JOIST BEARING
K	KIP = 1,000 POUNDS
LONG	LONGITUDINAL
LRFD	LOAD AND RESISTANCE FACTORED DESIGN
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
MAS	MASONRY
MAT'L	MATERIAL
MAX	MAXIMUM
MBM	METAL BUILDING MANUFACTURER
MIN	MINIMUM
OC	ON CENTER
PEM	PRE-ENGINEERED MEMBER (NOT BY J&S STRUCTURAL ENGINEERS)
PEMB	PRE-ENGINEERED METAL BUILDING (NOT BY J&S STRUCTURAL ENGINEERS)
PL	PLATE
LB	POUND
PSF	POUNDS PER SQUARE FOOT
REF	REFERENCE
REINF	REINFORCEMENT
REQD	REQUIRED
SCHED	SCHEDULE
SPA	SPACE
SQ	SQUARE
STD	STANDARD
STL	STEEL
T&B	TOP AND BOTTOM
TG	TONGUE-AND-GROOVE
TO	TOP OF
TOF	TOP OF FOOTING
TOL	TOP OF LINTEL
TOS	TOP OF STEEL
TRANS	TRANSVERSE
TYP	TYPICAL
UNO	UNLESS NOTED OTHERWISE
VERT	VERTICAL
WWR	WELDED WIRE REINFORCEMENT



Craig Luebbert
Architect
24 NW Chipman 'B'. 816.875.4863



Construction Drawings for:

Heartland Market

DATE ISSUED:
4/05/23


REVISIONS:

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

GENERAL
STRUCTURAL
NOTES


S001



 FOUNDATION PLAN
3/16" = 1'-0"



Craig Luebert
Architecture
24 NW Chipman 'B', 816.875.4863



Construction Drawings for:
Heartland Market

DATE ISSUED:
4/05/23


REVISIONS

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER
**FOUNDATION
PLAN
S100**



Craig Luebert
Architecture
24 NW Chipman 'B', 816.875.4863



Construction Drawings for:

Heartland Market


DATE ISSUED:
4/05/23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

FRAMING
PLAN
S200



FRAMING PLAN
3/16" = 1'-0"


NOTES:


1. 2x6 TYP T&B - SEE 21/S400

2. TB INDICATES TRUSS BEARING ELEVATION.


3. (2)L3 1/2x3 1/2x5/16"

4. SNOW DRIFT (PSF)







11 TYPICAL SLAB-ON-GRADE JOINTS
S300 NO SCALE




31 TYPICAL INSTALLATION OF PIPE
S300 NO SCALE (@ FOUNDATIONS)




12 ADDITIONAL SLAB-ON-GRADE REINF
S300 NO SCALE




13 DETAIL AT MAN DOOR
S300 NO SCALE




14 MASONRY WALL FTG AT ENTRY
S300 NO SCALE




24 TYPICAL BOND BEAM DETAILS
S300 NO SCALE



33 TYPICAL MASONRY WALL REINFORCEMENT DETAILS
S300 NO SCALE




43 MASONRY WALL FTG AT BUMPOUT
S300 NO SCALE



44 TYPICAL MASONRY WALL FOOTING
S300 NO SCALE



Craig Luebert
Architecture
24 NW Chipman 'B' 816.875.4863



Construction Drawings for:

Heartland Market

DATE ISSUED:
4/05/23


REVISIONS:

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


FOUNDATION AND
MASONRY DETAILS

S300




21 PARAPET SUPPORT DETAIL

S400 SCALE: NO SCALE




22 TYP TRUSS BRG AT EXT

S400 SCALE: NO SCALE




23 TYP TRUSS BRG AT EXT

S400 SCALE: NO SCALE




24 TYP TRUSS BRG AT EXT

S400 SCALE: NO SCALE




33 TYP NON-BEARING DETAIL

S400 SCALE: NO SCALE




34 TYP LINTEL DETAIL

S400 NO SCALE



35 TYP MASONRY BEAM/LINTEL BEARING

S400 NO SCALE



36 TYP STEEL LINTEL DETAIL

S400 NO SCALE



Craig Luebert
Architecture
24 NW Chipman 'B' 816.875.4863

Construction Drawings for:
Heartland Market

DATE ISSUED:
4/05/23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

FRAMING
DETAILS
S400

MECHANICAL SPECIFICATIONS

1. GENERAL PROVISIONS:
- A. PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, NECESSARY FOR THE COMPLETE INSTALLATION OF THE PLUMBING AND MECHANICAL SYSTEMS OUTLINED.
- B. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE AUTHORITIES.
- C. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION OVER THE SITE.
- D. ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.
- E. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, PIPE, DUCT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNDAMAGED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERING SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.
- F. PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS AS NECESSARY. PATCH AROUND ALL OPENINGS SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.
- G. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
2. OPERATION AND MAINTENANCE MANUALS:
- A. DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, WIRING DIAGRAMS, CATALOGS, OILS, LUBRICATION AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.
- B. ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATION AND MAINTENANCE MANUALS.
- C. ALL LITERATURE LISTED ABOVE AND ALL PAPERS LISTING WARRANTIES, ETC. SHALL BE BOUND IN A 3-RING BINDER AND LABELED WITH THE PROJECT NAME, ADDRESS, ARCHITECT, ENGINEER, CONTRACTORS, ETC.
3. MANUFACTURERS:
- A. MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSTRUED AS LIMITING COMPETITION. ARTICLES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO STRUCTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN, UNLESS NOTED OTHERWISE.
4. MOTORS:
- A. PROVIDE THERMAL OVERLOAD PROTECTION FOR EACH MOTOR PROVIDED BY THIS WORK.
5. TESTING, BALANCING, AND COMMISSIONING:
- A. ALL PIPING SHALL BE TESTED FOR LEAKS BEFORE BEING CONCEALED IN WALL CONSTRUCTION OR COVERED WITH INSULATION.
- B. SEWER AND VENT PIPING SHALL BE HYDROSTATICALLY TESTED WITH NO LESS THAN 10 FEET OF HEAD FOR A PERIOD OF NOT LESS THAN 90 MINUTES. PER THE LOCAL PLUMBING CODE, WITH NO LEAKS.
- C. DOMESTIC WATER PIPING SHALL BE HYDROSTATICALLY TESTED AT A PRESSURE OF NOT LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE, BUT NOT LESS THAN 60 PSI, FOR A PERIOD OF NOT LESS THAN 2 HOURS, WITH NO LEAKS.
- D. NATURAL GAS PIPING SHALL BE PNEUMATICALLY TESTED AT A PRESSURE OF NOT LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE, BUT NOT LESS THAN 50 PSI, FOR A PERIOD OF NOT LESS THAN 2 HOURS, WITH NO LEAKS.
- E. DUCTWORK AND PIPING SHALL BE BALANCED BY QUALIFIED INDEPENDENT BALANCING PERSONNEL, WHO HAVE PREVIOUS EXPERIENCE WITH BALANCING PROCEDURES AND ARE CERTIFIED BY THE ASSOCIATED AIR BALANCE COUNCIL (AABC) OR NATIONAL BALANCING BUREAU (NBBB).
- 1) BALANCING SHALL INCLUDE THE BALANCING OF THE EQUIPMENT AND AIR DISTRIBUTION SYSTEMS TO PROVIDE DESIGN QUANTITIES INDICATED AND VERIFICATION OF PERFORMANCE OF ALL EQUIPMENT AND AUTOMATIC CONTROLS.
- 2) WITH IN 90 DAYS OF THE COMPLETION OF THE TESTING AND BALANCING WORK, SUBMIT THE TEST AND BALANCING REPORT BEARING THE SIGNATURE OF THE TEST AND BALANCE ENGINEER. THE REPORTS SHALL BE CERTIFIED PROOF THAT THE SYSTEMS HAVE BEEN TESTED, ADJUSTED, AND BALANCED IN ACCORDANCE WITH THE REFERENCED STANDARD. ARE AN ACCURATE REPRESENTATION OF HOW THE SYSTEMS HAVE BEEN INSTALLED AND ARE OPERATING. REPORTS SHALL BE BOUND IN A VINYL BINDER AND THE BINDER LABELED OR MAY BE AN ELECTRONIC PDF SUBMITTAL.
- F. GREASE DUCT SHALL BE TESTED PRIOR TO USE OR CONCEALMENT OF ANY PORTION OF THE GREASE DUCT SYSTEM. DUCTS SHALL BE CONSIDERED TO BE CONCEALED WHEN INSTALLED IN SHUTS OR COVERED BY DUCT WRAP INSULATION THAT PREVENTS THE DUCTWORK FROM BEING VISUALLY INSPECTED FROM ALL SIDES. THE PERMIT HOLDER SHALL BE RESPONSIBLE TO PROVIDE THE NECESSARY EQUIPMENT AND PERFORM THE GREASE DUCT LEAKAGE TEST PER NFPA 96 AND ALL LOCAL CODES.
- G. BEFORE DOMESTIC WATER PIPING IS PLACED IN SERVICE, ALL DOMESTIC WATER DISTRIBUTION SYSTEMS, INCLUDING THOSE FOR COLD WATER AND HOT WATER SYSTEMS, SHALL BE FLUSHED, DISINFECTED AND CHLORINATED IN ACCORDANCE WITH HEALTH DEPARTMENT REGULATIONS. THE SYSTEMS SHALL BE THOROUGHLY FLUSHED OF ALL DIRT AND FOREIGN MATERIAL, THEN FILLED WITH WATER TREATED WITH 50 PPM OF CHLORINE. DURING THE FILLING PROCESS, VALVES AND FAUCETS SHALL BE OPENED SEVERAL TIMES TO ASSURE THE ENTIRE SYSTEM OF THE TREATED WATER SHALL BE LEFT IN THE SYSTEM FOR 24 HOURS AFTER WHICH TIME THE SYSTEM SHALL BE FLUSHED. IF THE RESIDUAL CHLORINE IS NOT LESS THAN 10 PPM, THE FLUSHING SHALL BE REPEATED. AFTER FLUSHING, SAMPLES OF WATER IN THE SYSTEM SHALL BE APPROVED BY THE BOARD OF HEALTH.
6. PLUMBING:
- A. PROVIDE AN APPROVED WATER HAMMER ARRESTOR FOR EACH PLUMBING FIXTURE SUPPLY AS REQUIRED BY FIXTURE MANUFACTURER.
- B. ALL EXPOSED WATER PIPE SHALL BE CHROME PLATED BRASS PIPE, NO FERROUS PIPE.
- C. PROVIDE CLEANOUTS AT EACH CHANGE OF DIRECTION AND AT 100 FOOT INTERVALS IN STRAIGHT RUNS.
- D. PROVIDE ACCESS PANELS FOR ALL CONCEALED VALVES AND TRAPS.
- E. CLEANOUTS:
- 1) VINYL TILE FLOOR: JR SMITH 44140, OR EQUAL.
- 2) QUARRY TILE FLOOR: JR SMITH 44200, OR EQUAL.
- 3) CARPETED FLOOR: JR SMITH 44020-Y, OR EQUAL.
- 4) UNFINISHED FLOOR: JR SMITH 44020-Y, OR EQUAL.
- 5) WALL: JR SMITH 44412, OR EQUAL, 24" ABOVE THE FLOOR.
- F. PROVIDE DIELECTRIC UNIONS WITH APPROPRIATE END CONNECTIONS TO MATCH THE PIPE SYSTEM IN WHICH INSTALLED (SOLDERED, SOLDERED, OR FLANGED). PROVIDE DIELECTRIC UNIONS ON ALL PIPING CONNECTIONS TO HOT WATER HEATERS AND DRAINAGE TANKS.
- G. WATER HEATERS:
- 1) EVERY WATER HEATER SHALL HAVE AN APPROVED MEANS INSTALLED ON THE COLD WATER SUPPLY LINE ABOVE THE EQUIPMENT TO PREVENT SIPHONING OF A STORAGE WATER HEATER OR TANK.
- 2) BOTTOM FED WATER HEATERS AND TANKS CONNECT TO WATER HEATERS SHALL HAVE A VACUUM RELIEF VALVE INSTALLED, ANSI 221.22.
- 3) STORAGE HEATERS OPERATING ABOVE ATMOSPHERIC PRESSURE SHALL HAVE AN APPROVED PRESSURE RELIEF VALVE AND/OR TEMPERATURE RELIEF VALVE.
- H. ALL SEWER PIPING LOCATED INSIDE THE BUILDINGS SHALL BE INSTALLED WITH THE FOLLOWING SLOPES:
- 1) INSTALL 2-1/2" AND SMALLER PIPE AT 1/4" PER FOOT FALL.
- 2) INSTALL 3" AND LARGER PIPE AT 1/8" PER FOOT FALL.
- 3) INSTALL ALL GREASE WASTE PIPING AT 1/4" PER FOOT FALL.
- I. ALL SEWER PIPING LOCATED EXTERIOR TO THE BUILDING SHALL BE INSTALLED WITH THE FOLLOWING SLOPES:
- 1) INSTALL 4" AND SMALLER PIPE AT A MINIMUM OF 2% SLOPE.
- 2) INSTALL 6" AND LARGER PIPE AT A MINIMUM OF 1% SLOPE.
7. PIPING:
- A. DOMESTIC COLD, HOT, AND HOT WATER RECIRCULATING (ABOVEGROUND).
- 1) TYPE I HARD DRAWN COPPER TUBING, ASTM B-30.
- a) WROUGHT COPPER SOLDERED FITTINGS, ASTM B75 ALLOY C12200, ANSI B16.22, MSS SP-104.
- b) MECHANICAL PRESS COPPER FITTINGS FOR USE IN PLUMBING OR MECHANICAL APPLICATIONS, ASME B16.22, ASME B16.51, OR ASME B16.18.
- c) MECHANICAL PRESS COPPER FITTINGS SHALL CONFORM TO ASME B16.22, ASME B16.51, OR ASME B16.18.
- 2) PEK HIGH-DENSITY CROSS-LINKED POLYETHYLENE TUBING SHALL BE MANUFACTURED TO THE REQUIREMENTS OF ASTM F1363 AND MEET THE STANDARD GRADE HYDROSTATIC PRESSURE RATINGS FROM PLASTIC PIPE INSTITUTE IN ACCORDANCE WITH TR-4/03.
- a) PEK-A AND PEK-B MEETINGS ANSI/NSF 61 AND ANSI/NSF312 STANDARDS FOR POTABLE WATER SAFETY AND LEAD-FREE STANDARDS AND MUST BE MARKED WITH "PEK-A", "NSF-61-01" OR OTHER NSF-APPROVED MARKING, ASTM F4203 FOR USE WITH CHLORINATED WATER.
- b) PEK MECHANICAL CRIMP/INSULATION OR EXPANSION FITTINGS INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. PIPE SIZES GIVEN ON THE DRAWINGS SHALL CONFORM TO PIPE SIZES. INCREASE PIPE SIZING SIZE TO EQUAL OR EXCEED COPPER PIPE INSIDE DIAMETER FOR SUPPLY MAINS.
- 3) VALVES:
- a) TO BE INSTALLED ON THE FIXTURE SUPPLY TO EACH PLUMBING FIXTURE.
- b) TO BE INSTALLED ON THE FIXTURE SUPPLY SIDE TO EACH APPLIANCE OR MECHANICAL EQUIPMENT.
- c) TYPES:
1. GATE VALVE, JOHAR 7-8-3019 OR EQUAL, LEAD-FREE NSF 61, ANSI B1.20.1.
2. GLOBE VALVE, JOHAR T-69 OR EQUAL.
3. BALL VALVE, JOHAR J100PMP OR EQUAL, COMPACT LEAD FREE BRASS BALL VALVE, UL424, CSA B31-12, FM, CALIFORNIA CODE A818, NSF61 ANNEX 6, NSF 61-01, OR OTHER NSF-APPROVED.
4. BALL VALVE, JOHAR T-100NE OR EQUAL, UL424, FM, CSA, NSF 61-01, MSS SP-110.
- B. DOMESTIC WATER SERVICE, "1-3"
- 1) TYPE K SOFT DRAWN COPPER TUBING, ASTM B-36.
- a) Cast Copper Alloy Fittings for Flared Copper Tube, ASME/ANSI B16.26.
- 2) POLYETHYLENE BUTYLENE (PEB) TUBING, CTS SIZES 1"-2" ANNA C901 4110 DRI C9250 (NSF 312 2-3", ANNA C901 4110 DRI C9250 MATERIAL AND INSTALLATION MUST CONFORM TO WATER DEPARTMENT REQUIREMENTS.
- C. LEAD CONTENT OF WATER SUPPLY PIPE AND FITTINGS:
- 1) PIPE AND PIPE FITTINGS, INCLUDING VALVES AND FAUCETS, UTILIZED IN THE WATER SUPPLY SYSTEM SHALL NOT HAVE MORE THAN 0% LEAD CONTENT.
- 2) PIPE, PIPE FITTINGS, JOINTS, VALVES, FAUCETS, AND FIXTURE FITTINGS UTILIZED TO SUPPLY WATER FOR DRINKING OR COOKING PURPOSES SHALL COMPLY WITH NSF 372 AND SHALL HAVE A WEIGHTED AVERAGE LEAD CONTENT OF 0.25% OR LESS.
- D. SANITARY SEWER, GREASE WASTE AND VENTS (UNDERGROUND, INTERIOR TO THE BUILDING).
- 1) ABS SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM ABS COMPOUND WITH A CELL CLASS OF 42222 FOR PIPE AND 32222 FOR FITTINGS AS PER ASTM D 3365 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620 FITTINGS SHALL CONFORM TO ASTM D 2688. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2226.
- 2) PVC SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 11432 PER ASTM D 4396 FOR PIPE AND 12454 PER ASTM D 1184 FOR FITTINGS AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620 FITTINGS SHALL CONFORM TO ASTM D 2688. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2226.
- 3) PVC SCHEDULE 40 SOLID WALL PIPE AND DRY FITTING SYSTEM (ASTM D 2685) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 12454 PER ASTM D 1184 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM D 1105 AND ASTM D 2685. INJECTION MOLDED FITTINGS SHALL CONFORM TO ASTM D 2685. FABRICATED FITTINGS SHALL CONFORM TO ASTM F 1866. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564. (WHERE APPROVED BY LOCAL JURISDICTIONS)
- 4) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
- 5) HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
- F. SANITARY SEWER, GREASE WASTE AND VENTS (UNDERGROUND, EXTERIOR TO THE BUILDING).
- 1) ABS SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM ABS COMPOUND WITH A CELL CLASS OF 42222 FOR PIPE AND 32222 FOR FITTINGS AS PER ASTM D 3365 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620 FITTINGS SHALL CONFORM TO ASTM D 2688. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2226.
- 2) PVC SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 11432 PER ASTM D 4396 FOR PIPE AND 12454 PER ASTM D 1184 FOR FITTINGS AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620 FITTINGS SHALL CONFORM TO ASTM D 2688. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2226.
- 3) PVC SCHEDULE 40 SOLID WALL PIPE AND DRY FITTING SYSTEM (ASTM D 2685) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 12454 PER ASTM D 1184 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 734. FITTINGS SHALL CONFORM TO ASTM F 734. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564.
- 4) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 188 AND GBTI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO GBTI STANDARD 310 AND BE CERTIFIED BY NSF INTERNATIONAL.
- 5) HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
- G. COPPER DIV: DRAINAGE TUBE SHALL CONFORM TO ASTM B306, WROUGHT COPPER FITTINGS, ANSI B16.24.
- H. REFRIGERANT:
- 1) DIVY, WROUGHT COPPER, ANSI B16.24 (CONDENSATE INSIDE BUILDINGS).
- 2) POLYETHYLENE GLYCOL (PEG) DIVY PIPE, SCHEDULE 40, SOLVENT JOINT (CONDENSATE ON ROOF).
- 3) POLYETHYLENE GLYCOL (PEG) DIVY PIPE, SCHEDULE 40, SOLVENT JOINT (INDIRECT WASTE).
- 4) DIVY, WROUGHT COPPER, ANSI B16.24 (WATER HEATER TAP, INDIRECT WASTE FROM DISHWASHER/SINKS).
- I. REFRIGERANT:
- 1) ASTM B 280, TYPE ACR, HARD-DRAWN STRAIGHT LENGTHS, AND SOFT-ANNEALED COILS, SEAMLESS COPPER TUBING.
- 2) WROUGHT COPPER, ANSI B16.22, STREAMLINED, PATENTED, BRAZED JOINTS, ANS A 9.9, CLASSIFICATION BAG-1 (SILVER).
- 3) TURNING SHALL BE CLEANED, READY FOR INSTALLATION, AND HAVE ENDS CAPPED TO PROTECT CLEANLINESS OF PIPE INTERIORS PRIOR TO SHIPPING.
- 4) SIZE AND INSTALLATION OF PIPE SHALL BE IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS.
- J. NATURAL GAS:
- 1) BLACK STEEL PIPE, SCHEDULE 40, ASTM A53.
- 2) PIPE 3" AND SMALLER, 150 LB. MALLEABLE IRON, THREADED FITTINGS.
- 3) PIPE 4" AND SMALLER, VERMILION MESSAPRESS 6 FOR WATER AND GAS, CSA L44, TSSA/ASME B31.
- 4) PIPE WITH ASTM A53 SCHEDULE 40 BLACK IRON PIPE.
- 5) PIPE 2-1/2" AND LARGER, KHELDED.
- 6) PLUS VALVE, ROCKWELL NORDSTROM FIGURE NO. 142 OR 143.
- 7) BALL VALVE, JOHAR T-100NE, APPROVALS: UL424, FM, CSA, NSF 61-01, MSS SP-110.
- 8) GAS PIPING PAINTING:
- a) ALL BLACK STEEL, GAS PIPING LOCATED EXTERIOR TO THE BUILDING SHALL BE PRIMED AND PAINTED TO EITHER MATCH ADJACENT EXTERIOR WHERE LOCATED ON OR NEAR EXTERIOR WALL AND PAINTED SAFETY YELLOW WHERE LOCATED ON ROOFS.
- b) ALL PIPE HANGERS AND SUPPORTS SHALL BE STANDARD PRODUCTS OF GRINNELL, FEE AND MASON, OR ELZEN. HANGER SPACING SHALL BE IN ACCORDANCE WITH MSS-SP-69.
- K. SLEEVES
- 1) PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK. ALL SLEEVES SHALL BE OF SUFFICIENT SIZE TO PERMIT PIPE MOVEMENT DUE TO EXPANSION AND CONTRACTION AND TO ACCOMMODATE PIPE INSULATION.
- 2) INTERIOR PARTITIONS: 16 GAUGE GALVANIZED STEEL, PACK BETWEEN PIPE AND SLEEVE WITH FIRE RATING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.
- 3) ROOF: PROSET OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WATERPROOF SEAL. COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF PARCHMENT.
- 4) PROTECTION AGAINST CONTACT: METALLIC FITTINGS, EXCEPT FOR CAST IRON, DUCTILE IRON AND GALVANIZED STEEL SHALL NOT BE PLACED IN DIRECT CONTACT WITH STEEL FRAMING MEMBERS, CONCRETE, OR CINDER WALLS AND FLOORS OR OTHER MASONRY. METALLIC PIPING SHALL NOT BE PLACED IN DIRECT CONTACT WITH CORROSIVE SOILS. SHEATHINGS USED TO PREVENT DIRECT CONTACT SHALL HAVE A THICKNESS OF GREATER THAN 0.028 INCH. SHEATHINGS SHALL BE MADE OF PLASTIC, ANY PIPE THAT PASSES THROUGH A FOUNDATION WALL OR FOOTING SHALL BE PROTECTED WITH A MINIMUM OF 1/2" ABOVE ROOF OR EQUAL TO HEIGHT OF PARAPET, whichever is greater. TERMINATE A MINIMUM OF 12" ABOVE ROOF OR EQUAL TO HEIGHT OF PARAPET, whichever is greater.
- L. PROVIDE CHROME PLATED BRUSHINGS ON ALL PIPE INTERIORS FINISHED AREAS.
- M. WATER HEATERS
- A. COMMERCIAL, LIGHT-DUTY, STORAGE, ELECTRIC, DOMESTIC-WATER HEATERS:
1. STANDARD, UL T14.
2. STORAGE-TANK CONSTRUCTION: STEEL, VERTICAL ARRANGEMENT.
- a. PRESSURE RATING: 150 PSIG.
- b. INTERIOR FINISH: COMPLY WITH NSF 61 AND NSF 312 BARRIER MATERIALS FOR POTABLE-WATER TANK LININGS, INCLUDING EXTENDING LINING MATERIAL INTO TAPPINGS.
3. FACTORY-INSTALLED, STORAGE-TANK APPURTENANCES:
- a. ANODE ROD: REPLACEMENTS WAGNER.
- b. DIP TUBE, REQUIRED UNLESS COLD-WATER INLET IS NEAR BOTTOM OF TANK.
- c. DRAIN VALVE: CORROSION-RESISTANT METAL WITH HOSE-END CONNECTION.
- d. INSULATION: COMPLY WITH ASHRAE/IES 90.1.
- e. JACKET: STEEL WITH ENAMELED FINISH OR HIGH-IMPACT COMPOSITE MATERIAL.
- f. HEAT-TRAP FITTINGS: INLET TYPE IN COLD-WATER INLET AND OUTLET TYPE IN HOT-WATER OUTLET.
- g. HEATING ELEMENTS: ELECTRIC, SCREEN-INTEGRATED, SCREEN-INTEGRATED.
- h. TEMPERATURE CONTROL: ADJUSTABLE THERMOSTAT.
- i. SAFETY CONTROL: HIGH-TEMPERATURE-LIMIT CUTOFF DEVICE OR SYSTEM.
- j. RELIEF VALVE: ASME RATED AND STAMPED FOR COMBINATION TEMPERATURE-AND-PRESSURE RELIEF VALVES, INCLUDING RELIEF CAPACITY AT LEAST AS GREAT AS HEAT INPUT, AND INCLUDE PRESSURE SETTING LESS THAN WORKING-PRESSURE RATING OF DOMESTIC-WATER HEATER. SELECT RELIEF VALVE WITH SENSING ELEMENT THAT EXTENDS INTO STORAGE TANK.
- B. DOMESTIC-WATER EXPANSION TANKS:
1. DESCRIPTION: STEEL, PRESSURE-RATED TANK CONSTRUCTED WITH WELDED JOINTS AND FACTORY-INSTALLED, BUTYL-RUBBER DIAPHRAGM. INCLUDE AIR PRECHARGE TO MINIMUM SYSTEM-OPERATING PRESSURE AT 12 PSI.
2. CONSTRUCTION:
- a. TAPPINGS: FACTORY-FABRICATED STEEL, WELDED TO TANK BEFORE TESTING AND LABELING. INCLUDE ASME B1.20.1 PIPE THREAD.
- b. INTERIOR FINISH: COMPLY WITH NSF 61 AND NSF 312 BARRIER MATERIALS FOR POTABLE-WATER TANK LININGS, INCLUDING EXTENDING FINISH INTO AND THROUGH TANK FITTINGS AND OUTLETS.
- c. AIR-CHARGING VALVE: FACTORY-INSTALLED.
3. CAPACITY AND CHARACTERISTICS:
- a. WORKING-PRESSURE RATING: 150 PSIG.
4. INSULATION AND DUCT LINING:
- a. ALL INSULATIONS AND ACCESSORIES SHALL HAVE A FIRE HAZARD CLASSIFICATION WITH A FLAME SPREAD RATING OF NOT OVER 25. FUEL GAS EQUIPMENT SHALL HAVE A FLAME SPREAD RATING OF NOT OVER 50, IN ACCORDANCE WITH NFPA.
- b. PIPE INSULATION - ABOVE GRADE:
- 1) THE PIPING INSULATION USED SHALL HAVE A THERMAL CONDUCTIVITY OF 0.21 BTU PER IN-HR-FT-2 OR LESS.
- 2) FIBERGLASS INSULATION WITH FACTORY APPLIED VAPOR BARRIER. AS JACKET, FACTORY APPLIED PRESSURE SEALING LONGITUDE LAP JOINT, NO STAPLES. ZESTON PREMOULDED PVC FITTING COVERS. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.


MECHANICAL SPECIFICATIONS (CONTINUED)

- SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM D 1105 AND ASTM D 2685. INJECTION MOLDED FITTINGS SHALL CONFORM TO ASTM D 2685. FABRICATED FITTINGS SHALL CONFORM TO ASTM F 1866. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564.
- 4) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 188 AND GBTI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO GBTI STANDARD 310 AND BE CERTIFIED BY NSF INTERNATIONAL.
- 5) HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
- E. SANITARY SEWER, GREASE WASTE AND VENTS (ABOVE GROUND, INTERIOR TO THE BUILDING).
- 1) ABS SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM ABS COMPOUND WITH A CELL CLASS OF 42222 FOR PIPE AND 32222 FOR FITTINGS AS PER ASTM D 3365 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620 FITTINGS SHALL CONFORM TO ASTM D 2688. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2226.
- 2) PVC SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 11432 PER ASTM D 4396 FOR PIPE AND 12454 PER ASTM D 1184 FOR FITTINGS AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620 FITTINGS SHALL CONFORM TO ASTM D 2688. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2226.
- 3) PVC SCHEDULE 40 SOLID WALL PIPE AND DRY FITTING SYSTEM (ASTM D 2685) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 12454 PER ASTM D 1184 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM D 1105 AND ASTM D 2685. INJECTION MOLDED FITTINGS SHALL CONFORM TO ASTM D 2685. FABRICATED FITTINGS SHALL CONFORM TO ASTM F 1866. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564. (WHERE APPROVED BY LOCAL JURISDICTIONS)
- 4) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 188 AND GBTI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO GBTI STANDARD 310 AND BE CERTIFIED BY NSF INTERNATIONAL.
- 5) HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
- F. SANITARY SEWER, GREASE WASTE AND VENTS (UNDERGROUND, EXTERIOR TO THE BUILDING).
- 1) ABS SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM ABS COMPOUND WITH A CELL CLASS OF 42222 FOR PIPE AND 32222 FOR FITTINGS AS PER ASTM D 3365 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620 FITTINGS SHALL CONFORM TO ASTM D 2688. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2226.
- 2) PVC SCHEDULE 40 CELLULAR CORE (FOAM CORE) PIPE AND DRY FITTING SYSTEM (ASTM F1488) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 11432 PER ASTM D 4396 FOR PIPE AND 12454 PER ASTM D 1184 FOR FITTINGS AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 620 FITTINGS SHALL CONFORM TO ASTM D 2688. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2226.
- 3) PVC SCHEDULE 40 SOLID WALL PIPE AND DRY FITTING SYSTEM (ASTM D 2685) PIPE AND FITTINGS SHALL BE MANUFACTURED FROM PVC COMPOUND WITH A CELL CLASS OF 12454 PER ASTM D 1184 AND CONFORM WITH NATIONAL SANITATION FOUNDATION (NSF) STANDARD 14. PIPE SHALL BE IRON PIPE SIZE (IPS) CONFORMING TO ASTM F 734. FITTINGS SHALL CONFORM TO ASTM F 734. SOLVENT CEMENTS SHALL CONFORM TO ASTM D 2564.
- 4) HUBLESS CAST IRON SOIL PIPE AND FITTINGS: HUBLESS CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 188 AND GBTI STANDARD 301. HUBLESS COUPLINGS SHALL CONFORM TO GBTI STANDARD 310 AND BE CERTIFIED BY NSF INTERNATIONAL.
- 5) HUB AND SPIGOT CAST IRON SOIL PIPE AND FITTINGS: HUB AND SPIGOT CAST IRON PIPE AND FITTINGS SHALL BE MANUFACTURED FROM GRAY CAST IRON AND SHALL CONFORM TO ASTM A 14.
- G. COPPER DIV: DRAINAGE TUBE SHALL CONFORM TO ASTM B306, WROUGHT COPPER FITTINGS, ANSI B16.24.
- H. REFRIGERANT:
- 1) DIVY, WROUGHT COPPER, ANSI B16.24 (CONDENSATE INSIDE BUILDINGS).
- 2) POLYETHYLENE GLYCOL (PEG) DIVY PIPE, SCHEDULE 40, SOLVENT JOINT (CONDENSATE ON ROOF).
- 3) POLYETHYLENE GLYCOL (PEG) DIVY PIPE, SCHEDULE 40, SOLVENT JOINT (INDIRECT WASTE).
- 4) DIVY, WROUGHT COPPER, ANSI B16.24 (WATER HEATER TAP, INDIRECT WASTE FROM DISHWASHER/SINKS).
- I. REFRIGERANT:
- 1) ASTM B 280, TYPE ACR, HARD-DRAWN STRAIGHT LENGTHS, AND SOFT-ANNEALED COILS, SEAMLESS COPPER TUBING.
- 2) WROUGHT COPPER, ANSI B16.22, STREAMLINED, PATENTED, BRAZED JOINTS, ANS A 9.9, CLASSIFICATION BAG-1 (SILVER).
- 3) TURNING SHALL BE CLEANED, READY FOR INSTALLATION, AND HAVE ENDS CAPPED TO PROTECT CLEANLINESS OF PIPE INTERIORS PRIOR TO SHIPPING.
- 4) SIZE AND INSTALLATION OF PIPE SHALL BE IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS.
- J. NATURAL GAS:
- 1) BLACK STEEL PIPE, SCHEDULE 40, ASTM A53.
- 2) PIPE 3" AND SMALLER, 150 LB. MALLEABLE IRON, THREADED FITTINGS.
- 3) PIPE 4" AND SMALLER, VERMILION MESSAPRESS 6 FOR WATER AND GAS, CSA L44, TSSA/ASME B31.
- 4) PIPE WITH ASTM A53 SCHEDULE 40 BLACK IRON PIPE.
- 5) PIPE 2-1/2" AND LARGER, KHELDED.
- 6) PLUS VALVE, ROCKWELL NORDSTROM FIGURE NO. 142 OR 143.
- 7) BALL VALVE, JOHAR T-100NE, APPROVALS: UL424, FM, CSA, NSF 61-01, MSS SP-110.
- 8) GAS PIPING PAINTING:
- a) ALL BLACK STEEL, GAS PIPING LOCATED EXTERIOR TO THE BUILDING SHALL BE PRIMED AND PAINTED TO EITHER MATCH ADJACENT EXTERIOR WHERE LOCATED ON OR NEAR EXTERIOR WALL AND PAINTED SAFETY YELLOW WHERE LOCATED ON ROOFS.
- b) ALL PIPE HANGERS AND SUPPORTS SHALL BE STANDARD PRODUCTS OF GRINNELL, FEE AND MASON, OR ELZEN. HANGER SPACING SHALL BE IN ACCORDANCE WITH MSS-SP-69.
- K. SLEEVES
- 1) PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK. ALL SLEEVES SHALL BE OF SUFFICIENT SIZE TO PERMIT PIPE MOVEMENT DUE TO EXPANSION AND CONTRACTION AND TO ACCOMMODATE PIPE INSULATION.
- 2) INTERIOR PARTITIONS: 16 GAUGE GALVANIZED STEEL, PACK BETWEEN PIPE AND SLEEVE WITH FIRE RATING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.
- 3) ROOF: PROSET OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WATERPROOF SEAL. COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF PARCHMENT.
- 4) PROTECTION AGAINST CONTACT: METALLIC FITTINGS, EXCEPT FOR CAST IRON, DUCTILE IRON AND GALVANIZED STEEL SHALL NOT BE PLACED IN DIRECT CONTACT WITH STEEL FRAMING MEMBERS, CONCRETE, OR CINDER WALLS AND FLOORS OR OTHER MASONRY. METALLIC PIPING SHALL NOT BE PLACED IN DIRECT CONTACT WITH CORROSIVE SOILS. SHEATHINGS USED TO PREVENT DIRECT CONTACT SHALL HAVE A THICKNESS OF GREATER THAN 0.028 INCH. SHEATHINGS SHALL BE MADE OF PLASTIC, ANY PIPE THAT PASSES THROUGH A FOUNDATION WALL OR FOOTING SHALL BE PROTECTED WITH A MINIMUM OF 1/2" ABOVE ROOF OR EQUAL TO HEIGHT OF PARAPET, whichever is greater. TERMINATE A MINIMUM OF 12" ABOVE ROOF OR EQUAL TO HEIGHT OF PARAPET, whichever is greater.
- L. PROVIDE CHROME PLATED BRUSHINGS ON ALL PIPE INTERIORS FINISHED AREAS.
- M. WATER HEATERS
- A. COMMERCIAL, LIGHT-DUTY, STORAGE, ELECTRIC, DOMESTIC-WATER HEATERS:
1. STANDARD, UL T14.
2. STORAGE-TANK CONSTRUCTION: STEEL, VERTICAL ARRANGEMENT.
- a. PRESSURE RATING: 150 PSIG.
- b. INTERIOR FINISH: COMPLY WITH NSF 61 AND NSF 312 BARRIER MATERIALS FOR POTABLE-WATER TANK LININGS, INCLUDING EXTENDING LINING MATERIAL INTO TAPPINGS.
3. FACTORY-INSTALLED, STORAGE-TANK APPURTENANCES:
- a. ANODE ROD: REPLACEMENTS WAGNER.
- b. DIP TUBE, REQUIRED UNLESS COLD-WATER INLET IS NEAR BOTTOM OF TANK.
- c. DRAIN VALVE: CORROSION-RESISTANT METAL WITH HOSE-END CONNECTION.
- d. INSULATION: COMPLY WITH ASHRAE/IES 90.1.
- e. JACKET: STEEL WITH ENAMELED FINISH OR HIGH-IMPACT COMPOSITE MATERIAL.
- f. HEAT-TRAP FITTINGS: INLET TYPE IN COLD-WATER INLET AND OUTLET TYPE IN HOT-WATER OUTLET.
- g. HEATING ELEMENTS: ELECTRIC, SCREEN-INTEGRATED, SCREEN-INTEGRATED.
- h. TEMPERATURE CONTROL: ADJUSTABLE THERMOSTAT.
- i. SAFETY CONTROL: HIGH-TEMPERATURE-LIMIT CUTOFF DEVICE OR SYSTEM.
- j. RELIEF VALVE: ASME RATED AND STAMPED FOR COMBINATION TEMPERATURE-AND-PRESSURE RELIEF VALVES, INCLUDING RELIEF CAPACITY AT LEAST AS GREAT AS HEAT INPUT, AND INCLUDE PRESSURE SETTING LESS THAN WORKING-PRESSURE RATING OF DOMESTIC-WATER HEATER. SELECT RELIEF VALVE WITH SENSING ELEMENT THAT EXTENDS INTO STORAGE TANK.
- B. DOMESTIC-WATER EXPANSION TANKS:
1. DESCRIPTION: STEEL, PRESSURE-RATED TANK CONSTRUCTED WITH WELDED JOINTS AND FACTORY-INSTALLED, BUTYL-RUBBER DIAPHRAGM. INCLUDE AIR PRECHARGE TO MINIMUM SYSTEM-OPERATING PRESSURE AT 12 PSI.
2. CONSTRUCTION:
- a. TAPPINGS: FACTORY-FABRICATED STEEL, WELDED TO TANK BEFORE TESTING AND LABELING. INCLUDE ASME B1.20.1 PIPE THREAD.
- b. INTERIOR FINISH: COMPLY WITH NSF 61 AND NSF 312 BARRIER MATERIALS FOR POTABLE-WATER TANK LININGS, INCLUDING EXTENDING FINISH INTO AND THROUGH TANK FITTINGS AND OUTLETS.
- c. AIR-CHARGING VALVE: FACTORY-INSTALLED.
3. CAPACITY AND CHARACTERISTICS:
- a. WORKING-PRESSURE RATING: 150 PSIG.
4. INSULATION AND DUCT LINING:
- a. ALL INSULATIONS AND ACCESSORIES SHALL HAVE A FIRE HAZARD CLASSIFICATION WITH A FLAME SPREAD RATING OF NOT OVER 25. FUEL GAS EQUIPMENT SHALL HAVE A FLAME SPREAD RATING OF NOT OVER 50, IN ACCORDANCE WITH NFPA.
- b. PIPE INSULATION - ABOVE GRADE:
- 1) THE PIPING INSULATION USED SHALL HAVE A THERMAL CONDUCTIVITY OF 0.21 BTU PER IN-HR-FT-2 OR LESS.
- 2) FIBERGLASS INSULATION WITH FACTORY APPLIED VAPOR BARRIER. AS JACKET, FACTORY APPLIED PRESSURE SEALING LONGITUDE LAP JOINT, NO STAPLES. ZESTON PREMOULDED PVC FITTING COVERS. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

MECHANICAL SPECIFICATIONS (CONTINUED)

- 3) FLEXIBLE CLOSED CELL ELASTOMERIC THERMAL INSULATION (UNSLIT OR PRESPLIT WITH PRESSURE SENSITIVE ADHESIVE SYSTEM FOR CLOSURE AND VAPOR SEALING, EQUAL TO ARMSTRONGS AP ARMAFLEX 2000.
- 4) FOR NON-CIRCULATING SYSTEMS, THE FIRST 8 FEET OF INLET AND OUTLET PIPING BETWEEN THE TANK AND THE HEAT TRAP (INCLUDING THE HEAT TRAP) MUST BE INSULATED.
- 5) FOR CIRCULATING SYSTEMS, ALL HOT WATER PIPING IN THE CIRCULATION LOOP MUST BE INSULATED AS SPECIFIED BELOW.
- 6) INSULATION SCHEDULE:
- a) DOMESTIC COLD WATER 1/2"
- b) DOMESTIC HOT WATER 1" FOR PIPING UP TO 1-1/4", 1-1/2" FOR PIPING 1-1/2" AND LARGER
- c) HOT WATER RECIRCULATING 1"
- d) CONDENSATE DRAINS INSIDE BUILDINGS 1/2"
- e) REFRIGERANT SUCT 3/4" FOR PIPING UP TO 1-1/4", 1" FOR PIPING 1-1/2" AND LARGER
- f) HORIZONTAL STORM PIPE 1/2"
- 7) ROOF DRAINS: 1" INSULATION SHALL BE PROVIDED AT ROOF DRAIN BODY AND A MINIMUM OF 10' OF HORIZONTAL PIPING OR A MINIMUM OF 5' IF COMBINATION OF HORIZONTAL AND VERTICAL STORM PIPING DOWNSTREAM OF ROOF DRAIN BODY.
- C. DUCTWORK: ACoustical INSULATION
- 1) DUCT LINING - 2 LB/GF. THICKNESS AS SCHEDULED, AIR STREAM SIDE COATED, INSTALL PER SMACNA STANDARDS.
- 2) DUCT LINING SCHEDULE:
- (1) RECTANGULAR SUPPLY DUCT 1/2" : THROUGHOUT THE FIRST 10 FEET OF DUCT.
- (2) RETURN AIR DUCT 1/2" : THROUGHOUT THE FIRST 10 FEET OF DUCT.
- D. DUCTWORK: THERMAL INSULATION
- 1) DUCT COVERING: 3/4 LB/GF. FIBERGLASS BLANKET WITH FACTORY APPLIED VAPOR BARRIER AND FACING, THICKNESS AS SCHEDULED, INSTALLATION IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS.
- 2) DUCT COVERING SCHEDULE: MINIMUM R-6
- (1) ROUND SUPPLY DUCT 2"
- (2) RECTANGULAR SUPPLY DUCT 2"
- (3) RETURN AIR DUCT 2"
- I. DUCTWORK:
- A. ALL DUCTWORK, UNLESS OTHERWISE INDICATED, SHALL BE FABRICATED FROM GALVANIZED SHEET STEEL COMPLYING WITH ASTM A 521, CONFORMING QUALITY, WITH 5 TO 20 ZINC COATINGS IN ACCORDANCE WITH ASTM A 525, AND MILL PHOSPHATIZED FOR EXPOSED LOCATIONS.
- B. WHERE DUCTWORK IS INDICATED TO BE EXPOSED TO VIEW IN OCCUPIED SPACES, PROVIDE MATERIALS WHICH ARE FREE FROM VISUAL IMPERFECTIONS INCLUDING PITTING, SEAM MARKS, ROLLER MARKS, STAINS AND DISCOLORATIONS, AND OTHER IMPERFECTIONS, INCLUDING THOSE WHICH WOULD IMPAIR PAINTING.
- C. DUCTWORK: METAL GAUGES, REINFORCING, ETC. SHALL BE CONSTRUCTED IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS," LATEST EDITION FOR A 2 INCH WATER GAUGE STATIC PRESSURE.
- 1) RECTANGULAR DUCT:
- a) ELBOWS, UNLESS INDICATED OTHERWISE SHALL BE CONSTRUCTED WITH CENTERLINE RADIUS OF NOT LESS THAN 1.5 DUCT WIDTH OR SQUARE ELBOW WITH DOUBLE WALL STREAMLINE VANES.
- b) RETURN AIR ACoustICAL EDGES AND SOUND BOOTS SHALL BE A SQUARE ELBOW WITH NO TURNING VANES.
- c) SLOPES FOR TRANSITIONS OR OTHER CHANGES IN DIMENSIONS SHALL BE MINIMUM 1 TO 3.
- 2) ROUND AND OVAL SPIRAL SEAM DUCT:
- a) PROVIDE RADUS TYPE FITTINGS FABRICATED OF MULTIPLE SECTIONS WITH MAXIMUM 15 DEGREE CHANGE OF DIRECTION PER SECTION, UNLESS SPECIFICALLY DETAILED OTHERWISE. USE 45 DEGREE LATERAL TRANSITION FOR BRANCHED TAKEOFF CONNECTIONS. WHERE 45 DEGREE BRANCHES ARE INDICATED PROVIDE CONICAL TYPE TEES.
- b) SLOPES FOR TRANSITIONS OR OTHER CHANGES IN DIMENSIONS SHALL BE MINIMUM 1 TO 3.
- c) AS AN OPTION, PROVIDE FACTORY-FABRICATED DUCT AND FITTINGS, IN LINE OF SHOP-FABRICATED DUCT AND FITTINGS.
- (1) ELBOWS: ONE PIECE CONSTRUCTION FOR 40 DEGREES AND 45 DEGREE ELBOW 14" AND SMALLER. PROVIDE MULTIPLE GORE CONSTRUCTION FOR LARGER DIAMETERS WITH STANDING SEAM CIRCUMFERENTIAL JOINT.
- (2) DIVIDED FLOW FITTINGS: 90 DEGREE TEES, CONSTRUCTED WITH SADDLE TAP SPOT WELDED AND BONDED TO DUCT FITTING BODY.
- d) ROUND LONGITUDINAL SEAM DUCT: USE FOR RIGID METAL DUCT ON LEAVING SIDE OF DUCT IN CONCEALED LOCATIONS FOR EXTENSION TO FLEX FOR DIFFUSERS, UNLESS OTHERWISE INDICATED.
- D. DUCT SIZES SHOWN ON THE DRAWINGS ARE SHEETMETAL SIZES, ALLOWANCE FOR DUCT LINER HAS BEEN MADE WHERE APPLICABLE.
- E. INSTALLATION OF METAL DUCTWORK:
- 1) GENERAL: ASSEMBLE AND INSTALL DUCTWORK IN ACCORDANCE WITH RECOGNIZED INDUSTRY PRACTICES WHICH WILL ACHIEVE AIR-TIGHT SYSTEMS (MAXIMUM 3% LEAKAGE), WITH NO DISCRETELY LOCATED LEAKS OR NOTATIONS OR, IF NOT OTHERWISE INDICATED, RUN DUCTWORK IN SHORTEST ROUTE WHICH DOES NOT OBSTRUCT USABLE SPACE OR BLOCK ACCESS FOR SERVICES BUILDINGS AND ITS EDGES SHALL BE WELDED TO WALLS, OVERHEAD CONDUITS, COLUMNS, AND OTHER STRUCTURAL AND PERMANENT ENCLOSURE ELEMENTS OF BUILDING, WHEREVER NOTED IN FINISHED AND OCCUPIED SPACES, CONCEAL DUCTWORK FROM VIEW BY LOCATING IN MECHANICAL SHUTTS, HOLLOW WALL CONSTRUCTION OR ABOVE SUSPENDED CEILING. DO NOT EXPOSE HORIZONTAL RUNS IN SOLID PARTITIONS, EXCEPT AS SPECIFICALLY SHOWN. COORDINATE LAYOUT WITH SUSPENDED CEILING AND LIGHTING LAYOUTS AND SIMILAR FINISHED WORK.
- 2) DO NOT ROUTE DUCTWORK THROUGH ELECTRICAL EQUIPMENT SPACES AND ENCLOSURES, UNLESS INDICATED OTHERWISE.
- 3) PENETRATIONS:
- a) WHERE DUCTS PASS THROUGH INTERIOR PARTITIONS OR EXTERIOR WALLS, AND ARE EXPOSED TO VIEW, CONCEAL SPACE BETWEEN OPENINGS AND DUCT OR DUCT INSULATION WITH SHEET METAL FLANGES OF SAME GAGE AS DUCT. OVERLAP OPENING ON 4 SIDES BY AT LEAST 1-1/2". FASTEN TO DUCT AND WALL.
- b) WHERE DUCTS PASS THROUGH FIRE-RATED FLOORS, WALLS, OR PARTITIONS, PROVIDE FIRESTOPPING BETWEEN DUCT AND WALL.
- 6) COORDINATION: COORDINATE DUCT INSTALLATIONS WITH INSTALLATION OF ACCESSORIES, DAMPERS, COIL FRAMES, EQUIPMENT, CONTROLS, AND OTHER ASSOCIATED WORK OF THE DUCTWORK SYSTEM.
- 7) INSTALLATION: INSTALL METAL DUCTWORK IN ACCORDANCE WITH SMACNA "HVAC DUCT CONSTRUCTION STANDARDS," LATEST EDITION.
- F. EQUIPMENT CONNECTIONS:
- 1) CONNECT METAL DUCTWORK TO EQUIPMENT AS INDICATED, PROVIDE FLEXIBLE CONNECTION FOR EACH DUCTWORK CONNECTION TO EQUIPMENT MOUNTED ON VIBRATION ISOLATORS, AND/OR EQUIPMENT CONTAINING ROTARY MACHINERY. PROVIDE ACCESS WAGNERS.
- 2) SEAL ALL CONCEALED DUCTWORK JOINTS WITH NON-HARDENING, NON-MIGRATING MASTIC SEALANT, AS RECOMMENDED FOR SEALING SEAMS IN DUCTWORK. GUM-BASE CAULKING AND GLAZING COMPOUNDS SHALL NOT BE ACCEPTABLE. DUCTS SHALL BE

LAST FILE LOCATION: N:\2022\22823\PLBG\22823P.DWG
SHEET FILE LOCATION: N:\2022\22823\PLBG\22823P.DWG
BY: SUNIL
1/11/2023 2:27 PM



PLUMBING PLAN NOTES:

- REFER TO CIVIL PLAN FOR CONTINUATION OF 4" SANITARY WASTE PIPING. MAINTAIN MINIMUM 30" COVER.
- ROUTE 4" GREASE PIPING OUTSIDE OF THE FOUNDATION WALL AND CONNECT TO GREASE INTERCEPTOR. MAINTAIN MINIMUM 30" COVER.
- 2" VENT MINIMUM 24" BELOW GRADE.
- LOCATION OF 4" VTR. VERIFY 10' CLEARANCE FROM ALL OUTDOOR AIR INTAKES. SEAL PENETRATION WEATHERTIGHT.
- ROUTE (3) SEPARATE 1-1/2" DRAINS FROM 3-COMPARTMENT SINK TO FLOOR SINK WITH AIR GAPS. LOCATE FLOOR SINK IN AN ACCESSIBLE LOCATION.
- ROUTE DRAIN FROM ICE MACHINE / COFFEE MACHINE & BEVERAGE DISPENSER TO FLOOR SINK WITH AIR GAP, AND PER THE MANUFACTURERS REQUIREMENTS. ROUTE CONDENSATE SEPARATELY TO FLOOR SINK.
- PROVIDE 1" CONDENSATE DRAIN FROM THE WALK IN COOLER / FREEZER EVAPORATOR TO THE FLOOR SINK. DISCHARGE THROUGH AN AIR GAP. SLOPE CONDENSATE DRAIN A MINIMUM OF 1/4" PER FOOT. HOLD EXPOSED CONDENSATE DRAIN IN WALK IN COOLER AS HIGH AS POSSIBLE. COORDINATE WITH ELECTRICAL FOR HEAT TRACING IN FREEZER.
- PROVIDE TRAP SEAL ON FLOOR DRAINS SUSCEPTIBLE TO DRYING OUT.
- PROVIDE WATER HEATER T&P DRAIN PIPE. ROUTE DRAIN PIPE DOWN AND DISCHARGE TO MOP SINK.
- NO COMBUSTIBLE MATERIALS WITHIN 18" OF TYPE I HOOD.
- ROUTE 1" CONDENSATE DRAIN FROM ROOF TOP UNIT TO NEAREST ROOF DRAIN / SCUPPER AS REQUIRED AND AS DETAILED.
- ROUTE DRAIN FROM RPZ BFP TO FLOOR SINK DRAIN WITH AN AIR GAP.
- ROUTE STORM DRAIN PIPE DOWN TO BELOW FLOOR, PROVIDE CLEANOUT AT BASE OF RISER.
- SEE CIVIL FOR CONTINUATION OF STORM DRAIN PIPING. MAINTAIN 30" COVER.
- INSTALL DOWN SPOUT 18" ABOVE GRADE. SEAL PENETRATION WEATHER TIGHT.



WASTE & VENT PLAN
SCALE: 1/4" = 1'-0"
FFE = 981.10

PLUMBING GENERAL NOTES:

- INSTALL ALL PIPE, ETC. AS HIGH AS POSSIBLE.
- COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
- REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATIONS AND MOUNTING HEIGHTS OF FIXTURES.
- REFER TO ARCHITECTURAL & STRUCTURAL DRAWINGS FOR REQUIREMENTS FOR SUPPORTING PIPING, EQUIPMENT, ETC. FROM THE STRUCTURE. PROVIDE ADDITIONAL STEEL AS REQUIRED TO PROPERLY SUPPORT SYSTEMS FROM THE STRUCTURE.
- PROVIDE 1" SCHEDULE 40 PVC CONDENSATE DRAIN PIPE FOR EACH ROOFTOP UNIT LAID DIRECTLY ON ROOF TO NEAREST ROOF DRAIN. PROVIDE WATER TRAP AND CLEAN OUTS AS DETAILED. SECURE PVC PIPE TO DRAIN WITH NYLON STRAP.
- NO PIPING SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
- CONTRACTOR TO TEST WATER PRESSURE ON SITE AND PROVIDE PRESSURE REDUCING VALVE ON WATER SERVICE IF PRESSURE IS OVER 80 PSI.

PLUMBING FIXTURE BRANCH PIPING SCHEDULE

FIXTURE	WASTE	VENT	CW	HW
WATER CLOSET (TANK TYPE)	4"	2"	1/2"	-
LAVATORY	1-1/4"	1-1/4"	1/2"	1/2"
HAND SINK				
MOP BASIN	2"	2"	3/4"	3/4"
FLOOR DRAIN	2"	2"	-	-
FLOOR SINK	3"	2"	-	-
FP WALL HYDRANT	-	-	3/4"	-

NOTE: INDIVIDUAL VENTS FOR FIXTURES ON PLANS AND RISER DIAGRAMS HAVE BEEN INCREASED WHERE HORIZONTAL VENT LENGTH IS IN EXCESS OF THE MAXIMUM DISTANCE INDICATED BY THE CODE.

PLUMBING DRAINAGE CALCULATIONS

FIXTURE	QUANTITY	FU	TOTAL FU
WATER CLOSET	3	4	12
LAVATORIES	4	1	4
URINAL	2	4	8
HAND SINK	1	1	1
3 COMP. SINK	1	2	2
MOP SINK	1	2	2
FLOOR DRAIN	5	2	10
FLOOR SINK	7	2	14
TOTAL			53
VENT MAINS - 4"			
WASTE MAIN - 4"			

* = COMBINATION WASTE & VENT DRAIN

GREASE INTERCEPTOR CALCULATIONS

Reference No. 45226 Project Name: Heartland Market

Step 1: Flow rate to grease interceptor

Fixture flow rate: (cu in / 231) = gal x 0.75 / 2 min = 2 min flow rate

NAME	TYPE	DIMENSIONS	QTY	CU IN	FLOW RATE
3CS	3 Compartment Sink	21" x 21" x 14" (3)	1	18,522	30 GPM
FD	Floor Drain	N/A	1	N/A	N/A
MB	Mop Basin	24" x 24" x 10"	1	5,760	9.35 GPM
Total					39.35 GPM

Step 2: Grease Production

Number of Seats x 4 turns per seat x Grease Production Value x Days between pump-out = Grease output

Number of seats in facility: 16

Grease production value: 0.025 lbs per serving (Convenience Store: Medium / No flatware)

Days between pump-outs: 90 days

16 x 4 x 0.025 x 90 = 144 lbs of FOG

SCHIER MODEL

GB-50

Description: Polyethylene Grease Interceptor
Dimensions: Length: 37", Width: 32.25", Height: 28.5"
Flow Rates/Grease Capacities: 50 GPM / 439.5 lbs
Liquid Capacity: 65 gal

BC

ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

4/28/2023



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
WASTE & VENT PLAN

P100

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.

PE COA #2009003629

4/28/2023

PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI


BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
WATER & GAS PLAN

P101

**PLUMBING PLAN NOTES:**

- REFER TO CIVIL PLAN FOR CONTINUATION OF DOMESTIC WATER LINE. MAINTAIN 48" MINIMUM COVER.
- PROVIDE NEW DOMESTIC WATER LINE WITH SHUT OFF VALVE AND REDUCED PRESSURE ZONE BACKFLOW PREVENTER INSIDE OF THE BUILDING. INSTALL 24" A.T.F. & 6" FROM WALL. ROUTE DRAIN FROM RPZ BFP TO FLOOR SINK DRAIN WITH AN AIR GAP.
- PROVIDE ELECTRIC WATER HEATER MOUNTED ABOVE MOP BASIN. MAKE HOT AND COLD WATER PIPING CONNECTIONS THROUGH DIELECTRIC UNIONS. PROVIDE AND INSTALL ALL HARDWARE AND APPURTENANCES FOR COMPLETE INSTALLATION PER APPLICABLE CODES AND MANUFACTURER'S RECOMMENDATIONS. PROVIDE THERMAL EXPANSION TANK.
- ROUTE PIPING ON INTERIOR SIDE OF WALL FOR FREEZE PROTECTION.
- ROUTE 3/4" CW DOWN TO FREEZE PROOF WALL HYDRANT MOUNTED AT 18" ABOVE GRADE. SEAL PENETRATION WEATHERTIGHT.
- CONNECT HOT WATER REGR. PIPING BACK TO WATER HEATER AS REQUIRED. REFER TO RISER DIAGRAM FOR MORE INFORMATION.
- COORDINATE WITH GAS COMPANY FOR INSTALLATION OF A METER WITH CAPACITY FOR 683 CFH @ 7" W.C. ROUTE PIPING UP INSIDE THE EXTERIOR WALL. ALL CONCEALED JOINTS ARE TO BE WELDED OR USE FITTINGS APPROVED FOR CONCEALED JOINTS. VERIFY ALL EQUIPMENT GAS CAPACITIES AND OPERATING PRESSURE PRIOR TO INSTALLATION OF ANY PIPING.
- INSTALL GAS PIPING ON ROOF. SUPPORT AS REQUIRED AND AS DETAILED.
- CONNECT GAS PIPING TO ROOF TOP UNIT AS DETAILED AND PER THE MANUFACTURERS INSTRUCTIONS.
- PROVIDE RPZ BACK FLOW PREVENTER FOR CONNECTION TO FOUNTAIN SODA SYSTEM. NO COPPER PIPING IS ALLOWED DOWNSTREAM OF BACK FLOW PREVENTER TO CARBONATOR & SODA SYSTEM.

**STORE - DOMESTIC WATER & NATURAL GAS PLAN**

SCALE: 1/4" = 1'-0"

PLUMBING FIXTURE WATER COUNT							
FIXTURE	QUANTITY	CM FU	CM TOTAL FU	HW FU	HW TOTAL FU	COMBINED FU	COMBINED TOTAL FU
WATER CLOSET	3	5	15	0	0	5	15
URINAL	2	5	10	0	0	5	10
LAVATORIES	4	1.5	6	1.5	6	2	8
HAND SINK	1	1.5	1.5	1.5	1.5	2	3
3 COMP SINK	1	2.25	2.25	2.25	2.25	3	3
MOP SINK	1	2.25	2.25	2.25	2.25	3	3
ICE & BEV. DISPENSER	3	0.5	1.5	0	0	0.5	1.5
COFFEE MACHINE	1	0.25	0.25	0	0	0.25	0.25
BLENDER	1	0.25	0.25	0	0	0.25	0.25
FP WALL HYDRANT	2	2.5	5	0	0	2.5	5
			44 FU		12 FU		48 FU
COLD WATER MAIN - 1-1/4" HOT WATER MAIN - 3/4"							

PEX PIPING REQUIREMENTS

PIPE SIZES GIVEN ON THE DRAWINGS ARE NOMINAL COPPER PIPE SIZE. IF PEX PIPING IS USED, INCREASE PEX PIPING ONE SIZE ABOVE LISTED SIZES AS REQUIRED TO EQUAL OR EXCEED COPPER PIPE INSIDE DIAMETER.

GAS DEMAND SCHEDULE			
EQUIPMENT		GAS INPUT (BTU/H)	
SN	ITEM	NEW	EXISTING
1	ROOF TOP UNIT -1	180,000	
2	ROOF TOP UNIT -2	180,000	
3	ROOF TOP UNIT -3	180,000	
4	MAKE UP AIR UNIT -1	143,000	
TOTAL BTU/HR		683,000	0
NEW TOTAL BTU/HR (EXISTING AND NEW)		683,000	
NEW TOTAL CFH (EXISTING AND NEW)		683	
MAXIMUM DEVELOPMENT LENGTH >		125FT	
MINIMUM SIZE OF GAS LINE REQUIRED		2" DIA.	
NOTE GAS LINE SIZED AS PER TABLE 402.4(2) OF IFGC FOR PRESSURE OF 7" W.C. AND SPECIFIC GRAVITY OF NATURAL GAS TO BE 0.6			

PLUMBING FIXTURE SCHEDULE:



HWC	HANDICAP WATER CLOSET: TOTO, #CST144EL/R/N, "DRAKE CLOSE COUPLED TOILET", 1.28 GALLON FLUSH, 16-1/2" HIGH ELONGATED BOWL, FLOOR MOUNTED, FLOOR OUTLET, TANK TYPE, VITREOUS CHINA, SIPHON-JET ACTION, #C834 OPEN FRONT SEAT WITH CHECK HINGE AND LESS COVER, CHROME PLATED ANGLE STOP AND RISER. HANDLE ON WIDE SIDE OF FIXTURE.
WC	WATER CLOSET: TOTO, #CST144S, "DRAKE CLOSE COUPLED TOILET", 1.6 GALLON FLUSH, ELONGATED BOWL, FLOOR MOUNTED, FLOOR OUTLET, TANK TYPE WITH LOCKING LID, VITREOUS CHINA, SIPHON-JET ACTION, #C834 OPEN FRONT SEAT WITH CHECK HINGE AND LESS COVER, CHROME PLATED ANGLE STOP AND RISER.
UI	URINAL, WALL HUNG: TOTO, #UT447.01, VITREOUS CHINA, WASH OUT, WALL HUNG URINAL WITH 3/4" TOP SPUD, #TMUINNG-12 FLUSH VALVE, FLOOR MOUNTED FIXTURE SUPPORT. SET RIM HEIGHT PER ARCHITECTURAL DRAWINGS.
LI	HANDICAP LAVATORY, WALL HUNG: TOTO #LT307, 20" x 18", VITREOUS CHINA, FRONT OVERFLOW, DELTA #501 FAUCET WITH SINGLE METAL LEVER FAUCET, OFFSET GRID ELBOW DRAIN AND 1-1/4" TAILPIECE, CHROME PLATED CAST BRASS P-TRAP WITH CLEANOUT (MOUNTED PARALLEL WITH WALL), CHROME PLATED LOOSE KEY ANGLE STOPS AND RISERS, FLOOR MOUNTED CONCEALED ARM LAVATORY SUPPORT, INSULATE EXPOSED DRAIN, WATER SUPPLIES, AND VALVES WITH FROWRAP SEAMLESS MOLDED CLOSED CELL VINYL INSULATION.
* HS	HAND SINK: ELKAY GHS-1716-C STAINLESS STEEL HAND SINK, T" BACKSPASH, FURNISHED COMPLETE WITH WALL HANGER, INTEGRAL SUPPORT BRACKETS, LK-499CHROME PLATED GOOSENECK SPOUT FAUCET WITH AERATOR, LK-8 DRAIN, LK-500 P-TRAP WITH CLEANOUT, WASTE ARM TO WALL, AND WALL FLANGE. PROVIDE CHROME PLATED ANGLE STOPS AND RISERS.
MB	MOP BASIN: FIAT, #MSB-2424, MOLDED STONE MOP BASIN, 2" DRAIN, 24" x 24" BASIN, VINYL BUMPER GUARD, STERN WILLIAMS #T-10-VB FAUCET, SPRINGS, CHECKS, VACUUM BREAKER, INTEGRAL STOPS, WALL BRACE & PAIL HOOK, WALL BRACKET WITH 30' HOSE.
FD	FLOOR DRAIN: SIOUX CHIEF, #842, PVC FLOOR DRAIN WITH ADJUSTABLE TOP AND CAST BRASS STRAINER. PROVIDE WITH #2692 QUAD CLOSE TRAP SEAL DEVICE.
FD1	FLOOR DRAIN: JR SMITH, #2005-F37, CAST IRON FLOOR DRAIN WITH RECESSED 6" NIKALOY STRAINER. PROVIDE WITH #2692 QUAD CLOSE TRAP SEAL DEVICE.
FS	FLOOR SINK: SIOUX CHIEF, #861 SQUARE PVC FLOOR SINK WITH STAINLESS STEEL MESH DEBRIS SCREEN, PVC HALF OPEN STRAINER.
HWH	HOT WATER HEATER: AO SMITH #DEL-40, 40 GALLON STORAGE, 208 VOLT, 1 PHASE, 5KW ELEMENT, NON SIMULTANEOUS, SINGLE ELEMENT OPERATION, 34 GALLON RECOVERY RATE, ASME TEMPERATURE AND PRESSURE RELIEF VALVE. PROVIDE HOLD RITE 50-SNHP-A WATER HEATER SHELF.
ET	HOT WATER EXPANSION TANK: AMTROL, #5T-5, 2 GALLON EXPANSION TANK WITH DIAPHRAGM.
RCP	HOT WATER RECIRCULATING PUMP: BELL & GOSSETT, #SERIES NBF-10, 3 GPM @ 7 FT. HEAD, 1/12 HP, 120 VOLT, WITH HONEYWELL #L6006C1018 AQUASTAT & TAGO #265-3 7 DAY DIGITAL TIMER, 120° - 125°F, 1/2" Ø PIPE.
* 3CS	3-COMPARTMENT SINK: REGENCY 600531014216 66" 16-GAUGE STAINLESS STEEL SINK, (3) 10" x 14" x 12" DEEP BOWLS, LEFT AND RIGHT 16" DRAINBOARDS, PROVIDE (3) 1-1/2" ROTARY OPERATED DRAINS WITH TAILPIECES, 2" WASTE MANIFOLD PIPING, CHROME PLATED ANGLE STOPS AND RISERS, WALL MOUNTED PRE RINSE FAUCET.
MY	MIXING VALVE: WATTS, #LFUS-B, THERMOSTATIC CONTROLLED MIXING VALVE, LEAD FREE BRONZE BODY, LOCKED TEMPERATURE ADJUSTMENT CAP (VANDAL RESISTANT), COPPER ENCAPSULATED THERMOSTAT ASSEMBLY WITH BRASS SHUTTLE, STAINLESSSTEEL SPRINGS, INTEGRAL CHECK VALVES ON HOT AND COLD INLETS. (SET TO 110°F). ASSE 1070 LISTED.
MV1	MIXING VALVE: WATTS, LFMMV THERMOSTATIC CONTROLLED MIXING VALVE, LEAD FREE BRONZE BODY, LOCKED TEMPERATURE ADJUSTMENT CAP (VANDAL RESISTANT), SOLID MAX HYDRAULIC PRINCIPLE THERMOSTAT, INTEGRAL FILTER WASHERS AND CHECK VALVES ON HOT AND COLD INLETS. (SET TO 110°F) ASSE #1017, #1069, #1070
BFP	BACKFLOW PREVENTOR: WATTS #SD-3, DUAL CHECK VALVE WITH ATMOSPHERIC PORT & STRAINER FOR CARBONATED BEVERAGE MACHINES
RPZ	REDUCED ZONE PRESSURE BACKFLOW PREVENTOR (FOR BAS IN BOX): WATTS #LF009, LEAD FREE BRONZE BODY CONSTRUCTION, TWO, IN-LINE INDEPENDENT CHECK VALVES, REPLACEABLE CHECK SEATS WITH AN INTERMEDIATE RELIEF VALVE, AND BALL VALVE TEST COCKS.
RPZ-1 RPZ-2	REDUCED ZONE PRESSURE BACKFLOW PREVENTOR: WATTS #LF009, LEAD FREE BRONZE BODY CONSTRUCTION, TWO, IN-LINE INDEPENDENT CHECK VALVES, REPLACEABLE CHECK SEATS WITH AN INTERMEDIATE RELIEF VALVE, AND BALL VALVE TEST COCKS, REQUIRED QUANTITY 2, ONE FOR DOMESTIC WATER LINE AND ONE FOR IRRIGATION SYSTEM. SEE PLAN FOR SIZES.
FPVH	FREEZEPROOF WALL HYDRANT: WOODFORD #17, 3/4" HOSE NOZZLE OUTLET, BRASS FACE, HANDWHEEL OPERATED, INTEGRAL VACUUM BREAKER.
NH	WATER HAMMER ARRESTOR: JR SMITH 'HYDROTROL' #5000 LEAD-FREE WATER HAMMER ARRESTOR, SIZED AS PER MANUFACTURER'S RECOMMENDATIONS.
GI	GREASE INTERCEPTOR: SCHIER MODEL #GB50, POLYETHYLENE GREASE INTERCEPTOR, 37" LENGTH, 32.25" WIDTH & 28.5" HEIGHT 50 GPM FLOW RATE, 439.5 LB. GREASE CAPACITY AND 65 GALLON LIQUID CAPACITY. PROVIDE ASSOCIATED PIPING PER CODE REQUIREMENTS. PROVIDE 4" INLET AND OUTLET, FIELD CUT RISER AND CAST IRON COVER.
RD	ROOF DRAIN: WATTS #RD-300-R, CAST IRON BODY, FLASHING CLAMP, GRAVEL STOP, UNDERDECK CLAMP, SUMP RECEIVER, AND DUCTILE IRON DOME.
ORD	OVERFLOW DRAIN: WATTS #RD300-M, CAST IRON BODY, FLASHING CLAMP, GRAVEL STOP, UNDERDECK CLAMP, SUMP RECEIVER, DUCTILE IRON DOME, AND 2' HIGH WATER DAM.
DS	DOWN SPOUT NOZZLE: WATTS #RD-40, CAST BRONZE, NICKEL BRONZE FINISH, WALL FLANGE.
FCO/MCO	VINYL TILE FLOOR: JR SMITH #4140, OR EQUAL. QUARRY TILE FLOOR: JR SMITH #4200, OR EQUAL. CARPETED FLOOR: JR SMITH #4020-Y, OR EQUAL. UNFINISHED FLOOR: JR SMITH #4020, OR EQUAL. WALL: JR SMITH #4472, OR EQUAL, 24" ABOVE THE FLOOR.

* COORDINATE WITH G.C. AND OWNER FOR EQUIPMENT THAT MAY BE PROVIDED BY OTHERS.


PLUMBING SYMBOLS

— — —	SOIL AND WASTE PIPING BELOW FLOOR/GRADE
— — —	SOIL AND WASTE PIPING ABOVE FLOOR/GRADE
— KR —	GREASE WASTE PIPING TO GREASE INTERCEPTOR
— —V— —	SANITARY VENT PIPING ABOVE GRADE
— —V— —	SANITARY VENT PIPING BELOW GRADE
— ST — —	STORM PIPING BELOW FLOOR/GRADE
— ST — —	STORM PIPING ABOVE FLOOR/GRADE
— SO — —	STORM OVERFLOW PIPING ABOVE FLOOR/GRADE
— — — —	DOMESTIC COLD WATER PIPING
— — — —	DOMESTIC HOT WATER PIPING
— — — —	DOMESTIC HOT WATER RECIRCULATION PIPING
— G — —	GAS PIPING
— —G— —	UNDER GROUND GAS PIPING
— D — —	EQUIPMENT DRAIN LINE
— — — —	PIPING TURNING DOWN
— — — —	PIPING TURNING UP
— — — —	TEE TOP CONNECTION
— — — —	UNION
— — — —	BACKFLOW PREVENTER
— — — —	FLOOR DRAIN
FCO	FLOOR CLEAN OUT
MCO	WALL CLEAN OUT
GCO	GRADE CLEAN OUT
— — — —	VALVE
— — — —	BALANCING VALVE
— — — —	SOLENOID VALVE
— — — —	PRESSURE REGULATOR
— — — —	CHECK VALVE
— — — —	CONNECT TO EXISTING
I.E.	INVERT ELEVATION OF PIPE
— — — —	MATCH MARKS ON PLUMBING RISER DIAGRAM
— — — —	CHECK VALVE
— — — —	THERMOMETER
— — — —	PRESSURE GAUGE
— — — —	TEMPERATURE AND PRESSURE RELIEF VALVE



- Notes:
- 4" FPT Inlet/outlet with 4" plain end adapters, single inlet and triple outlet.
 - Unit weight - w/ cast iron cover: 148 lbs. (For wet weight add 542 lbs.)
 - Maximum operating temperature: 150° F continuous
 - Capacities - Liquid: 65 gal.
Grease: 439.5 lbs. (60 gal.) @50 GPM
Solids: 13 gal.
 - For gravity drainage applications only.
 - Do not use for pressure applications.
 - Cover placement allows full access to tank for proper maintenance.
 - Vent not required unless per local code.
 - Engineered inlet and outlet diffusers with inspection ports are removable to inspect / clean piping.
 - Integral air relief / Anti-siphon / Sampling access.
 - Adjustable cover adapter provides up to 4" of additional height.
 - Designed for below-grade, above-grade, indoor or outdoor installations.
 - Safety Start®, access restrictor built into cover adapter, prevents accidental entry to tank (450 lb rating).



GREASE INTERCEPTOR DETAIL
SCALE: NONE



CONDENSATE DRAIN DETAIL (INSIDE)
SCALE: NONE



PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
PLUMBING SCHEDULE & DETAIL

P200

BC
ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

4/28/2023

STATE OF MISSOURI
REGISTERED PROFESSIONAL ENGINEER
BRIAN A. QUISSELL
NUMBER
PE-2004000829

This drawing has been prepared by the Engineer, or under his supervision. This drawings is provided for the use of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all the ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing on this drawing, are the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Designer/Engineer is strictly prohibited.

© 2022 BC Engineers, Inc.

PE COA #2009003629

4/28/2023



PROJECT FOR:

HEARTLAND AND MARKET

LEE SUMMIT, MISSOURI




BC PROJECT #: 22823


ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
PLUMBING RISER DIAGRAMS

P201





MECHANICAL SYMBOLS

	NEW SUPPLY DIFFUSER
	NEW RETURN AIR GRILLE
	EXHAUST GRILLE/FAN
	THERMOSTAT, MOUNTED AT 48" AFF
	DUCT-MOUNTED SMOKE DETECTOR
	MOTORIZED DAMPER/LOUVER
	NEW DUCTWORK
	SIZE OF RECTANGULAR DUCT
	SIZE OF ROUND DUCT
	FLEXIBLE DUCTWORK
	FLEXIBLE CONNECTION TO FAN
	FLOOR PLAN NOTE DESIGNATION
	S.A. SUPPLY AIR
	R.A. RETURN AIR
	EXHAUST AIR
	TRANSITION IN DUCT SIZE
	ELBOW WITH TURNING VANES
	MANUAL VOLUME DAMPER
	MANUAL VOLUME DAMPER
	MOTORIZED CONTROL DAMPER
	SUPPLY AIR DUCT UP/DOWN
	RETURN AIR DUCT UP/DOWN
	EXHAUST AIR DUCT UP/DOWN
	CHANGE IN ELEVATION UP (UP) DOWN (DN) IN DIRECTION OF FLOW
	SCHEDULED MECHANICAL EQUIPMENT

MECHANICAL PLAN NOTES:

- PROVIDE CONCEALED SUPPLY AND RETURN DUCTWORK, TYPICAL FOR ALL UNIT. ROUTE DUCTWORK UP HIGH AND SUPPORT FROM THE STRUCTURE. PROVIDE TRANSITION AS REQUIRED TO INSTALL DUCTWORK BETWEEN JOISTS.
- PROVIDE CEILING MOUNTED LAY IN SUPPLY DIFFUSER AS DETAILED.
- PROVIDE RETURN GRILLES ON BOTH SIDE OF THE MALL FOR TRANSFER OF RETURN AIR. MOUNT RETURN GRILL AT 7'-6" AFF.
- PROVIDE SINGLE PACKAGED ROOF TOP HVAC UNIT AS SHOWN ON THE PLAN. INSTALLATION OF EQUIPMENT SHALL COMPLY WITH EQUIPMENT MANUFACTURER'S INSTALLATION AND CLEARANCE REQUIREMENTS TO ALLOW FOR INSPECTION, SERVICE, REPAIR OR REPLACEMENT. FRESH AIR INTAKE OF THE ROOF TOP HVAC UNIT SHALL BE LOCATED A MINIMUM OF 10 FOOT FROM VENT THRU ROOF, FLUES AND EXHAUST FANS.
- PROVIDE CEILING MOUNTED EXHAUST FAN WITH INTEGRAL BACKDRAFT DAMPER. ROUTE DUCTWORK UP AND TERMINATE THROUGH ROOF. SUPPORT UNIT FROM STRUCTURE AS REQUIRED BY THE MANUFACTURER.
- ROUTE 10"Ø EXHAUST DUCT UP TO ROOF. PROVIDE ROOF CAP. ENSURE MIN. 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES. MIN. 10" AFF.
- PROVIDE 1 DAY PROGRAMMABLE THERMOSTAT WITH CONTROL FOR HEATING & COOLING. MOUNT 48" ABOVE THE FINISHED FLOOR.
- PROVIDE DUCT MOUNTED SMOKE DETECTOR FOR HVAC UNIT THAT ARE GREATER THAN 2000 CFM. IN COMPLIANCE WITH IMC SECTION 606 AND NFPA 72. PROVIDE REMOTE ANNUNCIATOR AND LOCATE AS PER AHJ.
- LOCATION OF WALK IN COOLER / FREEZER REMOTE CONDENSER. SUPPORT CONDENSING UNIT FROM ROOF AS DETAILED. CONNECT REFRIGERANT PIPING TO CONDENSING UNIT AS REQUIRED. RECHARGE LINES AS REQUIRED. INSTALL PIPING AS RECOMMENDED BY MANUFACTURER. VERIFY EXACT LOCATION WITH INSTALLING CONTRACTOR.
- INSTALL TYPE 1 EXHAUST HOOD OVER KITCHEN EQUIPMENT. REFER TO KITCHEN HOOD MANUFACTURER'S DRAWINGS FOR MORE INFORMATION.
- INSTALL ROOF MOUNTED EXHAUST HOOD FAN ON PRE-FABRICATED ROOF CURB AS PER MANUFACTURER SPECIFICATION. PROVIDE 40" MINIMUM CLEARANCE TO ROOF SURFACE.
- INSTALL GAS FIRED MAKE UP AIR UNIT ON PRE-FABRICATED ROOF CURB AS PER MANUFACTURER SPECIFICATION.
- LOCATION OF MANUAL FULL STATION FOR HOOD SUPPRESSION SYSTEM. COORDINATE EXACT LOCATION WITH FIRE MARSHALL.
- MAINTAIN A MIN OF 18" FROM ALL COMBUSTIBLE MATERIALS TO TYPE 1 HOOD. PROVIDE FIRE WRAPPED GREASE DUCT FROM EXHAUST FAN DOWN TO TYPE I GREASE HOOD. TRANSITION AND CONNECT AS REQUIRED. TRANSITION AND CONNECT TO KITCHEN EQUIPMENT SUPPLIED EXHAUST FAN. REFER TO GREASE DUCT DETAIL.



MECHANICAL FLOOR PLAN

SCALE: 1/4" = 1'-0"

MECHANICAL PLAN NOTES CONTINUED:

- TRANSITION AND CONNECT ROUND DUCT TO MAKE UP AIR UNIT'S MAIN SUPPLY DROPS WITH BALANCING DAMPER AS REQUIRED AND ROUTE TO SUPPLY PLENUM ON HOOD.
- ROUTE 16"Ø TYPE I GREASE DUCT UP TO KEF-1 AND CONNECT AS REQUIRED. MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES.
- ROUTE MAKE UP AIR SUPPLY DUCT DOWN FROM MAKE UP AIR UNIT. TRANSITION AND CONNECT MAKE UP AIR SUPPLY DUCT AS REQUIRED. VERIFY THE EXACT SIZE AND LOCATION OF STRUCTURE BEFORE INSTALLING DUCTWORK. MOUNT DUCT AS HIGH AS POSSIBLE.
- INTERLOCK RTU-1, RTU-2, RTU-3 AND MUA-1 AS REQUIRED TO SHUT DOWN WHEN THE FIRE SUPPRESSION SYSTEM IS ACTIVATED.
- CONNECT 8"Ø SUPPLY DUCT TO KITCHEN HOOD AC CONNECTION AND SET TO 108 CFM AS LISTED ON SHEET M200.
- REFER TO ARCHITECTURAL PLAN FOR INFORMATION ON ROOF TOP UNIT SCREENING.

MECHANICAL GENERAL NOTES:

- COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
- THIS CONTRACTOR SHALL PERFORM ALL WORK INDICATED AND/OR AS REQUIRED FOR THE PROPER INSTALLATION AND OPERATION OF THE MECHANICAL SYSTEMS.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATIONS OF DIFFUSERS.
- INSTALL ALL DUCT, PIPE, ETC. AS HIGH AS POSSIBLE.
- DUCT SIZES SHOWN ARE ACTUAL SHEET METAL SIZES AND INCLUDE AN ALLOWANCE FOR DUCT LINER WHERE APPLICABLE.
- PROVIDE FLEXIBLE CONNECTION BETWEEN DUCTWORK AND ROOFTOP UNITS, EXHAUST FANS, AND OTHER MOTORIZED EQUIPMENT.
- NO DUCT SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
- ALL MECHANICAL SYSTEMS SHALL BE BALANCED BY A CERTIFIED BALANCING CONTRACTOR. REFER TO SPECIFICATIONS FOR DETAILS.

BUILDING TEMPERATURE SET POINTS

OCCUPIED MODE ZONE SET POINTS (5° DEADBAND)

COOLING SET POINT 75°F (ADJUSTABLE), 50% RH

HEATING SET POINT 70°F (ADJUSTABLE), 50% RH

UNOCCUPIED MODE ZONE SET POINTS

COOLING SET POINT 80°F (ADJUSTABLE), 50% RH

HEATING SET POINT 65°F (ADJUSTABLE), 50% RH

THE MECHANICAL CONTRACTOR SHALL ENSURE THE SYSTEMS ARE WIRED, INTERLOCKED, PROGRAMMED CORRECTLY, AND FULLY TESTED IN ALL MODES TO ENSURE THESE REQUIREMENTS ARE MET.

THE SYSTEMS SHALL BE BALANCED BY A NEBB CERTIFIED BALANCER, AND SHALL BE STARTED BY FACTORY TRAINED PERSONNEL.

ROOFTOP UNIT SCHEDULE																				
MARK	MFGR	MODEL NO.	NOM. TONS	EVAP. CFM	EXT. STATIC P. IN. WG. (NOTE 2)	COOLING				HEATING (GAS)		ELECTRICAL			OUTDOOR AIR (CFM)	TOTAL WEIGHT (LBS)	SEER /EER	REF.	NOTES	
						TOTAL BTUH	SENS. BTUH	AMB.	EVAP. EAT DB/WB	BTUH INPUT	BTUH OUTPUT	VOLT/Ø/HZ	BLOWER MOTOR	MIN. MCA (AMPS)						MOCP (AMPS)
RTU-1	LENNOX	LGH092H4B	7.5	3,000	0.7	87,200	65,400	105	80/67	180,000	144,000	208/3/60	3 HP	42	50	500	1,450	- /12.5	R-410a	1,2,3,4,5,6,7,8
RTU-2	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	↓	1,2,3,4,5,6,7,8
RTU-3	↓	LGH120H4B	10	4,000	↓	116,700	87,525	↓	↓	↓	↓	↓	↓	49	60	↓	1,585	- /12.0	↓	1,2,3,4,5,6,7,8

- NOTES:
- PROVIDE OUTDOOR AIR ECONOMIZER WITH STANDARD CONTROLLER, FIXED DRY BULB CONTROL, BAROMETRIC RELIEF DAMPER, CONSTANT AIR VOLUME, HINGED ACCESS DOORS, SCROLL COMPRESSORS WITH CRANKCASE HEATER, HIGH PRESSURE SWITCHES, FREEZESTAT, HAIL GUARDS, STANDARD COOLING DOWN TO 30°F. OUTDOOR AIR DAMPER TO FULLY CLOSE W/ FAN SHUTDOWN FOR ALL UNITS.
 - EXTERNAL STATIC PRESSURE LISTED REPRESENTS STATIC PRESSURE REQUIRED FOR DUCTWORK AND DIFFUSERS OUTSIDE THE HVAC UNIT COMPLETELY INDEPENDENT OF ANY PRESSURE DROP THROUGH THE HVAC EQUIPMENT INCLUDING BUT NOT LIMITED TO FILTERS, COILS AND ECONOMIZERS. THE FAN AND MOTOR SHALL BE SIZED APPROPRIATELY TO MEET THIS DEFINITION OF EXTERNAL STATIC PRESSURE.
 - PROVIDE COMMERCIAL T-DAY PROGRAMMABLE HEAT/COOL/AUTO CHANGEOVER THERMOSTAT WITH ECONOMIZER OUTPUT AND BUILT IN HUMIDITY SENSOR FOR EACH UNIT. ECONOMIZER/OUTDOOR AIR DAMPER IS TO CLOSE DURING UNOCCUPIED HOURS.
 - PROVIDE 18" HIGH (AT LOWEST POINT) PRE-FABRICATED INSULATED ROOF CURB WITH SLOPE TO MATCH SLOPE OF ROOF FOR EACH UNIT.
 - PROVIDE NEW 2" MERV 8 FILTERS UPON COMPLETION OF CONSTRUCTION.
 - MECHANICAL CONTRACTOR SHALL COORDINATE ALL UNIT MOCP'S OF ACTUAL INSTALLED EQUIPMENT WITH ELECTRICAL CONTRACTOR.
 - PROVIDE FACTORY MOUNTED SMOKE DETECTOR IN RETURN OF UNIT.
 - PROVIDE HOT GAS REHEAT (HUMIDITROL) OPTION FOR DEHUMIDIFICATION.

EXHAUST FAN SCHEDULE										
MARK	MFGR	MODEL	CFM	EXTERNAL STATIC P. IN. WG.	RPM	ELECTRICAL		FAN TYPE	CONTROLS	NOTES
						VOLT/Ø/HZ	PWR			
EF-1	COOK	GC-166	150	0.3	1,100	120/1/60	51 W	CEILING EXH.	SWITCH	1
EF-2	↓	GC-180	225	↓	1,450	↓	99.5 W	↓	↓	1

- NOTES:
- PROVIDE CEILING GRILLE, INTEGRAL BACK DRAFT DAMPER, VARI-SPEED CONTROLLER (NEAR FAN AND ABOVE CEILING), AND WEATHER HEAD.

DIFFUSER, REGISTER & GRILLE SCHEDULE						
MARK	MFGR	MODEL	NECK SIZE	FACE SIZE	FINISH	NOTES
SD-1	TITUS	TMS/3	6"Ø	24"X24"	WHITE	-
SD-2			8"Ø			-
SD-3			10"Ø			-
SD-4			12"Ø			-
SD-5		PAR/3				-
RG-1			18"X18"	24"X24"		-
RG-2			20"X20"			-
RG-3		BSORL	10"X8"			-




AIR BALANCE SCHEDULE (STORE)							
SUPPLY AIR UNIT	OUTSIDE AIRFLOW (CFM)	RETURN AIRFLOW	SUPPLY AIRFLOW	OA/SA %	EXHAUST AIR UNIT	EXHAUST AIRFLOW (CFM)	REMARKS
RTU-1	455	2,545	3,000	15.16%	EF-1	150	
RTU-2	455	2,545	3,000	15.16%	EF-2	225	
RTU-3	230	3,710	4,000	5.75%	KEF-1	2,400	
MUA-1	1,920	0	1,920	100.00%			
TOTAL	3,060	8,860	11,920	25.67%	TOTAL	2,775	
RESULTING BUILDING PRESSURIZATION						285 CFM	

OUTDOOR AIR CALCULATIONS									
UNIT	Area (sqft)	OCCUPANCY CLASSIFICATION / Room Name	Occupant Density #/1000 sqft	People outdoor airflow rate in breathing zone, (Rp) cfm/person	Area outdoor airflow rate in breathing zone, (Ra) cfm/sqft	Exhaust airflow rate cfm/sqft	Breathing zone outdoor airflow (Vbz)	Zone air distribution effectiveness ss (Ez)	Zone outdoor airflow (cfm)
RTU-1 & RTU-2	72	MAIN ENTRY / Entry 100	10	5	0.06		8	0.8	10
	205	DINING / Sitting 101	70	7.5	0.18		145	0.8	181
	1635	SALES / Sales 102	15	7.5	0.12		380	0.8	475
	144	CORRIDOR / Hall 103	0	0	0.06		9	0.8	11
	265	SALES / Cashier 112	15	7.5	0.12		62	0.8	77
	236	SALES / Checkout 113	15	7.5	0.12		55	0.8	69
	304	SALES / Food & Beverage 113	15	7.5	0.12		71	0.8	88
								Total	910
RTU-3	106	OFFICE / Office 106	5	5	0.06		9	0.8	11
	52	PREP AREA / Work 107	15	7.5	0.12		12	0.8	15
	268	PREP AREA / Food Prep 108	15	7.5	0.12		62	0.8	78
	234	STORAGE / Cleaning 109	0	0	0.12		28	0.8	35
	300	SALES / Drive Thru 110	15	7.5	0.12		70	0.8	87
								Total	227

- NOTES:
- PROVIDE 455 CFM OF OUTDOOR AIR FOR RTU-1 & RTU-2 AND 230 CFM OF OUTDOOR AIR FOR RTU-3.


SEQUENCE OF OPERATION

- A. PROVIDE STAND ALONE OR APPLICATION SPECIFIC CONTROLLERS AS REQUIRED TO PERFORM THE FOLLOWING SEQUENCES OF OPERATIONS.
- B. PACKAGED ROOFTOP UNITS
- UNIT SHALL CONSIST OF SUPPLY AIR FAN, FILTERS, DX COOLING COIL, GAS-FIRED HEAT SECTION, AND A T-DAY PROGRAMMABLE THERMOSTAT.
 - PROVIDE AN OVERRIDE SWITCH TO OPERATE THE UNIT DURING UNOCCUPIED HOURS. THIS SWITCH SHALL BE PART OF THE PROGRAMMABLE THERMOSTAT. OVERRIDE SWITCH ALLOWS THE UNIT TO OPERATE FOR TWO HOURS (ADJUSTABLE).
 - OCCUPIED MODE: BASED ON THE ROOFTOP UNIT'S HOURS OF OCCUPANCY, START THE UNIT AT THE BEGINNING OF OCCUPANCY AND SHUT DOWN THE UNIT AT THE END OF OCCUPANCY (NOTE: OUTSIDE AIR DAMPER WITHIN THE RTU SHALL OPEN AND THEN THE RTU SHALL START). THE UNIT SHALL START EARLIER AS DETERMINED BY THE PROGRAM FOR EARLY WARM-UP OR COOL DOWN. ON A SYSTEM STARTUP, THE RTU FAN SHALL START AND RUN CONTINUOUSLY AND THE INTERNAL FACTORY CONTROLS SHALL BE ENABLED. BASED ON THE SPACE TEMPERATURE SENSOR, THE UNIT SHALL CYCLE THE HEATING/COOLING TO MAINTAIN THE SPACE TEMPERATURE SETPOINT.
3.1. ECONOMIZER MODE: WHEN ENTHALPY OF OA IS BELOW 28 BTU/LB, ECONOMIZER MODE SHALL BE ENABLED. ECONOMIZER MODE SHALL LINEARLY MODULATE OUTDOOR AIR CFM FROM MINIMUM OA CFM TO 100% BASED ON ENTHALPY READINGS AND INTENT IS NO MORE THAN 55% RELATIVE HUMIDITY.
 - UNOCCUPIED MODE: THE RTU INTERNAL OA DAMPERS SHALL REMAINED CLOSED WHEN THE BUILDING IS NOT OCCUPIED. THE RTU SHALL STOP HEATING/COOLING AND THE FAN SHALL STOP. IF THE SPACE TEMPERATURE FALLS BELOW 60 DEGREE F (ADJUSTABLE), THE UNIT SHALL START AND HEAT UNTIL THE SPACE TEMPERATURE IS 61 DEGREE F (ADJUSTABLE) AND THEN SHUTDOWN. IF THE SPACE TEMPERATURE RISES ABOVE 65 DEGREE F (ADJUSTABLE), THE UNIT SHALL START AND COOL UNTIL THE SPACE TEMPERATURE IS 64 DEGREE F (ADJUSTABLE) AND THEN SHUTDOWN AND INTENT IS NO MORE THAN 55% RELATIVE HUMIDITY.
 - UPON DETECTION OF SMOKE BY UNIT SMOKE DETECTOR ALL RTUS SHALL SHUT DOWN AND AN ALARM SHALL BE SENT TO THE FIRE ALARM CONTROL PANEL (WHERE APPLICABLE). LOCAL REMOTE ANNUNCIATORS SHALL ALSO BE ACTIVATED.
 - ALL ROOF TOP UNITS SHALL BE INTERLOCKED WITH THE MAKE UP AIR UNIT SO THAT THE OUTDOOR AIR DAMPERS ARE OPEN, AND THE SUPPLY FANS RUN WHENEVER THE MAKE UP AIR UNIT FAN IS RUNNING.
- C. KITCHEN HOOD EXHAUST FAN
- THE KITCHEN HOOD EXHAUST FAN SHALL BE ENABLED WHEN ANY COOKING APPLIANCE LOCATED UNDER ITS RESPECTIVE HOOD, IS IN USE.
- D. RESTROOM EXHAUST FAN
- EXHAUST FAN SHALL BE POWERED BY LIGHT SWITCH IN RESTROOM. EXHAUST FAN SHALL BE "ON" WHEN LIGHT IS ON AND EXHAUST FAN SHALL BE "OFF" WHEN LIGHT SWITCH IS OFF
- E. MAKE UP AIR UNIT
- THE MAKE UP AIR UNIT SHALL BE ENABLED WHEN THE KITCHEN HOOD EXHAUST FAN (KEF-1) IS ENERGIZED, THE INTERNAL MOTORIZED DAMPER WITHIN WITH MAU-1 SHALL OPEN AND THE FAN SHALL RUN. IF OA IS LESS THAN 65" (ADJ.), THE MAU-1 GAS-FIRED HEAT SECTION SHALL BE ENABLED TO MAINTAIN A MINIMUM OF 65".
 - WHEN KEF-1 IS OFF, MAU-1 SHALL BE DE-ENERGIZED AND THE INTERNAL MOTORIZED DAMPED SHALL CLOSE.
- F. ANSUL SYSTEM ACTIVATION
- UPON ACTIVATION OF ANSUL SYSTEM, SHUT DOWN MAU-1 AND RTU-3. PROVIDE RELAYS CONTACTS, INTERLOCKS, TRANSFORMERS AND ALL ASSOCIATED WIRING TO ACCOMPLISH SEQUENCE. MAU-1 IS ALREADY PREWIRED TO SHUT DOWN IN HOOD CONTROL PANEL. MECHANICAL CONTRACTOR SHALL INTERLOCK RTU-1 AND RTU-2 TO ALSO SHUT DOWN.




FIRE RATED ENCLOSURE - GREASE DUCTS

- THERMAL CERAMICS FIREMASTER FASTWRAP XL IS TESTED TO ASTM E2336 AND UL LISTED PER HNK1.G18 TO PROVIDE ZERO CLEARANCE TO COMBUSTIBLES AND TO PROVIDE A 1- OR 2- HOUR ENCLOSURE. THROUGH PENETRATIONS FIRESTOP SYSTEMS ARE TESTED IN ACCORDANCE WITH ASTM E 814 UL 1479. ICC-ES APPROVAL PER REPORT ESR 2213 OR ESR 2832.
- COMPLIANT TO THE FOLLOWING CODES:
NFPA 96
INTERNATIONAL MECHANICAL CODES
UNIFORM MECHANICAL CODE,
CALIFORNIA MECHANICAL CODE
- INSULATION APPLIED IN TWO LAYERS WITH TIGHT COMPRESSION JOINT ON BOTH LAYERS AT ALL JOINTS.
- MINIMUM 16 GAUGE CARBON STEEL (OR 18 GAGE STAINLESS STEEL) RECTANGULAR OR ROUND GREASE EXHAUST DUCT
- INSTALL UL LISTED AND LIQUID TIGHT THERMAL CERAMICS FASTDOOR XL ACCESS DOORS AT ALL CHANGES IN DIRECTION AND AT MINIMUM EVERY 20 FT ON HORIZONTAL RUNS.
- SUPPORT HANGER SYSTEMS DO NOT NEED TO BE WRAPPED PROVIDED THE HANGER RODS ARE MINIMUM OF 3/8 IN. DIAMETER AND SUPPORTS ARE MINIMUM 2 X 2 X 1/8 IN. STEEL ANGLE OR SMACNA EQUIVALENT SUPPORT SYSTEM.
- THERMAL CERAMICS DUCT WRAP SHALL BE INSTALLED DIRECTLY ONTO THE DUCT AND APPLIED FROM THE HOOD CONNECTION TO THE CONNECTION TO THE FAN.
- THERMAL CERAMICS DUCT ENCLOSURE SYSTEM SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS AND UL LISTINGS.



Morgan
ThermalCeramics
P.O. Box 923
Augusta, Georgia 30903-0923
Phone: (706) 560-4038



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
WASH BAY MECHANICAL PLAN

M101

BC
ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA # 2009003629


4/28/2023

STATE OF MISSOURI
REGISTERED PROFESSIONAL ENGINEER
BRIAN A. QUISSELL
NUMBER
PE-200400829

ND-2 HANGING ANGLE DETAIL

1/2" DIA. ALL THREAD ROD
CONNECTED TO ROOF JOIST
THROUGH ANOTHER HANGING
ANGLE

1/2" DIA. HEAVY DUTY NUT
ONE ABOVE AND ONE BELOW
HANGING ANGLE



*ROD AND NUTS TO BE SUPPLIED BY INSTALLING CONTRACTOR
HANGING ANGLE IS PRE-FINISHED AT FACTORY

HANGING ANGLE LOCATIONS

HOOD STYLE	DIM FROM REAR	DIM FROM FRONT (24"H)	DIM FROM FRONT (30"H)
CANOPY ND2	4.166"	2.246"	2.246"
ND2-PSP-F	4.166"	2.246"	2.246"
BACKSHELF BD-2	4.166"	2.246	-
VHB/VHB-G	36"x36"	42"x42"	48"x48"
FRONT/BACK DIMS BY SIZE	2.246"	2.246"	2.246"


CALCULATIONS UTILIZED

EXHAUST CFM=LENGTH OF HOOD X CFM/LIN.FT. (LOAD)
SUPPLY CFM=EXHAUST CFM X PERCENTAGE REQUIRED
TOTAL DUCT AREA=144 X CFM
DUCT LENGTH= DUCT DEPTH
DUCT DUCT AREA

*CAPTIVE-AIRE DUCT CONNECTION SIZES ARE CALCULATED USING AN EXHAUST
VELOCITY OF 1500-1800 FPM AND A SUPPLY VELOCITY OF 300-400 FPM.

BUILDING CODES

CAPTIVE-AIRE HOODS ARE BUILT IN COMPLIANCE WITH:



CLEARANCE TO COMBUSTIBLES

CAPTIVE-AIRE HOODS HAVE OPTIONAL CLEARANCE
REDUCTION SYSTEMS AVAILABLE AS FOLLOWS:

MATERIAL	CLEARANCE REDUCTION SYSTEM
NON-COMBUSTIBLE	NONE REQUIRED
LIMITED-COMBUSTIBLE	3" UNINSULATED STANDOFF
COMBUSTIBLE	1" INSULATED STANDOFF

GENERAL NOTES

INSTALLATION

- ALL ELECTRICAL "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY ELECTRICAL CONTRACTOR.
- ALL PLUMBING "FIELD" CONNECTIONS AND RELATED INTERCONNECTIONS BY PLUMBING CONTRACTORS.
- HANGING BRACKETS LOCATED AND WELDED AS SHOWN ON PLANS. ALL OTHER HANGER MATERIALS PROVIDED BY INSTALLING CONTRACTORS.
- ALL CONNECTIONS FROM CAPTIVE-AIRE DUCT PER MECHANICAL CONTRACTOR'S PLANS.
- COOKING EQUIPMENT TO SHUTOFF IN EVENT OF FIRE.
- EXHAUST FANS TO TURN ON IN EVENT OF FIRE.
- ALL LIGHTS FIXTURE SHOWN INSTALLED BY CAPTIVE-AIRE ARE FACTORY PREWIRED. INTERCONNECTIONS BETWEEN HOODS AND TO SWITCHES BY ELECTRICAL CONTRACTORS.
- LAMPS FOR LIGHT FIXTURES BY INSTALLING CONTRACTORS.
- SEISMIC RESTRAINTS ARE RESPONSIBILITY OF INSTALLING CONTRACTOR.
- INSTALLING CONTRACTORS ASSUME ALL RELATED RESPONSIBILITY FOR VERIFICATION OF DIMENSIONAL DATA CONTAINED ON THESE DOCUMENTS FOR ACCURACY. INFORMATION AND ADMINISTRATION OF CODE REQUIREMENTS IS IN EFFECT PRIOR TO ANY RELEASE FOR PRODUCTION OF EQUIPMENT SHOWN.



BALANCE

- KITCHEN HOODS MUST BE BALANCED WITH KITCHEN.
- KITCHEN SHALL BE NEGATIVE WITH RESPECT TO DRIVING AREA.
- RESTAURANT SHALL BE POSITIVE WITH RESPECT TO AMBIENT PRESSURE.

ADDITIONAL

- WRITTEN HOOD DIMENSIONS HAVE PRECEDENCE OVER SCALE.
- SIGNED AND "APPROVED" COPIES OF THIS DOCUMENT MUST BE RECEIVED BY THE FACTORY PRIOR TO COMMENCEMENT OF FABRICATION.

FILTER DETAIL



CaptiveAir Captrate Solo Filter
ETL Listed Grease Extracting Filters
Made From 430 Stainless Steel

HOOD INFORMATION - JOB#5702408

HOOD NO	TAG	MODEL	MANUFACTURER	LENGTH	MAX COOKING TEMP	TYPE	APPLIANCE DUTY	DESIGN CFM/FT	TOTAL EXH CFM	EXHAUST PLENUM RISER(S)							MUA CFM	AC CFM	HOOD CONSTRUCTION	HOOD CONFIG	
										WIDTH	LENG	HEIGHT	DIA	CFM	VEL	SP				END TO END	ROW
1	KH-1	5424 EX-2-ACPSP-F	ECON-AIR	12' 0"	450 DEG	I	MEDIUM	200	2400			4'	16'	2400	1719	-1.062'	1920	756	430 SS WHERE EXPOSED	ALONE	ALONE

HOOD INFORMATION

HOOD NO	TAG	TYPE	FILTER(S)				LIGHT(S)				UTILITY CABINET(S)				FIRE SYSTEM	ELECTRICAL	SWITCHES	FIRE SYSTEM HANGING PIPING	HOOD HANGING WEIGHT
			QTY	HEIGHT	LENGTH	EFFICIENCY @ 7 MICRONS	QTY	TYPE	WIRE GUARD	LOCATION	SIZE	TYPE	SIZE	MODEL #	QUANTITY				
1	KH-1	CAPTRATE SOLO FILTER	9	16'	16'	85% SEE FILTER SPEC	3	RECESSED ROUND	NO	RIGHT	12"x54"x24"	TANK FS	4.0/4.0/4.0	DCV-1111	1 LIGHT 1 FAN			YES	1236 LBS

HOOD OPTIONS

HOOD NO	TAG	OPTION									
		FIELD WRAPPER	18.00' HIGH	FRONT, LEFT, RIGHT.	BACKSPLASH	122.00' HIGH X 192.00' LONG	430 SS VERTICAL.	RIGHT VERTICAL END PANEL	27' TOP WIDTH, 21' BOTTOM WIDTH, 80' HIGH	INSULATED 430 SS.	LEFT VERTICAL END PANEL
1	KH-1										

PERFORATED SUPPLY PLENUM(S)

HOOD NO	TAG	POS	LENGTH	WIDTH	HEIGHT	TYPE	RISER(S)				
							WIDTH	LENG	DIA	CFM	SP
1	KH-1	Front	156'	24'	6'	MUA	8"	36"		640	0.183'
						MUA	8"	36"		640	0.183'
						MUA	8"	36"		640	0.183'
						AC			8"	108	0.037'
						AC			8"	108	0.037'
						AC			8"	108	0.037'
						AC			8"	108	0.037'
						AC			8"	108	0.037'
						AC			8"	108	0.037'
						AC			8"	108	0.037'

SPECIFICATION: CAPTRATE® GREASE-STOP® SOLO FILTER

THE CAPTRATE GREASE-STOP SOLO FILTER IS A SINGLE-STAGE FILTER FEATURING A UNIQUE S-Baffle DESIGN IN CONJUNCTION WITH A SLOTTED REAR Baffle DESIGN, TO DELIVER EXCEPTIONAL FILTRATION EFFICIENCY.


FILTER IS STAINLESS STEEL CONSTRUCTION, AND SIZED TO FIT INTO STANDARD 2-INCH DEEP HOOD CHANNEL(S).

UNITS SHALL INCLUDE STAINLESS STEEL HANDLES AND A FASTENING DEVICE TO SECURE THE TWO COMPONENTS WHEN ASSEMBLED.

GREASE EXTRACTION EFFICIENCY PERFORMANCE SHALL REMOVE AT LEAST 75% OF GREASE PARTICLES FIVE MICRONS IN SIZE, AND 85% GREASE PARTICLES SEVEN MICRONS IN SIZE AND LARGER, WITH A CORRESPONDING PRESSURE DROP NOT TO EXCEED 1.0 INCHES OF WATER GAUGE.

THE CAPTRATE GREASE-STOP SOLO WAS TESTED TO ASTM STANDARD ASTM F2519-05. MANUFACTURER APPROVED FOR USE IN SOLID FUEL APPLICATIONS AS A SPARK ARRESTER.

EFFICIENCY VS. PARTICLE DIAMETER



CAPTIVATE FILTERS ARE BUILT IN COMPLIANCE WITH:

NFPA #96.
UL STANDARD #1046.
INT. MECH. CODE (IMC).
ULC-S649.

*** NOTE ***

ALL WALLS AND STRUCTURES THAT COME WITHIN 18" OF HOOD MUST BE METAL STUDS AND SHEETROCK. WOOD STUDS OR ANY OTHER COMBUSTIBLE MATERIAL WITHIN 18" OF HOOD NO ALLOWED.

*** NOTE ***

HOOD MANUFACTURER RECOMMENDS NO RETURNS OR 4-WAY DIFFUSERS WITHIN 10 FEET OF HOOD IN ALL DIRECTION.


*** NOTE ***

MAKEUP AIR SHALL BE DELIVERED INTO SPACE IN MANNER THAT WILL NOT DISRUPT HOODS ABILITY TO CAPTURE AND CONTAIN.

FOR QUESTIONS, CALL THE:
KANSAS CITY REGIONAL OFFICE
1126 SWIFT STREET, KANSAS CITY, MO 64116
PHONE: (816) 221-8575
FAX: (816) 221-8311


CUSTOMER APPROVAL TO MANUFACTURE:

Approved as Noted ☐
Approved with NO Exception Taken ☐
Revise and Resubmit ☐
SIGNATURE _____
Your Title _____ Date _____




ASSEMBLY INSTRUCTIONS

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TPI GRADE 5 (MINIMUM) ALL-THREAD. SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TPI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION BENEATH HOOD HANGING ANGLES AND ABOVE CEILING ANCHORS. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.



ASSEMBLY INSTRUCTIONS

HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TPI GRADE 5 (MINIMUM) ALL-THREAD. SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TPI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION ABOVE CEILING ANCHORS. SINGLE HEX NUT BENEATH HANGING ANGLE IS ACCEPTABLE FOR PSP HANGING ANGLES. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.




ASSEMBLY INSTRUCTIONS


HANGING ANGLE MUST BE SUPPORTED WITH 1/2" - 13 TPI GRADE 5 (MINIMUM) ALL-THREAD. SANDWICH HANGING ANGLES AND CEILING ANCHOR POINTS WITH 1/2" GRADE 5 (MINIMUM) STEEL FLAT WASHERS AND 1/2" - 13 TPI GRADE 5 (MINIMUM) HEX NUTS AS SHOWN. MUST USE DOUBLED HEX NUT CONFIGURATION ABOVE CEILING ANCHORS. SINGLE HEX NUT BENEATH HANGING ANGLE IS ACCEPTABLE FOR FULL LENGTH HANGING ANGLES. MAINTAIN 1/4" OF EXPOSED THREADS BENEATH BOTTOM HEX NUT. TORQUE ALL HEX NUTS TO 57 FT-LBS.

PATENT NUMBERS

AC-PSP (UNITED STATES) - US PATENT 7963830 B2.
AC-PSP WALL (CANADA) - CA PATENT 2820509.
AC-PSP ISLAND (CANADA) - CA PATENT 2520330.



PLAN VIEW - HOOD #1 (KH-1)
12' 0.00" LONG 5424EX-2-ACPSP-F
NOTE: ADDITIONAL HANGING ANGLES PROVIDED FOR HOODS 12' AND LONGER.
ACPSP SHIPS LOOSE FOR FIELD INSTALLATION



SECTION VIEW - MODEL 5424EX-2-ACPSP-F
HOOD - #1 (KH-1)

REVISIONS

DESCRIPTION	DATE



www.captiveaire.com

Air Solutions



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

4/28/2023



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI

Heartland Market - Lee's Summit

LEES SUMMIT, MO, 64082

DATE: 10/25/2022

DWG.#:
5702408

DRAWN BY: michael.c

SCALE:
3/4" = 1'-0"

MASTER DRAWING

SHEET NO.

1

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
HOOD DETAILS

M200

FIRE SYSTEM INFORMATION – JOB#5702408

FIRE SYSTEM NO	TAG	TYPE	SIZE	FLOW POINTS	INSTALLATION	
					SYSTEM	LOCATION ON HOOD
1		TANK FS	4.0/4.0/4.0	46	FIRE CABINET RIGHT	RIGHT, HOOD 1

GAS VALVE(S)

FIRE SYSTEM NO	TAG	TYPE	SIZE	SUPPLIED BY
1		SC ELECTRICAL	2.000	ECON-AIR

FIRE SYSTEM PARTS LIST KEY

FIRE SYSTEM NO	TAG	KEY NUMBER – PART DESCRIPTION	QTY BY FACTORY	QTY BY DIST
1		0 – 0 – TANK FIRE SUPPRESSION POST-DISCHARGE PROCEDURE UTILITY CABINET LABEL SHEET.	1	0
		0 – 0 – TANK FIRE SUPPRESSION MAINTENANCE GUIDE UTILITY CABINET LABEL SHEET.	1	0
		0 – 0 – 12-F28021-32144-DT-360 DUCT FIRE THERMOSTAT WITH 12 FOOT WIRE LEADS. NO, CLOSE ON TEMP RISE AT 360°F.	1	0
		0 – 0 – 87-120042-001 SECONDARY ACTUATOR VALVE (SVA) – SINGLE ACTUATOR, REQUIRES PRIMARY RELEASE ACTUATOR, TANK FIRE SUPPRESSION.	2	0
		0 – 0 – 87-120045-001 HOSE, SECONDARY ACTUATOR HOSE, 7.5' BRAIDED STAINLESS STEEL, TANK FIRE SUPPRESSION.	2	0
		0 – 0 – 87-300001-001 TANK – PRESSURIZED TANK USED FOR TANK FIRE SUPPRESSION.	3	0
		0 – 0 – 87-300030-001 PRIMARY ACTUATOR KIT (PAK) – ACTUATOR AND RELEASE SOLENOID ASSEMBLY, ONE NEEDED PER FIRE SYSTEM, SUPERVISED, TANK FIRE SUPPRESSION.	1	0
		0 – 0 – 87-300152-001 HARDWARE, SVA BOLTS, TANK FIRE SUPPRESSION.	12	0
		0 – 0 – 9055455PC PRO PRESS 1/2 PRESS X PRESS 90 ELBOW L.D.	13	0
		0 – 0 – 9097200PC PRO PRESS PC611 1/2 PRESS TEE L.D.	7	0
		0 – 0 – 9B694A115 HARDWARE, DATANKLOCK LOCKING BRACKET SQUARE NUTS 5/16" ZINC, TANK FIRE SUPPRESSION.	6	0
		0 – 0 – A0034332 JUNCTION BOX FOR MANUAL PULL STATION. 1.5" DEEP BACK BOX, RED COLOR.	1	0
		0 – 0 – B1145 3/8" BLACK IRON 90 ELL.	3	0
		0 – 0 – CBI-104 CHROME PLATED PIPE FITTING 3/8" NPT TEE.	2	0
		0 – 0 – CBI-106 CHROME PLATED PIPE FITTING 3/8" NPT 90 DEGREE ELBOW.	2	0
		0 – 0 – CBI-107 CHROME PLATED PIPE FITTING 3/8" NPT UNION.	2	0
		0 – 0 – DATANKLOCK DISCHARGE ADAPTER TANK LOCKING PLATE FOR FIRE SYSTEM TANK INSTALLATION IN UTILITY CABINETS, TANK FIRE SUPPRESSION.	3	0
		0 – 0 – TANK STRAP TANK STRAP – USED FOR TANK FIRE SUPPRESSION.	9	0
		0 – 0 – TFS-UCTANKBRACKET TANK BRACKET FOR FIRE SYSTEM TANK INSTALLATION IN UTILITY CABINETS, TANK FIRE SUPPRESSION.	3	0
		0 – 0 – WK-283952-000 DISCHARGE ADAPTER, TANK FIRE SUPPRESSION.	3	0
		16 – 16 – 79210 1/2" X 3/8" NPT MALE ADAPTER, VIEGA.	9	0
		16 – 16 – DL-F NOZZLE – TANK PROTECTION APPLIANCE COVERAGE NOZZLE (INCLUDES METAL BLOW OFF CAP, LANYARD, USED WITH CHROME-PLATED PIPE)- 4 FLOW POINTS.	11	0
		26 – 26 – QSA-3/8 QUIK SEAL – 3/8" (UL).	9	0
		34 – 34 – A0034331 24VDC SINGLE ACTION MANUAL ACTUATION DEVICE (PUSH/PULL STATION) WITH PROTECTIVE COVER, ONE (1) NORMALLY OPEN CONTACT. RED COLOR.	1	0

- NOTES
- FIELD PIPE DROPS AS SHOWN
 - PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
 - FIELD INSTALLED DROP: FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED
 - SHIP LOOSE DROP: FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
 - RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVING, SALAMANDERS, ETC.
 - OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION. IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
 - FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.

- APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.
- THIS FIRE SYSTEM COMPLIES WITH UL 300 REQUIREMENTS.

- DL-F NOZZLE PART NUMBER REPLACES 3070-3/BH-10-SS

JOB #: 5702408.
JOB NAME: HEARTLAND MARKET – LEE'S SUMMIT.

SYSTEM SIZE: TANK-SP-3 TOTAL FP REQUIRED: 46.
HOOD # 1 12' 0.00' LONG x 54' WIDE x 24" HIGH.
RISER # 1 SIZE: 16" DIA.
HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.




- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

LEGEND – FIRE CABINET TANK SYSTEM

- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.

INCLUDES FIELD INSTALLATION AND HOOKUP DURING NORMAL BUSINESS HOURS BY CERTIFIED INSTALLERS ONLY IN THE LOCATION NOTED ABOVE. TWO SITE VISITS ONLY (ONE VISIT TO SET PULL STATION & SYSTEM HOOKUP AND ONE VISIT FOR ONE TEST). ADDITIONAL VISITS WILL RESULT IN ADDITIONAL CHARGES). ONE MECHANICAL OR ELECTRICAL GAS VALVE PER SYSTEM AT A MAXIMUM SIZE OF 2" PERMIT AND SYSTEM TEST.

EXCLUDES UNION LABOR & PREVAILING WAGE CLAROR & WAGES WILL BE ADDED IF APPLICABLE). GAS VALVE INSTALLATION, ELECTRICAL HOOKUP AND CONNECTIONS, HANGING OF FIRE CABINET, SHUNT TRIP, HANDHELD EXTINGUISHER(S), ON-SITE RE-PIPING DUE TO EQUIPMENT LAYOUT CHANGES.




SECTION VIEW – MODEL 5424EX-2-ACPSP-F
HOOD – #1

GAS VALVES AND STRAINERS													
TYPE	SIZE	VOLTAGE	GAS VALVE SIZING			FLOW AT 1 IN.W.C. PRESSURE				DIMENSIONS			
			MIN. INLET PRESSURE (0 IN.W.C.)	MAX. INLET PRESSURE (138 IN.W.C.)	FLOW AT 1 IN.W.C. DROP NATURAL GAS BTU/HR	FLOW AT 1 IN.W.C. DROP PROPANE BTU/HR	DIM "A"	DIM "B"	DIM "C"	DIM "D"	DIM "E"	DIM "F"	DIM "G"
ELECTRICAL	2"	120 VAC	0 PSI	1 PSI	2,940,000	1,900,000	7-5/8"	6-3/8"	7-1/4"	7-13/16"	10-5/8"	13-15/16"	HORIZONTAL/VERTICAL
			0 IN.W.C.	138 IN.W.C.	BTU/HR	BTU/HR							

ALL GAS VALVES/STRAINERS PROPER CLEARANCE MUST BE PROVIDED IN ORDER TO SERVICE THE STRAINERS A MINIMUM OF 4" CLEARANCE DISTANCE MUST BE PROVIDED AT THE BACK OF THE STRAINER. CUSTOMER MUST VERIFY BTU CONSUMPTION AS WELL AS PRESSURE RATING SPECIFIC GRAVITY OF NATURAL GAS = 0.64, SPECIFIC GRAVITY OF LP = 1.52.

CALCULATIONS
TO CALCULATE GAS FLOW FOR OTHER THAN 1 IN.W.C. PRESSURE DROP:
NEW BTU/HR = (BTU/HR AT 1 IN.W.C. PRESSURE DROP) X NEW PRESSURE DROP^{3/4}
TO CALCULATE GAS FLOW FOR OTHER THAN 0.64 SPECIFIC GRAVITY:
NEW BTU/HR = (BTU/HR AT 0.64) X (0.64 / NEW SPECIFIC GRAVITY)^{1/4}



REVISIONS	
DESCRIPTION	DATE:

CAPTIVE

www.captiveaire.com

Air Solutions

1329 East Kemper Rd., Ste. 4210, Cincinnati, OH, 45246 PHONE: (513) 860-5655 EMAIL: reg120@econair.com

Heartland Market – Lee's Summit
LEES SUMMIT, MD, 64082

DATE: 10/25/2022

DWG.#:
5702408

DRAWN BY: michael.co

SCALE:
3/4" = 1'-0"

MASTER DRAWING

SHEET NO.
2

BC
ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

4/28/2023

BRIAN A. QUISSELL
REGISTERED PROFESSIONAL ENGINEER
PE-2004000829

PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
HOOD DETAILS

M201

EXHAUST FAN INFORMATION - JOB#5702408

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	MANUFACTURER	CFM	ESP	RPM	MOTOR ENCL	HP	BHP	PHASE	VOLT	FLA	DISCHARGE VELOCITY	WEIGHT (LBS)	SONES
1	KEF-1	1	EADUI80H	ECON-AIR	2400	1.800	1318	ODP,PREMIUM	3.000	1.5120	3	208	9.5	554 FPM	200	18.4

MUA FAN INFORMATION - JOB#5702408

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	BLOWER	HOUSING	MIN CFM	DESIGN CFM	ESP	RPM	MOTOR ENCL	HP	BHP	PHASE	VOLT	FLA	MCA	MOCP	WEIGHT (LBS)	SONES
2	MAU-1	1	EA1-D.250-1SD	ISMF-1-MOD	A1-D.250	1000	1920	0.500	2023	ODP,PREMIUM	2.000	1.2880	3	208	6.1	7.7A	15A	510	19.9

GAS FIRED MAKE-UP AIR UNIT(S)

FAN UNIT NO	TAG	INPUT BTUS	OUTPUT BTUS	TEMP RISE	REQUIRED INPUT GAS PRESSURE	GAS TYPE	BURNER EFFICIENCY(%)
2	MAU-1	142989	131550	66°F	7 IN. W.C. - 14 IN. W.C.	NATURAL	92

FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	KEF-1	1	GREASE BOX
		1	EXHAUST FAN HEAT BAFFLE
		1	FAN BASE CERAMIC SEAL - INSTALLED AT PLANT - FOR GREASE DUCTS
		1	UNIT MOUNTED VFD FOR USE WITH ECPM03
		1	VFD MOUNTING BRACKET FOR DU/DR 180 - 200
		1	2 YEAR PARTS WARRANTY
2	MAU-1	1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, -5 TO 15" WC
		1	MOTORIZED BACKDRAFT DAMPER FOR A1-D HOUSING - MEETS AMCA CLASS 1A RATING
		1	SEPARATE 120V WIRING PACKAGE (REQUIRED AND USED ONLY FOR DCV OR PREWIRE WITH VFD) - THREE PHASE ONLY
		1	LOW FIRE START
		1	SIZE 1 TEMPERED COMMERCIAL DOWN DISCHARGE FOR DIRECT DRIVE AHUS
		1	UNIT MOUNTED VFD FOR USE WITH ECPM03
		1	2 YEAR PARTS WARRANTY




FAN ACCESSORIES

FAN UNIT NO	TAG	EXHAUST			SUPPLY		
		GREASE CUP	GRAVITY DAMPER	WALL MOUNT	SIDE DISCHARGE	GRAVITY DAMPER	MOTORIZED DAMPER
1	KEF-1	YES					
2	MAU-1						YES

CURB ASSEMBLIES


NO	ON FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	KEF-1	41 LBS	CURB	26.500"W X 26.500"L X 20.000"H ALONG LENGTH, RIGHT VENTED HINGED.
2	# 2	MAU-1	63 LBS	CURB	21.000"W X 71.000"L X 15.000"H ALONG WIDTH, RIGHT INSULATED.

FAN #1 EADUI80H - EXHAUST FAN (KEF-1)




PITCHED CURBS ARE AVAILABLE FOR PITCHED ROOFS.

SPECIFY PITCH:
EXAMPLE: 7/12 PITCH = 30° SLOPE.



- FAN #2 EA1-D250-1SD - HEATER (MAU-1)
1. DIRECT GAS FIRED HEATED MAKE UP AIR UNIT WITH 15" MIXED FLOW DIRECT DRIVE FAN.
 2. INTAKE HOOD WITH EZ FILTERS.
 3. DOWN DISCHARGE - AIR FLOW RIGHT -> LEFT.
 4. GAS PRESSURE GAUGE, 0-35", 2.5" DIAMETER, 1/4" THREAD SIZE.
 5. GAS PRESSURE GAUGE, -5 TO +15 INCHES WC, 2.5" DIAMETER, 1/4" THREAD SIZE.
 6. MOTORIZED BACK DRAFT DAMPER 16" X 18" FOR SIZE 1 STANDARD & MODULAR HEATER UNITS W/EXTENDED SHAFT, STANDARD GALVANIZED CONSTRUCTION, 3/4" REAR FLANGE, LOW LEAKAGE, 1FBI20S ACTUATOR INCLUDED.
 7. SEPARATE 120VAC WIRING PACKAGE FOR MAKE-UP AIR UNITS. OPTION MUST BE SELECTED WHEN MOUNTING VFD IN PREWIRE PANEL OR WITH DCV PACKAGE. PROVIDES SEPARATE 120VAC INPUT TO SUPPLY FAN. THIS 120V SIGNAL MUST BE RUN BY ELECTRICIAN FROM DCV TO MUA SWITCH.
 8. LOW FIRE START. ALLOWS THE BURNER CIRCUIT TO ENERGIZE WHEN THE MODULATION CONTROL IS IN A LOW FIRE POSITION.
 9. DOWN DISCHARGE CONSTRUCTION FOR SIZE 1 DIRECT DRIVE AHUS.
 10. UNIT MOUNTED VFD FOR USE WITH ECPM03.
 11. HINGED DOUBLE WALL INSULATED DOOR ASSEMBLY (BURNER/BLOWER SECTION).
 12. 2 YEAR PARTS WARRANTY.
- NOTE: SUPPLY DUCT MUST BE INSTALLED TO MEET SMACNA STANDARDS. A MINIMUM STRAIGHT DUCT LENGTH MUST BE MAINTAINED DOWNSTREAM OF UNIT DISCHARGE AS OUTLINED IN AMCA PUBLICATION 201. WHEN USING RECTANGULAR DUCTWORK, ELBOWS MUST BE RADIUS BACK WITH TURNING VANES. FLEXIBLE DUCTWORK AND SQUARE THROAT/SQUARE BACK ELBOWS SHOULD NOT BE USED. ANY TRANSITION AND/OR TURNS IN THE DUCTWORK WILL CAUSE SYSTEM EFFECT. SYSTEM EFFECT WILL DRASTICALLY INCREASE STATIC PRESSURE AND REDUCE AIRFLOW. DO NOT RELY ON UNIT TO SUPPORT DUCT IN ANY WAY. FAILURE TO PROPERLY SIZE DUCTWORK MAY CAUSE SYSTEM EFFECTS AND REDUCE PERFORMANCE OF THE EQUIPMENT.
SUGGESTED STRAIGHT DUCT SIZE IS 14" x 14".



DIRECT FIRED (DF) PROFILE PLATE ASSEMBLY


DIRECT FIRED PROFILE PLATE SPECIFICATIONS:

DESCRIPTION:
DIRECT FIRED BURNERS SHALL HAVE PATENTED (US PATENT NO. US669923B2), SELF-ADJUSTING PROFILE PLATES DESIGNED TO ENSURE PROPER AIR VELOCITY AND PRESSURE DROP ACROSS THE BURNER. PROFILE PLATES SHALL ALLOW BURNERS TO ACHIEVE CLEAN COMBUSTION BY LIMITING BY-PRODUCT LEVELS TO A MAXIMUM OF 5PPM OF CARBON MONOXIDE (CO), AND 5PPM OF NITROGEN DIOXIDE (NO2). DIRECT FIRED UNITS SHALL BE CONFIGURED WITH THE BLOWER MOUNTED DOWNSTREAM OF THE BURNER. THIS ARRANGEMENT WILL ENSURE A CONSISTENT AIRFLOW, REGARDLESS OF INLET AIR TEMPERATURE.




APPLICATION:
SPRING-LOADED BURNER PROFILE PLATES ARE ENGINEERED TO AUTOMATICALLY REACT TO THE MOMENTUM OF A FRESH AIR STREAM, WITHOUT THE NEED FOR ANY MOTORS OR ACTUATORS TO MECHANICALLY ADJUST THEM. WITH THIS FEATURE, ALL DF UNITS ARE DESIGNED FOR DEMAND CONTROL VENTILATION (DCV) REQUIREMENTS.

CERTIFICATIONS:
ALL PROFILE PLATE ASSEMBLIES SHALL BE INCLUDED IN THE DF UNIT'S ETL LISTING AND COMPLY WITH COMBINED SAFETY STANDARDS ANSI Z89.1 AND CSA 3.7 (NON-RECIRCULATING DF HEATERS) AND ANSI Z89.18 (RECIRCULATING DF HEATERS).

GENERAL CONSTRUCTION:
-PROFILE PLATES SHALL BE FORMED FROM G90 GALVANIZED STEEL.
-PROFILE PLATES SHALL VARY IN SIZE PER UNIT.
-PROFILE PLATES SHALL BE MOUNTED ALONG THE SAME PLANE AS THE DISCHARGE OF THE BURNER.
-DESIGN SHALL INCORPORATE PROPERLY TORQUED, PERMANENTLY MOUNTED SPRING HINGES.
-SPRING HINGES SHALL BE MADE FROM PLATED STEEL.



ROOF OPENING 2" SMALLER THAN CURB DIMENSION.



REVISIONS	
DESCRIPTION	DATE

CAPTIVE



Air Solutions

1329 East Kemper Rd., Ste. 4210, Cincinnati, OH 45246 PHONE: (513) 960-5555 EMAIL: reg120@captair.com

Heartland Market - Lee's Summit
LEES SUMMIT, MO, 64082

DATE: 10/25/2022

DWG.#:
5702408

DRAWN BY:
michael.co

SCALE:
3/4" = 1'-0"

MASTER DRAWING

SHEET NO.
3


BC

ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

4/28/2023



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI





BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023


REVISION:

SHEET TITLE
HOOD DETAILS

M202



REVISIONS		
	DESCRIPTION	DATE:
△		
△		
△		
△		



Heartland Market - Lee's Summit
LEES SUMMIT, MD, 64082

DATE: 10/25/2022

DWG.#:
5702408

DRAWN BY: michael.co

SCALE:
3/4" = 1'-0"

MASTER DRAWING

SHEET NO.
5

This drawing has been prepared by the Engineer, or under his supervision. This drawings is provided as an instrument of service by the Designer/Engineer, and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of space, and all other content appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.

© 2022 BC Engineers, Inc.

PE COA #2009003629

4/28/2023



PROJECT FOR:

HEARTLAND AND MARKET

LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
HOOD DETAILS

M204

ELECTRICAL SPECIFICATIONS

1. GENERAL PROVISIONS:
- A. PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, NECESSARY FOR THE COMPLETE INSTALLATION OF THE ELECTRICAL SYSTEMS OUTLINED.

B. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE AUTHORITIES.

C. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST APPROVED EDITION OF THE NATIONAL ELECTRIC CODE (NEC), AND ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL AGENCIES HAVING JURISDICTION OVER THE SITE.

D. ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.

E. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, CONDUIT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNHARMED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERING SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.

F. PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILING, AND ROOFS AS NECESSARY. PATCH AROUND ALL OPENINGS SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.

G. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
2. OPERATION AND MAINTENANCE MANUALS:
- A. DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, WIRING DIAGRAMS, CATALOG CUTS, LUBRICATION AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.

B. ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATION AND MAINTENANCE MANUALS.

C. ALL LITERATURE LISTED ABOVE AND ALL PAPERS LISTING WARRANTIES, ETC. SHALL BE BOUND IN A 3-RING BINDER AND LABELED WITH THE PROJECT NAME, ADDRESS, ARCHITECT, ENGINEER, CONTRACTORS, ETC.
3. MANUFACTURERS:
- A. MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSTRUED AS LIMITING COMPETITION. ARTICLES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO STRUCTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN, UNLESS NOTED OTHERWISE.
4. TESTING, AND BALANCING:
- A. ALL CIRCUITS SHALL BE TESTED FOR CONTINUITY, SHORTS, AND GROUNDS BEFORE CONNECTING TO THE PROPER PHASE AS DESIGNED TO BALANCE THE LOADING BETWEEN PHASES.

B. POWER AND LIGHTING PANELS SHALL BE PROPERLY PHASED TO DISTRIBUTE THE LOAD AND SHALL BE CONNECTED AND ADJUSTED TO OPERATE AS SPECIFIED.

C. ALL MOTORS AND SIMILAR EQUIPMENT SHALL BE CHECKED FOR PROPER PHASE ROTATION AND OPERATION.
5. RACEWAYS:
- A. CONDUIT INSIDE THE BUILDING SHALL BE METALLIC TUBING (EMT), BEARING THE UL LABEL, WITH COMPRESSION TYPE FITTINGS OR SCREW SET FITTINGS.

B. CONDUIT EXPOSED TO THE WEATHER, INSTALLED UNDERGROUND, IN CONCRETE, OR USED FOR SERVICE ENTRANCE SHALL BE STANDARD RIGID CONDUIT (GALVANIZED) WITH THREADED FITTINGS.

C. UNDERGROUND CONDUIT MAY BE POLYVINYL CHLORIDE WITH A DEFLECTION TEMPERATURE, UNDER LOAD AT 264 PSI, OF 10 DEGREES C, AND A TENSILE STRENGTH OF 5,200 PSI. JOINTS SHALL BE FLUSH SOLVENT WELDED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE EQUAL TO CARLON POWER AND COMMUNICATIONS DUCT TYPE DB (DIRECT BURIAL). CONDUIT AND FITTINGS SHALL BE PROVIDED BY THE SAME MANUFACTURER.

D. FLEXIBLE METAL CONDUIT SHALL ONLY BE USED FOR CONNECTIONS TO MOTORS, TRANSFORMERS, AND LIGHT FIXTURES. MAXIMUM LENGTH SHALL BE 6'-0".
6. CONDUCTORS:
- A. WIRES SHALL BE CONTINUOUS WITHOUT SPLICES OR TAPS IN CONDUIT RUNS. ALL SPLICES SHALL BE MADE IN JUNCTION, PULL, OR OUTLET BOXES. ALL WIRE SHALL BE INSTALLED IN CONDUIT, WIRERAYS, OR OTHER PROTECTIVE COVER SANCTIONED BY CODES.

B. CONDUCTORS FOR LIGHTING AND POWER SHALL BE COPPER, MINIMUM NO. 12 AWG, 600 VOLT.

C. NO. 10 GAUGE AND SMALLER CONDUCTORS SHALL BE TYPE THHN (WET LOCATIONS) OR THHN (DRY LOCATIONS), SOLID CONDUCTOR, UNLESS OTHERWISE INDICATED.

D. NO. 8 GAUGE AND LARGER CONDUCTORS SHALL BE TYPE THWN (WET LOCATIONS) OR THHN (DRY LOCATIONS), STRANDED, UNLESS OTHERWISE INDICATED.

E. SERVICE ENTRANCE AND PANEL FEEDER CONDUCTORS, NO. 3 GAUGE AND LARGER SHALL BE TYPE XHHW-2 (WET LOCATIONS) OR THHN (DRY LOCATIONS), STRANDED COPPER, UNLESS OTHERWISE INDICATED.
7. MC CABLE:
- A. MC CABLE SHALL CONSIST OF INTERLOCK ARMORED CABLE MADE OF THREE OR FOUR TYPE THHN SOLID 180 AMPS AND LARGER MAY BE STRANDED COPPER CONDUCTORS INSULATED WITH HEAT AND MOISTURE RESISTANT POLYVINYL CHLORIDE (PVC), WITH NYLON OR EQUIVALENT UL LISTED JACKET, PER UL STANDARD 85. THE THREE CONDUCTORS SHALL BE TWISTED TOGETHER WITH THE COPPER GROUNDING CONDUCTOR, SUITABLE FILLERS, AND WRAPPED IN BINDER TAPE. THE ASSEMBLY SHALL BE ARMORED WITH SPIRALLY WRAPPED INTERLOCKED ARMOR OR ALUMINUM OR GALVANIZED STEEL.

B. CABLES SHALL BE TESTED IN ACCORDANCE WITH UL STANDARD 1569 FOR TYPE MC CABLE AND RATED AT 600 VOLTS, 90 DEG. C FOR DRY LOCATIONS AND 75 DEG. C FOR WET LOCATIONS.
8. WIRING DEVICES:
- A. WALL SWITCHES SHALL BE SPECIFICATION GRADE, QUIET TYPE, FLUSH TOGGLE SWITCH, RATED FOR 20 AMPS, WITH THERMOPLASTIC COVER PLATES.

1) SINGLE POLE: HUBBELL K5S1221-X, OR EQUAL.

2) THREE WAY: HUBBELL K5S1223-X, OR EQUAL.

B. RECEPTACLES SHALL BE SPECIFICATION GRADE, DUPLEX, GROUNDING, THREE-WIRE TYPE, RATED FOR 20 AMPS, WITH THERMOPLASTIC COVER PLATES. HUBBELL K5S952-X, OR EQUAL.

C. GROUND FAULT INTERRUPTER RECEPTACLES (GFI) SHALL BE HUBBELL K5P20-XL. DEVICE COVER PLATES SHALL BE AS HEREINBEFORE SPECIFIED.

D. ISOLATED GROUND RECEPTACLES (IG) SHALL BE HUBBELL K5R552IG, ORANGE COLOR. DEVICE COVER PLATES SHALL BE AS HEREINBEFORE SPECIFIED.

E. RECEPTACLES OUTSIDE BUILDING AND WHERE NOTED AS WEATHERPROOF, SHALL BE LISTED WEATHER-RESISTANT HUBBELL K5RT320-X OR EQUAL AND SHALL BE INSTALLED IN A WEATHERPROOF ENCLOSURE WHICH SHALL BE INTERMATIC W5P1010MC OR W5P1010HMC DIECAST METAL WEATHERPROOF RECEPTACLE COVER. COVER SHALL BE WEATHER PROOF RATED WHILE IN USE.

F. EXTERIOR RECEPTACLES SHALL BE WEATHER RESISTANT TYPE PER NEC 200.8. DEVICES SHALL BE HUBBELL K5R200WRTR, OR EQUAL.

G. VERIFY DEVICES AND DEVICE COVERPLATES COLOR WITH ARCHITECT.
9. BOXES:
- A. HOT DIPPED GALVANIZED STEEL BOXES. PROVIDE TYPE TO SUIT CONDITIONS FOR INSTALLATION.

B. ALL BOXES SHALL BE FLUSH MOUNTED, UNLESS INDICATED OTHERWISE.
10. PANELBOARDS:
- A. FURNISH AND INSTALL CIRCUIT BREAKER PANELBOARDS AS SHOWN ON THE DRAWINGS. PANELBOARDS SHALL BE LISTED BY UL AND SO LABELED, AND SHALL BE FULLY RATED FOR THE VOLTAGE AND CURRENT CAPACITY INDICATED ON THE PANEL SCHEDULE. PANELBOARDS SHALL BE EQUAL TO GENERAL ELECTRIC, TYPE AG WITH BOLT IN TYPE BREAKERS. PANELBOARD LUGS SHALL BE RATED AT 75°C.

1) CIRCUIT BREAKER INTERRUPTING CAPACITIES SHALL MEET OR EXCEED THE AVAILABLE RMS SYMMETRICAL FAULT CURRENTS INDICATED AND AS REQUIRED TO MEET OR EXCEED THE AVAILABLE FAULT CURRENT FROM LOCAL UTILITY.

B. CIRCUIT BREAKERS SHALL MEET APPLICABLE PORTIONS OF UL STANDARD 484 AND NEMA AS-L. CIRCUIT BREAKERS SHALL BE BOLT-ON, GROUP MOUNTED, AMBIENT MAGNETIC, WITH COMMON TRIP, UL RATED TO CARRY 60% OF NAMEPLATE RATING CONTINUOUSLY IN FREE AIR AT 40° C. CIRCUIT BREAKERS SHALL BE TRIP INDICATING AND FULLY INTERCHANGEABLE WITHOUT DISTURBING ADJACENT UNITS. WIRE TERMINALS SHALL BE RATED 75 DEGREES C. THE OPERATING MECHANISM SHALL BE TRIP-FREE SO THAT CONTACTS CANNOT BE HELD CLOSED AGAINST ANY ABNORMAL OVERCURRENT OR SHORT CIRCUIT CONDITION.

2) BREAKERS SHALL MEET APPLICABLE NEMA AND/OR UL SPECIFICATIONS.

C. PANELBOARD BOXES SHALL BE GALVANIZED SHEET STEEL WITH AMPLE WIRING GUTTER SPACE IN ACCORDANCE WITH NEC. FRONTS SHALL BE OF SHEET STEEL PAINTED LIGHT GRAY OVER A SUITABLE RUST INHIBITOR PRIMER. PANELBOARDS SHALL BE EQUIPPED WITH ONE PIECE DOOR, CYLINDER TUMBLER TYPE LOCK, DIRECTORY CARD-HOLDER AND QUARTER-TURN ADJUSTABLE TRIM CLAMPS.

D. PANELBOARD INTERIORS SHALL CONSIST OF REINFORCED GALVANIZED SHEET STEEL FRAMES WITH ALUMINUM BUS BARS AND CIRCUIT BREAKERS, PROPERLY SUPPORTED TO PREVENT VIBRATIONS AND BREAKAGE IN HANDLING. BUS BARS SHALL BE SEQUENCE PHASED. PANELBOARD SHALL HAVE A FULL SIZED SOLID ALUMINUM NEUTRAL AND GROUND BUS.

E. BUS BAR BRACING SHALL BE UL LISTED AS INDICATED ON DRAWINGS. ADDITIONAL BRACING SHALL BE PROVIDED AS REQUIRED TO MEET OR EXCEED INDICATED AVAILABLE FAULT CURRENTS.

F. DIRECTORY CARDS SHALL BE COMPLETELY FILLED IN BY TYPEWRITER, LISTING CIRCUIT NUMBERS AND LOAD SERVED, INCLUDING EXISTING CIRCUITS. CIRCUIT BREAKERS SHALL BE IDENTIFIED BY CIRCUIT NUMBER LABELS AS HEREINBEFORE SPECIFIED.

ELECTRICAL SPECIFICATIONS (CONTINUED)

11. DISCONNECTS:
- A. DISCONNECTS SHALL BE EXTERNALLY OPERATED, QUICK-MAKE, QUICK-BREAK, SAFETY, WITH PROVISIONS FOR PAD LOCKING. FUSED AND NON-FUSED DISCONNECT SWITCHES SHALL BE PROVIDED AS INDICATED.

B. INDOOR SWITCHES SHALL BE NEMA 1 AND OUTDOOR SWITCHES SHALL BE NEMA 3R, UNLESS INDICATED OTHERWISE.
12. FUSES:
- A. FUSES PROTECTING CIRCUIT BREAKER PANELS SHALL BE CURRENT LIMITING U.L. CLASS RK-1 FUSES WITH 200,000 AMPERES RMS SYM INTERRUPTING CAPACITY. FUSING ELEMENTS SHALL BE SILVER FOR RATINGS ABOVE 60 AMPERES.

B. ALL OTHER FUSES SHALL BE U.L. CLASS RK-5, DUAL-ELEMENT WITH A MINIMUM TIME-DELAY OF 10 SECONDS AT 500% RATING. FUSES SHALL HAVE CURRENT-LIMITING SHORT-CIRCUIT LINKS AND 200,000 AMPERES RMS SYM INTERRUPTING CAPACITY. FUSING ELEMENTS SHALL BE COPPER.
13. LIGHT FIXTURES:
- A. WHERE LIGHT FIXTURES ARE MOUNTED IN A LAY-IN CEILING, PROVIDE A MINIMUM OF 2 SUPPORT WIRES ATTACHED DIRECTLY BETWEEN EACH LIGHT FIXTURE AND THE BUILDING STRUCTURE. SUPPORT WIRES SHALL BE A MINIMUM OF 12 GAUGE GALVANIZED STEEL WIRE, SOFT ANNEALED.

B. FIXTURES ARE REQUIRED AT ALL LIGHTING OUTLETS SHOWN ON THE DRAWINGS. APPROVED LIGHTING FIXTURE WIRE IS REQUIRED IN ALL FIXTURES AND FIXTURE RACEWAYS. WEATHERPROOF WIRING IS REQUIRED FOR EXTERIOR FIXTURES. ALL PARTS OF FIXTURES AND WIRING SHALL BE IN ACCORDANCE WITH NEC REQUIREMENTS.

C. ALL FIXTURES SHALL CARRY UL AND ETL LABELS. ALL FLUORESCENT FIXTURE BALLASTS SHALL BE HIGH FREQUENCY ELECTRONIC BALLASTS WITH A "TOTAL HARMONIC DISTORTION" OF LESS THAN 20%, REGARDLESS OF THE NUMBER OF LAMPS CONNECTED TO EACH BALLAST AND SHALL HAVE CBM LABEL. ALL FLUORESCENT FIXTURES INSTALLED SHALL INCORPORATE BALLAST PROTECTION. ALL FLUORESCENT BALLASTS SHALL HAVE AN AUDIBLE NOISE RATING OF "CLASS A" OR BETTER. ALL FLUORESCENT BALLASTS SHALL HAVE A STANDARD BALLAST FACTOR UNLESS SPECIFIED OTHERWISE.

D. ALL FLUORESCENT LAMPS SHALL BE 3500 K COLOR TEMPERATURE WITH A MINIMUM COLOR RENDERING INDEX (CRI) OF 92 OR AS INDICATED ON LIGHT FIXTURE SCHEDULE.
14. SLEEVES:
- A. PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK.

B. INTERIOR PARTITIONS: 16 GAUGE GALVANIZED STEEL, PACK BETWEEN CONDUIT AND SLEEVE WITH FIRE SAFING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.

C. ROOF: PROSECT OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WEATHERPROOF SEAL, COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF WARRANTY.
15. GROUNDING:
- A. GROUND ALL ELECTRICAL APPARATUS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE (NEC) 250, AND ANY LOCAL REQUIREMENTS. INSURE CONTINUOUS BOND WHERE FLEXIBLE CONDUIT IS USED. PROVIDE BONDING JUMPER INSIDE ALL FLEXIBLE CONDUIT.

B. BOND METAL PIPING SYSTEMS IN COMPLIANCE WITH NEC 250.41(A)(4).

ELECTRICAL GENERAL NOTES:

1. COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
2. IT IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY TO PROPERLY BALANCE ALL BRANCH CIRCUITS BETWEEN THE PHASES OF THE SYSTEM REGARDLESS OF CIRCUITING INDICATED.
3. ALL EXPOSED RACEWAYS SHALL BE IN EMT CONDUIT, MC CABLE IS NOT PERMITTED IN EXPOSED AREAS.
4. ELECTRICAL CONTRACTOR TO COORDINATE MANUFACTURER ELECTRICAL REQUIREMENTS FOR HVAC EQUIPMENT BEING FURNISHED WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN.
5. ALL MATERIALS EXPOSED WITHIN PLENUMS SHALL BE NONCOMBUSTIBLE OR SHALL HAVE A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE-DEVELOPED INDEX OF NOT MORE THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM E 84.
6. EACH BRANCH CIRCUIT SHALL HAVE A DEDICATED NEUTRAL PER NEC 200.4.
7. KITCHEN EQUIPMENT - VERIFY ALL ELECTRICAL REQUIREMENTS AND ROUGH-IN LOCATION PRIOR TO WORK.
8. ALL BRANCH CIRCUITS SHALL BE SIZED TO ALLOW FOR A MAXIMUM OF 3% VOLTAGE DROP. ALL FEEDERS SHALL BE SIZED TO ALLOW FOR A MAXIMUM OF 2% VOLTAGE DROP. E/C SHALL VERIFY WIRE SIZE INDICATED IS SUFFICIENT AND INCREASE CONDUCTOR SIZE AS REQUIRED BASED OFF ACTUAL INSTALLED LENGTH OF CONDUCTORS.
9. PROVIDE SEAL-OFF FITTINGS AT ALL COOLER/FREEZER PENETRATIONS.

ELECTRICAL SYMBOLS LIST

CIRCUITING & NOTES	
+48"	SPECIAL MOUNTING HEIGHT FOR ASSOCIATED DEVICE (CENTERLINE OF DEVICE)
GFI	GROUND FAULT CIRCUIT INTERRUPTER DEVICE
WP	WEATHERPROOF ENCLOSURE ON DEVICE
WR	WEATHERPROOF RESISTANT DEVICE
IG	ISOLATED GROUND DEVICE
EM	EMERGENCY BATTERY BACKUP
<div>X</div>	ELECTRICAL FLOOR PLAN NOTE WITH DESIGNATION
<div>2 LP</div>	CONDUIT CONCEALED WHERE POSSIBLE OR AS NOTED, ARROWS INDICATE HOME RUN TO PANEL. CIRCUIT NUMBERS INDICATED
<div>⎓</div>	#12 WIRE IN CONDUIT, UNLESS NOTED OTHERWISE ON DRAWINGS OR SPECIFICATION
<div>↶</div>	GROUNDING CONDUCTOR, #12 WIRE UNLESS NOTED OTHERWISE ON DRAWINGS OR SPECIFICATION
<div>↷</div>	CONDUIT ROUTED UNDER FLOOR/GRADE
LIGHTING	
<div>⎓</div>	EMERGENCY TWIN HEAD LIGHT FIXTURE
<div>⎓⎓</div>	EXIT LIGHT WITH DIRECTIONAL ARROWS INDICATED
<div>A</div>	FLUORESCENT STRIP FIXTURE WITH TYPE DESIGNATION
<div>A •</div>	FLUORESCENT FIXTURE WITH TYPE DESIGNATION
<div>A HL</div>	NIGHT LIGHT, CONNECT TO UNSWITCHED CIRCUIT
<div>A Q</div>	CEILING OR RECESSED FIXTURE WITH TYPE DESIGNATION
<div>A Q+</div>	WALL MOUNTED FIXTURE WITH TYPE DESIGNATION
POWER DEVICES	
<div>⌀</div>	DUPLEX RECEPTACLE, BOTTOM OF BOX AT 16" AFF, UNLESS NOTED OTHERWISE
<div>⌀</div>	FOURPLEX RECEPTACLE, BOTTOM OF BOX AT 16" AFF, UNLESS NOTED OTHERWISE
<div>⌀⌀</div>	TVSS SURGE SUPPRESSION RECEPTACLE
<div>⌀ ⚡</div>	DEVICE MOUNTED ABOVE COUNTER AND/OR SPLASH GUARD
<div>⌀</div>	HEAVY DUTY OUTLET - NEMA CONFIGURATION SIZE PER EQUIPMENT MANUFACTURER'S RECOMMENDATION
<div>≡</div>	PANEL BOARD, TOP OF BOX 8'-0" AFF
<div>⊙</div>	JUNCTION BOX
<div>⊞</div>	NON-FUSED DISCONNECT SWITCH
<div>⊞</div>	FUSED DISCONNECT SWITCH
<div>⊞</div>	MAGNETIC STARTER
<div>⊞</div>	MOTOR WITH DESIGNATION
<div>⊞</div>	FLOOR BOX
CONTROLS	
<div>S</div>	SINGLE POLE WALL SWITCH, TOP OF BOX AT 48" AFF
<div>S P</div>	SINGLE POLE WALL SWITCH WITH PILOT LIGHT, TOP OF BOX AT 48" AFF
<div>S O</div>	INFRARED OCCUPANCY SENSOR, WATT STOPPER #PW-100, TOP OF BOX AT 48" AFF
<div>S M</div>	MANUAL MOTOR STARTER WITH OVERLOADS
<div>⊙</div>	DUAL TECHNOLOGY CEILING MOUNT OCCUPANCY SENSORS, WATTSTOPPER DT-300
<div>⊞</div>	OCCUPANCY SENSOR POWER PACK, WATTSTOPPER BZ-150 OR EQUAL, PROVIDE LOW VOLTAGE WIRING TO OCCUPANCY SENSORS AND MOMENTARY SWITCHES
<div>S MO</div>	MOMENTARY SWITCH, TOP OF BOX AT 48" AFF
COMMUNICATIONS	
<div>▼</div>	DATA/TELEPHONE OUTLET WITH 3/4" CONDUIT STUBBED UP TO ABOVE ACCESSIBLE CEILING, BOTTOM OF BOX AT 16", UNLESS NOTED OTHERWISE. PROVIDE WITH FULL STRING

LIGHT FIXTURE SCHEDULE

MARK NO.	MANUFACTURER & CATALOG NUMBER	VOLTS WATTS	LAMPS	DESCRIPTION	EQUIVALENT MANUFACTURERS
A	COLUMBIA LJT24-35-HLG-FS-A12125-EU	120 49	LED-INCL 5000 LUM 3500K	2X4' LED TROFFER WITH ACRYLIC PRISMATIC LENS AND FIXED-OUTPUT DRIVER. 5000 LUMENS AT 3500K	WILLIAMS LITHONIA OR EQUAL
A EM	COLUMBIA LJT24-35-HLG-FS-A12125-EU ELL14	120 49	LED-INCL 5000 LUM 3500K	SAME AS ABOVE WITH EMERGENCY BATTERY PACK - 1400 LUMEN EM LIGHT	WILLIAMS LITHONIA OR EQUAL
B	COLUMBIA LXM4-35-HL-RFA-EU	120 52	LED-INCL 5000 LUM 3500K	4' LED VAPOR-TIGHT FIXTURE WITH FROSTED ACRYLIC LENS AND FIXED-OUTPUT DRIVER. 5000 LUMENS AT 3500K	WILLIAMS LITHONIA OR EQUAL
BE	COLUMBIA LXM4-35-HL-RFA-EU ELL14	120 52	LED-INCL 5000 LUM 3500K	SAME AS FIXTURE 'B' WITH EMERGENCY BACKUP	WILLIAMS LITHONIA OR EQUAL
F	METEOR LA6-60-408-UNV-SFV5-60-60-BLK-STD	120 60	LED-INCL 6000 LUM 4000K	WALL MOUNTED UP/DOWN LIGHT, BLACK FINISH. WALL MOUNT AT 12'-0" AFF.	WILLIAMS LITHONIA OR EQUAL
F2	L5I XLCW 5 LED 56 CM EW BLK	120 41	LED-INCL	WALL MOUNTED LED AREA LIGHT, SYMMETRICAL OPTICS, BLACK FINISH. WALL MOUNT AT 12'-0" AFF	WILLIAMS LITHONIA OR EQUAL
G	L5I SCV LED 15L 5C UNV DIM 50 NHT	120 102	LED-INCL 15,000 LUM 5000K	LED PETROLEUM CANOPY LIGHT WITH SYMMETRICAL DISTRIBUTION. 15,000 LUMENS AT 5000K COLOR TEMPERATURE. VERIFY CANOPY CONSTRUCTION AND ORDER CORRECT FIXTURE MOUNTING AND TYPE BASED ON CANOPY BEING PROVIDED	-
52	HUBBELL RAR2-320L-110-4KT-2-UNV-ASQ-BLT-BG POLE: S65H-25-50-B-2-BLT-B3	208 222	LED-INCL 30,000 LUM 4000K	POLE MOUNTED AREA LIGHT, TYPE 2 SYMMETRICAL DISTRIBUTION. MOUNTED ON 2 1/2" POLE WITH VIBRATION DAMPER AND 2 HIGH CONCRETE BASE	WILLIAMS LITHONIA OR EQUAL
53	HUBBELL RAR2-320L-110-4KT-3-UNV-ASQ-BLT-BG POLE: S65H-25-50-B-1-BLT-B3	208 110	LED-INCL 15,000 LUM 4000K	POLE MOUNTED AREA LIGHT, TYPE 3 SYMMETRICAL DISTRIBUTION. MOUNTED ON 2 1/2" POLE WITH VIBRATION DAMPER AND 2 HIGH CONCRETE BASE	WILLIAMS LITHONIA OR EQUAL
54	HUBBELL RAR2-320L-110-4KT-4UNV-ASQ-BLT POLE: S65H-25-50-B-1-BLT-B3	208 110	LED-INCL 15,000 LUM 4000K	POLE MOUNTED AREA LIGHT, TYPE 4W SYMMETRICAL DISTRIBUTION. MOUNTED ON 2 1/2" POLE WITH VIBRATION DAMPER AND 2 HIGH CONCRETE BASE	WILLIAMS LITHONIA OR EQUAL
55	DUAL-LITES EV2	120 1	INCL	EMERGENCY LIGHT WITH TWIN ADJUSTABLE 1 WATT LED HEADS AND SEALED LEAD GELGUM BATTERY, MOUNT AT 7'-6". TO CLEAR OBSTACLES, (PROVIDES 1 FC AVG. ON 2' CENTER FIXTURE SPACING)	SURE-LITES LITHONIA OR EQUAL
56	DUAL-LITES EVC-U-R-Y-M-D4 WITH EVO-D-X	120 5	INCL	COMBINATION EMERGENCY/EXIT LIGHT WITH LED LAMPS, RED LETTERS ON WHITE BACKGROUND, TWIN 6W EMERGENCY LIGHT HEADS, UNIVERSAL MOUNT, HIGH CAPACITY BATTERY BACKUP AND REMOTE TWIN HEAD OUTDOOR RATED FIXTURE	SURE-LITES LITHONIA OR EQUAL



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing hereon, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

4/28/2023



PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823


REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:


SHEET TITLE
ELECTRICAL
SPECIFICATION

E000

SHEET FILE LOCATION: N:\2022\22823\ELEC\22823E.DWG
LAST SAVED: 11/30/2022 5:13 PM
BY: PAUL



ELECTRICAL LIGHTING PLAN
SCALE: 1/4" = 1'-0"



- LIGHTING PLAN NOTES:**
- 1 ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTROL. SEE DETAIL, THIS SHEET.
 - 2 LOCATION OF EXTERIOR LIGHTING CONTROLS. SEE DETAIL, SHEET THIS SHEET.
 - 3 CONNECT TO LIGHTS PROVIDED WITH CANOPY, IF PROVIDED WITH OPTION. VERIFY ALL REQUIREMENTS WITH CANOPY SUPPLIER.
 - 4 SWITCH BANK FOR INTERIOR LIGHTING CONTROLS.
 - 5 ROUTE SWITCH LEG TO INDICATED SWITCH IN BANK. SEE PLAN NOTE #4.

PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823
REVIEW SET
ISSUE DATE: 4-28-2023
REVISION:


SHEET TITLE
ELECTRICAL LIGHTING
PLAN

E101

BC
ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629
4/28/2023
STATE OF MISSOURI
DARIN T. SEIDEL
REGISTERED PROFESSIONAL ENGINEER
NUMBER
RE-200900300



POWER PLAN NOTES:

1. DEVICES MOUNTED IN CASEWORK - VERIFY EXACT LOCATIONS. ROUTE ALL WIRING CONCEALED.
2. RECEPTACLES MOUNTED IN COOLER SOFFIT WALL FOR DECORATIVE SIGNAGE.
3. CONNECT TO WALK-IN COOLER/FREEZER DOOR LIGHTS/HEATERS PER MANUFACTURER'S INSTRUCTIONS.
4. CONNECT TO WALK-IN COOLER/FREEZER EVAPORATOR PER MANUFACTURER'S INSTRUCTIONS. VERIFY EXACT LOCATIONS AND ELECTRICAL REQUIREMENTS WITH EQUIPMENT SUPPLIER. PROVIDE CONTROL WIRING TO CONDENSING UNIT(S) PER MANUFACTURER'S INSTRUCTIONS.
5. POWER FOR OPEN AIR COOLER FLOOR BOX. VERIFY REQUIREMENTS WITH OWNER.
6. CONNECT TO EVAPORATOR CONDENSATE HEAT TRACE. VERIFY ALL REQUIREMENTS WITH EQUIPMENT SUPPLIER.
7. DUPLEX RECEPTACLE MOUNTED FLUSH IN CEILING ABOVE STOREFRONT WINDOW FOR DISPLAY SIGNAGE PER NEC.
8. JUNCTION BOX WITH TOGGLE DISCONNECT FOR POWER TO BUILDING SIGNAGE. VERIFY EXACT LOCATION AND REQUIREMENTS WITH SIGNAGE VENDOR. ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTROLS. SEE EXTERIOR LIGHTING DETAIL ON SHEET E-101.
9. JUNCTION BOX FOR POWER TO ELECTRICAL HAND DRYER. VERIFY EXACT LOCATION AND REQUIREMENTS.
10. LOCATION OF FUEL SYSTEM RACEWAY, CONTROLS, TANK MONITORS, ETC. FIELD VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
11. RECEPTACLE FOR ATM MACHINE. VERIFY LOCATION AND OTHER REQUIREMENTS WITH OWNER. MOUNT POWER AND DATA RECEPTACLE AT +36" AFF.
12. POWER FOR MERCHANDISE GONDOLA FLOOR BOX. VERIFY REQUIREMENTS WITH OWNER.
13. 4"x4"x3/4" PLYWOOD TELEPHONE BACKBOARD WITH SIEMENS #ECB5-5 GROUND BAR AND #6CU BOND TO BUILDING ELECTRODE SYSTEM.
14. PROVIDE (1) 4" TO PROPERTY LINE FOR BUILDING TELEPHONE SERVICE. TERMINATE AT LOCATION DIRECTED BY LOCAL SERVICE PROVIDER. VERIFY ROUTING & DISTANCE. REFER TO CIVIL UTILITY DRAWINGS.
15. SECONDARY FEEDER TO TRANSFORMER. SEE RISER DIAGRAM SHEET E2, AND ELECTRICAL SITE PLAN SHEET E3.01.




ELECTRICAL POWER PLAN

POWER PLAN NOTES:

16. CT CABINET, DISCONNECT SW. AND METER MOUNTED ON BUILDING. SEE ELECTRICAL SITE PLAN SHEET E3.01.
17. DATA DROP FOR WIRELESS ACCESS POINT - COORDINATE LOCATION WITH OWNER.
18. POWER FOR DONUT CASE FLOOR BOX. VERIFY REQUIREMENTS WITH OWNER.
19. PROVIDE 7.5 KVA 208V-240V, 1 PH TRANSFORMER FOR COFFEE BREWER OR DRINK DISPENSER INDICATED. VERIFY ELECTRICAL REQUIREMENTS WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.
20. ROUTE CIRCUIT THROUGH HOOD SHUT-DOWN RELAY - SEE HOOD SHUT-DOWN RELAY DIAGRAM ON THIS SHEET.
21. PROVIDE JUNCTION BOX FOR HEATED AIR CURTAIN. CONNECT PER MANUFACTURER'S REQUIREMENTS. VERIFY EXACT LOCATION WITH OWNER PRIOR TO ROUGH-IN.

EQUIPMENT SCHEDULE

NUMBER	DESCRIPTION	NUMBER	DESCRIPTION
1	COFFEE DISPENSER - SURE IMMERSION 312	22	HOT FOOD CASE (CHICKEN)
2	REFR LIQUID DISPENSER - KAN PAK	23	LOTTERY EQUIPMENT
3	COFFEE BREWER - BUNN SH DBC (240V, 1 PH)	24	COUNTER TOP WARMER
4	CAPPUCCINO DISPENSER - CURTIS	25	PIZZA PREP TABLE
5	ICED TEA BREWING SYSTEM - CURTIS	26	CONVECTION OVEN
7	COFFEE CREAMER AND SUGAR DISPENSER - BSG	27	COUNTER TOP GRIDDLE
8	DONUT CASE	28	MICROWAVE OVEN
9	FEDERAL SELF-SERVE ISLAND	29	WORKTOP FREEZER
11	FRYERS	30	COUNTERTOP BLENDER
11	STACKED OVEN	31	MERCHANDIZER
14	SELF SERVE MERCHANDIZER	32	MERCHANDIZER
15	NACHO DISPENSER	33	HOT DOG ROLLER
16	ICE AND BEVERAGE DISPENSER	34	BUN WARMER
17	FRESH BLENDER	35	MICROWAVE
19	FROZEN BEVERAGE DISPENSER (240V, 1PH)	36	HOOD
20	FROZEN DRINK MACHINE	39	ATM
21	WAFFLE MAKER	40	BAG-N BOX



HOOD SHUT-DOWN DETAIL
SCALE: NONE



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

4/28/2023



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI


BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
MECHANICAL POWER
PLAN

E103



POWER PLAN NOTES:


- 1 CONNECT TO WALK-IN COOLER FREEZER CONDENSING UNIT(S) ON ROOF PER MANUFACTURER'S INSTRUCTIONS. VERIFY ALL REQUIREMENTS WITH EQUIPMENT SUPPLIER.

NORTH
MECHANICAL POWER PLAN
SCALE: 1/4" = 1'-0"


BY: PAUL

LAST SAVED: 11/30/2022 5:13 PM

SHEET FILE LOCATION: N:\2022\22823\ELEC\22823E.DWG



ELECTRICAL RISER DIAGRAM
SCALE: NONE



**ENGINEERS
INCORPORATED**
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

4/28/2023



PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
ELECTRICAL RISER
DIAGRAM & FAULT CALCS


E201

PANEL: A1		VOLTS: 120/208V				PH: 3Ø		WIRE: 4W		LOCATION: WORK ROOM 104			MOUNTING: SURFACE			
BUS: 400A		MAIN: 400A MCB		IC:	22,000		RMS SYM AMPS					FEEDER: SEE RISER DIAGRAM				
CKT	DESCRIPTION	AMPS	POLE	WIRE	ØA	ØB	ØC	ØA	ØB	ØC	WIRE	POLE	AMPS	DESCRIPTION	CKT NO	
1	01 COFFEE SYSTEM (GF)	20	1	12	1,800			2,412			8	2	40	04 REFR ISLAND	2	
3	02 REFRIG GREASER (GF)	20	1	12		360				2,412					4	
5	03 COFFEE BREWER	30	2	10			3,492			3,000	10	2	30	11 STACKED OVEN	6	
7						3,492		3,000				8				
9	03 COFFEE BREWER	30	2	10			3,492			2,080	10	2	30	14 REFR MERCHANIZER	10	
11	03 COFFEE BREWER	30	2	10					5,020					RTU-1	12	
13						3,492		5,020					14			
15						3,492			5,020		6	3	50		16	
17	04 CAPPUCCINO DISP (GF)	20	1	12			1,800			5,020					18	
19	05 ICE TEA BREWER (GF)	20	1	12	1,656			1,920			12	1	20	17 FRESH BLENDER (GF)	20	
21	01 GREASER (GF)	20	1	12		50				3,492	10	2	30	19 FROZEN BEV DISPENSER	22	
23	08 DONUT CASE	20	1	12			1,200			3,492					24	
25					1,085			1,440			12	1	20	20 FROZEN DRINK MACH (GF)	26	
27	10 FRYER	70	3	4			1,085			1,800	12	1	20	21 WAFFLE MAKER (GF)	28	
29	(ST)						1,085			3,360	8	1	40	22 HOT CHICKEN CASE (GF)	30	
31	(SHUNT TRIP SPACE)								180		12	1	20	23 LOTTERY EQUIPMENT	32	
33							1,085			1,200	12	1	20	24 CTR TOP WARMER (GF)	34	
35	10 FRYER	70	3	4			1,085			520	12	1	20	25 PIZZA PREP TABLE (GF)	36	
37	(ST)				1,085			10,050			1/0	2	150	PANEL F	38	
39	(SHUNT TRIP SPACE)									10,100					40	
41	23 MICROWAVE (GF)	20	1	12			1,680				252	12	1	20	24 FREEZER (GF)	42
NOTES:					24,610	21,564	25,834	24,522	26,604	17,732						
(HL)-HANDLE LOCK, (ST)-SHUNT TRIP BRKR					44,132		48,168		43,566	TOTAL CONNECTED LOAD:		140,866 VA				
(GF)-SFGI BRKR							NEG DEMAND LOAD:		103,948 VA							
							DEMAND AMPS @ 208 VOLT / 3Ø:		288.53							

PANEL: A2		VOLTS: 120/208V				PH: 3Ø		WIRE: 4W		LOCATION: WORK ROOM 104			MOUNTING: SURFACE		
BUS: 400A		MAIN: 400A MCB		IC:	22,000		RMS SYM AMPS					FEEDER: SEE RISER DIAGRAM			
CKT	DESCRIPTION	AMPS	POLE	WIRE	ØA	ØB	ØC	ØA	ØB	ØC	WIRE	POLE	AMPS	DESCRIPTION	CKT NO
43	30 BLENDER (GF)	20	1	12	1,800			1,800			12	1	20	31 SHELF MERCH (GF)	44
45	32 SELF MECH (GF)	20	1	12		864				1,320	12	1	20	33 HOT DOG ROLLER (GF)	46
47	34 BUN WARMER	15	2	12			100			1,546	12	1	20	35 MICROWAVE (GF)	48
49	(GF)				100			1,440			12	1	20	36 PIZZA WARMER (GF)	50
51	ROOFTOP RECS	20	1	12		720				800	12	1	20	MAU VFD	52
53	04 CAPPUCCINO DISP (GF)	20	1	12			1,800			250	12	1	20	HCP/HOOD LIGHTS	54
55	15 NACHO DISPENSER (GF)	20	1	12	300			1,141							56
57	16 BEV DISPENSER (GF)	20	1	12		800				1,141	12	3	15	KEP-1	58
59	16 BEV DISPENSER (GF)	20	1	12			800			1,141					60
61					5,020			733							62
63	RTU-2	50	3	6		5,020				733	12	3	15	MAU-1	64
65							5,020			733					66
67					5,850			3,000			10	2	30	11 STACKED OVEN	68
69	RTU-3	60	3	6		5,850				3,000					70
71							5,850			180	8	1	40	ATM MACHINE	72
73	NACHO DISPENSER (GF)	20	1	12	300			1,440			12	1	20	20 FROZEN DRINK MACH (GF)	74
75	BAG-N BOX (GF)	20	1	12		360				1,440	12	1	20	20 FROZEN DRINK MACH (GF)	76
77	16 BEV DISPENSER (GF)	20	1	12			800					1	20	SPARE	78
79	21 COUNTER TOP GRIDDLE	20	2	12	1,680			22,730							80
81					1,680					26,030	3/0	3	200	PANEL B	82
83	AIR MACHINE	20	1	12			800							27,130	84
NOTES:					15,020	15,264	15,170	32,284	34,464	31,030	TOTAL CONNECTED LOAD: 143,232 VA NEG DEMAND LOAD: 128,471 VA DEMAND AMPS @ 208 VOLT / 3Ø: 357.94				
(GF)-GF/GI BRKR					47,304		44,728		46,200						

PANEL: B		VOLTS: 120/208V			PH: 3Ø		WIRE: 4W		LOCATION: WORK ROOM 104			MOUNTING: SURFACE			
BUS: 225A		MAIN: 200A MLO			IC: 22,000		RMS SYM AMPS					FEEDER: SEE RISER DIAGRAM			
CKT	DESCRIPTION	AMPS	POLE	WIRE	ØA	ØB	ØC	ØA	ØB	ØC	WIRE	POLE	AMPS	DESCRIPTION	CKT NO
1	HOT WATER HEATER	30	2	10	2,500			180			12	1	20	POS	2
3					2,500			180			12	1	20	POS	4
5	RECIRC PUMP	20	1	12			600			180	12	1	20	POS	6
7	SPARE	20	1				1,000				12	1	20	SHOW WINDOW	8
9	FLOOR BOXES	20	1	12		540				1,000	12	1	20	SHOW WINDOW	10
11	FLOOR BOXES	20	1	12			540			1,000	12	1	20	BLDG SIGNAGE	12
13	FLOOR BOXES	20	1	12	540			1,000			12	1	20	BLDG SIGNAGE	14
15	FLOOR BOXES	20	1	12		540				500	12	1	20	COOLER DISPLAY CASE LTG	16
17	OFFICE RECS	20	1	12			360			540	12	1	20	DISPLAY CASE SIGNS	18
19	OFFICE RECS	20	1	12	900			500			12	1	20	COOLER DISPLAY CASE LTG	20
21	FREEZER EVAP	20	1	12		1,100				360	12	1	20	DISPLAY CASE SIGNS	22
23	COOLER EVAP	20	1	12			1,100			360	12	1	20	DISPLAY CASE SIGNS	24
25	BEER GAVE EVAP	20	1	12	1,100			2,150			10	2	30	COOLER COND UNIT	26
27	COND HEAT TRACE (6P)	20	1	12		1,100				2,150					28
29	COOLER EVAP	20	1	12			1,100			3,900	6	2	50	BEER GAVE COND UNIT	30
31	WALK-IN CONDENSING UNIT	15	2	12	800			3,900							32
33					800			3,900			6	2	50	FREEZER COND UNIT	34
35	WALK-IN CONDENSING UNIT	15	2	12			800			3,900					36
37					800			2,100			6	2	50	COOLER COND UNIT	38
39	HAND DRYER (HL)	20	1	12		1,000				2,100					40
41	HAND DRYER (HL)	20	1	12			1,000			1,850	8	1	20	SALES AREA LIGHTING	42
43	WALL PACK LTG	20	1	12	540			500			10	1	20	COOLER / FREEZER LTG	44
45	EXTERIOR LTG CONTROLS	20	1	12		250				1,340	10	1	20	BOH LTG	46
47	26 CTR TOP CONV OVEN	15	2	12			1,170			660	10	2	20	SITE LIGHTING	48
49					1,170			660							50
51	DISP CANOPY SIGN	20	1	8		1,200				770	10	2	20	SITE LIGHTING	52
53	DISP CANOPY SIGN	20	1	8			1,200			770					54
55	SPARE	20	1	10				1,200			10	1	20	BUILDING PYLON SIGN	56
57	SPARE	20	1	10					800		12	1	20	COOLER EVAP	58
59	CASHER RECS	20	1	12			360			800	12	1	20	FREEZER EVAP	60
61	DISPLAY RECS	20	1	12	540							1	20	SPARE	62
63	MENUBOARD	20	1	12		1,000						1	20	SPARE	64
65	CANOPY LIGHTING	20	1	8			1,020			1,020	8	1	20	CANOPY LIGHTING	66
67	MENU CANOPY LIGHT	20	1	12	600									BUSSED SPACE	68
69	AIR CURTAIN	40	2	8		2,900								BUSSED SPACE	70
71							2,900							BUSSED SPACE	72
73	SPARE	20	1											BUSSED SPACE	74
75	SPARE	20	1											BUSSED SPACE	76
77	SPARE	20	1											BUSSED SPACE	78
79	SPARE	20	1											BUSSED SPACE	80
81	SPARE	20	1											BUSSED SPACE	82
83	SPARE	20	1											BUSSED SPACE	84
NOTES:					9,540	12,930	12,150	13,190	13,100	14,950					
(GF)-GF/GI BRKR, (HL)-HANDLE LOCK					22,730		26,030		27,130	TOTAL CONNECTED LOAD:		75,840 VA			
(GF)-GF/GI BRKR											NEG DEMAND LOAD:		70,855 VA		
											DEMAND AMPS @ 208 VOLT / 3Ø:		196.67		

SHEET FILE LOCATION: N:\2022\22823\ELEC\22823E.DWG
LAST SAVED: 11/30/2022 5:13 PM
BY: PAUL




D/T MENUBOARD
SCALE: 1/4" = 1'-0"

CANOPY LIGHTING PLAN
SCALE: 1" = 30"

ELECTRICAL SITE PLAN
SCALE: 1" = 30"

ELECTRICAL PLAN NOTES:

- 3/4" C FOR POWER CONNECTION TO DISPENSER (8 TOTAL.) VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- 3/4" C FOR INTERCOM CONNECTION DISPENSER (8 TOTAL.) VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- 3/4" C FOR VEEDER ROOT CONDUCTORS FOR SUMP SENSOR (8 TOTAL.) VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- CONNECT TO MONUMENT SIGN PER MANUFACTURER'S INSTRUCTIONS. VERIFY EXACT LOCATION AND ELECTRICAL REQUIREMENTS. ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTACTOR. SEE EXTERIOR LIGHTING DIAGRAM SHEET E-101
- CONNECT TO CANOPY SIGN PER MANUFACTURER'S INSTRUCTIONS. VERIFY EXACT LOCATION AND ELECTRICAL REQUIREMENTS. ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTACTOR. SEE EXTERIOR LIGHTING DIAGRAM SHEET E-101
- ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTACTOR IN 1" C FOR EACH CIRCUIT. SEE EXTERIOR LIGHTING DIAGRAM SHEET E-101
- 3/4" C FOR POWER TO EACH STP MOTOR (4 TOTAL). VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- (18) TOTAL 3/4" C FOR VEEDER ROOT CONDUCTORS. VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- BUILDING MOUNTED ELECTRICAL SERVICE EQUIPMENT. SEE RISER DIAGRAM, SHEET E-201.
- PROVIDE RED PUSHBUTTON TYPE SWITCH TO PROVIDE MASTER EMERGENCY SHUTOFF OF FUEL DISPENSING STATIONS. PROVIDE SIGN ADJACENT TO SWITCH INDICATING PURPOSE. EMERGENCY SWITCH AND ALL COMPONENTS SHALL BE IN ACCORDANCE WITH NEC 514. VERIFY EXACT LOCATION PRIOR TO ROUGH-IN. (EMERGENCY STOP MUST BE GREATER THAN 20 FT AND LESS THAN 100 FT FROM DISPENSERS.) (1) 3/4" C FROM TANK AREA TO PUSHBUTTON LOCATION FOR CONDUCTORS.
- PROPOSED LOCATION OF KNOX BOX / KEY BOX. VERIFY LOCATION WITH FIRE MARSHAL.
- COORDINATE PLACEMENT OF PRIMARY AND SECONDARY CONDUITS, PAD FOR UTILITY TRANSFORMER, AND MOUNTING OF METERS AND CT CABINETS WITH EVERGY.
- TO EXISTING PRIMARY ELECTRICAL SERVICE. VERIFY WITH CIVIL PLANS EXACT LOCATION.
- (1) 2" CONDUIT FOR SPEAKER/MIC, (1) 2" C FOR HDMI, (1) 1" C FOR POWER. VERIFY LOCATION OF DIGITAL MENUBOARD WITH OWNER.
- DIRECT BURIAL LOOP FOR DRIVE-THRU. VERIFY ELECTRICAL REQUIREMENTS WITH MANUFACTURER'S INSTRUCTIONS - LIKE THOSE FROM THE HOWARD COMPANY (WWW.HOWARDCOMPANY.COM.)



This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2022 BC Engineers, Inc.

PE COA #2009003629

4/28/2023



PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

SHEET TITLE
ELECTRICAL SITE PLAN

E301