CONSTRUCTION STAKE PLOT PLAN

Ordered by: Elevate Design and Build LLC

Lag 957.0

956

MSFF 947 59

12.7

0 30' B.L.

5' U.E.

SAN

, NX

955.9

|957.0

R=325' L=66.95

Description: Lot 141 Hook Farms, Second Plat, Lee's Summit, MO. Address: 2626 SW Firefly Ln. Lot Area 10,818 sf As-graded plot plan per Sec. 7-160 Code of j.F956.0 Ordinances is required prior to occupancy. 1.86' S25°16'18"W E.F955.5 73.3' S29°10'47"W £.F.956.6 7.5' X 6.0' U.E 957 £957.0 140.03' S73°35'53"E 141 10/09/2024 Bar 957.0 **E**956.0 *6951.5) £957.9 0 E956.7 Cov Patio F958.5 9 opp Egress Well S61°47'43"E 28 Top 957.7 Lag 957.2 6' o/s Bars 62' x 55 8' Walls MBOE 957.5 Egress Well 10' Top 957.5 MBOE Per MDP

83

E-F955.6 E95k E956.A SW Firefly Lane Lat Sta 11+08.46 42.61' Lat F/L 944.8 MH Sta 11+19.66 SAN

F956.2

20

20.67

€957.2 F95°

12'

E-F956.7

SAN

Staked 10-03-2024

This plot plan is not an "as-built" survey as the house was staked prior to being built and cannot be used in place of a "Surveyors Real Property Report". This plot plan was prepared for use before and during foundation construction only and should not be used to establish property lines for fences or other structures. House staked as shown on this plot plan. House dimensions may have been assumed and contractor must check house dimensions shown and compare to the final house plans. Contractor to verify all elevations at job site. Builder must make final decision as to cuts and foundation heights at the job site, any floor elevations shown are shown as a quide only. Sanitary sewer and lateral elevations cannot be verified at time of staking, and it may be necessary to expose sanitary sewer service connection prior to excavation for foundation. Underground utilities and un-platted easements may not be shown. This does not constitute a boundary survey and builder must check to make sure description shown is correct with the deed for the property. It is recommended that no work be done until building permits are obtained and plot plan has been verified by local building codes authorities to comply with all setback and other restrictions.

Top 955.62 Inv 942.57

RN CONSTRUCTION ENGINEERING SERVICES, INC.

16810-C East 40 Highway
Independence, MO 64055 = DRAINAGE PATTERN BODED:
NUMBER
LS-2114
LAND
LAND (816)478-2323 lee@engineeringkc.com

SCALE: 1"=20' DATE: 10-03-2024 JOB NO: 19218

Front left 955.85 Front Right 956.89

Standard Basement Top Fdn 959.0

Standard Full Basement

Low opening is egress Well el 957.5

Gar Flr 958.5

Bas Flr 951.3 8' Wall

MBOE