RE: 3603730
Summit/193 Highland Meadows

MiTek USA, Inc.
16023 Swingley Ridge Rd
Chesterfield, MO 63017
314-434-1200

Site Information:

Customer: Project Name: 3603730
Lot/Block: Model:
Address: Subdivision:
City: State:

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2018/TPI2014 Design Program: MiTek 20/20 8.6
Wind Code: ASCE 7-16 Wind Speed: 115 mph
Roof Load: 45.0 psf Floor Load: N/A psf

This package includes 75 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I58837488	A1	6/12/2023	21	I58837508	CJ8	6/12/2023
2	I58837489	A2	6/12/2023	22	I58837509	CJ9	6/12/2023
3	I58837490	A3	6/12/2023	23	I58837510	CJ10	6/12/2023
4	I58837491	A4	6/12/2023	24	I58837511	D1	6/12/2023
5	I58837492	A5	6/12/2023	25	I58837512	D2	6/12/2023
6	I58837493	A6	6/12/2023	26	I58837513	E1	6/12/2023
7	I58837494	A7	6/12/2023	27	I58837514	E2	6/12/2023
8	I58837495	A8	6/12/2023	28	I58837515	E3	6/12/2023
9	I58837496	A9	6/12/2023	29	I58837516	E4	6/12/2023
10	I58837497	B1	6/12/2023	30	I58837517	F1	6/12/2023
11	I58837498	B1A	6/12/2023	31	I58837518	F2	6/12/2023
12	I58837499	B2	6/12/2023	32	I58837519	F3	6/12/2023
13	I58837500	B3	6/12/2023	33	I58837520	F4	6/12/2023
14	I58837501	CJ1	6/12/2023	34	I58837521	J1	6/12/2023
15	I58837502	CJ2	6/12/2023	35	I58837522	J2	6/12/2023
16	I58837503	CJ3	6/12/2023	36	I58837523	J3	6/12/2023
17	I58837504	CJ4	6/12/2023	37	I58837524	J4	6/12/2023
18	I58837505	CJ5	6/12/2023	38	I58837525	J5	6/12/2023
19	I58837506	CJ6	6/12/2023	39	I58837526	J6	6/12/2023
20	I58837507	CJ7	6/12/2023	40	I58837527	J7	6/12/2023

The truss drawing(s) referenced above have been prepared by MiTek USA, Inc under my direct supervision based on the parameters provided by Builders FirstSource (Valley Center).

Truss Design Engineer's Name: Sevier, Scott

My license renewal date for the state of Missouri is December 31, 2023.

Missouri COA: 001193

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

June 12, 2023

Sevier, Scott

MiTek USA, Inc.
16023 Swingley Ridge Rd
Chesterfield, MO 63017
314-434-1200

RE: 3603730 - Summit/193 Highland Meadows

Site Information:

Project Customer: Project Name: 3603730
Lot/Block: Subdivision:
Address:
City, County: State:

No.	Seal#	Truss Name	Date
41	I58837528	J8	6/12/2023
42	I58837529	J9	6/12/2023
43	I58837530	J10	6/12/2023
44	I58837531	J11	6/12/2023
45	I58837532	J12	6/12/2023
46	I58837533	J13	6/12/2023
47	I58837534	J14	6/12/2023
48	I58837535	J15	6/12/2023
49	I58837536	J16	6/12/2023
50	I58837537	J17	6/12/2023
51	I58837538	J18	6/12/2023
52	I58837539	J19	6/12/2023
53	I58837540	J20	6/12/2023
54	I58837541	J21	6/12/2023
55	I58837542	J22	6/12/2023
56	I58837543	J23	6/12/2023
57	I58837544	J24	6/12/2023
58	I58837545	J25	6/12/2023
59	I58837546	J26	6/12/2023
60	I58837547	J27	6/12/2023
61	I58837548	J28	6/12/2023
62	I58837549	J29	6/12/2023
63	I58837550	L1	6/12/2023
64	I58837551	LG1	6/12/2023
65	I58837552	LG2	6/12/2023
66	I58837553	LG3	6/12/2023
67	I58837554	P1	6/12/2023
68	I58837555	P2	6/12/2023
69	I58837556	P3	6/12/2023
70	I58837557	P4	6/12/2023
71	I58837558	P5	6/12/2023
72	I58837559	P6	6/12/2023
73	I58837560	V1	6/12/2023
74	I58837561	V2	6/12/2023
75	I58837562	V3	6/12/2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	A1	Hip Girder	1	1	I58837488 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:37 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCbqi724zJC?f

-1-10-8 | 3-8-14 | 7-2-4 | 11-6-4 | 16-0-0 | 20-5-12 | 24-9-12 | 28-3-2 | 32-0-0 | 33-10-8
1-10-8 | 3-8-14 | 3-5-6 | 4-4-0 | 4-5-12 | 4-5-12 | 4-4-0 | 3-5-6 | 3-8-14 | 1-10-8

Scale = 1:60.2



3-8-14 | 7-2-4 | 11-6-4 | 16-0-0 | 20-5-12 | 24-9-12 | 28-3-2 | 32-0-0
3-8-14 | 3-5-6 | 4-4-0 | 4-5-12 | 4-5-12 | 4-4-0 | 3-5-6 | 3-8-14

Plate Offsets (X,Y)-- [2:Edge,0-4-4], [4:0-6-0,0-1-11], [9:0-6-0,0-1-11], [11:Edge,0-4-4], [14:0-3-8,0-4-4], [16:0-3-8,0-3-0], [18:0-3-8,0-3-0], [20:0-3-8,0-4-4]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.83	Vert(LL)	-0.59	17	>654	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.96	Vert(CT)	-1.05	17	>365	180	M18AHS	142/136
BCLL	0.0	Rep Stress Incr	NO	WB	0.86	Horz(CT)	0.17	11	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 174 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP 2400F 2.0E *Except*
4-7,7-9: 2x6 SPF 2100F 1.8E
BOT CHORD 2x6 SP 2400F 2.0E *Except*
15-19: 2x6 SPF 2100F 1.8E
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2 , Right: 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-0-13 oc purlins, except
2-0-0 oc purlins (2-4-1 max.): 4-9.
BOT CHORD Rigid ceiling directly applied or 6-3-10 oc bracing.

REACTIONS. (size) 2=0-3-8, 11=0-3-8
Max Horz 2=45(LC 25)
Max Uplift 2=-790(LC 4), 11=-790(LC 5)
Max Grav 2=3398(LC 1), 11=3398(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-7148/1577, 3-4=-8415/1909, 4-5=-10926/2522, 5-6=-11885/2732, 6-8=-11885/2732, 8-9=-10926/2522, 9-10=-8415/1910, 10-11=-7148/1578
BOT CHORD 2-21=-1466/6701, 20-21=-1466/6701, 18-20=-1762/7978, 17-18=-2452/10919, 16-17=-2421/10919, 14-16=-1717/7978, 13-14=-1422/6702, 11-13=-1422/6702
WEBS 3-21=-902/250, 3-20=-362/1573, 4-20=-122/682, 4-18=-847/3525, 5-18=-1162/314, 5-17=-325/1180, 6-17=-343/115, 8-17=-326/1179, 8-16=-1162/314, 9-16=-847/3524, 9-14=-122/682, 10-14=-363/1573, 10-13=-902/250

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 790 lb uplift at joint 2 and 790 lb uplift at joint 11.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 547 lb down and 132 lb up at 7-2-4, 284 lb down and 91 lb up at 8-0-12, 284 lb down and 91 lb up at 10-0-12, 284 lb down and 91 lb up at 12-0-12, 284 lb down and 91 lb up at 14-0-12, 284 lb down and 91 lb up at 16-0-0, 284 lb down and 91 lb up at 17-11-4, 284 lb down and 91 lb up at 19-11-4, 284 lb down and 91 lb up at 21-11-4, and 284 lb down and 91 lb up at 23-11-4, and 547 lb down and 132 lb up at 24-9-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

June 12,2023

Continued on page 2

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (plf)
      Vert: 1-4=-70, 4-9=-70, 9-12=-70, 22-25=-20
   Concentrated Loads (lb)
      Vert: 19=-284(B) 20=-547(B) 17=-284(B) 14=-547(B) 15=-284(B) 28=-284(B) 29=-284(B) 30=-284(B) 31=-284(B) 32=-284(B) 33=-284(B)

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	A2	Hip	1	1	I58037489 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:38 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSdPqnL8w3uIiXbGKWrCbci724zJC?f



Plate Offsets (X,Y)-- [2:0-4-13,Edge], [10:0-4-13,Edge]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	25.0	Plate Grip DOL	1.15	TC	0.76	Vert(LL)	-0.31	14	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.97	Vert(CT)	-0.56	12-14	>692	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.23	Horz(CT)	0.14	10	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 121 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2 *Except*
5-7: 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-6-0, Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (3-2-8 max.): 5-7.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 10=0-3-8
Max Horz 2=-56(LC 13)
Max Uplift 2=-313(LC 8), 10=-313(LC 9)
Max Grav 2=1571(LC 1), 10=1571(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-3016/623, 4-5=-2941/587, 5-6=-3516/725, 6-7=-3516/724, 7-8=-2941/587,
8-10=-3016/623
BOT CHORD 2-16=-508/2789, 14-16=-442/2792, 12-14=-450/2792, 10-12=-517/2789
WEBS 5-16=0/261, 5-14=-197/947, 6-14=-574/195, 7-14=-197/947, 7-12=0/261

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-3-14, Interior(1) 1-3-14 to 9-2-4, Exterior(2R) 9-2-4 to 13-8-9, Interior(1) 13-8-9 to 22-9-12, Exterior(2R) 22-9-12 to 27-4-1, Interior(1) 27-4-1 to 33-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 313 lb uplift at joint 2 and 313 lb uplift at joint 10.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	A3	Hip	1	1	I58837490 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:40 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3ulrXbGKWrCbqi724zJC?f



Plate Offsets (X,Y)-- [2:0-4-13,Edge], [10:0-4-13,Edge]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.76	Vert(LL)	-0.27	13-15	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.92	Vert(CT)	-0.64	13-15	>605	180	MT20HS	148/108
BCLL	0.0	Rep Stress Incr	YES	WB	0.34	Horz(CT)	0.14	10	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 125 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF 1650F 1.5E
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-6-0, Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except 2-0-0 oc purlins (3-5-3 max.): 5-7.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 10=0-3-8
Max Horz 2=-67(LC 17)
Max Uplift 2=-305(LC 8), 10=-305(LC 9)
Max Grav 2=1571(LC 1), 10=1571(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-3035/617, 4-5=-2789/576, 5-6=-2605/575, 6-7=-2605/575, 7-8=-2789/576, 8-10=-3035/617
BOT CHORD 2-16=-506/2817, 15-16=-506/2817, 13-15=-496/2841, 12-13=-515/2817, 10-12=-515/2817
WEBS 4-15=-258/131, 5-15=-37/478, 6-15=-471/148, 6-13=-471/148, 7-13=-37/478, 8-13=-258/132

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-3-14, Interior(1) 1-3-14 to 11-2-4, Exterior(2R) 11-2-4 to 16-0-0, Interior(1) 16-0-0 to 20-9-12, Exterior(2R) 20-9-12 to 25-4-1, Interior(1) 25-4-1 to 33-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 305 lb uplift at joint 2 and 305 lb uplift at joint 10.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	A4	Hip	1	1	I58837491 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:41 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSdPqnL8w3uliXbGKWrCbci724zJC?f



Plate Offsets (X,Y)-- [2:0-4-13,Edge], [9:0-4-13,Edge]

LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.87	Vert(LL)	-0.25	14-15	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.80	Vert(CT)	-0.47	14-15	>816	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.44	Horz(CT)	0.14	9	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 124 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF 1650F 1.5E
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-6-0, Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except 2-0-0 oc purlins (3-6-2 max.): 5-6.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 9=0-3-8
Max Horz 2=78(LC 16)
Max Uplift 2=-295(LC 8), 9=-295(LC 9)
Max Grav 2=1571(LC 1), 9=1571(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-3067/618, 4-5=-2579/563, 5-6=-2383/570, 6-7=-2579/563, 7-9=-3067/618
BOT CHORD 2-15=-501/2846, 14-15=-501/2846, 12-14=-380/2382, 11-12=-510/2846, 9-11=-510/2846
WEBS 4-14=-542/169, 5-14=-17/384, 6-12=-14/384, 7-12=-541/170

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-3-14, Interior(1) 1-3-14 to 13-2-4, Exterior(2R) 13-2-4 to 17-8-9, Interior(1) 17-8-9 to 18-9-12, Exterior(2R) 18-9-12 to 23-4-1, Interior(1) 23-4-1 to 33-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 295 lb uplift at joint 2 and 295 lb uplift at joint 9.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	A5	Common	3	1	I58837492 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:43 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSePqnL8w3uIiXbGKWrCbdi724zJC?f



Plate Offsets (X,Y)-- [7:0-3-0,Edge], [10:0-4-13,Edge]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.71	Vert(LL)	-0.29	12-14	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.85	Vert(CT)	-0.56	12-14	>703	180	MT20HS	148/108
BCLL	0.0	Rep Stress Incr	YES	WB	0.69	Horz(CT)	0.16	10	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 119 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2 *Except*
6-7,7-11: 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF 1650F 1.5E *Except*
13-15: 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-14

REACTIONS. (size) 2=0-3-8, 10=0-3-8
Max Horz 2=96(LC 12)
Max Uplift 2=-249(LC 8), 10=-282(LC 9)
Max Grav 2=1543(LC 1), 10=1619(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3776/669, 3-5=-3403/599, 5-6=-2355/483, 6-8=-2386/471, 8-10=-3186/570
BOT CHORD 2-16=-570/3531, 14-16=-422/2848, 12-14=-456/2954, 10-12=-456/2954
WEBS 3-16=-456/178, 5-16=-47/553, 5-14=-863/228, 6-14=-121/973, 8-14=-913/247, 8-12=0/274

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-5-2, Interior(1) 2-5-2 to 17-0-0, Exterior(2R) 17-0-0 to 20-3-10, Interior(1) 20-3-10 to 34-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) All plates are MT20 plates unless otherwise indicated.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 249 lb uplift at joint 2 and 282 lb uplift at joint 10.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	A6	Hip	1	1	I58837493 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:44 2023 Page 1

ID:icBJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

7-10-1	15-0-0	19-0-0	25-10-4	33-0-0	34-10-8
7-10-1	7-1-15	4-0-0	6-10-4	7-1-12	1-10-8

Scale = 1:58.2



7-10-1	15-0-0	19-0-0	25-10-4	33-0-0
7-10-1	7-1-15	4-0-0	6-10-4	7-1-12

Plate Offsets (X,Y)-- [1:0-1-1,0-0-10], [8:0-4-13,Edge]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	25.0	Plate Grip DOL	1.15	TC	0.96	Vert(LL)	-0.28	10-12	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.99	Vert(CT)	-0.53	10-12	>745	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.59	Horz(CT)	0.17	8	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 122 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
8-11: 2x4 SPF 1650F 1.5E
WEBS 2x4 SPF No.2
SLIDER Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (3-5-11 max.): 3-4.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 2-13

REACTIONS. (size) 1=0-3-8, 8=0-3-8
Max Horz 1=-89(LC 17)
Max Uplift 1=-229(LC 8), 8=-295(LC 9)
Max Grav 1=1481(LC 1), 8=1620(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-3705/723, 2-3=-2674/581, 3-4=-2422/561, 4-6=-2630/564, 6-8=-3195/613
BOT CHORD 1-15=-612/3449, 13-15=-612/3449, 12-13=-386/2448, 10-12=-503/2965, 8-10=-503/2965
WEBS 2-15=0/310, 2-13=-1073/259, 3-13=-44/482, 3-12=-266/205, 4-12=-35/399,
6-12=-641/189

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-3-10, Interior(1) 3-3-10 to 15-0-0, Exterior(2E) 15-0-0 to 19-0-0, Exterior(2R) 19-0-0 to 23-8-0, Interior(1) 23-8-0 to 34-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 229 lb uplift at joint 1 and 295 lb uplift at joint 8.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER
PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	A7	Hip	1	1	I58837494 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:46 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

6-10-1 | 13-0-0 | 19-6-0 | 21-0-0 | 25-7-4 | 30-2-8 | 33-0-0 | 34-10-8
6-10-1 | 6-1-15 | 6-6-0 | 1-6-0 | 4-7-4 | 4-7-4 | 2-9-8 | 1-10-8

Scale = 1:59.2



6-10-1 | 13-0-0 | 19-6-0 | 21-0-0 | 25-7-4 | 30-2-8 | 33-0-0
6-10-1 | 6-1-15 | 6-6-0 | 1-6-0 | 4-7-4 | 4-7-4 | 2-9-8

Plate Offsets (X,Y)-- [7:0-0-11,Edge], [8:0-2-7,0-2-5], [13:0-7-0,Edge], [14:Edge,0-3-8]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	25.0	Plate Grip DOL	1.15	TC	0.84	Vert(LL)	-0.44	12-13	>903	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.93	Vert(CT)	-0.79	12-13	>501	180	MT20HS	148/108
BCLL	0.0	Rep Stress Incr	YES	WB	0.73	Horz(CT)	0.35	8	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 160 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2 *Except*
5-9: 2x8 SP 2400F 2.0E
BOT CHORD 2x4 SPF No.2 *Except*
7-13: 2x4 SP 2400F 2.0E
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (2-2-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 1=0-3-8, 8=0-3-8
Max Horz 1=-82(LC 17)
Max Uplift 1=-239(LC 8), 8=-306(LC 9)
Max Grav 1=1481(LC 1), 8=1620(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-3763/742, 2-3=-2975/627, 3-4=-3587/788, 4-5=-3468/741, 5-6=-3675/749,
6-7=-5115/1003, 7-8=-570/154
BOT CHORD 1-17=-631/3511, 15-17=-631/3511, 14-15=-30/375, 12-13=-607/3586, 11-12=-905/5010,
7-11=-906/5011
WEBS 2-15=-820/224, 13-15=-423/2414, 3-13=-189/1038, 4-12=-429/124, 5-12=-200/1053,
6-12=-1688/366

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-3-10, Interior(1) 3-3-10 to 13-0-0, Exterior(2R) 13-0-0 to 17-8-0, Interior(1) 17-8-0 to 21-0-0, Exterior(2R) 21-0-0 to 25-7-4, Interior(1) 25-7-4 to 34-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 239 lb uplift at joint 1 and 306 lb uplift at joint 8.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	A8	Hip	1	1	I58937495 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:47 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSePqnL8w3uIi XbGKWr-bqi7?4zJC?f

Scale = 1:59.2



Plate Offsets (X,Y)-- [7:0-5-4,0-2-8], [9:0-2-7,0-0-12], [10:0-8-0,Edge], [19:0-2-12,0-3-0], [20:0-2-12,Edge], [21:Edge,0-1-8]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	-0.25	9-13	>984	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.81	Vert(CT)	-0.46	9-13	>540	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.45	Horz(CT)	0.11	10	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 144 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
7-11: 2x6 SPF 2100F 1.8E

BOT CHORD 2x4 SPF No.2 *Except*
9-16: 2x4 SPF 1650F 1.5E, 10-12: 2x6 SPF No.2

WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (5-2-1 max.): 3-7.

BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 1=0-3-8, 21=0-3-0, 10=0-3-8
Max Horz 1=-69(LC 17)
Max Uplift 1=-93(LC 12), 21=-283(LC 8), 10=-227(LC 9)
Max Grav 1=347(LC 25), 21=1885(LC 1), 10=930(LC 26)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-441/298, 2-3=-32/682, 3-4=-414/2550, 4-5=-430/2578, 5-6=-988/222, 6-7=-1056/282, 7-8=-1437/331, 8-9=-2369/503, 9-10=-410/114

BOT CHORD 1-23=-260/387, 22-23=-260/387, 20-21=-1902/332, 19-20=-747/204, 6-19=-335/127, 13-14=-423/2334, 9-13=-423/2335, 9-12=-45/319

WEBS 2-22=-864/203, 3-22=-302/1450, 20-22=-1331/316, 3-20=-2707/569, 7-14=-12/260, 8-14=-1076/251, 5-20=-2026/414, 5-19=-301/1830, 14-19=-191/1252, 7-19=-338/114

NOTES-

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-3-10, Interior(1) 3-3-10 to 11-0-0, Exterior(2R) 11-0-0 to 15-8-0, Interior(1) 15-8-0 to 23-0-0, Exterior(2R) 23-0-0 to 27-8-0, Interior(1) 27-8-0 to 34-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 1, 283 lb uplift at joint 21 and 227 lb uplift at joint 10.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	A9	HIP GIRDER	1	3	I58837496 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:50 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NS[illegible]PqnL8[illegible]

4-10-1	9-0-0	14-3-0	19-6-0	25-0-0	30-2-8	30-8-8	33-0-0	34-10-8
4-10-1	4-1-15	5-3-0	5-3-0	5-6-0	5-2-8	0-6-0	2-3-8	1-10-8

Scale = 1:59.2



4-10-1	9-0-0	14-3-0	19-6-0	25-0-0	30-2-8	30-8-8	33-0-0
4-10-1	4-1-15	5-3-0	5-3-0	5-6-0	5-2-8	0-6-0	2-3-8

Plate Offsets (X,Y)-- [5:0-5-8,0-2-4], [6:0-8-8,0-0-0], [8:Edge,0-1-12], [13:0-5-4,Edge], [14:Edge,0-3-8]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.82	Vert(LL)	-0.58	12-13	>677	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.95	Vert(CT)	-1.05	12-13	>377	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.86	Horz(CT)	0.33	8	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 445 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP 2400F 2.0E *Except*
2-5: 2x4 SPF 1650F 1.5E, 5-9: 2x8 SP 2400F 2.0E
BOT CHORD 2x4 SPF No.2 *Except*
1-16,6-13: 2x4 SP 2400F 2.0E
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except
2-0-0 oc purlins (5-10-8 max.): 2-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=0-3-8, 8=0-3-8
Max Horz 1=-61(LC 34)
Max Uplift 1=-860(LC 4), 8=-888(LC 5)
Max Grav 1=3925(LC 1), 8=3775(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-10084/2273, 2-3=-11591/2700, 3-4=-16697/3842, 4-5=-17203/3957,
5-6=-14118/3202, 6-7=-1082/306, 7-8=-1211/319
BOT CHORD 1-17=-2114/9530, 15-17=-2102/9461, 14-15=-315/1398, 13-14=-129/614, 4-13=-289/166,
12-13=-3003/13692, 6-12=-3003/13692
WEBS 2-17=-252/1433, 2-15=-677/2682, 3-15=-2455/606, 13-15=-2376/10505, 3-13=-1211/5336,
5-13=-932/3887, 5-12=-390/1845, 7-10=-47/298

NOTES-
1) 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-7-0 oc, 2x8 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 2 rows staggered at 0-7-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 860 lb uplift at joint 1 and 888 lb uplift at joint 8.
8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

Continued on page 2

NOTES-

10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 379 lb down and 89 lb up at 3-0-12, 323 lb down and 79 lb up at 5-0-12, 323 lb down and 79 lb up at 7-0-12, 323 lb down and 100 lb up at 9-0-12, 323 lb down and 100 lb up at 11-0-12, 323 lb down and 100 lb up at 13-0-12, 323 lb down and 100 lb up at 15-0-12, 323 lb down and 100 lb up at 17-0-0, 323 lb down and 100 lb up at 18-11-4, 323 lb down and 99 lb up at 20-11-4, and 323 lb down and 99 lb up at 22-11-4, and 989 lb down and 281 lb up at 24-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (plf)
      Vert: 1-2=-70, 2-5=-70, 5-9=-70, 14-18=-20, 13-21=-20, 11-24=-20
   Concentrated Loads (lb)
      Vert: 17=-323(F) 12=-989(F) 27=-379(F) 28=-323(F) 29=-323(F) 30=-323(F) 31=-323(F) 32=-323(F) 33=-323(F) 34=-323(F) 35=-323(F) 36=-323(F)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	B1	Roof Special	1	1	I58837497 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:52 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NS...



Plate Offsets (X,Y)-- [2:0-2-14,0-2-8], [3:0-7-4,Edge], [5:0-9-8,0-2-0], [8:0-3-0,Edge], [11:0-4-13,Edge], [15:0-3-0,0-2-4], [18:0-6-0,0-2-0], [19:0-3-8,0-1-8]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.82	Vert(LL)	-0.80	17	>511	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.89	Vert(CT)	-1.43	17-18	>284	180	M18AHS	142/136
BCLL	0.0	Rep Stress Incr	YES	WB	0.72	Horz(CT)	0.26	11	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 144 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF 1650F 1.5E *Except*
1-3: 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
17-20: 2x4 SP 2400F 2.0E, 11-14: 2x4 SPF 1650F 1.5E
WEBS 2x4 SPF No.2 *Except*
7-17,5-18,3-18: 2x4 SPF 1650F 1.5E
SLIDER Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 9-15

REACTIONS. (size) 20=0-3-8, 11=0-3-8
Max Horz 20=-129(LC 45)
Max Uplift 20=-306(LC 8), 11=-288(LC 9)
Max Grav 20=1634(LC 1), 11=1652(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1960/352, 3-4=-6205/1091, 4-5=-6205/1091, 5-6=-6524/1139, 6-7=-6304/1175, 7-9=-2485/508, 9-11=-3274/597, 2-20=-1659/387
BOT CHORD 18-19=-259/1956, 17-18=-1381/8544, 13-15=-481/3036, 11-13=-481/3036
WEBS 3-19=-779/152, 5-17=-2949/550, 15-17=-290/2233, 7-17=-770/4454, 7-15=-309/112, 9-15=-912/244, 9-13=0/281, 2-19=-380/2120, 4-18=-474/142, 5-18=-2519/510, 3-18=-783/4412

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-6-5, Interior(1) 1-6-5 to 1-10-4, Exterior(2E) 1-10-4 to 5-3-1, Interior(1) 5-3-1 to 18-0-0, Exterior(2R) 18-0-0 to 21-4-13, Interior(1) 21-4-13 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 306 lb uplift at joint 20 and 288 lb uplift at joint 11.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 64 lb down and 167 lb up at 1-10-4 on top chord, and 25 lb down and 32 lb up at 1-10-4, 22 lb down and 31 lb up at 1-11-0, and 22 lb down and 31 lb up at 3-11-0, and 22 lb down and 31 lb up at 5-11-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

Continued on page 2

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER
PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

NOTES-

11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (plf)
      Vert: 1-2=-70, 2-3=-70, 3-5=-70, 5-7=-70, 7-12=-70, 17-20=-20, 16-21=-20
   Concentrated Loads (lb)
      Vert: 3=33(F)

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	B1A	Roof Special	1	1	I58837498 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:55 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCpqi724zJC?f



Plate Offsets (X,Y)-- [2:0-2-14,0-2-8], [3:0-7-4,Edge], [7:0-3-4,0-2-12], [12:0-4-13,Edge], [18:0-8-12,0-4-12], [20:0-3-8,0-1-8]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.90	Vert(LL)	-0.76	17	>537	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.86	Vert(CT)	-1.36	17	>299	180	M18AHS	142/136
BCLL	0.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.24	12	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 156 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2 *Except*
3-5,9-13: 2x4 SPF 1650F 1.5E, 5-7: 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
18-21: 2x6 SPF 2100F 1.8E, 12-15: 2x4 SPF 1650F 1.5E
WEBS 2x4 SPF No.2 *Except*
7-18: 2x4 SPF 1650F 1.5E
SLIDER Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 3-5, 7-8.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-19

REACTIONS. (size) 12=0-3-8, 21=0-3-8
Max Horz 21=-125(LC 13)
Max Uplift 12=-293(LC 9), 21=-311(LC 8)
Max Grav 12=1652(LC 1), 21=1634(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2275/418, 3-4=-6176/1118, 4-5=-6174/1116, 5-6=-6932/1266, 6-7=-6721/1294, 7-8=-2391/539, 8-10=-2592/540, 10-12=-3277/606, 2-21=-1753/409
BOT CHORD 19-20=-292/2232, 18-19=-1608/9407, 14-16=-492/3040, 12-14=-492/3040
WEBS 3-20=-541/110, 5-18=-3411/650, 8-16=-43/488, 10-16=-787/223, 10-14=0/258, 2-20=-434/2323, 4-19=-404/130, 3-19=-727/4085, 7-16=-919/174, 5-19=-3379/674, 16-18=-367/2559, 7-18=-818/4563

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-6-5, Interior(1) 1-6-5 to 1-10-4, Exterior(2E) 1-10-4 to 5-3-1, Interior(1) 5-3-1 to 17-2-4, Exterior(2E) 17-2-4 to 18-9-12, Exterior(2R) 18-9-12 to 22-2-9, Interior(1) 22-2-9 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) The Fabrication Tolerance at joint 18 = 16%
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) Bearing at joint(s) 21 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 293 lb uplift at joint 12 and 311 lb uplift at joint 21.
9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Continued on page 2

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows I58837498
3603730	B1A	Roof Special	1	1	Job Reference (optional)

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCbdi7J4zJC?f

NOTES-

12) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 64 lb down and 167 lb up at 1-10-4 on top chord, and 25 lb down and 32 lb up at 1-10-4, 22 lb down and 31 lb up at 1-11-0, and 22 lb down and 31 lb up at 3-11-0, and 22 lb down and 31 lb up at 5-11-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
13) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (plf)
      Vert: 1-2=-70, 2-3=-70, 3-5=-70, 5-7=-70, 7-8=-70, 8-13=-70, 18-21=-20, 17-22=-20
   Concentrated Loads (lb)
      Vert: 3=33(B)

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	B2	Roof Special	2	1	I58837499 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:56 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uli Xb GKWr Poi724zJC?f

-1-10-8	3-10-4	8-1-8	8-3-8	12-4-12	12-8-12	18-0-0	25-10-4	34-0-0	35-10-8
1-10-8	3-10-4	4-3-4	0-2-0	4-1-4	0-4-0	5-3-4	7-10-4	8-1-12	1-10-8

Scale: 3/16"=1'



3-10-4	8-3-8	12-4-12	18-0-0	25-10-4	34-0-0
3-10-4	4-5-4	4-1-4	5-7-4	7-10-4	8-1-12

Plate Offsets (X,Y)-- [2:0-8-5,Edge], [6:0-9-12,0-2-0], [11:0-4-13,Edge], [15:0-3-0,0-3-0], [19:0-3-8,0-2-8]

LOADING (psf)		**SPACING-** 2-0-0	**CSI.**	**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	25.0	Plate Grip DOL 1.15	TC 0.90	Vert(LL)	-0.65	17	>632	240	MT20	197/144
TCDL	10.0	Lumber DOL 1.15	BC 0.96	Vert(CT)	-1.16	17	>351	180	M18AHS	142/136
BCLL	0.0	Rep Stress Incr YES	WB 0.77	Horz(CT)	0.23	11	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014	Matrix-AS						Weight: 145 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF 1650F 1.5E *Except*
14-17: 2x4 SPF No.2
WEBS 2x4 SPF No.2 *Except*
7-18: 2x4 SPF 1650F 1.5E
SLIDER Left 2x8 SP 2400F 2.0E 2-6-0, Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (2-2-14 max.): 4-6.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-16, 9-15

REACTIONS. (size) 2=0-3-8, 11=0-3-8
Max Horz 2=-142(LC 13)
Max Uplift 2=-297(LC 8), 11=-282(LC 9)
Max Grav 2=1665(LC 1), 11=1664(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-2763/501, 4-5=-5191/936, 5-6=-6300/1124, 6-7=-6559/1205, 7-9=-2529/510,
9-11=-3303/603
BOT CHORD 2-20=-326/2531, 19-20=-330/2540, 18-19=-787/5188, 13-15=-487/3063, 11-13=-487/3063
WEBS 6-18=-2298/472, 7-15=-344/113, 9-15=-894/240, 9-13=0/275, 15-18=-312/2349,
7-18=-786/4713, 5-19=-1025/241, 4-19=-504/2885, 5-18=-217/1203

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-6-5, Interior(1) 1-6-5 to 3-10-4, Exterior(2R) 3-10-4 to 7-3-1, Interior(1) 7-3-1 to 18-0-0, Exterior(2R) 18-0-0 to 21-4-13, Interior(1) 21-4-13 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 297 lb uplift at joint 2 and 282 lb uplift at joint 11.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	B3	Roof Special	1	1	I58837590 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:58 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWr-0oi724zJC?f

Scale: 3/16"=1'



Plate Offsets (X,Y)-- [2:Edge,0-0-0], [11:0-4-13,Edge], [15:0-3-12,Edge]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.87	Vert(LL)	-0.41	5	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.84	Vert(CT)	-0.82	13-15	>495	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.17	11	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 152 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP 2400F 2.0E *Except*
6-7: 2x4 SPF No.2, 7-8,8-12: 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF No.2 *Except*
2-17: 2x4 SP 2400F 2.0E, 11-14: 2x4 SPF 1650F 1.5E
WEBS 2x4 SPF No.2
SLIDER Left 2x8 SP 2400F 2.0E 2-6-0, Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (2-7-15 max.): 4-6.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-15

REACTIONS. (size) 2=0-3-8, 11=0-3-8
Max Horz 2=-142(LC 13)
Max Uplift 2=-299(LC 8), 11=-281(LC 9)
Max Grav 2=1661(LC 1), 11=1661(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-2987/552, 4-5=-4870/919, 5-6=-4746/897, 6-7=-2916/623, 7-9=-3088/620,
9-11=-3299/625
BOT CHORD 2-18=-367/2755, 17-18=-371/2756, 5-17=-615/187, 13-15=-325/2265, 11-13=-508/3061
WEBS 4-17=-410/2264, 15-17=-507/3645, 6-17=-475/2930, 6-15=-3093/549, 7-15=-179/1045,
7-13=-160/864, 9-13=-479/219

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-6-5, Interior(1) 1-6-5 to 5-10-4, Exterior(2R) 5-10-4 to 9-3-1, Interior(1) 9-3-1 to 18-0-0, Exterior(2R) 18-0-0 to 21-4-13, Interior(1) 21-4-13 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 299 lb uplift at joint 2 and 281 lb uplift at joint 11.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ1	Diagonal Hip Girder	2	1	I58937591 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:12:59 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NScPqnL8w3uITXbGKWrCDoi7J4zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.33	Vert(LL)	-0.03	7-8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.06	7-8	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.30	Horz(CT)	0.01	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 46 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-4-9, 7=Mechanical
Max Horz 2=97(LC 27)
Max Uplift 2=-191(LC 4), 7=-103(LC 8)
Max Grav 2=617(LC 1), 7=575(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-797/136
BOT CHORD 2-8=-154/731, 7-8=-154/731
WEBS 3-7=-704/168

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 191 lb uplift at joint 2 and 103 lb uplift at joint 7.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 83 lb down and 173 lb up at 1-7-11, 12 lb down and 15 lb up at 2-9-8, 15 lb down and 32 lb up at 4-5-10, 35 lb down and 52 lb up at 5-7-7, and 52 lb down and 76 lb up at 7-3-10, and 76 lb down and 87 lb up at 8-5-6 on top chord, and 11 lb down and 64 lb up at 1-7-11, 10 lb down and 6 lb up at 2-9-8, 24 lb down and 7 lb up at 4-5-10, 22 lb down at 5-7-7, and 33 lb down at 7-3-10, and 45 lb down at 8-5-6 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-4=-70, 4-5=-20, 6-9=-20
Concentrated Loads (lb)
Vert: 12=49(F) 15=-6(B) 16=-45(F) 17=-76(B) 18=32(F) 19=6(B) 20=7(F) 21=-12(B) 22=-29(F) 23=-41(B)

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ2	Diagonal Hip Girder	1	1	I58937592 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:02 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCbdi724zJC?f



Plate Offsets (X,Y)-- [3:0-0-8,0-1-3]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.22	3-9	>595	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.91	Vert(CT)	-0.41	3-9	>320	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.42	Horz(CT)	0.17	8	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 46 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SPF 2100F 1.8E
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-10-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 8-10-14 oc bracing.

REACTIONS. (size) 8=Mechanical, 2=0-4-9
Max Horz 2=90(LC 5)
Max Uplift 8=-154(LC 8), 2=-227(LC 4)
Max Grav 8=694(LC 1), 2=779(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1695/407
BOT CHORD 3-9=-427/1701, 8-9=-426/1699
WEBS 4-8=-1726/450

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 154 lb uplift at joint 8 and 227 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 12 lb down and 15 lb up at 2-9-8, 12 lb down and 15 lb up at 2-9-8, 32 lb down and 39 lb up at 5-7-7, 32 lb down and 39 lb up at 5-7-7, and 59 lb down and 73 lb up at 8-5-6, and 59 lb down and 73 lb up at 8-5-6 on top chord, and 10 lb down and 6 lb up at 2-9-8, 10 lb down and 6 lb up at 2-9-8, 32 lb down and 25 lb up at 5-7-7, 32 lb down and 25 lb up at 5-7-7, and 61 lb down and 32 lb up at 8-5-6, and 61 lb down and 32 lb up at 8-5-6 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-70, 3-5=-70, 5-6=-20, 10-11=-20, 3-7=-20
Concentrated Loads (lb)
Vert: 15=-12(F=-6, B=-6) 16=-109(F=-54, B=-54) 17=12(F=6, B=6) 18=-63(F=-32, B=-32) 19=-123(F=-61, B=-61)

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ3	Diagonal Hip Girder	1	1	I58837593 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:03 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCDoi724zJC?f



Plate Offsets (X,Y)-- [2:0-0-0,0-0-15]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	0.00	6-9	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	0.00	6-9	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.00	Horz(CT)	-0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 14 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-8-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 6=Mechanical, 2=0-4-3
Max Horz 2=43(LC 11)
Max Uplift 6=-1(LC 9), 2=-167(LC 8)
Max Grav 6=61(LC 3), 2=396(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -2-7-13 to 1-7-1, Exterior(2R) 1-7-1 to 2-8-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1 lb uplift at joint 6 and 167 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

MiTek®
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ4	Diagonal Hip Girder	2	1	I58837594 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:04 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uli Xb GKWrCpci724zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	-0.01	8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.18	Vert(CT)	-0.01	7-8	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.06	Horz(CT)	0.00	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 31 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-4-9, 7=Mechanical
Max Horz 2=78(LC 7)
Max Uplift 2=-164(LC 4), 7=-49(LC 8)
Max Grav 2=508(LC 1), 7=256(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-311/36
BOT CHORD 2-8=-36/261, 7-8=-36/261
WEBS 3-7=-278/55

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 164 lb uplift at joint 2 and 49 lb uplift at joint 7.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 17 lb down and 30 lb up at 3-10-4, and 17 lb down and 30 lb up at 3-10-4 on top chord, and 11 lb down and 1 lb up at 3-10-4, and 11 lb down and 1 lb up at 3-10-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-4=-70, 4-5=-20, 6-9=-20
Concentrated Loads (lb)
Vert: 13=2(F=1, B=1)

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ5	Diagonal Hip Girder	1	1	I58837595 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:05 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NS...PqnL8...



Plate Offsets (X,Y)-- [2:0-0-0,0-0-15]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	25.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	0.01	6-9	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.11	Vert(CT)	0.01	6-9	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.00	Horz(CT)	-0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 19 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-4-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 6=Mechanical, 2=0-4-3
Max Horz 2=58(LC 7)
Max Uplift 6=-24(LC 8), 2=-158(LC 4)
Max Grav 6=117(LC 37), 2=388(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 24 lb uplift at joint 6 and 158 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 81 lb down and 170 lb up at 1-8-1, and 14 lb down and 27 lb up at 1-8-1 on top chord, and 11 lb down and 63 lb up at 1-8-1, and 8 lb down and 0 lb up at 1-8-1 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-70, 3-4=-20, 5-7=-20
Concentrated Loads (lb)
Vert: 10=48(B) 11=24(F=-8, B=32)

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER
PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ6	Diagonal Hip Girder	1	1	I58837596 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:06 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSdPqnL8w3uIiXbGKWrCbdi724zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	-0.06	8-9	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.88	Vert(CT)	-0.12	8-9	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.52	Horz(CT)	0.03	8	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 60 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SPF No.2
BOT CHORD 2x4 SPF 1650F 1.5E
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-4-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-4-9, 8=Mechanical
Max Horz 2=114(LC 7)
Max Uplift 2=-232(LC 4), 8=-189(LC 8)
Max Grav 2=923(LC 1), 8=1042(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1501/243, 3-4=-1348/243
BOT CHORD 2-10=-260/1397, 9-10=-260/1397, 8-9=-236/1296
WEBS 4-9=-71/579, 4-8=-1429/281

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 232 lb uplift at joint 2 and 189 lb uplift at joint 8.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 21 lb down and 35 lb up at 4-2-8, 21 lb down and 35 lb up at 4-2-8, and 49 lb down and 72 lb up at 7-0-7, and 49 lb down and 72 lb up at 7-0-7 on top chord, and 12 lb down at 4-2-8, 12 lb down at 4-2-8, 32 lb down at 7-0-7, 32 lb down at 7-0-7, and 263 lb down and 86 lb up at 9-10-6, and 263 lb down and 86 lb up at 9-10-6 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-5=-70, 5-6=-20, 7-11=-20
Concentrated Loads (lb)
Vert: 10=-1(F=-1, B=-1) 14=-78(F=-39, B=-39) 15=-54(F=-27, B=-27) 16=-526(F=-263, B=-263)

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ7	Jack-Open	1	1	I58837597 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:07 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCoi7J4zJC?f



Plate Offsets (X,Y)-- [2:0-0-0,0-0-15]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	0.00	7	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	0.00	7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 10 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-9-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-4-9, 4=Mechanical
Max Horz 2=46(LC 8)
Max Uplift 3=-50(LC 1), 2=-181(LC 8), 4=-12(LC 1)
Max Grav 3=36(LC 8), 2=405(LC 1), 4=19(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 50 lb uplift at joint 3, 181 lb uplift at joint 2 and 12 lb uplift at joint 4.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ8	Diagonal Hip Girder	1	1	Job Reference (optional) I58837598

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:08 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NS PqnL8v3uli Xb GKWr 9oi724zJC?f



LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	0.02	6-9	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.23	Vert(CT)	0.03	6-9	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.00	Horz(CT)	-0.01	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 20 lb	FT = 20%

(SPACING- 2-0-0)

LUMBER-
TOP CHORD 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-7-1 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 6=Mechanical, 2=0-4-9
Max Horz 2=60(LC 7)
Max Uplift 6=-31(LC 21), 2=-151(LC 4)
Max Grav 6=119(LC 37), 2=354(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 6 and 151 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 73 lb down and 152 lb up at 1-10-3, and 73 lb down and 152 lb up at 1-10-3 on top chord, and 11 lb down and 58 lb up at 1-10-3, and 11 lb down and 58 lb up at 1-10-3 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
7) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-70, 3-4=-20, 5-7=-20
Concentrated Loads (lb)
Vert: 10=86(F=43, B=43) 11=59(F=30, B=30)

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ9	Jack-Open	2	1	I58837599 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:09 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCDqi724zJC?f



Plate Offsets (X,Y)-- [3:0-2-15,0-0-8]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	0.00	5-6	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.18	Vert(CT)	0.00	5-6	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.02	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 11 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-5-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 6=0-4-9, 5=Mechanical, 3=Mechanical
Max Horz 6=37(LC 11)
Max Uplift 6=-177(LC 8), 5=-17(LC 25), 3=-68(LC 25)
Max Grav 6=421(LC 1), 5=40(LC 3), 3=18(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-6=-361/340

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -2-7-13 to 1-7-1, Exterior(2R) 1-7-1 to 2-2-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) Refer to girder(s) for truss to truss connections.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 177 lb uplift at joint 6, 17 lb uplift at joint 5 and 68 lb uplift at joint 3.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	CJ10	Jack-Open	2	1	I58837510 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:00 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	-0.00	7	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	-0.00	4-7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 8 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-6-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-4-7, 4=Mechanical
Max Horz 2=34(LC 8)
Max Uplift 3=-23(LC 12), 2=-78(LC 8)
Max Grav 3=64(LC 1), 2=230(LC 1), 4=42(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 3 and 78 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	D1	Hip Girder	1	1	I58937511 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:10 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NS...PqnL8...



Plate Offsets (X,Y)-- [3:0-2-8,0-0-12]

LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	-0.08	7-8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.78	Vert(CT)	-0.14	7-8	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.07	Horz(CT)	0.03	5	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 56 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x6 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SP No.3 , Right: 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-8-12 oc purlins, except
2-0-0 oc purlins (3-9-5 max.): 3-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-3-8, 5=0-3-8
Max Horz 2=-36(LC 26)
Max Uplift 2=-260(LC 4), 5=-260(LC 5)
Max Grav 2=1108(LC 1), 5=1108(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1988/371, 3-4=-1810/369, 4-5=-1980/369
BOT CHORD 2-8=-319/1836, 7-8=-320/1817, 5-7=-305/1828
WEBS 3-8=0/300, 4-7=0/297

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 260 lb uplift at joint 2 and 260 lb uplift at joint 5.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 85 lb down and 62 lb up at 4-9-0, and 62 lb down and 54 lb up at 6-9-0, and 85 lb down and 62 lb up at 8-9-0 on top chord, and 260 lb down and 77 lb up at 4-9-0, and 40 lb down at 6-9-0, and 260 lb down and 77 lb up at 8-8-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-70, 3-4=-70, 4-6=-70, 9-12=-20

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	D1	Hip Girder	1	1	I58837511 Job Reference (optional)

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uliXbGKWrCbdi724zJC?f

LOAD CASE(S) Standard
Concentrated Loads (lb)
Vert: 3=-62(F) 4=-62(F) 8=-260(F) 7=-260(F) 15=-62(F) 16=-33(F)

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	D2	Common	2	1	I58837512 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:12 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uli Xb GKWr--0ci724zJC?f



Plate Offsets (X,Y)-- [2:0-1-8,0-0-1], [6:0-2-13,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	-0.05	8-15	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.34	Vert(CT)	-0.08	8-15	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.02	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 45 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-6-0, Right 2x4 SPF No.2 2-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 6=0-3-8
Max Horz 2=-46(LC 13)
Max Uplift 2=-160(LC 8), 6=-160(LC 9)
Max Grav 2=739(LC 1), 6=739(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-862/264, 4-6=-862/264
BOT CHORD 2-8=-148/813, 6-8=-148/813
WEBS 4-8=0/264

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 6-9-0, Exterior(2R) 6-9-0 to 9-9-0, Interior(1) 9-9-0 to 15-4-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 160 lb uplift at joint 2 and 160 lb uplift at joint 6.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER
PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	E1	Hip Girder	1	2	I58837513 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:14 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uIrXbGKWrCbdi7J4zJC?f



Plate Offsets (X,Y)-- [1:0-3-0,0-0-5], [14:0-3-0,0-2-4], [18:0-1-8,0-2-8], [19:0-1-12,0-3-0]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.91	Vert(LL)	-0.15	18-19	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.93	Vert(CT)	-0.26	18-19	>943	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.74	Horz(CT)	0.03	10	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 302 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
15-17: 2x4 SP 2400F 2.0E
WEBS 2x4 SPF No.2 *Except*
19-20: 2x6 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (6-0-0 max.): 3-8.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
5-8-9 oc bracing: 16-18
5-10-1 oc bracing: 14-16.

REACTIONS. (size) 1=0-3-8, 16=0-3-8, 10=0-3-8
Max Horz 1=-69(LC 9)
Max Uplift 1=-317(LC 8), 16=-1581(LC 5), 10=-329(LC 5)
Max Grav 1=1449(LC 21), 16=7028(LC 1), 10=1518(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-3=-3085/728, 3-4=-817/331, 4-5=-817/331, 5-7=-267/550, 7-8=-267/550, 8-9=-1745/457, 9-10=-3624/799
BOT CHORD 1-19=-646/2838, 18-19=-640/2805, 16-18=-4239/971, 14-16=-4239/971, 13-14=-306/1532, 12-13=-706/3403, 10-12=-706/3403
WEBS 3-19=-314/1775, 3-18=-2411/471, 4-18=-423/144, 5-18=-1218/5503, 5-16=-5914/1360, 5-14=-1022/4573, 7-14=-307/128, 8-14=-2480/515, 8-13=-335/1692, 9-13=-1951/417, 9-12=-142/989

NOTES-
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-2-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 317 lb uplift at joint 1, 1581 lb uplift at joint 16 and 329 lb uplift at joint 10.
8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

Continued on page 2

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	E1	Hip Girder	1	2	I58837513 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:14 2023 Page 2
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCbdi7J4zJC?f

NOTES-

10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1383 lb down and 328 lb up at 9-0-0, 370 lb down and 111 lb up at 11-0-12, 370 lb down and 111 lb up at 13-0-12, 370 lb down and 111 lb up at 15-0-12, 370 lb down and 111 lb up at 17-0-12, 370 lb down and 111 lb up at 19-0-12, 370 lb down and 111 lb up at 21-0-12, 370 lb down and 111 lb up at 23-0-12, 370 lb down and 111 lb up at 25-0-12, 370 lb down and 111 lb up at 27-0-12, 370 lb down and 111 lb up at 29-0-12, 365 lb down and 92 lb up at 31-0-12, and 365 lb down and 89 lb up at 33-0-12, and 552 lb down and 122 lb up at 35-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-3=-70, 3-8=-70, 8-11=-70, 21-25=-20

Concentrated Loads (lb)

Vert: 19=-1383(F) 14=-370(F) 15=-370(F) 29=-370(F) 30=-370(F) 31=-370(F) 32=-370(F) 33=-370(F) 34=-370(F) 35=-370(F) 36=-370(F) 37=-365(F) 38=-365(F) 39=-552(F)

MiTek®
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	E2	Roof Special Girder	1	1	I58937514 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:15 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSePqnL8w3uITXbGKWrCDoi7J4zJC?f



LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	-0.03	8-9	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.06	8-9	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.18	Horz(CT)	0.01	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 44 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2 *Except*
1-3: 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 7=Mechanical, 2=0-3-8
Max Horz 2=132(LC 7)
Max Uplift 7=-84(LC 8), 2=-123(LC 4)
Max Grav 7=435(LC 1), 2=538(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-642/22, 3-4=-603/26, 4-5=-611/84
BOT CHORD 2-9=-78/494, 8-9=-192/1056, 7-8=-84/555
WEBS 3-9=-13/282, 4-8=-514/110, 5-8=0/264, 5-7=-626/126, 4-9=-658/212

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
2) Provide adequate drainage to prevent water ponding.
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) Refer to girder(s) for truss to truss connections.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 84 lb uplift at joint 7 and 123 lb uplift at joint 2.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 139 lb down and 262 lb up at 1-4-0 on top chord, and 41 lb down and 44 lb up at 1-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-70, 3-4=-70, 4-6=-70, 7-10=-20
Concentrated Loads (lb)
Vert: 3=71(F)

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	E3	Roof Special	1	1	I58837515 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147,
8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:16 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSuPqnL8w3uliXbGKWrCbdi724zJC?f



Plate Offsets (X,Y)-- [2:0-3-5,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	-0.07	7-8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.37	Vert(CT)	-0.14	7-8	>883	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.35	Horz(CT)	0.01	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 42 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 7=Mechanical, 2=0-3-8
Max Horz 2=131(LC 11)
Max Uplift 7=-88(LC 12), 2=-149(LC 8)
Max Grav 7=444(LC 1), 2=600(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-713/135, 4-5=-635/145
BOT CHORD 2-8=-293/653, 7-8=-320/768
WEBS 5-7=-754/286

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 3-4-0, Exterior(2E) 3-4-0 to 5-4-0, Interior(1) 5-4-0 to 10-1-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Provide adequate drainage to prevent water ponding.
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) Refer to girder(s) for truss to truss connections.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 88 lb uplift at joint 7 and 149 lb uplift at joint 2.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	E4	Half Hip Girder	1	1	I58837516 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:18 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSdPqnL8w3uli XbGKWrCbdi724zJC?f



Plate Offsets (X,Y)-- [2:0-3-5,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.02	8-9	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.04	8-9	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.21	Horz(CT)	0.01	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 40 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-6.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 7=Mechanical, 2=0-3-8
Max Horz 2=67(LC 7)
Max Uplift 7=-102(LC 5), 2=-179(LC 4)
Max Grav 7=518(LC 1), 2=676(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-841/165, 4-5=-837/175, 5-6=-837/175, 6-7=-471/115
BOT CHORD 2-9=-168/769, 8-9=-170/760
WEBS 5-8=-293/114, 6-8=-175/871

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 102 lb uplift at joint 7 and 179 lb uplift at joint 2.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 33 lb down and 38 lb up at 3-4-0, 30 lb down and 38 lb up at 5-4-12, and 30 lb down and 37 lb up at 7-4-12, and 30 lb down and 39 lb up at 9-2-12 on top chord, and 103 lb down and 44 lb up at 3-4-0, 19 lb down at 5-4-12, and 19 lb down at 7-4-12, and 19 lb down at 9-2-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

June 12,2023

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-4=-70, 4-6=-70, 7-10=-20

Continued on page 2

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

LOAD CASE(S) Standard

Concentrated Loads (lb)

Vert: 9=-78(B) 4=-9(B) 14=-9(B) 15=-9(B) 16=-12(B) 17=-10(B) 18=-10(B) 19=-11(B)

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	F1	Half Hip Girder	1	1	I58837517 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:19 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSdPqnL8w3uIiXbGKWr-Dbi724zJC?f



Plate Offsets (X,Y)-- [2:0-3-1,0-0-13]

LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.02	8-9	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.45	Vert(CT)	-0.04	8-9	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.25	Horz(CT)	0.01	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 36 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-9-14 oc purlins, except end verticals, and 2-0-0 oc purlins (5-10-10 max.): 4-6.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 7=Mechanical, 2=0-3-8
Max Horz 2=60(LC 7)
Max Uplift 7=-101(LC 5), 2=-183(LC 4)
Max Grav 7=572(LC 1), 2=707(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-927/168, 4-5=-850/166, 5-6=-927/175, 6-7=-535/113
BOT CHORD 2-9=-176/860, 8-9=-178/927
WEBS 5-8=-297/121, 6-8=-185/1024

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 101 lb uplift at joint 7 and 183 lb uplift at joint 2.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 77 lb down and 55 lb up at 3-2-8, and 54 lb down and 55 lb up at 5-3-4, and 54 lb down and 55 lb up at 7-3-4 on top chord, and 117 lb down and 40 lb up at 3-2-8, and 36 lb down at 5-3-4, and 36 lb down at 7-3-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-4=-70, 4-6=-70, 7-10=-20

June 12,2023

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	F1	Half Hip Girder	1	1	I58837517 Job Reference (optional)

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uliXbGKWrCbdi724zJC?f

LOAD CASE(S) Standard
Concentrated Loads (lb)
Vert: 4=-54(F) 9=-117(F) 14=-54(F) 15=-54(F) 16=-36(F) 17=-36(F)

16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	F2	Half Hip	1	1	I58937518 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:20 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uITXbGKWrCDoi7J4zJC?f



Plate Offsets (X,Y)-- [2:0-3-1,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	0.02	7-10	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.18	Vert(CT)	-0.02	7-10	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	-0.01	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 34 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 6=Mechanical
Max Horz 2=87(LC 11)
Max Uplift 2=-144(LC 8), 6=-69(LC 8)
Max Grav 2=544(LC 1), 6=385(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-434/153
BOT CHORD 2-7=-226/414, 6-7=-227/406
WEBS 4-6=-467/233

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 5-2-8, Exterior(2E) 5-2-8 to 8-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 144 lb uplift at joint 2 and 69 lb uplift at joint 6.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	F3	Half Hip	1	1	I58827519 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:21 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NS...PqnL8v3...



Plate Offsets (X,Y)-- [2:0-3-13,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	0.07	7-10	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.41	Vert(CT)	-0.13	7-10	>842	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.03	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 34 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 4-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 6=Mechanical
Max Horz 2=113(LC 11)
Max Uplift 2=-141(LC 8), 6=-72(LC 8)
Max Grav 2=544(LC 1), 6=385(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-294/156
BOT CHORD 2-7=-155/252
WEBS 4-7=-34/284, 4-6=-468/236

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 7-2-8, Exterior(2E) 7-2-8 to 8-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 141 lb uplift at joint 2 and 72 lb uplift at joint 6.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	F4	Jack-Partial	11	1	I58937520 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:22 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uliXbGKWrCDoi7J4zJC?f



Plate Offsets (X,Y)-- [2:0-1-8,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	1.00	Vert(LL)	-0.23	7-10	>455	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.68	Vert(CT)	-0.51	7-10	>203	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.09	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 29 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 7=Mechanical
Max Horz 2=140(LC 8)
Max Uplift 2=-123(LC 8), 7=-91(LC 8)
Max Grav 2=537(LC 1), 7=390(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-563/68
WEBS 4-7=-279/215

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 9-0-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 123 lb uplift at joint 2 and 91 lb uplift at joint 7.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J1	Jack-Open	3	1	I58937521 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:23 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uIiXbGKWrCbdi724zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	-0.02	4-7	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.17	Vert(CT)	-0.03	4-7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 11 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=65(LC 8)
Max Uplift 3=-45(LC 12), 2=-60(LC 8)
Max Grav 3=124(LC 1), 2=254(LC 1), 4=74(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 4-1-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 45 lb uplift at joint 3 and 60 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J2	Jack-Open	1	1	I58837522 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:34 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWr-bqi724zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	-0.00	7	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	-0.00	7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 6 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-1-7 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=39(LC 8)
Max Uplift 3=-19(LC 12), 2=-51(LC 8)
Max Grav 3=53(LC 1), 2=167(LC 1), 4=35(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 3 and 51 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J3	Jack-Open	1	1	I58837523 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:45 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uITXbGKWrCDoi7J4zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	0.00	5	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	0.00	5	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MR							Weight: 5 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-1-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 4=Mechanical, 5=0-3-8
Max Horz 5=38(LC 8)
Max Uplift 3=-71(LC 1), 4=-34(LC 1), 5=-150(LC 8)
Max Grav 3=40(LC 8), 4=20(LC 8), 5=333(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-280/212

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 71 lb uplift at joint 3, 34 lb uplift at joint 4 and 150 lb uplift at joint 5.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J4	Jack-Closed	2	1	I63337524 Job Reference (optional)

Builders First Source, Valley Center, KS 67147

8.630 s Nov 21 2022 MiTek Industries, Inc. Fri Jun 9 11:17:38 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-gQQdP1ub9F8ABBnlOi6?Cq5FoaWqLiNy8rdUuz8LNR

Scale = 1:19.1



Plate Offsets (X,Y)-- [2:0-3-1,0-0-9]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.58	Vert(LL)	0.09	7-10	>866	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.37	Vert(CT)	-0.17	7-10	>466	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.04	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 24 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Sheathed, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 7=Mechanical, 2=0-3-8
Max Horz 2=113(LC 11)
Max Uplift 7=-57(LC 8), 2=-123(LC 8)
Max Grav 7=291(LC 1), 2=448(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-334/78

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 6-10-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7 except (jt=lb) 2=123.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows	I58837525
3603730	J5	Jack-Open	2	1	Job Reference (optional)	

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:47 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSuPqnL8w3uIiXbGKWrCbdi7z4zJC?f



Plate Offsets (X,Y)-- [2:0-1-12,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	0.03	5-8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.19	Vert(CT)	-0.04	5-8	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.01	4	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 16 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=90(LC 8)
Max Uplift 4=-54(LC 12), 2=-106(LC 8)
Max Grav 4=138(LC 1), 2=375(LC 1), 5=83(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 4-10-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 4 and 106 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J6	Jack-Open	2	1	I58837526 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:48 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCDoi7J4zJC?f



Plate Offsets (X,Y)-- [2:0-1-8,0-0-1]

LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	-0.00	8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	-0.00	5-8	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 11 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-10-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=65(LC 8)
Max Uplift 4=-28(LC 12), 2=-103(LC 8)
Max Grav 4=62(LC 1), 2=303(LC 1), 5=43(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 2-10-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 4 and 103 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J7	Jack-Open	1	1	I58337527 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:49 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NS...PqnL8w3uIi...



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	0.00	5	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	0.00	5	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MR							Weight: 6 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-4-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 4=Mechanical, 5=0-3-8
Max Horz 5=40(LC 8)
Max Uplift 3=-43(LC 1), 4=-26(LC 1), 5=-138(LC 8)
Max Grav 3=26(LC 8), 4=19(LC 8), 5=316(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-266/199

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 43 lb uplift at joint 3, 26 lb uplift at joint 4 and 138 lb uplift at joint 5.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J8	Jack-Open	4	1	I58837528 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:50 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NS[illegible]PqnL8[illegible]



Plate Offsets (X,Y)-- [2:0-1-8,0-0-5]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	0.01	5-8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	5-8	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 12 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-4-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=70(LC 8)
Max Uplift 4=-33(LC 12), 2=-103(LC 8)
Max Grav 4=79(LC 1), 2=316(LC 1), 5=52(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 3-3-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 33 lb uplift at joint 4 and 103 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J9	Jack-Open	2	1	I58837529 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:51 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSdPqnL8w3uliXbGKWrCDoi7z4zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	0.00	5	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	0.00	5	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MR							Weight: 6 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-2-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 4=Mechanical, 5=0-3-8
Max Horz 5=39(LC 8)
Max Uplift 3=-53(LC 1), 4=-29(LC 1), 5=-142(LC 8)
Max Grav 3=31(LC 8), 4=19(LC 8), 5=322(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-271/204

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 53 lb uplift at joint 3, 29 lb uplift at joint 4 and 142 lb uplift at joint 5.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J10	Jack-Partial	9	1	I58837530 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:24 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSoPqnL8w3uIiXbGKWrCbci7z4zJC?f

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023



Plate Offsets (X,Y)-- [2:0-1-12,0-0-5]

LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.60	Vert(LL)	0.10	7-10	>819	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.40	Vert(CT)	-0.20	7-10	>414	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.04	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 24 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 7=Mechanical
Max Horz 2=118(LC 8)
Max Uplift 2=-114(LC 8), 7=-71(LC 8)
Max Grav 2=459(LC 1), 7=304(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-359/52

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 7-2-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 114 lb uplift at joint 2 and 71 lb uplift at joint 7.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J11	Jack-Open	2	1	I58837531 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:25 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCDqi724zJC?f



Plate Offsets (X,Y)-- [2:0-1-12,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.42	Vert(LL)	0.06	5-8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.27	Vert(CT)	-0.10	5-8	>701	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.02	4	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 18 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=102(LC 8)
Max Uplift 4=-67(LC 12), 2=-110(LC 8)
Max Grav 4=173(LC 1), 2=415(LC 1), 5=101(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-263/43

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 5-10-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 67 lb uplift at joint 4 and 110 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J12	Jack-Open	2	1	I58837532 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:26 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Plate Offsets (X,Y)-- [2:0-1-8,0-0-5]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	-0.01	5-8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.11	Vert(CT)	-0.02	5-8	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.01	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 14 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=78(LC 8)
Max Uplift 4=-41(LC 12), 2=-103(LC 8)
Max Grav 4=101(LC 1), 2=336(LC 1), 5=64(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 3-10-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 41 lb uplift at joint 4 and 103 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J13	Jack-Open	4	1	I58837533 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:27 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uliXbGKWrCDoi7J4zJC?f



Plate Offsets (X,Y)-- [2:0-1-12,0-0-5]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	0.00	8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	8	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 9 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 1-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=54(LC 8)
Max Uplift 4=-13(LC 12), 2=-108(LC 8)
Max Grav 4=18(LC 1), 2=282(LC 1), 5=24(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 1-10-13 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 4 and 108 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J14	Jack-Open	2	1	I58837534 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:28 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uli Xb GKWrC 0qi7J4zJC?f



Plate Offsets (X,Y)-- [2:0-1-12,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.29	Vert(LL)	0.04	5-8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.20	Vert(CT)	-0.05	5-8	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.01	4	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 17 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=92(LC 8)
Max Uplift 4=-57(LC 12), 2=-107(LC 8)
Max Grav 4=144(LC 1), 2=382(LC 1), 5=86(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 5-0-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 57 lb uplift at joint 4 and 107 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J15	Jack-Open	2	1	I58837535 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:29 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCbdi7z4zJC?f



Plate Offsets (X,Y)-- [3:0-2-13,0-0-8]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	0.00	5-6	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.00	5-6	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 11 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-1-3 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 5=Mechanical, 3=Mechanical, 6=0-3-8
Max Horz 6=59(LC 8)
Max Uplift 3=-27(LC 12), 6=-112(LC 8)
Max Grav 5=57(LC 3), 3=55(LC 1), 6=315(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-6=-273/202

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 2-9-11 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) Refer to girder(s) for truss to truss connections.
5) Bearing at joint(s) 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 3 and 112 lb uplift at joint 6.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER
PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J16	Jack-Open	2	1	I58837536 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:30 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSuPqnL8w3uliXbGKWrCDoi7J4zJC?f



LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	0.00	5	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	0.00	5	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MR							Weight: 5 lb	FT = 20%

SPACING- 2-0-0

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-1-3 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 4=Mechanical, 5=0-3-8
Max Horz 5=38(LC 8)
Max Uplift 3=-74(LC 1), 4=-35(LC 1), 5=-152(LC 8)
Max Grav 3=42(LC 8), 4=21(LC 8), 5=336(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-282/213

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 74 lb uplift at joint 3, 35 lb uplift at joint 4 and 152 lb uplift at joint 5.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J17	Roof Special Girder	1	1	I58937537 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:31 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCbpi724zJC?f



LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	-0.04	6-7	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.39	Vert(CT)	-0.10	6-7	>950	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.10	Horz(CT)	0.01	6	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 34 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2 *Except*
1-3: 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 6=Mechanical, 2=0-3-8
Max Horz 2=82(LC 7)
Max Uplift 6=-69(LC 8), 2=-148(LC 4)
Max Grav 6=399(LC 1), 2=550(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-719/68, 3-4=-649/64
BOT CHORD 2-7=-78/629, 6-7=-126/565
WEBS 4-6=-614/155, 4-7=0/253

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
2) Provide adequate drainage to prevent water ponding.
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) Refer to girder(s) for truss to truss connections.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 69 lb uplift at joint 6 and 148 lb uplift at joint 2.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 28 lb down and 36 lb up at 2-0-0, and 29 lb down and 37 lb up at 4-0-12, and 29 lb down and 38 lb up at 6-0-12 on top chord, and 65 lb down and 14 lb up at 2-0-0, and 25 lb down at 4-0-12, and 25 lb down at 6-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-70, 3-4=-70, 4-5=-70, 6-8=-20

June 12,2023

Continued on page 2

LOAD CASE(S) Standard
Concentrated Loads (lb)
Vert: 3=-13(B) 7=-15(B) 11=-17(B) 12=-17(B) 13=-25(B) 14=-25(B)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J18	Half Hip	1	1	I58837538 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:32 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCbci724zJC?f



Plate Offsets (X,Y)-- [2:0-2-13,0-0-5]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.01	8-9	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.13	Vert(CT)	-0.02	8-9	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	-0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 31 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (6-0-0 max.): 4-6.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 8=Mechanical
Max Horz 2=75(LC 8)
Max Uplift 2=-134(LC 8), 8=-59(LC 8)
Max Grav 2=495(LC 1), 8=343(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-395/164, 4-5=-387/189
BOT CHORD 2-9=-179/378
WEBS 5-8=-303/153, 5-9=-203/418

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 4-0-0, Exterior(2E) 4-0-0 to 8-0-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 134 lb uplift at joint 2 and 59 lb uplift at joint 8.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J19	Half Hip	1	1	I58837539 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:33 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCbci7J4zJC?f



Plate Offsets (X,Y)-- [2:0-3-5,0-0-1], [4:0-2-8,Edge]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.11	8-11	>828	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.45	Vert(CT)	-0.24	8-11	>379	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.03	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 29 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-6.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 8=Mechanical
Max Horz 2=97(LC 11)
Max Uplift 2=-134(LC 8), 8=-59(LC 8)
Max Grav 2=495(LC 1), 8=343(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-562/82

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 6-0-0, Exterior(2E) 6-0-0 to 8-0-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 134 lb uplift at joint 2 and 59 lb uplift at joint 8.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J20	Jack-Partial	6	1	I58837540 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:35 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCDdi724zJC?f



Plate Offsets (X,Y)-- [2:0-2-0,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.77	Vert(LL)	0.14	7-10	>644	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.52	Vert(CT)	-0.32	7-10	>293	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.06	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 26 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 7=Mechanical
Max Horz 2=128(LC 8)
Max Uplift 2=-118(LC 8), 7=-80(LC 8)
Max Grav 2=494(LC 1), 7=343(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-445/59

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 8-0-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 118 lb uplift at joint 2 and 80 lb uplift at joint 7.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J21	Jack-Partial	3	1	I58937541 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:36 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCbci724zJC?f



Plate Offsets (X,Y)-- [2:0-2-4,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	1.00	Vert(LL)	-0.21	10	>446	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.32	Vert(CT)	-0.38	10	>242	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.21	9	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 29 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 2=0-3-8, 9=Mechanical
Max Horz 2=128(LC 8)
Max Uplift 2=-117(LC 8), 9=-79(LC 8)
Max Grav 2=496(LC 1), 9=343(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-12=-250/52, 4-5=-458/209
BOT CHORD 4-9=-310/466
WEBS 5-9=-594/396

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 8-0-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 117 lb uplift at joint 2 and 79 lb uplift at joint 9.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J22	Jack-Open	2	1	I58837542 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:37 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSdPqnL8w3uIrXbGKWrCDoi7z4zJC?f



Plate Offsets (X,Y)-- [2:0-2-4,0-0-1], [4:0-5-8,0-1-15]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	0.11	7	>661	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.39	Vert(CT)	-0.15	7	>465	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.09	6	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 20 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 5=Mechanical, 2=0-3-8, 6=Mechanical
Max Horz 2=102(LC 8)
Max Uplift 5=-52(LC 12), 2=-110(LC 8), 6=-6(LC 12)
Max Grav 5=153(LC 1), 2=416(LC 1), 6=97(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 5-10-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 52 lb uplift at joint 5, 110 lb uplift at joint 2 and 6 lb uplift at joint 6.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J23	Jack-Open	2	1	I58837543 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:39 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSdPqnL8w3uli XbGKWrCbci7?4zJC?f



Plate Offsets (X,Y)-- [2:0-1-8,0-0-5]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	0.02	7	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.11	Vert(CT)	-0.02	7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.02	6	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MR							Weight: 15 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (size) 5=Mechanical, 2=0-3-8, 6=Mechanical
Max Horz 2=78(LC 8)
Max Uplift 5=-26(LC 12), 2=-103(LC 8), 6=-9(LC 12)
Max Grav 5=82(LC 1), 2=337(LC 1), 6=60(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 3-10-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 5, 103 lb uplift at joint 2 and 9 lb uplift at joint 6.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J24	Jack-Open	1	1	I58837544 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:18:40 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.09	Vert(LL)	-0.00	4-7	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	-0.01	4-7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 8 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=50(LC 8)
Max Uplift 3=-30(LC 12), 2=-54(LC 8)
Max Grav 3=83(LC 1), 2=203(LC 1), 4=52(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 2-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 30 lb uplift at joint 3 and 54 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J25	Jack-Open	2	1	I58837545 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:40 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uITXbGKWrCDoi7J4zJC?f

Scale = 1:9.7



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.10	Vert(LL)	0.01	3-6	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(CT)	-0.01	3-6	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	1	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 7 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=0-3-8, 2=Mechanical, 3=Mechanical
Max Horz 1=36(LC 8)
Max Uplift 1=-17(LC 8), 2=-31(LC 8)
Max Grav 1=132(LC 1), 2=87(LC 1), 3=53(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 17 lb uplift at joint 1 and 31 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J26	Jack-Open	3	1	I58837546 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:41 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7z4zJC?f



Plate Offsets (X,Y)-- [2:0-1-8,0-0-9]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	0.03	5-8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.17	Vert(CT)	-0.04	5-8	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.01	4	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 16 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=88(LC 8)
Max Uplift 4=-52(LC 12), 2=-106(LC 8)
Max Grav 4=132(LC 1), 2=368(LC 1), 5=80(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 4-8-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 52 lb uplift at joint 4 and 106 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J27	Jack-Open	4	1	I58837547 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:42 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NScPqnL8w3uIiXbGKWrCbdi724zJC?f



Plate Offsets (X,Y)-- [2:0-1-8,0-0-1]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	-0.00	8	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	-0.00	5-8	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 11 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 2-0-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-7-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=62(LC 8)
Max Uplift 4=-24(LC 12), 2=-104(LC 8)
Max Grav 4=52(LC 1), 2=296(LC 1), 5=38(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 2-7-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 24 lb uplift at joint 4 and 104 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J28	MONO TRUSS	6	1	I58837548 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:43 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	0.00	6	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	0.00	7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00		n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 8 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-10-4 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 7=0-3-8, 5=0-1-8
Max Horz 7=41(LC 11)
Max Uplift 7=-115(LC 8), 5=-21(LC 1)
Max Grav 7=301(LC 1), 5=27(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-7=-273/197

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 1-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 5.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 115 lb uplift at joint 7 and 21 lb uplift at joint 5.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	J29	Jack-Open	4	1	I58837549 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:44 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSuPqnL8w3uIrXbGKWrCDoi7z4zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	-0.00	7	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	-0.00	7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 6 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=35(LC 8)
Max Uplift 3=-21(LC 12), 2=-51(LC 8)
Max Grav 3=57(LC 1), 2=169(LC 1), 4=36(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 3 and 51 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	L1	Monopitch	6	1	I58837550 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:52 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	-0.00	7	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.02	Vert(CT)	-0.00	7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 6 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-11-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 2=0-3-8
Max Horz 2=35(LC 11)
Max Uplift 4=-14(LC 12), 2=-52(LC 8)
Max Grav 4=67(LC 1), 2=158(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 14 lb uplift at joint 4 and 52 lb uplift at joint 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	LG1	GABLE	1	1	I58837551 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:53 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uli Xb GKWrCbdi7J4zJC?f

Scale = 1:48.8



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.16	Horz(CT)	0.00	9	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S							Weight: 76 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 15-8-15.
(lb) - Max Horz 1=-189(LC 10)
Max Uplift All uplift 100 lb or less at joint(s) 1, 9 except 14=-116(LC 12), 15=-116(LC 12), 16=-111(LC 12), 12=-115(LC 13), 11=-117(LC 13), 10=-111(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 9, 13, 14, 15, 16, 12, 11, 10

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-251/161

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-4-1 to 3-4-1, Interior(1) 3-4-1 to 7-10-7, Exterior(2R) 7-10-7 to 10-10-7, Interior(1) 10-10-7 to 15-4-14 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) All plates are 1.5x4 MT20 unless otherwise indicated.
4) Gable requires continuous bottom chord bearing.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 9 except (jt=lb) 14=116, 15=116, 16=111, 12=115, 11=117, 10=111.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	LG2	GABLE	1	1	I58837552 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:54 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIi XbGKWrCbqi7J4zJC?f

Scale = 1:57.6



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	0.01	9	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S							Weight: 87 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 5-13

REACTIONS. All bearings 17-4-7.
(lb) - Max Horz 1=-209(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 1, 9 except 15=-117(LC 12), 16=-107(LC 12), 17=-143(LC 12), 12=-115(LC 13), 11=-108(LC 13), 10=-143(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 9, 13, 15, 16, 12, 11, 10 except 17=250(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-264/176

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-4-1 to 3-4-1, Interior(1) 3-4-1 to 8-8-3, Exterior(2R) 8-8-3 to 11-8-3, Interior(1) 11-8-3 to 17-0-6 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) All plates are 1.5x4 MT20 unless otherwise indicated.
4) Gable requires continuous bottom chord bearing.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 9 except (jt=lb) 15=117, 16=107, 17=143, 12=115, 11=108, 10=143.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

STATE OF MISSOURI
SCOTT M. SEVIER
NUMBER PE-2001018807
PROFESSIONAL ENGINEER

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	LG3	GABLE	2	1	I58937553 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:55 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uITXbGKWrCDoi7J4zJC?f



Plate Offsets (X,Y)-- [3:0-2-9,Edge], [7:0-0-10,0-1-8]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	-0.00	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S							Weight: 48 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except
2-0-0 oc purlins (6-0-0 max.): 3-7.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 12-6-11.
(lb) - Max Horz 1=143(LC 12)
Max Uplift All uplift 100 lb or less at joint(s) 1, 7, 9, 12, 11, 10, 8 except 13=-126(LC 12)
Max Grav All reactions 250 lb or less at joint(s) 1, 7, 9, 13, 12, 11, 10, 8

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-4-1 to 3-4-1, Interior(1) 3-4-1 to 3-11-8, Exterior(2R) 3-11-8 to 6-11-8, Interior(1) 6-11-8 to 12-3-10 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) All plates are 1.5x4 MT20 unless otherwise indicated.
5) Gable requires continuous bottom chord bearing.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 7, 9, 12, 11, 10, 8 except (jt=lb) 13=126.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 7, 8.
9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	P1	Roof Special	1	1	I58837554 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:57 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uli XbGKWr-bqi724zJC?f



Plate Offsets (X,Y)-- [1:0-0-0,0-0-3], [2:0-5-4,Edge], [2:0-2-0,0-0-5], [4:0-5-4,Edge], [4:0-2-0,0-1-3], [5:Edge,0-0-3]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.85	Vert(LL)	-0.30	9	>515	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.95	Vert(CT)	-0.57	9	>273	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.27	5	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 40 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP 2400F 2.0E
BOT CHORD 2x4 SPF No.2 *Except*
2-4: 2x4 SPF 1650F 1.5E
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 1=0-3-8, 5=0-3-8
Max Horz 1=-38(LC 17)
Max Uplift 1=-79(LC 8), 5=-112(LC 9)
Max Grav 1=594(LC 1), 5=659(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1784/508, 3-4=-1784/501
BOT CHORD 2-8=-414/1724, 4-8=-414/1724
WEBS 3-8=-55/397

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 2-9-1, Interior(1) 2-9-1 to 6-6-0, Exterior(2R) 6-6-0 to 9-6-0, Interior(1) 9-6-0 to 13-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 5=112.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	P2	ROOF SPECIAL	2	1	I58937555 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:13:58 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSdPqnL8w3uliXbGKWr-bqi724zJC?f



Plate Offsets (X,Y)-- [2:0-0-10,0-0-15], [3:0-4-12,Edge], [3:0-2-0,0-4-10], [3:0-2-3,1-9-1], [5:0-4-12,Edge], [6:0-0-10,0-0-15]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	25.0	Plate Grip DOL	1.15	TC	0.84	Vert(LL)	-0.28	10	>549	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.74	Vert(CT)	-0.54	10	>288	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.25	6	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 45 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP 2400F 2.0E
BOT CHORD 2x4 SPF No.2 *Except*
3-5: 2x4 SP 2400F 2.0E
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-6-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 2=0-3-8, 6=0-3-8
Max Horz 2=34(LC 12)
Max Uplift 2=-112(LC 8), 6=-112(LC 9)
Max Grav 2=657(LC 1), 6=657(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1762/488, 4-5=-1762/492
BOT CHORD 3-9=-402/1691, 5-9=-402/1691
WEBS 4-9=-74/473

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 6-6-0, Exterior(2R) 6-6-0 to 9-6-0, Interior(1) 9-6-0 to 13-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=112, 6=112.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	P3	ROOF SPECIAL GIRDER	1	2	I58827556 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:14:00 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uJr Xb?GKWr-Cbci724zJC?f



Plate Offsets (X,Y)-- [1:0-2-8,0-0-0], [2:0-4-0,0-1-12], [6:0-4-0,0-1-12], [7:0-2-8,0-0-0]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	25.0	Plate Grip DOL	1.15	TC	0.65	Vert(LL)	-0.18	9-22	>844	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.86	Vert(CT)	-0.31	9-22	>494	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.12	Horz(CT)	0.16	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 82 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SPF 2100F 1.8E
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
JOINTS 1 Brace at Jt(s): 9

REACTIONS. (size) 1=0-3-8, 7=0-3-8
Max Horz 1=30(LC 8)
Max Uplift 1=-253(LC 4), 7=-252(LC 5)
Max Grav 1=1233(LC 1), 7=1226(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-1301/268, 3-4=-4113/844, 4-5=-4112/854, 5-6=-292/83, 6-7=-1306/284
BOT CHORD 1-10=-193/910, 2-10=-115/549, 3-9=-810/4079, 5-9=-810/4079, 6-8=-60/321, 7-8=-187/918
WEBS 4-9=-198/966

NOTES-
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-4-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) Bearing at joint(s) 1, 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=253, 7=252.
8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 225 lb down and 63 lb up at 2-4-3, 219 lb down and 65 lb up at 4-2-12, 210 lb down and 75 lb up at 6-2-12, 210 lb down and 75 lb up at 6-9-4, and 219 lb down and 65 lb up at 8-9-4, and 225 lb down and 63 lb up at 10-10-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

June 12,2023

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	P3	ROOF SPECIAL GIRDER	1	**2**	I58837556 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:14:00 2023 Page 2
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCbqi7J4zJC?f

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (plf)
      Vert: 1-4=-70, 4-7=-70, 10-11=-20, 17-20=-20, 8-14=-20
   Concentrated Loads (lb)
      Vert: 10=-225(B) 9=-421(B) 20=-225(B) 23=-219(B) 24=-219(B)

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	P4	Half Hip Girder	2	1	I58837557 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:14:01 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uITXbGKWrCDoi7J4zJC?f



Plate Offsets (X,Y)-- [2:0-0-0,0-0-10]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	-0.09	5-6	>727	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.69	Vert(CT)	-0.17	5-6	>379	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.03	Horz(CT)	0.02	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 15 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-6-12 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS. (size) 5=Mechanical, 2=0-3-8
Max Horz 2=29(LC 7)
Max Uplift 5=-42(LC 4), 2=-78(LC 4)
Max Grav 5=245(LC 1), 2=318(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 3-6=-251/74

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 2.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
9) "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidlines.
10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 36 lb down and 58 lb up at 1-9-4 on top chord, and 23 lb down at 1-9-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-70, 3-4=-70, 5-7=-20
Concentrated Loads (lb)
Vert: 6=-8(B) 11=-6(B)

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	P5	Half Hip	2	1	I58837558 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:14:03 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3ulI XbGKWrCDoi724zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	0.11	3-7	>603	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.61	Vert(CT)	-0.18	3-7	>370	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.08	6	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 16 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 4-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 6=Mechanical, 2=0-3-8
Max Horz 2=41(LC 8)
Max Uplift 6=-45(LC 8), 2=-75(LC 8)
Max Grav 6=239(LC 1), 2=310(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 4-7=-365/262

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-12, Interior(1) 2-1-12 to 3-6-4, Exterior(2E) 3-6-4 to 5-5-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 2.
7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	P6	HALF HIP	2	1	I58837559 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:14:03 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uIT Xb GKWrCbdi7J4zJC?f



Plate Offsets (X,Y)-- [3:0-4-0,0-2-1], [4:0-2-0,0-2-2]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	25.0	Plate Grip DOL	1.15	TC	0.51	Vert(LL)	-0.07	6	>918	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.28	Vert(CT)	-0.12	6	>511	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.07	5	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-R							Weight: 16 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-6-12 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 5=Mechanical, 2=0-3-8
Max Horz 2=78(LC 8)
Max Uplift 5=-55(LC 12), 2=-70(LC 8)
Max Grav 5=230(LC 1), 2=316(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-12, Interior(1) 2-1-12 to 5-5-0 zone; cantilever left and right exposed ; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) Refer to girder(s) for truss to truss connections.
4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 2.
5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	V1	Valley	1	1	I58837560 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:14:04 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDdi7J4zJC?f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.31	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S							Weight: 33 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=14-0-12, 3=14-0-12, 4=14-0-12
Max Horz 1=33(LC 12)
Max Uplift 1=-49(LC 8), 3=-53(LC 13), 4=-63(LC 8)
Max Grav 1=246(LC 25), 3=246(LC 26), 4=633(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-448/206

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-11-5 to 3-11-5, Interior(1) 3-11-5 to 7-1-2, Exterior(2R) 7-1-2 to 10-1-2, Interior(1) 10-1-2 to 13-2-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Gable requires continuous bottom chord bearing.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3, 4.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

MiTek
16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	V2	Valley	1	1	I58937561 Job Reference (optional)

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:14:05 2023 Page 1
ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSePqnL8w3uIi XbGKWrCbci724zJC?f

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.14	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S							Weight: 23 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=10-0-12, 3=10-0-12, 4=10-0-12
Max Horz 1=-22(LC 17)
Max Uplift 1=-33(LC 8), 3=-36(LC 13), 4=-42(LC 8)
Max Grav 1=166(LC 25), 3=166(LC 26), 4=427(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-302/195

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-11-5 to 3-11-5, Interior(1) 3-11-5 to 5-1-2, Exterior(2R) 5-1-2 to 8-1-2, Interior(1) 8-1-2 to 9-2-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Gable requires continuous bottom chord bearing.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3, 4.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

Job	Truss	Truss Type	Qty	Ply	Summit/193 Highland Meadows
3603730	V3	Valley	1	1	I58937562 Job Reference (optional)

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/04/2023

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.630 s Nov 19 2022 MiTek Industries, Inc. Thu Jun 8 14:14:06 2023 Page 1

ID:icBMJaMgT1gasuUyx9?RhvzDEHb-RfC?PsB70Hq3NSqPqnL8w3uIiXbGKWrCbdi7z4zJC?f



Plate Offsets (X,Y)-- [2:0-3-0,Edge]

LOADING (psf)		SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.10	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.20	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-P							Weight: 12 lb	FT = 20%

SPACING- 2-0-0

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=6-0-12, 3=6-0-12
Max Horz 1=12(LC 12)
Max Uplift 1=-28(LC 8), 3=-28(LC 9)
Max Grav 1=194(LC 1), 3=194(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-253/215, 2-3=-253/225

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Gable requires continuous bottom chord bearing.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

June 12,2023

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

*** Plate location details available in MiTek 20/20 software or upon request.**

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

MiTek Engineering Reference Sheet: MII-7473 rev. 5/19/2020

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.