

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
12/04/2024

NOTE BACK WALL NEED CONCRETE FLOOR LIP

EXTERIOR WALLS 2 X 6 TYP.

43 X 13

FOUNDATION PLAN
1642 SF FINISHED
372 SF UNFINISHED

**Pier Plan Layout 18" Dia Piers 20' Deep
or to Rock With #4 @ #4 Rebar Verticals
Total of 47 Piers**



**BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.**

TRUMARK CUSTOM HOMES
KYLE V
LOT 150 WOODSIDE RIDGE
2082 NW O'BRIEN RD
LEE SUMMIT MO

SCALE
1/4" = 1'-0"

DATE
10-22-24

PLAN NO.
4305

SHEET NO
2 OF 5