

A New Building For:



940 NE Colburn Rd
Lee's Summit, MO.

DRAWING SCHEDULE

COVER

ARCHITECTURAL

A0.0 - CODE REVIEW
A0.1 - ADA GUIDELINES
A100 - FLOOR PLAN / NOTES / WALL TYPES
A101 - INTERIOR ELEVATIONS / ENLARGED TOILET PLANS / DETAILS
A101.1 - INTERIOR ELEVATIONS
A102 - REFLECTED CEILING PLAN / DETAILS
A103 - ROOF PLAN / DETAILS
A200 - EXTERIOR ELEVATIONS
A201 - CANOPY ELEVATIONS
A300 - BUILDING SECTIONS / DETAILS
A301 - WALL SECTIONS
A302 - WALL SECTIONS
A303 - TRASH ENCLOSURE PLAN AND MONUMENT SIGN / ELEVATIONS / SECTION / DETAILS
A400 - SCHEDULES / DETAILS



STRUCTURAL

S001 STRUCTURAL NOTES
S100 - FOUNDATION PLAN
S200 - FRAMING PLAN
S300 - FOUNDATION AND MASONRY DETAILS
S400 - FRAMING DETAILS

MEP

MP00 - MECHANICAL AND PLUMBING SPEC'S
P100 - PLUMBING WASTE AND VENT
P101 - PLUMBING WATER AND GAS
P200 - PLUMBING SCHEDULE AND DETAIL
P201 - PLUMBING RISER DIAGRAMS

M100 - MECHANICAL FLOOR PLAN
M101 - SCHEDULES / DETAILS / NOTES
M200 - CAPTIVE AIRE HOOD
M201 - CAPTIVE AIRE HOOD
M202 - CAPTIVE AIRE HOOD
M203 - CAPTIVE AIRE HOOD
M204 - CAPTIVE AIRE HOOD

E000 - ELECTRICAL SPECS
E101 - ELECTRICAL LIGHTING PLAN
E102 - ELECTRICAL POWER PLAN
E103 - ELECTRICAL POWER PLAN
E201 - ELECTRICAL RISER DIAGRAM & FAULT CALC'S
E202 - ELECTRICAL SCHEDULES
E301 - ELECTRICAL SITE PLAN

ARCHITECT



24 NW CHIPMAN "B"
LEE'S SUMMIT, MO. 64063
PHONE: (816) 536-3472

DESIGN / BUILD CONTRACTOR



17211 E 199th St,
Pleasant Hill, MO 64080

STRUCTURAL ENGINEER



J & S STRUCTURAL ENGINEERS
15185 LOWELL AVE
OVERLAND PARK, KS 66223
913-549-4701

MEP ENGINEER



5720 Reeder St, Shawnee, KS 66203
Phone: (913) 262-1772

GENERAL NOTES

- ALL CONSTRUCTION WORK SHALL BE IN ACCORDANCE WITH THE INCLUDED DRAWINGS.
- ALL CONSTRUCTION WORK SHALL COMPLY WITH GOVERNING BUILDING CODES IN EFFECT AT THE TIME CONSTRUCTION PERMITS ARE ISSUED FOR THIS PROJECT.
- SUB-CONTRACTORS SHALL FIELD VERIFY ALL DIMENSIONS SHOWN, AND SHALL REPORT ANY DISCREPANCY TO THE ENGINEER PRIOR TO COMMENCING WITH ANY RELATED CONSTRUCTION WORK. SUB-CONTRACTORS SHALL FURTHER REPORT TO THE ENGINEER ALL DISCREPANCIES BETWEEN ACTUAL AND SHOWN CONDITIONS, PRIOR TO BEGINNING WORK RELATED THERETO.
- DIMENSIONS ARE TO FACE OF FINISH WALL UNLESS NOTED OTHERWISE.
- THE SUB-CONTRACTORS SHALL VERIFY LOCATION OF EXISTING UTILITIES, AND SHALL BE RESPONSIBLE FOR PROTECTING THESE UTILITIES DURING THE EXECUTION OF HIS WORK AND RELOCATION.
- SUB-CONTRACTOR TO LAY OUT BUILDING PRIOR TO ANY CONSTRUCTION. NOTIFY ENGINEER OF ANY DISCREPANCY IMMEDIATELY.
- SUB-CONTRACTOR TO ASSURE PROPER DRAINAGE AWAY FROM BUILDING.
- THE SUB-CONTRACTORS SHALL BE SOLELY RESPONSIBLE FOR THE DESIGN, ADEQUACY, AND SAFETY OF ERECTION BRACING, SHORING AND TEMPORARY SUPPORTS, ETC. THE SUB-CONTRACTORS ARE RESPONSIBLE FOR THE STABILITY OF THE STRUCTURE PRIOR TO THE APPLICATION OF ALL SHEAR WALLS, ROOF SHEATHING, STRUCTURAL ELEMENTS AND FINISH MATERIALS.
- THE SUB-CONTRACTORS ARE RESPONSIBLE FOR CHECKING ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSION FOR THEIR ACCURACY AND CONFIRMING THAT WORK IS BUILDABLE AS SHOWN BEFORE PROCEEDING WITH CONSTRUCTION. IF THERE ARE ANY QUESTIONS REGARDING THESE OR OTHER COORDINATION QUESTIONS, THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING CLARIFICATION FROM THE ENGINEER BEFORE PROCEEDING WITH THE WORK IN QUESTION OR ANY RELATED WORK.


THE SUB-CONTRACTORS SHALL TAKE ABSOLUTE CARE TO PROTECT NEWLY INSTALLED MATERIALS, MILLWORK, BUILT-INS AND FINISHES.

THE SUB-CONTRACTORS SHALL BE RESPONSIBLE FOR ALL DAMAGE TO EXISTING STRUCTURES, UTILITIES, WALKS, STREETS, PAVED AREAS, CURBS, TREES AND OTHER LANDSCAPING CAUSED THROUGH HIS OPERATIONS UNDER THIS CONTRACT.

THE SUB-CONTRACTORS SHALL PERFORM HIGH QUALITY PROFESSIONAL WORK. JOIN MATERIALS TO UNIFORM, ACCURATE FITS SO THEY MEET WITH NEAT, STRAIGHT LINES, FREE OF SHEARS OR OVERLAPS. INSTALL EXPOSED MATERIALS APPROPRIATELY LEVEL, PLUMB AND AT ACCURATE RIGHT ANGLES OR FLUSH WITH ADJOINING MATERIALS. WORK OF EACH TRADE SHALL MEET ALL NATIONAL STANDARDS PUBLISHED BY THAT TRADE, EXCEPT IN THE CASE WHERE THE CONTRACT DOCUMENTS ARE MORE STRINGENT.


ABBREVIATIONS

A/C	AIR CONDITIONING	EA	EACH	JB	JUNCTION BOX	RM	ROOM
AB	ANCHOR BOLT	EJ	EXPANSION JOINT	JST	JOIST	RO	ROUGH OPENING
AC	ACOUSTICAL	ELEG	ELECTRIC/ELECTRICAL	JT	JOINT	ROW	RIGHT OF WAY
ACT	ACOUSTICAL TILE	EL	ELEVATION	L	LENGTH	RTU	ROOF TOP UNIT
AFF	ABOVE FINISHED FLOOR	EMERG	EMERGENCY ENCLOSURE	LAV	LAVATORY	RV	ROOF VENT
AGG	AGGREGATE	ENT	ENTRANCE	LT	LIGHT	SCHED	SCHEDULE
ALT	ALTERNATE	EP	ELECTRICAL PANEL	LVL	LEVEL	SECT	SECTION
ALUM	ALUMINUM	EQ	EQUAL	MAS	MASONRY	SF	SQUARE FEET
AND	AND	EQUIP	EQUIPMENT	MAX	MAXIMUM	SHT	SHEET
APPROX	APPROXIMATELY	EX	EACH WAY	MECH	MECHANICAL	SIM	SIMILAR
ARCH	ARCHITECTURAL	EXH	EXHAUST	MEMB	MEMBRANE	SPEC	SPECIFICATION
ASPH	ASPHALT	EXP	EXPANSION	MTL	METAL	SPK	SPEAKER
AVG	AVERAGE	EXT	EXTERIOR	MFG	MANUFACTURER	SG	SQUARE
BD	BOARD	FD	FLOOR DRAIN	MISG	MISCELLANEOUS	SST	STAINLESS STEEL
B.F.F.	BELOW FINISHED FLOOR	FDN	FOUNDATION	MO	MASONRY OPENING	STD	STANDARD
BIT	BITUMINIOUS	FFE	FINISHED FLOOR ELEVATION	NIC	NOT IN CONTRACT	STL	STEEL
BKR	BREAKER	FLR	FLOOR	NOM	NOMINAL	STRUC	STRUCTURAL
BLDS	BUILDING	FLR	FLOOR	NTS	NOT TO SCALE	SUP	SUPPLY
BT	BEAM	FLASH	FLASHING	OA	OVERALL	SUSP	SUSPEND
BRG	BEARING	FLOUR	FLOURSCENT	OC	ON CENTER	TEMP	TEMPORARY
BTU	BRITISH THERMAL UNIT	FOS	FACE OF STUD	OD	OUTSIDE DIAMETER	THK	THICK
		FRM	FRAME	OFF	OFFICE	THRES	THRESHOLD
		FRP	FIBERGLASS	OPNG	OPENING	TYP	TYPICAL
CCT	CIRCUIT	FT	FOOT	P	POLE	UC	UNDERCUT
CEM	CEMENT	FTG	FOOTING	PL	PLATE	UL	UNDERWRITER
CFM	CUBIC FEET/MINUTE	FUR	FURRING	PLG	PLUMBING	UNO	UNLESS NOTED OTHERWISE
CJ	CONTROL JOINT	GA	GAUGE	PLYD	PLYWOOD	UR	URINAL
CLS	CELLING	GAL	GALLON	PNL	PANEL	UTIL	UTILITIES
CLR	CLEAR	GALV	GALVANIZED	PR	PAIR	VB	VOLT
CMU	CONCRETE MASONRY UNIT	GEN	GENERAL	PREFAB	PREFABRICATED	VERT	VAPOR BARRIER
CNDT	CONDUIT	GRD	GROUND	PSF	POUNDS/SQUARE FOOT	VEST	VESTIBULE
CO	CLEAN OUT	GYP	GYPSUM	PSI	POUNDS/SQUARE INCH	VOL	VOLUME
COL	COLUMN	HB	HOSE BIBB	PVC	POLYVINYL CHLORIDE	VTR	VENT THROUGH ROOF
CONC	CONCRETE	HDR	HEADER	QT	QUARRY TILE	W	WITH
COND	CONDENSATE	HDR	HEADWARE	R	RADIUS	WC	WATER CLOSET
CORN	CORNER	HGT	HEIGHT	RSR	RISER	WD	WOOD
CONST	CONSTRUCTION	HTR	HEATER	R/A	RETURN AIR	WIND	WINDOW
CONT	CONTINUOUS	HD	HOT WATER	RCPT	RECEPTACLE	WH	WATER HEATER
CT	CERAMIC TILE	INS	INSIDE DIAMETER	RD	ROOF DRAIN	WP	WATER PROOFING
CM	GOLD WATER	IN	INCHES	REG	REGRESSED	WINGCT	WINGWOT
DBL	DOUBLE	INSUL	INSULATION	REF	REFERENCE	WT	WEIGHT
DEPT	DEPARTMENT	INT	INTERIOR	REG	REGISTER	WWF	WELDED WIRE FABRIC
DIA	DIAMETER			REQD	REQUIRED	YD	YARD
DIM	DIMENSION			RFG	ROOFING		
DISC	DISCONNECT						
DN	DOWN						
DR	DOWNSPOUT						
DTL	DETAIL						
DWG	DRAWING						
DWL	DOWNEL						





Craig Luebert
Architecture



Construction Documents for:

HEARTLAND MARKET

940 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT,
ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A. Luebert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.


DATE ISSUED:
7.14.23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

A100



NOTE: ALL DIMENSIONS ARE FROM FACE OF MASONRY
BLOCK TO FACE OF STUD UNLESS SHOWN OTHERWISE.

CJ - CONTROL JOINT PER INDUSTRY STANDARDS, PROVIDE BACKER
ROD AND CAULK, TYP.

WALL TYPES

- A** 8" CMU BLOCK WALL W/ 3 5/8" MTL. STUDS
@ 16" O.C. 5/8" GYP. BD. BATT INSULATION
- B** 3 5/8" MTL. STUDS W/ GYP. BD BOTH
SIDES. EXTEND WALL TO B.O. OF
TRUSSES. GYP. BD. TO B.O. TRUSSES
(1) SIDE ONLY
- C** (2) 3 5/8" MTL. STUDS @ 16" O.C.
PLUMBING WALL FACE OF STUD TO
FACE OF STUD IS 8"
- D** 3 5/8" MTL. STUDS W/ GYP. BD BOTH
SIDES. EXTEND WALL 4" ABOVE CEILING
PROVIDE KICKER STUDS TO STRUCT AS
REQUIRED


PLAN NOTES

- NOTE NOT USED
- PROVIDE 1 1/2" BETWEEN COOLER AND WALL
- COOLERS / FREEZERS SHALL MEET UL RATINGS AND CONFORMANCE WITH IBC 2018.
WALK-IN COOLER SHALL CONFORM TO 2803.4 THERMAL BARRIER
AND 2803.4.1.3 WALK-IN COOLERS IN NON-SPRINKLERED BUILDINGS.
- PROVIDE 2" RIGID INSUL. UNDER
SLAB W/ 15 mil VAPOR BARRIER AT COOLERS AND FREEZER- INDICATED BY
HATCH - FLOORS TO BE SEALED CONCRETE
- STEEL ROOF ACCESS LADDER SEE DETAIL SIA104
- SHELVING / FIXTURES BY OWNER
- FLOOR DRAIN
- 4" DIA. x 6'-6" TALL PIPE BOLLARD FILL W/ CONC. - 3'-6" FROM FIN. GRADE TO TOP OF BOLLARD
TYP OF 23 IN FRONT OF BUILDING AND ON EAST SIDE
- PROVIDE STAINLESS STEEL BEHIND HOOD FROM FIN. FLOOR
TO B.O. OF HOOD
- SOUND BATT INSULATE WALLS SURROUNDING TOILET ROOMS
- APPLY 1/2" GYP. BD. ON COOLER WALL - TYPICAL
- WALL ABOVE COOLER TO EXTEND TO B.O. OF ROOF DECKING
W/ GYP. BD. ON BOTH SIDES
- 4" REINF. CONCRETE SLAB - G.C. TO VERIFY SIZE
- CHAIN LINK FENCE W/ GATE. SECURE TO FLOOR


EQUIPMENT LIST

G.C. TO VERIFY ALL EQUIPMENT W/ OWNER


- | | | |
|---|---|--|
| 01 SURE IMMERSION 312 FILTER STYLE COFFEE SYST. | 18 NEWCO - LEMONADE DISPENSER | 37 OUTDOOR CO2 TANK |
| 02 KAN PAK REFRIGERATED LIQUID DISPENSER (CREAMER) | 19 CORNELIUS - VIPER 4 FLAVOR FROZEN DISPENSER | 38 HOOD - REF MECHANICAL DRAWINGS. PROVIDE
STAINLESS STEEL FROM B.O. OF HOOD TO FLOOR |
| 03 3-BURN DUAL SOFT HEAT COFFEE BREWER - SH-DBC-(3) | 20 Bunn ULTRA-2 HP Ultra Goumet Ice Frozen Drink Machine | 39 ATM |
| 04 CURTIS PRIMO CAPPUCCINO DISPENSING SYSTEMS - POGT5 (2) | 21 HATCO ROUND WAFFLE MAKER - RWIM-2 | |
| 05 ICED TEA BREWING SYSTEM - TCT'S10600 | 22 RESFAB HOT FOOD CASE (CHICKEN) KK-4P | |
| 06 NEWCO ICED COFFE MACHINE - 736661 | 23 LOTTERY EQUIPMENT | |
| 07 BEVERAGE SOLUTIONS GROUP - CREAMER AND SUGAR STATION | 24 NEMCO COUNTER TOP WARMER 6055A-43 | |
| 08 ROYSTON DONUT CASE 60101610 | 25 MICALI PIZZA PREP TABLE - C-PP4HC | |
| 09 FEDERAL REFRIGERATED SELF-SERVE ISLAND. PROVIDE ELEC IN
FLOOR - VERIFY LOCATION WITH MANUF. | 26 CADCO HEAVY DUTY COUNTERTOP CONVECTION OVEN | |
| 10 RESFAB FRYERS - (2) | 27 AVANTCO COUNTERTOP GRIDDLE | |
| 11 LINCOLN ELECTRIC OVEN (2) STACKED | 28 SHARP MICROWAVE OVEN R-21LCP5 | |
| 12 OUTDOOR GREASE TANK - 1,400 LB CAPACITY | 29 AVANTCO WORKTOP FREEZER SSINT | |
| 13 REGENCY (3) COMPARTMENT SINK WITH 2 DRAINBOARDS | 30 FREAL BLENDER | |
| 14 FEDERAL REFRIGERATED SELF-SERVE MERCHANDISER | 31 NEMCO DUAL SHELF MERCHANDISER - 6480-36S | |
| 15 GEHL'S MACHO DISPENSER (2) | 32 NEMCO DUAL SHELF MERCHANDISER - 648018S-B | |
| 16 LANCER ICE AND BEVERAGE DISPENSER BD: 4500-44 - (2) | 33 APW WYOTT HOT ROD ROLLER - HR(S) - 50S W/ SNEEZE GUARD | |
| 17 MULTIPLEX FRESH BLENDER | 34 APW WYOTT BUN WARMER - BWD-75 | |
| | 35 SAMSUNG MICROWAVE MS14K6000AS | |
| | 36 HATCO GLO RAY PIZZA WARMER GRPVS-3618D | |



8 Fountain Disp. Cabinet - Drive Thru 110
SCALE: 3/8" = 1'




7 POS Cabinet - Drive Thru 110
SCALE: 3/8" = 1'






2 Vanity Detail
SCALE: 1 1/2" = 1'


- ### TOILET ACCESSORIES
- ALL WASH-ROOM ACCESSORIES INSTALL PER MANUFACTURERS RECOMMENDATIONS AND PER ANSI A117.1-2009 AND LOCAL CODE. SEE SHEET A0.1 FOR FIXTURE / ACCESSORIES MOUNTING HEIGHTS. PROVIDE BLOCKING IN WALLS AS REQUIRED FOR INSTALLATION.
- A GRAB BARS ————— BOBRICK® B-5806x42, B-5806x36, B-5806x18
 - B MIRROR ————— BRADLEY 28"X 36"
 - C TOILET TISSUE DISPENSER ————— BOBRICK B-2892 SURFACE MOUNTED
 - D SOAP DISPENSER ————— B-818615
 - F SANITARY NAPKIN DISPOSAL ————— B-270
 - G CHANGING STATION ————— FOUNTAINS 100 EH BP
 - H HAND DRYER ————— ELECTRIC HAND DRYER - XL-SB
 - J ADA SIGNS ————— SEE SHEET A0.1




1 Toilet Plan
SCALE: 1/4" = 1'




3 Toilet Elevations
SCALE: 3/8" = 1'




5 North Wall Cooler Elevation
SCALE: 3/8" = 1'



4 Cashier Elevation
SCALE: 3/8" = 1'




5A North Wall Cooler Elevation Cont'd
SCALE: 3/8" = 1'



1

East Wall Cooler / Freezer Elevation

SCALE: 3/8"=1'



Craig Luebbert
Architecture

C
L
A

Construction Documents for:

HEARTLAND MARKET

940 NE Colbern Rd.
Lee's Summit, MO.


COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER
A101.1




NORTH

1


Reflected Ceiling Plan

SCALE: 3/16"=1'




6 Soffit Above Beverage Center

SCALE: 1 1/2"=1'




5 Soffit Detail

SCALE: 1 1/2"=1'




4 Bulkhead Detail @ Cooler

SCALE: 1 1/2"=1'







3 Ceiling Grid Detail / Light Attachment

SCALE: nts






2 Ceiling Grid Detail


SCALE: nts



OVERFLOW LAMBS TONGUE

JOSAM SERIES OR EQUAL CAST BRONZE DOWNSPOUT NOZZLE, LOOSE WALL FLANGE AND INLET THREADED CONNECTION. 4" PIPE SIDE





Craig Luebbert
Architecture

CL A

Construction Documents for:

HEARTLAND MARKET



940 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A. Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.


DATE ISSUED:	7.14.23
REVISIONS:	
Δ CITY COMMENTS - 6.6.22	
ARCHITECTURAL PROJECT NUMBER	

SHEET NUMBER

A200




6 Stucco Joint
SCALE: NTS




5 Precast Detail
SCALE: 1 1/2"=1'




1 South Elevation
SCALE: 3/16"=1'




3 East Elevation
SCALE: 3/16"=1'



2 West Elevation
SCALE: 3/16"=1'



4 North Elevation
SCALE: 3/16"=1'



HEARTLAND MARKET

940 NE Colbern Rd.
Lee's Summit, MO.

DATE ISSUED
7.14.23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER

A201



SCALE: NTS

5

-

-


- 

-

-

- SCALE: NTS

2 Canopy Elevation



Construction Documents for:

HEARTLAND MARKET

940 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A. LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A. Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.


DATE ISSUED:
7.14.23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER


SHEET NUMBER

A300



3 Opening Detail
SCALE: 1 1/2"=1'

1 Cross Section
SCALE: 1/4"=1'



2 Longitudinal Section
SCALE: 1/4"=1'

#XJ15 Double-J Control Joint (XJ15)

Expanded flange control joint with a taped reveal for a clean finish

#XJ15 Expanded Flange Control Joint (Double-J) is used to relieve stresses in large plastered areas of walls, ceilings, and stucco areas. This expanded wing control joint minimizes cracking and assures proper plaster and stucco thickness. The Double-J has a 5/16" reveal and rolled outer edges to prevent visible separation cracking. The applied plastic tape keeps the reveal clean and is removed easily after the finish application.

The #XJ15 enables plaster to key into the return lip to eliminate shrinkage separation, a preferred finish feature. The joint is taped, preventing stucco from getting caught inside during installation and providing a neatly finished job upon completion.

The #XJ15 Double-J Control Joint is also available in zinc alloy for increased corrosion resistance.

Product Data & Ordering Information:

Material: 26 Gauge, G60 Hot-Dipped Galvanized Steel

Also available in 99.97% pure Zinc - ASTM B-69 compliant

Dimensions: 1/2" to 7/8" Grounds, 10' lengths

Ground	Length	Pcs./Ctn.	Ft./Ctn.	Wt./Ctn.	Ctn./Skid
1/2"	10'	24	240	54 lbs.	27
3/4"	10'	24	240	69 lbs.	30
7/8"	10'	24	240	76 lbs.	30

ASTM & Code Standards:

- ASTM C841 (interior), C1063 (exterior), CE 240.01, ASTM C926, ML/SFA-920, the International Code Council IBC and IRC.
- All Expanded Metal Lath Accessories are fabricated from prime galvanized steel G60 zinc coating by the hot dipped method, conforming to steel and coating specification ASTM A653/A653M or zinc alloy meeting ASTM B-69 as required in ASTM C1063 and C847.
- SDS & Product Certification Information is available at www.clarkdietrich.com/SupportDocs
- For installation and placement instructions refer to ASTM C1063, C841 and C926.

Storage:

All stored materials shall be kept dry. Materials shall be stacked off the ground, supported on a level platform, and protected from the weather and surface contamination conforming to ASTM C1063.


Limitations:

Galvanized steel products should not be used with magnesium oxychloride cement stucco or Portland cement stucco containing calcium chloride additives. The selection of the appropriate type of material for accessories shall be determined by the surrounding climatic and environmental conditions such as salt air, industrial pollution and high humidity.

System Bulletin

StoPowerwall®

Portland cement stucco with StoGuard® air and water-resistive barrier system, drainage, and Sto high performance finishes



Substrate: Glass mat gypsum sheathing in compliance with ASTM C 1177, building code compliant wood-based sheathing (plywood or OSB), concrete, or concrete masonry (CMU)

1)	StoGuard® Air and Water-Resistive Barrier
2)	Code compliant paper or felt Water-Resistive Barrier
3)	Code compliant minimum 2.5 lb/yd² (1.4 kg/m²) self-furred galvanized steel diamond mesh metal lath
4)	ASTM C926 compliant stucco scratch coat (as manufactured or listed by Sto Corp.)
5)	ASTM C926 compliant stucco brown coat (as manufactured or listed by Sto Corp.)
6)	Sto Primer
7)	Sto Textured Finishes

System Description

StoPowerwall is a drainable stucco wall assembly that features a code compliant StoGuard air and water-resistive barrier system. It combines the strength and durability of traditional stucco with StoGuard air and water protection and Sto high performance finishes.

Uses

StoPowerwall can be used in residential or commercial wall construction for superior aesthetics, durability, and air and moisture control.

Features	Benefits
Integrally colored factory blended Sto textured, StoCast finishes, or Sto Specialty finishes	Consistent color and aesthetics increase curb appeal
StoGuard air and water-resistive barrier system	Fully compatible, code compliant air and water-resistive barrier system
Impact and puncture resistance	Withstands abuse, reduced maintenance
Optional Sto Crack Defense	Resists stucco cracking

Properties

Weight (excluding sheathing / studs)	< 12 psf (56.6 kg/m²)
Assembly Thickness (from outer face of sheathing)	Nominal 7/8 inch (22mm)
R-value (from outer face of sheathing)	0.84 ft²•h•°F / Btu (0.148 m²•K / W)
Wind Load Resistance	Capable of achieving: +65, -48 psf (+3.11, -2.29 kPa)
StoGuard air and water-resistive barrier system code compliance with StoGuard Detail Components	• IBC and IRC (2015, 2018) • ASHRAE 90.1-2019
Construction Types, Fire Resistance	• For use on all Types of Construction • ASTM E119 hourly rated assemblies


Warranty

10 year Limited Warranty when used with Sto Crack Defense




Maintenance

Requires periodic cleaning to maintain appearance, repair of cracks and impact damage if they occur, recoating to enhance appearance of weathered finish. Sealants and other façade components must be maintained to prevent water infiltration.


09.22.36 (Metal Lath)



*All Dimensions Nominal



2 Wall Section
SCALE: 3/4"=1'




1 Wall Section
SCALE: 3/4"=1'

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23

REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A302

940 NE Colbern Rd.
Lee's Summit, MO.

Construction Documents for:

HEARTLAND MARKET

Craig Luebbert
Architecture



COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020

Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebbert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.

DATE ISSUED:
7.14.23


REVISIONS:
CITY COMMENTS -6.6.22

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

A302

Craig Luebert
Architecture



Construction Documents for:

HEARTLAND MARKET

940 NE Colbern Rd.
Lee's Summit, MO.

COPYRIGHT: CRAIG A LUEBBERT, ARCHITECT, LLC 2020
Do not reproduce these drawings and specifications without express written permission of the Architect. The drawings and specifications are instruments of service and shall remain the property of the Craig A Luebert, Architect, LLC whether the project for which they are made is executed or not. These drawings and specifications shall not be used by anyone on any other project for additions to this project by others except by the express written permission of the Architect.


DATE ISSUED:
7.14.23

REVISIONS:


ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


A303




5 Gate Detail
SCALE: 1 1/2"=1'




6 Monument Sign Section
SCALE: 3/4"=1'




7 Monument Sign Elevation
SCALE: 1/2"=1'




3 Trash Enclosure Section
SCALE: 3/4"=1'



4 Trash Enclosure Elevation - North / South
SCALE: 1/2"=1'



1 Trash Enclosure Plan
SCALE: 1/2"=1'



2 Trash Enclosure Elevation
SCALE: 1/2"=1'




ROOM FINISH SCHEDULE

[illegible]

CEILINGS	
ACT-1	ACOUSTICAL TILE CEILING - 2 x 2 TEGULAR
ACT-2	VINYL FACED ACOUSTICAL TILE CEILING - 2 x 2
GYP-1	GYP.BD SOFFIT - 8'-0" AFF

NOTE: TEMPERED GLAZING / SAFETY GLAZING SHALL MEET THE SAFETY GLAZING IN HAZARDOUS LOCATIONS REQUIRED PER IBC 2406 AND IBC 2406.3

5



STRUCTURAL NOTES

- GENERAL NOTES:
- DESIGN AND CONSTRUCTION SHALL CONFORM TO THE 2018 INTERNATIONAL BUILDING CODE.
 - THE DRAWINGS REPRESENT THE FINISHED STRUCTURE, NOT THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE NEW STRUCTURE DURING CONSTRUCTION INCLUDING, BUT NOT LIMITED TO, BRACING, SHORING FOR CONSTRUCTION LOADS AND EQUIPMENT, ETC. THE ARCHITECT-ENGINEER IS NOT RESPONSIBLE FOR THE CONTRACTOR'S MEANS AND METHODS, SEQUENCES OF CONSTRUCTION, OR THE SAFETY PROGRAM. OBSERVATION VISITS TO THE SITE BY THE ARCHITECT-ENGINEER WILL NOT INVOLVE REVIEW OF THESE ITEMS.
 - CONTRACTOR IS TO ESTABLISH AND VERIFY OPENINGS AND INSERTS FOR ITEMS TO BE INSTALLED BY OTHER TRADES PRIOR TO SUBMITTAL OF SHOP DRAWINGS AND CONSTRUCTION.
 - CONSTRUCTION MATERIAL AND EQUIPMENT PLACED ON FRAMED CONSTRUCTIONS SHALL BE SUCH THAT THE LOAD DOES NOT EXCEED THE DESIGN LIVE LOAD OF THE CONSTRUCTION. PROVIDE SHORING OF CONSTRUCTIONS WHERE NECESSARY FOR LOADS.
 - DETAILS THAT ARE NOTED AS "TYP." ON DETAIL TITLES ARE TO BE APPLIED TO THE PROJECT CONSTRUCTION AS GENERAL CONSTRUCTION METHODS UNLESS NOTED OTHERWISE. THESE DETAILS ARE NOT CUT AT ALL LOCATIONS THEY OCCUR AND MAY NOT BE CUT AT ALL.
 -

DESIGN:
ALL CONSTRUCTION SHALL COMPLY WITH THE FOLLOWING CODES AND STANDARDS, EXCEPT WHERE NOTED TO THE CONTRARY ON DRAWINGS OR WHERE MORE STRINGENT REQUIREMENTS ARE SHOWN.

ACI 117	STANDARD SPECIFICATIONS FOR TOLERANCE FOR CONCRETE CONSTRUCTION AND MATERIALS
ACI 301	SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS
ACI 318	BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE
AISC	SPECIFICATIONS FOR STRUCTURAL STEEL FOR BUILDINGS
AISI-NAS	NORTH AMERICAN SPECIFICATION FOR THE DESIGN OF COLD-FORMED STEEL STRUCTURAL MEMBERS
AWS D1.1	STRUCTURAL WELDING CODE

DEAD LOADS:
20 PSF ROOF LOAD

LIVE LOADS:
20 PSF ROOF LOAD

SNOW LOADS:
SNOW LOADS IN ACCORD WITH THE 2018 INTERNATIONAL BUILDING CODE AND ASCE 7 INCLUDING DRIFTING SNOW LOADS CHAPTER 16.
Ce = 1.0 Cf = 1.0
Is = 1.0 Pg = 20 PSF
Pf = 16 PSF Pf(min) = 20 PSF
RAIN ON SNOW LOAD= 5 PSF
DESIGN SNOW LOAD SHALL BE WORST CASE OF:
CASE 1: 20 PSF + SNOW DRIFT (SEE 31/54.0 FOR JOIST SNOW DRIFT)
CASE 2: 25 PSF (BALANCED SNOW + RAIN-ON-SNOW)

WIND LOAD:
WIND LOADS IN ACCORD WITH THE 2018 INTERNATIONAL BUILDING CODE.
ULTIMATE DESIGN WIND SPEED = 115 MPH
EXPOSURE "C"
Gcpi = +/- 0.18

SEISMIC LOAD:
SEISMIC DESIGN IN ACCORD WITH 2018 INTERNATIONAL BUILDING CODE.
Ie=1.0
SITE CLASS = D
MAPPED SPECTRAL RESPONSE COEFFICIENTS: Ss = 0.1005 Si = 0.0686
SPECTRAL RESPONSE COEFFICIENTS: SDS = 0.107 SDI = 0.110
SEISMIC DESIGN CATEGORY B
R = 3.5
Cs = 0.0306

LATERAL LOAD RESISTANCE SYSTEM:
LATERAL LOAD SYSTEM CONSISTS OF ROOF DIAPHRAGMS TRANSFERRING LATERAL LOADS TO MASONRY SHEAR WALLS SUPPORTED BY CONCRETE FOUNDATIONS.

- FOUNDATIONS:
- A GEOTECHNICAL REPORT HAS NOT BEEN COMPLETED. FOUNDATIONS HAVE BEEN DESIGNED TO BEAR ON STRUCTURAL SOIL CAPABLE OF SUPPORTING 1500PSF.
 - MINIMUM FROST DEPTH: 3'-0"

CONCRETE:

1. CONCRETE MIX DESIGNS:
FOOTINGS:
MIN 28 DAY COMPRESSIVE STRENGTH = 3,000 PSI
W/C RATIO = 0.50
MAX AGGREGATE SIZE = ¾"
SLUMP = 4"±1"
AIR CONTENT = 6% ±1.5% (ASTM C 260)

SLAB ON GRADE:
MIN 28 DAY COMPRESSIVE STRENGTH = 4,000 PSI
W/C RATIO = 0.45
MAX AGGREGATE SIZE = ¾"
MAX SLUMP = 4"
AIR CONTENT = 1.5% (ASTM C 260)

EXTERIOR CONCRETE:
MIN 28 DAY COMPRESSIVE STRENGTH = 4,500 PSI
W/C RATIO = 0.40
MAX AGGREGATE SIZE = ¾"
SLUMP = 4"±1"
AIR CONTENT = 6% ± 1.5% (ASTM C 260)

- IF CONTRACTOR DESIRES TO INCREASE SLUMP ABOVE ALLOWABLE LIMITS TO FACILITATE PLACEMENT OR PUMPING, THIS SHALL BE DONE UTILIZING AN APPROPRIATE APPROVED ADMIXTURE. NO WATER SHALL BE ADDED AT THE PROJECT SITE WITHOUT THE ENGINEER'S PERMISSION. ALL ADMIXTURES SHALL BE APPROVED IN WRITING BY THE ENGINEER.
- THE CONTRACTOR SHALL REJECT ANY CONCRETE THAT EXCEEDS THE SLUMP LIMITS NOTED ABOVE OR EXCEEDS THE TOTAL ALLOWABLE MIXING TIME.
- FLY ASH MAY BE INCLUDED IN FOUNDATION CONCRETE.
- NO ALUMINUM SHALL BE PLACED IN CONCRETE.
- DURING HOT WEATHER (80 DEGREES F AND ABOVE, THE CONTRACTOR SHALL COMPLY WITH THE RECOMMENDATIONS ACI 305"HOT WEATHER CONCRETE." DURING COLD WEATHER (40 DEGREES F AND BELOW), THE CONTRACTOR SHALL COMPLY WITH THE RECOMMENDATIONS OF ACI-306 "COLD WEATHER CONCRETING."
- THE CONCRETE MIX DESIGNS ARE TO BE SUBMITTED AS A FORMAL SUBMITTAL TO THE ENGINEER OF RECORD FOR REVIEW AND ACCEPTANCE. AFTER ACCEPTANCE OF THE MIX DESIGN BY THE ENGINEER OF RECORD, THE ACCEPTED DESIGNS MUST BE FORWARDED TO THE CITY INSPECTION DEPT. & THE SPECIAL INSPECTOR PRIOR TO CONCRETE BEING DELIVERED TO THE SITE.

CONCRETE REINFORCEMENT:

- REINFORCING STEEL SHALL BE ASTM A615, GRADE 60.
- CONCRETE COVER REQUIREMENTS FOR CAST-IN-PLACE, UNLESS OTHERWISE NOTED ON DETAILS:

CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH: 3"

OTHER: #6 BARS AND LARGER: 2"
 #6 BARS AND SMALLER: 1-½"
- REINFORCING BAR SPLICES SHALL BE IN ACCORD WITH THE REQUIREMENTS OF ACI 318-11 AND THE REINFORCING SPLICE LENGTH TABLE SHOWN ON THE DRAWINGS.

- MASONRY:
- THE MINIMUM 28-DAY COMPRESSIVE STRENGTH OF THE CONCRETE MASONRY UNITS SHALL BE 1900 PSI ON THE NET AREA, PROVIDING A STRUCTURAL DESIGN COMPRESSIVE STRENGTH OF 1500 PSI PER THE 2018 INTERNATIONAL BUILDING CODE, TABLE 2105.2.2.1.2.
 - MORTAR SHALL BE TYPE S IN ACCORD WITH ASTM C270 AND ARTICLES 2.1 AND 2.6 A OF TMS 602/ACI 530.1/ASCE6, MORTAR PROPORTIONS FOR UNIT MASONRY, USING CEMENT LIME OR MORTAR CEMENT MIXES. (MASONRY CEMENT IS NOT ACCEPTABLE).
 - MINIMUM 28-DAY COMPRESSIVE STRENGTH OF GROUT SHALL BE THE GREATER OF 2500 PSI OR THE COMPRESSIVE STRENGTH OF THE MASONRY UNITS. AIR ENTRAINMENT AND OTHER ADDITIVES ARE NOT ACCEPTABLE IN GROUT MIX. GROUT SHALL HAVE A SLUMP OF 8 TO 11 INCHES.
 - MASONRY REINFORCING STEEL SHALL BE ASTM A615, GRADE 60.
 - HORIZONTAL JOINT REINFORCING SHALL BE STANDARD LADDER TYPE, GALVANIZED, AT 16-INCHES ON CENTER, UNLESS OTHERWISE NOTED ON PLAN.
 - MINIMUM BOND BEAM REINFORCING SHALL BE 2 - #4 IN 6" AND 8" BOND BEAMS AND 2 - #5 IN 12" BOND BEAMS. BOND BEAM REINFORCING SHALL BE CONTINUOUS THROUGH CONTROL JOINTS EXCEPT AS NOTED ON TYPICAL MASONRY WALL OPENING DETAIL.
 - SPLICE LENGTHS FOR MASONRY REINFORCEMENT SHALL BE IN ACCORD WITH THE REINFORCING SPLICE LENGTH TABLE OR AS SHOWN ON THE DRAWINGS.
 - PROVIDE BOND BEAMS AT TOP OF ALL WALLS, AT ROOFS, STRUCTURAL FLOORS, OVER ALL OPENINGS IN WALLS AND WHERE SHOWN ON THE DRAWINGS.
 - REINFORCING SHALL BE HELD IN PLACE PRIOR TO GROUTING WITH WIRE POSITIONERS PLACED AT INTERVALS NOT EXCEEDING 192 BAR DIAMETERS NOR 10 FEET. PROVIDE POSITIONERS AT REINFORCING SPLICES.
 - VERTICAL REINFORCING SHALL BE AS FOLLOWS, UNLESS OTHERWISE NOTED ON THE PLANS OR DETAILS.

8" CONC BLOCK	1-#5 @ 4'-0" OC
10" CONC BLOCK	1-#5 @ 4'-0" OC
12" CONC BLOCK	2-#6'S @ 4'-0" OC

- PROVIDE #5 VERTICAL REINFORCING AT JAMB OPENINGS, ENDS AND CORNERS OF ALL WALLS AND EACH SIDE OF CONTROL JOINTS. SPECIAL JAMB REINFORCING, WHERE REQUIRED, IS CALLED OUT ON THE PLANS.
- VERTICAL REINFORCING REQUIRED BY THESE NOTES OR SHOWN ON THE FOUNDATION PLANS SHALL EXTEND FROM FOUNDATION TO TOP OF WALL UNLESS OTHERWISE NOTED.
- ELECTRICAL PANELS, CONDUITS, PIPES, FIRE EXTINGUISHER CABINETS, ETC., ARE TO BE LOCATED SO AS NOT TO INTERFERE WITH REINFORCED AND/OR GROUTED CELLS. PIPES AND CONDUITS PASSING HORIZONTALLY THROUGH WALLS SHALL BE SLEEVED. MINIMUM SPACING OF SLEEVES SHALL BE THREE DIAMETERS.
- ALL MASONRY BELOW HIGHEST ADJACENT GRADE SHALL BE GROUTED SOLID.
- GROUT SHALL BE MECHANICALLY CONSOLIDATED IN A MANNER TO FILL THE GROUT SPACE AND RECONSOLIDATED IN ACCORD WITH THE 2018 INTERNATIONAL BUILDING CODE.
- PROVIDE GROUT AND MASONRY UNIT TESTING PRIOR TO AND DURING CONSTRUCTION IN ACCORD WITH THE 2018 INTERNATIONAL BUILDING CODE.
- REINFORCEMENT PLACEMENT, GROUT SPACES AND GROUTING OPERATION SHALL BE INSPECTED BY TESTING LABORATORY IN ACCORD WITH THE 2018 INTERNATIONAL BUILDING CODE REQUIREMENTS. MORTAR FIN PROJECTION INTO THE GROUT SPACE SHALL NOT EXCEED ½ INCH.

- STRUCTURAL STEEL
- FABRICATOR SHALL BE AN "APPROVED FABRICATOR" IN ACCORD WITH THE 2018 INTERNATIONAL BUILDING CODE SECTION 1704.2.5, REGISTERED AND APPROVED BY THE LOCAL BUILDING DEPARTMENT. IN LIEU OF THE PREVIOUS, FABRICATOR SHALL INCLUDE IN THEIR BID THE SERVICES OF A SPECIAL INSPECTOR TO PROVIDE INSPECTION/TESTING SERVICES FOR IN-SHOP WORK TO MEET THE REQUIREMENTS OF 2018 INTERNATIONAL BUILDING CODE SECTION 1704.
 - STRUCTURAL STEEL SHALL MEET ASTM A36 UNLESS NOTED OTHERWISE. STRUCTURAL STEEL WIDE FLANGE SHAPES SHALL MEET ASTM A992.
 - STEEL TUBES SHALL MEET ASTM A500, GRADE B.
 - STEEL PIPE SHALL MEET ASTM A53, TYPE E OR S, GRADE B.
 - BOLTS SHALL BE ¾" DIAMETER A325-N UNLESS OTHERWISE NOTED.
 - FIELD BOLTING INSTALLATION SHALL BE INSPECTED IN ACCORD WITH THE 2018 INTERNATIONAL BUILDING CODE AND THE AISC LRFD MANUAL, SECOND EDITION. BOLTS SHALL BE INSTALLED SNUG TIGHT UNLESS NOTES OTHERWISE NOTED. ASTM A-325-SC SHALL BE FULLY TIGHTENED USING LOAD INDICATOR WASHERS.
 - ALL WELDING SHALL CONFORM TO THE PROVISIONS OF THE AMERICAN WELDING SOCIETY CODE AWS D1.1-10. ELECTRODES SHALL MATCH BASE METALS AS SPECIFIED IN 2018 INTERNATIONAL BUILDING CODE.
 - ALL FIELD WELDING SHALL BE VISUALLY INSPECTED BY THE TESTING LABORATORY.
 - HOT DIP GALVANIZE ALL EXPOSED STEEL MEMBERS TO MEET ASTM 525 G60.
 - ALL STEEL BELOW GRADE SHALL BE ENCASED IN CONCRETE WHERE POSSIBLE; IF NOT POSSIBLE, STEEL SHALL BE THOROUGHLY COATED WITH TWO COATS OF ASPHALTIC PAINT.
 - SEE ARCHITECTURAL DRAWINGS FOR ANY ADDITIONAL STRUCTURAL STEEL NOT CALLED OUT ON STRUCTURAL DRAWINGS.

PREFABRICATED WOOD TRUSSES:

- ROOF AND FLOOR TRUSSES SHALL BE DESIGNED IN ACCORDANCE WITH TRUSS PLATE INSTITUTES (TP) DESIGN SPECIFICATION FOR METAL PLATE CONNECTED WOOD TRUSSES AND THE NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION. BRACE TOP AND BOTTOM CHORDS OF TRUSSES DURING ERECTION PER MANUFACTURER RECOMMENDATIONS.
 - ROOF TRUSSES SHALL BE DESIGNED FOR AND CONSTRUCTED FOR A MAXIMUM LIVE LOAD DEFLECTION OF L/360. FLOOR TRUSSES SHALL BE DESIGNED AND CONSTRUCTED FOR A MAXIMUM LIVE LOAD DEFLECTION OF L/360 WITH NON BEARING WALLS BELOW AND L/480 AT CLEAR SPAN TRUSSES.
 - TRUSS SPACING IS AS DETERMINED BY TRUSS MANUFACTURER. MAXIMUM SPACING IS 24" OC.
 - LOADS ARE NOTED IN THE LOADING SECTION AND ARE MINIMUM. TRUSS DESIGNER IS RESPONSIBLE FOR ESTABLISHING FINAL LOADS USED FOR DESIGN, INCLUDING LIVE, DEAD, SNOW (WITH DRIFTS) AND WIND LOADS. TRUSS FABRICATOR TO SUPPLY SEALED TRUSS SHOP DRAWINGS AND SEALED PLAN PLACEMENT DRAWINGS PREPARED UNDER THE SUPERVISION OF THE SAME LICENSED PROFESSIONAL ENGINEER IN THE STATE OF MISSOURI. SHOP DRAWINGS SHOULD INCLUDE DETAILED ERECTION DRAWINGS, AS WELL AS DESIGN INFORMATION FOR EACH TRUSS. PROVIDE ALL INFORMATION AS REQUIRED IN THE 2018 IBC SECTION 2303.4.1.
 - TRUSS MANUFACTURER IS RESPONSIBLE FOR DESIGNING ALL TRUSS-TO-TRUSS, TRUSS-TO-WALL AND TRUSS-TO-BEAM CONNECTIONS UNLESS NOTED OTHERWISE.
- ROUGH CARPENTRY:
- ALL WOOD FRAMING MEMBERS INDICATED ARE NOMINAL SIZES. PROVIDE ACTUAL DRESSED SIZES, KILN DRIED, WITH MAXIMUM IN PLACE MOISTURE CONTEXT OF 19%.
 - ALL BOLTS ARE A36 OR A307, GRADE A, AND ALL NAILS ARE BOX NAILS UNLESS NOTED OTHERWISE.
 - SHEARWALL SHEATHING IS 7/16" SHEATHING ATTACHED WITH NO. 8D NAILS SPA AT 6" MAX UNLESS NOTED OTHERWISE. SEE SHEARWALL SCHEDULE.
 - UNLESS NOTED OTHERWISE, FASTENER QUALITY, QUANTITY SIZE AND SPACING SHALL COMPLY WITH THE 2018 IBC FASTENING SCHEDULE (TABLE 2304.9)
 - ALL WOOD IN CONTACT WITH THE CONCRETE OR EXPOSED TO WEATHER SHALL BE PRESERVATIVE TREATED.
 - 15/32" ROOF SHEATHING STRUCTURAL WITH 10d NAILS AT 6" OC.
 - JOIST HEADERS AND WALL STUDS TO BE #2 DOUGLAS FIR AND LVL -E=1,900,000 PSI

- POST-INSTALLED ANCHORS:
- EXPANSION BOLTS INSTALLED IN CONCRETE SHALL BE HILTI KWIK BOLT-II ANCHORS OR APPROVED EQUAL WITH EMBEDMENT NOTED ON THE DRAWINGS OR EMBEDMENT AS RECOMMENDED BY MANUFACTURER WHERE NO EMBEDMENT IS SHOWN. INSTALL IN ACCORD WITH MANUFACTURER'S RECOMMENDATIONS AND ICBO REPORT ER-4627.
 - SCREW ANCHORS SHALL BE KWIK CON II CONCRETE ANCHORS BY HILTI, INC. OR APPROVED EQUAL. INSTALL IN ACCORD WITH MANUFACTURER'S RECOMMENDATIONS AND ICBO REPORT ER-5259
 - ADHESIVE ANCHORS SHALL BE HILTI INC., HIT HY 200 ADHESIVE. ANCHORING SYSTEM OR APPROVED EQUAL, WITH EMBEDMENT NOTED ON THE DRAWINGS OR EMBEDMENT AS RECOMMENDED BY MANUFACTURER WHERE NO EMBEDMENT IS SHOWN. INSTALL IN ACCORD WITH MANUFACTURER'S RECOMMENDATIONS AND ICBO REPORT ESR-3187.
 - ANCHORS ARE NOT TO BE INSTALLED UNTIL CONCRETE OR GROUT HAS REACHED ITS DESIGN STRENGTH.

FIRE RATINGS:
1. FOR FIRE-RATING REQUIREMENTS AND METHODS, SEE ARCHITECTURAL DRAWINGS.

- SPECIAL STRUCTURAL INSPECTIONS:
- IN ACCORD WITH THE 2018 INTERNATIONAL BUILDING CODE, SECTION 1704, AS NOTED BELOW. TESTING AND INSPECTION SHALL BE BY AN INDEPENDENT TESTING/INSPECTION FIRM, UNDER THE SUPERVISION OF A LICENSED ENGINEER EMPLOYED BY THAT FIRM. THE BASIS FOR WELDING INSPECTOR QUALIFICATION SHALL BE AWS D1.1.
 - SPECIAL INSPECTION IS TO BE PROVIDED IN ADDITION TO THE INSPECTIONS CONDUCTED BY THE LOCAL DEPARTMENT OF BUILDING SAFETY AND SHALL NOT BE CONSTRUED TO RELIEVE THE OWNER OR HIS AUTHORIZED AGENT FROM REQUESTING THE PERIODIC AND CALLED INSPECTIONS REQUIRED BY THE 2018 INTERNATIONAL BUILDING CODE
 - VERIFICATION OF SOLS: PER SECTION 1705.6 AND TABLE 1705.6.
 - CONCRETE: PER SECTION 1705.3 AND TABLE 1705.3.(ALL CONCRETE EXCEPT SLABS-ON-GRADE AND SIDEWALKS). ANCHOR BOLTS SHALL BE INSPECTED.
 - STEEL: PER SECTION 1705.2 AND TABLE 1705.2.2. PROVIDE INSPECTION OF ALL SHOP WELDING AT CONTRACTOR'S EXPENSE IF WELDING IS NOT DONE IN AN APPROVED FABRICATOR'S SHOP.
 - HIGH STRENGTH BOLTING: PER SECTION 1704.3.3.
 - STRUCTURAL MASONRY: PER SECTION 1705.4.
 - EXPANSION BOLT, SCREW ANCHOR AND EPOXY ANCHOR INSTALLATION TO VERIFY INSTALLATION IN ACCORD WITH ICBO REPORTS NOTED PREVIOUSLY OR APPROVED EQUAL.
 - THE INSPECTOR SHALL OBSERVE THE WORK ASSIGNED TO BE CERTAIN IT CONFORMS WITH THE APPROVED DESIGN DRAWINGS AND SPECIFICATIONS.
 - THE INSPECTOR SHALL FURNISH DAILY INSPECTION REPORTS ON THE WORK TO THE BUILDING OFFICIAL AND TO THE ENGINEER OF RECORD FOR CONFORMANCE TO THE CONTRACT DOCUMENTS. ALL DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION, AND, IF UNCORRECTED, TO THE ENGINEER OF RECORD AND THE BUILDING OFFICIAL.
 - THE TESTING/INSPECTION FIRM'S ENGINEER SHALL COMPLETE, SIGN AND SEAL A FINAL REPORT CERTIFYING THAT TO THE BEST OF HIS KNOWLEDGE, THE WORK IS IN CONFORMANCE WITH THE CONTRACT DOCUMENTS.

- DEFERRED SUBMITTALS:
- THE FOLLOWING ITEMS ARE DEFERRED SUBMITTAL ITEMS:
 - STEEL JOISTS
 - PRE ENGINEERED WOOD TRUSSES
 - DEFERRED SUBMITTAL ITEMS SHALL BE PREPARED AND SEALED BY A LICENSED PROFESSIONAL ENGINEER IN THE STATE OF THE PROJECT WITH CALCULATIONS, DRAWINGS, DETAILS, AND CUT SHEETS SUBMITTED TO THE ENGINEER OF RECORD FOR REVIEW. ONCE REVIEWED, CONTRACTOR SHALL FORWARD TO THE BUILDING DEPARTMENT FOR APPROVAL. FABRICATION AND/OR INSTALLATION OF DEFERRED SUBMITTAL ITEMS SHALL NOT OCCUR UNTIL APPROVAL OF THE BUILDING DEPARTMENT IS RECEIVED.

- SHOP DRAWING REVIEW:
- J&S STRUCTURAL ENGINEERS, PA WILL REVIEW SHOP DRAWINGS AND RELATED SUBMITTALS FOR GENERAL CONFORMANCE WITH THE DESIGN CONCEPT AND THE INFORMATION GIVEN IN THE CONSTRUCTION DOCUMENTS. REVIEW OF A SPECIFIC ITEM SHALL NOT INCLUDE REVIEW OF AN ASSEMBLY OF WHICH THE ITEM IS A COMPONENT.
 - THE FOLLOWING IS A LIST OF REQUIRED SHOP DRAWINGS AND RELATED SUBMITTALS. THE CONTRACTOR SHALL REFER TO THE SPECIFICATIONS FOR MORE INFORMATION AND A COMPLETE LIST OF REQUIRED SUBMITTALS:
 - CONCRETE MIX DESIGNS, TESTS AND MATERIAL CERTIFICATIONS
 - CONCRETE REINFORCING SHOP DRAWINGS AND REINFORCING MATERIAL CERTIFICATIONS
 - CONCRETE BLOCK COMPRESSION TESTS AND MATERIAL CERTIFICATIONS
 - MASONRY GROUT AND AND MORTAR MIX DESIGNS
 - MASONRY REINFORCING SHOP DRAWINGS
 - STRUCTURAL STEEL SHOP DRAWINGS MATERIAL CERTIFICATIONS, WELDER CERTIFICATIONS.

ABBREVIATIONS:	
ASD	ALLOWABLE STRESS DESIGN
ARCH	ARCHITECT
BPL	BASEPLATE
BTW	BETWEEN
BOTT	BOTTOM
BOTT OF BOL	BOTTOM OF
CIP	CAST IN PLACE
CL	CENTERLINE
CLR	CLEAR
CMU	CONCRETE MASONRY UNIT
COL	COLUMN
COMP	COMPRESSIBLE
CONC	CONCRETE
CONT	CONTINUOUS
CJ	CONTROL JOINT
DIM	DIMENSION
EA	EACH
EF	EACH FACE
ELEV	ELEVATION
EMBED	EMBEDMENT
EQ	EQUAL
EW	EACH WAY
EXP	EXPANSION
FF	FINISH FLOOR
FND	FOUNDATION
FTG	FOOTING
GALV	GALVANIZED
GB	GRADE BEAM
HSS	HOLLOW STRUCTURAL SECTION
HORIZ	HORIZONTAL
IJ	ISOLATION JOINT
INFO	INFORMATION
INSUL	INSULATION
JT	JOINT
JB	JOIST BEARING
K	KIP = 1,000 POUNDS
LONG	LONGITUDINAL
LRFD	LOAD AND RESISTANCE FACTORED DESIGN
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
MAS	MASONRY
MAT'L	MATERIAL
MAX	MAXIMUM
MBM	METAL BUILDING MANUFACTURER
MIN	MINIMUM
OC	ON CENTER
PEM	PRE-ENGINEERED MEMBER (NOT BY J&S STRUCTURAL ENGINEERS)
PEMB	PRE-ENGINEERED METAL BUILDING (NOT BY J&S STRUCTURAL ENGINEERS)
PL	PLATE
LB	POUND
PSF	POUNDS PER SQUARE FOOT
REF	REFERENCE
REINF	REINFORCEMENT
REQD	REQUIRED
SCHED	SCHEDULE
SPA	SPACE
SQ	SQUARE
STD	STANDARD
STL	STEEL
T&B	TOP AND BOTTOM
T&G	TONGUE-AND-GROOVE
TO	TOP OF
TOF	TOP OF FOOTING
TOL	TOP OF LINTEL
TOS	TOP OF STEEL
TRANS	TRANSVERSE
TYP	TYPICAL
UNO	UNLESS NOTED OTHERWISE
VERT	VERTICAL
WWR	WELDED WIRE REINFORCEMENT

EPOXY EMBEDMENT TABLE

BAR SIZE	REINFORCING STEEL			THREADED ROD ANCHORS	
	MINIMUM EMBEDMENT DEPTH			ANCHOR DIAMETER	MINIMUM EMBEDMENT DEPTH
	Pc=3,000 psi	Pc=3,500 psi	Pc=4,000 psi		
#3	3 1/2"	3"	2 3/4"	3/8"	5 1/4"
#4	5"	4 3/4"	4 1/4"	1/2"	6 3/8"
#5	6 1/4"	5 3/4"	5 1/4"	5/8"	7 1/2"
#6	7 1/2"	7"	6 1/2"	3/4"	10"
#7	9"	8 1/2"	7 3/4"	7/8"	11 1/4"
#8	10 1/2"	9 3/4"	9"	1"	12 1/2"
#9	11 1/2"	10 3/4"	10"	1 1/4"	15"
#10	13 1/2"	13"	12"	1 1/4"	18"

- NOTES:
- CONTRACTOR HAS THE OPTION TO EPOXY DOWELS AS AN ALTERNATE TO HOOKED OR CAST-IN-PLACE DOWELS WHERE NOTED ON DETAILS.
 - SEE GENERAL STRUCTURAL NOTES FOR APPROVED EPOXY.

MASONRY REINFORCEMENT SPLICE TABLE

BAR SIZE	6" BLOCK		8" BLOCK		10" BLOCK		12" BLOCK	
	BAR @ CL	BAR @ CL	BAR @ EDGE	BAR @ CL	BAR @ EDGE	BAR @ CL	BAR @ EDGE	BAR @ EDGE
#4	2'-1"	2'-1"	2'-1"	2'-1"	2'-6"	2'-1"	2'-4"	
#5	2'-11"	2'-7"	4'-0"	2'-7"	3'-10"	2'-7"	3'-8"	
#6	-	4'-5"	8'-3"	4'-5"	7'-9"	4'-5"	7'-4"	
#7	-	5'-11"	-	5'-2"	10'-7"	5'-2"	10'-0"	

NOTES:
WHEN REQUIRED SPLICE LENGTH EXCEEDS 4'-0" USE HIGH LIFT GROUTING OR USE MECHANICAL TENSION SPLICES WITH LOW LIFT GROUTING


CONCRETE SPLICE LENGTH TABLE

BAR SIZE	FOOTING OR GRADE BEAM	WALL (VERTICAL)	WALL (HORIZONTAL)	SLAB	COLUMN	BEAM (BOTTOM)	BEAM (TOP)
#3	-	1'-8"	1'-8"	1'-8"	-	-	-
#4	2'-3"	2'-3"	2'-3"	2'-3"	-	-	-
#5	2'-9"	2'-9"	2'-9"	2'-9"	2'-0"	2'-7"	3'-5"
#6	3'-4"	3'-4"	3'-4"	3'-4"	2'-5"	3'-1"	4'-1"
#7	4'-10"	4'-10"	4'-10"	4'-10"	3'-6"	4'-6"	5'-11"
#8	5'-6"	5'-6"	-	-	4'-0"	5'-2"	6'-9"
#9	-	-	-	-	4'-6"	5'-10"	7'-7"
#10	-	-	-	-	5'-1"	6'-7"	8'-6"
#11	-	-	-	-	5'-7"	7'-3"	9'-6"


- NOTES:
- WHEN BARS OF DIFFERENT SIZE ARE LAP SPLICED, THE LARGER SPLICE LENGTH SHALL BE USED.
 - BEAM TOP BAR IS DEFINED AS ANY HORIZONTAL BAR THAT HAS MORE THAN 12" OF FRESH CONCRETE BELOW THE BAR.
 - TABLE SHALL ONLY BE USED WHEN:
 - CONCRETE IS NORMAL WEIGHT
 - REINFORCEMENT STEEL IS UNCOATED
 - REINFORCEMENT STEEL MEETS ASTM A615, GRADE 60

Construction Drawings for:

Heartland Market



Craig Luebbert
Architect




24 NW Chipman 'B', 816.875.4863

SHEET NUMBER


ARCHITECTURAL PROJECT NUMBER

GENERAL
STRUCTURAL
NOTES

S001



Craig Luebbert
Architecture
24 NW Chipman 'B', 816.875.4863



Construction Drawings for:

Heartland Market



DATE ISSUED:
4/05/23

REVISIONS:


ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER


FOUNDATION
PLAN
S100



FOUNDATION PLAN
3/16" = 1'-0"



Craig Luebbert
Architecture
24 NW Chipman 'B', 816.875.4863



Construction Drawings for:

Heartland Market



DATE ISSUED:
4/05/23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER

SHEET NUMBER

FRAMING
PLAN
S200





FRAMING PLAN

3/16" = 1'-0"

NOTES:

- 1 2x6 TYP T&B - SEE 21/S400
2. TB INDICATES TRUSS BEARING ELEVATION.
- 3 (2)L3 1/2x3 1/2x5/16"
4. SNOW DRIFT (PSF)






Craig Luebert
Architecture
24 NW Chipman 'B' 816.875.4863


Construction Drawings for:
Heartland Market

DATE ISSUED:	4/05/23
REVISIONS:	
ARCHITECTURAL PROJECT NUMBER	


SHEET NUMBER
FOUNDATION AND
MASONRY DETAILS
S300




11 TYPICAL SLAB-ON-GRADE JOINTS
S300 NO SCALE




31 TYPICAL INSTALLATION OF PIPE
S300 NO SCALE (@ FOUNDATIONS)




12 ADDITIONAL SLAB-ON-GRADE REINF
S300 NO SCALE




13 DETAIL AT MAN DOOR
S300 NO SCALE




14 MASONRY WALL FTG AT ENTRY
S300 NO SCALE




24 TYPICAL BOND BEAM DETAILS
S300 NO SCALE




33 TYPICAL MASONRY WALL REINFORCEMENT DETAILS
S300 NO SCALE



43 MASONRY WALL FTG AT BUMPOUT
S300 NO SCALE



44 TYPICAL MASONRY WALL FOOTING
S300 NO SCALE



Craig Luebert
Architecture
24 NW Chipman 'B' 816.875.4863

C L A

Construction Drawings for:

Heartland Market


DATE ISSUED:
4/05/23

REVISIONS:

ARCHITECTURAL PROJECT NUMBER


SHEET NUMBER

FRAMING
DETAILS
S400




21 PARAPET SUPPORT DETAIL

S400 SCALE: NO SCALE




22 TYP TRUSS BRG AT EXT

S400 SCALE: NO SCALE




23 TYP TRUSS BRG AT EXT

S400 SCALE: NO SCALE




24 TYP TRUSS BRG AT EXT

S400 SCALE: NO SCALE




33 TYP NON-BEARING DETAIL

S400 SCALE: NO SCALE



34 TYP LINTEL DETAIL


S400 NO SCALE



NOTES:
BOTTOM PLATE OR ANGLE SHALL:
• EXTEND TO END OF BEAM WHEN NO BOLTS
• EXTEND TO END OF BEAM @ CONTROL JOINT
• STOP AT EDGE OF OPENING WHEN BOLTED AND NO CONTROL JOINT


34 TYP MASONRY BEAM/LINTEL BEARING

S400 NO SCALE



35 TYP STEEL LINTEL DETAIL

S400 NO SCALE



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/24



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI


BC PROJECT #: 22823

REVIEW SET
RECORDED: 11-20-2024

REVISION:
△ RISER REV 3-15-2024
△ CITY COM. 10-14-2024

SHEET TITLE
MECHANICAL FLOOR PLAN

M100



MECHANICAL SYMBOLS

	NEW SUPPLY DIFFUSER
	NEW RETURN AIR GRILLE
	EXHAUST GRILLE/FAN
	THERMOSTAT, MOUNTED AT 48" AFF
	DUCT-MOUNTED SMOKE DETECTOR
	MOTORIZED DAMPER/LOUVER
	NEW DUCTWORK
	SIZE OF RECTANGULAR DUCT
	SIZE OF ROUND DUCT
	FLEXIBLE DUCTWORK
	FLEXIBLE CONNECTION TO FAN
	FLOOR PLAN NOTE DESIGNATION
	S.A. SUPPLY AIR
	R.A. RETURN AIR
	EXH. EXHAUST AIR
	TRANSITION IN DUCT SIZE
	ELBOW WITH TURNING VANES
	MANUAL VOLUME DAMPER
	MANUAL VOLUME DAMPER
	MOTORIZED CONTROL DAMPER
	SUPPLY AIR DUCT UP/DOWN
	RETURN AIR DUCT UP/DOWN
	EXHAUST AIR DUCT UP/DOWN
	CHANGE IN ELEVATION UP (UP) DOWN (DN) IN DIRECTION OF FLOW
	SCHEDULED MECHANICAL EQUIPMENT

MECHANICAL PLAN NOTES:

- PROVIDE CONCEALED SUPPLY AND RETURN DUCTWORK, TYPICAL FOR ALL UNIT. ROUTE DUCTWORK UP HIGH AND SUPPORT FROM THE STRUCTURE. PROVIDE TRANSITION AS REQUIRED TO INSTALL DUCTWORK BETWEEN JOISTS.
- PROVIDE CEILING MOUNTED LAY IN SUPPLY DIFFUSER AS DETAILED.
- PROVIDE RETURN GRILLES ON BOTH SIDE OF THE MALL FOR TRANSFER OF RETURN AIR. MOUNT RETURN GRILL AT 7'-6" AFF.
- PROVIDE SINGLE PACKAGED ROOF TOP HVAC UNIT AS SHOWN ON THE PLAN. INSTALLATION OF EQUIPMENT SHALL COMPLY WITH EQUIPMENT MANUFACTURER'S INSTALLATION AND CLEARANCE REQUIREMENTS TO ALLOW FOR INSPECTION, SERVICE, REPAIR OR REPLACEMENT. FRESH AIR INTAKE OF THE ROOF TOP HVAC UNIT SHALL BE LOCATED A MINIMUM OF 10 FOOT FROM VENT THRU ROOF, FLUES AND EXHAUST FANS.
- PROVIDE CEILING MOUNTED EXHAUST FAN WITH INTEGRAL BACKDRAFT DAMPER. ROUTE DUCTWORK UP AND TERMINATE THROUGH ROOF. SUPPORT UNIT FROM STRUCTURE AS REQUIRED BY THE MANUFACTURER.
- ROUTE 10"Ø EXHAUST DUCT UP TO ROOF. PROVIDE ROOF CAP. ENSURE MIN. 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES. MIN. 10" AFF.
- PROVIDE 1 DAY PROGRAMMABLE THERMOSTAT WITH CONTROL FOR HEATING & COOLING. MOUNT 48" ABOVE THE FINISHED FLOOR.
- PROVIDE DUCT MOUNTED SMOKE DETECTOR FOR HVAC UNIT THAT ARE GREATER THAN 2000 CFM. IN COMPLIANCE WITH IMC SECTION 606 AND NFPA 72. PROVIDE REMOTE ANNUNCIATOR AND LOCATE AS PER AHJ.
- LOCATION OF WALK IN COOLER / FREEZER REMOTE CONDENSER. SUPPORT CONDENSING UNIT FROM ROOF AS DETAILED. CONNECT REFRIGERANT PIPING TO CONDENSING UNIT AS REQUIRED. RECHARGE LINES AS REQUIRED. INSTALL PIPING AS RECOMMENDED BY MANUFACTURER. VERIFY EXACT LOCATION WITH INSTALLING CONTRACTOR.
- INSTALL TYPE 1 EXHAUST HOOD OVER KITCHEN EQUIPMENT. REFER TO KITCHEN HOOD MANUFACTURER'S DRAWINGS FOR MORE INFORMATION.
- INSTALL ROOF MOUNTED EXHAUST HOOD FAN ON PRE-FABRICATED ROOF CURB AS PER MANUFACTURER SPECIFICATION. PROVIDE 40" MINIMUM CLEARANCE TO ROOF SURFACE.
- INSTALL GAS FIRED MAKE UP AIR UNIT ON PRE-FABRICATED ROOF CURB AS PER MANUFACTURER SPECIFICATION.
- LOCATION OF MANUAL FULL STATION FOR HOOD SUPPRESSION SYSTEM. COORDINATE EXACT LOCATION WITH FIRE MARSHALL.
- MAINTAIN A MIN OF 18" FROM ALL COMBUSTIBLE MATERIALS TO TYPE 1 HOOD. PROVIDE FIRE WRAPPED GREASE DUCT FROM EXHAUST FAN DOWN TO TYPE I GREASE HOOD. TRANSITION AND CONNECT AS REQUIRED. TRANSITION AND CONNECT TO KITCHEN EQUIPMENT SUPPLIED EXHAUST FAN. REFER TO GREASE DUCT DETAIL.



MECHANICAL FLOOR PLAN

SCALE: 1/4" = 1'-0"

MECHANICAL PLAN NOTES CONTINUED:

- TRANSITION AND CONNECT ROUND DUCT TO MAKE UP AIR UNIT'S MAIN SUPPLY DROPS WITH BALANCING DAMPER AS REQUIRED AND ROUTE TO SUPPLY PLENUM ON HOOD.
- ROUTE 16"Ø TYPE I GREASE DUCT UP TO KEF-1 AND CONNECT AS REQUIRED. MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES.
- ROUTE MAKE UP AIR SUPPLY DUCT DOWN FROM MAKE UP AIR UNIT. TRANSITION AND CONNECT MAKE UP AIR SUPPLY DUCT AS REQUIRED. VERIFY THE EXACT SIZE AND LOCATION OF STRUCTURE BEFORE INSTALLING DUCTWORK. MOUNT DUCT AS HIGH AS POSSIBLE.
- INTERLOCK RTU-1, RTU-2, RTU-3 AND MUA-1 AS REQUIRED TO SHUT DOWN WHEN THE FIRE SUPPRESSION SYSTEM IS ACTIVATED.
- CONNECT 8"Ø SUPPLY DUCT TO KITCHEN HOOD AC CONNECTION AND SET TO 108 CFM AS LISTED ON SHEET M200.
- REFER TO ARCHITECTURAL PLAN FOR INFORMATION ON ROOF TOP UNIT SCREENING.

MECHANICAL GENERAL NOTES:

- COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
- THIS CONTRACTOR SHALL PERFORM ALL WORK INDICATED AND/OR AS REQUIRED FOR THE PROPER INSTALLATION AND OPERATION OF THE MECHANICAL SYSTEMS.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATIONS OF DIFFUSERS.
- INSTALL ALL DUCT, PIPE, ETC. AS HIGH AS POSSIBLE.
- DUCT SIZES SHOWN ARE ACTUAL SHEET METAL SIZES AND INCLUDE AN ALLOWANCE FOR DUCT LINER WHERE APPLICABLE.
- PROVIDE FLEXIBLE CONNECTION BETWEEN DUCTWORK AND ROOFTOP UNITS, EXHAUST FANS, AND OTHER MOTORIZED EQUIPMENT.
- NO DUCT SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
- ALL MECHANICAL SYSTEMS SHALL BE BALANCED BY A CERTIFIED BALANCING CONTRACTOR. REFER TO SPECIFICATIONS FOR DETAILS.

BUILDING TEMPERATURE SET POINTS

OCCUPIED MODE ZONE SET POINTS (5° DEADBAND)

COOLING SET POINT 75°F (ADJUSTABLE), 50% RH

HEATING SET POINT 70°F (ADJUSTABLE), 50% RH

UNOCCUPIED MODE ZONE SET POINTS

COOLING SET POINT 80°F (ADJUSTABLE), 50% RH

HEATING SET POINT 65°F (ADJUSTABLE), 50% RH

THE MECHANICAL CONTRACTOR SHALL ENSURE THE SYSTEMS ARE WIRED, INTERLOCKED, PROGRAMMED CORRECTLY, AND FULLY TESTED IN ALL MODES TO ENSURE THESE REQUIREMENTS ARE MET.

THE SYSTEMS SHALL BE BALANCED BY A NEBB CERTIFIED BALANCER, AND SHALL BE STARTED BY FACTORY TRAINED PERSONNEL.

NOTES:



1. PROVIDE OUTDOOR AIR ECONOMIZER WITH STANDARD CONTROLLER, FIXED DRY BULB CONTROL, BAROMETRIC RELIEF DAMPER, CONSTANT AIR VOLUME, HINGED ACCESS DOORS, SCROLL COMPRESSORS WITH CRANKCASE HEATER, HIGH PRESSURE SWITCHES, FREEZE/STAT, HAIL GUARDS, STANDARD COOLING DOWN TO 30°F. OUTDOOR AIR DAMPER TO FULLY CLOSE W/ FAN SHUTDOWN FOR ALL UNITS.
2. EXTERNAL STATIC PRESSURE LISTED REPRESENTS STATIC PRESSURE REQUIRED FOR DUCTWORK AND DIFFUSERS OUTSIDE THE HVAC UNIT COMPLETELY INDEPENDENT OF ANY PRESSURE DROP THROUGH THE HVAC EQUIPMENT INCLUDING BUT NOT LIMITED TO FILTERS, COILS AND ECONOMIZERS. THE FAN AND MOTOR SHALL BE SIZED APPROPRIATELY TO MEET THIS DEFINITION OF EXTERNAL STATIC PRESSURE.
3. PROVIDE COMMERCIAL 7-DAY PROGRAMMABLE HEAT/COOL/AUTO CHANGE-OVER THERMOSTAT WITH ECONOMIZER OUTPUT AND BUILT IN HUMIDITY SENSOR FOR EACH UNIT. ECONOMIZER/OUTDOOR AIR DAMPER IS TO CLOSE DURING UNOCCUPIED HOURS.
4. PROVIDE 18" HIGH (AT LOWEST POINT) PRE-FABRICATED INSULATED ROOF CURB WITH SLOPE TO MATCH SLOPE OF ROOF FOR EACH UNIT.
5. PROVIDE NEW 2" MERV 8 FILTERS UPON COMPLETION OF CONSTRUCTION.
6. MECHANICAL CONTRACTOR SHALL COORDINATE ALL UNIT MOC'S OF ACTUAL INSTALLED EQUIPMENT WITH ELECTRICAL CONTRACTOR.
7. PROVIDE FACTORY MOUNTED SMOKE DETECTOR IN RETURN OF UNIT.
8. PROVIDE HOT GAS REHEAT (HUMIDITROL) OPTION FOR DEHUMIDIFICATION.

NOTES: PROVIDE CEILING GRILLE, INTEGRAL BACK DRAFT DAMPER, VARI-SPEED CONTROLLER (NEAR FAN AND ABOVE CEILING), AND WEATHER HEAD.


SUPPLY AIR UNIT	OUTSIDE AIRFLOW (CFM)	RETURN AIRFLOW	SUPPLY AIRFLOW	OA/SA	EXHAUST AIR UNIT	EXHAUST AIRFLOW (CFM)	REMARKS
RTU-1	455	2,545	3,000	15.16%	EF-1	150	
RTU-2	455	2,545	3,000	15.16%	EF-2	225	
RTU-3	230	3,770	4,000	5.75%	KEF-1	2,400	
MUA-1	1,920	0	1,920	100.00%			
TOTAL	3,060	8,860	11,920	25.67%	TOTAL	2,775	
RESULTING BUILDING PRESSURIZATION						205 CFM	

NOTES: 1. PROVIDE 455 CFM OF OUTDOOR AIR FOR RTU-1 & RTU-2 AND 230 CFM OF OUTDOOR AIR FOR RTU-3.

1. UPON ACTIVATION OF ANSUL SYSTEM, SHUT DOWN MAU-1 AND RTU-3. PROVIDE RELAYS CONTACTS, INTERLOCKS, TRANSFORMERS AND ALL ASSOCIATED WIRING TO ACCOMPLISH SEQUENCE. MAU-1 IS ALREADY WIRED TO SHUT DOWN IN HOOD CONTROL PANEL. MECHANICAL CONTRACTOR SHALL INTERLOCK RTU-1 AND RTU-2 TO ALSO SHUT DOWN.



SCALE: NONE



SCALE: NONE

M101

FIRE SYSTEM INFORMATION - JOB#5702408

FIRE SYSTEM NO	TAG	TYPE	SIZE	FLOW POINTS	INSTALLATION	
					SYSTEM	LOCATION ON HOOD
1		TANK FS	4.0/4.0/4.0	46	FIRE CABINET RIGHT	RIGHT, HOOD 1

GAS VALVE(S)

FIRE SYSTEM NO	TAG	TYPE	SIZE	SUPPLIED BY
1		SC ELECTRICAL	2.000	ECON-AIR

FIRE SYSTEM PARTS LIST KEY

FIRE SYSTEM NO	TAG	KEY NUMBER - PART DESCRIPTION	QTY BY FACTORY	QTY BY DIST
1		0 - 0 - TANK FIRE SUPPRESSION POST-DISCHARGE PROCEDURE UTILITY CABINET LABEL SHEET.	1	0
		0 - 0 - TANK FIRE SUPPRESSION MAINTENANCE GUIDE UTILITY CABINET LABEL SHEET.	1	0
		0 - 0 - 12-F28021-32144-DT-360 DUCT FIRE THERMOSTAT WITH 12 FOOT WIRE LEADS. NO, CLOSE ON TEMP RISE AT 360°F.	1	0
		0 - 0 - 87-120042-001 SECONDARY ACTUATOR VALVE (SVA) - SINGLE ACTUATOR, REQUIRES PRIMARY RELEASE ACTUATOR, TANK FIRE SUPPRESSION.	2	0
		0 - 0 - 87-120045-001 HOSE, SECONDARY ACTUATOR HOSE, 7.5' BRAIDED STAINLESS STEEL, TANK FIRE SUPPRESSION.	2	0
		0 - 0 - 87-300001-001 TANK - PRESSURIZED TANK USED FOR TANK FIRE SUPPRESSION.	3	0
		0 - 0 - 87-300030-001 PRIMARY ACTUATOR KIT (PAK) - ACTUATOR AND RELEASE SOLENOID ASSEMBLY, ONE NEEDED PER FIRE SYSTEM, SUPERVISED, TANK FIRE SUPPRESSION.	1	0
		0 - 0 - 87-300152-001 HARDWARE, SVA BOLTS, TANK FIRE SUPPRESSION.	12	0
		0 - 0 - 9055455PC PRO PRESS 1/2 PRESS X PRESS 90 ELBOW L.D.	13	0
		0 - 0 - 9097200PC PRO PRESS PC611 1/2 PRESS TEE L.D.	7	0
		0 - 0 - 98694A115 HARDWARE, DATANKLOCK LOCKING BRACKET SQUARE NUTS 5/16" ZINC, TANK FIRE SUPPRESSION.	6	0
		0 - 0 - A0034332 JUNCTION BOX FOR MANUAL PULL STATION. 1.5" DEEP BACK BOX, RED COLOR.	1	0
		0 - 0 - B1145 3/8" BLACK IRON 90 ELL.	3	0
		0 - 0 - CBI-104 CHROME PLATED PIPE FITTING 3/8" NPT TEE.	2	0
		0 - 0 - CBI-106 CHROME PLATED PIPE FITTING 3/8" NPT 90 DEGREE ELBOW.	2	0
		0 - 0 - CBI-107 CHROME PLATED PIPE FITTING 3/8" NPT UNION.	2	0
		0 - 0 - DATANKLOCK DISCHARGE ADAPTER TANK LOCKING PLATE FOR FIRE SYSTEM TANK INSTALLATION IN UTILITY CABINETS, TANK FIRE SUPPRESSION.	3	0
		0 - 0 - TANK STRAP TANK STRAP - USED FOR TANK FIRE SUPPRESSION.	9	0
		0 - 0 - TFS-UCTANKBRACKET TANK BRACKET FOR FIRE SYSTEM TANK INSTALLATION IN UTILITY CABINETS, TANK FIRE SUPPRESSION.	3	0
		0 - 0 - WK-283952-000 DISCHARGE ADAPTER, TANK FIRE SUPPRESSION.	3	0
		16 - 16 - 79210 1/2" X 3/8" NPT MALE ADAPTER, VIEGA.	9	0
		16 - 16 - DL-F NOZZLE - TANK PROTECTION APPLIANCE COVERAGE NOZZLE (INCLUDES METAL BLOW OFF CAP, LANYARD, USED WITH CHROME-PLATED PIPE)- 4 FLOW POINTS.	11	0
		26 - 26 - QSA-3/8 QUIK SEAL - 3/8" (UL).	9	0
		34 - 34 - A0034331 24VDC SINGLE ACTION MANUAL ACTUATION DEVICE (PUSH/PULL STATION) WITH PROTECTIVE COVER, ONE (1) NORMALLY OPEN CONTACT. RED COLOR.	1	0

- NOTES
- FIELD PIPE DROPS AS SHOWN
 - PIPING, ELBOWS, TEES, AND NOZZLES SUPPLIED BY CAS.
 - FIELD INSTALLED DROPS: FACTORY WILL PROVIDE QTY 2 60IN LONG PIECES OF CHROME PLATED PIPING SHIPPED LOOSE TO BE FIELD-INSTALLED.
 - SHIP LOOSE DROPS: FACTORY WILL PROVIDE THE EXACT CHROME PIPE LENGTH NEEDED SHIPPED LOOSE TO BE FIELD-INSTALLED.
 - RELOCATE NOZZLES IF FLOW PATTERN IS BLOCKED BY SHELVEING, SALAMANDERS, ETC.
 - OVERLAPPING COVERAGE SHALL NOT BE USED ON ANY APPLIANCE WITH AN OBSTRUCTION.
 - IF APPLICABLE, EXTENDED PRE-PIPED DROPS ARE SHIPPED LOOSE.
 - FACTORY PIPING EXTENDS A MAXIMUM OF 6" ABOVE THE TOP OF THE HOOD.
 - APPLIANCE DIMENSIONS LISTED REPRESENT THE COOKING SURFACE SIZE, NOT THE OVERALL APPLIANCE SIZE.
 - THIS FIRE SYSTEM COMPLIES WITH U.L. 300 REQUIREMENTS.

- DL-F NOZZLE PART NUMBER REPLACES 3070-3/8H-10-SS
- JOB #: 5702408.
- JOB NAME: HEARTLAND MARKET - LEE'S SUMMIT.



SYSTEM SIZE: TANK-SP-3 TOTAL FP REQUIRED: 46.
HOOD # 1 12' 0.00' LONG x 54' WIDE x 24" HIGH.
RISER # 1 SIZE: 16" DIA.
HOOD # 1 METAL BLOW-OFF CAPS INCLUDED.

- HEAVY-DUTY APPLIANCES (RATED 600°F) WILL REQUIRE AN ADDITIONAL DOWNSTREAM FIRESTAT IN THE EVENT THAT THE DUCTWORK CONTAINS ANY HORIZONTAL RUNS OVER 25 FT IN LENGTH.
- MEDIUM TO LIGHT-DUTY APPLIANCES (RATED 450°F) WILL NOT REQUIRE ANY ADDITIONAL DOWNSTREAM DETECTION.

LEGEND - FIRE CABINET TANK SYSTEM

- 4 GALLON TANK.
- PRIMARY ACTUATOR RELEASE.
- SECONDARY ACTUATOR RELEASE.
- PRESSURE SUPERVISION SWITCH.
- PRIMARY HOSE ASSEMBLY.
- SECONDARY HOSE ASSEMBLY.
- REMOTE MANUAL ACTUATION DEVICE.

INCLUDES: FIELD INSTALLATION AND HOOKUP DURING NORMAL BUSINESS HOURS BY CERTIFIED INSTALLERS ONLY IN THE LOCATION NOTED ABOVE. TWO SITE VISITS ONLY (ONE VISIT TO SET PULL STATION & SYSTEM HOOKUP AND ONE VISIT FOR ONE TEST) ADDITIONAL VISITS WILL RESULT IN ADDITIONAL CHARGES). ONE MECHANICAL OR ELECTRICAL GAS VALVE PER SYSTEM AT A MAXIMUM SIZE OF 2" PERMIT, AND SYSTEM TEST. EXCLUDES: UNION LABOR & PREVAILING WAGE CLAUSE & WAGES WILL BE ADDED IF APPLICABLE. GAS VALVE INSTALLATION, ELECTRICAL HOOKUP AND CONNECTIONS, HANGING OF FIRE CABINET, SHUNT TRIP, HANDHELD EXTINGUISHER(S), ON-SITE RE-PIPING DUE TO EQUIPMENT LAYOUT CHANGES.



GAS VALVE SIZING											
TYPE	SIZE	VOLTAGE	MIN. INLET PRESSURE	MAX. INLET PRESSURE	FLOW AT 1 IN.W.C. DROP NATURAL GAS	FLOW AT 1 IN.W.C. DROP PROPANE	DIM "A"	DIM "B"	DIM "C"	DIM "D"	DIM "E"
GAS VALVE FOR FSP	ELECTRICAL	2"	120 VAC	0 PSI (0 IN.W.C.)	5 PSI (138 IN.W.C.)	2,340,000 BTU/HR	7-5/8"	6-3/8"	7-1/4"	7-13/16"	15-5/8"


ALL GAS VALVES/STRAINERS

PROPER CLEARANCE MUST BE PROVIDED IN ORDER TO SERVICE THE STRAINERS A MINIMUM OF 4" CLEARANCE DISTANCE MUST BE PROVIDED AT THE BACK OF THE STRAINER. CUSTOMER MUST VERIFY BTU CONSUMPTION AS WELL AS PRESSURE RATING SPECIFIC GRAVITY OF NATURAL GAS = 0.54, SPECIFIC GRAVITY OF LP = 1.52

CALCULATIONS

TO CALCULATE GAS FLOW FOR OTHER THAN 1 IN.W.C. PRESSURE DROP NEW BTU/HR = (BTU/HR AT 1 IN.W.C. PRESSURE DROP) X NEW PRESSURE DROP³

TO CALCULATE GAS FLOW FOR OTHER THAN 0.54 SPECIFIC GRAVITY NEW BTU/HR = (BTU/HR AT 0.54) X (0.54 / NEW SPECIFIC GRAVITY)³



REVISIONS	
DESCRIPTION	DATE



CAPTIVE

ENGINEERS INCORPORATED

5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

PE COA #2009003629



Heartland Market - Lee's Summit
LEES SUMMIT, MO, 64082

PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI

DATE: 10/25/2022

DWG.#:
5702408

DRAWN BY: michael.co

SCALE:
3/4" = 1'-0"

MASTER DRAWING

SHEET NO.
2

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:
RISER REV 3-15-2024
CITY COM. 10-14-2024

SHEET TITLE
HOOD DETAILS

M201

EXHAUST FAN INFORMATION – JOB#5702408

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	MANUFACTURER	CFM	ESP	RPM	MOTOR ENCL	HP	BHP	PHASE	VOLT	FLA	DISCHARGE VELOCITY	WEIGHT (LBS)	SONES
1	KEF-1	1	EADUI80H	ECON-AIR	2400	1.800	1318	ODP,PREMIUM	3.000	1.5120	3	208	9.5	554 FPM	200	18.4

MUA FAN INFORMATION – JOB#5702408

FAN UNIT NO	TAG	QTY	FAN UNIT MODEL #	BLOWER	HOUSING	MIN CFM	DESIGN CFM	ESP	RPM	MOTOR ENCL	HP	BHP	PHASE	VOLT	FLA	MCA	MOCP	WEIGHT (LBS)	SONES
2	MAU-1	1	EA1-D.250-1SD	ISMF-1-MOD	A1-D.250	1000	1920	0.500	2023	ODP,PREMIUM	2.000	1.2880	3	208	6.1	7.7A	15A	510	19.9

GAS FIRED MAKE-UP AIR UNIT(S)

FAN UNIT NO	TAG	INPUT BTUS	OUTPUT BTUS	TEMP RISE	REQUIRED INPUT GAS PRESSURE	GAS TYPE	BURNER EFFICIENCY(%)
2	MAU-1	142989	131550	66°F	7 IN. W.C. – 14 IN. W.C.	NATURAL	92

FAN OPTIONS

FAN UNIT NO	TAG	QTY	DESCRIPTION
1	KEF-1	1	GREASE BOX
		1	EXHAUST FAN HEAT BAFFLE
		1	FAN BASE CERAMIC SEAL – INSTALLED AT PLANT – FOR GREASE DUCTS
		1	UNIT MOUNTED VFD FOR USE WITH ECPM03
		1	VFD MOUNTING BRACKET FOR DU/DR 180 – 200
		1	2 YEAR PARTS WARRANTY
2	MAU-1	1	INLET PRESSURE GAUGE, 0-35"
		1	MANIFOLD PRESSURE GAUGE, –5 TO 15" WC
		1	MOTORIZED BACKDRAFT DAMPER FOR A1-D HOUSING – MEETS AMCA CLASS 1A RATING
		1	SEPARATE 120V WIRING PACKAGE (REQUIRED AND USED ONLY FOR DCV OR PREWIRE WITH VFD) – THREE PHASE ONLY
		1	LOW FIRE START
		1	SIZE 1 TEMPERED COMMERCIAL DOWN DISCHARGE FOR DIRECT DRIVE AHUS
		1	UNIT MOUNTED VFD FOR USE WITH ECPM03
		1	2 YEAR PARTS WARRANTY



FAN ACCESSORIES

FAN UNIT NO	TAG	EXHAUST			SUPPLY		
		GREASE CUP	GRAVITY DAMPER	WALL MOUNT	SIDE DISCHARGE	GRAVITY DAMPER	MOTORIZED DAMPER
1	KEF-1	YES					
2	MAU-1						YES

CURB ASSEMBLIES

NO	ON FAN	TAG	WEIGHT	ITEM	SIZE
1	# 1	KEF-1	41 LBS	CURB	26,500"W X 26,500"L X 20,000"H ALONG LENGTH, RIGHT VENTED HINGED.
2	# 2	MAU-1	63 LBS	CURB	21,000"W X 71,000"L X 15,000"H ALONG WIDTH, RIGHT INSULATED.

FAN #1 EADUI80H – EXHAUST FAN (KEF-1)




- FEATURES:**
- DIRECT DRIVE CONSTRUCTION (NO BELTS/PULLEYS).
 - ROOF MOUNTED FANS.
 - RESTAURANT MODEL.
 - UL705 AND UL762 AND ULC-S645
 - VARIABLE SPEED CONTROL.
 - INTERNAL WIRING.
 - THERMAL OVERLOAD PROTECTION (SINGLE PHASE).
 - HIGH HEAT OPERATION 300°F (149°C).
 - GREASE CLASSIFICATION TESTING.
 - NEMA 3R SAFETY DISCONNECT SWITCH.

NORMAL TEMPERATURE TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING AIR AT 300°F (149°C) UNTIL ALL FAN PARTS HAVE REACHED THERMAL EQUILIBRIUM, AND WITHOUT ANY DETERIORATING EFFECTS TO THE FAN WHICH WOULD CAUSE UNSAFE OPERATION.

ABNORMAL FLARE-UP TEST
EXHAUST FAN MUST OPERATE CONTINUOUSLY WHILE EXHAUSTING BURNING GREASE VAPORS AT 600°F (316°C) FOR A PERIOD OF 15 MINUTES WITHOUT THE FAN BECOMING DAMAGED TO ANY EXTENT THAT COULD CAUSE AN UNSAFE CONDITION.


OPTIONS

- GREASE BOX.
- EXHAUST FAN HEAT BAFFLE.
- FAN BASE CERAMIC SEAL – INSTALLED AT PLANT – FOR GREASE DUCTS.
- UNIT MOUNTED VFD FOR USE WITH ECPM03.
- VFD MOUNTING BRACKET FOR DU/DR 180 – 200.
- 2 YEAR PARTS WARRANTY.




PITCHED CURBS ARE AVAILABLE FOR PITCHED ROOFS.

SPECIFY PITCH:
EXAMPLE: 7/12 PITCH = 30° SLOPE.



SUPPLY SIDE HEATER INFORMATION

WINTER TEMPERATURE = 9°F. TEMP. RISE = 66°F.
BTUS CALCULATED OFF ACTUAL AIR DENSITY.
OUTPUT BTUS AT ALTITUDE OF 0.0 FT. = 135380.
INPUT BTUS AT ALTITUDE OF 0.0 FT. = 147152.
OUTPUT BTUS AT ALTITUDE OF 792 FT. = 131550.
INPUT BTUS AT ALTITUDE OF 792 FT. = 142989.




DIRECT FIRED (DF) PROFILE PLATE ASSEMBLY

DIRECT FIRED PROFILE PLATE SPECIFICATIONS:
DESCRIPTION:
DIRECT FIRED BURNERS SHALL HAVE PATENTED (US PATENT NO. US662923B2), SELF-ADJUSTING PROFILE PLATES DESIGNED TO ENSURE PROPER AIR VELOCITY AND PRESSURE DROP ACROSS THE BURNER. PROFILE PLATES SHALL ALLOW BURNERS TO ACHIEVE CLEAN COMBUSTION BY LIMITING BY-PRODUCT LEVELS TO A MAXIMUM OF 50PPM OF CARBON MONOXIDE (CO) AND 0.5PPM OF NITROGEN DIOXIDE (NO2). DIRECT FIRED UNITS SHALL BE CONFIGURED WITH THE BLOWER MOUNTED DOWNSTREAM OF THE BURNER. THIS ARRANGEMENT WILL ENSURE A CONSISTENT AIRFLOW, REGARDLESS OF INLET AIR TEMPERATURE.

APPLICATION:
SPRING-LOADED BURNER PROFILE PLATES ARE ENGINEERED TO AUTOMATICALLY REACT TO THE MOMENTUM OF A FRESH AIR STREAM, WITHOUT THE NEED FOR ANY MOTORS OR ACTUATORS TO MECHANICALLY ADJUST THEM. WITH THIS FEATURE, ALL OF UNITS ARE DESIGNED FOR DEMAND CONTROL VENTILATION (DCV) REQUIREMENTS.

CERTIFICATIONS:
ALL PROFILE PLATE ASSEMBLIES SHALL BE INCLUDED IN THE DF UNIT'S ETL LISTING AND COMPLY WITH COMBINED SAFETY STANDARDS ANSI Z89.4 AND CSA 3.7 (NON-RECIRCULATING DF HEATERS) AND ANSI Z89.18 (RECIRCULATING DF HEATERS).



GENERAL CONSTRUCTION:
-PROFILE PLATES SHALL BE FORMED FROM G90 GALVANIZED STEEL.
-PROFILE PLATES SHALL VARY IN SIZE PER UNIT.
-PROFILE PLATES SHALL BE MOUNTED ALONG THE SAME PLANE AS THE DISCHARGE OF THE BURNER.
-DESIGN SHALL INCORPORATE PROPERLY TORQUED, PERMANENTLY MOUNTED SPRING HINGES.
-SPRING HINGES SHALL BE MADE FROM PLATED STEEL.




ROOF OPENING 2" SMALLER THAN CURB DIMENSION.

- FAN #2 EA1-D.250-1SD – HEATER (MAU-1)
1. DIRECT GAS FIRED HEATED MAKE UP AIR UNIT WITH 15" MIXED FLOW DIRECT DRIVE FAN.
 2. INTAKE HOOD WITH EZ FILTERS.
 3. DOWN DISCHARGE – AIR FLOW RIGHT –> LEFT.
 4. GAS PRESSURE GAUGE, 0-35", 2.5" DIAMETER, 1/4" THREAD SIZE.
 5. GAS PRESSURE GAUGE, –5 TO +15 INCHES WC, 2.5" DIAMETER, 1/4" THREAD SIZE.
 6. MOTORIZED BACK DRAFT DAMPER 16" X 18" FOR SIZE 1 STANDARD & MODULAR HEATER UNITS W/EXTENDED SHAFT, STANDARD GALVANIZED CONSTRUCTION, 3/4" REAR FLANGE, LOW LEAKAGE, TFB202S ACTUATOR INCLUDED.
 7. SEPARATE 120VAC WIRING PACKAGE FOR MAKE-UP AIR UNITS. OPTION MUST BE SELECTED WHEN MOUNTING VFD IN PREWIRE PANEL OR WITH DCV PACKAGE. PROVIDES SEPARATE 120VAC INPUT TO SUPPLY FAN. THIS 120V SIGNAL MUST BE RUN BY ELECTRICIAN FROM DCV TO MUA SWITCH.
 8. LOW FIRE START. ALLOWS THE BURNER CIRCUIT TO ENERGIZE WHEN THE MODULATION CONTROL IS IN A LOW FIRE POSITION.
 9. DOWN DISCHARGE CONSTRUCTION FOR SIZE 1 DIRECT DRIVE AHUS.
 10. UNIT MOUNTED VFD FOR USE WITH ECPM03.
 11. HINGED DOUBLE WALL INSULATED DOOR ASSEMBLY (BURNER/BLOWER SECTION).
 12. 2 YEAR PARTS WARRANTY.


NOTE: SUPPLY DUCT MUST BE INSTALLED TO MEET SMACNA STANDARDS. A MINIMUM STRAIGHT DUCT LENGTH MUST BE MAINTAINED DOWNSTREAM OF UNIT DISCHARGE AS OUTLINED IN AMCA PUBLICATION 201. WHEN USING RECTANGULAR DUCTWORK, ELBOWS MUST BE RADIUS BACK WITH TURNING VANES. FLEXIBLE DUCTWORK AND SQUARE THROAT/SQUARE BACK ELBOWS SHOULD NOT BE USED. ANY TRANSITION AND/OR TURNS IN THE DUCTWORK WILL CAUSE SYSTEM EFFECT. SYSTEM EFFECT WILL DRASTICALLY INCREASE STATIC PRESSURE AND REDUCE AIRFLOW. DO NOT RELY ON UNIT TO SUPPORT DUCT IN ANY WAY. FAILURE TO PROPERLY SIZE DUCTWORK MAY CAUSE SYSTEM EFFECTS AND REDUCE PERFORMANCE OF THE EQUIPMENT.
SUGGESTED STRAIGHT DUCT SIZE IS 14" x 14".



HINGE KIT INSTALLATION



OPEN POSITION




PARTS INCLUDED

- 2 - FAN PLATES (LEFT & RIGHT)
- 2 - CURB PLATES (LEFT & RIGHT)
- 2 - 3/8"-16 WHIZ BOLTS
- 6 - 3/8"-16 WHIZ NUTS
- SHEET METAL SCREWS
- 24 - # 14 X 3/4" SCREWS

HINGE KIT FIELD INSTALLATION


STEP 1)

ASSEMBLE FAN PLATE WITH CURB PLATE AS SHOWN ON PIC. 1 AND PIC. 2 (IF PARTS ARE NOT ASSEMBLED).




STEP 2)

SEE DETAIL "A" FOR POSITIONING FAN PLATE ON FAN BASE. LINE UP FAN BASE EDGE TO INSIDE EDGE OF FAN PLATE AS SHOWN ON PIC. 3.



STEP 3)

SCREW THE FAN PLATE TO THE FAN BASE USING (2) # 14 X 3/4" LG. SHEET METAL SCREWS. NOTE: IF THE SCREWS HIT THE CURB, THEN RUN THE SCREWS FROM INSIDE THE FAN BASE, ALWAYS BE SURE THAT SCREWS DO NOT INTERFERE WITH CURB WHEN FAN SWINGS SEE PIC. 4.



STEP 4)

SCREW THE CURB PLATE TO THE CURB USING (2) # 14 X 3/4" LG. SHEET METAL SCREWS. TIGHTEN NUT AND BOLT ASSEMBLY, ENSURE FAN SWINGS PROPERLY.

REVISIONS	
DESCRIPTION	DATE

CAPTIVE

www.captiveair.com

Air Solutions

1329 East Kemper Rd., Ste. 4210, Cincinnati, OH 45246 PHONE: (513) 960-5555 EMAIL: reg120@captair.com

Heartland Market – Lee's Summit
LEES SUMMIT, MO, 64082

DATE: 10/25/2022

DWG.#:
5702408

DRAWN BY: michael.co

SCALE:
3/4" = 1'-0"

MASTER DRAWING

SHEET NO.
3

BC
ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

△ RISER REV 3-15-2024

△ CITY COM. 10-14-2024

SHEET TITLE
HOOD DETAILS

M202

M203



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/24



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI


BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:
△ RISER REV 3-15-2024
△ CITY COM. 10-14-2024

SHEET TITLE
WASTE & VENT PLAN

P100



NOTE:

REFER TO SANITARY WASTE
AND VENT RISER DIAGRAM
FOR ALL BRANCH PIPE
SIZES.

PLUMBING PLAN NOTES:

- REFER TO CIVIL PLAN FOR CONTINUATION OF 4" SANITARY WASTE PIPING. MAINTAIN MINIMUM 30" COVER.
- ROUTE 4" GREASE PIPING OUTSIDE OF THE FOUNDATION WALL AND CONNECT TO GREASE INTERCEPTOR. MAINTAIN MINIMUM 30" COVER.
- 2" VENT MINIMUM 24" BELOW GRADE.
- LOCATION OF 4" VTR. VERIFY 10' CLEARANCE FROM ALL OUTDOOR AIR INTAKES. SEAL PENETRATION WEATHERTIGHT.
- ROUTE (3) SEPARATE 1-1/2" DRAINS FROM 3-COMPARTMENT SINK TO FLOOR SINK WITH AIR GAPS. LOCATE FLOOR SINK IN AN ACCESSIBLE LOCATION.
- ROUTE DRAIN FROM ICE MACHINE / COFFEE MACHINE & BEVERAGE DISPENSER TO FLOOR SINK WITH AIR GAP, AND PER THE MANUFACTURERS REQUIREMENTS. ROUTE CONDENSATE SEPARATELY TO FLOOR SINK.
- PROVIDE 1" CONDENSATE DRAIN FROM THE WALK IN COOLER / FREEZER EVAPORATOR TO THE FLOOR SINK. DISCHARGE THROUGH AN AIR GAP. SLOPE CONDENSATE DRAIN A MINIMUM OF 1/4" PER FOOT. HOLD EXPOSED CONDENSATE DRAIN IN WALK IN COOLER AS HIGH AS POSSIBLE. COORDINATE WITH ELECTRICAL FOR HEAT TRACING IN FREEZER.
- PROVIDE TRAP SEAL ON FLOOR DRAINS SUSCEPTIBLE TO DRYING OUT.
- PROVIDE WATER HEATER T&P DRAIN PIPE. ROUTE DRAIN PIPE DOWN AND DISCHARGE TO MOP SINK.
- NO COMBUSTIBLE MATERIALS WITHIN 18" OF TYPE I HOOD.
- ROUTE 1" CONDENSATE DRAIN FROM ROOF TOP UNIT TO NEAREST ROOF DRAIN / SCUPPER AS REQUIRED AND AS DETAILED.
- ROUTE DRAIN FROM RPZ BFP TO FLOOR SINK DRAIN WITH AN AIR GAP.
- ROUTE STORM DRAIN PIPE DOWN TO BELOW FLOOR, PROVIDE CLEANOUT AT BASE OF RISER.
- SEE CIVIL FOR CONTINUATION OF STORM DRAIN PIPING. MAINTAIN 30" COVER.
- INSTALL DOWN SPOUT 18" ABOVE GRADE. SEAL PENETRATION WEATHER TIGHT.



WASTE & VENT PLAN

SCALE: 1/4" = 1'-0" FFE = 981.10'

PLUMBING GENERAL NOTES:

- INSTALL ALL PIPE, ETC. AS HIGH AS POSSIBLE.
- COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
- REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATIONS AND MOUNTING HEIGHTS OF FIXTURES.
- REFER TO ARCHITECTURAL & STRUCTURAL DRAWINGS FOR REQUIREMENTS FOR SUPPORTING PIPING, EQUIPMENT, ETC. FROM THE STRUCTURE. PROVIDE ADDITIONAL STEEL AS REQUIRED TO PROPERLY SUPPORT SYSTEMS FROM THE STRUCTURE.
- PROVIDE 1" SCHEDULE 40 PVC CONDENSATE DRAIN PIPE FOR EACH ROOFTOP UNIT LAID DIRECTLY ON ROOF TO NEAREST ROOF DRAIN. PROVIDE WATER TRAP AND CLEAN OUTS AS DETAILED. SECURE PVC PIPE TO DRAIN WITH NYLON STRAP.
- NO PIPING SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
- CONTRACTOR TO TEST WATER PRESSURE ON SITE AND PROVIDE PRESSURE REDUCING VALVE ON WATER SERVICE IF PRESSURE IS OVER 80 PSI.

PLUMBING FIXTURE BRANCH PIPING SCHEDULE

FIXTURE	WASTE	VENT	CW	HW
WATER CLOSET (TANK TYPE)	4"	2"	1/2"	-
LAVATORY	1-1/4"	1-1/4"	1/2"	1/2"
HAND SINK				
MOP BASIN	2"	2"	3/4"	3/4"
FLOOR DRAIN	2"	2"	-	-
FLOOR SINK	3"	2"	-	-
FP WALL HYDRANT	-	-	3/4"	-

NOTE: INDIVIDUAL VENTS FOR FIXTURES ON PLANS AND RISER DIAGRAMS HAVE BEEN INCREASED WHERE HORIZONTAL VENT LENGTH IS IN EXCESS OF THE MAXIMUM DISTANCE INDICATED BY THE CODE.

PLUMBING DRAINAGE CALCULATIONS

FIXTURE	QUANTITY	FU	TOTAL FU
WATER CLOSET	3	4	12
LAVATORIES	4	1	4
URINAL	2	4	8
HAND SINK	1	1	1
3 COMP. SINK	1	2	2
MOP SINK	1	2	2
FLOOR DRAIN	5	2	10
FLOOR SINK	7	2	14
TOTAL			53

VENT MAINS - 4"

WASTE MAIN - 4"

* = COMBINATION WASTE & VENT DRAIN

GREASE INTERCEPTOR CALCULATIONS

Reference No. 45226

Project Name: Heartland Market

Step 1: Flow rate to grease interceptor

Fixture flow rate: (cu in / 231) = gal x 0.75 / 2 min = 2 min flow rate

NAME	TYPE	DIMENSIONS	QTY	CU IN	FLOW RATE
3CS	3 Compartment Sink	21" x 21" x 14" (3)	1	18,522	30 GPM
FD	Floor Drain	N/A	1	N/A	N/A
MB	Mop Basin	24" x 24" x 10"	1	5,760	9.35 GPM

Total

39.35 GPM

Step 2: Grease Production

Number of Seats x 4 turns per seat x Grease Production Value x Days between pump-out = Grease output

Number of seats in facility: 16

Grease production value: 0.025 lbs per serving (Convenience Store: Medium / No flatware)


Days between pump-outs: 90 days

16 x 4 x 0.025 x 90 = 144 lbs of FOG

SCHIER MODEL

GB-50

Description: Polyethylene Grease Interceptor
Dimensions: Length: 37", Width: 32.25", Height: 28.5"
Flow Rates/Grease Capacities: 50 GPM / 439.5 lbs
Liquid Capacity: 65 gal



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/24



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023


REVISION:

△ RISER REV 3-15-2024

△ CITY COM. 10-14-2024

SHEET TITLE
WATER & GAS PLAN

P101



PLUMBING PLAN NOTES:

- REFER TO CIVIL PLAN FOR CONTINUATION OF DOMESTIC WATER LINE. MAINTAIN 48" MINIMUM COVER.
- PROVIDE NEW DOMESTIC WATER LINE WITH SHUT OFF VALVE AND REDUCED PRESSURE ZONE BACKFLOW PREVENTER INSIDE OF THE BUILDING. INSTALL 24" A.T.F. & 6" FROM WALL. ROUTE DRAIN FROM RPZ BFP TO FLOOR SINK DRAIN WITH AN AIR GAP.
- PROVIDE ELECTRIC WATER HEATER MOUNTED ABOVE MOP BASIN. MAKE HOT AND COLD WATER PIPING CONNECTIONS THROUGH DIELECTRIC UNIONS. PROVIDE AND INSTALL ALL HARDWARE AND APPURTENANCES FOR COMPLETE INSTALLATION PER APPLICABLE CODES AND MANUFACTURER'S RECOMMENDATIONS. PROVIDE THERMAL EXPANSION TANK.
- ROUTE PIPING ON INTERIOR SIDE OF WALL FOR FREEZE PROTECTION.
- ROUTE 3/4" CW DOWN TO FREEZE PROOF WALL HYDRANT MOUNTED AT 18" ABOVE GRADE. SEAL PENETRATION WEATHERTIGHT.
- CONNECT HOT WATER REQIRC. PIPING BACK TO WATER HEATER AS REQUIRED. REFER TO RISER DIAGRAM FOR MORE INFORMATION.
- COORDINATE WITH GAS COMPANY FOR INSTALLATION OF A METER WITH CAPACITY FOR 683 CFH @ 7" W.C. ROUTE PIPING UP INSIDE THE EXTERIOR WALL. ALL CONCEALED JOINTS ARE TO BE WELDED OR USE FITTINGS APPROVED FOR CONCEALED JOINTS. VERIFY ALL EQUIPMENT GAS CAPACITIES AND OPERATING PRESSURE PRIOR TO INSTALLATION OF ANY PIPING.
- INSTALL GAS PIPING ON ROOF. SUPPORT AS REQUIRED AND AS DETAILED.
- CONNECT GAS PIPING TO ROOF TOP UNIT AS DETAILED AND PER THE MANUFACTURERS INSTRUCTIONS.
- PROVIDE RPZ BACK FLOW PREVENTER FOR CONNECTION TO FOUNTAIN SODA SYSTEM. NO COPPER PIPING IS ALLOWED DOWNSTREAM OF BACK FLOW PREVENTER TO CARBONATOR & SODA SYSTEM.



STORE - DOMESTIC WATER & NATURAL GAS PLAN


SCALE: 1/4" = 1'-0"

PLUMBING FIXTURE WATER COUNT							
FIXTURE	QUANTITY	CM FU	CM TOTAL FU	HM FU	HM TOTAL FU	COMBINED FU	COMBINED TOTAL FU
WATER CLOSET	3	5	15	0	0	5	15
URINAL	2	5	10	0	0	5	10
LAVATORIES	4	1.5	6	1.5	6	2	8
HAND SINK	1	1.5	1.5	1.5	1.5	2	3
3 COMP SINK	1	2.25	2.25	2.25	2.25	3	3
MOP SINK	1	2.25	2.25	2.25	2.25	3	3
ICE & BEV. DISPENSER	3	0.5	1.5	0	0	0.5	1.5
COFFEE MACHINE	1	0.25	0.25	0	0	0.25	0.25
BLENDER	1	0.25	0.25	0	0	0.25	0.25
FP WALL HYDRANT	2	2.5	5	0	0	2.5	5
			44 FU		12 FU		48 FU
COLD WATER MAIN - 1-1/4" HOT WATER MAIN - 3/4"							

PEX PIPING REQUIREMENTS

PIPE SIZES GIVEN ON THE DRAWINGS ARE NOMINAL COPPER PIPE SIZE. IF PEX PIPING IS USED, INCREASE PEX PIPING ONE SIZE ABOVE LISTED SIZES AS REQUIRED TO EQUAL OR EXCEED COPPER PIPE INSIDE DIAMETER.

GAS DEMAND SCHEDULE			
EQUIPMENT		GAS INPUT (BTU/H)	
SN	ITEM	NEW	EXISTING
1	ROOF TOP UNIT -1	180,000	
2	ROOF TOP UNIT -2	180,000	
3	ROOF TOP UNIT -3	180,000	
4	MAKE UP AIR UNIT -1	143,000	
TOTAL BTU/HR		683,000	0
NEW TOTAL BTU/HR (EXISTING AND NEW)		683,000	
NEW TOTAL CFH (EXISTING AND NEW)		683	
MAXIMUM DEVELOPMENT LENGTH >		125FT	
MINIMUM SIZE OF GAS LINE REQUIRED		2" DIA.	
NOTE GAS LINE SIZED AS PER TABLE 402.4(2) OF IFGC FOR PRESSURE OF 7" W.C AND SPECIFIC GRAVITY OF NATURAL GAS TO BE 0.6			



**ENGINEERS
INCORPORATED**
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/24



PLUMBING FIXTURE SCHEDULE:






<u>HWC</u>	HANDICAP WATER CLOSET: TOTO, #CST144EL/R/N, "DRAKE CLOSE COUPLED TOILET", 1.28 GALLON FLUSH, 16-1/2" HIGH ELONGATED BOWL, FLOOR MOUNTED, FLOOR OUTLET, TANK TYPE, VITREOUS CHINA, SIPHON-JET ACTION, #SCB34 OPEN FRONT SEAT WITH CHECK HINGE AND LESS COVER, CHROME PLATED ANGLE STOP AND RISER. HANDLE ON WIDE SIDE OF FIXTURE.
<u>WC</u>	WATER CLOSET: TOTO, #CST144S, "DRAKE CLOSE COUPLED TOILET", 1.6 GALLON FLUSH, ELONGATED BOWL, FLOOR MOUNTED, FLOOR OUTLET, TANK TYPE WITH LOCKING LID, VITREOUS CHINA, SIPHON-JET ACTION, #SCB34 OPEN FRONT SEAT WITH CHECK HINGE AND LESS COVER, CHROME PLATED ANGLE STOP AND RISER.
<u>U1</u>	URINAL, WALL HUNG: TOTO, #UT447.01, VITREOUS CHINA, WASH OUT, WALL HUNG URINAL WITH 3/4" TOP SPUD, #TMUNNC-12 FLUSH VALVE, FLOOR MOUNTED FIXTURE SUPPORT. SET RIM HEIGHT PER ARCHITECTURAL DRAWINGS.
<u>LI</u>	HANDICAP LAVATORY, WALL HUNG: TOTO #LT307, 20"x 18", VITREOUS CHINA, FRONT OVERFLOW, DELTA #501 FAUCET WITH SINGLE METAL LEVER FAUCET, OFFSET GRID ELBOW DRAIN AND 1-1/4" TAILPIECE, CHROME PLATED CAST BRASS P-TRAP WITH CLEANOUT (MOUNTED PARALLEL WITH WALL), CHROME PLATED LOOSE KEY ANGLE STOPS AND RISERS, FLOOR MOUNTED CONCEALED ARM LAVATORY SUPPORT, INSULATE EXPOSED DRAIN, WATER SUPPLIES, AND VALVES WITH FROWRAP SEAMLESS MOLDED CLOSED CELL VINYL INSULATION.
<u>* HS</u>	HAND SINK: ELKAY GHS-1716-C STAINLESS STEEL HAND SINK, T" BACKSPASH, FURNISHED COMPLETE WITH WALL HANGER, INTEGRAL SUPPORT BRACKETS, LK-499CHROME PLATED GOOSENECK SPOUT FAUCET WITH AERATOR, LK-8 DRAIN, LK-500 P-TRAP WITH CLEANOUT, WASTE ARM TO WALL, AND WALL FLANGE. PROVIDE CHROME PLATED ANGLE STOPS AND RISERS.
<u>MB</u>	MOP BASIN: FIAT, #MSB-2424, MOLDED STONE MOP BASIN, 2" DRAIN, 24"x 24" BASIN, VINYL BUMPER GUARD, STERN WILLIAMS #TT-10-VB FAUCET, SPRINGS, CHECKS, VACUUM BREAKER, INTEGRAL STOPS, WALL BRACE & PAIL HOOK, WALL BRACKET WITH 30" HOSE.
<u>FD</u>	FLOOR DRAIN: SIOUX CHIEF, #842, PVC FLOOR DRAIN WITH ADJUSTABLE TOP AND CAST BRASS STRAINER. PROVIDE WITH #2692 QUAD CLOSE TRAP SEAL DEVICE.
<u>FD1</u>	FLOOR DRAIN: JR SMITH, #2005-F37, CAST IRON FLOOR DRAIN WITH RECESSED 6" NIKALOY STRAINER. PROVIDE WITH #2692 QUAD CLOSE TRAP SEAL DEVICE.
<u>FS</u>	FLOOR SINK: SIOUX CHIEF, #861 SQUARE PVC FLOOR SINK WITH STAINLESS STEEL MESH DEBRIS SCREEN, PVC HALF OPEN STRAINER.
<u>HWH</u>	HOT WATER HEATER: AO SMITH #DEL-40, 40 GALLON STORAGE, 208 VOLT, 1 PHASE, SKN ELEMENT, NON SIMULTANEOUS, SINGLE ELEMENT OPERATION, 34 GALLON RECOVERY RATE, ASME TEMPERATURE AND PRESSURE RELIEF VALVE. PROVIDE HOLD RITE 50-SVHP-A WATER HEATER SHELF.
<u>ET</u>	HOT WATER EXPANSION TANK: AMTROL, #5T-5, 2 GALLON EXPANSION TANK WITH DIAPHRAGM.
<u>RCP</u>	HOT WATER RECIRCULATING PUMP: BELL & GOSSETT, #SERIES NBF-10, 3 GPM @ 7 FT. HEAD, 1/12 HP, 120 VOLT, WITH HONEYWELL #L6006C1018 AQUASTAT & TAGO #265-3 7 DAY DIGITAL TIMER, 120° - 125°F, 1/2" Ø PIPE.
<u>* 3CS</u>	3-COMPARTMENT SINK: REGENCY 600531014216 66" 16-GAUGE STAINLESS STEEL SINK, (3) 10"x14"x12" DEEP BOWLS, LEFT AND RIGHT 16" DRAINBOARDS, PROVIDE (3) 1-1/2" ROTARY OPERATED DRAINS WITH TAILPIECES, 2" WASTE MANIFOLD PIPING, CHROME PLATED ANGLE STOPS AND RISERS, WALL MOUNTED PRE RINSE FAUCET.
<u>MV</u>	MIXING VALVE: MATTS, #LFUSG-B, THERMOSTATIC CONTROLLED MIXING VALVE, LEAD FREE BRONZE BODY, LOCKED TEMPERATURE ADJUSTMENT CAP (VANDAL RESISTANT), COPPER ENCAPSULATED THERMOSTAT ASSEMBLY WITH BRASS SHUTTLE, STAINLESSSTEEL SPRINGS, INTEGRAL CHECK VALVES ON HOT AND COLD INLETS. (SET TO 110°F). ASSE 1070 LISTED.
<u>MV1</u>	MIXING VALVE: MATTS, LFMMV THERMOSTATIC CONTROLLED MIXING VALVE, LEAD FREE BRONZE BODY, LOCKED TEMPERATURE ADJUSTMENT CAP (VANDAL RESISTANT), SOLID MAX HYDRAULIC PRINCIPLE THERMOSTAT, INTEGRAL FILTER WASHERS AND CHECK VALVES ON HOT AND COLD INLETS. (SET TO 110°F) ASSE #1017, #1069, #1070
<u>BFP</u>	BACKFLOW PREVENTOR: MATTS #SD-3, DUAL CHECK VALVE WITH ATMOSPHERIC PORT & STRAINER FOR CARBONATED BEVERAGE MACHINES
<u>RPZ</u>	REDUCED ZONE PRESSURE BACKFLOW PREVENTOR (FOR BAS IN BOX): MATTS #LF009, LEAD FREE BRONZE BODY CONSTRUCTION, TWO, IN-LINE INDEPENDENT CHECK VALVES, REPLACEABLE CHECK SEATS WITH AN INTERMEDIATE RELIEF VALVE, AND BALL VALVE TEST COCKS.
<u>RPZ-1</u> <u>RPZ-2</u>	REDUCED ZONE PRESSURE BACKFLOW PREVENTOR: MATTS #LF009, LEAD FREE BRONZE BODY CONSTRUCTION, TWO, IN-LINE INDEPENDENT CHECK VALVES, REPLACEABLE CHECK SEATS WITH AN INTERMEDIATE RELIEF VALVE, AND BALL VALVE TEST COCKS, REQUIRED QUANTITY 2, ONE FOR DOMESTIC WATER LINE AND ONE FOR IRRIGATION SYSTEM. SEE PLAN FOR SIZES.
<u>FPVH</u>	FREEZEPROOF WALL HYDRANT: WOODFORD #17, 3/4" HOSE NOZZLE OUTLET, BRASS FACE, HANDWHEEL OPERATED, INTEGRAL VACUUM BREAKER.
<u>WH</u>	WATER HAMMER ARRESTOR: JR SMITH 'HYDROTROL' #5000 LEAD-FREE WATER HAMMER ARRESTOR, SIZED AS PER MANUFACTURER'S RECOMMENDATIONS.
<u>GI</u>	GREASE INTERCEPTOR: SCHIER MODEL #GB50, POLYETHYLENE GREASE INTERCEPTOR, 37" LENGTH, 32.25" WIDTH & 28.5" HEIGHT 50 GPM FLOW RATE, 439.5 LB. GREASE CAPACITY AND 65 GALLON LIQUID CAPACITY. PROVIDE ASSOCIATED PIPING PER CODE REQUIREMENTS. PROVIDE 4" INLET AND OUTLET, FIELD CUT RISER AND CAST IRON COVER.
<u>RD</u>	ROOF DRAIN: MATTS #RD-300-R, CAST IRON BODY, FLASHING CLAMP, GRAVEL STOP, UNDERDECK CLAMP, SUMP RECEIVER, AND DUCTILE IRON DOME.
<u>ORD</u>	OVERFLOW DRAIN: MATTS #RD300-M, CAST IRON BODY, FLASHING CLAMP, GRAVEL STOP, UNDERDECK CLAMP, SUMP RECEIVER, DUCTILE IRON DOME, AND 2" HIGH WATER DAM.
<u>DS</u>	DOWN SPOUT NOZZLE: MATTS #RD-40, CAST BRONZE, NICKEL BRONZE FINISH, WALL FLANGE.
<u>FCO/MCO</u>	VINYL TILE FLOOR: JR SMITH #4140, OR EQUAL. QUARRY TILE FLOOR: JR SMITH #4200, OR EQUAL. CARPETED FLOOR: JR SMITH #4020-Y, OR EQUAL. UNFINISHED FLOOR: JR SMITH #4020, OR EQUAL. WALL: JR SMITH #4472, OR EQUAL, 24" ABOVE THE FLOOR.

* COORDINATE WITH G.C. AND OWNER FOR EQUIPMENT THAT MAY BE PROVIDED BY OTHERS.

PLUMBING SYMBOLS

	SOIL AND WASTE PIPING BELOW FLOOR/GRADE
	SOIL AND WASTE PIPING ABOVE FLOOR/GRADE
	GREASE WASTE PIPING TO GREASE INTERCEPTOR
	SANITARY VENT PIPING ABOVE GRADE
	SANITARY VENT PIPING BELOW GRADE
	STORM PIPING BELOW FLOOR/GRADE
	STORM PIPING ABOVE FLOOR/GRADE
	STORM OVERFLOW PIPING ABOVE FLOOR/GRADE
	DOMESTIC COLD WATER PIPING
	DOMESTIC HOT WATER PIPING
	DOMESTIC HOT WATER RECIRCULATION PIPING
	GAS PIPING
	UNDER GROUND GAS PIPING
	EQUIPMENT DRAIN LINE
	PIPING TURNING DOWN
	PIPING TURNING UP
	TEE TOP CONNECTION
	UNION
	BACKFLOW PREVENTER
	FLOOR DRAIN
	FLOOR CLEAN OUT
	WALL CLEAN OUT
	GRADE CLEAN OUT
	VALVE
	BALANCING VALVE
	SOLENOID VALVE
	PRESSURE REGULATOR
	CHECK VALVE
	CONNECT TO EXISTING
	INVERT ELEVATION OF PIPE
	MATCH MARKS ON PLUMBING RISER DIAGRAM
	CHECK VALVE
	THERMOMETER
	PRESSURE GAUGE
	TEMPERATURE AND PRESSURE RELIEF VALVE

- Notes:
- 4" FPT Inlet/outlet with 4" plain end adapters, single inlet and triple outlet.
 - Unit weight - w/ cast iron cover: 148 lbs. (For wet weight add 542 lbs.)
 - Maximum operating temperature: 150° F continuous
 - Capacities - Liquid: 65 gal
Grease: 439.5 lbs. (60 gal.) @50 GPM
Solids: 13 gal.
 - For gravity drainage applications only.
 - Do not use for pressure applications.
 - Cover placement allows full access to tank for proper maintenance.
 - Vent not required unless per local code.
 - Engineered inlet and outlet diffusers with inspection ports are removable to inspect / clean piping.
 - Integral air relief / Anti-siphon / Sampling access.
 - Adjustable cover adapter provides up to 4" of additional height.
 - Designed for below-grade, above-grade, indoor or outdoor installations.
 - Safety Start®, access restrictor built into cover adapter, prevents accidental entry to tank (450 lb rating).



PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:

△ RISER REV	3-15-2024
△ CITY COM.	10-14-2024

SHEET TITLE
PLUMBING SCHEDULE & DETAIL

P200



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/24



PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023


REVISION:

△ RISER REV 3-15-2024

△ CITY COM. 10-14-2024


SHEET TITLE
PLUMBING RISER DIAGRAMS

P201




* = COMBINATION WASTE & VENT DRAIN

WASTE & VENT RISER



PROVIDE PRESSURE
REDUCING VALVE
NATTS #LF223 OR
EQUAL

DOMESTIC WATER RISER



NATURAL GAS RISER

ELECTRICAL SPECIFICATIONS

1. GENERAL PROVISIONS:
- A. PROVIDE ALL LABOR, MATERIALS, EQUIPMENT, NECESSARY FOR THE COMPLETE INSTALLATION OF THE ELECTRICAL SYSTEMS OUTLINED.

B. OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATES OF COMPLIANCE OR APPROVAL AS REQUIRED BY THE AUTHORITIES.

C. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST APPROVED EDITION OF THE NATIONAL ELECTRIC CODE (NEC), AND ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL AGENCIES HAVING JURISDICTION OVER THE SITE.

D. ALL TESTING REQUIRED BY AUTHORITIES SHALL BE CONSIDERED PART OF THIS WORK.

E. DURING CONSTRUCTION, ALL FIXTURES, EQUIPMENT, CONDUIT, ETC. SHALL BE COVERED, PLUGGED, OR CAPPED AS REQUIRED TO KEEP CLEAN AND UNHARMED. ALL DAMAGED ITEMS SHALL BE RESTORED TO ORIGINAL CONDITION OR REPLACED. ALL PROTECTIVE COVERING SHALL BE REMOVED BEFORE FINAL ACCEPTANCE.

F. PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILING, AND ROOFS AS NECESSARY. PATCH AROUND ALL OPENINGS SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.

G. CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECTS FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
2. OPERATION AND MAINTENANCE MANUALS:
- A. DURING THE COURSE OF CONSTRUCTION, COLLECT AND COMPILE OPERATING INSTRUCTIONS, WIRING DIAGRAMS, CATALOG CUTS, LUBRICATION AND PREVENTIVE MAINTENANCE INSTRUCTIONS, PARTS LISTS, ETC. FOR ALL EQUIPMENT FURNISHED UNDER THIS CONTRACT.

B. ALL LITERATURE AND INSTRUCTIONS SHIPPED WITH THE EQUIPMENT SHALL BE SAVED FOR INCLUSION IN THE OPERATION AND MAINTENANCE MANUALS.

C. ALL LITERATURE LISTED ABOVE AND ALL PAPERS LISTING WARRANTIES, ETC. SHALL BE BOUND IN A 3-RING BINDER AND LABELED WITH THE PROJECT NAME, ADDRESS, ARCHITECT, ENGINEER, CONTRACTORS, ETC.
3. MANUFACTURERS:
- A. MANUFACTURERS, MODEL NUMBERS, ETC. INDICATED OR SCHEDULED ON THE DRAWINGS SHALL BE INTERPRETED AS HAVING ESTABLISHED A STANDARD OF QUALITY AND SHALL NOT BE CONSTRUED AS LIMITING COMPETITION. ARTICLES, FIXTURES, ETC. OF EQUAL QUALITY BY MANUFACTURERS SHALL BE ACCEPTABLE, SUBJECT TO STRUCTURAL AND ELECTRICAL CONSTRAINTS OF THE PROJECT DESIGN, UNLESS NOTED OTHERWISE.
4. TESTING, AND BALANCING:
- A. ALL CIRCUITS SHALL BE TESTED FOR CONTINUITY, SHORTS, AND GROUNDS BEFORE CONNECTING TO THE PROPER PHASE AS DESIGNED TO BALANCE THE LOADING BETWEEN PHASES.

B. POWER AND LIGHTING PANELS SHALL BE PROPERLY PHASED TO DISTRIBUTE THE LOAD AND SHALL BE CONNECTED AND ADJUSTED TO OPERATE AS SPECIFIED.

C. ALL MOTORS AND SIMILAR EQUIPMENT SHALL BE CHECKED FOR PROPER PHASE ROTATION AND OPERATION.
5. RACEWAYS:
- A. CONDUIT INSIDE THE BUILDING SHALL BE METALLIC TUBING (EMT), BEARING THE UL LABEL, WITH COMPRESSION TYPE FITTINGS OR SCREW SET FITTINGS.

B. CONDUIT EXPOSED TO THE WEATHER, INSTALLED UNDERGROUND, IN CONCRETE, OR USED FOR SERVICE ENTRANCE SHALL BE STANDARD RIGID CONDUIT (GALVANIZED) WITH THREADED FITTINGS.

C. UNDERGROUND CONDUIT MAY BE POLYVINYL CHLORIDE WITH A DEFLECTION TEMPERATURE, UNDER LOAD AT 264 PSI, OF 10 DEGREES C, AND A TENSILE STRENGTH OF 5,200 PSI. JOINTS SHALL BE FLUSH SOLVENT WELDED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE EQUAL TO CARLON POWER AND COMMUNICATIONS DUCT TYPE DB (DIRECT BURIAL). CONDUIT AND FITTINGS SHALL BE PROVIDED BY THE SAME MANUFACTURER.

D. FLEXIBLE METAL CONDUIT SHALL ONLY BE USED FOR CONNECTIONS TO MOTORS, TRANSFORMERS, AND LIGHT FIXTURES. MAXIMUM LENGTH SHALL BE 6'-0".
6. CONDUCTORS:
- A. WIRES SHALL BE CONTINUOUS WITHOUT SPLICES OR TAPS IN CONDUIT RUNS. ALL SPLICES SHALL BE MADE IN JUNCTION, PULL, OR OUTLET BOXES. ALL WIRE SHALL BE INSTALLED IN CONDUIT, WIRERAYS, OR OTHER PROTECTIVE COVER SANCTIONED BY CODES.

B. CONDUCTORS FOR LIGHTING AND POWER SHALL BE COPPER, MINIMUM NO. 12 AWG, 600 VOLT.

C. NO. 12 GAUGE AND SMALLER CONDUCTORS SHALL BE TYPE THHN (WET LOCATIONS) OR THHN (DRY LOCATIONS), SOLID CONDUCTOR, UNLESS OTHERWISE INDICATED.

D. NO. 8 GAUGE AND LARGER CONDUCTORS SHALL BE TYPE THWN (WET LOCATIONS) OR THHN (DRY LOCATIONS), STRANDED, UNLESS OTHERWISE INDICATED.

E. SERVICE ENTRANCE AND PANEL FEEDER CONDUCTORS, NO. 3 GAUGE AND LARGER SHALL BE TYPE XHHW-2 (WET LOCATIONS) OR THHN (DRY LOCATIONS), STRANDED COPPER, UNLESS OTHERWISE INDICATED.
7. MC CABLE:
- A. MC CABLE SHALL CONSIST OF INTERLOCK ARMORED CABLE MADE OF THREE OR FOUR TYPE THHN SOLID 16 AWG AND LARGER MAY BE STRANDED COPPER CONDUCTORS INSULATED WITH HEAT AND MOISTURE RESISTANT POLYVINYL CHLORIDE (PVC), WITH NYLON OR EQUIVALENT UL LISTED JACKET, PER UL STANDARD 85. THE THREE CONDUCTORS SHALL BE TWISTED TOGETHER WITH THE COPPER GROUNDING CONDUCTOR, SUITABLE FILLERS, AND WRAPPED IN BINDER TAPE. THE ASSEMBLY SHALL BE ARMORED WITH SPIRALLY WRAPPED INTERLOCKED ARMOR OR ALUMINUM OR GALVANIZED STEEL.

B. CABLES SHALL BE TESTED IN ACCORDANCE WITH UL STANDARD 1569 FOR TYPE MC CABLE AND RATED AT 600 VOLTS, 90 DEG. C FOR DRY LOCATIONS AND 75 DEG. C FOR WET LOCATIONS.
8. WIRING DEVICES:
- A. WALL SWITCHES SHALL BE SPECIFICATION GRADE, QUIET TYPE, FLUSH TOGGLE SWITCH, RATED FOR 20 AMPS, WITH THERMOPLASTIC COVER PLATES.

1) SINGLE POLE: HUBBELL K5S1221-X, OR EQUAL.

2) THREE WAY: HUBBELL K5S1223-X, OR EQUAL.

B. RECEPTACLES SHALL BE SPECIFICATION GRADE, DUPLEX, GROUNDING, THREE-WIRE TYPE, RATED FOR 20 AMPS, WITH THERMOPLASTIC COVER PLATES. HUBBELL K5S952-X, OR EQUAL.

C. GROUND FAULT INTERRUPTER RECEPTACLES (GFI) SHALL BE HUBBELL K5P20-XL. DEVICE COVER PLATES SHALL BE AS HEREINBEFORE SPECIFIED.

D. ISOLATED GROUND RECEPTACLES (IG) SHALL BE HUBBELL K5R5952G, ORANGE COLOR. DEVICE COVER PLATES SHALL BE AS HEREINBEFORE SPECIFIED.

E. RECEPTACLES OUTSIDE BUILDING AND WHERE NOTED AS WEATHERPROOF, SHALL BE LISTED WEATHER-RESISTANT HUBBELL K5P7R20-X OR EQUAL AND SHALL BE INSTALLED IN A WEATHERPROOF ENCLOSURE WHICH SHALL BE INTERMATIC W5P1010MC OR W5P1010HMC DIECAST METAL WEATHERPROOF RECEPTACLE COVER. COVER SHALL BE WEATHER PROOF RATED WHILE IN USE.

F. EXTERIOR RECEPTACLES SHALL BE WEATHER RESISTANT TYPE PER NEC 200.8. DEVICES SHALL BE HUBBELL K5R20XWRTR, OR EQUAL.

G. VERIFY DEVICES AND DEVICE COVERPLATES COLOR WITH ARCHITECT.
9. BOXES:
- A. HOT DIPPED GALVANIZED STEEL BOXES. PROVIDE TYPE TO SUIT CONDITIONS FOR INSTALLATION.

B. ALL BOXES SHALL BE FLUSH MOUNTED, UNLESS INDICATED OTHERWISE.
10. PANELBOARDS:
- A. FURNISH AND INSTALL CIRCUIT BREAKER PANELBOARDS AS SHOWN ON THE DRAWINGS. PANELBOARDS SHALL BE LISTED BY UL AND SO LABELED, AND SHALL BE FULLY RATED FOR THE VOLTAGE AND CURRENT CAPACITY INDICATED ON THE PANEL SCHEDULE. PANELBOARDS SHALL BE EQUAL TO GENERAL ELECTRIC, TYPE AG WITH BOLT IN TYPE BREAKERS. PANELBOARD LUGS SHALL BE RATED AT 75°C.

1) CIRCUIT BREAKER INTERRUPTING CAPACITIES SHALL MEET OR EXCEED THE AVAILABLE RMS SYMMETRICAL FAULT CURRENTS INDICATED AND AS REQUIRED TO MEET OR EXCEED THE AVAILABLE FAULT CURRENT FROM LOCAL UTILITY.

B. CIRCUIT BREAKERS SHALL MEET APPLICABLE PORTIONS OF UL STANDARD 484 AND NEMA AB-1L. CIRCUIT BREAKERS SHALL BE BOLT-ON, GROUP MOUNTED, AMBIENT MAGNETIC, WITH COMMON TRIP, UL RATED TO CARRY 60% OF NAMEPLATE RATING CONTINUOUSLY IN FREE AIR AT 40° C. CIRCUIT BREAKERS SHALL BE TRIP INDICATING AND FULLY INTERCHANGEABLE WITHOUT DISTURBING ADJACENT UNITS. WIRE TERMINALS SHALL BE RATED 75 DEGREES C. THE OPERATING MECHANISM SHALL BE TRIP-FREE SO THAT CONTACTS CANNOT BE HELD CLOSED AGAINST ANY ABNORMAL OVERCURRENT OR SHORT CIRCUIT CONDITION.

2) BREAKERS SHALL MEET APPLICABLE NEMA AND/OR UL SPECIFICATIONS.

C. PANELBOARD BOXES SHALL BE GALVANIZED SHEET STEEL WITH AMPLE WIRING GUTTER SPACE IN ACCORDANCE WITH NEC. FRONTS SHALL BE OF SHEET STEEL PAINTED LIGHT GRAY OVER A SUITABLE RUST INHIBITOR PRIMER. PANELBOARDS SHALL BE EQUIPPED WITH ONE PIECE DOOR, CYLINDER TUMBLER TYPE LOCK, DIRECTORY CARD-HOLDER AND QUARTER-TURN ADJUSTABLE TRIM CLAMPS.

D. PANELBOARD INTERIORS SHALL CONSIST OF REINFORCED GALVANIZED SHEET STEEL FRAMES WITH ALUMINUM BUS BARS AND CIRCUIT BREAKERS, PROPERLY SUPPORTED TO PREVENT VIBRATIONS AND BREAKAGE IN HANDLING. BUS BARS SHALL BE SEQUENCE PHASED. PANELBOARD SHALL HAVE A FULL SIZED SOLID ALUMINUM NEUTRAL AND GROUND BUS.

E. BUS BAR BRACING SHALL BE UL LISTED AS INDICATED ON DRAWINGS. ADDITIONAL BRACING SHALL BE PROVIDED AS REQUIRED TO MEET OR EXCEED INDICATED AVAILABLE FAULT CURRENTS.

F. DIRECTORY CARDS SHALL BE COMPLETELY FILLED IN BY TYPEWRITER, LISTING CIRCUIT NUMBERS AND LOAD SERVED, INCLUDING EXISTING CIRCUITS. CIRCUIT BREAKERS SHALL BE IDENTIFIED BY CIRCUIT NUMBER LABELS AS HEREINBEFORE SPECIFIED.

ELECTRICAL SPECIFICATIONS (CONTINUED)

11. DISCONNECTS:
- A. DISCONNECTS SHALL BE EXTERNALLY OPERATED, QUICK-MAKE, QUICK-BREAK, SAFETY, WITH PROVISIONS FOR PAD LOCKING. FUSED AND NON-FUSED DISCONNECT SWITCHES SHALL BE PROVIDED AS INDICATED.

B. INDOOR SWITCHES SHALL BE NEMA 1 AND OUTDOOR SWITCHES SHALL BE NEMA 3R, UNLESS INDICATED OTHERWISE.
12. FUSES:
- A. FUSES PROTECTING CIRCUIT BREAKER PANELS SHALL BE CURRENT LIMITING U.L. CLASS RK-1 FUSES WITH 200,000 AMPERES RMS SYM INTERRUPTING CAPACITY. FUSING ELEMENTS SHALL BE SILVER FOR RATINGS ABOVE 60 AMPERES.

B. ALL OTHER FUSES SHALL BE U.L. CLASS RK-5, DUAL-ELEMENT WITH A MINIMUM TIME-DELAY OF 10 SECONDS AT 500% RATING. FUSES SHALL HAVE CURRENT-LIMITING SHORT-CIRCUIT LINKS AND 200,000 AMPERES RMS SYM INTERRUPTING CAPACITY. FUSING ELEMENTS SHALL BE COPPER.
13. LIGHT FIXTURES:
- A. WHERE LIGHT FIXTURES ARE MOUNTED IN A LAY-IN CEILING, PROVIDE A MINIMUM OF 2 SUPPORT WIRES ATTACHED DIRECTLY BETWEEN EACH LIGHT FIXTURE AND THE BUILDING STRUCTURE. SUPPORT WIRES SHALL BE A MINIMUM OF 12 GAUGE GALVANIZED STEEL WIRE, SOFT ANNEALED.

B. FIXTURES ARE REQUIRED AT ALL LIGHTING OUTLETS SHOWN ON THE DRAWINGS. APPROVED LIGHTING FIXTURE WIRE IS REQUIRED IN ALL FIXTURES AND FIXTURE RACEWAYS. WEATHERPROOF WIRING IS REQUIRED FOR EXTERIOR FIXTURES. ALL PARTS OF FIXTURES AND WIRING SHALL BE IN ACCORDANCE WITH NEC REQUIREMENTS.

C. ALL FIXTURES SHALL CARRY UL AND ETL LABELS. ALL FLUORESCENT FIXTURE BALLASTS SHALL BE HIGH FREQUENCY ELECTRONIC BALLASTS WITH A "TOTAL HARMONIC DISTORTION" OF LESS THAN 20%, REGARDLESS OF THE NUMBER OF LAMPS CONNECTED TO EACH BALLAST AND SHALL HAVE CBM LABEL. ALL FLUORESCENT FIXTURES INSTALLED SHALL INCORPORATE BALLAST PROTECTION. ALL FLUORESCENT BALLASTS SHALL HAVE AN AUDIBLE NOISE RATING OF "CLASS A" OR BETTER. ALL FLUORESCENT BALLASTS SHALL HAVE A STANDARD BALLAST FACTOR UNLESS SPECIFIED OTHERWISE.

D. ALL FLUORESCENT LAMPS SHALL BE 5800 K COLOR TEMPERATURE WITH A MINIMUM COLOR RENDERING INDEX (CRI) OF 92 OR AS INDICATED ON LIGHT FIXTURE SCHEDULE.
14. SLEEVES:
- A. PROVIDE, SET, AND PROPERLY LOCATE PIPE SLEEVES AS REQUIRED FOR THIS WORK.

B. INTERIOR PARTITIONS: 16 GAUGE GALVANIZED STEEL, PACK BETWEEN CONDUIT AND SLEEVE WITH FIRE SAFING AND CAULK AT EACH END WITH FIRE RESISTANT SEALANT.

C. ROOF: PROSECT OR EQUAL, MANUFACTURED PVC SCHEDULE 40 PIPE SLEEVE WITH WEATHERPROOF SEAL, COORDINATE WITH ROOFING CONTRACTOR AND FLASH AS REQUIRED TO MAINTAIN ROOF WARRANTY.
15. GROUNDING:
- A. GROUND ALL ELECTRICAL APPARATUS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE (NEC) 250, AND ANY LOCAL REQUIREMENTS. INSURE CONTINUOUS BOND WHERE FLEXIBLE CONDUIT IS USED. PROVIDE BONDING JUMPER INSIDE ALL FLEXIBLE CONDUIT.

B. BOND METAL PIPING SYSTEMS IN COMPLIANCE WITH NEC 250.41(A)(4).

ELECTRICAL GENERAL NOTES:

1. COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
2. IT IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY TO PROPERLY BALANCE ALL BRANCH CIRCUITS BETWEEN THE PHASES OF THE SYSTEM REGARDLESS OF CIRCUITING INDICATED.
3. ALL EXPOSED RACEWAYS SHALL BE IN EMT CONDUIT, MC CABLE IS NOT PERMITTED IN EXPOSED AREAS.
4. ELECTRICAL CONTRACTOR TO COORDINATE MANUFACTURER ELECTRICAL REQUIREMENTS FOR HVAC EQUIPMENT BEING FURNISHED WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN.
5. ALL MATERIALS EXPOSED WITHIN PLENUMS SHALL BE NONCOMBUSTIBLE OR SHALL HAVE A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE-DEVELOPED INDEX OF NOT MORE THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM E 84.
6. EACH BRANCH CIRCUIT SHALL HAVE A DEDICATED NEUTRAL PER NEC 200.4.
7. KITCHEN EQUIPMENT - VERIFY ALL ELECTRICAL REQUIREMENTS AND ROUGH-IN LOCATION PRIOR TO WORK.
8. ALL BRANCH CIRCUITS SHALL BE SIZED TO ALLOW FOR A MAXIMUM OF 3% VOLTAGE DROP. ALL FEEDERS SHALL BE SIZED TO ALLOW FOR A MAXIMUM OF 2% VOLTAGE DROP. E/C SHALL VERIFY WIRE SIZE INDICATED IS SUFFICIENT AND INCREASE CONDUCTOR SIZE AS REQUIRED BASED OFF ACTUAL INSTALLED LENGTH OF CONDUCTORS.
9. PROVIDE SEAL-OFF FITTINGS AT ALL COOLER/FREEZER PENETRATIONS.

ELECTRICAL SYMBOLS LIST

CIRCUITING & NOTES	
+48"	SPECIAL MOUNTING HEIGHT FOR ASSOCIATED DEVICE (CENTERLINE OF DEVICE)
GFI	GROUND FAULT CIRCUIT INTERRUPTER DEVICE
WP	WEATHERPROOF ENCLOSURE ON DEVICE
WR	WEATHERPROOF RESISTANT DEVICE
IG	ISOLATED GROUND DEVICE
EM	EMERGENCY BATTERY BACKUP
<div><div>X</div></div>	ELECTRICAL FLOOR PLAN NOTE WITH DESIGNATION
<div><div>2</div><div>LP</div></div>	CONDUIT CONCEALED WHERE POSSIBLE OR AS NOTED, ARROWS INDICATE HOME RUN TO PANEL. CIRCUIT NUMBERS INDICATED
<div><div>⎓</div></div>	#12 WIRE IN CONDUIT, UNLESS NOTED OTHERWISE ON DRAWINGS OR SPECIFICATION
<div><div>↶</div></div>	GROUNDING CONDUCTOR, #12 WIRE UNLESS NOTED OTHERWISE ON DRAWINGS OR SPECIFICATION
<div><div>↷</div></div>	CONDUIT ROUTED UNDER FLOOR/GRADE
LIGHTING	
<div><div>⎓</div></div>	EMERGENCY TWIN HEAD LIGHT FIXTURE
<div><div>⎓⎓</div></div>	EXIT LIGHT WITH DIRECTIONAL ARROWS INDICATED
<div><div>A</div><div>⎓</div></div>	FLUORESCENT STRIP FIXTURE WITH TYPE DESIGNATION
<div><div>A</div><div>•</div></div>	FLUORESCENT FIXTURE WITH TYPE DESIGNATION
<div><div>A</div><div>⎓</div><div>HL</div></div>	NIGHT LIGHT, CONNECT TO UNSWITCHED CIRCUIT
<div><div>A</div><div>⊙</div></div>	CEILING OR RECESSED FIXTURE WITH TYPE DESIGNATION
<div><div>A</div><div>⊙</div><div>+</div></div>	WALL MOUNTED FIXTURE WITH TYPE DESIGNATION
POWER DEVICES	
<div><div>⊕</div></div>	DUPLEX RECEPTACLE, BOTTOM OF BOX AT 16" AFF, UNLESS NOTED OTHERWISE
<div><div>⊕</div></div>	FOURPLEX RECEPTACLE, BOTTOM OF BOX AT 16" AFF, UNLESS NOTED OTHERWISE
<div><div>⊕⊕</div></div>	TVSS SURGE SUPPRESSION RECEPTACLE
<div><div>⊕</div><div>⚡</div></div>	DEVICE MOUNTED ABOVE COUNTER AND/OR SPLASH GUARD
<div><div>⊕</div><div>⚡</div></div>	HEAVY DUTY OUTLET - NEMA CONFIGURATION SIZE PER EQUIPMENT MANUFACTURER'S RECOMMENDATION
<div><div>⎓</div></div>	PANEL BOARD, TOP OF BOX 8'-0" AFF
<div><div>⊙</div></div>	JUNCTION BOX
<div><div>⊞</div></div>	NON-FUSED DISCONNECT SWITCH
<div><div>⊞</div></div>	FUSED DISCONNECT SWITCH
<div><div>⊞</div><div>⚡</div></div>	MAGNETIC STARTER
<div><div>⊞</div><div>⚡</div></div>	MOTOR WITH DESIGNATION
<div><div>⊞</div></div>	FLOOR BOX
CONTROLS	
<div><div>S</div></div>	SINGLE POLE WALL SWITCH, TOP OF BOX AT 48" AFF
<div><div>S</div><div>P</div></div>	SINGLE POLE WALL SWITCH WITH PILOT LIGHT, TOP OF BOX AT 48" AFF
<div><div>S</div><div>o</div></div>	INFRARED OCCUPANCY SENSOR, WATT STOPPER #PW-100, TOP OF BOX AT 48" AFF
<div><div>S</div><div>m</div></div>	MANUAL MOTOR STARTER WITH OVERLOADS
<div><div>⊞</div><div>S</div></div>	DUAL TECHNOLOGY CEILING MOUNT OCCUPANCY SENSORS, WATTSTOPPER DT-300
<div><div>⊞</div><div>S</div></div>	OCCUPANCY SENSOR POWER PACK, WATTSTOPPER BZ-150 OR EQUAL, PROVIDE LOW VOLTAGE WIRING TO OCCUPANCY SENSORS AND MOMENTARY SWITCHES
<div><div>S</div><div>mo</div></div>	MOMENTARY SWITCH, TOP OF BOX AT 48" AFF
COMMUNICATIONS	
<div><div>▼</div></div>	DATA/TELEPHONE OUTLET WITH 3/4" CONDUIT STUBBED UP TO ABOVE ACCESSIBLE CEILING, BOTTOM OF BOX AT 16", UNLESS NOTED OTHERWISE. PROVIDE WITH FULL STRING

LIGHT FIXTURE SCHEDULE

MARK NO.	MANUFACTURER & CATALOG NUMBER	VOLTS WATTS	LAMPS	DESCRIPTION	EQUIVALENT MANUFACTURERS
A	COLUMBIA LJT24-35-HLG-FS-A12125-EU	120 49	LED-INCL 5000 LUM 3500K	2X4' LED TROFFER WITH ACRYLIC PRISMATIC LENS AND FIXED-OUTPUT DRIVER. 5000 LUMENS AT 3500K	WILLIAMS LITHONIA OR EQUAL
A EM	COLUMBIA LJT24-35-HLG-FS-A12125-EU ELL14	120 49	LED-INCL 5000 LUM 3500K	SAME AS ABOVE WITH EMERGENCY BATTERY PACK - 1400 LUMEN EM LIGHT	WILLIAMS LITHONIA OR EQUAL
B	COLUMBIA LXM4-35-HL-RFA-EU	120 52	LED-INCL 5000 LUM 3500K	4' LED VAPOR-TIGHT FIXTURE WITH FROSTED ACRYLIC LENS AND FIXED-OUTPUT DRIVER. 5000 LUMENS AT 3500K	WILLIAMS LITHONIA OR EQUAL
BE	COLUMBIA LXM4-35-HL-RFA-EU ELL14	120 52	LED-INCL 5000 LUM 3500K	SAME AS FIXTURE 'B' WITH EMERGENCY BACKUP	WILLIAMS LITHONIA OR EQUAL
F	METEOR LA6-60-408-UNV-SFVS-60-60-BLK-STD	120 60	LED-INCL 6000 LUM 4000K	WALL MOUNTED UP/DOWN LIGHT, BLACK FINISH. WALL MOUNT AT 12'-0" AFF.	WILLIAMS LITHONIA OR EQUAL
F2	L5I XLCW 5 LED 56 CM EW BLK	120 41	LED-INCL	WALL MOUNTED LED AREA LIGHT, SYMMETRICAL OPTICS, BLACK FINISH. WALL MOUNT AT 12'-0" AFF	WILLIAMS LITHONIA OR EQUAL
G	L5I SCV LED 15L 5C UNV DIM 50 NHT	120 102	LED-INCL 15,000 LUM 5000K	LED PETROLEUM CANOPY LIGHT WITH SYMMETRICAL DISTRIBUTION. 15,000 LUMENS AT 5000K COLOR TEMPERATURE. VERIFY CANOPY CONSTRUCTION AND ORDER CORRECT FIXTURE MOUNTING AND TYPE BASED ON CANOPY BEING PROVIDED	-
52	HUBBELL RAR2-320L-110-4KT-2-UNV-ASQ-BLT-BG POLE: S65H-25-50-B-2-BLT-B3	208 222	LED-INCL 30,000 LUM 4000K	POLE MOUNTED AREA LIGHT, TYPE 2 SYMMETRICAL DISTRIBUTION. MOUNTED ON 2 1/2" POLE WITH VIBRATION DAMPER AND 2 HIGH CONCRETE BASE	WILLIAMS LITHONIA OR EQUAL
53	HUBBELL RAR2-320L-110-4KT-3-UNV-ASQ-BLT-BG POLE: S65H-25-50-B-1-BLT-B3	208 110	LED-INCL 15,000 LUM 4000K	POLE MOUNTED AREA LIGHT, TYPE 3 SYMMETRICAL DISTRIBUTION. MOUNTED ON 2 1/2" POLE WITH VIBRATION DAMPER AND 2 HIGH CONCRETE BASE	WILLIAMS LITHONIA OR EQUAL
54	HUBBELL RAR2-320L-110-4KT-4UNV-ASQ-BLT POLE: S65H-25-50-B-1-BLT-B3	208 110	LED-INCL 15,000 LUM 4000K	POLE MOUNTED AREA LIGHT, TYPE 4W SYMMETRICAL DISTRIBUTION. MOUNTED ON 2 1/2" POLE WITH VIBRATION DAMPER AND 2 HIGH CONCRETE BASE	WILLIAMS LITHONIA OR EQUAL
<div><div>⚡</div></div>	DUAL-LITES EV2	120 1	INCL	EMERGENCY LIGHT WITH TWIN ADJUSTABLE 1 WATT LED HEADS AND SEALED LEAD GELGUM BATTERY, MOUNT AT 7'-6". TO CLEAR OBSTACLES, (PROVIDES 1 FC AVG. ON 2' CENTER FIXTURE SPACING)	SURE-LITES LITHONIA OR EQUAL
<div><div>⚡</div></div>	DUAL-LITES EVC-U-R-Y-M-D4 WITH EVO-D-X	120 5	INCL	COMBINATION EMERGENCY/EXIT LIGHT WITH LED LAMPS, RED LETTERS ON WHITE BACKGROUND, TWIN 6W EMERGENCY LIGHT HEADS, UNIVERSAL MOUNT, HIGH CAPACITY BATTERY BACKUP AND REMOTE TWIN HEAD OUTDOOR RATED FIXTURE	SURE-LITES LITHONIA OR EQUAL



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing hereon, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/2024



PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:
RISER REV 3-15-2024
CITY COM. 10-14-2024

SHEET TITLE
ELECTRICAL
SPECIFICATION

E000




**ENGINEERS
INCORPORATED**
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/2024



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI


BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:
△ RISER REV 3-15-2024
△ CITY COM. 10-14-2024

SHEET TITLE
ELECTRICAL LIGHTING
PLAN

E101




ELECTRICAL LIGHTING PLAN
SCALE: 1/4" = 1'-0"

PHOTOCELL, UNIVERSAL VOLTAGE,
LOCATED ON ROOF IN SHADED
AREA FACING NORTH

INTERMATIC HET91615CR
16 CIRCUIT, EACH CKT
ADDRESSABLE,
ASTRONOMICAL
TIMECLOCK W/ INTEGRAL
OVERRIDE SWITCH

COORDINATE EACH CIRCUIT
TIME SETTING WITH OWNER
REPRESENTATIVE




EXTERIOR LIGHTS/SIGNAGE CONTROL DIAGRAM

SCALE: NONE

LIGHTING PLAN NOTES:

- 1 ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTROL. SEE DETAIL, THIS SHEET.
- 2 LOCATION OF EXTERIOR LIGHTING CONTROLS. SEE DETAIL, SHEET THIS SHEET.
- 3 CONNECT TO LIGHTS PROVIDED WITH CANOPY, IF PROVIDED WITH OPTION. VERIFY ALL REQUIREMENTS WITH CANOPY SUPPLIER.
- 4 SWITCH BANK FOR INTERIOR LIGHTING CONTROLS.
- 5 ROUTE SWITCH LEG TO INDICATED SWITCH IN BANK. SEE PLAN NOTE #4.




5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/2024



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI


BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:
RISER REV 3-15-2024
CITY COM. 10-14-2024

SHEET TITLE
ELECTRICAL POWER PLAN

E102



POWER PLAN NOTES:

- DEVICES MOUNTED IN CASEWORK - VERIFY EXACT LOCATIONS. ROUTE ALL WIRING CONCEALED.
- RECEPTACLES MOUNTED IN COOLER SOFFIT WALL FOR DECORATIVE SIGNAGE.
- CONNECT TO WALK-IN COOLER/FREEZER DOOR LIGHTS/HEATERS PER MANUFACTURER'S INSTRUCTIONS.
- CONNECT TO WALK-IN COOLER/FREEZER EVAPORATOR PER MANUFACTURER'S INSTRUCTIONS. VERIFY EXACT LOCATIONS AND ELECTRICAL REQUIREMENTS WITH EQUIPMENT SUPPLIER. PROVIDE CONTROL WIRING TO CONDENSING UNIT(S) PER MANUFACTURER'S INSTRUCTIONS.
- POWER FOR OPEN AIR COOLER FLOOR BOX. VERIFY REQUIREMENTS WITH OWNER.
- CONNECT TO EVAPORATOR CONDENSATE HEAT TRACE. VERIFY ALL REQUIREMENTS WITH EQUIPMENT SUPPLIER.
- DUPLEX RECEPTACLE MOUNTED FLUSH IN CEILING ABOVE STOREFRONT WINDOW FOR DISPLAY SIGNAGE PER NEC.
- JUNCTION BOX WITH TOGGLE DISCONNECT FOR POWER TO BUILDING SIGNAGE. VERIFY EXACT LOCATION AND REQUIREMENTS WITH SIGNAGE VENDOR. ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTROLS. SEE EXTERIOR LIGHTING DETAIL ON SHEET E-101.
- JUNCTION BOX FOR POWER TO ELECTRICAL HAND DRYER. VERIFY EXACT LOCATION AND REQUIREMENTS.
- LOCATION OF FUEL SYSTEM RACEWAY, CONTROLS, TANK MONITORS, ETC. FIELD VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- RECEPTACLE FOR ATM MACHINE. VERIFY LOCATION AND OTHER REQUIREMENTS WITH OWNER. MOUNT POWER AND DATA RECEPTACLE AT +36" AFF.
- POWER FOR MERCHANDIZE GONDOLA FLOOR BOX. VERIFY REQUIREMENTS WITH OWNER.
- 4"x4"x3/4" PLYWOOD TELEPHONE BACKBOARD WITH SIEMENS #ECB5-5 GROUND BAR AND #6CU BOND TO BUILDING ELECTRODE SYSTEM.
- PROVIDE (1) 4" TO PROPERTY LINE FOR BUILDING TELEPHONE SERVICE. TERMINATE AT LOCATION DIRECTED BY LOCAL SERVICE PROVIDER. VERIFY ROUTING & DISTANCE. REFER TO CIVIL UTILITY DRAWINGS.
- SECONDARY FEEDER TO TRANSFORMER. SEE RISER DIAGRAM SHEET E2, AND ELECTRICAL SITE PLAN SHEET E3.01.




ELECTRICAL POWER PLAN

POWER PLAN NOTES:

- CT CABINET, DISCONNECT SW. AND METER MOUNTED ON BUILDING. SEE ELECTRICAL SITE PLAN SHEET E3.01.
- DATA DROP FOR WIRELESS ACCESS POINT - COORDINATE LOCATION WITH OWNER.
- POWER FOR DONUT CASE FLOOR BOX. VERIFY REQUIREMENTS WITH OWNER.
- PROVIDE 7.5 KVA 208V-240V, 1 PH TRANSFORMER FOR COFFEE BRENER OR DRINK DISPENSER INDICATED. VERIFY ELECTRICAL REQUIREMENTS WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- ROUTE CIRCUIT THROUGH HOOD SHUT-DOWN RELAY - SEE HOOD SHUT-DOWN RELAY DIAGRAM ON THIS SHEET.
- PROVIDE JUNCTION BOX FOR HEATED AIR CURTAIN. CONNECT PER MANUFACTURER'S REQUIREMENTS. VERIFY EXACT LOCATION WITH OWNER PRIOR TO ROUGH-IN.


EQUIPMENT SCHEDULE

NUMBER	DESCRIPTION	NUMBER	DESCRIPTION
1	COFFEE DISPENSER - SURE IMMERSION 312	22	HOT FOOD CASE (CHICKEN)
2	REFR LIQUID DISPENSER - KAN PAK	23	LOTTERY EQUIPMENT
3	COFFEE BREWER - BUNN SH DBC (240V, 1 PH)	24	COUNTER TOP WARMER
4	CAPPUCCINO DISPENSER - CURTIS	25	PIZZA PREP TABLE
5	ICED TEA BREWING SYSTEM - CURTIS	26	CONVECTION OVEN
7	COFFEE CREAMER AND SUGAR DISPENSER - BSG	27	COUNTER TOP GRIDDLE
8	DONUT CASE	28	MICROWAVE OVEN
9	FEDERAL SELF-SERVE ISLAND	29	WORKTOP FREEZER
10	FRYERS	30	COUNTERTOP BLENDER
11	STACKED OVEN	31	MERCHANDIZER
14	SELF SERVE MERCHANDIZER	32	MERCHANDIZER
15	NACHO DISPENSER	33	HOT DOG ROLLER
16	ICE AND BEVERAGE DISPENSER	34	BUN WARMER
17	FRESH BLENDER	35	MICROWAVE
19	FROZEN BEVERAGE DISPENSER (240V, 1PH)	36	HOOD
20	FROZEN DRINK MACHINE	39	ATM
21	WAFFLE MAKER	49	BAG-N BOX



HOOD SHUT-DOWN DETAIL

SCALE: NONE



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/2024



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023


REVISION:

△ RISER REV 3-15-2024

△ CITY COM. 10-14-2024

SHEET TITLE
MECHANICAL POWER
PLAN


E103



POWER PLAN NOTES:

- 1 CONNECT TO WALK-IN COOLER FREEZER CONDENSING UNIT(S) ON ROOF PER MANUFACTURER'S INSTRUCTIONS. VERIFY ALL REQUIREMENTS WITH EQUIPMENT SUPPLIER.

NORTH
MECHANICAL POWER PLAN
SCALE: 1/4" = 1'-0"



ENGINEERS
INCORPORATED
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/2024



PROJECT FOR:
HEARTLAND MARKET
LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023


REVISION:

△ RISER REV 3-15-2024

△ CITY COM. 10-14-2024

SHEET TITLE
ELECTRICAL RISER
DIAGRAM & FAULT CALCS

E201



ELECTRICAL RISER DIAGRAM
SCALE: NONE

PANEL: A2		VOLTS: 120/208V		PH: 3Ø	WIRE: 4W	LOCATION: WORK ROOM 104		MOUNTING: SURFACE								
BUS: 400A		MAN: 400A MCB	IC: 22,000	RMS SYM AMPS				FEEDER:	SEE RISER DIAGRAM							
CKT	DESCRIPTION	AMPS	POLE	WIRE	ØA	ØB	ØC	ØA	ØB	ØC	WIRE	POLE	AMPS	DESCRIPTION	CKT NO	
43	3Ø BLENDER (GF)	20	1	12	1,800			1,800				12	1	20	31 SHELF MERCH (GF)	44
45	3Ø SELF MECH (GF)	20	1	12		864			1,320			12	1	20	33 HOT DOG ROLLER (GF)	46
47	3Ø BUN WARMER (GF)	15	2	12			100			1,596		12	1	20	35 MICROWAVE (GF)	48
49	(GF)				100			1,440				12	1	20	36 PIZZA WARMER (GF)	50
51	ROOFTOP RECS	20	1	12		120			800			12	1	20	MAU VFD	52
53	Ø4 GAPPUCINO DISP (GF)	20	1	12			1,800			250		12	1	20	HCP/HOOD LIGHTS	54
55	15 NACHO DISPENSER (GF)	20	1	12	300				1,141							56
57	16 BEV DISPENSER (GF)	20	1	12		800				1,141		12	3	15	KEP-1	58
59	16 BEV DISPENSER (GF)	20	1	12			800			1,141						60
61					5,020				733							62
63	RTU-2	50	3	6		5,020				733		12	3	15	MAU-1	64
65							5,020			733						66
67					5,850			3,000				10	2	30	11 STACKED OVEN	68
69	RTU-3	60	3	6		5,850			3,000							70
71							5,850			180	5	1	40	ATM MACHINE	72	
73	NACHO DISPENSER (GF)	20	1	12	300			1,440				12	1	20	20 FROZEN DRINK MACH (GF)	74
75	BAG-N BOX (GF)	20	1	12		360			1,440			12	1	20	20 FROZEN DRINK MACH (GF)	76
77	16 BEV DISPENSER (GF)	20	1	12			800					1	20	SPARE	78	
79	2T COUNTER TOP GRIDDLE	20	2	12	1,650			23,140								80
81						1,650			26,030			3/Ø	3	200	PANEL B	82
83	AIR MACHINE	20	1	12			800			27,130						84
NOTES:					15,020	15,264	15,170	32,644	34,464	31,030						
					47,714		44,725		46,200		TOTAL CONNECTED LOAD:					143,642 VA
(GF)-GFCI BRKR															129,484 VA	
DEMAND AMPS @ 208 VOLT / 3Ø:															359.41	

PANEL: F		VOLTS: 120/208V			PH: 1Ø		3W		LOCATION: WRK RM 104			MOUNTING: SURFACE		
BUS: 225A		MAIN: 150A MLO			IG:		22,000		RMS SYM AMPS			FEEDER: SEE RISER DIAGRAM		
CKT	DESCRIPTION	AMPS	POLE	WIRE	ØA	ØB	ØA	ØB	WIRE	POLE	AMPS	DESCRIPTION	CKT NO	
1	DISPENSER #1	20	1	12	1,000		1,500		12	2	20	FUEL PUMP #1	2	
3	(SWITCHED NEUTRAL BRKR)							1,500					4	
5	DISPENSER #2	20	1	12	1,000		1,500		12	2	20	FUEL PUMP #2	6	
7	(SWITCHED NEUTRAL BRKR)							1,500					8	
9	DISPENSER #3	20	1	12	1,000		1,500		12	2	20	FUEL PUMP #3	10	
11	(SWITCHED NEUTRAL BRKR)							1,500					12	
13	DISPENSER #4	20	1	12	1,000		1,500		12	2	20	FUEL PUMP #4	14	
15	(SWITCHED NEUTRAL BRKR)							1,500					16	
17	SPARE	20	1							1	20	SPARE	18	
19	SPARE	20	1					1,000	12	1	20	DISPENSER #5	20	
21	SPARE	20	1						12	1	20	(SWITCHED NEUTRAL BRKR)	22	
23	SPARE	20	1					1,000	12	1	20	DISPENSER #6	24	
25	SPARE	20	1						12	1	20	(SWITCHED NEUTRAL BRKR)	26	
27	SPARE	20	1					1,000	12	1	20	DISPENSER #7	28	
29	SPARE	20	1						12	1	20	(SWITCHED NEUTRAL BRKR)	30	
31	SPARE	20	1					1,000	12	1	20	DISPENSER #8	32	
33	TVSS	30	2	10	50				12	1	20	(SWITCHED NEUTRAL BRKR)	34	
35						50		50	12	1	20	TANK MONITOR SYSTEM	36	
NOTES:					4,050	50	6,000	10,050						
					10,050				TOTAL CONNECTED LOAD:					20,150 VA
									NEG DEMAND LOAD:					20,150 VA
									DEMAND AMPS @ 208 VOLT / 1Ø:					96.8A



**ENGINEERS
INCORPORATED**
5720 Reeder
Shawnee, Ks. 66203
(913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2023 BC Engineers, Inc.

PE COA #2009003629

10/14/2024



PROJECT FOR:

HEARTLAND MARKET

LEE'S SUMMIT, MISSOURI

BC PROJECT #: 22823

REVIEW SET
ISSUE DATE: 4-28-2023

REVISION:
RISER REV 3-15-2024


CITY COM. 10-14-2024

SHEET TITLE
ELECTRICAL SITE PLAN


E301

ELECTRICAL PLAN NOTES:


- 3/4" C FOR POWER CONNECTION TO DISPENSER (8 TOTAL.) VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- 3/4" C FOR INTERCOM CONNECTION DISPENSER (8 TOTAL.) VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- 3/4" C FOR VEEDER ROOT CONDUCTORS FOR SUMP SENSOR (8 TOTAL.) VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- CONNECT TO MONUMENT SIGN PER MANUFACTURER'S INSTRUCTIONS. VERIFY EXACT LOCATION AND ELECTRICAL REQUIREMENTS. ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTACTOR. SEE EXTERIOR LIGHTING DIAGRAM SHEET E-101
- CONNECT TO CANOPY SIGN PER MANUFACTURER'S INSTRUCTIONS. VERIFY EXACT LOCATION AND ELECTRICAL REQUIREMENTS. ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTACTOR. SEE EXTERIOR LIGHTING DIAGRAM SHEET E-101
- ROUTE CIRCUIT TO PANEL VIA EXTERIOR LIGHTING CONTACTOR IN 1" C FOR EACH CIRCUIT. SEE EXTERIOR LIGHTING DIAGRAM SHEET E-101
- 3/4" C FOR POWER TO EACH STP MOTOR (4 TOTAL). VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- (18) TOTAL 3/4" C FOR VEEDER ROOT CONDUCTORS. VERIFY ALL REQUIREMENTS WITH FUEL SYSTEM SUPPLIER.
- BUILDING MOUNTED ELECTRICAL SERVICE EQUIPMENT. SEE RISER DIAGRAM SHEET E-201.
- PROVIDE RED PUSHBUTTON TYPE SWITCH TO PROVIDE MASTER EMERGENCY SHUTOFF OF FUEL DISPENSING STATIONS. PROVIDE SIGN ADJACENT TO SWITCH INDICATING PURPOSE. EMERGENCY SWITCH AND ALL COMPONENTS SHALL BE IN ACCORDANCE WITH NEC 514. VERIFY EXACT LOCATION PRIOR TO ROUGH-IN. (EMERGENCY STOP MUST BE GREATER THAN 20 FT AND LESS THAN 100 FT FROM DISPENSERS.) (1) 3/4" C FROM TANK AREA TO PUSHBUTTON LOCATION FOR CONDUCTORS, TWO REQUIRED.
- PROPOSED LOCATION OF KNOX BOX / KEY BOX. VERIFY LOCATION WITH FIRE MARSHAL.
- COORDINATE PLACEMENT OF PRIMARY AND SECONDARY CONDUITS, PAD FOR UTILITY TRANSFORMER, AND MOUNTING OF METERS AND CT CABINETS WITH EVERGY.
- TO EXISTING PRIMARY ELECTRICAL SERVICE. VERIFY WITH CIVIL PLANS EXACT LOCATION.
- (1) 2" CONDUIT FOR SPEAKER/MIC, (1) 2" C FOR HDMI, (1) 1" C FOR POWER. VERIFY LOCATION OF DIGITAL MENUBOARD WITH OWNER.
- DIRECT BURIAL LOOP FOR DRIVE-THRU. VERIFY ELECTRICAL REQUIREMENTS WITH MANUFACTURER'S INSTRUCTIONS - LIKE THOSE FROM THE HOWARD COMPANY (WWW.HOWARDCOMPANY.COM.)




D/T MENUBOARD
SCALE: 1/4" = 1'-0"




CANOPY LIGHTING PLAN
SCALE: 1" = 30'




ELECTRICAL SITE PLAN
SCALE: 1" = 30'




POLE FOUNDATION DETAIL
SCALE: NONE




FOUNDATION PLAN
SCALE 3/16"=1'-0"





- FOOTING NOTES**
1. OWNER / GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR FOOTING AND ANCHOR BOLT INSTALLATION.
 2. ALL FOOTINGS SHALL BE CAST ON LEVEL UNDISTURBED SOIL, ROCK OR PROPERLY COMPACTED SUBGRADE. FOOTING SIZE BASED ON MINIMUM 1500 PSF SOIL BEARING AT BASE AND 150 PSF PER FOOT OF DEPTH LATERAL BEARING CAPACITY. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL SOIL PARAMETERS.
 3. FOOTING CONCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3000 PSI.
 4. FOOTING DESIGN BASED ON AN ASSUMED 1'-0" BURY OF THE COLUMNS FROM THE BOTTOM OF BASE PLATE TO FINISHED GRADE. ANY AMOUNT OF BURY LESS THAN 1'-0" WILL RESULT IN A LARGER FOOTING SIZE.
 5. TOPS OF ALL FOOTINGS ARE ASSUMED TO BE AT SAME ELEVATION. OWNER / GENERAL CONTRACTOR SHALL PROVIDE BURIAL DEPTH FROM HIGH GRADE UNDER CANOPY. WHERE TOPS OF FOOTINGS ARE AT DIFFERENT ELEVATIONS, THE OWNER / GENERAL CONTRACTOR SHALL PROVIDE THE CANOPY MANUFACTURER WITH ALL FOOTING AND GRADE ELEVATION PRIOR TO CANOPY FABRICATION. VARIATIONS FROM DESIGN ELEVATIONS MAY RESULT IN INADEQUATE CLEARANCE AND UNDER SIZED FOOTINGS.
 6. OWNER / GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR PLACING NON-SHRINK GROUT UNDER ALL COLUMN BASES AFTER CANOPY IS LEVELED AND SECURED.
 7. FOOTING REINFORCING STEEL SHALL BE ASTM A615 GRADE 60 DEFORMED BILLET STEEL BARS WITH SPACING AS SHOWN ON DRAWING.
 8. FOOTINGS ARE ASSUMED TO BE CONSTRAINED BY FUEL ISLAND AND DRIVE MAT CONCRETE. WHERE THIS CONDITION DOES NOT EXIST, THE OWNER SHALL NOTIFY CANOPY MANUFACTURER.
 9. ANCHOR BOLTS SHALL BE PLACED IN ACCORDANCE WITH THIS DRAWING. TEMPLATES SHALL BE USED TO ENSURE PROPER PLACEMENT OF ANCHOR BOLTS. ANCHOR BOLTS ARE TO BE INSTALLED SUCH THAT A MINIMUM OF 8" OF THREAD IS EXPOSED ABOVE TOP OF FOOTING. BOTTOM OF THREADS SHALL NOT END MORE THAN 3/4" ABOVE TOP OF FOOTER.
 10. ANY DISCREPANCIES BETWEEN THE ABOVE NOTES AND LOCAL BUILDING CODE REQUIREMENTS SHALL BE REPORTED TO THE CANOPY MANUFACTURER IMMEDIATELY. COMMENCEMENT OF FOOTING INSTALLATION SHALL INDICATE THAT THE ABOVE NOTE MEET LOCAL BUILDING CODE REQUIREMENTS.




FOUNDATION DETAIL
SCALE 3/8" = 12"



ANCHOR BOLTS
(4) REQ'D. PER FOOTING

FOR ANCHOR BOLT SHIPMENT		
		
32	-AB3 (1 1/4" Ø x 30" ANCHORBOLT)	
		
ABT1 (TEMPLATE)		
8	WOOD	TEMPLATE

REV	DATE	BY	DESCRIPTION
0	7/12/23	TJH	PERMIT / APPROVAL



DAVID E. SCHATTE
10609 99TH STREET
OVERLAND PARK, KS. 66214
LICENSE #E-27047



1019 E. North Street
Ottawa, Kansas 66067
Phone: 785.242.8111
Fax: 785.242.2022

THESE PLANS ARE SUBJECT TO
FEDERAL COPYRIGHT LAWS
ANY USE OF SAME WITHOUT THE
EXPRESS WRITTEN PERMISSION
OF FASHION INC. IS PROHIBITED


SITE:
AMOCO
LEE'S SUMMIT, MO
50' x 120'
(8) COLUMN CANOPY

SCALE:
AS SHOWN
DRAWN BY:
TJH
CHECKED BY:
DES

JOB NUMBER:
457750

SHEET TITLE:
FOUNDATION PLAN

SHEET NUMBER:
CA1 of 2



PULL DRAIN ELBOW END THRU HOLE
AND GLUE 3"Ø NIPPLE INTO ELBOW AND
GLUE 3"Ø COUPLING INTO NIPPLE.

CA2 of :