



WATER MAIN

Engineer's Opinion of Probable Costs

| | | | UNIT | UNIT | UNIT |
|--|--|------|----------|------------|--------------|
| NO. | ITEM | UNIT | QUANTITY | PRICE (\$) | TOTAL |
| 10.0 | WATER MAIN | | | | |
| 10.01 | 8" C900 PVC PRESSURE CLASS 235 | LF | 3,708 | \$40.00 | \$148,320.00 |
| 10.02 | 5 1/4" FIRE HYDRANT ASSEMBLY (INCLUDES 8"x6" TEE, THRUST BLOCKS, GATE VALVE, HYDRANT) | EA | 10 | \$5,500.00 | \$55,000.00 |
| 10.03 | 8" GATE VALVE | EA | 9 | \$150.00 | \$1,350.00 |
| 10.04 | 8" 11.25 DEGREE BEND | EA | 6 | \$150.00 | \$900.00 |
| 10.05 | 8" 22.5 DEGREE BEND | EA | 9 | \$150.00 | \$1,350.00 |
| 10.06 | 8" 45 DEGREE BEND | EA | 3 | \$160.00 | \$480.00 |
| 10.07 | 12" C900 PVC PRESSURE CLASS 235 | LF | 2,108 | \$70.00 | \$147,560.00 |
| 10.08 | 5 1/4" FIRE HYDRANT ASSEMBLY (INCLUDES 12"x6" TEE, THRUST BLOCKS, GATE VALVE, HYDRANT) | EA | 5 | \$5,500.00 | \$27,500.00 |
| 10.09 | 12" GATE VALVE | EA | 18 | \$800.00 | \$14,400.00 |
| 10.10 | 12" 11.25 DEGREE BEND | EA | 5 | \$592.00 | \$2,960.00 |
| 10.11 | 12" 22.5 DEGREE BEND | EA | 2 | \$600.00 | \$1,200.00 |
| 10.12 | 12" BLOWOFF ASSEMBLY (INCLUDES ALL APPURTENANCES) | EA | 1 | \$6,000.00 | \$6,000.00 |
| 10.13 | 8"x8" TEE | EA | 2 | \$700.00 | \$1,400.00 |
| 10.14 | 12"x8" TEE | EA | 2 | \$787.00 | \$1,574.00 |
| 10.15 | 12"x12" TEE | EA | 2 | \$787.00 | \$1,574.00 |
| 10.16 | 12"x12" CROSS | EA | 1 | \$787.00 | \$787.00 |
| 10.17 | TRACER WIRE | LF | 5,816 | \$2.00 | \$11,632.00 |
| 10.18 | 24" STEEL CASING PIPE TO BE BORED & JACKED (INCLUDES ALL APPURTENANCES) | LF | 101 | \$750.00 | \$75,750.00 |
| 10.19 | REMOVAL AND SALVAGE OF EXISTING FIRE HYDRANT | EA | 1 | \$2,500.00 | \$2,500.00 |
| 10.20 | CONNECT TO EXISTING WATER MAIN | EA | 3 | \$5,000.00 | \$15,000.00 |
| | | | | | |
| WATER MAIN SUB-TOTAL | | | | | \$517,237.00 |
| ESTIMATE DOES NOT INCLUDE: LANDSCAPING, ROCK EXCAVATION, IRRIGATION, UTILITY(GAS, COMM, ELEC) FEES SUB-TOTAL | | | | \$ 517,237 | |
| 10% CONTINGENCY | | | | \$ 51,724 | |

JEFFREY W.
BARTZ
NUMBER
PE-2012022594
01/09/2025

TOTAL \$